

Planting & Maintenance Specification

1. A pH test to be performed prior to planting and corrected if required.
2. Turf to be laid on 100mm topsoil over 150mm deep prepared area.
3. Planting beds to have quality compost mixed through existing soil.
4. Garden beds to be mulched with a minimum of 75 thick of mulch.
5. Garden beds to be fertilized with Dynamic Lifter after planting and watered well into soil.
6. Fertilizing should take place every Spring, preferably during both Spring and Autumn periods.
7. Hedged species to be pruned every Spring and Autumn.
8. New trees to be secured with stakes to avoid rocking. Planting holes to be large enough for root ball and backfill of good quality planting mix.

Landscaping Certification

J. Wright
 Julie Wright Certificate of Horticulture
 37 McKillop Road, Beacon Hill NSW 2100

SYZYGIUM AUSTRALE 'SOUTHERN AUSSIE'
 HEDGED AT 3 METRES

EXISTING TREE TO REMAIN

SYZYGIUM AUSTRALE 'SOUTHERN AUSSIE'
 HEDGED AT 1.5 METRES

POSSIBLE GRASSCRETE CARSPACE AND ACCESS


EXISTING PLANTING TO REMAIN

SYZYGIUM AUSTRALE 'SOUTHERN AUSSIE'
 HEDGED AT 3 METRES

Plant Schedule

Common Name	Botanical Name	Qty.	Pot Size
Lillypilly	Syzygium Australe 'Southern Aussie'	55	300mm
New Zealand Flax	Phormium Tenax	6	200mm

LANDSCAPING PLAN

	lic 139095c abn 44 002 281 263 info@beecraft.com.au www.beecraft.com.au 9450 1530 6a larool rd terrey hills nsw		NEW RESIDENCE & SECONDARY DWELLING 1186 BARRENJOEY ROAD, PALM BEACH LOT 1 DP1050253	
	LANDSCAPING PLAN DATE SEPT 2016	DRAWN J.WRIGHT	DRG. BAR-08 SCALE 1:200	