

Engineering Referral Response

| | |
|--|---|
| Application Number: | DA2024/1701 |
| Proposed Development: | Construction of a sewage reticulation system as ancillary development to the Warringah Mall Shopping Centre |
| Date: | 28/12/2024 |
| To: | Kye Miles |
| Land to be developed (Address): | Lot 103 DP 1247294 , 145 Old Pittwater Road BROOKVALE NSW 2100 |

Reasons for referral

This application seeks consent for the following:

- New Dwellings or
- Applications that require OSD where additional impervious area exceeds 50m² or
- Alterations to existing or new driveways or
- Where proposals affect or are adjacent to Council drainage infrastructure incl. watercourses and drainage channels or
- Torrens, Stratum and Community Title Subdivisions or
- All new Commercial and Industrial and RFB Development with the exception of signage or
- Works/uses in flood affected areas

And as such, Council's development engineers are required to consider the likely impacts on drainage regimes.

Officer comments

The proposed development is in Region 2. A geotechnical report has been provided.

The proposed development is near Council infrastructure present within the site (Stormwater Pipe). To demonstrate compliance with the Northern Beaches Council's Water Management for Development Policy. It is required that following details are submitted with the application:

1. Accurately locate, confirm dimensions including depth and plot to scale Council's Public drainage system and associated infrastructure on the DA site plans that outline the proposal. This should be carried out by service locating contractor and registered surveyor. (Evidence of methodology adopted used for locating stormwater system should be provided). Show the stormwater pipe on plans and produce a longitudinal section.
2. All structures are to be located clear of any council pipeline, pit or easement and comply with minimum vertical and horizontal clearances.

The proposal is therefore unsupported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Engineering Conditions:

Nil.