



STORMWATER NOTES

- 1. All roof collection components (ie gutters / DPs etc)are to be located / sized by the Developments contracting Plumber for a **5% AEP** event capacity. (70m2 roof area per 125mm dp via gutter 12800mm2 @ 1:200min).
- 2. Trunk lines shown on plan to be 150mm dia uPVC. 3. All pipes to be uPVC to AS 1254:2002.
- 4. All pipes to be laid at the grade required to match pit invert levels.
- 5. All pipes to be installed and laid in accordance with AS 3500.3:2003.
- 6. All roof guttering/ down pipes / valley gutters / box gutters etc are to be sized and installed in accordance with AS 3500.3:2003.
- 7. All pits are to be proprietary uv resistant polypropylene or similar unless noted (approved by the Engineer)and are to include a min 50mm sediment trap in the base and a maximesh screen laid at 45' across the pit to protect the oulet pipe.
- 8. All pits greater than 600mm in depth are to be proprietary precast concrete (approved by the Engineer).
- 9. All pits greater than 1000mm in depth are to have adequate access requirements in accordance with OH&S/Workcover requirements (ie; minimum dimensions 900x900mm with step irons).
- 10.All works are to be inspected and certified by the Principle Certifying Authority prioir to backfilling.
- 11.All works requiring certification by the Engineer will require a works as executed survey prepared by a registered Surveyor detailing all levels etc as on the Engineering plans.
- 12. The system is too be flushed and cleaned of all sediment and debris annually.
- 13. The system will require regular cleaning and maintenance to ensure its ability to function is maintained. 14.To ensure the system's ability to function is maintained it is to be inspected and certified as operating effectively by a licensed plumber every 5 years, and a engineer every 20yrs.
- 15.All existing predevelopment catchment area run-off conditions exiting the site are to be maintained with no run-off flows being diverted from the predevelopment
- 16.Flows from upstream properties entering the site are to be monitored during construction and diverted about the OSD system / residence etc as required.

Job No : 220604

SW2

Drawing No:

TUNE 2022

Document Certification Barrenjoey Consulting Engineers pty Itd per

Director

LUCAS MOILOY MIEA CPENG NER