



Annexure A

Pavillion Residences No 3 Pty Limited v Northern Beaches Council

Amended Plans and Documents



NOTES:	REVISIONS:	PROJECT TITLE:	CLIENT:	ARCHITECT:	DRAWING TITLE:	DRAWING No:	PROJECT No:	REVISION:	NORTH POINT:															
FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.	<table border="1"> <thead> <tr> <th>DATE</th> <th>REV</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>25/03/19</td> <td>A</td> <td>-ADDED BIKE RACKS & ELEC CPD -RECONFIGURE STORE RM PLANT RM -ADDED DIMENSION TO DRIVEWAY -BIN AREA REMOVE AND REPLACED AS BULKY GOODS AREA -CHANGE OF STONE AT BASE</td> </tr> <tr> <td>04/06/19</td> <td>B</td> <td>-REORGANIZATION OF WAITING BAYS AT STREET -RECONFIGURATION OF STREET FACADE -GARBAGE AREA MODIFIED WITH SEPARATE RETAIL</td> </tr> <tr> <td>24/03/20</td> <td>C</td> <td></td> </tr> <tr> <td>05/05/20</td> <td>D</td> <td>LIFT + ADAPTIBLE CARPARK MIRRORRED</td> </tr> </tbody> </table>	DATE	REV	DESCRIPTION	25/03/19	A	-ADDED BIKE RACKS & ELEC CPD -RECONFIGURE STORE RM PLANT RM -ADDED DIMENSION TO DRIVEWAY -BIN AREA REMOVE AND REPLACED AS BULKY GOODS AREA -CHANGE OF STONE AT BASE	04/06/19	B	-REORGANIZATION OF WAITING BAYS AT STREET -RECONFIGURATION OF STREET FACADE -GARBAGE AREA MODIFIED WITH SEPARATE RETAIL	24/03/20	C		05/05/20	D	LIFT + ADAPTIBLE CARPARK MIRRORRED	RESIDENTIAL DEVELOPMENT 21 WHISTLER ST MANLY	Urban Partners	WOLSKI . COPPIN ARCHITECTURE SUITE 3 LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088 T: 9953 8477 E: info@wolskicoppin.com.au DAVID WOLSKI NSW ARB No. 5297	BASEMENT	DA01	21806	D	
DATE	REV	DESCRIPTION																						
25/03/19	A	-ADDED BIKE RACKS & ELEC CPD -RECONFIGURE STORE RM PLANT RM -ADDED DIMENSION TO DRIVEWAY -BIN AREA REMOVE AND REPLACED AS BULKY GOODS AREA -CHANGE OF STONE AT BASE																						
04/06/19	B	-REORGANIZATION OF WAITING BAYS AT STREET -RECONFIGURATION OF STREET FACADE -GARBAGE AREA MODIFIED WITH SEPARATE RETAIL																						
24/03/20	C																							
05/05/20	D	LIFT + ADAPTIBLE CARPARK MIRRORRED																						
							SCALE: 1:100 @ A3	DATE: 5/05/2020																



NOTES: FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORKS ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

REVISIONS:

DATE	REV	DESCRIPTION
29.03.19	A	RECONFIGURE ENTRY & LIFT FOYER ADDED WAITING BAY NEW LOCATION OF BIN AREA RECONFIGURE RETAIL 01.02
04.06.19	B	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE
24.03.20	C	GARBAGE AREA MODIFIED
05.05.20	D	RESIDENTIAL ENTRY LIFT + STAIRS MODIFIED TO IMPROVE SIGHTLINES TO CARLIFT

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9953 8477 E: info@wolski Coppin.com.au
DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: DA02

DRAWING No.: 21806
PROJECT No.: D
REVISION: D

SCALE: 1:100 @ A3
DATE: 5/05/2020

NORTH POINT: N

© BIM Server: WSRV01 - BIM Server 20/21806 21 Whistler Street Manly Revision D



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.

THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORKS ON SITE.

THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

DATE	REV	DESCRIPTION
20.03.19	A	ADDED DIMENSIONS TO COURTYARD ADDED INFORMATION TO ADJOINING BUILDING NO.33
04.06.19	B	CHANGE OF STONE AT BASE REORGANIZATION OF WRITING BAYS AT STREET RECONFIGURATION OF STREET FACADE
05/05/20	C	-LIFT + STAIRS MIRRORED

REVISIONS:

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
 SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
 T: 9553 8477 E: info@wolski Coppin.com.au
 DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: LEVEL 1

DRAWING No: DA 03

PROJECT No: 21806

REVISION: C

NORTH POINT: N

SCALE: 1:100 @ A3

DATE: 5/05/2020

BIM Server: BMSRV01 - BIM Server 20/21806 21 Whistler Street Manly Revision D



NOTES: FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

REVISIONS:

DATE	REV	DESCRIPTION
20.03.19	A	ADDED DIMENSIONS TO COURTYARD ADDED INFORMATION TO ADJOINING BUILDING NO.39
04.06.19	B	CHANGE OF STONE AT BASE REORGANIZATION OF WHISTLER BAYS AT STREET RECONFIGURATION OF STREET FACADE
05/05/20	C	-LIFT + STAIRS MIRRORED

PROJECT TITLE: RESIDENTIAL DEVELOPMENT 21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9553 8477 E: info@wolski Coppin.com.au
DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: LEVEL 2

DRAWING No: DA04

PROJECT No: 21806

REVISION: C

NORTH POINT: N

SCALE: 1:100 @ A3

DATE: 5/05/2020

BIM Server: BMSRV01 - BIM Server 20/21806 21 Whistler Street Manly Revision D



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.

THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE.

THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

DATE	REV	DESCRIPTION
20.03.19	A	ADDED DIMENSIONS TO COURTYARD ADDED INFORMATION TO ADJOINING BUILDING NO.33
04.06.19	B	CHANGE OF STONE AT BASE REORGANIZATION OF WRITING BAYS AT STREET RECONFIGURATION OF STREET FACADE
05/02/20	C	-LIFT + STAIRS MIRRORED

REVISIONS:

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9953 8477 E: info@wolski Coppin.com.au
DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: LEVEL 3

DRAWING No: DA05

PROJECT No: 21806

REVISION: C

NORTH POINT: N

SCALE: 1:100 @ A3

DATE: 5/05/2020

BIM Server: BIMSrv01 - BIM Server 20/21806 21 Whistler Street Manly Revision D



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.

THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE.

THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

DATE	REV	DESCRIPTION
20.03.19	A	ADDED DIMENSIONS TO COURTYARD ADDED INFORMATION TO ADJOINING BUILDING NO.33
04.06.19	B	CHANGE OF STONE AT BASE REORGANIZATION OF WRITING BAYS AT STREET RECONFIGURATION OF STREET FACADE
05/05/20	C	-LIFT + STAIRS MIRRORED

REVISIONS:

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9953 8477 E: info@wolski Coppin.com.au
DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: LEVEL 4

DRAWING No: DA06

PROJECT No: 21806


REVISION: C

NORTH POINT: N

SCALE: 1:100 @ A3

DATE: 5/05/2020

BIM Server: BMSRV01 - BIM Server 20/21806 21 Whistler Street Manly Revision D



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.

THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE.

THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

REVISIONS:

DATE	REV	DESCRIPTION
20.03.19	A	ADDED INFORMATION TO ADJOINING BUILDING NO.33
04.06.19	B	CHANGE OF STONE AT BASE REORGANIZATION OF WHISTLING BAYS AT STREET RECONFIGURATION OF STREET FACADE
05/02/20	C	-LIFT + STAIRS MIRRORED

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9953 8477 E: info@wolskicoppin.com.au
DAVID WOLSKI NSW A/RB No. 5297

DRAWING TITLE: ROOF

DRAWING No: DA07


PROJECT No: 21806

REVISION: C


SCALE: 1:100 @ A3

DATE: 5/05/2020

NORTH POINT: N



NOTES:	REVISIONS:	PROJECT TITLE:	CLIENT:	ARCHITECT:	DRAWING TITLE:	DRAWING No:	PROJECT No:	REVISION:	NORTH POINT:						
FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.	<table border="1"> <thead> <tr> <th>DATE</th> <th>REV</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>04 08 19</td> <td>A</td> <td>CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE</td> </tr> </tbody> </table>	DATE	REV	DESCRIPTION	04 08 19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE	RESIDENTIAL DEVELOPMENT 21 WHISTLER ST MANLY	Urban Partners	WOLSKI . COPPIN ARCHITECTURE SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088 T: 9953 8477 E: info@wolski Coppin.com.au DAVID WOLSKI NSW ARB No. 5297	SECTION AA	DA08	21806	A	
DATE	REV	DESCRIPTION													
04 08 19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE													
							SCALE: 1:100 @ A3	DATE: 5/05/2020							



NOTES: FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

DATE	REV	DESCRIPTION
04 08 19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE

REVISIONS:

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9953 8477 E: info@wolskicoppin.com.au
DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: SECTION B B

DRAWING No: DA09


PROJECT No: 21806

REVISION: A


NORTH POINT:

SCALE: 1:100 @ A3 DATE: 5/05/2020

BIM Server: BMSRV01 - BIM Server 20/21806 21 Whistler Street Manly Revision D



NOTES:	REVISIONS:	PROJECT TITLE:	CLIENT:	ARCHITECT:	DRAWING TITLE:	DRAWING No:	PROJECT No:	REVISION:	NORTH POINT:									
FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.	<table border="1"> <thead> <tr> <th>DATE</th> <th>REV</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>04/08/19</td> <td>A</td> <td>CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIRMATION OF STREET FACADE</td> </tr> <tr> <td>05/05/20</td> <td>B</td> <td>GROUND FLOOR FACADE ALTERED TO IMPROVE VEHICULAR SIGHTLINES</td> </tr> </tbody> </table>	DATE	REV	DESCRIPTION	04/08/19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIRMATION OF STREET FACADE	05/05/20	B	GROUND FLOOR FACADE ALTERED TO IMPROVE VEHICULAR SIGHTLINES	RESIDENTIAL DEVELOPMENT 21 WHISTLER ST MANLY	Urban Partners	WOLSKI . COPPIN ARCHITECTURE SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088 T: 9953 8477 E: info@wolskicoppin.com.au DAVID WOLSKI NSW ARB No. 5297	EAST ELEVATION	DA10	21806	B	
DATE	REV	DESCRIPTION																
04/08/19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIRMATION OF STREET FACADE																
05/05/20	B	GROUND FLOOR FACADE ALTERED TO IMPROVE VEHICULAR SIGHTLINES																
							SCALE: 1:100 @ A3	DATE: 5/05/2020										



NOTES: FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

DATE	REV	DESCRIPTION
04/08/19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE
05/02/20	B	LIFT + STAIR MIRRORED

REVISIONS:

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9953 8477 E: info@wolski Coppin.com.au
DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: NORTH ELEVATION

DRAWING No.: DA11


PROJECT No.: 21806

REVISION: B

NORTH POINT:

SCALE: 1:100 @ A3 DATE: 5/05/2020

BIM Server: BMSRV01 - BIM Server 20/21806 21 Whistler Street Manly Revision D



NOTES: FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

REVISIONS:

DATE	REV	DESCRIPTION
04/08/19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE
05/02/20	B	LIFT + STAIR MIRRORED

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9953 8477 E: info@wolski Coppin.com.au
DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: SOUTH ELEVATION

DRAWING No: DA12


PROJECT No: 21806

REVISION: B


NORTH POINT:

SCALE: 1:100 @ A3 DATE: 5/05/2020

BIM Server: BMSRV01 - BIM Server 20/21806 21 Whistler Street Manly Revision D



NOTES:	REVISIONS:	PROJECT TITLE:	CLIENT:	ARCHITECT:	DRAWING TITLE:	DRAWING No:	PROJECT No:	REVISION:	NORTH POINT:									
FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.	<table border="1"> <thead> <tr> <th>DATE</th> <th>REV</th> <th>DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>04/08/19</td> <td>A</td> <td>CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE</td> </tr> <tr> <td>05/05/20</td> <td>B</td> <td>LIFT + STAIR MIRRORED</td> </tr> </tbody> </table>	DATE	REV	DESCRIPTION	04/08/19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE	05/05/20	B	LIFT + STAIR MIRRORED	RESIDENTIAL DEVELOPMENT 21 WHISTLER ST MANLY	Urban Partners	WOLSKI . COPPIN ARCHITECTURE SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088 T: 9953 8477 E: info@wolski Coppin.com.au DAVID WOLSKI NSW ARB No. 5297	WEST ELEVATION	DA13	21806	B	
DATE	REV	DESCRIPTION																
04/08/19	A	CHANGE OF STONE AT BASE REORGANIZATION OF WAITING BAYS AT STREET RECONFIGURATION OF STREET FACADE																
05/05/20	B	LIFT + STAIR MIRRORED																
							SCALE: 1:100 @ A3	DATE: 5/05/2020										



1 rendered masonry
dulux satin - vivid white or equal




2 feature wall cladding
"Andesite" Stone cladding stretcher bond + dark oak innowood trim contrast strips or similar



3 feature rendered masonry
dulux satin - beautiful beige + dark oak "innowood" trim contrast strips or similar



4 window & door frames/ steel works
powder coated - dulux pewter pearl or equal




5 entry awning / exposed slab edge
dulux satin - vivid white or equal



6 glazed curtain wall
powdercoated frame - dulux pewter pearl or equal with fire rated backup panel glazing





7 privacy screen
powder coated - dulux hog bristle or similar



8 glazed balustrades
powder coated - dulux pewter pearl or equal



9 external wall cladding
innowood cladding - dark oak horiz cladding or equal



NOTES: FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS. THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE. THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

REVISIONS:

DATE	REV	DESCRIPTION
26 06 19	A	REVISED FINISHES SCHEDULE
19 05 20	B	REVISED FINISHES SCHEDULE

PROJECT TITLE: **RESIDENTIAL DEVELOPMENT**
21 WHISTLER ST MANLY

CLIENT: **Urban Partners**

ARCHITECT: **WOLSKI . COPPIN ARCHITECTURE**
SUITE 3, LEVEL 1, 507 MILITARY ROAD MOSMAN NSW 2088
T: 9953 8477 E: info@wolskicoppin.com.au DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE: **FINISHES**

DRAWING No: **C06**

PROJECT No: **21806**


REVISION: **B**

NORTH POINT:

DATE: 19/05/2020

1: 100 @a3

BIM Server: BIMSRV01 - BIM Server 20/21806 21 Whistler Street Manly revision D



Alterations & Additions for Proposed Mixed Use Development 21 Whistler Street, Manly

Traffic and Parking Assessment

Ref: 110/2018

Date: May 2020

Issue: D

Table of Contents

1.0	INTRODUCTION	1
2.0	PROPOSED DEVELOPMENT SCHEME.....	2
2.1	Site, Context and Existing Use	2
2.2	Proposed Development.....	2
3.0	ROAD NETWORK AND TRAFFIC CONDITIONS	3
3.1	Road Network.....	3
3.2	Traffic Controls	3
3.3	Traffic Conditions	4
3.4	Transport Services	4
4.0	ACCESS AND TRAFFIC	5
4.1	Access.....	5
4.2	Traffic	6
5.0	PARKING	7
6.0	INTERNAL CIRCULATION AND SERVICING	8
7.0	COUNCIL ISSUES	9
8.0	CONCLUSION	10

List of Figures

Figure 1	Location
Figure 2	Site
Figure 3	Road Network
Figure 4	Traffic Controls

List of Appendices

Appendix A	Development Plans
Appendix B	Transport Services
Appendix C	Comparable Access Plan
Appendix D	Car Stacker Details
Appendix E	Turning Path Assessment

1.0 Introduction

This report has been prepared to accompany revised plans for a Development Application to Northern Beaches Council for proposed alterations and additions for a residential apartment based mixed use development at 21 Whistler Street, Manly (Figure 1).


Manly is a very popular and scenic location which benefits from good public transport services and a vibrant commercial centre. The high demand for new residential apartments in the area has resulted in an ongoing process of redeveloping under-utilised sites.

The proposed development scheme involves major alterations and additions to an existing residential cottage and comprises:

- 8 apartments
- 2 retail tenancies
- basement carparking with car lift access


The purpose of this report is to:

- * describe the site, its context and revised development scheme
- * describe the existing road network and conditions on that network
- * assess the adequacy of the proposed on-site parking provision
- * assess the proposed vehicle access and the potential traffic implications
- * assess the proposed internal circulation and servicing arrangements



SPIT BRIDGE OPENING TIMES
Monday to Friday

LEGEND



LOCATION

FIG 1

2.0 Proposed Development Scheme

2.1 Site, Context and Existing Use

The site (Figure 2) is Lot B in DP 368451 which occupies square shaped area of some 277m². The site has a frontage of some 17.75m to the eastern side of Whistler Street located within the Manly Commercial Centre. The surrounding uses comprise:

- * the small retail buildings which adjoin to the north and south
- * the commercial buildings and multi-level public car park on the eastern side of Whistler Street
- * the mixed retail and commercial uses which extend along Belgrave Street
- * the main commercial 'strip' along The Corso to the south
- * the Ferry Wharf and Bus Interchange located to the south

There is an existing older style residential cottage on the site at present.


2.2 Proposed Development

It is proposed to demolish the existing buildings and excavate the site to provide for basement parking and a level building platform. New 5-level building will be constructed comprising:

- 8 x Two-Bedroom Apartments
- 2 x Ground level retail units (150m² GFA)

A total of 12 parking spaces will be provided in the basement level with access by car lift and a new driveway on the Whistler Street frontage.

Details of the proposed development are provided on the revised architectural drawings prepared by Wolski Coppin Architecture which accompany the Development Application and are reproduced in parts in Appendix A.



LEGEND



SITE

FIG 2

3.0 Road Network and Traffic Conditions

3.1 Road Network


The road network serving the site (Figure 3) comprises:

- * *Pittwater Road / Belgrave Street* – a State Road and arterial route linking between Manly and Mona Vale
- * *Sydney Road* – a State Road and sub-arterial road route linking between Manly and Balgowlah (local road east of Belgrave Street)
- * *North Steyne / South Steyne* – a Regional Road and part of a collector route connecting between Manly and Queenscliffe
- * *Whistler Street* – a local access road

3.2 Traffic Controls

The existing traffic controls, which have been applied to the road system serving the site, (Figure 4) comprise:

- * the traffic signals on Belgrave Street/Pittwater Road at the:
 - Raglan Street intersection
 - Sydney Road intersection
 - Gilbert Street intersection
 - East Esplanade intersection
- * the ONE WAY northerly traffic flow on Whistler Street
- * the 1P restrictions along Whistler Street in the vicinity of the site




LEGEND

-  **ARTERIAL**
-  **SUB-ARTERIAL**
-  **COLLECTOR**



ROAD NETWORK

FIG 3




MANLY

2095

OPENING TIMES
 Saturday to Friday
 7.15am - 1.15pm
 (9.15pm DST only)

LEGEND

-  TRAFFIC SIGNAL CONTROL
-  ROUNDABOUT
-  RESTRICTED TURNING MOVEMENT



**TRAFFIC
CONTROLS**

FIG 4

3.3 Traffic Conditions

An indication of the traffic conditions on the road system serving the site is provided by the data published by RMS. The data is expressed in terms of Annual Average Daily Traffic (AADT) and the most recent recorded volumes are provided in the following:

Location	AADT
Pittwater Road (W of Raglan St)	15,371
Sydney Road (W of Pittwater Rd)	16,523

The traffic movements along Whistler Street adjacent to the site are only some 150 vph during the AM and PM peak periods.

Traffic conditions in the vicinity of the site are generally satisfactory with a high level of control provided by the numerous traffic signals which provide for vehicle access and pedestrian crossing movements.

3.4 Transport Services

There are convenient public transport services in the vicinity of the site including bus and ferry services (Appendix B details). These frequent high capacity services provide connections to the City, the rail network, other bus services and the surrounding residential areas. It is apparent that the site is conveniently located to take advantage of those frequent high capacity transport services.

4.0 Access and Traffic

4.1 Access

Vehicle access to / from the basement will involve a car lift which will be programmed to automatically “revert” to and “wait” at the ground level to facilitate ingressing car access. If a car approaches to enter while an egress movement is occurring (a small LED warning sign will be displayed externally), the ingressing car will enter and be able to wait in the designated waiting bay located behind the car lift while the egressing car travels to the ground level.

The proposed system replicates that adopted for a development scheme for 138/139 North Steyne, Manly (see Appendix C details) and details of this arrangement are elaborated further in the following section. The ability for egressing drivers to sight pedestrians walking along the frontage footway by setting back the doorways either side with glass walls on the lift to provide sight triangles. This arrangement could be assisted by small mirrors mounted under the proposed awning and/or a small LED warning light system could be provided.

A vehicle waiting bay is provided behind the car lift to accommodate an ingressing car if the lift is transporting an egress car from the basement. In a detailed step-by-step manner it is advised by lift manufacturer ‘Safe Tech’ that the system will be set up to operate as follows:

1. By default, the car lift automatically reverts to and dwells on the ground level to receive ingressing cars without any waiting period, driver will activate a “remote” on approach to open the lift door.
2. When called by a driver wishing to egress from the basement, the car lift will travel down, thus leaving an opening allowing any car which might arrive to ingress to access the car lift’s waiting area via the roof of the lift during this time.

Transport and Traffic Planning Associates

3. Once the lift detects no car activity on the ground level (i.e. car above the lift accessing the waiting bay) it shuts the lift door and transport the egress car to the ground level.
4. When arriving at the ground level the street-front lift door will be open.
5. The egress car will exit onto the street in a forward direction.
6. The waiting bay lift door will now be opened while the street-front door shuts concurrently
7. The ingressing car will reverse into the lift to be transported down to the basement

While the above arrangement accommodates opposing traffic flows appropriately, it is nevertheless noted that the parking spaces are of residential nature only. There will be minimal opposing traffic flows during the peak periods and as such it is apparent that the lift operation would impede on the Whistler Street traffic movements.

4.2 Traffic

TfNSW have released updated traffic generation data for high density apartments however, this is for sites in convenient proximity to railway stations.

Having regard for the earlier RMS criteria for “high density” residential developments, the following assessment is made:

Proposed 8 apartments @ 0.29 vtpH 2 – 3 vtpH

Thus, the projected peak traffic generation is only some 2-3 vtpH (ie 1vt every 20-30 minutes) and the potential impact of this on the access driveway and the surrounding road system will be entirely imperceptible.

5.0 Parking

Council's DCP specifies a parking provision in relation to the proposed development as follows:

Residential

1 resident space per 2 bed apartment; plus
0.16 visitor parking space for each dwelling

Retail 1 space per 40m² GFA with a 50% offset allowed with Sect 94 contribution

Application of these criteria to the proposed development would indicate the following:

8 x Two-bedroom apartments	8 spaces
Visitors (8 apartments)	1.3 (2) spaces
Retail (120m ²)	4 spaces (50% - 2 spaces)
Total:	12 spaces

It is proposed to provide 12 spaces (with a contribution for 2 spaces) including 1 accessible space in the basement along with provision for bicycles in the resident stores which comply with Class 1 locker dimensions. The primary parking system is entirely independent and accommodates 11 spaces. It operates with a 'puzzle-like' arrangement, allowing vehicles to be moved vertically and horizontally within the system to 'receive' or 'present' vehicles to users (see details provided in Appendix D). The accessible space is provided in a 'standalone' form in the NE corner.

It is apparent that the proposed parking provision will satisfy the DCP requirements.

6.0 Internal Circulation and Servicing

Internal Circulation

The design of the access aisle and circulation area within the carpark will comply with the requirements of AS2890.1. The arrangements, which include an appropriately located turntable, reflect the site constraints, however, it is demonstrated that there will be quite adequate provision for manoeuvring as indicated on the turning path assessment in Appendix E.

Servicing

Refuse will be removed from the street by Council services while any small service vehicles (e.g. service personnel) will be able to park in the adjacent public car park. Any occasional delivery vehicle requirements will be satisfied by the available on-street parking as is normal for small developments of this nature. In particular, it is noted that there are 2 sign-posted "Loading Bays" some 20m south of the site at Whistler Street.

7.0 Council Issues

Council's Traffic Engineer has raised the following traffic parking and access issues which are responded to in the following:

- ❖ The accessible space provided in a car stacker is not acceptable

Answer: The accessible space is no longer contained in a car stacker

- ❖ The shared zone for the accessible space is not 2.4m wide with a bollard as required by AS2890.6

Answer: The Access Consultant has certified that the proposed arrangement is satisfactory

- ❖ The proposed turntable will result in cars overhanging the shared space

Answer: the turntable has been relocated

- ❖ The provision of convex mirrors is not a satisfactory alternative solution to the provision of sight line angles

Answer: The adjacent doors have been moved back and the glass walls in the lift will enable sight lines to be available. This arrangement could be supplemented with small mirrors and/or a small LED warning system activated by the car lift door opening

- ❖ If an ingressing car travels to the basement level while a car is waiting to egress there will be nowhere to pass in the basement

Answer: A signal sign will be located on the wall opposite the car stacker spaces which will activate when a car is detected in a descending lift

It is noted that the Council advice confirms that:

- ❖ the traffic movements generated by the proposed development will not have any significant impact on the road network
- ❖ the proposed circumstances for service vehicles for the proposed development will be satisfactory


8.0 Conclusion

Assessment of the revised mixed use development scheme at Manly has concluded that:

- * there will not be any adverse traffic / safety implications
- * the proposed parking provision will be adequate and compliant with Council's code
- * the waiting bay provided with the car lift satisfactorily accommodate the need of a waiting vehicle such that reliance on Whistler Street is not necessary
- * the proposed vehicle access, internal circulation and servicing arrangements will be suitable and appropriate

Appendix A

Development Plans



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.
 THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE.
 THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

REVISIONS:

DATE	REV	DESCRIPTION
04/06/19	A	CHANGE OF STORE AT BASE REDIRECTION OF WHISTLER STREET RECONFIGURATION OF STREET FACADE
05/05/20	B	GROUND FLOOR FACADE ALTERED TO IMPROVE VEHICLE SIGHTLINES

PROJECT TITLE:

RESIDENTIAL DEVELOPMENT
 21 WHISTLER ST MANLY

CLIENT:

Urban Partners

ARCHITECT:

WOLSKI . COPPIN ARCHITECTURE
 1/1953 8477
 DAVID WOLSKI

DRAWING TITLE:

EAST ELEVATION

DRAWING No:

DA10

PROJECT No:

21806

REVISION:

B


NORTH POINT:

SCALE:

1:100 @ A3

DATE:

5/05/2020



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.

THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE.

THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

DATE	REV	DESCRIPTION
04/05/19	A	CHANGE OF STORE AT BASE RECONFIGURATION OF WHISTLER/BAYLY STREET RECONFIGURATION OF STREET FACADE

REVISIONS:

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUITE 3, LEVEL 1, 507 MILBURY ROAD, MOSMAN NSW 2088
T: 9953 8477 E: info@wolskicoppin.com.au
DAVID WOLSKI NSW AIB No. 5297

DRAWING TITLE: SECTION AA

DRAWING No.: DA08


PROJECT No.: 21806

REVISION: A

SCALE: 1:100 @ A3

DATE: 4/05/2020

NORTH POINT:



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.
 THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS FROM TO ANY COMMENCEMENT OF WORK ON SITE.
 THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

REVISIONS:

DATE	REV	DESCRIPTION
04/06/19	A	CHANGE OF STONE AT BASE RECONFIGURATION OF WHISTLER STREET RECONFIGURATION OF STREET FACADE

PROJECT TITLE:

RESIDENTIAL DEVELOPMENT
 21 WHISTLER ST MANLY

CLIENT:

Urban Partners

ARCHITECT:

WOLSKI . COPPIN ARCHITECTURE
 51/52 LEVEL 1, 507 ARBILARY ROAD MOSMAN NSW 2088
 T: 9933 8477 E: info@wolski Coppin.com.au
 DAVID WOLSKI NSW ARB No. 5297

DRAWING TITLE:

SECTION BB

DRAWING No:

DA09

PROJECT No:


21806

REVISION:

A

NORTH POINT:

SCALE: 1:100 @ A3
 DATE: 4/05/2020



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.

THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE.

THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

DATE	REV	DESCRIPTION
25.03.19	A	ADDED BIKE RACKS & ELEC CPD REMOVED ENGINE ROOM FROM PLANT ROOM ADDED OVERHEAD TO DRIVEWAY REPLACED AS BULKY GOODS AREA CHANGE OF STONE AT BASE
04.06.19	B	REORGANIZATION OF WAITING BAYS AT STREET REORGANIZATION OF OFFICE FRIGABE
24.02.20	C	GARBAGE AREA MODIFIED WITH SEPARATE RETAIL
06.05.20	D	LEFT - ADAPTABLE CARPARK MIRRORRED

REVISIONS:


PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY


CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
SUBF 3, LEVEL 1, 507 MILBURY ROAD MOSMAN NSW 2088
1: 9933 8477 E: info@wolski-coppin.com.au
(DAVID WOLSKI) NSW AFB No. 5297

DRAWING TITLE: BASEMENT

DRAWING No: DA01
PROJECT No: 21806
REVISION: D
SCALE: 1:100 @ A3
DATE: 5/05/2020





NOTES:
 FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.
 THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE.
 THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

REVISIONS:

DATE	REV	DESCRIPTION
28.03.19	A	RECONFIGURE ENTRY & LIFT FOYER
04.06.19	B	REORGANIZATION OF WAITING BAY AT STREET
24.02.20	C	GARBAGE AREA MODIFIED
06.05.20	D	RESIDENTIAL ENTRY LIFT STAIRS MODIFIED TO IMPROVE SIGHTLINES TO CARLIFT

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
 21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
 SUITE 3, LEVEL 1, 307 MILITARY ROAD MOSMAN NSW 2088
 T: 9553 8477 E: info@wolskicoppin.com.au
 DAVID WOLSKI NEW A&B NO. 5797

DRAWING TITLE: DA02

DRAWING No: 21806
PROJECT No: D
REVISION: D
DATE: 5/05/2020

SCALE: 1:100 @ A3

NORTH POINT: [North Arrow]

SERVER: B:\SRV01 - Bldg Server\20\21806\21 Whistler Street Manly Revision D



NOTES:

FIGURED DIMENSIONS ARE TO BE TAKEN IN PREFERENCE TO SCALED DIMENSIONS.

THE CONTRACTOR IS TO CHECK AND VERIFY FIGURED DIMENSIONS PRIOR TO ANY COMMENCEMENT OF WORK ON SITE.

THIS DRAWING IS COPYRIGHT AND SHALL REMAIN THE PROPERTY OF WOLSKI COPPIN ARCHITECTURE.

DATE	REV	DESCRIPTION
20.03.19	A	ADDED DIMENSIONS TO COURTYARD ADDED INFORMATION TO ADJOINING BUILDING NO.33
04.06.19	B	CHANGE OF STORE AT BASE REORGANIZATION OF WHISTLER ST AT STREET RECONFIGURATION OF STREET FACADE
05.02.20	C	LIFT - STAIRS MARKED

PROJECT TITLE: RESIDENTIAL DEVELOPMENT
21 WHISTLER ST MANLY

CLIENT: Urban Partners

ARCHITECT: WOLSKI . COPPIN ARCHITECTURE
5/18E 3, LEVEL 1, 507 MILBARY ROAD MOSMAN NSW 2088
1: 9553 8477 E: info@wolski Coppin.com.au
(DAVID WOLSKI) NSW A/RB No. 5297


DRAWING TITLE: LEVEL 1

DRAWING No: DA 03	PROJECT No: 21806	REVISION: C	NORTH POINT:
SCALE: 1:100 @ A3	DATE: 5/05/2020		

Appendix B


Transport Services

Manly bus network map



Legend

- Sydney Buses routes
- Ferry
- Diagrammatic Map - Not to Scale
- Rail line
- Railway station
- Bus route/suburb
- ◻ Bus/Rail interchange



Manly area map



- Legend**
- Bus stand
 - Kiss and ride
 - Ferry/Wharf
 - Parking
 - Taxi rank
 - Walking Route
 - Bus zone

Bus services at Manly

Bus departure information


Please use this listing to find your bus number, route destination and bus stand.
Refer to the Interchange Map to find the bus stand location.



Bus Stand	Route Number	Bus Route Destination
A	135	Warringah Mall via Balgowlah & Manly Vale
A	136	Chatswood via Curl Curl, Narraweena & Frenchs Forest
A	139	Warringah Mall via Harbord & South Curl Curl
B	155	Bayview Garden Village via Dee Why & Mona Vale
B	156	McCarrs Creek via Dee Why & Mona Vale
B	158	Cromer via Dee Why
B	159	Dee Why via Wingala
B	169	Narraweena via Dee Why
C	131	North Balgowlah via Balgowlah Heights
C	132	Warringah Mall via Balgowlah Hts & North Balgowlah
C	171/E71	City - Wynyard via Balgowlah Heights
D	143	Chatswood via Neutral Bay & St Leonards
D	144	Chatswood via Neutral Bay & RNS Hospital
E	140	Epping via Neutral Bay (Limited Stops)
E	142	Skyline Shops via Balgowlah & Allambie Heights
E	E50	Milsons Point (Express)
F	E70	City - Wynyard (Express)
G	151	City - QVB via Neutral Bay & North Sydney
H	151	Mona Vale via Manly Vale & Dee Why
J	135	Quarantine Station via Manly Hospital

Bus Operator Legend

 Sydney Buses




Key
ts

176	178	184	187
177	179	184	188
178	180	185	188
179	181	186	189
180	182	187	190
181	183	188	191
182	184	189	192
183	185	190	193
184	186	191	194
185	187	192	195
186	188	193	196
187	189	194	197
188	190	195	198
189	191	196	199
190	192	197	200
191	193	198	201
192	194	199	202
193	195	200	203
194	196	201	204
195	197	202	205
196	198	203	206
197	199	204	207
198	200	205	208
199	201	206	209
200	202	207	210
201	203	208	211
202	204	209	212
203	205	210	213
204	206	211	214
205	207	212	215
206	208	213	216
207	209	214	217
208	210	215	218
209	211	216	219
210	212	217	220
211	213	218	221
212	214	219	222
213	215	220	223
214	216	221	224
215	217	222	225
216	218	223	226
217	219	224	227
218	220	225	228
219	221	226	229
220	222	227	230
221	223	228	231
222	224	229	232
223	225	230	233
224	226	231	234
225	227	232	235
226	228	233	236
227	229	234	237
228	230	235	238
229	231	236	239
230	232	237	240
231	233	238	241
232	234	239	242
233	235	240	243
234	236	241	244
235	237	242	245
236	238	243	246
237	239	244	247
238	240	245	248
239	241	246	249
240	242	247	250
241	243	248	251
242	244	249	252
243	245	250	253
244	246	251	254
245	247	252	255
246	248	253	256
247	249	254	257
248	250	255	258
249	251	256	259
250	252	257	260
251	253	258	261
252	254	259	262
253	255	260	263
254	256	261	264
255	257	262	265
256	258	263	266
257	259	264	267
258	260	265	268
259	261	266	269
260	262	267	270
261	263	268	271
262	264	269	272
263	265	270	273
264	266	271	274
265	267	272	275
266	268	273	276
267	269	274	277
268	270	275	278
269	271	276	279
270	272	277	280
271	273	278	281
272	274	279	282
273	275	280	283
274	276	281	284
275	277	282	285
276	278	283	286
277	279	284	287
278	280	285	288
279	281	286	289
280	282	287	290
281	283	288	291
282	284	289	292
283	285	290	293
284	286	291	294
285	287	292	295
286	288	293	296
287	289	294	297
288	290	295	298
289	291	296	299
290	292	297	300
291	293	298	301
292	294	299	302
293	295	300	303
294	296	301	304
295	297	302	305
296	298	303	306
297	299	304	307
298	300	305	308
299	301	306	309
300	302	307	310
301	303	308	311
302	304	309	312
303	305	310	313
304	306	311	314
305	307	312	315
306	308	313	316
307	309	314	317
308	310	315	318
309	311	316	319
310	312	317	320
311	313	318	321
312	314	319	322
313	315	320	323
314	316	321	324
315	317	322	325
316	318	323	326
317	319	324	327
318	320	325	328
319	321	326	329
320	322	327	330
321	323	328	331
322	324	329	332
323	325	330	333
324	326	331	334
325	327	332	335
326	328	333	336
327	329	334	337
328	330	335	338
329	331	336	339
330	332	337	340
331	333	338	341
332	334	339	342
333	335	340	343
334	336	341	344
335	337	342	345
336	338	343	346
337	339	344	347
338	340	345	348
339	341	346	349
340	342	347	350
341	343	348	351
342	344	349	352
343	345	350	353
344	346	351	354
345	347	352	355
346	348	353	356
347	349	354	357
348	350	355	358
349	351	356	359
350	352	357	360
351	353	358	361
352	354	359	362
353	355	360	363
354	356	361	364
355	357	362	365
356	358	363	366
357	359	364	367
358	360	365	368
359	361	366	369
360	362	367	370
361	363	368	371
362	364	369	372
363	365	370	373
364	366	371	374
365	367	372	375
366	368	373	376
367	369	374	377
368	370	375	378
369	371	376	379
370	372	377	380
371	373	378	381
372	374	379	382
373	375	380	383
374	376	381	384
375	377	382	385
376	378	383	386
377	379	384	387
378	380	385	388
379	381	386	389
380	382	387	390
381	383	388	391
382	384	389	392
383	385	390	393
384	386	391	394
385	387	392	395
386	388	393	396
387	389	394	397
388	390	395	398
389	391	396	399
390	392	397	400
391	393	398	401
392	394	399	402
393	395	400	403
394	396	401	404
395	397	402	405
396	398	403	406
397	399	404	407
398	400	405	408
399	401	406	409
400	402	407	410
401	403	408	411
402	404	409	412
403	405	410	413
404	406	411	414
405	407	412	415
406	408	413	416
407	409	414	417
408	410	415	418
409	411	416	419
410	412	417	420
411	413	418	421
412	414	419	422
413	415	420	423
414	416	421	424
415	417	422	425
416	418	423	426
417	419	424	427
418	420	425	428
419	421	426	429
420	422	427	430
421	423	428	431
422	424	429	432
423	425	430	433
424	426	431	434
425	427	432	435
426	428	433	436
427	429	434	437
428	430	435	438
429	431	436	439
430	432	437	440
431	433	438	441
432	434	439	442
433	435	440	443
434	436	441	444
435	437	442	445
436	438	443	446
437	439	444	447
438	440	445	448
439	441	446	449
440	442	447	450
441	443	448	451
442	444	449	452
443	445	450	453
444	446	451	454
445	447	452	455
446	448	453	456
447	449	454	457
448	450	455	458
449	451	456	459
450	452	457	460
451	453	458	461
452	454	459	462
453	455	460	463
454	456	461	464
455	457	462	465
456	458	463	466
457	459	464	467
458	460	465	468
459	461	466	469
460	462	467	470
461	463	468	471
462	464	469	472
463	465	470	473
464	466	471	474
465	467	472	475
466	468	473	476
467	469	474	477
468	470	475	478
469	471	476	479
470	472	477	480
471	473	478	481
472	474	479	482
473	475	480	483
474	476	481	484
475	477	482	485
476	478	483	486
477	479	484	487
478	480	485	488
479	481	486	489
480	482	487	490
481	483	488	491
482	484	489	492
483	485	490	493
484	486	491	494
485	487	492	495
486	488	493	496
487	489	494	497
488	490	495	498
489	491	496	499
490	492	497	500
491	493	498	501
492	494	499	502
493	495	500	503
494	496	501	504
495	497	502	505
496	498	503	506
497	499	504	507
498	500	505	508
499	501	506	509
500	502	507	510
501	503	508	511
502	504	509	512
503	505	510	513
504	506	511	514
505	507		


Appendix C

Comparable Access Plan





East Elevation 1:200




West Elevation 1:200

PRELIMINARY 01 DECEMBER 2017


RD
 RobertDay
 ABN 53 667 372 703
 Level 17 Sandie SURRY HILLS NSW
 T +61 2 8202 8000 F adam.russell@robertday.com.au
 NOMINATED ARCHITECT: Adam Russell ARB #6762


REV.	DATE	DESCRIPTION

NOTES
 * DRAWINGS FOR PRELIMINARY APPLICATION ONLY
 * ALL DIMENSIONS SHOWN IN MILLIMETRES - ALL LEVELS SHOWN IN METRES UNLESS OTHERWISE NOTED
 * ALL DIMENSIONS + LEVELS TO BE CHECKED ON SITE PRIOR TO COMMENCEMENT OF WORK
 * WORK TO FIGURED DIMENSIONS - DO NOT SCALE OFF DRAWINGS
 * VERIFY ALL DIMENSIONS ON SITE - REPORT ALL DISCREPANCIES TO THE ARCHITECT



CLIENT:	TITLE	
SUN PROPERTY GROUP	ELEVATION EAST & WEST	
PROJECT ADDRESS	JOB NO.	DATE
139 NORTH STEYNE MANLY	SPG-NOR	15.11.2017
	SCALE	DWG NO. ISSUE
	1:200@A3	A300 -





Existing trees to be retained
Refer Landscape Architects documents.

Existing tree to be removed
shown dotted. Refer Landscape Architects documents.

Balcony profile above shown dotted


Landscape, refer to Landscape Architect's documents.

Existing footpath to be converted to driveway.

Courtyard profile above shown dotted

	Proposed	Control
Site Area	226.5m ²	729.2m ²
Level Ground GFA	307.9m ²	-
Level One GFA	307.9m ²	-
Level Two GFA	254.4m ²	-
Level Three GFA	1095.9m ²	1093.8m ²
Total GFA	1.51	1.51
FSR	562.6m ² 76%	328.1m ² 45%
Open Space	138.6m ² 26%	135.0m ² 25%
Landscaped Area	%	

PRELIMINARY 01 DECEMBER 2017



CLIENT:	SUN PROPERTY GROUP				TITLE
PROJECT ADDRESS	JOB NO.	DATE	SCALE	DWG NO.	ISSUE
139 NORTH STEYNE MANLY	SPG-NOR	29.09.2017	1:200@A3	A201	-



RobertsDay ABN: 53 447 979 703
 Level 17 Rundle SURRY HILLS NSW
 T +61 2 8202 8000 L admin@rd.com.au robertsday.com.au
 NOMINATED ARCHITECT Adam Esauell ARB 46762


REV. DATE	DESCRIPTION

NOTES
 - DRAWINGS FOR PRELIMINARY USE ONLY
 - ALL DIMENSIONS SHOWN IN MILLIMETRES - ALL LEVELS SHOWN IN METRES UNLESS OTHERWISE NOTED
 - ALL DIMENSIONS - EXCEPT FOR CURVES ON SITE - FROM TO CORNER POINT OF WORK
 - VERIFY ALL DIMENSIONS ON SITE - REPORT ALL DISCREPANCIES TO THE ARCHITECT

Appendix D

Car Stacker Details

- Page 1 Section Dimensions Car data
- Page 2 Door Width dimensions
- Page 3 Width dimensions Approach Free spaces
- Page 4 Function Load plan
- Page 5 Technical data
- Page 6 Electrical To be performed by the customer
- Page 7 Description



Loadable up to 2600 kg! Single parking spaces can also be upgraded to handle heavier loads at a later date!

Dimensions


Tolerances for space requirements ⁺³/₀³
 Dimensions in cm.

Suitable for


Standard passenger cars:
 Limousine, station wagon, SUV, van
 according to clearance and maximal surface load.

	Standard	Special ²
Width	190 cm ⁴	190 cm ⁴
Weight	max. 2000 kg	max. 2600 kg
Wheel load	max. 500 kg	max. 650 kg

Clearance profile




4300-175




Height	Car height		
	UF	GF	LF
325	150	150	150
345	150	170	150
365	150	190	150
365	170	170	150
380	150	205	150
405	190	190	150
435	205	205	150

4300-200




Height	Car height		
	UF	GF	LF
350	150	175	175
375	175	175	175
380	150	205	175
405	175	205	175
435	205	205	175

4300-230



Height	Car height		
	UF	GF	LF
380	150	205	205
405	175	205	205
420	190	205	205
435	205	205	205

4300-240



Height	Car height		
	UF	GF	LF
390	150	215	215
405	165	215	215
415	175	215	215
435	195	215	215
445	205	215	215
455	215	215	215

- 1 Standard type
 - 2 Special system: maximum load for extra charge.
 - 3 To follow the minimum finished dimensions, make sure to consider the tolerances according to VOB, part C (DIN 18330 and 18331) and the DIN 18202.
 - 4 Car width for platform width 230 cm. If wider platforms are used it is also possible to park wider cars.
 - 5 Potential equalization from foundation grounding connection to system (provided by the customer).
 - 6 Slope with drainage channel and sump.
 - 7 These floor areas need to be horizontal and on equal level across the full width of the pit
 - 8 For convenient use of your parking space and due to the fact that the cars keep becoming longer we recommend a pit length of 570 cm.
 - 9 At the transition section between pit floor and walls no hollow mouldings/coves are possible. If hollow mouldings/coves are required, the systems must be designed smaller or the pits accordingly wider.
- !** If sprinklers are required make sure to provide the necessary free spaces during the planning stage.

Page 1
Section
Dimensions
Car data

Page 2
Door
Width dimensions

Page 3
Width dimensions
Approach
Free spaces

Page 4
Function
Load plan


Page 5
Technical data

Page 6
Electrical
To be performed by the customer

Page 7
Description


Garages with sliding doors (standard) | Widths dimensions

Sliding door behind columns




Type	GT	Height	H1
4300	175	325/345/365/405	210
4300	175	380/435	220
4300	200	350/375	210
4300	200	380/405/435	220
4300	230	380/405/420/435	220
4300	240	390/405/415/435/445/455	230

Sliding door between columns




Type	GT	Height	H1
4300	175	325/345/365/405	220
4300	175	380/435	230
4300	200	350/375	220
4300	200	380/405/435	230
4300	230	380/405/420/435	230
4300	240	390/405/415/435/445/455	240

Sliding door in front of columns



Type	GT	Height	H1
4300	175	325/345/365/405	220
4300	175	380/435	230
4300	200	350/375	220
4300	200	380/405/435	230
4300	230	380/405/420/435	230
4300	240	390/405/415/435/445/455	240

Columns per each grid unit




Usable platform width	RB	B1	B2
230	250	250	230
240	260	260	240
250	270	270	250
260	280	280	260
270	290	290	270

Columns per each grid unit


Not available!

Columns per each grid unit




Usable platform width	RB	B1	B2
230	250	250	230
240	260	260	240
250	270	270	250
260	280	280	260
270	290	290	270

Columns every second grid unit




Usable platform width	RB	B3	B4
230	250	500	480
240	260	520	500
250	270	540	520
260	280	560	540
270	290	580	560

Columns every second grid unit



Usable platform width	RB	B3	B4
230	250	500	480
240	260	520	500
250	270	540	520
260	280	560	540
270	290	580	560

Columns every second grid unit



Usable platform width	RB	B3	B5
230	250	500	480
240	260	520	500
250	270	540	520
260	280	560	540
270	290	580	560

! According to the BGR 232, an inspection book is required for the commercial use of a gate with electric drive. Prior to commissioning, and then once a year, the gate has to be inspected by an expert and the findings entered in the inspection book. The inspection has to be carried out independent of any maintenance work.

For parking boxes on the edges and boxes with intermediate walls we recommend our maximum platform width of 270 cm. Please consider adjoining grids. Problems may occur if smaller platform widths are used (depending on car type, access and individual driving behaviour and capability).

For larger limousines and SUV wider driveways are necessary (in particular on the boxes on the sides due to the missing manoeuvring radius).


10 RB = Grid unit width **must** strictly conform to dimensions quoted!

11 Only applies to manually operated doors. The electrically driven doors must have 35 cm.


- Page 1
Section
Dimensions
Car data
- Page 2
Door
Width
dimensions
- Page 3
Width
dimensions
Approach
Free spaces
- Page 4
Function
Load plan
- Page 5
Technical
data
- Page 6
Electrical
To be performed by the customer
- Page 7
Description

Garages with roll doors | Widths dimensions

Roll door behind columns



Columns per each grid unit



Type	GT	Height	H1
4300	175	325/345/365/405	210
4300	175	380/435	220
4300	200	350/375	210
4300	200	380/405/435	220
4300	230	380/405/420/435	220
4300	240	390/405/415/435/445/455	230

Usable platform width	RB ¹⁰	B5	B6
230	250	250	230
240	260	260	240
250	270	270	250
260	280	280	260
270	290	290	270


! According to the BGR 232, an inspection book is required for the commercial use of a gate with electric drive. Prior to commissioning, and then once a year, the gate has to be inspected by an expert and the findings entered in the inspection book. The inspection has to be carried out independent of any maintenance work.

For parking boxes on the edges and boxes with intermediate walls we recommend our maximum platform width of 270 cm. Please consider adjoining grids. Problems may occur if smaller platform widths are used (depending on car type, access and individual driving behaviour and capability).

For larger limousines and SUV wider driveways are necessary (in particular on the boxes on the sides due to the missing manoeuvring radius).


¹⁰ RB = Grid unit width **must** strictly conform to dimensions quoted!

Approach



! The illustrated maximum approach angles must not be exceeded. Incorrect approach angles will cause serious manoeuvring & positioning problems on the parking system for which the local agency of KLAUS Multiparking accepts no responsibility.

Longitudinal free space



¹⁰ RB = Grid unit width **must** strictly conform to dimensions quoted!

Page 1
Section
Dimensions
Car data

Page 2
Door
Width
dimensions

Page 3
Width
dimensions
Approach
Free spaces

Page 4
Function
Load plan


Page 5
Technical
data

Page 6
Electrical
To be performed by the customer

Page 7
Description

Function with standard numbering and identification of parking levels

e.g. for parking space No. 8:
Check first that all doors are closed, then select No. 8 on operating panel.



For driving the vehicle off platform No. 8 the ground floor parking platforms are shifted to the left.

The empty space is now below the vehicle which shall be driven off the platform. The platform No. 8 will be lifted.

The vehicle on platform No. 8 can now be driven off the platform.

Load plan

4300-175

Type 4300-175			
Height	GF	H3	H4
325	150	130	245
345	170	150	265
365	190	170	285
365	170	150	265
380	205	185	300
405	190	170	285
435	205	185	300

4300-200

Type 4300-200			
Height	GF	H3	H4
350	175	155	270
375	175	155	270
380	205	185	300
405	205	185	300
435	205	185	300

4300-230

Type 4300-230			
Height	GF	H3	H4
380	205	185	300
405	205	185	300
420	205	185	300
435	205	185	300

4300-240

Type 4300-240			
Height	GF	H3	H4
390	215	195	310
405	215	195	310
415	215	195	310
435	215	195	310
445	215	195	310
455	215	195	310

Load plan – top view

Usable platform width	RB ¹⁰	RB1	RB2	Platform load	F1	F2	F3	F4	F5	F6	F7	F8	F9 ¹²
230	250	260	135	2000 kg	±5	±2,5	±14,5	+70	±29	±0,2	±2,5	+25	+50
240	260	270	140	2600 kg	±5	±2,5	±14,5	+80	±29	±0,2	±2,5	+35	+70
250	270	280	145										
260	280	290	150										
270	290	300	155										

! The system is dowelled to floor and walls. The drilling depth in the floor is approx. 15 cm. The drilling depth in the walls is approx. 12 cm.

Floor and walls are to be made of concrete (grade of concrete min. C20/25)!

The dimensions for the points of support are rounded values. If the exact position is required, please contact KLAUS Multiparking.

¹⁰ RB = Grid unit width **must** strictly conform to dimensions quoted!

¹² All forces in kN

Page 1
Section
Dimensions
Car data

Page 2
Door
Width
dimensions

Page 3
Width
dimensions
Approach
Free spaces

Page 4
Function
Load plan

Page 5
Technical
data

Page 6
Electrical
To be performed by the customer

Page 7
Description

Technical data

Field of application

By default, the system can only be used for a fixed number of users.

If different users use the system (e.g. short-time parkers in office buildings or hotels) the Multiparking system needs to be adjusted. If required, would you please contact us.

Available documents

- wall recess plans
- maintenance offer/contract
- declaration of conformity
- test sheet on airborne and slid-borne sound


Environmental conditions

Environmental conditions for the area of multiparking systems: Temperature range -10 to $+40^{\circ}\text{C}$. Relative humidity 50% at a maximum outside temperature of $+40^{\circ}\text{C}$.

If lifting or lowering times are specified, they refer to an environmental temperature of $+10^{\circ}\text{C}$ and with the system set up directly next to the hydraulic unit. At lower temperatures or with longer hydraulic lines, these times increase.

Numbering

Standard numbering of the parking spaces:



Initial position: lower floor platform No. 2 at entrance level (covering of pit; safety regulation).

Different numbering is only possible at extra cost

Please take note of the following specifications:

- In general, the empty space must be arranged to the left.
- The numbers must be provided 8 – 10 weeks before the delivery date.

Sound insulation

According to DIN 4109 (Sound insulation in buildings), para. 4, annotation 4, KLAUS Multiparkers are part of the building services (garage systems).

Normal sound insulation:

DIN 4109, para. 4, Sound insulation against noises from building services.

Table 4 in para. 4.1 contains the permissible sound level values emitted from building services for personal living and working areas. According to line 2 the maximum sound level in personal living and working areas must not exceed 30 dB (A).

Noises created by users are not subject to the requirements (see table 4, DIN 4109).

The following measures are to be taken to comply with this value:

- Sound protection package according to offer/order (KLAUS Multiparking GmbH)
- Minimum sound insulation of building $R'_w = 57$ dB (to be provided by customer)

Increased sound insulation (special agreement):

Draft DIN 4109-10, Information on planning and execution, proposals for increased sound insulation.

Agreement: Maximum sound level in personal living and working areas 25 dB (A). *Noises created by users are not subject to the requirements (see table 4, DIN 4109).*

The following measures are to be taken to comply with this value:

- Sound protection package according to offer/order (KLAUS Multiparking GmbH)
- Minimum sound insulation of building $R'_w = 62$ dB (to be provided by customer)

Note: User noises are noises created by individual users in our Multiparking systems. These can be noises from accessing the platforms, slamming of vehicle doors, motor and brake noises.

Electrically driven doors

In accordance with BGR 232 commercially used power-driven doors must be subjected to annual inspections. We urgently recommend concluding a maintenance agreement that includes this service for the entire system.

Building application documents

According to LBO and GaVo (garage regulations) the Multiparking systems are subject to approval. We will provide the required building application documents.

Care

To avoid damages resulting from corrosion, make sure to follow our cleaning and care instructions and to provide good ventilation of your garage.

Corrosion protection

See separate sheet regarding corrosion protection.

CE Certification

The systems on offer comply with DIN EN 14010 and EC Machine Directive 2006/42/EC. Furthermore, this system underwent voluntary conformity testing by TÜV SÜD.


ZERTIFIKAT ◆ CERTIFICATE ◆ 認証証書 ◆ CERTIFICADO ◆ CERTIFICAT



Certificate concerning the examination of conformity

Certificate no:	KP 194
Certification body:	TÜV SÜD Industrie Service GmbH Zertifizierungsstelle für Produkte der Fördertechnik Westendstr. 199 80686 München - Germany
Applicant / Certification holder:	Klaus Multiparking GmbH Hermann-Krum-Str. 2 88319 Altrach - Germany
Date of application:	2012-03-09
Manufacturer:	Klaus Multiparking GmbH Hermann-Krum-Str. 2 88319 Altrach - Germany
Product:	Equipment for power driven parking of motor vehicles
Type:	TrendVario 4100 2.000 kg and 2.600 kg TrendVario 4300 2.000 kg and 2.600 kg
Test laboratory:	TÜV SÜD Industrie Service GmbH Prüflaboratorium für Produkte der Fördertechnik Prüfbereich Maschinen der Fördertechnik Gottlieb-Daimler-Str. 7 70794 Filderstadt - Germany
Date and number of the test report / mark of conformity:	2014-01-22 TÜ SW-12-230 DG
Test specifications:	- 2006 / 42 / EC, Annex I - DIN EN 14010
Validity:	This Certificate is valid until 2019-02-13
Result:	The equipment fulfills the requirements of the test specifications for the respective scope of application stated in the annex (page 1) of this certificate, keeping the mentioned conditions.
Date of issue:	2014-02-14

Certification body for lifts and cranes




Chadri Noureddine

TUV®

Page 1
Section
Dimensions
Car data

Page 2
Door
Width
dimensions

Page 3
Width
dimensions
Approach
Free spaces

Page 4
Function
Load plan

Page 5
Technical
data

Page 6
Electrical
To be performed by the customer

Page 7
Description


Electrical data

Control box

The control box must be accessible at all times from outside!

Dimensions approx. 100 x 100 x 30 cm.

Cutting through of wall from control box to parking system (contact the local agency of KLAUS Multiparking for clarification).



Electrical supply to the control box / Foundation earth connector

Suitable electrical supply min. 5 x 2,5 mm² (3 PH+N+PE) to control box with mains fuse 3 x 16 A slow or over-current cut-out 3 x 16 A trigger characteristic K or C. DIN/VDE and local regulations must be taken into consideration.

Suitable electrical supply to the control box must be provided by the customer during installation. The functionality can be monitored on site by our fitters together with the electrician. If this cannot be done during installation for some reason for which the customer is responsible, the customer must commission an electrician at their own expense and risk.

In accordance with DIN EN 60204 (Safety of Machinery. Electrical Equipment), grounding of the steel structure is necessary, provided by the customer (distance between grounding max. 10 m).

Operating device

Easy-to-survey positioning (e.g. on column).

Protection against unauthorized use.

May also be recessed in wall if required.

To be performed by the customer

Safety fences

Any constraints that may be necessary according to DIN EN ISO 13857 in order to provide protection for the park pits for pathways directly in front, next to or behind the unit. This is also valid during construction.

Numbering of parking spaces

Consecutive numbering of parking spaces.

Building services

Any required lighting, ventilation, fire extinguishing and fire alarm systems as well as clarification and compliance with the relevant regulatory requirements.

Drainage

For the middle area of the pit we recommend a drainage channel, which you connect to a floor drain system or sump (50 x 50 x 20 cm). The drainage channel may be inclined to the side, however not the pit floor itself (longitudinal incline is available). In the interests of environmental protection we recommend painting the pit floor. Oil and petrol separators must be provided according to the statutory provisions when connecting to the public sewage system!

Wall cuttings

Any necessary wall cuttings.

Strip footings

If due to structural conditions strip footings must be effected, the customer shall provide an accessible platform reaching to the top of the said strip footings to enable and facilitate themounting work.

Electrical supply to the control box / Foundation earth connector

Suitable electrical supply to the control box must be provided by the customer during installation. The functionality can be monitored on site by our fitters together with the electrician. If this cannot be done during installation for some reason for which the customer is responsible, the customer must commission an electrician at their own expense and risk.

In accordance with DIN EN 60204 (Safety of Machinery. Electrical Equipment), grounding of the steel structure is necessary, provided by the customer (distance between grounding max. 10 m).

Door suspension

The lintel height H2 (see page 2) is absolutely necessary. With differing heights, additional fixings are required for extra charge.

Door shields

Door shields that may be necessary. If desired, they can be ordered from KLAUS Multiparking for an additional charge.

If the following are not included in the quotation, they will also have to be provided / paid for by the customer:

– Costs for final technical approval by an authorized body

Description

General description:

Multiparking system providing independent parking spaces for cars, one on top of the other and side by side.

Dimensions are in accordance with the underlying dimensions of parking pit, height and width.

The parking bays are accessed horizontally (installation deviation $\pm 1\%$).

Along the complete width of the parking automat an approach lane (driving lane in accordance with local regulations) must be available. Parking spaces are arranged on three different levels, one level on top of the other.

The platforms of both the lower floor (LF) and upper floor (UF) are moved vertically, the platforms of the ground floor (GF) horizontally. At approach level (GF) there is always one parking space less available. This vacant space is used for shifting the ground floor (GF) parking spaces sideways, thus enabling an upper floor (UF) parking space or lower floor (LF) parking space to be lowered or lifted to approach level. Consequently, a unit of five parking spaces (2 on the upper floor, 1 on the ground floor, 2 on the lower floor) is the smallest unit available for this parking system.

The TrendVario 4300 allows parking of passenger cars and station wagons.

For safety reasons the platforms can only be moved behind locked doors.

All necessary safety devices are installed. This consists mainly of a chain monitoring system, locking lever for the upper and lower platforms and locked doors. The doors can only be opened if the selected parking space has reached the park position and all openings are secured.

A steel framework mounted inside the pit, consisting of:

- Seriated supports
- Steel pillars with sliding platform supports
- Cross and longitudinal members
- running rails for the transversely movable ground floor (GF) platforms

Platforms consisting of:

- Side members
- Cross members
- Platform base sections
- 1 wheel stop (on the right per parking space)
- Screws, small parts, etc.

Lifting device for upper floor (UF) and lower floor (LF) platforms:

- Hydraulic cylinder with solenoid valve
- Chain wheels
- Chains
- Limit switches
- The platforms are suspended on four points and guided along the supports using plastic sliding bearings.

Drive unit of transversely movable platforms on the ground floor (GF):

- Gear motor with chain wheel
- Chains
- Running and guide rollers (low-noise)
- Power supply via cable chain

Page 1
Section
Dimensions
Car data

Page 2
Door
Width
dimensions

Page 3
Width
dimensions
Approach
Free spaces

Page 4
Function
Load plan

Page 5
Technical
data

Page 6
Electrical
To be performed by the customer

Page 7
Description

Description

Hydraulic unit consisting of:

- Hydraulic power unit (low-noise, installed onto a console with a rubber-bonded-to-metal mounting)
- Hydraulic oil reservoir
- Oil filling
- Internal geared wheel pump
- Pump holder
- Clutch
- 3-phase-AC-motor (3.0 kW, 230/400 V, 50 Hz)
- Motor circuit breaker
- Test manometer
- Pressure relief valve
- Hydraulic hoses (which reduce noise transmission onto the hydraulic pipe)

Control system:

- Central control panel (operating device) used to select the desired parking space
- With series installation, the doors are opened manually
If desired, this can also be done using electric motors
- Electric wiring is made from the electric cabinet by the manufacturer

Roller doors:

Size

Dimensions modified based on width and height measurements.

Shutter box

- 2-piece, roll formed aluminium box 45° consisting of upper and lower part
- lacquered type

Guide rails

- extruded aluminium guide rails with brush insert
- lacquered type

Gate type

- aluminium gate type, roll formed
- end rod with electronic safety strip
- lacquered type

Colour options

Shutter box, guide rails and gate type are available with the following colour options:

- RAL 9010 (white)
- RAL 7038 (light grey)
- RAL 9006 (aluminium metallic)

Door actuation

Powered electrically by means of tube motor in the shaft.

For safety reasons the movement of the platforms is always made behind locked doors. Position sensing, i.e. “door open” and “door closed” is effected by electric signalers.

Sliding doors:

Size

Sliding door, dimensions: approx. 2500 mm x 2000 mm (width x height).

Frame

- Frame construction with vertical centre stay bar made from extruded aluminium profiles (anodized, layer thickness approx 20 µm).
- To open the doors a recessed grip is integrated in the aluminium profile.
- A rubber lip is used for the finishing of the closing edge to the building.

Standard door panel

- Perforated steel plate
- Thickness 1mm, RV 5/8, galvanized, layer thickness: approx. 20 µm
- Ventilation cross-section of the panel approx. 40%
- Not suitable for outdoor garages

Alternative door panel

- Perforated aluminium plate
- Thickness 2mm, RV 5/8 E6/EV1, anodized, layer thickness: approx. 20 µm
- Ventilation cross-section of the panel approx. 40%

Beaded steel plate

- Thickness 1mm, galvanized, layer thickness: approx. 20 µm.
- additional power coating, layer thickness: approx. 25 µm on the outside and approx. 12 µm on the inside
- Colour options for the outside (building view):
RAL 1015 (light ivory), RAL 3003 (ruby),
RAL 5014 (pigeon blue), RAL 6005 (moss green),
RAL 7016 (charcoal grey), RAL 7035 (light grey),
RAL 7040 (window grey), RAL 8014 (sepia),
RAL 9006 (white aluminium), RAL 9016 (traffic white)
- Inside of the gates in light grey

Plain aluminium sheet

- Thickness 2mm, E6/EV1, anodized, layer thickness: approx. 20 µm

Wooden panelling

- Nordic spruce in grade A
- vertical tongue and groove boards
- preimpregnated colourless

Laminated safety glass

- Laminated safety glass made from single pane safety glass 8/4mm

Wire grating

- Mesh size 12 x 12 mm
- Mesh size 40 x 40 mm (for manual sliding gates only)

Running rails

- The running gear of each door consists of 2 twin-pair rolling gadgets, adjustable in height
- The running rails of the doors are fixed to brackets or the concrete lintel, or on a building-specific door suspension using ceiling fittings
- The guide consists of 2 plastic rollers mounted to a base plate, which is dowelled to the floor
- Running rails, ceiling fittings and guide roller base plate are hot-dip galvanized

Door actuation

Standard:

- Manually, i.e. the door is opened and closed by hand

Alternatively:

- Electric drive via electric motor mounted to the rail system at the turning point of the sliding doors. The drive pinion engages into the chain mounted to the door.

For safety reasons the movement of the platforms is always made behind locked doors. Position sensing, i.e. “door open” and “door closed” is effected by electric signalers.

Separation (if necessary):

- Upon request

Please note:


Door panels (on the side, cover for running rails, etc.) and door suspensions are not included in the standard version but can be delivered against surcharge as special equipment.

We reserve the right to change this specification without further notice

KLAUS Multiparking reserves the right in the course of technical progress to use newer or other technologies, systems, processes, procedures or standards in the fulfillment of their obligations other than those originally offered provided the customer derives no disadvantage from their so doing.


Appendix E

Turning Path Assessment





LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.



**SWEPT PATH ANALYSIS
OF AN 85th PERCENTILE
VEHICLE ENTERING THE LIFT**


SP 1



No.33
(BELGRAVE ST.)
THREE STOREY REND COMMERCIAL & UNIT
BUILDING
(METAL ROOF)



LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.



**SWEPT PATH ANALYSIS
OF AN 85th PERCENTILE
VEHICLE ENTERING THE SITE**


SP 3



No.33
(BELGRAVE ST.)
THREE STOREY REND COMMERCIAL & UNIT
BUILDING
(METAL ROOF)


LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.



**SWEPT PATH ANALYSIS
OF AN 85th PERCENTILE
VEHICLE ENTERING THE SITE**


SP 5



No.33
(BELGRAVE ST.)
THREE STOREY REND COMMERCIAL & UNIT
BUILDING



LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.



**SWEPT PATH ANALYSIS
OF AN 85th PERCENTILE
VEHICLE EXITING THE SITE**


SP 6



No.33
 (BELGRAVE ST.)
 THREE STOREY REND COMMERCIAL & UNIT
 BUILDING
 (METAL ROOF)


LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.



**SWEPT PATH ANALYSIS
 OF AN 85th PERCENTILE
 VEHICLE ENTERING THE SITE**


SP 7



No.33 (BELGRAVE ST.)
 THREE STOREY REND COMMERCIAL & UNIT BUILDING (METAL ROOF)



LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.




SWEPT PATH ANALYSIS OF AN 85th PERCENTILE VEHICLE EXITING THE SITE

SP 8




No.33
(BELGRAVE ST.)
THREE STOREY REND COMMERCIAL & UNIT
BUILDING
(METAL ROOF)



**SWEPT PATH ANALYSIS
OF AN 85th PERCENTILE
VEHICLE ENTERING THE SITE**


SP 9



No.33
(BELGRAVE ST.)
TWO STOREY REND COMMERCIAL & UNIT
BUILDING
(METAL ROOF)



LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.



**SWEPT PATH ANALYSIS
OF AN 85th PERCENTILE
VEHICLE EXITING THE SITE**


SP 10



No.33
(BELGRAVE ST.)
THREE STOREY REND COMMERCIAL & UNIT
BUILDING
(METAL ROOF)


LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.




**SWEPT PATH ANALYSIS
OF AN 85th PERCENTILE
VEHICLE ENTERING THE SITE**

SP 11



LEGEND

This drawing has been prepared using vehicle modelling computer software AutoTrack V5.00a in conjunction with AutoCAD 2013. The vehicle used is based upon vehicle data provided by Austroads and incorporates a reasonable degree of tolerance. However, it is not possible to account for all vehicle types/characteristics and/or driver ability.



SWEPT PATH ANALYSIS OF AN 85th PERCENTILE VEHICLE EXITING THE SITE

SP 12