

Application Number:

Development Permissible:

DEVELOPMENT APPLICATION ASSESSMENT REPORT

DA2022/1410

Responsible Officer:	Nick Keeler
Land to be developed (Address):	Lot 3 DP 327163, 41 Wyuna Avenue FRESHWATER NSW 2096
Proposed Development:	Demolition works and construction of a dwelling house including swimming pool
Zoning:	Warringah LEP2011 - Land zoned R2 Low Density Residential

Existing use Rights:	INO
Consent Authority:	Northern Beaches Council
Land and Environment Court Action:	No
Owner:	Jade Ilsa Thornton
Applicant:	Scott Warring Thornton

Yes

Application Lodged:	06/09/2022	
Integrated Development:	No	
Designated Development:	No	
State Reporting Category:	Residential - Single new detached dwelling	
Notified:	15/09/2022 to 29/09/2022	
Advertised:	Not Advertised	
Submissions Received:	0	
Clause 4.6 Variation:	Nil	
Recommendation:	Approval	

Estimated Cost of Works:	\$ 853,000.00
--------------------------	---------------

PROPOSED DEVELOPMENT IN DETAIL

The applicant seeks development consent for the demolition of the existing dwelling and construction of a new two-storey dwelling with basement garage, a swimming pool and associated earthworks, landscaping, retaining walls and driveway.

ASSESSMENT INTRODUCTION

The application has been assessed in accordance with the requirements of the Environmental Planning and Assessment Act 1979 and the associated Regulations. In this regard:

• An assessment report and recommendation has been prepared (the subject of this report)

DA2022/1410 Page 1 of 29



taking into account all relevant provisions of the Environmental Planning and Assessment Act 1979, and the associated regulations;

- A site inspection was conducted and consideration has been given to the impacts of the development upon the subject site and adjoining, surrounding and nearby properties;
- Notification to adjoining and surrounding properties, advertisement (where required) and referral
 to relevant internal and external bodies in accordance with the Act, Regulations and relevant
 Development Control Plan;
- A review and consideration of all submissions made by the public and community interest groups in relation to the application;
- A review and consideration of all documentation provided with the application (up to the time of determination):
- A review and consideration of all referral comments provided by the relevant Council Officers, State Government Authorities/Agencies and Federal Government Authorities/Agencies on the proposal.

SUMMARY OF ASSESSMENT ISSUES

Warringah Development Control Plan - B9 Rear Boundary Setbacks Warringah Development Control Plan - D1 Landscaped Open Space and Bushland Setting


SITE DESCRIPTION

Property Description:	Lot 3 DP 327163 , 41 Wyuna Avenue FRESHWATER NSW 2096
Detailed Site Description:	The subject site consists of one (1) allotment located on the northern side of Wyuna Avenue.
	The site is regular in shape with a frontage of 12.19m along Wyuna Avenue and a depth of 44.5m. The site has a surveyed area of 542.5m ² .
	The site is located within the R2 Low Density Residential zone and accommodates single storey residential dwelling and a detached garage.
	The site falls approx. 2m from the north towards the south.
	The site contains a predominately landscaped dwelling curtilage with large grassed areas at the front and rear. Two heritage listed trees are located at the front of the site within the road reserve.
	Detailed Description of Adjoining/Surrounding Development
	Adjoining and surrounding development is predominately characterised by low density residential dwellings. There are some medium density residential flat buildings in the locality, including to the east and south of the site.

Мар:

DA2022/1410 Page 2 of 29





SITE HISTORY

A search of Council's records has revealed that there are no recent or relevant applications for this site.

The land has been used for residential purposes for an extended period of time.

ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 (EPAA)

The relevant matters for consideration under the Environmental Planning and Assessment Act, 1979, are:

Section 4.15 Matters for Consideration	Comments
Section 4.15 (1) (a)(i) – Provisions of any environmental planning instrument	See discussion on "Environmental Planning Instruments" in this report.
Section 4.15 (1) (a)(ii) – Provisions of any draft environmental planning instrument	There are no current draft environmental planning instruments.
Section 4.15 (1) (a)(iii) – Provisions of any development control plan	Warringah Development Control Plan applies to this proposal.
Section 4.15 (1) (a)(iiia) – Provisions of any planning agreement	None applicable.
Section 4.15 (1) (a)(iv) – Provisions of the Environmental Planning and Assessment Regulation 2021 (EP&A Regulation 2021)	Part 4, Division 2 of the EP&A Regulation 2021 requires the consent authority to consider "Prescribed conditions" of development consent. These matters have been addressed via a condition of consent.
	Clause 29 of the EP&A Regulation 2021 requires the submission of a design verification certificate from the building designer at lodgement of the development application. This clause is not relevant to this application.

DA2022/1410 Page 3 of 29



Section 4.15 Matters for	Comments
Consideration	Clauses 36 and 94 of the EP&A Regulation 2021 allow Council to request additional information. Additional information was requested in relation to an arborist report.
	Clause 61 of the EP&A Regulation 2021 requires the consent authority to consider AS 2601 - 1991: The Demolition of Structures. This matter has been addressed via a condition of consent.
	Clauses 62 and/or 64 of the EP&A Regulation 2021 requires the consent authority to consider the upgrading of a building (including fire safety upgrade of development). This clause is not relevant to this application.
	Clause 69 of the EP&A Regulation 2021 requires the consent authority to consider insurance requirements under the Home Building Act 1989. This matter has been addressed via a condition of consent.
	Clause 69 of the EP&A Regulation 2021 requires the consent authority to consider the provisions of the Building Code of Australia (BCA). This matter has been addressed via a condition of consent.
Section 4.15 (1) (b) – the likely impacts of the development, including environmental impacts on the natural and built environment and social and economic impacts in the locality	(i) Environmental Impact The environmental impacts of the proposed development on the natural and built environment are addressed under the Warringah Development Control Plan section in this report.
	(ii) Social Impact The proposed development will not have a detrimental social impact in the locality considering the character of the proposal.
	(iii) Economic Impact The proposed development will not have a detrimental economic impact on the locality considering the nature of the existing and proposed land use.
Section 4.15 (1) (c) – the suitability of the site for the development	The site is considered suitable for the proposed development.
Section 4.15 (1) (d) – any submissions made in accordance with the EPA Act or EPA Regs	See discussion on "Notification & Submissions Received" in this report.
Section 4.15 (1) (e) – the public interest	No matters have arisen in this assessment that would justify the refusal of the application in the public interest.

DA2022/1410 Page 4 of 29



EXISTING USE RIGHTS

Existing Use Rights are not applicable to this application.

BUSHFIRE PRONE LAND

The site is not classified as bush fire prone land.

NOTIFICATION & SUBMISSIONS RECEIVED

The subject development application has been publicly exhibited from 15/09/2022 to 29/09/2022 in accordance with the Environmental Planning and Assessment Act 1979, Environmental Planning and Assessment Regulation 2021 and the Community Participation Plan.

As a result of the public exhibition of the application Council received no submissions.

REFERRALS

Internal Referral Body	Comments			
Landscape Officer	Additional Information Comment 4/01/2023 Additional information including amended Architectural Plans, amended Stormwater I Report are noted.			
	The amendments have reduced potential impacts on the street trees. The Arborist's Repusupervision during works by a Project Arborist, which is concurred with.			
	Specific tree protection conditions for before, during and after works have been included level of protection for the trees.			
	No objections are raised with regard to landscape issues subject to conditions as recomr			
	Original Comment The application seeks consent for demolition works and construction of a dwelling house pool.			
	The plans indicate that a new driveway crossover is proposed in Wyuna Avenue, adjacer trees. One tree is located in the verge and the other in the roadway.			
	The street trees in Wyuna Avenue are listed heritage items under WLEP 2011. No Arbori sighted with the application.			
	In order to establish potential impacts and subsequent mitigation of impacts on the trees have, an Arboricultural Impact Assessment prepared by a qualified Consultant Arborist (r qualification AQF Level 5) is required to be provided. The Arborist's report should also ac adjacent to the site affected by the proposed works.			
	The proposal is unable to be supported with regard to landscape issues due to lack of su to make an assessment.			

DA2022/1410 Page 5 of 29



Internal Referral Body	Comments		
NECC (Development Engineering)	1st referral Development Engineering has no objection to the application subject to the following con 2nd referral The location of the boundary pit and outlet to kerb has been relocated in response to imp Development Engineering has no objection to the application subject to the following con		
Strategic and	HERITAGE COMMENTS		
Place	Discussion of reason for referra	l	
Planning (Heritage Officer)	This application has been referred as it is adjacent to a local heritage item, being <i>Item I trees, Wyuna Avenue, Freshwater</i> , listed in Schedule 5 of Warringah LEP 2011. Ther heritage trees located adjacent to this property.		
	Details of heritage items affecte	d	
	Details of this heritage item, as contained within the Heritage Inventory, are: Item I79 - Street trees, Wyuna Avenue, Freshwater Statement of Significance A cultural landscape which demonstrates integrity of form & intactness. Aesthetically primportant streetscape qualities. Physical Description Established Brushbox trees (Lophostemum confertus) planted along both sides of the sof 8 - 10 metres and at regular intervals of approximately 8 metres.		
	Other relevant heritage listings		
	Sydney Regional Environmental Plan (Sydney Harbour Catchment) 2005	No	Comment if applicable
	Australian Heritage Register	No	
	NSW State Heritage Register	No	
	National Trust of Aust (NSW) Register	No	
	RAIA Register of 20th Century Buildings of Significance	No	
	Other	No	
	Consideration of Application		
	Original comment		

This application is for the demolition of the existing dwelling and construction of a new c pool and landscaping. The proposal also includes a new double driveway crossing.

There are 2 heritage listed Brushbox trees located outside this property - one located w itself and the other adjacent to the kerb. The location of the existing driveway crossing is alignment of the tree located within the road. Concern is raised as to the impact of cons works, including the new double driveway crossing, on the health of these 2 heritage list rees.

DA2022/1410 Page 6 of 29



Internal Referral Body	Comments
	It is noted that Landscape Referral Comments have asked for the submission of an Arb Impact Assessment report to address the impact of the works on these heritage trees. I supported.
	Heritage can only support the application on the basis that the health of the heritage list trees are not affected by the proposed construction works. To be sure of this, we will als see the Arboricultural Impact Assessment report and any Landscape Referral Condition being able to provide heritage support.
	Revised comment Amended plans and an Arborist Report have been submitted. These have been reviewe Council's landscape comments and required conditions. It is now considered that the pr landscape conditions will adequately protect the health of the two heritage listed street t to this site.
	Therefore, no heritage objections are raised, on the basis that all required landscaped conditions are included on any Notice of Determination. No additional heritage correquired.
	Further Comments Consider against the provisions of CL5.10 of WLEP 2011: Is a Conservation Management Plan (CMR) Required? No Hag a CMR been provided?
	Is a Conservation Management Plan (CMP) Required? No Has a CMP been provided? Is a Heritage Impact Statement required? No Has a Heritage Impact Statement been pr

External Referral Body	Comments
and Infrastructure) 2021, s2.48	The proposal was referred to Ausgrid who provided a response stating that the proposal is acceptable subject to compliance with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice. These recommendations will be included as a condition of consent.

ENVIRONMENTAL PLANNING INSTRUMENTS (EPIS)*

All, Environmental Planning Instruments (SEPPs and LEPs), Development Controls Plans and Council Policies have been considered in the merit assessment of this application.

In this regard, whilst all provisions of each Environmental Planning Instruments (SEPPs and LEPs), Development Controls Plans and Council Policies have been considered in the assessment, many provisions contained within the document are not relevant or are enacting, definitions and operational provisions which the proposal is considered to be acceptable against.

As such, an assessment is provided against the controls relevant to the merit consideration of the application hereunder.

State Environmental Planning Policies (SEPPs) and State Regional Environmental Plans

DA2022/1410 Page 7 of 29



(SREPs)

SEPP (Building Sustainability Index: BASIX) 2004

A BASIX certificate has been submitted with the application (see Certificate No. 1321242S_02, dated 28/07/2022).

The BASIX Certificate indicates that the development will achieve the following:

Commitment	Required Target	Proposed
Water	40	43
Thermal Comfort	Pass	Pass
Energy	50	52

A condition has been included in the recommendation of this report requiring compliance with the commitments indicated in the BASIX Certificate.

SEPP (Transport and Infrastructure) 2021

Ausgrid

Section 2.48 of Chapter 2 requires the Consent Authority to consider any development application (or an application for modification of consent) for any development carried out:

- within or immediately adjacent to an easement for electricity purposes (whether or not the electricity infrastructure exists).
- immediately adjacent to an electricity substation.
- within 5.0m of an overhead power line.
- includes installation of a swimming pool any part of which is: within 30m of a structure supporting an overhead electricity transmission line and/or within 5.0m of an overhead electricity power line.

Comment:

The proposal was referred to Ausgrid who raised no objections.

SEPP (Resilience and Hazards) 2021

Chapter 4 - Remediation of Land

Sub-section 4.6 (1)(a) of Chapter 4 requires the Consent Authority to consider whether land is contaminated. Council records indicate that the subject site has been used for residential purposes for a significant period of time with no prior land uses. In this regard it is considered that the site poses no risk of contamination and therefore, no further consideration is required under sub-section 4.6 (1)(b) and (c) of this Chapter and the land is considered to be suitable for the residential land use.

DA2022/1410 Page 8 of 29



Warringah Local Environmental Plan 2011

Is the development permissible?	Yes	
After consideration of the merits of the proposal, is the development consistent with:		
aims of the LEP?	Yes	
zone objectives of the LEP?	Yes	

Principal Development Standards

Standard	Requirement	Proposed	% Variation	Complies
Height of Buildings:	8.5m	8.5m	N/A	Yes

Compliance Assessment

Clause	Compliance with Requirements
4.3 Height of buildings	Yes
5.10 Heritage conservation	Yes
6.2 Earthworks	Yes
6.4 Development on sloping land	Yes

Warringah Development Control Plan

Built Form Controls

Built Form Control	Requirement	Proposed	% Variation*	Complies
B1 Wall height	7.2m	5.7m	N/A	Yes
B3 Side Boundary Envelope	E - 5m	Within envelope	N/A	Yes
	W - 5m	Within envelope	N/A	Yes
B5 Side Boundary Setbacks	E - 0.9m	1.3m	N/A	Yes
	W - 0.9m	1.3m	N/A	Yes
B7 Front Boundary Setbacks	6.5m	6.5m	N/A	Yes
B9 Rear Boundary Setbacks	6m	Dwelling - 10.3m	N/A	Yes
		Pool - 2.1m	65%	No
D1 Landscaped Open Space (LOS) and Bushland Setting	40% (217m ²)	35.4% (192m ²)	11.5% (25m ²)	No

Compliance Assessment

Clause	Compliance	Consistency
	with	Aims/Objectives
	Requirements	

DA2022/1410 Page 9 of 29



Clause	Compliance with Requirements	Consistency Aims/Objectives
A.5 Objectives	Yes	Yes
B1 Wall Heights	Yes	Yes
B3 Side Boundary Envelope	Yes	Yes
B5 Side Boundary Setbacks	Yes	Yes
B7 Front Boundary Setbacks	Yes	Yes
B9 Rear Boundary Setbacks	No	Yes
C2 Traffic, Access and Safety	Yes	Yes
C3 Parking Facilities	Yes	Yes
C4 Stormwater	Yes	Yes
C7 Excavation and Landfill	Yes	Yes
C8 Demolition and Construction	Yes	Yes
C9 Waste Management	Yes	Yes
D1 Landscaped Open Space and Bushland Setting	No	Yes
D2 Private Open Space	Yes	Yes
D3 Noise	Yes	Yes
D6 Access to Sunlight	Yes	Yes
D7 Views	Yes	Yes
D8 Privacy	Yes	Yes
D9 Building Bulk	Yes	Yes
D10 Building Colours and Materials	Yes	Yes
D11 Roofs	Yes	Yes
D12 Glare and Reflection	Yes	Yes
D14 Site Facilities	Yes	Yes
D16 Swimming Pools and Spa Pools	Yes	Yes
D20 Safety and Security	Yes	Yes
E1 Preservation of Trees or Bushland Vegetation	Yes	Yes
E2 Prescribed Vegetation	Yes	Yes
E6 Retaining unique environmental features	Yes	Yes
E10 Landslip Risk	Yes	Yes

Detailed Assessment

B9 Rear Boundary Setbacks

Description of non-compliance

The control requires all structures to be setback 6m from the rear boundary.

The proposed swimming pool is setback a minimum of 2.1m from the rear boundary, which represents a variation of 65%.

The proposed dwelling is setback 10.3m from the rear boundary and therefore complies with the control

DA2022/1410 Page 10 of 29



requirement.

On land zoned R2 Low Density Residential, where the minimum rear building setback is 6 metres, exempt development, swimming pools and outbuildings that, in total, do not exceed 50% of the rear setback area, provided that the objectives of this provision are met.

The rear setback area of the site is 73.7m². The extent of the non-compliance is 15.3m² which represents 20.8% of the rear setback area. As such, the variation outlined above applies in this instance.

Merit consideration:

With regard to the consideration for a variation, the development is considered against the underlying Objectives of the Control as follows:

To ensure opportunities for deep soil landscape areas are maintained.

Comment:

While the proposal does not comply with the minimum landscaped open space requirement, the site is considered to maintain an adequate amount of deep soil landscape area. See detailed assessment under Part D1 of WDCP.

To create a sense of openness in rear yards.

Comment:

The proposed development is not considered to unreasonably impact upon the openness of the rear yard.

• To preserve the amenity of adjacent land, particularly relating to privacy between buildings.

Comment:

The amenity and privacy impact of the proposed development on adjacent properties is not considered to be unreasonable in the context of the site and surrounds.

• To maintain the existing visual continuity and pattern of buildings, rear gardens and landscape elements.

Comment:

The existing visual continuity and building pattern is not considered to be unreasonably impacted by the proposed development. Proposed landscaping is able to be provided to reduce the visual impact of built structures.

To provide opportunities to maintain privacy between dwellings.

Comment:

Adequate levels of privacy between dwellings is considered to be maintained.

Having regard to the above assessment, it is concluded that the proposed development is consistent

DA2022/1410 Page 11 of 29



with the relevant objectives of WDCP and the objectives specified in s1.3 of the Environmental Planning and Assessment Act, 1979. Accordingly, this assessment finds that the proposal is supported, in this particular circumstance.

D1 Landscaped Open Space and Bushland Setting

Description of non-compliance

The control requires the minimum landscape open space (LOS) as being of 40% (217m²) of the site area with minimum dimensions of 2 metres.

The proposed development includes 35.4% (192m²) landscaped open space, representing a variation of 11.5% (25m²).

The site has 48.4% (262.8m²) LOS when including areas with dimensions less than 2 metres.

Merit consideration

With regard to the consideration for a variation, the development is considered against the underlying Objectives of the Control as follows:

• To enable planting to maintain and enhance the streetscape.

Comment:

Landscaping is proposed within the front setback area to assist in softening the visual impact of the proposed dwelling and enhance the visual quality of the streetscape.

To conserve and enhance indigenous vegetation, topographical features and habitat for wildlife.

Comment:

The site has been altered over the residential history of the allotment. There are no known threatened species or significant vegetation identified on site.

To provide for landscaped open space with dimensions that are sufficient to enable the
establishment of low lying shrubs, medium high shrubs and canopy trees of a size and density
to mitigate the height, bulk and scale of the building.

Comment:

Sufficient landscaped open space is provided to establish vegetation that is able to mitigate the visual bulk of the proposed development. There is adequate room for canopy trees and vegetation that is of a scale to reduce the dominance of the built form. In addition to this, the proposal incorporates several roof gardens to assist in improving the landscaped quality of the site.

• To enhance privacy between buildings.

Comment:

Acceptable levels of privacy is maintained between dwellings.

DA2022/1410 Page 12 of 29



• To accommodate appropriate outdoor recreational opportunities that meet the needs of the occupants.

Comment:

Adequate private open space is demonstrated.

• To provide space for service functions, including clothes drying.

Comment:

Acceptable space for service functions is provided.

To facilitate water management, including on-site detention and infiltration of stormwater.

Comment:

The site has adequate permeable surfaces to ensure that water management and the natural infiltration of stormwater into the ground can occur.

Having regard to the above assessment, it is concluded that the proposed development is consistent with the relevant objectives of WDCP and the objectives specified in s1.3 of the Environmental Planning and Assessment Act, 1979. Accordingly, this assessment finds that the proposal is supported, in this particular circumstance.

THREATENED SPECIES, POPULATIONS OR ECOLOGICAL COMMUNITIES

The proposal will not significantly affect threatened species, populations or ecological communities, or their habitats.

CRIME PREVENTION THROUGH ENVIRONMENTAL DESIGN

The proposal is consistent with the principles of Crime Prevention Through Environmental Design.

POLICY CONTROLS

Northern Beaches Section 7.12 Contributions Plan 2022

The proposal is subject to the application of Northern Beaches Section 7.12 Contributions Plan 2022.

A monetary contribution of \$8,530 is required for the provision of new and augmented public infrastructure. The contribution is calculated as 1% of the total development cost of \$853,000.

CONCLUSION

The site has been inspected and the application assessed having regard to all documentation submitted by the applicant and the provisions of:

- Environmental Planning and Assessment Act 1979;
- Environmental Planning and Assessment Regulation 2021;
- All relevant and draft Environmental Planning Instruments;

DA2022/1410 Page 13 of 29



- Warringah Local Environment Plan;
- Warringah Development Control Plan; and
- Codes and Policies of Council.

This assessment has taken into consideration the submitted plans, Statement of Environmental Effects, all other documentation supporting the application and public submissions, and does not result in any unreasonable impacts on surrounding, adjoining, adjacent and nearby properties subject to the conditions contained within the recommendation.

In consideration of the proposal and the merit consideration of the development, the proposal is considered to be:

- Consistent with the objectives of the DCP
- Consistent with the zone objectives of the LEP
- Consistent with the aims of the LEP
- Consistent with the objectives of the relevant EPIs
- Consistent with the objects of the Environmental Planning and Assessment Act 1979

It is considered that the proposed development satisfies the appropriate controls and that all processes and assessments have been satisfactorily addressed.

RECOMMENDATION

THAT Council as the consent authority grant Development Consent to DA2022/1410 for Demolition works and construction of a dwelling house including swimming pool on land at Lot 3 DP 327163, 41 Wyuna Avenue, FRESHWATER, subject to the conditions printed below:

DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

1. Approved Plans and Supporting Documentation

The development must be carried out in compliance with the endorsed stamped plans and documentation listed below, except as amended by any other condition of consent:

a) Approved Plans

Architectural Plans - Endorsed with Council's stamp			
Drawing No.	Dated	Prepared By	
TH-03-DA Issue B	01/11/2022	Rachel Hudson Architect	
TH-04-DA Issue A	28/06/2022	Rachel Hudson Architect	
TH-05-DA Issue A	28/06/2022	Rachel Hudson Architect	
TH-06-DA Issue A	28/06/2022	Rachel Hudson Architect	
TH-07-DA Issue A	28/06/2022	Rachel Hudson Architect	
TH-08-DA Issue A	28/06/2022	Rachel Hudson Architect	
TH-09-DA Issue A	28/06/2022	Rachel Hudson Architect	
TH-10-DA Issue A	28/06/2022	Rachel Hudson Architect	

DA2022/1410 Page 14 of 29



TH-11-DA Issue A	28/06/2022	Rachel Hudson Architect
TH-12-DA Issue A	28/06/2022	Rachel Hudson Architect
TH-13-DA Issue A	28/06/2022	Rachel Hudson Architect
TH-14-DA Issue A	28/06/2022	Rachel Hudson Architect

Engineering Plans		
Drawing No.	Dated	Prepared By
2207003 D01 Issue B	08/11/2022	NB Consulting Engineers
2207003 D02 Issue B	08/11/2022	NB Consulting Engineers
2207003 D03 Issue B	08/11/2022	NB Consulting Engineers
2207003 D04 Issue B	08/11/2022	NB Consulting Engineers
2207003 D05 Issue B	08/11/2022	NB Consulting Engineers

Reports / Documentation – All recommendations and requirements contained within:			
Report No. / Page No. / Section No.	Dated	Prepared By	
BASIX Certificate No. 1321242S_02	28/07/2022	Rachel Hudson	
Arboricultural Impact Assessment	16/11/2022	Tree Management Strategies	
Geotechnical Investigation (Ref: J4388)	28/07/2022	White Geotechnical Group	

- b) Any plans and / or documentation submitted to satisfy the Conditions of this consent.
- c) The development is to be undertaken generally in accordance with the following:

Landscape Plans			
Drawing No.	Dated	Prepared By	
Tho.LAN.01 Rev 02	01/08/2022	Mark Hill Garden Design	

Waste Management Plan		
Drawing No/Title.	Dated	Prepared By
Waste Management Plan	02/08/2022	Scott Thornton

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of Council and approved plans.

2. Compliance with Other Department, Authority or Service Requirements

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department,	EDMS Reference	Dated
Authority or Service		

DA2022/1410 Page 15 of 29



Ausgrid	Ausgrid Referral Response	14/09/2022	1
Ausynu	Ausgriu Neierrai Nesponse	14/03/2022	i

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website www.northernbeaches.nsw.gov.au)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

3. Approved Land Use

Nothing in this consent shall authorise the use of the site beyond the definition of a *dwelling house*, in accordance with the Dictionary of the Warringah Local Environmental Plan 2011.

Any variation to the approved land use beyond the scope of the above definition will require the submission to Council of a new development application.

Reason: To ensure compliance with the terms of this consent.

4. Prescribed Conditions

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (i) showing the name, address and telephone number of the Principal Certifier for the work, and
 - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
 - (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
 - (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and
 - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must

DA2022/1410 Page 16 of 29



not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
 - (i) protect and support the adjoining premises from possible damage from the excavation, and
 - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
 - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

5. **General Requirements**

(a) Unless authorised by Council:

Building construction and delivery of material hours are restricted to:

- 7.00 am to 5.00 pm inclusive Monday to Friday,
- 8.00 am to 1.00 pm inclusive on Saturday,
- No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

• 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (c) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of an Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (d) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.

DA2022/1410 Page 17 of 29



- (e) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (f) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (g) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (h) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (i) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (j) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (k) Prior to the commencement of any development onsite for:
 - i) Building/s that are to be erected
 - ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
 - iii) Building/s that are to be demolished
 - iv) For any work/s that is to be carried out
 - v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

- (I) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.
- (m) The works must comply with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice.
- (n) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.
 - (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

- (i) Swimming Pools Act 1992
- (ii) Swimming Pools Amendment Act 2009

DA2022/1410 Page 18 of 29



- (iii) Swimming Pools Regulation 2018
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
- (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
- (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
- (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

FEES / CHARGES / CONTRIBUTIONS

6. **Policy Controls**

Northern Beaches Section 7.12 Contributions Plan 2022

A monetary contribution of \$8,530.00 is payable to Northern Beaches Council for the provision of local infrastructure and services pursuant to section 7.12 of the Environmental Planning & Assessment Act 1979 and the Northern Beaches Section 7.12 Contributions Plan (as amended).

The monetary contribution is based on a development cost of \$853,000.00.

The total amount payable will be adjusted at the time the payment is made, in accordance with the provisions of the Northern Beaches Section 7.12 Contributions Plan (as amended).

Details demonstrating compliance, by way of written receipts issued by Council, are to be submitted to the Certifier prior to issue of any Construction Certificate or, if relevant, the Subdivision Certificate (whichever occurs first).

A copy of the Contributions Plan is available for inspection at 725 Pittwater Road, Dee Why or on Council's website at Northern Beaches Council - Development Contributions.

Reason: To provide for contributions in accordance with the Contribution Plan to fund the provision of new or augmented local infrastructure and services.

7. Security Bond

A bond (determined from cost of works) of \$5,000 and an inspection fee in accordance with Council's Fees and Charges paid as security are required to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from

DA2022/1410 Page 19 of 29



the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, and details demonstrating payment are to be submitted to the Certifier prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at www.northernbeaches.nsw.gov.au).

Reason: To ensure adequate protection of Council's infrastructure.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

8. Heritage Listed Trees

- a) The site is adjacent to Heritage Listed Trees as identified in the Warringah Local Environmental Plan. Heritage Listed Trees are to be protected from damage during construction.
- b) The following Heritage Listed Trees are located within the immediate vicinity of the approved works:
 - 2 x Lophostemon conferta, forward of the property in Wyuna Ave.

(Note: All Street trees in Wyuna Ave are Heritage Listed).

- c) A Tree Protection Plan for the 2 x Heritage Listed Trees forward of the property shall be prepared by an Arborist with minimum AQF Level 5 in arboriculture incorporating the following:
- i) layout of the development, including existing and proposed underground services,
- ii) location of all trees identified for retention, including extent of canopy,
- iii) access routes throughout the site for construction activity,
- iv) location of tree protection fencing / barriers,
- v) root protection in the form of mulching or boards proposed within the tree protection zone,
- vi) trunk and branch protection within the tree protection zone,
- vii) location of stockpile areas and materials storage.
- viii) inspection hold points,
- ix) tree protection measures in accordance with the recommendations of the Arboricultural Impact Assessment dated 16-11-22 prepared by Tree Management Strategies and AS4970-Protection of Trees on Development Sites.
- x) annotated photographs of the trees' trunks, branches and any exposed roots
- c) The Tree Protection Plan for the 2 x Heritage Listed Trees forward of the property shall be provided to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: protection of significant community assets.

9. **Boundary Identification Survey**

A boundary identification survey, prepared by a Registered Surveyor, is to be prepared in respect of the subject site.

DA2022/1410 Page 20 of 29



The plans submitted for the Construction Certificate are to accurately reflect the property boundaries as shown on the boundary identification survey, with setbacks between the property boundaries and the approved works consistent with those nominated on the Approved Plans of this consent.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of any Construction Certificate.

Reason: To ensure all approved works are constructed within the subject site and in a manner anticipated by the development consent.

10. On-site Stormwater Detention Details

The Applicant is to provide a certification of drainage plans detailing the provision of on-site stormwater detention in accordance with Northern Beaches Council's WATER MANAGEMENT FOR DEVELOPMENT POLICY, and generally in accordance with the concept drainage plans prepared by NB Consulting Engineers, Job number 2207003 drawings D01-D05 Issue B, dated 8/11/2022.Detailed drainage plans are to be prepared by a suitably qualified Civil Engineer.

Detailed drainage plans, including engineering certification, are to be submitted to the Principal Certifier for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater and stormwater management arising from the development.

11. Utilities Services

Prior to the issue of the Construction Certificate, the Applicant is to obtain an approval from TfNSW to relocate the School Zone sign and confirm the satisfactory arrangements have been made for the approved development.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To ensure that services have been provided as required by this Consent.

12. Structural Adequacy and Excavation Work

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required. All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To provide public and private safety.

13. Vehicle Crossings Application

The Applicant is to submit an application for driveway levels with Council in accordance with Section 138 of the Roads Act 1993. The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Principal Certifier prior to the issue of the Construction

DA2022/1410 Page 21 of 29



Certificate.

Reason: To facilitate suitable vehicular access to private property.

14. Compliance with Standards

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.

15. External Finishes to Roof

The external finish to the roof shall have a medium to dark range in order to minimise solar reflections to neighbouring properties. Any roof with a metallic steel finish is not permitted.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure that excessive glare or reflectivity nuisance does not occur as a result of the development.

16. Sydney Water "Tap In"

The approved plans must be submitted to the Sydney Water Tap in service, prior to works commencing, to determine whether the development will affect any Sydney Water assets and/or easements. The appropriately stamped plans must then be submitted to the Certifier demonstrating the works are in compliance with Sydney Water requirements.

Please refer to the website www.sydneywater.com.au for:

- o "Tap in" details see http://www.sydneywater.com.au/tapin
- o Guidelines for Building Over/Adjacent to Sydney Water Assets.

Or telephone 13 000 TAP IN (1300 082 746).

Reason: To ensure compliance with the statutory requirements of Sydney Water.

17. Fireplace

The proposed fireplaces must not utilise solid fuel or oil combustion.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

Reason: To ensure air pollution is mitigated and residential amenity is maintained.

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

18. **Project Arborist**

a) A Project Arborist, with minimum AQF Level 5 in arboriculture, shall be engaged to provide tree protection measures in accordance with the approved Tree Protection Plan and Australian Standard 4970-2009 Protection of Trees on Development Sites. The Project Arborist is to specify and oversee all tree protection measures such as tree protection fencing, trunk and branch protection and ground protection.

DA2022/1410 Page 22 of 29



- b) The Project Arborist is to supervise all demolition, excavation and construction works near all trees to be retained including construction methods near the existing trees to protect tree roots, trunks, branches and canopy. Where required, manual excavation is to occur ensuring no tree root at or >25mm (Ø) is damaged by works unless approved by the Project Arborist.
- c) Existing ground levels shall be maintained within the tree protection zone of trees to be retained unless authorised by the Project Arborist.
- d) The Project Arborist shall be in attendance and supervise all works as nominated in the approved Tree Protection Plan.
- e) All tree protection measures specified must:
- i) be in place before work commences on the site, and
- ii) be maintained in good condition during the construction period, and
- iii) remain in place for the duration of the construction works.
- f) The Project Arborist shall provide certification to the Principal Certifier that all recommendations listed for the protection of the existing trees have been carried out satisfactorily to ensure no impact to the health of the trees. Photographic documentation of the condition of all trees to be retained shall be recorded including at commencement, during the works and at completion.
- Note: i) A separate permit or development consent may be required if the branches or roots of a protected tree on the site or on an adjoining site are required to be pruned or removed.
 - ii) Any potential impact to trees as assessed by the Project Arborist will require redesign of any approved component to ensure existing trees upon the subject site and adjoining properties are preserved and shall be the subject of a modification application where applicable.

Reason: Tree protection.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

19. Protection of Existing Street Trees

- a) All existing street trees in the vicinity of the works shall be retained during all construction stages and the street trees fronting the development site shall be protected by tree protection fencing in accordance with Australian Standard 4687-2007 Temporary Fencing and Hoardings and in accordance with Section 4 of Australian Standard 4970-2009 Protection of Trees on Development Sites.
- b) As a minimum, the tree protection fencing for street tree(s) fronting the development site shall consist of standard 2.4m panel length to four sides unless otherwise directed by the Project Arborist.
- c) All fencing shall be located to allow for unrestricted and safe pedestrian access upon the road verge.
- d) Should any problems arise with regard to the existing or proposed trees on public land during construction, Council's Tree Services section is to be contacted immediately to resolve the matter to Council's satisfaction and at the cost of the applicant.

DA2022/1410 Page 23 of 29



Reason: Tree protection.

20. Tree and Vegetation Protection

- a) Existing trees and vegetation shall be retained and protected including:
 - all trees and vegetation within the site not indicated for removal/transplanting, excluding exempt trees and vegetation under the relevant planning instruments of legislation,
 - ii) all trees and vegetation located on adjoining properties,
 - iii) all road reserve trees and vegetation.
- b) Tree protection shall be undertaken as follows:
 - tree protection shall be in accordance with the approved Tree Protection Plan and Australian Standard 4970-2009 Protection of Trees on Development Sites including the provision of temporary fencing to protect existing trees within 5 metres of development,
 - ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained unless authorised by the Project Arborist,
 - iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with the Project Arborist,
 - iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
 - v) structures are to bridge tree roots at or >25mm (\emptyset) diameter unless directed by the Project Arborist on site,
 - vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone without consultation with the Project Arborist including advice on root protection measures,
 - vii) should either or all of v), vi) and vii) occur during site establishment and construction works, the Project Arborist shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Principal Certifier,
 - viii) any temporary access to or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of Australian Standard 4970-2009 Protection of Trees on Development Sites,
 - ix) the activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
 - x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy and shall be in accordance with Australian Standard 4373-2007 Pruning of Amenity Trees,
 - xi) the tree protection measures specified in this clause must: i) be in place before work commences on the site, and ii) be maintained in good condition during the construction period, and iii) remain in place for the duration of the construction works.

The Principal Certifier must ensure that:

DA2022/1410 Page 24 of 29



c) The activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites do not occur within the tree protection zone of any tree and any temporary access to or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained on the site during the construction is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.

Note: All street trees within the road verge and trees within private property are protected under Northern Beaches Council development control plans except where Council's written consent for removal has been obtained. The felling, lopping, topping, ringbarking or removal of any tree(s) is prohibited.

Reason: Tree and vegetation protection.

21. Condition of Trees

- a) During the construction period the applicant is responsible for ensuring all existing trees required to be retained are maintained in a healthy and vigorous condition. This is to be done by ensuring that all identified tree protection measures are adhered to or by seeking arboricultural advice from the Project Arborist during the works.
- b) In this regard all protected trees shall not exhibit:
- i) a general decline in health and vigour,
- ii) damaged, crushed or dying roots due to poor pruning techniques,
- iii) more than 10% loss or dieback of roots, branches and foliage,
- iv) mechanical damage or bruising of bark and timber of roots, trunk and branches,
- v) yellowing of foliage or a thinning of the canopy untypical of its species,
- vi) an increase in the amount of deadwood not associated with normal growth,
- vii) an increase in kino or gum exudation,
- viii) inappropriate increases in epicormic growth that may indicate that the plants are in a stressed condition,
- ix) branch drop, torn branches and stripped bark not associated with natural climatic conditions.
- c) Any mitigating measures and recommendations required by the Project Arborist are to be implemented.
- d) The owner of the adjoining allotment of land is not liable for the cost of work carried out for the purpose of this clause.

Reason: Protection of trees.

22. Road Reserve

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public safety.

23. Removing, Handling and Disposing of Asbestos

Any asbestos material arising from the demolition process shall be removed and disposed of in accordance with the following requirements:

DA2022/1410 Page 25 of 29



- Work Health and Safety Act;
- Work Health and Safety Regulation;
- Code of Practice for the Safe Removal of Asbestos [NOHSC:2002 (1998)];
- Guide to the Control of Asbestos Hazards in Buildings and Structures [NOHSC: 3002 (1998):
- Clause 42 of the Protection of the Environment Operations (Waste) Regulation 2005;
 and
- The demolition must be undertaken in accordance with Australian Standard AS2601 –
 The Demolition of Structures.

Reason: For the protection of the environment and human health.

24. Survey Certificate

A survey certificate prepared by a Registered Surveyor is to be provided demonstrating all perimeter walls columns and or other structural elements, floor levels and the finished roof/ridge height are in accordance with the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifier when the external structure of the building is complete.

Reason: To demonstrate the proposal complies with the approved plans.

25. Installation and Maintenance of Sediment Control

Prior to any works commencing on site, including demolition, sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004). Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site.

26. Vehicle Crossings

The Applicant is to construct one vehicle crossing 3.5 metres wide in accordance with Northern Beaches Council Drawing No A4-3330/1 N and the driveway levels application approval. An Authorised Vehicle Crossing Contractor shall construct the vehicle crossing and associated works within the road reserve in plain concrete. All redundant laybacks and crossings are to be restored to footpath/grass. Prior to the pouring of concrete, the vehicle crossing is to be inspected by Council and a satisfactory "Vehicle Crossing Inspection" card issued.

A copy of the vehicle crossing inspection form is to be submitted to the Principal Certifier.

Reason: To facilitate suitable vehicular access to private property.

27. Waste Management During Development

The reuse, recycling or disposal of waste during works must be done generally in accordance with the Waste Management Plan for this development.

Details demonstrating compliance must be submitted to the Principal Certifier.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

DA2022/1410 Page 26 of 29



CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

28. Landscape Completion

- a) Landscaping is to be implemented in accordance with the approved Landscape Plan.
- b) Prior to the issue of any Occupation Certificate details (from a qualified horticulturalist, landscape architect or landscape designer) shall be submitted to the Principal Certifier certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

29. Condition of Retained Vegetation - Project Arborist

Prior to the issue of an Occupation Certificate a report prepared by the Project Arborist shall be submitted to the Principal Certifier assessing the health and impact on all existing trees required to be retained including the following information:

- a) compliance to any Arborist recommendations for tree protection generally and during excavation works,
- b) extent of damage sustained by vegetation as a result of the construction works,
- c) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: Tree protection.

30. Positive Covenant and Restriction as to User for On-site Stormwater Disposal Structures
The Applicant shall lodge the Legal Documents Authorisation Application with the original
completed request forms (NSW Land Registry standard forms 13PC and/or 13RPA) to Council
and a copy of the Works-as-Executed plan (details overdrawn on a copy of the approved
drainage plan), hydraulic engineers' certification.

The Applicant shall create on the Title a restriction on the use of land and a positive covenant in respect to the ongoing maintenance and restriction of the on-site stormwater disposal structures within this development consent. The terms of the positive covenant and restriction are to be prepared to Council's standard requirements at the applicant's expense and endorsed by Northern Beaches Council's delegate prior to lodgement with the NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant. A copy of the certificate of title demonstrating the creation of the positive covenant and restriction for on-site storm water detention as to user is to be submitted.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure the on-site stormwater disposal system is maintained to an appropriate operational standard.

31. Removal of All Temporary Structures/Material and Construction Rubbish

Once construction has been completed all silt and sediment fences, silt, rubbish, building debris, straw bales and temporary fences are to be removed from the site.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

DA2022/1410 Page 27 of 29



Reason: To ensure bushland management.

32. House / Building Number

House/building number is to be affixed to the building to be readily visible from the public domain.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: Proper identification of buildings.

33. Waste Management Confirmation

Prior to the issue of an Occupation Certificate, evidence / documentation must be submitted to the Principal Certifier that all waste material from the development site arising from demolition and/or construction works has been appropriately recycled, reused or disposed of generally in accordance with the approved Waste Management Plan.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

34. Swimming Pool Requirements

The Swimming Pool shall not be filled with water nor be permitted to retain water until:

- (a) All required safety fencing has been erected in accordance with and all other requirements have been fulfilled with regard to the relevant legislative requirements and relevant Australian Standards (including but not limited) to:
 - (i) Swimming Pools Act 1992;
 - (ii) Swimming Pools Amendment Act 2009;
 - (iii) Swimming Pools Regulation 2018
 - (iv) Australian Standard AS1926 Swimming Pool Safety
 - (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
 - (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools
- (b) A certificate of compliance prepared by the manufacturer of the pool safety fencing, shall be submitted to the Principal Certifier, certifying compliance with Australian Standard 1926.
- (c) Filter backwash waters shall be discharged to the Sydney Water sewer mains in accordance with Sydney Water's requirements. Where Sydney Water mains are not available in rural areas, the backwash waters shall be managed onsite in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system. Appropriate instructions of artificial resuscitation methods.
- (d) A warning sign stating 'YOUNG CHILDREN SHOULD BE SUPERVISED WHEN USING THIS POOL' has been installed.
 - (e) Signage showing resuscitation methods and emergency contact
 - (f) All signage shall be located in a prominent position within the pool area.
 - (g) Swimming pools and spas must be registered with the Division of Local Government.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

DA2022/1410 Page 28 of 29



Reason: To protect human life.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

35. Swimming Pool/Spa Motor Noise

The swimming pool / spa motor shall not produce noise levels that exceed 5dBA above the background noise when measured from the nearest property boundary.

Reason: To ensure that the development does not impact on the acoustic privacy of surrounding residential properties.

In signing this report, I declare that I do not have a Conflict of Interest.

Signed

Nick Keeler, Planner

April

The application is determined on 04/01/2023, under the delegated authority of:

Rodney Piggott, Manager Development Assessments

DA2022/1410 Page 29 of 29