

Engineering Referral Response

Application Number:	DA2025/0447
Proposed Development:	Demolition works and construction of a residential flat building containing eleven (11) units with basement car parking, swimming pool and associated site works
Date:	29/05/2025
To:	Olivia Ramage
Land to be developed (Address):	Lot 2 SP 57603 , 2 / 32 Golf Avenue MONA VALE NSW 2103 Lot 2 SP 57603 , 2 / 32 Golf Avenue MONA VALE NSW 2103 Lot 4 SP 57603 , 4 / 32 Golf Avenue MONA VALE NSW 2103 Lot 4 SP 57603 , 4 / 32 Golf Avenue MONA VALE NSW 2103 Lot 1 SP 57603 , 1 / 32 Golf Avenue MONA VALE NSW 2103 Lot 1 SP 57603 , 1 / 32 Golf Avenue MONA VALE NSW 2103 Lot 3 SP 57603 , 3 / 32 Golf Avenue MONA VALE NSW 2103 Lot 3 SP 57603 , 3 / 32 Golf Avenue MONA VALE NSW 2103 Lot CP SP 57603 , 32 Golf Avenue MONA VALE NSW 2103

Reasons for referral

This application seeks consent for the following:

- New Dwellings or
- Applications that require OSD where additional impervious area exceeds 50m2 or
- Alterations to existing or new driveways or
- Where proposals affect or are adjacent to Council drainage infrastructure incl. watercourses and drainage channels or
- Torrens, Stratum and Community Title Subdivisions or
- All new Commercial and Industrial and RFB Development with the exception of signage or
- Works/uses in flood affected areas

And as such, Council's development engineers are required to consider the likely impacts on drainage regimes.

Officer comments

The submitted stormwater plan, which includes connecting site stormwater through the existing easement benefiting the site and extending the Council drainage system in Darley Street, is

acceptable subject to conditions.

The proposed driveway crossing is acceptable and complies with Council's standard (normal) profile. The existing crossing is to be reinstated with kerb, footpath, and turf.

The submitted Geotechnical Report satisfactorily addresses the relevant DCP controls.

Development Engineering supports the proposal, subject to the recommended conditions.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Engineering Conditions:

FEES / CHARGES / CONTRIBUTIONS

Construction, Excavation and Associated Works Security Bond(s)

The applicant is to lodge a bond with Council for the following:

Drainage Works

As security against any damage or failure to complete the construction of stormwater drainage works required as part of this consent a bond of \$75000.00.

Crossing / Kerb & Gutter / Footpath Works

As security against any damage or failure to complete the construction of any vehicular crossings, kerb and gutter, any footpath works and removal of any redundant driveways required as part of this consent a bond of \$20,000.00.

Maintenance for Civil Works

A maintenance bond of \$10,000.00 for the construction of stormwater drainage works. The maintenance bond will only be refunded upon completion of the six month maintenance period, if work has been completed in accordance with the approved plans and to the satisfaction of Council. The maintenance bond is to be paid prior to Council prior to issuing of practical completion.

Details confirming payment of the bond(s) are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

Traffic Management and Control

The Applicant is to submit an application for Traffic Management Plan to Council for approval prior to issue of the Construction Certificate. The Traffic Management Plan shall be prepared to TfNSW standards by an appropriately certified person.

Reason: To ensure appropriate measures have been considered for site access, storage and the

operation of the site during all phases of the construction process.

Stormwater Disposal

The applicant is to submit Stormwater Engineering Plans for the new development within this development consent in accordance with AS/NZS 3500 and Council's Water Management for Development Policy, prepared by an appropriately qualified and practicing Civil or Hydraulic Engineer who has membership to Engineers Australia, National Engineers Register (NER) or Professionals Australia (RPENG) , indicating all details relevant to the collection and disposal of stormwater from the site, buildings, paved areas and where appropriate adjacent catchments. Stormwater shall be conveyed from the site to [the inter-allotment drainage easement and proposed Councils pipeline in Darley Street..

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for disposal of stormwater management arising from the development.

Geotechnical Report Recommendations have been Incorporated into Designs and Structural Plans

The recommendations of the risk assessment required to manage the hazards as identified in the Geotechnical Report prepared by Crozier Geotechnical Consultants dated 11 April 2025 are to be incorporated into the construction plans. Prior to issue of the Construction Certificate, Form 2 of the Geotechnical Risk Management Policy for Pittwater (Appendix 5 of P21 DCP) is to be completed and submitted to the Accredited Certifier. Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.

Submission Roads Act Application for Civil Works in the Public Road

The Applicant is to submit an application for approval for infrastructure works on Council's roadway. Engineering plans for the new development works within the road reserve and this development consent are to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

The application is to include Civil Engineering plans for the design of driveway crossing, reinstatement of existing crossing reconstruction of concrete footpath full front the development in Golf Avenue which are to be generally in accordance with the Civil Engineering plans submitted by RTS Consulting Engineers, Project Number 240101_1 drawings CW001A, CW100A, CW200A, CW201A, SW001A, SW002A, SW100A and SW300A dated 11/04/2025. and Council's specification for engineering works - AUS-SPEC #1. All plans must be prepared by a qualified Civil Engineer and must incorporate the following design details:

1. The driveway crossing is to be constructed with a width of 5.5 metres at the kerb and 5.8 metres at the property boundary, in accordance with Council's Normal profile.
2. The existing driveway crossing is to be fully reinstated, including kerb, footpath, and turf.
3. The footpath along the entire site frontage is to be reconstructed to a width of 1.5 metres.

4. A new stormwater pit with a 1.8-metre lintel is to be provided in Darley Street.
5. A 375mm diameter RRJ Class 3 concrete pipe is to be installed between the new stormwater pit and the existing pit SPP50174 in Darley Street.
6. Kerb and gutter, including any laybacks, are to be reconstructed along the length of the new stormwater pipeline in Darley Street.
7. A detailed services plan is to be provided, along with concurrence from any affected service authorities.
8. If any damage occurs to existing concrete footpaths or laybacks during drainage construction, they must be reconstructed to the nearest footpath joint, or as approved by Council's Engineer.

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Principal Certifier prior to the issue of the Construction Certificate

Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification.

Utilities Services

Prior to the issue of the Construction Certificate, written evidence of the following service provider requirements must be provided to the Principal Certifier:

- a) a letter from Ausgrid demonstrating that satisfactory arrangements can be made for the installation and supply of electricity,
- b) a response from Sydney Water as to whether the proposed works subject to this consent would affect any Sydney Water infrastructure, and whether further requirements need to be met, and
- c) other relevant utilities or services - that the development as proposed to be carried out is satisfactory to those other service providers, or if it is not, the changes that are required to make the development satisfactory to them.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To ensure relevant utility and service providers' requirements are provided to the Principal Certifier.

Sub-Soil Seepage

The Applicant is to submit plans demonstrating that all sub-soil seepage drainage is discharged via a suitable silt arrester pit, directly to Council's nearest stormwater drainage line being **[INSERT]** and is to be carried out in accordance with relevant Australian Standards.

Note: At the time of determination the following (but not limited to) Standards applied:

- Australian/New Zealand Standard AS/NZS 3500.3 - 2003 Plumbing and drainage - Stormwater drainage
- Australian/New Zealand Standard AS/NZS 3500.3 - 2003 / Amdt 1 - 2006 Plumbing and drainage - Stormwater drainage.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To ensure appropriate drainage and Stormwater management on site to protect amenity of residents.

Shoring of Council's Road Reserve (Temporary road anchors)

Should the proposal require shoring to support an adjoining property or Council land, the Applicant shall provide the adjoining properties with engineering drawings, detailing the proposed shoring works for their consideration and approval.

Written approval from Council under Section 138 of the Roads Act 1993 is required if temporary ground anchors are to be used within Council's road reserve. The Owner's approval is to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: To ensure that owners consent is obtained for ancillary works, and to ensure the protection of adjoining properties and Council land.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Road Reserve

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public safety.

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

Post- Construction Stormwater Assets Dilapidation Report (Council stormwater assets)

The Applicant shall submit a post-construction Dilapidation Survey of Council's Stormwater Assets is to be prepared by a suitably qualified person in accordance with Council's Guidelines for Preparing a Dilapidation Survey of Council Stormwater Asset in order to determine if the asset has been damaged by the works. Council's Guidelines are available

at: <https://www.northernbeaches.nsw.gov.au/media/60355?1730767288>

The post-construction / demolition dilapidation report must be submitted to Council for review and approval. Any damage to Council's stormwater infrastructure is to be rectified prior to the release of any Drainage security bonds. Council's acceptance of the Dilapidation Survey is to be submitted to the Principal Certifier prior to the issue of the Occupation Certificate.

Reason: Protection of Council's infrastructure.

Certification of Civil Works and Works as Executed Data in accordance with Road Act Approval

The Applicant shall submit a certification by a suitably qualified Civil Engineer, who has membership to Engineers Australia, National Engineers Register (NER) or Professionals Australia (RPENG) that the completed works have been constructed in accordance with this consent and the approved Section 138 and/or Construction Certificate plans. Works as Executed data certified by a registered surveyor in relation to boundaries and/or relevant easements, prepared in accordance with Council's 'Guideline for preparing Works as Executed data for Council Assets' in an approved format shall be submitted to the Principal Certifier for approval prior to the issue of the Occupation Certificate.

Reason: To ensure compliance of works with Council's specification for engineering works.

Stormwater Disposal

The stormwater drainage works shall be certified as compliant with all relevant Australian Standards and Codes by a suitably qualified person. Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater arising from the development.

Positive Covenant for the Maintenance of Stormwater Pump-out Facilities

The Applicant shall lodge the Legal Documents Authorisation Application with Council. The application shall include the original completed request forms (NSW Land Registry standard forms 13PC) and a copy of the Works-as-Executed plan (details overdrawn on a copy of the approved drainage plan by a Registered Surveyor), and Civil Engineers' certification.

The Applicant shall create on the Title a positive covenant in respect to the ongoing maintenance of the pump-out facility on the property being developed. Northern Beaches Council shall be nominated in the instrument as the only party authorised to release, vary or modify the instrument. Northern Beaches Council's delegate shall sign these documents prior to the submission to the NSW Land Registry Services.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction for on-site storm water detention as to user is to be submitted.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure adequate provision is made for the stormwater pump out system to be maintained to an appropriate operational standard.

Geotechnical Certification Prior to Occupation Certificate

The Applicant is to submit the completed Form 3 of the Geotechnical Risk Management Policy (Appendix 5 of P21 DCP) to the Principal Certifier prior to issue of the Occupation Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.