

13 July 2020



H P G Fairlight Project Pty Ltd & Carl O Peterson  
Level 2 643 Military Road  
MOSMAN NSW 2088

Dear Sir/Madam

**Application Number:** DA2020/0302  
**Address:** Lot 6 DP 3742 , 41 Upper Clifford Avenue, FAIRLIGHT NSW 2094  
**Proposed Development:** Demolition works and construction of multi dwelling housing

Please find attached the Notice of Determination for the above mentioned Application.

Please be advised that a copy of the Assessment Report associated with the application is available on Council's website at [www.northernbeaches.nsw.gov.au](http://www.northernbeaches.nsw.gov.au)

Please read your Notice of Determination carefully and the assessment report in the first instance.

If you have any further questions regarding this matter please contact the undersigned on 1300 434 434 or via email quoting the application number, address and description of works to [council@northernbeaches.nsw.gov.au](mailto:council@northernbeaches.nsw.gov.au)

Regards,



Rodney Piggott  
**Manager Development Assessments**

## NOTICE OF DETERMINATION

<b>Application Number:</b>	DA2020/0302
<b>Determination Type:</b>	Development Application

### APPLICATION DETAILS

<b>Applicant:</b>	H P G Fairlight Project Pty Ltd & Carl O Peterson
<b>Land to be developed (Address):</b>	Lot 6 DP 3742 , 41 Upper Clifford Avenue FAIRLIGHT NSW 2094
<b>Proposed Development:</b>	Demolition works and construction of multi dwelling housing

### DETERMINATION - APPROVED

<b>Made on (Date)</b>	09/07/2020
<b>Consent to operate from (Date):</b>	09/07/2020
<b>Consent to lapse on (Date):</b>	09/07/2025

### Detail of Conditions

*The conditions, which have been applied to the consent, aim to ensure that the Environmental Impacts of Development are minimised and the Health and Safety of the community is maintained in accordance with the relevant standards and the Building Code of Australia.*

### Note:

*If the works are to be certified by a Private Certifying Authority, then it is the certifier's responsibility to ensure all outstanding fees and bonds have been paid to Council prior to the issue of the Construction Certificate or as otherwise specified by Consent conditions.*

## DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

### 1. **Approved Plans and Supporting Documentation**

The development must be carried out in compliance (except as amended by any other condition of consent) with the following:

#### a) Approved Plans

<b>Architectural Plans - Endorsed with Council's stamp</b>		
<b>Drawing No.</b>	<b>Dated</b>	<b>Prepared By</b>
DA 01 Site Plan	3 July 2020 Issue I	Platform Architects
DA 02 Basement Floor Plan	3 July 2020 Issue I	Platform Architects
DA 03 Ground Floor Plan	3 July 2020 Issue I	Platform Architects
DA 04 First Floor Plan	3 July 2020 Issue I	Platform Architects
DA 05 Second Floor Plan	3 July 2020 Issue I	Platform Architects
DA 06 Third Floor Plan	3 July 2020 Issue I	Platform Architects
DA 08 Ground Floor Plan - Garden	3 July 2020 Issue I	Platform Architects
DA 09 First Floor Plan	3 July 2020 Issue I	Platform Architects
DA 10 Second Floor Plan	3 July 2020 Issue I	Platform Architects
DA 11 Roof Plan - Sheet 1	3 July 2020 Issue I	Platform Architects
DA 12 Roof Plan - Sheet 2	3 July 2020 Issue I	Platform Architects
DA 13 Elevation 1 South	3 July 2020 Issue I	Platform Architects
DA 14 Elevation 2 - North	3 July 2020 Issue I	Platform Architects
DA 15 Elevation 3 - South	3 July 2020 Issue I	Platform Architects
DA 16 Elevation 4 - North	3 July 2020 Issue I	Platform Architects
DA 17 Elevation 5 - North	3 July 2020 Issue I	Platform Architects
DA 18 Sectional Elevation 6 - East Sheet 1	3 July 2020 Issue I	Platform Architects
DA 19 Section Elevation 6 - East Sheet 2	3 July 2020 Issue I	Platform Architects
DA 20 Sectional Elevation 7 - West Sheet 1	3 July 2020 Issue I	Platform Architects
DA 21 Sectional Elevation 7 - West Sheet 2	3 July 2020 Issue I	Platform Architects
DA 22 Section AA Sheet 1	3 July 2020 Issue I	Platform Architects
DA 23 Section AA Sheet 2	3 July 2020 Issue I	Platform Architects
DA 24 Section B-B	3 July 2020 Issue I	Platform Architects
External Finishes Schedule	Undated	Platform Architects

<b>Engineering Plans</b>		
<b>Drawing No.</b>	<b>Dated</b>	<b>Prepared By</b>
C1 Cover Sheet & Notes	24 February 2020	ACOR Consultants
C2 Stormwater Management Plan - Basement	2 March 2020	ACOR Consultants
C3 Stormwater Management Plan -	24 February 2020	ACOR Consultants

Ground		
C4 Stormwater Management Plan - Ground	24 February 2020	ACOR Consultants
C5 Stormwater Management Detail Sheet No. 1	24 February 2020	ACOR Consultants
C6 Stormwater Management Detail Sheet No. 2	24 February 2020	ACOR Consultants
C7 Stormwater Management Detail Sheet No. 3	2 March 2020	ACOR Consultants
C8 Erosion & Sediment Control Plan	24 February 2020	ACOR Consultants
C9 Erosion & Sediment Control Notes	24 February 2020	ACOR Consultants
C10 Erosion & Sediment Control Detail Sheet	24 February 2020	ACOR Consultants

**Reports / Documentation – All recommendations and requirements contained within:**

Report No. / Page No. / Section No.	Dated	Prepared By
BASIX Certificate No. 1073822M	16 March 2020	Credwell Energy
NatHERS Certificate No. 4673150	16 March 2020	Credwell Energy
NCC Assessment Report C19314-NCC-r2	11 March 2020	Credwell Consulting
Arboricultural Impact Assessment Report	February 2020	Axiom Arbor Tree Services
Construction Methodology Plan	Undated	TQM Design & Construct
Report on Geotechnical Site Investigation	26 February 2020	Crozier Geotechnical Consultants
Traffic Management Plan	19 February 2020	PW Traffic Plans
Traffic and Parking Assessment	March 2020	Transport and Traffic Planning Associates

b) Any plans and / or documentation submitted to satisfy the Conditions of this consent.

c) The development is to be undertaken generally in accordance with the following:

Landscape Plans		
Drawing No.	Dated	Prepared By
Landscape Plan	26 February 2020	Paul Scrivener Landscape Architects
Planting Plan	26 February 2020	Paul Scrivener Landscape Architects

Waste Management Plan		
Drawing No/Title.	Dated	Prepared By

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of Council and approved plans.

## 2. **Approved Land Use**

Nothing in this consent shall authorise the use of site/onsite structures/units/tenancies as detailed on the approved plans for any land use of the site beyond the definition of multi dwelling housing, defined by the Manly Local Environmental Plan 2013 as follows:

*Multi dwelling housing means 3 or more dwellings (whether attached or detached) on one lot of land, each with access at ground level, but does not include a residential flat building.*

Any variation to the approved land use and/occupancy of any unit beyond the scope of the above definition will require the submission to Council of a new development application.

Reason: To ensure compliance with the terms of this consent.

## 3. **Prescribed Conditions**

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
  - (i) showing the name, address and telephone number of the Principal Certifying Authority for the work, and
  - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
  - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.
- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
  - (i) in the case of work for which a principal contractor is required to be appointed:
    - A. the name and licence number of the principal contractor, and
    - B. the name of the insurer by which the work is insured under Part 6 of that Act,
  - (ii) in the case of work to be done by an owner-builder:
    - A. the name of the owner-builder, and
    - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
- (i) protect and support the adjoining premises from possible damage from the excavation, and
  - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
  - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
  - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

#### 4. **General Requirements**

- (a) Unless authorised by Council:  
Building construction and delivery of material hours are restricted to:

- 7.00 am to 5.00 pm inclusive Monday to Friday,
- 8.00 am to 1.00 pm inclusive on Saturday,
- No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (c) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of a final Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (d) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be

maintained in a safe and clean state until such time as new construction works commence.

- (e) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (f) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (g) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (h) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (i) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (j) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (k) Prior to the commencement of any development onsite for:
  - i) Building/s that are to be erected
  - ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
  - iii) Building/s that are to be demolished
  - iv) For any work/s that is to be carried out
  - v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

- (l) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.
- (m) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.
  - (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

- (i) Swimming Pools Act 1992
- (ii) Swimming Pools Amendment Act 2009



- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
- (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
- (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
- (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

## FEES / CHARGES / CONTRIBUTIONS

### 5. **Policy Controls**

#### Northern Beaches 7.12 Contributions Plan 2019

A monetary contribution of \$38,000.00 is payable to Northern Beaches Council for the provision of local infrastructure and services pursuant to section 7.12 of the Environmental Planning & Assessment Act 1979 and the Northern Beaches Section 7.12 Contributions Plan 2019. The monetary contribution is based on a development cost of \$3,800,000.00.

The monetary contribution is to be paid prior to the issue of the first Construction Certificate or Subdivision Certificate whichever occurs first, or prior to the issue of the Subdivision Certificate where no Construction Certificate is required. If the monetary contribution (total or in part) remains unpaid after the financial quarter that the development consent is issued, the amount unpaid (whether it be the full cash contribution or part thereof) will be adjusted on a quarterly basis in accordance with the applicable Consumer Price Index. If this situation applies, the cash contribution payable for this development will be the total unpaid monetary contribution as adjusted.

The proponent shall provide to the Certifying Authority written evidence (receipt/s) from Council that the total monetary contribution has been paid.

The Northern Beaches Section 7.12 Contributions Plan 2019 may be inspected at 725 Pittwater Rd, Dee Why and at Council's Customer Service Centres or alternatively, on Council's website at [www.northernbeaches.nsw.gov.au](http://www.northernbeaches.nsw.gov.au)

This fee must be paid prior to the issue of the Construction Certificate. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To provide for contributions in accordance with the Contribution Plan to fund the provision of new or augmented local infrastructure and services.



## 6. **Security Bond**

A bond (determined from cost of works) of \$5,000 and an inspection fee in accordance with Council's Fees and Charges paid as security to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, details demonstrating payment are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at [www.northernbeaches.nsw.gov.au](http://www.northernbeaches.nsw.gov.au)).

Reason: To ensure adequate protection of Council's infrastructure.

## 7. **Construction, Excavation and Associated Works Security Bond**

The applicant is to lodge a Bond of \$10,000 as security against any damage or failure to complete the construction of any vehicular crossings, kerb and gutter, any footpath works and removal of any redundant driveways required as part of this consent.

Details confirming payment of the bond are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

## 8. **On-slab Landscape Works**

a) Details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate indicating the proposed method of waterproofing to all internal walls and slab, and drainage of the garage concrete slab, soil and planting is being provided.

b) Landscape treatment details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate indicating the proposed soil type, planting, automatic irrigation, services connections, and maintenance activity schedule.

c) The following soil depths are required to support landscaping as proposed:

- 300mm for lawn
- 600mm for shrubs
- 1000mm for trees

d) Design certification shall be submitted to the Certifying Authority by a qualified Structural Engineer, that the concrete slab is designed structurally to support the 'wet' weight of landscaping (soil, materials and established planting).

Reason: To ensure appropriate and secure waterproofing and drainage is installed to direct water flow into the drainage system.

## 9. **Geotechnical Report**

The applicant must submit a geotechnical report and certificate, prepared by an appropriately qualified geotechnical engineer containing the following:

- (a) certification that the existing rock formations and substrate on the site are capable of withstanding the proposed loads to be imposed;
- (b) the extent of the proposed excavation, including any requirements for excavation methodology and shoring works that are necessary to ensure the stability of the excavation;
- (c) required protection for adjoining properties;
- (d) the provision of appropriate subsoil drainage during and upon completion of construction works.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the structural integrity of the subject site and adjoining sites during the excavation process.

## 10. **Boundary Identification Survey**

A boundary identification survey, prepared by a Registered Surveyor, is to be prepared in respect of the subject site.

The plans submitted for the Construction Certificate are to accurately reflect the property boundaries as shown on the boundary identification survey, with setbacks between the property boundaries and the approved works consistent with those nominated on the Approved Plans of this consent.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

Reason: To ensure all approved works are constructed within the subject site and in a manner anticipated by the development consent.

## 11. **On-site Stormwater Detention Details**

The Applicant is to provide a certification of drainage plans detailing the provision of on-site stormwater detention in accordance with Northern Beaches Council's MANLY SPECIFICATION FOR ON-SITE STORMWATER MANAGEMENT 2003, and generally in accordance with the concept drainage plans prepared by Acor Consultants Pty Ltd, Project No. CC200036, drawing number C1 -C4, Rev c, dated 24/2/2020. Detailed drainage plans are to be prepared by a suitably qualified Civil Engineer.

The drainage plans must address the following:

- i. Maximum discharge to street kerb is 25 l/s

Detailed drainage plans, including engineering certification, are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater and stormwater management arising from the development.

## 12. **Submission Roads Act Application for Civil Works in the Public Road**

An Application for Works to be approved within Council Roadway, including engineering plans is to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

The application is to include four (4) copies of Civil Engineering plans for the design of the retaining walls through the nature strip, driveway crossing and footpath which are to be generally in accordance with the Development Application and Council's specification for engineering works - AUS-SPEC #1 and/or Council's Minor Works Policy. The plan shall be prepared by a qualified structural engineer. The design must include the following information:

- 1 ) The proposed retaining wall shall be designed in complies with Australian Standard: Earth retaining Structure AS 4678-2002
- 2 ) An appropriate drainage system for the retaining wall shall be designed and included on the drawing
- 3 ) All Public and private utility services are to be located on the plan and cross-section plan. All costs related to any relocation of utility service shall be borne by the applicant.
- 4 ) The proposed footpath must be designed with Council's standard and satisfaction

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges. An approval is to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To provide public and private safety.

### 13. **Tanking of Basement Level**

The basement area is to be permanently tanked. The Applicant is to submit structural details of the tanking, prepared by a suitably qualified Engineer. Where temporary dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Office of Environment and Heritage. The bore license must be obtained prior to commencement of dewatering works. All requirements of the NSW Office of Water are to be complied with and a copy of the approval must be submitted to the Certifying Authority. Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To prevent ingress of sub-surface flows into the basement area and to comply with State Government Requirements.

### 14. **Structural Adequacy and Excavation Work**

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required. All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer, except where site conditions permit the following:

- (a) maximum height of 900mm above or below ground level and at least 900mm from any property boundary, and
- (b) Comply with AS3700, AS3600 and AS1170 and timber walls with AS1720 and AS1170.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To provide public and private safety.

### 15. **Shoring of Council's Road Reserve (Temporary road anchors)**

Should the proposal require shoring to support an adjoining property or Council land, the

Applicant shall provide the adjoining properties with engineering drawings, detailing the proposed shoring works for their consideration and approval.

Written approval from Council under Section 138 of the Roads Act 1993 is required if temporary ground anchors are to be used within Council's road reserve. The Owner's approval is to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure that owners consent is obtained for ancillary works, and to ensure the protection of adjoining properties and Council land.

**16. Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.

**17. Amendment to Landscape Plan and Planting Plan**

The approved Landscape Plan and Planting Plan are to be amended to replace (where necessary) vegetation along the northern half of the western side boundary (adjacent to Unit 1) with species that are anticipated to grow to a maximum of 5m in height at maturity. Details demonstrating compliance with this condition are to be submitted to the satisfaction of the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To allow reasonable sharing of views.

**18. Garage to Upper Clifford Avenue**

The proposed garage for Unit 1 fronting Upper Clifford Avenue is not to cover or block airflow to any part of the ventilation screen (air conditioning vent) on the western elevation of the garage at 39 Upper Clifford Avenue, Fairlight. Details demonstrating compliance with this condition are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Retention of air circulation to the garage of 39 Upper Clifford Avenue, Fairlight.

**19. Vehicle Access & Parking**

All internal driveways, vehicle turning areas, garages and vehicle parking space/ loading bay dimensions must be designed and constructed to comply with the relevant section of AS 2890 (Off-street Parking standards). Where disabled parking spaces are provided they must be in accordance with AS2890.6:2009

With respect to this, the following revision(s) must be undertaken;

All internal driveways and vehicle access ramps must have ramp grades and transitions complying with AS 2890.1. To ensure the gradient requirements and height clearances are satisfied, a driveway profile must be prepared for all internal ramps showing ramp lengths, grades, surface RL's and overhead clearances, taken from the crest of the ramp to the base. The driveway profile must be taken along the steepest grade of travel or sections having significant changes in grades, where scraping or height restrictions could potentially occur and is to demonstrate compliance with AS 2890 for the respective type of vehicle.

Plans prepared by a suitably qualified Engineer shall be submitted to the accredited certifier prior to the issue of a Construction Certificate.

Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles.

**20. Visitor Parking Spaces**

The installation of any security roller shutter for parking areas shall not restrict access to any designated visitor car parking space. In the event that the approved visitor car parking spaces are located behind any proposed security roller shutter, an intercom system is required to be installed to enable visitor access into the basement car parking area. This requirement is to be reflected on the Construction Certificate plans and any supporting documentation for the endorsement of the Certifying Authority prior to the release of the Construction Certificate.

Reason: To ensure visitor car parking is accessible to visitors.

**21. Waste and Recycling Requirements**

Details demonstrating compliance with Northern Beaches Development Control Plan – Part C9 Waste Management, including the required Northern Beaches Waste Management Plan, are to be submitted to and approved by the Certifying Authority prior to the issue of any Construction Certificate.

Note: If the proposal, when compliant with Northern Beaches Development Control Plan – Part C9 Waste Management, causes inconsistencies with other parts of the approval i.e. architectural or landscaped plans a modification(s) to the development may be required.

Reason: To ensure adequate and appropriate waste and recycling facilities are provided.

## **CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT**

**22. Pre-Construction Dilapidation Report**

Dilapidation reports, including photographic surveys, of the following adjoining properties must be provided to the Principal Certifying Authority prior to any works commencing on the site (including demolition or excavation):

- 54 Lauderdale Avenue
- 39 Upper Clifford Avenue
- 43 Upper Clifford Avenue

The reports must detail the physical condition of those properties listed below, both internally and externally, including walls, ceilings, roof, structural members and other similar items.

The dilapidation report is to be prepared by a suitably qualified person. A copy of the report must be provided to Council, the Principal Certifying Authority and the owners of the affected properties prior to any works commencing.

In the event that access for undertaking the dilapidation report is denied by an adjoining owner, the applicant must demonstrate, in writing that all reasonable steps have been taken to obtain access. The Principal Certifying Authority must be satisfied that the requirements of this condition have been met prior to commencement of any works.

Note: This documentation is for record keeping purposes and may be used by an applicant or affected property owner to assist in any action required to resolve any civil dispute over damage rising from the works.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the commencement of any works on site.

Reason: To maintain proper records in relation to the proposed development.

**23. Public Liability Insurance - Works on Public Land**

Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of, and approved works within Council's road reserve or public land, as approved in this consent. The Policy is to note, and provide protection for Northern Beaches Council, as an interested party and a copy of the Policy must be submitted to Council prior to commencement of the works. The Policy must be valid for the entire period that the works are being undertaken on public land.

Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land.

**24. Tree Removal Within the Property**

The following tree located on the property and assessed as impacted by development, and without an alternative design layout to retain the tree, as assessed and recommended in the Arboricultural Impact Assessment prepared by Axiom Arbor Tree Services, is granted approval for removal:

- Tree 5 Cheese Tree (subject to tree replacement within the site)

Note: Any request to remove a tree approved for retention under the development application is subject to a Section 4.55 modification application, or an assessment by a AQF level 5 Arborist that determines that the tree presents an imminent risk to life or property.

Exempt Species located within the site do not require consent for removal.

**25. Work Zones and Permits**

Prior to commencement of the associated works, the applicant shall obtain a Work Zone Permit if it is proposed to reserve an area of road pavement for the parking of vehicles associated with a construction site. Separate application is required with a Traffic Management / Control Plan for standing of construction vehicles in a trafficable lane.

Reason: To ensure Work zones are monitored and installed correctly.

## **CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK**

**26. Road Reserve**

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public safety.

**27. Survey Certificate**

A survey certificate prepared by a Registered Surveyor at the following stages of construction:

- (a) Commencement of perimeter walls columns and or other structural elements to ensure the wall or structure, to boundary setbacks are in accordance with the approved details.



(b) At ground level to ensure the finished floor levels are in accordance with the approved levels, prior to concrete slab being poured/flooring being laid.

(c) At completion of the roof frame confirming the finished roof/ridge height is in accordance with levels indicated on the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To determine the height of buildings under construction comply with levels shown on approved plans.

28. **Traffic Control During Works**

Lighting, fencing, traffic control and advanced warning signs shall be provided for the protection of the works and for the safety and convenience of the public and others in accordance with RMS Traffic Control At Work Sites Manual and to the satisfaction of the Roads Authority. Traffic movement in both directions on public roads, and vehicular access to private properties is to be maintained at all times during the works

Reason: Public safety.

29. **Excavation Works Supervision**

All excavation works approved in the Construction Certificate are to be supervised by an appropriately qualified and practising geotechnical engineer. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure safety of the excavation works.

30. **Tree Protection Measures / Project Arborist**

A Project Arborist with AQF minimum Level 5 qualification in arboriculture/horticulture is to be appointed to supervise and certify tree protection measures for existing trees to be retained and protected, requiring site attendance during excavation and construction works, in accordance with AS4970- 2009 Protection of Trees on Development Sites, with particular reference to Section 4, and the recommendations of the Arboricultural Impact Assessment prepared by Axiom Arbor Tree Services dated February 2020.

This shall include all tree sensitive works in the vicinity of the existing trees that have been identified for retention in the Arboricultural Impact Assessment, and in particular the following trees: T1, T2, T3 and T4 (all Broad Leaf Paperbark) located on adjoining property.

The following activities as listed in the Arboricultural Impact Assessment shall be specifically supervised and certified as approved following attendance on site, review of the works and acceptance of the works. A Project Arborist shall be appointed prior to the commencement of works in accordance with the Arboricultural Impact Assessment section 6 Recommendations, including the actions detailed under the following:

- i) 6.1 Assigning a site arborist,
- ii) 6.2 Tree works,
- iii) 6.3 Tree Protection Fencing,
- iv) 6.4 Mulching within a TPZ,
- v) 6.5 Supervision of excavation works and demolition within the TPZ of protected Trees,



- vi) 6.6 Plantings within Tree Protection Zones,
- vii) 6.7 Restricted activities,
- viii) 6.8 Site Materials Storage, and
- ix) 6.9 Hold Points.

The Arborist shall submit certification to the Certifying Authority that the works and activities described in the above sections have been correctly installed and adhered to during the construction period.

The tree protection measures specified in this clause must:

- x) be in place before work commences on the site, and
- xi) be maintained in good condition during the construction period, and
- xii) remain in place for the duration of the construction works.

The Certifying Authority or a Project Arborist AQF Level 5 must ensure that:

- xiii) the activities listed in section 4.2 of AS4970-2009 Protection of Trees on Development Sites, do not occur within the tree protection zone of any tree, and
- xiv) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree, or any other tree to be retained on the site during the construction, is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.

A separate permit or development consent may be required if the branches or roots of a protected tree on the site or on an adjoining site are required to be pruned or removed.

Reason: To ensure tree protection is provided and maintained.

### 31. **Tree and Vegetation Protection - General**

a) Existing trees and vegetation shall be retained and protected as identified in the Arboricultural Impact Assessment prepared by Axiom Arbor Tree Services, including:

- i) all trees and vegetation within the site not approved for removal, excluding exempt vegetation under the relevant planning instruments of legislation,
- ii) all trees and vegetation located on adjoining properties, and in particular Tree 1, 2, 3 and 4 located on the neighbouring site of 43 Upper Clifford Avenue,
- iii) all trees and vegetation within the road reserve.

b) Tree protection shall be generally undertaken as follows:

- i) all tree protection shall be in accordance with AS4970-2009 Protection of Trees on Development Sites, and the recommendations of the Arboricultural Impact Assessment,
- ii) removal of existing tree roots greater than 25mm is not permitted without consultation with a AQF minimum Level 5 Arborist,
- iii) existing ground levels shall remain under the tree protection zone of trees to be retained, unless authorised by AQF minimum Level 5 Arborist,
- iv) any tree roots exposed during excavation with a diameter greater than 25mm within the tree protection zone must be assessed by an AQF minimum Level 5 Arborist. Details including photographic evidence of works undertaken shall be submitted to the Certifying Authority,
- v) to minimise the impact on trees and vegetation to be retained and protected, no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- vi) no tree roots greater than 25mm diameter are to be cut from protected trees unless authorised by a AQF minimum Level 5 Project Arborist on site,
- vii) all structures are to bridge tree roots greater than 25mm diameter unless directed by a AQF minimum Level 5 Arborist on site,
- viii) excavation for stormwater lines and all other utility services is not permitted within the tree

protection zone, without consultation with a AQF minimum Level 5 Arborist, including advice on root protection measures,

ix) should either or all of vi), vii) and viii) occur during site establishment and construction works, a AQF minimum Level 5 Arborist shall provide recommendations for tree protection measures.

Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Certifying Authority,

x) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works, is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS 4970-2009,

xi) tree pruning to enable construction shall not exceed 10% of any tree canopy, and shall be in accordance with AS4373-2009 Pruning of Amenity Trees.

c) All protected trees are to be retained for the life of the development, or for their safe natural life. Trees that die or are removed by approval must be replaced with a locally native canopy tree

Reason: To retain and protect significant planting on development and adjoining sites.

### 32. **Implementation of Traffic Management Plan**

All works including Demolition, Excavation and Construction activities are to be undertaken in accordance with the approved Traffic Management Plan (TMP).

All controls in the TMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate RMS accreditation.

Should the implementation or effectiveness of the TMP be impacted by surrounding major development not encompassed in the approved TMP, the TMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved TMP is to be kept onsite at all times and made available to Council on request.

Reason: To ensure compliance of the developer/builder in adhering to the Traffic Management procedures agreed and are held liable to the conditions of consent.

### 33. **Waste/Recycling Requirements (Waste Plan Submitted)**

During demolition and/or construction the proposal/works shall be generally consistent with the approved Waste Management Plan.

Reason: To ensure waste is minimised and adequate and appropriate waste and recycling facilities are provided.

### 34. **Waste/Recycling Requirements (Materials)**

During demolition and/or construction the following materials are to be separated for recycling – timber – bricks – tiles – plasterboard – metal – concrete, and evidence of disposal for recycling is to be retained on site.

Reason: To ensure waste is minimised and recovered for recycling where possible.

## CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

### 35. **Landscape Works Completion**

Landscape works are to be implemented in accordance with the Landscape Plans numbered Sheet 1 of 2 and Sheet 2 of 2, prepared by Paul Scrivener Landscape, inclusive of the following requirements:

- i) the proposed Tuckeroo (*Cupaniopsis anacardoides*) tree planting within the Unit 1 garden level (RL 52.15) shall be deleted and replaced with a non invasive seeding native tree suited to the site location, listed either in Manly DCP Schedule 4, Part B - Native Tree Selection, or in Council's Tree Guide, such as Blueberry Ash (*Elaeocarpus reticulatus*) or Snow-in-Summer (*Melaleuca linariifolia*), or as selected by the Landscape Architect, to attain a height of approximately 6 metres at maturity, equal to the roof parapet height of No. 43 Upper Clifford Avenue (RL 58.70), (\*)
- ii) the proposed Cheese Tree (*Glochion ferdinandi*) tree planting within the Unit 1 garden level (RL 52.15) shall be deleted and replaced with a native tree suited to the site location, as listed either in Manly DCP Schedule 4, Part B - Native Tree Selection, or in Council's Tree Guide, such as Blueberry Ash (*Elaeocarpus reticulatus*) or Snow-in-Summer (*Melaleuca linariifolia*), or as selected by the Landscape Architect, to attain a height of approximately 6 metres at maturity, equal to the roof parapet height of No. 43 Upper Clifford Avenue (RL 58.70), (\*)
- iii) the proposed Lillypilly (*Acmena smithii*) tree planting within the Unit 2 patio garden level (RL 50.79) shall be deleted and replaced with a native tree suited to the site location, as listed either in Manly DCP Schedule 4, Part B - Native Tree Selection, or in Council's Tree Guide, such as Magenta Lillypilly (*Syzygium paniculatum*), Blueberry Ash (*Elaeocarpus reticulatus*) or Riberry (*Syzygium leuhmannii*), or as selected by the Landscape Architect, to attain a height of approximately 8 metres at maturity, equal to the roof parapet height of No. 43 Upper Clifford Avenue (RL 58.70), (\*)
- iv) all tree planting within the site shall be planted at 75 litre container size, located within natural ground areas of substantial area (minimum 12m<sup>2</sup>) for each tree, located away from common boundaries, planted at least 4 metres from buildings for medium sized trees and at least 3 metres from buildings for small sized trees, and all at least 4 metres from all other trees.

(\*) The above conditions satisfy Manly DCP clause 3.3.1 Landscaping Design, item b) iii) trees should be positioned in locations that minimise significant impacts on neighbours in terms of blocking winter sunlight to either living rooms, private open space or solar collectors; or where the proposed location of the tree may be otherwise positioned to minimise any significant loss of views.

Prior to the issue of an Occupation Certificate, a landscape report prepared by a landscape architect or landscape designer shall be submitted to the Certifying Authority, certifying that the landscape works have been completed in accordance with the Landscape Plan and any conditions of consent.

Reason: To ensure that the landscape treatments are installed to provide landscape amenity and soften the built form.

### 36. **Condition of Retained Vegetation**

Prior to the issue of an Occupation Certificate, a report prepared by an Arborist with AQF minimum Level 5 qualifications in arboriculture/horticulture shall be submitted to the Certifying Authority, assessing the health and impact on all existing trees required to be retained, identified as trees numbered 1, 2, 3, and 4 located within the adjoining property at No. 43, as a result of the development works, including the following information:

- i) compliance to any Arborist recommendations for tree protection and excavation works,
- ii) extent of damage sustained by vegetation as a result of the construction works,
- iii) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: To retain and protect significant planting on development sites.

### 37. **Post-Construction Dilapidation Report**

Post-Construction Dilapidation Reports for the properties listed in the condition titled 'Pre-

Construction Dilapidation Report', including photos of any damage evident at the time of inspection, must be submitted after the completion of works. The reports must:

- Compare the post-construction report with the pre-construction report;
- Clearly identify any recent damage and whether or not it is likely to be the result of the development works; and
- Should any damage have occurred, suggested remediation methods.

Copies of the reports must be given to the property owners referred to in the Pre-Construction Dilapidation Report Condition. Copies must also be lodged with Council.

Details demonstrating compliance with this condition are to be submitted to the Principal Certifying Authority prior to the issuing of any Occupation Certificate.

Reason: To maintain proper records in relation to the proposed development.

**38. Positive Covenant and Restriction as to User for On-site Stormwater Disposal Structures**

The Applicant shall lodge the Legal Documents Authorisation Application with the original completed request forms (NSW Land Registry standard forms 13PC and/or 13RPA) to Council and a copy of the Works-as-Executed plan (details overdrawn on a copy of the approved drainage plan), hydraulic engineers' certification.

The Applicant shall create on the Title a restriction on the use of land and a positive covenant in respect to the ongoing maintenance and restriction of the on-site stormwater disposal structures within this development consent. The terms of the positive covenant and restriction are to be prepared to Council's standard requirements at the applicant's expense and endorsed by Northern Beaches Council's delegate prior to lodgement with the NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction for on-site storm water detention as to user is to be submitted.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of final Occupation Certificate.

Reason: To ensure the on-site stormwater disposal system is maintained to an appropriate operational standard.

**39. Removal of Redundant Driveways**

All redundant driveways shall be removed and reinstated to Council standard kerb and gutter. Suitably prepared plans shall be submitted to for an approval under and approved by Council. All costs associated with the works shall be borne by the applicant.

A plan checking fee (amount to be advised) and lodgement of a performance bond may be required from the applicant prior to the release of the approval.

Reason: To maximise on street car parking by removing driveways that are no longer needed in accordance with Council policy.

**40. Reconstructing Damaged Road Reserve**

Any damaged Road reserve shall be reconstructed to Council standard. Suitably prepared plans shall be submitted to for an approval under and approved by Council. All costs associated with the works shall be borne by the applicant. A plan checking fee (amount to be advised) and

lodgement of a performance bond may be required from the applicant prior to the release of the approval.

Reason: To maintain road reserve to the standards.

41. **Waste/Recycling Compliance Documentation**

Evidence of disposal for recycling from the construction/demolition works shall be submitted to the Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure waste is minimised and recycled.

## **ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES**

42. **Landscape Maintenance**

Any existing landscaping including trees required to be retained together with any additional landscaping required by this consent is to be maintained for the life of the development.

A 12 month establishment period shall apply for all new landscaping. If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components. All planting must be maintained for the life of the development, or for their safe useful life expectancy. Planting that may die or is approved for removal must be replaced.

Reason: To maintain local environmental amenity and ensure landscaping continues to soften the built form.

43. **Building B Void**

The void proposed in Building B (fronting Lauderdale Avenue), above the car park and below the entry level of Unit 3, is to remain a void and is not to be converted to habitable space without prior consent.

Reason: To ensure consistency with approved plans.

44. **Resident Parking Permits**

Any residents and/or tenants of the subject site are not eligible for resident parking permits. This condition is to be provided on the property Title.

Reason: To ensure the tenants are aware that they are not entitled to a permit regardless if they are within a Resident Parking Scheme (RPS).

45. **Fencing Height / Vegetation**

All fencing and/or vegetation along the frontage road(s) shall not impede pedestrian or driver visibility. This requires that vegetation does not exceed one (1) metre in height within the required splay. Appropriate plants shall be selected within the 2.0 x 2.5m splay to ensure this condition is met.

Reason: To ensure maximum vehicular and pedestrian visibility.

46. **Future Landscaping**

Any future replacement planting within the front setback area fronting Upper Clifford Avenue, is to be limited to species that are anticipated to grow to a maximum of 5m in height at maturity.

Reason: To allow reasonable sharing of views.

47. **Accessibility of Parking Facilities**

The parking facilities including visitor parking are to be accessible and identifiable at all times. Necessary signs and markings have to be maintained throughout the lifetime of the development.

Reason: To ensure residents and visitors are not forced to park on public streets when parking has been provided within the development.

48. **Parking Enclosure**

No parking spaces, or access thereto, shall be constrained or enclosed by any form of structure such as fencing, cages, walls, storage space, or the like, unless consented to under this application, or without prior consent from Council.

Reason: To ensure accessibility is maintained.

## Right to Review by the Council

You may request Council to review this determination of the application under Division 8.2 of the Environmental Planning & Assessment Act 1979. Any Division 8.2 Review of Determination application should be submitted to Council within 3 months of this determination, to enable the assessment and determination of the application within the 6 month timeframe.

*NOTE: A fee will apply for any request to review the determination.*

## Right of Appeal

If you are dissatisfied with this decision Division 8.3 of the Environmental Planning & Assessment Act 1979 may give you the right to appeal to the Land and Environment Court within 6 months after the date on which you receive this notice.

**Signed**                      On behalf of the Consent Authority



Name                      Rodney Piggott, Manager Development Assessments

Date                      09/07/2020



## GENERAL ADVICE

### Advisory Notes (General)

Where are you in the development process?



**Note:** The advice within this document is provided in good faith as a guide to assist applicants understand the broad process and will not detail every step or every requirement for demolition, building construction works or subdivision required or business operating requirements under New South Wales or Commonwealth Legislation. If you require clarification or have any questions, please contact your Certifier or Council's Planning and Development Enquiries Team.

The attached Notice of Determination includes conditions of consent which must be complied with.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

## **Building Certification**

The Environmental Planning and Assessment Act 1979 provides that:

- Building work cannot occur unless a construction certificate has been issued;
- Occupation of building works cannot occur unless an occupation certificate has been issued
- Subdivision cannot be registered until a subdivision certificate has been issued
- Mandatory Inspection for building work must be completed

Please refer to process chart for more detail.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

## **Certification Services**

Construction Certificates / Occupation Certificates / Subdivision Certificates / Strata Certificates, can be issued by Council or an accredited private certifier (Note Council must be the Principal Certifying Authority (PCA) for subdivisions).

Council is well placed to provide Certification Services. Council can issue Construction Certificates and act as your Principle Certifying Authority at competitive rates. Please visit our web site [www.northernbeaches.nsw.gov.au](http://www.northernbeaches.nsw.gov.au) or speak to our Customer Service Officers if you have any further questions about our Certification Services or if you wish to use Council as your certifier.

## **Charges Associated with the Development Consent**

All bonds, fees, Development Contributions or the Long Service Levy detailed within the Notice of Determination are required to be paid prior to the issuing of any Construction Certificate.

## **Bonds are released after:**

1. 'Final Occupation Certificate' has been received by Council; and
2. Final inspection by a Council Officer where:
  - the development is complete
  - damage has not been caused to council assets during the works
  - conditions of development consent have been met.

The bond will be released to the person or business who paid the bond to Council (The name that appears on the original receipt)

## **Acceptable Form of Security Bonds**

Council will accept bank guarantee (in a form acceptable to Council) in lieu of cash and is required prior to the issue of a construction certificate.

## **Modifications to the consent**

If you seek to make any changes to the development (which may include internal / external configuration of the building, variation to facades, site layout or any changes to the proposed operation or use), the modifications may require the submission and approval of an application to modify the development consent prior to the issuing of a Construction Certificate and prior to the works being

carried out. The proposed changes should be discussed with the PCA.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

### **Other Matters not detailed within the Notice of Determination**

The Notice of Determination does not stipulate every requirement that must be completed to satisfy New South Wales and Commonwealth legislation.

You should check, as may be relevant, with other authorities including but not limited to:

- Workcover NSW for work safety and asbestos requirements
- Sydney Water – Quick Check Agent for the provision of water and sewer services
- Energy & Gas suppliers for utility services
- Department of Fair Trading for advice about builders and licensing
- Building Professionals Board for advice about private certifiers
- NSW Roads and Maritime Services for works on state roads only
- Human Rights and Equal Opportunity Commission for access issues
- NSW Land and Property Information for Land Title matters
- Australia Post for the positioning and dimensions of mail boxes in new commercial and residential developments;

### **Dial Before You Dig**

Underground assets may exist in the area that is subject to your application. In the interests of health and safety and in order to protect damage to third party assets please contact Dial before you dig at [www.1100.com.au](http://www.1100.com.au) or telephone on 1100 before excavating or erecting structures (This is the law in NSW). If alterations are required to the configuration, size, form or design of the development upon contacting the Dial before You Dig service, an amendment to the development consent (or a new development application) may be necessary. Individuals owe asset owners a duty of care that must be observed when working in the vicinity of plant or assets. It is the individual's responsibility to anticipate and request the nominal location of plant or assets on the relevant property via contacting the Dial before you dig service in advance of any construction or planning activities.

### **Telecommunications Act 1997 (Commonwealth)**

Telstra (and its authorised contractors) are the only companies that are permitted to conduct works on Telstra's network and assets. Any person interfering with a facility or installation owned by Telstra is committing an offence under the Criminal Code Act 1995 (Cth) and is liable for prosecution. Furthermore, damage to Telstra's infrastructure may result in interruption to the provision of essential services and significant costs. If you are aware of any works or proposed works which may affect or impact on Telstra's assets in any way, you are required to contact :Telstra's Network Integrity Team on Phone Number 1800810443.

(1) if the development is likely to disturb or impact upon telecommunications infrastructure, written confirmation from the service provider that they have agreed to the proposed works must be submitted

to the Principal Certifying Authority prior to the issue of a Construction Certificate or any works commencing, whichever occurs first; and

(2) The arrangements and costs associated with any adjustment to telecommunications infrastructure shall be borne in full by the applicant/developer.

### **Model**

If you submitted a model with the application it must be collected from the Council offices within fourteen (14) days of the date of this determination. Models not collected will be disposed of by Council.

### **Trade waste agreement**

A Trade Waste Agreement must be obtained from Sydney Water prior to the discharge of trade wastewater to the sewer system. Trade wastewater is defined as 'discharge water containing any substance produced through industrial or commercial activities or operation on the premises'.

### **Waste collection**

Liquid and solid wastes generated on the site must be collected, transported and disposed of in accordance with the requirements of the Protection of the Environment Operations Act 1997. Records must be kept of all waste disposal from the site.

Material to be removed from the site must be source separated on site to maximise recycling, and the material disposed of to an appropriate disposal and recycling facility in accordance with the approved Waste Management Plan.

### **Aboriginal Heritage**

If in undertaking excavation or works and any Aboriginal site or object is, or is thought to have been found, all works are to cease immediately and the applicant is to contact the Aboriginal Heritage Officer for Warringah Council, and the Cultural Heritage Division of the Department of Environment and Climate Change (DECC).

### **On-Site Sewage Management System**

This approval does not authorise the installation or operation of a new or modification of an existing on-site wastewater management system. An On-Site Sewage Management System must not be installed or operated unless an 'Approval to Install an On Site Sewage Management System' is obtained from Warringah Council.

### **Cost of Works**

The applicant shall bear the cost of all works associated with the development that occurs on Council's property.

### **Relocation of stormwater drainage**

Council is not responsible for the cost of relocating Council's stormwater drainage pipes through the subject property.

### **Tree preservation**

Where tree work has not been approved by this Development Consent the developer is notified that a general Tree Preservation Order applies to all trees in the Northern Beaches Local Government Area. This order prohibits the ringbarking, cutting down, topping, lopping, pruning, transplanting, injuring, or wilful destruction of such trees except without the prior written consent of Council.

### **Storage bins on footpath and roadway**

Approval is required from Council prior to the placement of any storage bin on Council's footpath and/or roadway.

### **Protection of Public Places**

- (1) If the work involved in the erection or demolition of a building:
- (a) is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient; or
  - (b) building involves the enclosure of a public place,

a hoarding and site fencing must be erected between the work site and the public place.

- (2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.
- (3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.
- (4) Any such hoarding, fence or awning is to be removed when the work has been completed.
- (5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained.

### **Road Opening Permit**

The developer/applicant is to obtain a "Road Opening Permit" from Council and pay all appropriate charges prior to commencement of any work on Council property. The developer/applicant shall be responsible for all public utilities and services in the area of the work, and as such shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.

### **Special Permits**

Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development are to occur entirely on the property. The applicant, owner or builder must apply for specific permits available from Council. A minimum of forty-eight (48) hours notice is required for all permits except work zones, which may require additional assessment time.

- Permit for on-street mobile plant

Restrictions apply to the hours of operation and the area of operation for on street mobile plant equipment (for example cranes, concrete pumps, cherry pickers). Separate permits are required for each occasion and each piece of equipment. It is the responsibility of the applicant, owner and builder to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

- Hoarding Permit

Permits are required to erect Class A, Class B and Class C hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

- Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given.



- Kerbside restrictions, work zones

Existing kerbside restrictions apply. An application must be made to Council for the alteration of existing kerbside restrictions or the provision of a construction zone.

Other permits may include out of construction hours permits.

### **Licensing requirements for removal of bonded asbestos**

Anyone who removes, repairs or disturbs bonded asbestos must hold a bonded or a friable asbestos licence, or a demolition licence in accordance with Workcover requirements and the Occupational Health and Safety Act 2000.

### **Pool Access**

Access to pools are required to be restricted by a child resistant barrier in accordance with the regulations prescribed in all relevant Acts, Regulations and Australian Standards including:

- (i) Swimming Pools Act 1992;
- (ii) Swimming Pools Amendment Act 2012;
- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools

It is your responsibility as a land owner to ensure any fencing is maintained.

### **Dewatering**

Where dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Department of Water and Energy. The bore license must be obtained prior to commencement of dewatering works.

### **Requirement to Notify about New Contamination Evidence**

Any new information revealed during works that has the potential to alter previous conclusions about site contamination or hazardous materials shall be immediately notified to Council and the Principal Certifying Authority.

### **Flood Evacuation Plan**

If your site is on flood prone land you may wish to consider the preparation of a flood evacuation plan.

Generally a Flood Evacuation Plan would be prepared by suitably qualified Engineer (e.g. Hydraulic) with a number of years experience in flood management and who is eligible for Membership to the Australian Institute of Engineers.

Some matters that you may wish to consider (but not limited to) include:

- (i) a route of evacuation to higher ground and / or point of shelter
- (ii) depth of water for a Possible Maximum Flood event surrounding the building
- (iii) details of 'last chance' evacuation water levels / times for evacuation prior to floodwaters surrounding the building
- (iv) provide details of flood warning systems and protocols
- (v) details of how this information will be distributed and people educated for users of the site.

You may seek to discuss this with the State Emergency Service of NSW.

### **Utility Service Requirements**

Where development requires the installation of, or the relocation of utility services being (but not limited to) gas, water, electricity and telecommunications, the installation of, or the relocation of utility services shall be conducted in accordance with the requirements of the relevant service provider / authority (unless stipulated by any other condition of the consent or will result in damage to threatened or endangered species defined under the Threatened Species Conservation Act 1995).

### **Plant & Equipment Kept Within Site**

All plant and equipment used in the erection of the building, including concrete pumps, wagons, lifts, mobile cranes, etc, shall be situated within the boundaries of the site and so placed that all concrete slurry, water, debris and the like shall be discharged onto the building site, and is to be contained within the site boundaries. This does not prevent any requirement to comply with the Protection of the Environment Operations Act.

### **Lighting**

Illumination of the site is to be arranged in accordance with the requirements of Australian Standard 4282 - 1997 Control of the obtrusive effects of outdoor lighting so as not to impact upon the amenity of the occupants of adjoining and nearby residential premises.

### **Silt and Sediment Control**

During any onsite demolition, excavation and construction works, the site should be maintained in accordance with "The Blue Book - Managing Urban Stormwater (MUS): Soils and Construction".

In managing the site provision shall be made throughout the period of works to prevent transmission of soil to the public road, drainage system, any riparian lands or off site in any manner. Upon completion of the development, any measures to prevent the transition of soil off site to remain in place until the site is stabilised.

A failure to prevent the transmission of silt and sediment and / or causing, water pollution, air pollution, noise pollution or land pollution may result in a breach of the Protection of the Environment Operations Act and orders, penalties and prosecutions may occur.

**Maintenance of Sediment and Erosion Control** Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain.

Reason: To avoid erosion and sedimentation impacts that will result in an adverse change in watercourse or riparian land condition

### **Installation and Maintenance of Sediment and Erosion Control**

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: soils and construction (2004).

Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site

### **Dividing Fences Act 1991**

The construction and maintenance of side boundary fences is to be agreed upon by all adjoining property owners of the fence. Works are to be in accordance with the Dividing Fences Act 1991.

## **OTHER MATTERS**



**Child Care Centres**

A license to operate a child care centre must be obtained from the NSW Department of Community Services prior to the commencement of the use of the child care centre.

**Disability Access**

This decision does not ensure compliance with the Commonwealth Disability Discrimination Act 1992. Applicants are strongly advised to investigate their requirements under that Act

**Food Premises**

Food premises are required to comply with the requirements of the Food Act 2003, the Food Standards Code and Australian Standards.

The proprietor of a food business must notify the NSW Food Authority of the details of the business. Notification may be done either online at [www.foodnotify.nsw.gov.au](http://www.foodnotify.nsw.gov.au) or by lodging a completed NSW Food Authority notification form to the NSW Food Authority or Council.

**Wheel washing facility**

All trucks leaving the site, having had access to unpaved or contaminated areas, shall depart via a wheel wash facility in order to prevent mud, dust or debris from being deposited on Council's roads. The wheel wash facility shall be constructed prior to any truck movements occurring. Water from the wheel wash facility must not cause pollution. Any direction of Council with regard to cleaning trucks or the clean up of road pavements adjoining the site shall be complied with immediately.

**Monitoring State of Roadways**

The applicant shall monitor the state of roadways leading to and from the site and shall take all necessary steps to clean up any adversely impacted road pavements as directed by Council.

**Storage of Dangerous Goods**

Prior to the storage of any "dangerous goods" on the premises, a copy of a license obtained from the Chemical Safety Branch of Work Cover Authority must be submitted to Council.

**Storage of Flammable and Combustible Liquids**

Flammable and combustible liquids must be stored in accordance with Australian Standard 1940 The Storage and Handling of Flammable and Combustible Liquids.

**Noise and Vibration**

The premises, including operation of vehicles, shall be conducted so as to avoid offensive noise or vibration and cause no interference to adjoining or nearby occupants. Special precautions must be taken to avoid nuisance in neighbouring residential areas, particularly from machinery, vehicles, warning sirens, public address systems and the like.

**Hairdressing/Beauty Treatment/ Skin penetration Requirements**

The premises must comply with the following requirements before the commencement of business:

- i) A hand wash basin with warm water delivered through a common spout must be provided in the treatment area. The hand wash basin must be provided with liquid soap and paper towel.
- ii) The wall behind the hand wash basin from the floor to a height of 450mm above the top of the washbasin and from the centre of the washbasin to a distance of 140mm beyond each side of the wash basin, must be finished with a material that is durable, smooth, impervious to moisture and capable of being easily cleaned (eg tiles).
- iii) The premises must be provided with washing, drainage, ventilation and lighting that are adequate for the carrying out of hairdressing/beauty treatment/skin penetration procedures.
- iv) The floor coverings must be smooth and impervious.

- v) All furniture, shelves and fittings must be constructed of, or covered with a material that is smooth, impervious to moisture and capable of being easily cleaned.
- vi) Adequate lockers must be provided for the storage of employees clothing and personal effects.
- vii) The premises must be provided with facilities that are adequate for the purpose of storing of hairdressing/beauty treatment/skin penetration appliance and utensils.
- viii) The premises must be provided with a sink sullied with hot and cold water for washing equipment.

### **Food Premises Construction Requirements**

The food premises must comply with the following specific construction requirements:

Solid walls must be provided in all food handling areas (solid includes brick, cement and foam filled preformed panels);

- ix) Walls in food preparation and wash up areas must be finished with a smooth and impervious surface to a height of at least 2 metres.
- x) Hand wash basins must be provided with warm water delivered through a common spout with taps that are hands free operation;
- xi) Coving with a radius of 25mm must be provided between all floor and wall joints in food handling areas;
- xii) The open space between the top of the coolroom and the ceiling must be fully enclosed and kept insect and pest proof;
- xiii) The coolroom must be able to be opened from the inside with out a key and fitted with an alarm that can only be operated from within the coolroom;
- xiv) The doors to the toilet air lock and toilet compartment must be tight fitting and self closing;
- xv) The rear external door must be self closing or be provided with a fly screen that is self closing;
- xvi) Where cooking or extensive heating processes or such other processes as may be specified are carried out in food preparation areas, an approved mechanical ventilation system shall be installed and operated in accordance with AS 1668 part 1 & 2.

### **Legionella Control**

Cooling towers, warm water systems, water cooling systems must be registered with the Council. Details of registration are to be provided to the Council prior to operation.

### **Pool/Spa Safety**

Owners of properties with swimming pools and spa's must meet safety compliance and registration requirements. Provisions also apply when renting/selling properties. Details are available from the Division of Local Government.

### **Grease Trap**

Contact Sydney Water to determine what trade waste provisions you are required to provide to your food premises. Should a grease trap be required by Sydney Water, it must be located in an area that is easily accessible for the removal of waste water and must not be installed in any kitchen, food preparation or food stage area. The design and location of the grease trap should also not impede on any commercial right of way or pedestrian access.

### **Bandicoot/Penguin**

Long-nosed Bandicoots & Little Penguins – Best Practices for Residents Residents are encouraged to follow a number of *Best Practices* to assist with the protection and management of the endangered populations of Long-nosed Bandicoots and Little Penguins:

- Long-nosed Bandicoots, Little Penguins and other native animals should never be fed as it may cause them nutritional problems, hardship if supplementary feeding is stopped, and it may increase predation.
- Feral cats or foxes should never be fed or food left out where they can access it, such as rubbish bins without lids or pet food bowls, as these animals present a significant threat to Long-nosed Bandicoots, Little Penguins and other wildlife.
- The use of insecticides, fertilisers, poisons and/or baits should be avoided on the property.

Garden insects will be kept in low numbers if Long-nosed Bandicoots are present.

- When the North Head Long-nosed Bandicoot Recovery Plan is released it should be implemented where relevant.
- Dead Long-nosed Bandicoots or Little Penguins should be reported by phoning Manly Council on 9976 1500 or Department of Environment and Conservation on 9960 6266.
- Please drive carefully as vehicle related injuries and deaths of Long-nosed Bandicoots and Little Penguins have occurred in the area. Care should also be taken at night in the drive way when moving cars as bandicoots will seek shelter beneath vehicles.
- Cat/s and or dog/s that currently live on the property should be kept indoors at night to avoid disturbance/death of native animals. Ideally, when the current cat/s and/or dog/s that live on the property no longer reside on the property it is recommended that they not be replaced by new dogs or cats.
- Report all sightings of feral rabbits, feral or stray cats and/or foxes to N B Council.