





21 December 2022

General Manager Northern Beaches Council PO Box 882 MONA VALE NSW 1660

Dear Sir/Madam

Re: Stormwater Management Plan – 152-154 Sydney Road, Fairlight

With reference to the Development Application for the above property, please find enclosed a copy of the site Stormwater Management Plan, STORM-1/A and Stormwater Management Details, STORM-2/A, for your perusal.

The plan shows collected flows from the proposed roofed areas, along with the surrounding paved and landscaped areas, being discharged to the Council drainage system within William Street.

Note that it is proposed to provide an combination rainwater/detention storage tank comprising of 7,100 litre on-site detention and 4,400 litre rainwater storage tank beneath the stairs on the northern side of the building for non-potable domestic reuse in accordance with Council & BASIX requirements.

This is to certify that the Stormwater Management Plan layout as shown on STORM-1/A and STORM-2/A by Taylor Consulting Civil & Structural Engineers has been designed in accordance with section 3.1.2, 'Drainage', of the Building Code of Australia Housing Provision, AS/NZS 3500.3.2 – Stormwater Drainage and Northern Beaches Council - Water Management for Development Policy.

Should you require any further information please contact the undersigned.

Yours faithfully

TAYLOR CONSULTING

D M SCHAEFER - Director


B.E. Civil – Hons. M.I.E. Aust. N.E.R.











STORMWATER SYSTEM DESIGN DATA

SITE DATA

SITE AREA =  $360 \text{ m}^2 (100\%)$ 

PROPOSED IMPERVIOUS AREA =  $297 \text{ m}^2$  (88%)

PROPOSED LANDSCAPED AREA =  $63 \text{ m}^2$  (12%) EXISTING IMPERVIOUS AREA =  $308 \text{ m}^2$  (86%) EXISTING LANDSCAPED AREA =  $52 \text{ m}^2$  (14%)

ISSUE DATE : REVISION DECEMBER 2022: REVISED RAINWATER/DETENTION STORAGE ARRANGEMENT

STORMWATER MANAGEMENT PLAN 152-154 SYDNEY ROAD, FAIRLIGHT SCALE @ A1 DRAWN CHECKED 1:100

2 DECEMBER 2022

MDB



STORM-**TAYLOR** CONSULTING CIVIL & STRUCTURAL ENGINEERS

"Seascape" Suite 7 22-26 Fisher Rd Dee Why NSW 2099 T 02 9982 7092 F 02 9982 5898 enquire@taylorconsulting.net.au www.taylorconsulting.net.au

BE Civil (Hons) MIE Aust:

DRAINAGE NOTES

+ DENOTES EXISTING GROUND LEVEL

CONSTRUCTION DETAILS.

20 MPa MASS CONCRETE.

CONSTRUCTION WORKS.

PLUMBING CODE.

AVOID TREE ROOTS

OSD SYSTEM DESIGN DATA

5 YR ARI = 8 l/s

100 YR ARI = 9 l/s

EXISTING SITE FLOWS

DEVELOPED SITE FLOWS

DETENTION SYSTEM DATA

TOTAL SITE AREA = 360m²

100YR TWL = RL 53.81 A.H.D.

ORIFICE DIAM = 40mm

AREA DRAINING TO THE TANK = 244 m<sup>2</sup> (68% TOTAL SITE AREA)

NOTE : DETENTION STORAGE VOLUME HAS BEEN OFFSET BY 24% VIA THE PROVISION

AREA BYPASSING TANK = 116m<sup>2</sup> (32% TOTAL SITE AREA) IMPERVIOUS AREA BYPASSING TANK = 50m<sup>2</sup> (43%) PERVIOUS AREA BYPASSING TANK = 66m<sup>2</sup> (57%)

IMPERVIOUS AREA TO TANK = 244m<sup>2</sup> (100%) PERVIOUS AREA TO TANK = 0m2 (0%)

OF 4400 LITRES OF RAINWATER STORAGE.

MAKE GOOD ALL DISTURBED AREAS.

CONSULTING FOR MORE INFORMATION.

STORM EVENTS AND CLEANED EVERY 6 MONTHS.

FALL STORMWATER PIPES AT 1% MIN. UNLESS OTHERWISE NOTED.

ALL STORMWATER PIPES TO HAVE SOLVENT CEMENT WATERTIGHT JOINTS.

SURFACE GRATES 300 SQ. UNLESS OTHERWISE NOTED.

REMOVE REDUNDANT DRAINAGE PITS AND SEAL PIPES.

APPROVED PRE-CAST PITS MAY BE USED.

SUB-SOIL DRAINAGE TO BE CONNECTED TO THE SITE DRAINAGE SYSTEM AS NECESSARY.

CHECK & LOCATE DEPTH OF EXISTING MAINS & SERVICES PRIOR TO CONSTRUCTION OF STORMWATER SYSTEM AS VARIATIONS IN POSITION OF MAINS COULD AFFECT DRAINAGE

INSPECTIONS MUST BE UNDERTAKEN BY THIS OFFICE (BY PRIOR ARRANGEMENT WITH ENGINEER) DURING CONSTRUCTION TO ENABLE FULL CERTIFICATION UPON COMPLETION OF

ALL CONSTRUCTION OF COUNCIL DRAINAGE WORKS TO COMPLY WITH COUNCIL STANDARD.

. PIT BENCHING TO BE HALF THE OUTGOING PIPE DIAMETER. CONCRETE FOR BENCHING TO BE

ALL PIPES TO BE LAID ON COMPACTED FINE CRUSHED ROCK OR SAND BEDDING 75mm THICK

PIPE ROUTES SHOWN ARE INDICATIVE ONLY AND SHOULD BE AS NECESSARY ACCORDING TO

CONTRACTOR SHALL ENSURE THAT SERVICES TO BUILDINGS NOT AFFECTED BY THE WORKS

MAINTAIN EXISTING SUPPLY TO BUILDINGS WHERE REQUIRED. ONCE WORKS ARE COMPLETE

AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL TEMPORARY SERVICES AND

STORMWATER SYSTEM REQUIRES SIGNIFICANT MAINTENANCE DUE TO POTENTIAL HIGH POLLUTANT LOAD. FILTERS AND POLLUTANT TRAPS SHOULD BE CHECKED AFTER LARGE

PLUMBING AND DRAINAGE WORKS TO COMPLY WITH AS-3500, THE NATIONAL DRAINAGE &

. WHERE POSSIBLE DRAINAGE LINES SHALL BE LAID IN AREAS PREVIOUSLY DISTURBED BY OTHER SITE WORKS AND FOLLOW TOPOGRAPHICAL FEATURES TO REDUCE IMPACT AND

THIS STORMWATER MANAGEMENT PLAN HAS BEEN PREPARED FOR SUBMISSION TO COUNCIL/CERTIFIER AND DOES NOT NECESSARILY CONTAIN ALL APPROPRIATE INFORMATION

TO ENABLE FOR ISSUE TO PLUMBER/BUILDER FOR CONSTRUCTION. CONTACT TAYLOR

ARE NOT DISRUPTED. CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES TO

SITE CONDITIONS, TREE POSITIONS ETC. CONFIRM SIGNIFICANT CHANGES IN PIPES SYSTEM DETAILS WITH SUPERVISING ENGINEER PRIOR TO COMMENCEMENT OF DRAINAGE

& PIPES BACKFILLED WITH COMPACTED SAND TO 300mm ABOVE TOP OF PIPE, ELSE

ATTACHED TO UNDERSIDE OF STRUCTURE AT 600mm c/c AS NECESSARY

