

Our Ref: 80813340 - 18 - 0077 :PL

Contact: Pak Lau

4 July 2018

Artazan Property Group Level 8, 210 George Street **Sydney NSW 2000**

Attention: Cian Fitzgerald

Cardno (NSW/ACT) Pty Ltd ABN 95 001 145 035

Suite 3.01, Level 3 3 Horwood Place Parramatta 2150 Australia

Phone +61 2 9496 7700 Fax +61 2 9439 5170

Dear Cian.

ST AUGUSTINE COLLEGE GOOLD BUILDING EXTENSION - OVERLAND FLOW ASSESSMENT

Cardno (NSW/ACT) has been engaged by Artazan Property Group (APG) to undertake a flood assessment of the existing overland flow path adjacent to the Goold Building, which is located on the eastern corner of St Augustine College. The college is proposing to:

- 1. Demolish the existing building (St Possidus Chalets) between the Goold building and the site boundary; and
- 2. Construct an extension and refurbishment of the Goold Building.

This report has been prepared to detail the result of the hydraulic assessment of the overland flow path, hence provides a guidance on the finished floor level of the proposed extension.

Catchment Analysis

The existing Goold Building is located in close proximity of the existing overland flowpath, which follows the alignment of an existing drainage easement. The existing overland flow path, has a catchment area of 38.6ha, which was delineated from the aerial photographs, 2m contours and the GIS data for the existing stormwater drainage infrastructure. Figure 1 shows the location of the buildings and the extent of the catchment.

A DRAINS model has been set up and the peak flow was calculated by ILSAX hydrological method. The Rainfall IFD data (2016) and the temporal patterns were obtained from the Bureau of Meteorology and Australian Rainfall and Runoff Datahub respectively.

Based on the current land use, the catchment has divided into two catchments. Catchment A has an area of 28.8ha, which is predominantly a residential area with 40% impervious. The time of concentration was assumed to be 20mins based on the travel time along the gutter and through the stormwater pipes. Catchment B has an area of 9.76ha, which represents the dense vegetated area to the north west of the school site. DRAINS modelling result shows the 1% AEP peak flow discharges at the overland flow path is approximately 5.5m³/s.





Figure 1 Extent of catchment



Hydraulic Assessment

Hydraulic modelling software, HEC-RAS, was used to analyse the flood levels and flow velocities along the existing and designed overland flowpath. The existing model is based on the detail survey data and imported to HEC-RAS from 12d design software. The model for the proposed overland flowpath is based on the detailed survey of the site. Cross sections have been created at 2m intervals along the centreline of the overland flowpath. The overland flowpath alignment is shown in Figure 2.

The roughness coefficient Manning's 'n' used in the analysis was 0.015 (paved area) and 0.035(grassed area). The upstream boundary condition for the analysis were assumed to be normal depth.




Figure 2 Overland flowpath alignment



Results

The 1% AEP flow depth along the existing overland flowpath that is adjacent to the Goold Building is between RL 27.76m and RL 28.31m. Table 1 shows the water levels at different location of the overland flowpath.

Table 1 HEC-RAS results

Location	1% AEP Water Level (RLm)	Comments
CH 54.00	28.69	At the metal shed in the neighbouring property. Existing surface level at the school boundary RL 28.25m. Proposed Goold Building Ground Floor RL 29.59m
CH 52.00	28.49	
CH 50.00	28.34	
CH 48.00	28.22	At the corner of the Goold Building
CH 42.66	28.16	Fore court of the Goold Building
CH 40.00	28.10	At the top of the retaining wall adjacent to the cricket nets
CH 38.00	27.95	At the bottom of the retaining wall, within the cricket nets area

A 500mm freeboard to the finished floor level is required from the 1% AEP flood level as per Northern Beach Council design guidelines. The proposed extension of Goold Building will have a finished floor level of RL 29.59m, which is 900mm higher than the 1% AEP flood level.

Conclusion

The proposed development will not cause any adverse impact on the existing flow condition as the demolition of the existing St Possidus Chalets will increase the available flow area, hence reduce the flow depths along the flow path.

The proposed extension of the Goold Building has more than 500mm freeboard from the 1% AEP flood level, which satisfies council's design requirement.

It is anticipated there will be some civil works associated with the proposed development, which may change the surface level along the overland flowpath. A detailed hydraulic analysis on the post development condition may be required for the development application submission.

If you have any query regarding to the above, please do not hesitate to contact the undersigned.

Yours sincerely,

Pak lan

Pak Lau Civil Engineer for Cardno

Direct Line: +61 2 9496 7846 Email: pak.lau@cardno.com.au



Appendix 16 – On-site Detention Checklist

This checklist is to be used to determine the on-site stormwater disposal requirement for developments and must be completed and included with the submission of any development application for these works. Please read this form carefully for its notes, guidelines, definition and relevant policies.

For assistance and support, please contact Council's Development Engineering and Certification team on 1300 434 434.

Part 1 Location of the Property			
House Humber	33	Legal Property De	escription VACCANT LAND
Street	CONSUL	Lot	3
Suburb	BROOKUALE	Section	
Postcode		DP	12815

Part 2 Site Details			
Northern Beaches Stormwater Regions (refer to Map 2 of Northern Beaches Council's Water Management for Development policy)		Total Site Area	SS6. II m ^L (AS PER CAD)
Pre-Development Impervious Area	0%	Post-Development Impervious Area	452.47 m
Is the site of the development located with referred to Council's Local Environmental	Plans?		Yes □ No 💢
If yes, On-site stormwater Detention syste to part 5 of this checklist If no, please proceed to part 3 of this chec		is not required and please proceed	NO. OSD IS REQUIRE

Part 3: Northern Beaches Stormwater Regions

(refer to Map 2 of Northern Beaches Council's Water Management for Development policy)

If the site of the development located within Region 1, please proceed to the part 4.1 of this checklist

If the site of the development located within Region 2, please proceed to the part 4.2 of this checklist

If the site of the development located within Region 3, please proceed to the part 4.3 of this checklist

If the site of the development located within Region 4, please refer to Council's Warriewood Valley Water Management Specification.



Part 4 Determination of OSD Requirements

Part 4.1 Northern Beaches Stormwater Region 1	
Is the additional impervious area of the development more than 50 m² on a cumulative basis since February 1996?	Yes □ No □
If yes, OSD is required and please refer to section 9.3.1 of Council's Water N Policy If no, OSD is not required and please proceed to the part 5 of this checklist	lanagement for Development

Part 4.2 Northern Beaches Stormwater Region 2			
Part 4.2.1 Description of Work			
Residential flat building, commercial, industrial, multiple occupancy development and subdivisions resulting in the creation of three lots or more, will require OSD in all case. Please provide a design in accordance with the section 9.3.2 of Council's Water Management for Development Policy. Any single residential building development, please proceed to part 4.2.2 of this checklist.			
Part 4.2.2 Exemption			
Is the site area less th	an 450m²?	Yes □ No 🔯	
Does the site of the development drain directly to the ocean without the need to pass through a drainage control structure such as pipe, bridge, culvert, kerb and gutter or natural drainage system? Yes □ No ▼			
Is it an alternation and addition development to the existing dwellings? Yes □ No ☒			
If yes to any of the above questions, OSD is not required. If no to all the above questions, proceed to part 4.2.3			
Part 4.2.3 Determination of OSD Requirements			
a) Site area m² x 0.40 (40%) =		Yes ⊠ No □ .3.2 of Council's Water	



Part 5 Disposal of Stormwater	
Does the site fall naturally towards the street?	Yes □ No 🛭
If yes, provide a design in accordance with section 5. Policy.	1 of Council's Water Management for Development
If no, provide a design in accordance with section 5.5 Policy.	of Council's Water Management for Development

Definitions	
Designed to help you fill out this application	Site area: This refers to the area of the land bounded by its existing or proposed boundaries. Impervious area: This refers to driveways, parking spaces, pathways, paved areas, hardstand areas, roofed areas, garages and outbuildings. Pre Development Impervious area: This refers all impervious areas of the site before the development. Post Development Impervious areas: This refers all the impervious areas within the site after the development is completed.



5 / 45-55 Epsom Road Rosebery NSW 2018

02 8662 9300

info@core.engineering

core.engineering


ABN 34 620 484 602

ELECTRICAL ● FIRE ● HYDRAULIC ● MECHANICAL ● STRUCTURAL● CIVIL ● FACADES

PROJECT ADDRESS: PROPOSED CARPARK A7. 33 CONSUL ROAD, BROOKVALE

DRAWING INDEX & COVER SHEET: CIVIL

PROJECT No.	DWG No.	DWG TITLES	REVISION
2290	C000	COVER SHEET & DRAWING INDEX	02
	C001	GENERAL NOTES	02
	C002	DIAL B4 YOU DIG INVESTIGATION	02
	C003	WASTE MANAGEMENT PLAN	02
	C100	SEDIMENTATION & EROSION CONTROL PLAN	02
	C101	AREA ANALYSIS & SEC DETAILS	02
	C102	STANDARD DETAILS LAYBACK & CARPARK	02
	C200	CONCEPT STORMWATER MANAGEMENT PLAN	02
	C201	OSD & SILT ARRESTOR & MISC DETAILS	02
	C202	MISC DETAILS	02
	C300	LANDSCAPE PLAN	02
	C301	PROPOSED PLANTS	02



SATE MAP (SOURCE: GOOGLE MAP)



SITE LAYOUT (SOURCE: SIX MAPS)

ISSUE FOR DA

ISSUE	DATE	AMENDMENT	CLIENT / BUILDER / ARCHITECT
00	29.09.2020	ISSUE FOR DISCUSSION	
01	02.10.2020	ISSUE FOR DEVELOPMENT APPLICATION	
02	09.10.2020	ISSUE FOR DEVELOPMENT APPLICATION	





33 CONSUL ROAD, BROOKVALE

	NORTH:
Road 118	
eering	© Copyright.
IL ● FACADES	This document and Desany way without prior codrawing. The contractor shall be read in conjunctions.
IL • FACADES	checked by any anti-vir

RTH:	SCALE:	VERIFIED:	DR
	NTS	AC	
		DESIGNED:	
Copyright.	remains the convisit of Core Consulting Engineers Dt. Ltd and connet be correduced in	HR	PR
way without prior conse	remains the copyright of Core Consulting Engineers Pty Ltd and cannot be reproduced in nt. The contractor shall verify all dimension and levels on site as this is not a workshop I refer any discrepancies to the engineer before proceeding with the work. This drawing	DRAWN :	
Il be read in conjunction	with other contract documents, drawings and project specifications. This file has been ogram with the latest virus update. However as new viruses are discovered everyday we	RQ	

	VERIFIED :	DRAWING TITLE :
	AC	COVER SHEET & DRAWING INDEX
	DESIGNED :	
_ n	HR	PROJECT:
•	DD 41401	

12/09/2020 N.T.S PROPOSED CARPARK A7. DRAWING No: 33 CONSUL ROAD, BROOKVALE C000

EXISTING UNDERGROUND SERVICES NOTES

THE LOCATIONS OF UNDERGROUND SERVICES SHOWN IN THIS SET OF DRAWINGS HAVE BEEN PLOTTED FROM SURVEY INFORMATION AND SERVICE AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE.CARDNO CAN NOT GUARANTEE THAT THE SERVICES INFORMATION SHOWN ON THESE DRAWINGS ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER.

CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ONSITE INCLUDING HAND EXCAVATION WHERE NECESSARY. CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT OF EXCAVATION WORKS. CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH, PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES.

COMMUNICATIONS - DUTY OF CARE NOTE

COMMUNICATIONS AND DATA PROVIDER PLANS SHOW ONLY THE PRESENCE OF CABLES AND PLANT. THEY ONLY SHOW THEIR POSITION RELATIVE TO ROAD BOUNDARIES, PROPERTY FENCES ETC. AT THE TIME OF INSTALLATION AND EACH PROVIDER DOES NOT WARRANT OR HOLD OUT THAT SUCH PLANS ARE ACCURATE THEREAFTER DUE TO CHANGES THAT MAY OCCUR OVER TIME. DO NOT ASSUME DEPTH OR ALIGNMENT OF CABLES OR PLANT AS THESE VARY SIGNIFICANTLY. THE CONTRACTOR HAS A DUTY OF CARE WHEN EXCAVATING NEAR COMMUNICATIONS AND DATA CABLES AND PLANT.

BEFORE USING MACHINE EXCAVATORS COMMUNICATIONS PLANT MUST FIRST BE PHYSICALLY EXPOSED BY SOFT DIG POTHOLING TO IDENTIFY IT'S LOCATION, PROVIDERS WILL SEEK COMPENSATION FOR DAMAGES CAUSED TO IT'S PROPERTY AND LOSSES CAUSED TO THE PROVIDERS AND IT'S CUSTOMERS.

TELSTRA - DUTY OF CARE NOTE

TELSTRA'S PLANS SHOW ONLY THE PRESENCE OF CABLES AND PLANT. THEY ONLY SHOW THEIR POSITION RELATIVE TO ROAD BOUNDARIES, PROPERTY FENCES ETC. AT THE TIME OF INSTALLATION AND TELSTRA DOES NOT WARRANT OR HOLD OUT THAT SUCH PLANS ARE ACCURATE THEREAFTER DUE TO CHANGES THAT MAY OCCUR OVER TIME. DO NOT ASSUME DEPTH OR ALIGNMENT OF CABLES OR PLANT AS THESE VARY SIGNIFICANTLY. THE CONTRACTOR HAS A DUTY OF CARE WHEN EXCAVATING NEAR TELSTRA CABLES AND PLANT. BEFORE USING MACHINE EXCAVATORS TELSTRA PLANT MUST FIRST BE PHYSICALLY EXPOSED BY SOFT DIG POTHOLING TO IDENTIFY IT'S LOCATION TELSTRA WILL SEEK COMPENSATION FOR DAMAGES CAUSED TO IT'S PROPERTY AND LOSSES CAUSED TO TELSTRA AND IT'S CUSTOMERS.

BULK EARTHWORKS NOTES

- STRIP ALL TOPSOIL/ORGANIC MATERIAL FROM CONSTRUCTION AREA AND REMOVE FROM SITE OR STOCK PILE AS DIRECTED BY SUPERINTENDENT.
- EXCAVATED MATERIAL TO BE USED AS STRUCTURAL FILL PROVIDED THE PLACEMENT MOISTURE CONTENT OF THE MATERIAL IS +/- 2% OF THE OPTIMUM MOISTURE CONTENT.
- COMPACT FILL AREAS AND SUBGRADE TO NOT LESS THAN:

LOCATION STANDARD DRY DENSITY (AS 1289 E 5.1.1.) UNDER BUILDING SLABS

ON GROUND UNDER ROADS AND

LANDSCAPED AREAS UNLESS NOTED OTHERWISE 98%

- 4. FOR NON COHESIVE MATERIAL, COMPACT TO 75% DENSITY INDEX.
- BEFORE PLACING FILL, PROOF ROLL EXPOSED SUBGRADE WITH AN 8 TONNE (MIN) DEADWEIGHT SMOOTH DRUM VIBRATORY ROLLER TO DETECT THEN REMOVE SOFT SPOTS (AREAS WITH MORE THAN 2mm MOVEMENT UNDER ROLLER).
- FREQUENCY OF COMPACTION TESTING SHALL BE NOT LESS THAN :-(A) 1 TEST PER 200m³ OF FILL PLACED PER 300 LAYER OF FILL.

(B) 3 TESTS PER VISIT

(C) 1 TEST PER 1000m² OF EXPOSED SUBGRADE "LEVEL 1" TESTING SHALL BE TESTING IN ACCORDANCE WITH AS 3798 (1996).

- . FILLING TO BE PLACED IN MAXIMUM 150mm LOOSE LAYERS AND COMPACTED AS SPECIFIED
- 8 NO FILLING SHALL TAKE PLACE TO EXPOSED SUBGRADE UNTIL THE AREA HAS BEEN PROOF ROLLED IN THE PRESENCE OF CARDNO AND APPROVAL GIVEN IN WRITING THAT FILLING CAN PROCEED.

EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- THE CONTRACTOR SHALL BE SOLELY RESPONSIBLE FOR THE CONTROL OF EROSION AND SEDIMENTATION TO THE SATISFACTION OF COUNCIL, NSW OFFICE OF WATER, OFFICE OF ENVIRONMENT AND HERITAGE, THE EROSION AND SEDIMENTATION CONTROLS SHOWN ON THE DRAWINGS SHALL ONLY BE USED AS A GUIDE BY THE CONTRACTOR, AND SHALL REPRESENT THE MINIMUM REQUIREMENT ONLY.
- 2. THE CONTRACTOR SHALL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE LOCATED AS DOCUMENTED OR AS OTHERWISE DIRECTED BY THE SUPERINTENDENT.
- ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH a. LOCAL AUTHORITY REQUIREMENTS
- b. EPA REQUIREMENTS
- c. NSW DEPARTMENT OF HOUSING MANUAL "MANAGING URBAN STORMWATER, SOILS AND CONSTRUCTION", 4th EDITION, MARCH 2004.
- 3. MAINTAIN THE EROSION CONTROL DEVICES TO THE SATISFACTION OF THE
- SUPERINTENDENT AND THE LOCAL AUTHORITY. 4. WHEN STORMWATER PITS ARE CONSTRUCTED, PREVENT SITE RUNOFF ENTERING UNLESS SEDIMENT FENCES ARE ERECTED AROUND PITS.
- 5. CONTRACTOR IS TO ENSURE ALL EROSION & SEDIMENT CONTROL DEVICES ARE MAINTAINED IN GOOD WORKING ORDER AND OPERATE EFFECTIVELY. REPAIRS AND OR MAINTENANCE SHALL BE UNDERTAKEN AS REQUIRED, PARTICULARLY FOLLOWING STORM EVENTS.

LAND DISTURBANCE

- 6. WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE WILL BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE:
- a. INSTALL A SEDIMENT FENCE ALONG THE BOUNDARIES AS SHOWN ON PLAN. REFER DETAIL. b. CONSTRUCT STABILISED CONSTRUCTION ENTRANCE TO LOCATION AS
- DETERMINED BY SUPERINTENDENT/ENGINEER. REFER DETAIL. c. INSTALL SEDIMENT BASIN AS SHOWN ON PLAN (D) INSTALL SEDIMENT
- TRAPS AS SHOWN ON PLAN. d. UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

EROSION CONTROL

- 7. DURING WINDY WEATHER, LARGE, UNPROTECTED AREAS WILL BE KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL.
- 8. FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

SEDIMENT CONTROL

- 9. STOCKPILES WILL NOT BE LOCATED WITHIN 2 METRES OF HAZARD AREAS. INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS. WHERE THEY ARE BETWEEN 2 AND 5 METRES FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSLOPE WATERS, E.G. THROUGH INSTALLATION OF SEDIMENT FENCING.
- 0. ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD OVER THE SURFACE) WILL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.
- 11. WATER WILL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS IT IS RELATIVELY SEDIMENT FREE, I.E. THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AN APPROVED STRUCTURE.
- 12. TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.
- 13. ACCEPTABLE RECEPTORS WILL BE PROVIDED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.
- 14. ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY:

OTHER MATTERS

- a. PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS
- INSTALLED OUTSIDE THE DRIP LINE
- b. ENSURING THAT NOTHING IS NAILED TO THEM c. PROHIBITING PAVING, GRADING, SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING
- (I) ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER
- (II) A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF MORE THAN 300 MILLIMETRES DEPTH
- (III) CARE IS TAKEN NOT TO CUT ROOTS UNNECESSARILY NOR TO COMPACT THE SOIL AROUND THEM.

STORMWATER DRAINAGE NOTES

STORMWATER DESIGN CRITERIA: (A) AVERAGE RECURRENCE INTERVAL:

> 100 YEAR ARI ROOFED AREAS TO SURCHARGE PIT 10 YEAR ARI PAVEMENTS (MINOR SYSTEM) 100 YEAR ARI OVERLAND FLOW PATHS (MAJOR SYSTEM)

(B) RAINFALL INTENSITIES: TIME OF CONCENTRATION: 5 MINUTES

100 YEAR ARI 193mm/hr 10 YEAR ARI 280mm/hr


- 2. PIPES 375 DIA. AND LARGER TO BE REINFORCED CONCRETE CLASS '2' APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS. U.N.O.
- 3. PIPES 300 DIA AND LESS SHALL BE DWV GRADE (CLASS SN8) uPVC WITH SOLVENT WELDED JOINTS.
- 4. ALL PIPES ARE TO BE UNIFORMLY SUPPORTED ALONG THE LENGTH OF THE BARREL BY SUITABLE FILL MATERIAL. REFER TO BEDDING SUPPORT
- 5. PIPES WITH SOCKETS SHALL BE LAID IN BEDDING WHERE SUITABLE RECESSES HAVE BEEN PROVIDED TO ENSURE PIPES DO NOT BEAR ON THEIR SOCKETS.
- 6. ALL STORMWATER DRAINAGE LINES UNDER PROPOSED BUILDING SLABS TO BE uPVC PRESSURE PIPE GRADE 6. ENSURE ALL VERTICALS AND DOWNPIPES ARE uPVC PRESSURE PIPE, GRADE 6 FOR A MIN OF 3.0m IN
- PIPES TO BE INSTALLED TO TYPE HS1 SUPPORT IN ACCORDANCE WITH AS 3725 (2007) IN ALL CASES BACKFILL TRENCH WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS THAN 75).
- 8. REFER TO AS/NRS 3725:2007 TABLE B1 FOR REQUIRED FILL DEPTHS ABOVE PIPE BARREL PRIOR TO USE OF COMPACTION MACHINERY OR TRAVERSING OF PIPES BY GENERAL SITE EQUIPMENT.
- 9. WHERE WORKING METHODS REQUIRE HIGHER CLASS PIPE, THE CONTRACTOR SHALL REFER TO AS 3725 (2007) TO DETERMINE THE APPROPRIATE PIPE CLASS. PROPOSED PIPE CLASS SHALL BE REVIEWED BY CORE PRIOR TO INSTALLATION.
- 10. ALL INTERNAL WORKS WITHIN PROPERTY BOUNDARIES ARE TO COMPLY WITH THE REQUIREMENTS OF AS 3500 3.1 (2003) AND AS/NZS 3500 3.2
- 11. PRECAST PITS MAY BE USED EXTERNAL TO THE BUILDING SUBJECT TO APPROVAL BY CORE.
- 12. ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE PREFABRICATED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA.
- 13. WHERE SUBSOIL DRAINS PASS UNDER FLOOR SLABS AND VEHICULAR PAVEMENTS, UNSLOTTED uPVC SEWER GRADE PIPE IS TO BE USED.
- 14. CARE IS TO BE TAKEN WITH LEVELS OF STORMWATER LINES. GRADES SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL.
- 15. GRATES AND COVERS SHALL CONFORM TO AS 3996.
- 16. ALL BOX CULVERTS SHALL BE STRUCTURALLY DESIGNED BY THE MANUFACTURER AND DELIVERED TO SITE AS FIT FOR PURPOSE.
- 17. AT ALL TIMES DURING CONSTRUCTION OF STORMWATER PITS, ADEQUATE SAFETY PROCEDURES SHALL BE TAKEN TO ENSURE AGAINST THE POSSIBILITY OF PERSONNEL FALLING DOWN PITS.
- 18. ALL EXISTING STORMWATER DRAINAGE LINES AND PITS THAT ARE TO REMAIN ARE TO BE INSPECTED AND CLEANED. DURING THIS PROCESS ANY PART OF THE STORMWATER DRAINAGE SYSTEM THAT WARRANTS REPAIR SHALL BE REPORTED TO THE SUPERINTENDENT/ENGINEER FOR FURTHER DIRECTIONS.

SITEWORKS NOTES


- . ORIGIN OF LEVELS:- REFER SURVEY DRAWING AND SETOUT PLAN.
- 2. CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORK. ANY DISCREPANCIES TO BE REPORTED TO CORE.
- 3. MAKE SMOOTH CONNECTION WITH EXISTING WORKS.
- 4. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL.
- 5. ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH SAND TO 300mm ABOVE PIPE. WHERE PIPE IS UNDER PAVEMENTS BACKFILL REMAINDER OF TRENCH TO UNDERSIDE OF PAVEMENT WITH SAND OR APPROVED GRANULAR MATERIAL COMPACTED IN 150mm LAYERS TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. (OR A DENSITY INDEX OF NOT LESS
- 6. PROVIDE 10mm WIDE EXPANSION JOINTS BETWEEN BUILDINGS AND ALL CONCRETE OR UNIT PAVEMENTS.
- 7. ASPHALTIC CONCRETE SHALL CONFORM TO R.M.S. SPECIFICATION R116.
- 8. ALL BASECOURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S. FORM 3051, COMPACTED TO MINIMUM 98% MODIFIED DENSITY IN ACCORDANCE WITH AS 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³ OF BASECOURSE MATERIAL PLACED.
- 9. ALL SUB-BASE COURSE MATERIAL SHALL BE IGNEOUS ROCK QUARRIED MATERIAL TO COMPLY WITH R.M.S. FORM 3051, AND COMPACTED TO MINIMUM 95% MODIFIED DENSITY IN ACCORDANCE WITH A.S 1289 5.2.1 FREQUENCY OF COMPACTION TESTING SHALL NOT BE LESS THAN 1 TEST PER 50m³ OF SUB-BASE COURSE MATERIAL PLACED.
- 10. AS AN ALTERNATIVE TO THE USE OF IGNEOUS ROCK AS A SUB-BASE MATERIAL IN (9) A CERTIFIED RECYCLED CONCRETE MATERIAL COMPLYING WITH R.M.S. FORM 3051 WILL BE CONSIDERED. SUBJECT TO MATERIAL SAMPLES AND APPROPRIATE CERTIFICATIONS BEING PROVIDED TO THE SATISFACTION OF CARDNO.
- 11. SHOULD THE CONTRACTOR WISH TO USE A RECYCLED PRODUCT THIS SHALL BE CLEARLY INDICATED IN THEIR TENDER AND THE PRICE DIFFERENCE BETWEEN AN IGNEOUS PRODUCT AND A RECYCLED PRODUCT SHALL BE CLEARLY INDICATED.
- 12. WHERE NOTED ON THE DRAWINGS THAT WORKS ARE TO BE CARRIED BY OTHERS, (eq. ADJUSTMENT OF SERVICES), THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE CO-ORDINATION OF THESE WORKS.

ISSUE FOR DA

SCALE:














	NIS	
		D
way without prior conse ring.The contractor shal	remains the copyright of Core Consulting Engineers Pty Ltd and cannot be reproduced in nt. The contractor shall verify all dimension and levels on site as this is not a workshop I refer any discrepancies to the engineer before proceeding with the work. This drawing with other contract documents, drawings and project specifications. This file has been	D
,	rogram with the latest virus update. However as new viruses are discovered everyday we	

SCALE:

	AC
	DESIGNED :
	HR
not be reproduced in is not a workshop work. This drawing	DRAWN :
This file has been covered everyday we	RQ

VERIFIED: DRAWING TITLE Λ **GENERAL NOTES** PROJECT PROPOSED CARPARK A7. 33 CONSUL ROAD, BROOKVALE

12/09/2020 N.T.S PROJECT No: REVISION: DRAWING No. C001

Plotted by: Ammar Khalid Cad File No: D:\HASAN\SEPTEMBER PROJECT\P-27 (0000) 33 Consul\SWMP\33 CONSUL - SWMP 09-10-2020.dwg

LEGEND:

AUSGRID

JEMENA GAS NORTH

TELSTRA

NBN

NORTHERN BEACHES COUNCIL

SYDNEY WATER

VERIZON BUSINESS


NOTE:

- * THIS PLAN IS SHOULD BE USED **FOR INDICATIVE PURPOSES** ONLY.
- * BEFORE WORKS ARE CARRIED **OUT THE CONTRACTOR SHOULD** CONTACT DIAL BEFORE YOU DIG TO OBTAIN AN UPDATED PLAN.
- * IF THE SERVICES ARE OBSERVED ON SITE AND NOT SEEN ON DIAL BEFORE YOU DIG PLANS. UNDERGROUND UTILITY MAPPING SHOULD BE DONE TO **EXPLORE UNDERGROUND** SERVICES.
- * THIS PLAN DOES NOT RELEASE ANY OTHER CONTRACTOR FROM HIS RESPONSIBILITIES. THIS PLAN SHOULD NOT BE CONSIDERED AS A DIAL BEFORE YOU DIG MAP.
- * THIS PLAN IS DRAWN ON THE BASIS OF AVAILABLE INFORMATION, INVESTIGATION REGARDING OTHER SERVICE SHALL BE DONE BY THE CONTRACTOR.

DIAL BEFORE YOU DIG REFERENCE DETAILS: JOB NO.: 1935313

USER REF NO.: NOT SUPPLIED WORKING ON BEHALF OF: PRIVATE





ISSUE FOR DISCUSSION

ISSUE DATE AMENDMENT
 00
 29.09.2020
 ISSUE FOR DISCUSSION

 01
 02.10.2020
 ISSUE FOR DEVELOPMENT APPLICATION

APG

CLIENT / BUILDER / ARCHITECT



5 / 45-55 Epsom Road Rosebery NSW 2018 02 8662 9300 info@core.engineering core.engineering

ABN 34 620 484 602

NTS

AC HR

12/09/2020 DIAL B4 YOU DIG INVESTIGATION PROPOSED CARPARK AT

33 CONSUL ROAD, BROOKVALE

2290 01 C002




EXISTING CONCRETE TO BE REMOVED AND SEND TO RECYCLING FACILITY. BRICKS TO BE REUSED IN CONSTRUCTION OF OSD & PITS. CAN ALSO BE USED IN SET OUT DURING INITIAL WORK.




EXISTING CAVITY TO BE FILLED AND GRADED WITH AVAILABLE TOP SOIL (STOCKPILE) AFTER CLEANING THE DEBRIS.



EXISTING CAVITY TO BE FILLED AND GRADED WITH AVAILABLE TOP SOIL (STOCKPILE) AFTER CLEANING THE DEBRIS.




EXISTING TOPSOIL TO BE CLEANED FROM WASTE, GRAVELS & CLEAN SOIL IS TO BE USED AS BACKFILL IN THE CAVITIES PRESENT ALONG THE TWO SIDES OF THE BOUNDARY. NOTE THE FILL IS TO BE COMPACTED AND GRADED AS PER PROPOSED DRIVEWAY PLAN.



WASTE MANAGEMENT PLAN

SCALE - 1:100




EXTERNAL GREEN AREA AND POLE TO BE PRESERVED. THE EXISTING STEEL FENCE TO BE REUSED.



STOCKPILE AT THE FRONT AREA TO BE RELOCATED AND REUSED AFTER REMOVING THE TOP SOIL, BOULDERS & GRAVELS.



GRASS AND VEGETATION TO BE REMOVED. EXISTING CAVITY TO BE FILLED AND GRADED WITH AVAILABLE TOP SOIL (STOCKPILE) AFTER CLEANING THE DEBRIS.




EXISTING TOPSOIL TO BE CLEANED FROM WASTE, GRAVELS CLEAN SOIL IS TO BE USED AS BACKFILL IN THE CAVITY PRESENT ALONG THE TWO SIDES OF THE BOUNDARY. NOTE THE FILL IS TO BE COMPACTED AND GRADED AS PER PROPOSED DRIVEWAY PLAN.

ISSUE FOR DA

ISSUE	DATE	AMENDMENT	CLIENT / BUILDER / ARCHITECT
00	29.09.2020	ISSUE FOR DISCUSSION	
01	02.10.2020	ISSUE FOR DEVELOPMENT APPLICATION	
02	09.10.2020	ISSUE FOR DEVELOPMENT APPLICATION	





	5 / 45-55 Epsom Road Rosebery NSW 2018
l G	P 02 8662 9300 E info@core.engineering W core.engineering ABN 34 620 484 602

NORTH:	SCA
© Copyright. This document and Design i	remain

recommend that this file is scanned upon receipt.

	NTS
any way without prior conse drawing.The contractor shal shall be read in conjunction	remains the copyright of Core Consulting Engineers Pty Ltd and cannot be reproduced int. The contractor shall verify all dimension and levels on site as this is not a workshop I refer any discrepancies to the engineer before proceeding with the work. This drawing with other contract documents, drawings and project specifications. This file has been rogram with the latest virus update. However as new viruses are discovered everyday w


	AC	
	DESIGNED :	
oduced in	HR	PROJEC [*]
orkshop drawing s been eryday we	DRAWN:	

	VERIFIED:	DRAWING TITLE :
	AC	WASTE MANAGEMENT PLAN
	DESIGNED :	
_	HR	PROJECT:


RAWING TITLE :	DATE:
WASTE MANAGEMENT PLAN	12/09/2020
	PROJECT No:
	2290
ROJECT:	2290
PROPOSED CARPARK A7.	DRAWING No:

33 CONSUL ROAD, BROOKVALE

C003




SEDIMENTATION & EROSION CONTROL PLAN SCALE - 1:100





ISSUE FOR DA



Plotted by: Ammar Khalid








POST DEVELOPMENT PAVED AREA

SITE AREA	556.11 m ² (AS PER CAD)
IMPERVIOUS AREA	452.47 m ² (81.36%)
PERVIOUS AREA	103.64 m² (18.64%)

SITE AREA 556.11 m² (AS PER CAD) **IMPERVIOUS AREA** 0 m² (0%) PERVIOUS AREA 556.11 m² (100%)

CATCHMENTS ANALYSIS

AS PER CATCHMENT ANALYSIS OF PRE AND POST DEVELOPMENT IT IS EVALUATED THAT THERE IS 100% INCREASE IN THE IMPERVIOUS AREA. AS THE LOT. BEFORE DEVELOPMENT WAS A VACCANT LOT. DUE TO THIS INCREASE IN IMPERVIOUS AREA STORMWATER MANAGEMENT IS PROPOSED IN ACCORDANCE WITH COUNCIL DCP. FURTHER COUNCIL OSD CHECKLIST IS ALSO PROVIDED AS PART OF THIS DA DOCUMENTATION.



SEDIMENT FENCE

- TO BE USED AS A TEMPORARY BARRIER TO INTERCEPT SEDIMENT LADEN RUN-OFF FROM SMALL DRAINAGE AREAS MAXIMUM DRAINAGE AREA FOR OVERLAND FLOW TO A SILT FENCE

- SHALL NOT EXCEED 0.6 Ms PER LINE OF FENCE
 DO NOT USE IF CONCENTRATED FLOW IS DIRECTED TO SILT FENCE
 MAXIMUM ALLOWABLE DISTANCE BETWEEN SILT FENCE FOR
 VARIOUS GRADES LISTED BELOW:

SLOPE V:H	MAX. SLOPE LENGTH
1:2	15
1:3	25
1:4	40
1:5	50
FLATTER THAN 1:5	60

EROSION CONTROL MEASURES.


- . ALL EROSION AND SEDIMENT CONTROL MEASURES, (INCLUDING RE-VEGETATION AND STORAGE OF SOIL AND TOP SOIL), SHALL BE IMPLEMENTED TO THE DEPARTMENT OF
- CONSERVATION OF NEW SOUTH WALES STANDARDS.
 2. TOPSOIL FROM ALL AREAS TO BE DISTURBED, SHALL BE STOCK PILED AND LATER RESPREAD TO AID VEGETATION.AS SHOWN IN C102
- 3. ALL DRAINAGE WORKS SHALL BE CONSTRUCTED AND STABILIZED AS EARLY AS POSSIBLE
- DURING DEVELOPMENT
- DURING DEVELOPMENT.

 4. SEDIMENT TRAPS SHALL BE CONSTRUCTED AROUND ALL PITS.

 5. DISTURBANCE TO VEGETATION SHALL BE LIMITED TO FILL AREAS, ROADWAYS AND DRAINAGE LINES. AREAS OTHER THAN SPECIFIED SHALL BE DISTURBED ONLY WITH PRIOR APPROVAL FROM THE COUNCIL ENGINEER.
- ALL DISTURBED AREAS SHALL BE REVEGETATED AS SOON AS THE RELEVANT WORKS ARE COMPLETED.
- 7. ALL SEDIMENT BASINS AND TRAPS SHALL BE CLEANED WHEN THE STRUCTURES ARE A MAXIMUM OF 60% FULL OF SOLID MATERIALS, INCLUDING DURING MAINTENANCE PERIOD.

 8. A STRIP OF TURF BEHIND AND FOR TOTAL LENGTH OF ALL THE KERBS SHALL BE PROVIDED.

 9. PIT GUARDS SHALL BE INSTALLED AROUND DRAINAGE PITS AT THE COMPLETION OF ROAD



SEDIMENT FENCE ISOMETRIC

SEDIMENT CONTROL DEVICES

- 1. IF SILT FENCE IS NOT USED HAY BALES CAN BE USED FOR SURFACE INLET PIT PROTECTION 2. ALL HAY BALES SHALL BE BOUND WITH WIRE. HAY BALES SHALL BE PLACED END TO END IN A SINGLE ROLE AND EMBEDDED INTO THE SOIL TO A DEPTH OF 100mm. EACH BALES SHALL BE SECURELY ANCHORED WITH TWO STEEL STAKES DRIVEN 600mm INTO THE GROUND AND LOCATED ON THE BALE CENTERLINE.
- 2. FILTER FENCE SHALL BE CONSTRUCTED BY STRETCHING A FILTER FABRIC (PROPEX OR SIMILAR) BETWEEN POSTS AT 3M CENTERS MAXIMUM. FABRIC SHALL BE BURIED INTO THE GROUND 200mm ALONG ITS LOWER EDGE.

TEMPORARY SITE CONTROL FOR ENTRY / EXIT **AREAS**

- THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OF SEDIMENT ONTO PUBLIC ROADS.
 PERIODIC TOP DRESSING WITH ADDITIONAL AGGREGATE MAY BE REQUIRED TO KEEP THE
- SITE CONTROL IN A 'USEABLE STATE'.
- 3. ALL SEDIMENT SPILLED. DROPPED OR WASHED ONTO PUBLIC ROADS MUST BE REMOVED
- MADE DESIGNATION OF LEEP AND CHECKED DAILY.
 REMOVAL AND CLEANING OF PUBLIC ROADS BY BROOMS AND SHOVELS ETC.. WASHING DOWN ROADS IS NOT PERMITTED.

SILT FENCE GROUND SURFACE



EARTH WET BASIN (EARTH BANK)

- REMOVE ALL VEGETATION AND TOPSOIL FROM UNDER THE DAM WALL AND FROM WITHIN
- THE STORAGE AREA.


 CONSTRUCT A CUT-OFF TRENCH 500mm DEEP AND 1200mm WIDE ALONG THE


 CENTERLINE OF THE EMBANKMENT EXTENDING TO A POINT ON THE GULLY WALL LEVEL
- WITH THE RISER CREST.
- WITH THE RISER CREST.

 MAINTAIN THE TRENCH FREE WATER AND RE-COMPACT THE MATERIALS WITH
 EQUIPMENT AS SPECIFIED IN THE SWMP TO 95% STANDARD PROCTOR DENSITY.

 SELECT FILL FOLLOWING THE SWMP THAT IS FREE ROOTS, WOOD, ROCK, LARGE STONE
- OR FOREIGN MATERIAL
- PREPARE THE SITE UNDER THE EMBANKMENT BY RIPPING TO AT LEAST 100mm TO HELP BOND COMPACTED FILL TO EXISTING SUBSTRATE.

 SPREAD THE FILL IN 100mm TO 150mm LAYERS AND COMPACT IT AT OPTIMUM MOISTURE
- CONTENT FOLLOWING THE SWMP.
- CONSTRUCT THE EMERGENCY SPILLWAY.
 REHABILITATE THE STRUCTURE FOLLOWING THE SWMF





CLIENT / BUILDER / ARCHITECT DATE AMENDMENT 29.09.2020 ISSUE FOR DISCUSSION ISSUE FOR DEVELOPMENT APPLICATION 01 02.10.2020 09 10 2020 SSUE FOR DEVELOPMENT APPLICATION.






5 / 45-55 Epsom Road sebery NSW 2018

ARN 34 620 484 602

NTS

VERIFIED:	DRAWING TITLE :
AC	AREA ANALYSIS & SEC DETAIL
DESIGNED:	
HR	PROJECT:
DRAWN:	PROPOSED CARPARK A7.
RQ	33 CONSUL ROAD, BROOKVALE


12/09/2020 1:100 AILS 2290 02 C101



PROPOSED CARPARK LAYOUT SCALE - 1:100

NOTE:

THIS CAR PARK IS PROPOSED AS PER ADVISE OF THE TRAFFIC CONSULTANT. REFER TO TRAFFIC ENGINEER REPORT & EVALUATION.



PAVEMENT DESIGN NOTES & SPECIFICATION


ENGINEER OBSERVATION AS PER MY SITE EVALUATION & GEOTECHNICAL INITIAL ADVISE I HAVE ANTICIPATED THE SUBGRADE IN MEDIUM CATEGORY SUBGRADE IS MAINLY COMPOSED OF MAINLY CLAYEY GRAVELS, FIRM SAND WITH SOME CLAY, SANDY CLAY, SILTY CLAY. THIS MATERIAL IS OBSERVED TO MAKE A POOR UNSEALED ROAD WHEN EXCESSIVELY WET OR DRY. THIS TYPE OF SUBGRADE NORMALLY HAVE CBR VALUE BETWWEN 6 TO 10.


SPECIFICATION OF THE PAVEMENT:
30mm ASPHALT WEARING COURSE
10mm SINGLE COAT PRIME SEAL.
175mm THICK BASE COURSE (DGB20) OR
220mm THICK SUB BASE DGB40. ON
COMPACTED SUB GRADE MIN CBR 5%.



PROPOSED LANDSCAPE AREA

SECTION A-A SCALE - 1:25






SECTION B-B SCALE - 1:25


SECTION C-C SCALE - 1:25

ISSUE FOR DA

ISSUE	DATE	AMENDMENT	CLIENT / BUILDER / ARCHITECT		CIVII		NORTH:	SCALE:	VERIFIED:	DRAWING TITLE :	DATE:	SCALE:
	02.10.2020	ISSUE FOR DISCUSSION ISSUE FOR DEVELOPMENT APPLICATION			CIVIL	5 / 45-55 Epsom Road Rosebery NSW 2018	(A)	NTS	AC	STANDARD DETAILS LAYBACK & CARPARK	12/09/2020	1:100
02	09.10.2020	ISSUE FOR DEVELOPMENT APPLICATION	-	ADC		P 02 8662 9300			DESIGNED:	LATBACK & CARPARK	PROJECT No:	REVISION:
			-	APG		E info@core.engineering W core.engineering	© Copyright. This document and Design	on remains the conviols of Core Consulting Engineers Pty I to and cannot be reproduce	HR din	PROJECT:	2290	02
		-	-		COREPROJECT	ABN 34 620 484 602	any way without prior consent. The contractor shall verify all dimension and levels on site as this is not a workshop drawing. The contractor shall refer any discrepancies to the engineer before proceeding with the work. This drawing		DRAWN:	PROPOSED CARPARK A7.	DRAWING No:	1
			-		ELECTRICAL ● FIRE ● HYDRAULIC ● M	CHANICAL • STRUCTURAL• CIVIL • FACADES	shall be read in conjunction checked by any anti-virus recommend that this file is	on with other contract documents, drawings and project specifications. This file has bee ; program with the latest virus update. However as new viruses are discovered everyda s scanned upon receipt.	we RQ	33 CONSUL ROAD, BROOKVALE	C10)2



STORMWATER MANAGEMENT PLAN SCALE - 1:100



NOTE:

THE PRODUCT SPECIFICATIONS ARE AS PER MANUFACTURER / PROVIDER INFORMATION

ISSUE FOR DA

LEGENDS

SWD

IR 🚫

HER 🚫

Cad File No: D:\HASAN\SEPTEMBER PROJECT\P-27 (0000) 33 Consul\SWMP\33 CONSUL - SWMP 09-10-2020.dwg

STORM WATER

DRAIN LINE (Ø150)

SW-PIT WITH LINTEL

FLOW DIRECTION

EXISTING SW PIT

SILT ARRESTOR

LINE- (AGI LINE)


RISER

Ø100 SUBSOIL DRAINAGE

(IR) INTERMEDIATE

(HER)HIGH END RISER





- 1. HOLE IN ORIFICE PLATE TO BE PRECISION CUT WITH SHARP EDGES TO THE SPECIFIED DIAMETER.
- 2. ORIFICE PLATE TO BE PLACED CENTRALLY OVER THE OUTLET PIPE.
- 3. ORIFICE PLATE TO BE MADE FROM STAINLESS STEEL HOT DIPPED GALVANIZED OR OTHERS NOT ACCEPTABLE.

CLIENT / BUILDER / ARCHITECT

- 4. OUTLET PIPE TO BE CAST INTO THE WALL OF THE PIT.
- 5. HOLE IN THE PLATE TO BE CENTRALLY PLACED.

ISSUE FOR DEVELOPMENT APPLICATION

ISSUE FOR DEVELOPMENT APPLICATION

AMENDMENT

ISSUE FOR DISCUSSION

APG

17 m³ OSD

Q5 (EXISTING) 17 l/s

Q100 (EXISTING) 33 l/s

A 550 sqm SITE WE REQUIRED.

CIVIL 5 / 45-55 Epsom Road Rosebery NSW 2018 P 02 8662 9300 E info@core.engineering W core.engineering W core.engineering ABN 34 620 484 602 ELECTRICAL • FIRE • HYDRAULIC • MECHANICAL • STRUCTURAL • CIVIL • FACADES

4. AS PER TABLE 2B OF ONSITE STORMWATER TECHNICAL SPECIFICATION FOR

5. FROM TABLE 3, FOR 17 I/sec 85mm ORIFICE PLATE IS REQUIRED WITH 1.25 M OSD.


IMPORTANT NOTE:


Plotted by: Ammar Khalid

INTERMEDIATE ACCESS IS PROVIDED BECAUSE THE LENGTH OF OSD IS GREATER 1. THAN 3M.

Cad File No: D:\HASAN\SEPTEMBER PROJECT\P-27 (0000) 33 Consul\SWMP\33 CONSUL - SWMP 09-10-2020.dwg

ISSUE FOR DA





TYPICAL CROSS SECTION


NOTES:

 Layback and gutter shall be poured in PLAIN CONCRETE and finished with a steel trowel. Minimum compressive strength of concrete shall be 25MPa at 28 days. Industrial/commercial properties shall increase the depth of concrete to 180mm and provide SL82 mesh with 30mm top cover.

500

- 2. The subgrade shall be thoroughly compacted by the use of vibratory compaction equipment until it shows no signs of movement, or as directed by Council.
- Vehicle crossing to be constructed in accordance with levels and specifications issued by Council.
- Kerbing to be constructed in accordance with Council Plan A4 2276/A and specifications.
- 5. Where Council or an Accredited Certifier (Civil Woks) directs that the gutter be retained, the contractor shall place a 75mm deep saw cut in the gutter invert and remove kerb and/or layback.
- Where Council or an Accredited Certifier (Civil Woks) directs that the gutter be removed, a Road Opening Permit must be obtained from Council's Customer Service Centre prior to commencing work. Once the permit is established the contactor may commence vehicle crossing works. Upon completion of the works, temporary restoration shall be provided as set out in the 'Specification Not to Scale. All Dimensions in Millimetres. For Trench Construction Within Council Roads'.
- The construction of all vehicle crossings and associated works on the road reserve must be completed by a Council approved concrete contractor.
- 8. EJ Expansion Joint 10mm Mastic. R – Radius


THIS DRAWING & DETAILS ARE TAKEN FORM COUNCIL DRAWING No. A4 2276/B



NOTES:

- Kerb and gutter shall be poured in PLAIN CONCRETE and finished with a steel trowel. Minimum compressive strength of concrete shall be 25MPa at 28 days.
- 2. The subgrade shall be thoroughly compacted by the use of vibratory compaction equipment until it shows no signs of movement, or as directed by Council.
- Where Council or an Accredited Certifier (Civil Woks) directs that the gutter be retained, the contractor shall place a 75mm deep saw cut in the gutter invert and remove kerb and/or layback.
- Where Council or an Accredited Certifier (Civil Woks) directs that the gutter be removed, a Road Opening Permit must be obtained from Council's Customer Service Centre prior to commencing work. Once the permit is established the contactor may commence vehicle crossing works. Upon completion of the works, temporary restoration shall be provided as set out in the 'Specification For Trench Construction Within Council Roads
- The construction of all vehicle crossings and associated works on the road reserve must be completed by a Council approved concrete contractor.

THIS DRAWING & DETAILS ARE TAKEN FORM COUNCIL DRAWING No. A4 2276/A



FORMWORK

THE FORMS SHALL BE ALIGNED TRUE TO GRADE AND WITH OUT IRREGULARITIES. THE TOLERANCE SHALL BE ±15mm PROVIDED THAT VARIATIONS IN LEVELS ARE NOT LOCAL AND ORE OVER LENGTH OF 3 METERS OR MORE.

FORMS SHALL BE CONSTRUCTED SO THAT THEY CAN BE REMOVED WITHOUT DAMAGING THE CONCRETE AND SHALL BE ADEQUATELY BRACED. THE INNER SURFACE OF FORMS SHALL BE ADEQUATELY OILED TO ENSURE THE NON-ADHESION OF THE CONCRETE. THE MATERIAL USED FOR FORMS FOR THE EXPOSED SURFACES SHALL BE DRESSED SOFT WOOF TIMBER.

TIMBER PEGS OF 50mm x 50mm-DIMENSION MINIMUM MUST BE PROVIDED FOR THE SUPPORT OF ALL FORMWORK. THE USE OF STEEL PEGS FOR THE SUPPORT OF FORMWORK IS PROHIBITED

MATERIALS

READY MIXED CONCRETE SHALL CONFORM TO THE PROVISIONS OF AS 1379 - 2007 " READY MIXED

THE MINIMUM COMPRESSIVE STRENGTH Fc OF THE CONCRETE SHALL BE 25 MPa AT 28 DAYS IN ACCORDANCE WITH AS 3600 - 2009 " CONCRETE STRUCTURES"

FOR HAND PLACED KERB AND GUTTER EXPANSION JOINT 10mm THICK FOR THE FULL DEPTH OF THE KERB AND GUTTER SHALL BE PROVIDED AT INTERVALS NOT EXCEEDING 6m.

FOR MACHINE PLACED KERB AND GUTTER, EXPANSION JOINTS 6mm THICK SHALL BE PROVIDED AT INTERVALS OF 6m AND CONSTRUCTION JOINTS SHALL BE FORMED EVERY 3m FOR THE FULL DEPTH OF THE KERB AND GUTTER.

JOINTS ARE ALSO REQUIRED WHERE THE GUTTER ABUTS GULLY PITS AND GUTTER CROSSINGS. EXPANSION JOINTS SHALL CONSIST OF PERFORMED JOINTING MATERIAL BITUMINOUS FIBERBOARD.

TOLERANCE

TOLERANCE ON THE LEVEL OF KERB AND GUTTER CONSTRUCTION BOTH HORIZONTAL AND VERTICAL SHALL BE PLUS OR MINUS 10mm.

KERB AND GUTTER

THECONSTRUCTION OF CONCRETE KERB AND GUTTER IS TO BE IN ACCORDANCE WITH AS 2876 - 2000 " CONCRETE KERBS AND CHANNELS (GUTTERS) - MANUALLY OR MACHINE PLACED " UNLESS OTHERWISE INDICATED BELOW.

KERB AND GUTTER DETAIL

KERB AND GUTTER SHALL BE IN ACCORDANCE WITH COUNCIL DRAWING NUMBER A4 2267/A/ AS DOCUMENTED BELOW.

LEVELS

DESIGN PLAN ARE TO BE PREPARED BY THE APPLICANT AND APPROVED BY THE COUNCIL PRIOR TO CONSTRUCTION.

PLACING CONCRETE

THE CONCRETE SHALL BE PLACED SO AS TO AVOID SEGREGATION AND SHALL BE ADEQUATELY COMPACTED. CARE SHALL BE TAKEN TO FILL EVERY PART OF THE FORMS AND TO WORK TO COARSER AGGREGATE BACK FROM THE FACE. EXPOSED SURFACES SHALL BE FINISHED WITH A STEEL FLOAT, AND CORNERS AND EDGES SHALL BE NEATLY ROUNDED WITH A NOISING TOOL. CONCRETE SHALL NOT BE DISTURBED AFTER IT HAS BEEN IN THE FORMS FOR TWENTY (20) MINUTES.

FINISH

AFTER REMOVAL OF THE FORMS, MINOR OR POROUS SECTIONS OR HOLES SHALL BE REPAIRED WITH A 3 TO 1 SAND AND CEMENT MORTAR MIX. THE EXPOSED SURFACES SHALL THEN BE RUBBED WITH A WOODEN FLOAT AND CLEAN WATER TO LEAVE THE SURFACES SMOOTH AND UNIFORM IN COLOR AND APPEARANCE.

BACKFILLING

AFTER REMOVAL OF FORMWORK THE FOOTWAY BEHIND THE KERB SHALL BE NEATLY TRIMMED, FILLED AND OR TURFED TO MAKE A SMOOTH CONNECTION TO THE UNDISTURBED NATURE STRIP.

CONSTRUCTION NOTES: INSTALL A 400mm MINIMUM WIDE ROLL OF TURF ON THE FOOTPATH NEXT TO THE KERB AND AT THE SAME LEVEL AS KERBSIDE TURF STRIP

NOT TO SCALE

TYPICAL DETAIL FOR ILLUSTRATION

ISSUE FOR DA

AMENDMENT DATE 29.09.2020 ISSUE FOR DISCUSSION 02.10.2020 ISSUE FOR DEVELOPMENT APPLICATION ISSUE FOR DEVELOPMENT APPLICATION 02 09.10.2020




LAY 1.4m LONG TURF STRIPS NORMAL TO THE KERB EVERY 10m

REHABILITATE DISTURBED SOIL BEHIND THE KERB

CLIENT / BUILDER / ARCHITECT





Plotted by: Ammar Khalid

NORTH:	SCALE:	VERIFIED:	DI
	NTS	AC	
		DESIGNED:	
© Copyright. This document and Design r	HR	PI	
any way without prior conse drawing. The contractor shall shall be read in conjunction	DRAWN:	_	
checked by any anti-virus pr recommend that this file is s	KŲ		

	VERIFIED:	DRAWING TITLE :			
	AC	MISC DETAILS			
	DESIGNED :				
duced in	HR	PROJECT:			
rkshop Irawing	DRAWN:	PROPOSED CARPARK A7.			
been ryday we	RQ	33 CONSUL ROAD, BROOKVAL			

100021 01(1)(
	DATE:	SCALE:			
	12/09/2020	1:100			
	PROJECT No :	REVISION:			
	2290	02			
	DRAWING No:				
	C202				