
PROPOSED RESIDENTIAL SUBDIVISION 4 FOREST ROAD, WARRIEWOOD NSW 2102

CIVIL ENGINEERING SERVICES - DEVELOPMENT APPLICATION

DWG No.	DESCRIPTION	REV
C1.001	COVER SHEET AND DRAWING INDEX	С
C1.101	NOTES AND LEGENDS	С
C1.201	TYPICAL DETAILS	С
C2.001	BULK EARTHWORKS PLAN	С
C2.101	BULK EARTHWORKS - SITE SECTION - SHEET 1	С
C2.102	BULK EARTHWORKS - SITE SECTION - SHEET 2	С
C2.103	BULK EARTHWORKS - SITE SECTION - SHEET 3	С
C2.104	BULK EARTHWORKS - SITE SECTION - SHEET 4	С
C2.105	BULK EARTHWORKS - SITE SECTION - SHEET 5	С
C3.001	GENERAL ARRANGEMENT - SITEWORKS AND GRADING PLAN	С
C4.101	RETAINING WALL - NOTES AND DETAILS	С
C5.101	ROAD DESIGN - TYPICAL ROAD CROSS SECTION	С
C5.201	ROAD DESIGN - LONGITUDINAL SECTIONS - SHEET 1	С
C5.202	ROAD DESIGN - LONGITUDINAL SECTIONS - SHEET 2	С
C7.001	STORMWATER MANAGEMENT PLAN	С
C7.101	STORMWATER MANAGEMENT - CATCHMENT PLAN	С
C7.201	STORMWATER MANAGEMENT - DETAILS - SHEET 1	С
C7.202	STORMWATER MANAGEMENT - DETAILS - SHEET 2	С
C7.203	STORMWATER MANAGEMENT - DETAILS - SHEET 3	С
C7.401	STORMWATER MANAGEMENT - DRAINAGE LONGITUDINAL SECTIONS - SHEET 1	С
C7.402	STORMWATER MANAGEMENT - DRAINAGE LONGITUDINAL SECTIONS - SHEET 2	С
C7.403	STORMWATER MANAGEMENT - DRAINAGE LONGITUDINAL SECTIONS - SHEET 3	С
C8.001	SOIL EROSION AND SEDIMENT CONTROL PLAN	С
C8.101	SOIL EROSION AND SEDIMENT CONTROL PLAN - NOTES AND DETAILS	С





LOCALITY PLAN


COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN

ISSUE FOR DA 16.10.23 ROB ISSUE FOR DA 20.01.23 UF ISSUE FOR DA Date Drawn

BMN PROPERTIES PTY LTD

133 ALEXANDER STREET CROWS NEST NSW 2065



Baulkham Hills NSW 2153

T +61 2 9634 6311

ACOR Consultants Pty Ltd
Unit 10, Level 1, No.1 Maitland Place

Project
RESIDENTIAL SUBDIVISION

NOT FOR CONSTRUCTION

COVER SHEET AND DRAWING INDEX

16.10.23 **JUN 22** AS SHOWN

GENERAL NOTES

- ALL WORK TO BE IN ACCORDANCE WITH THE NORTHERN BEACHES COUNCIL STANDARD DRAWINGS AND SPECIFICATIONS, AND TO THE REQUIREMENTS OF COUNCIL ENGINEERS.
- A SURVEY OF THE SITE HAS BEEN UNDERTAKEN BY MICHAEL KIRKWOOD AND ASSOCIATE PTY LTD AS RECEIVED BY ACOR CONSULTANTS PTY LTD' ON 03.05.21 ALL LEVELS TO A.H.D. DRAWINGS SHOW DETAILS AT THE TIME OF SURVEY
- ALL RUBBISH, DEBRIS, UNDERGROWTH, FENCES & TREES NOTED ON THE PLAN WITHIN THE LIMIT OF WORKS ARE TO BE REMOVED FROM SITE AREA TO THE SATISFACTION OF COUNCIL OR THE SUPERINTENDENT
- NO DISTURBANCE TO THE SITE SHALL BE PERMITTED OTHER THAN IN THE IMMEDIATE AREA OF THE WORKS AND NO MATERIAL SHALL BE REMOVED FROM SITE WITHOUT COUNCIL
- NO WORK WITHIN ADJOINING PROPERTIES TO BE UNDERTAKEN WITHOUT WRITTEN PERMISSION FROM THE OWNERS OR RESPONSIBLE AUTHORITY
- THE CONTRACTOR SHALL OBTAIN LEVELS FROM ESTABLISHED BENCHMARKS ONLY
- THE LOCATION OF RECOVERY MARKS AND BENCH MARKS SHOULD BE VERIFIED AND CONFIRMED BY THE CONTRACTOR AND ANY DISCREPANCIES SHOULD BE CLARIFIED IN WRITING WITH THE SURVEYOR PRIOR TO THE COMMENCEMENT OF WORK
- THE CONTRACTOR SHALL ERECT A POLLUTION WARNING SIGN AT THE ENTRANCE TO THE SUBDIVISION OR PROPOSED DEVELOPMENT
- SERVICE CONDUITS SHALL BE PLACED AS DIRECTED BY INTEGRAL ENERGY, NBN / TELSTRA. AND AS REQUIRED BY THE RELEVANT SERVICE AUTHORITY AND AS PER SERVICE AUTHORITY APPROVED PLANS
- 10. STREET SIGNS REQUIRED WHERE SHOWN, STREET SIGNS TO COUNCIL STANDARD SHALL BE INSTALLED BY THE CONTRACTOR.
- 11. SIGNPOSTING AND LINEMARKING TO CONFORM WITH AS1742.2 & AS1743.
- 12. KERB RAMP CROSSINGS TO BE PROVIDED WHERE SHOWN ON PLAN AND CONSTRUCTED AS DETAILED AND TO COUNCIL STANDARDS
- 13. NO TREES ARE TO BE REMOVED OR LOPPED OTHER THAN THOSE SHOWN AND THOSE IN ROAD RESERVES, WITHOUT COUNCILS WRITTEN PERMISSION. A TREE INSPECTION WITH COUNCIL SHALL BE ARRANGED ONCE LOTS HAVE BEEN PEGGED.
- 14. ALL NEW WORKS ARE TO MAKE SMOOTH JUNCTIONS WITH ALL EXISTING CONDITIONS. AC JOINTS TO BE SAW CUT AT CONNECTION TO EXISTING PAVEMENT. THE CONTRACTOR IS TO MAKE ALL DUE ALLOWANCES FOR WORKS DURING CONSTRUCTION.
- 15. SUBSOIL DRAINAGE TO BE PROVIDED BEHIND KERBING AS PER APPROVED PLANS AND AS DIRECTED BY COUNCIL OR THE CERTIFIER DURING CONSTRUCTION.
- 16. THE THICKNESS OF ROAD PAVEMENTS SHALL BE CONFIRMED BY THE CONTRACTOR UPON COMPLETION OF SUBGRADE TESTING UNDERTAKEN BY THE CONTRACTOR.
- 17. SERVICES TO EXISTING DEVELOPMENTS ARE TO BE MAINTAINED AT ALL TIMES.
- 18. PROPOSED SERVICES CROSSING EXISTING ROADS SHALL BE THRUST BORED UNDER THE ROAD SO AS NOT TO DAMAGE EXISTING SURFACES.
- 19. CONTRACTOR IS TO VERIFY THE LOCATION OF ALL EXISTING SERVICES WITH EACH RELEVANT AUTHORITY PRIOR TO COMMENCEMENT OF CONSTRUCTION. ANY DAMAGE TO SERVICES SHALL BE REPAIRED BY THE CONTRACTOR OR THE RELEVANT AUTHORITY AT THE CONTRACTOR'S EXPENSE. SERVICES SHOWN ON THESE PLANS ARE ONLY THOSE EVIDENT AT THE TIME OF SURVEY. ANY UTILITIES ADJUSTMENTS REQUIRED TO BE AT THE CONTRACTORS EXPENSE.
- 20. ENSURE ADEQUATE TRENCH FOUNDATION AND BEDDING COMPACTION SPECIFICALLY ADJACENT TO DRAINAGE STRUCTURES AND PROTECTION TO PIPES FROM CONSTRUCTION TRAFFIC. CRACKED STORMWATER PIPES WILL NOT BE ACCEPTED.
- 21. PROVIDE GALVANISED STEEL KERB OUTLETS PLACED IN KERB ON LOW SIDE OF LOTS, 500mm FROM BOUNDARY OR WHERE SHOWN. PROVIDE SUITABLE ADAPTOR TO ALLOW CONNECTION OF 90mm DIA. S.W.PIPE IN ACCORDANCE WITH COUNCIL STANDARDS
- 22. NO MATERIALS TO BE STOCKPILED ON FUTURE ALLOTMENTS WITHOUT APPROVAL IN WRITING FROM THE CLIENTS REPRESENTATIVE.
- 23. EROSION AND SILT PROTECTION MEASURES ARE TO BE MAINTAINED AT ALL TIMES AND THE LENGTH OF TRENCH OPENINGS MINIMISED.
- 24. THE CONTRACTORS ITP SHALL ALLOW FOR A HOLD POINT TO ALLOW CHECK LEVELS AND PROOF ROLL PRIOR TO PLACEMENT OF
- SUB BASE COURSE BASE COURSE MATERIAL
- WEARING COURSE MATERIAL. PRIME COAT TWO WEEKS PRIOR TO AC SEAL, THICKNESS OF AC SEAL AS SPECIFIED
- 26. ALL PIPES TO BE SOCKET/SPIGOT RUBBER RING JOINT FRC PIPES CLASS '3' OR REINFORCED
- 27. GRATES TO COMPLY WITH COUNCIL STANDARDS, ALL GRATES TO BE CYCLE FRIENDLY GALVANISED BOLT DOWN TYPE.
- 28. STEP IRONS REQUIRED IN PITS GREATER THAN 1.0m DEPTHS.

CONCRETE CLASS '3'. UNLESS NOTED OTHERWISE.

29. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE FULL QA DOCUMENTATION OF THE PROJECT TO ENSURE WORKS MEET THE RELEVANT SECTIONS OF THE CC FOR ROADS AND DRAINAGE WORKS. A COMPLETE ITP PLAN SHALL BE SUBMITTED TO THE SUPERINTENDENT FOR APPROVAL PRIOR TO WORKS COMMENCING ON SITE, COVERING ALL ASPECTS OF THE CONTRACT.

GENERAL NOTES

- 30. ALL WORKS ARE TO BE SETOUT BY A REGISTERED SURVEYOR.
- 31. THE CLIENT WILL PREPARE WAE DRAWINGS AT COMPLETION TO ENSURE THE WORKS MEET THE REQUIREMENTS OF THE DESIGN.
- 32. A TRAFFIC CONTROL PLAN IS TO BE SUBMITTED TO COUNCIL BY THE CONTRACTOR FOR APPROVAL PRIOR TO WORKS COMMENCING.
- 33. CONTRACTOR IS TO PROVIDE A 3m LONG LENGTH OF 100Ø SUBSOIL DRAINAGE LINE ON THE UPSTREAM SIDE OF DRAINAGE PITS, INCLUDING GEOFABRIC SOCK AND NOM. 20mm GRAVEL
- 34. ALL DRAINAGE TRENCHES WITHIN THE ROAD RESERVE ARE TO BE BACKFILLED WITH CLEAN SHARP SAND.
- 35. SUB-BASE AND BASE MATERIALS FOR ROADS MUST COMPLY WITH RMS SPECIFICATION 3051. ALL OTHER ROAD PAVEMENT MATERIALS MUST COMPLY WITH THE RELEVANT RMS SPECIFICATION.
- 36. ALL ROADS ARE TO HAVE A TEMPORARY SINGLE COAT SEAL APPLIED PRIOR TO LAYING OF THE ASPHALTIC CONCRETE SEAL. AC TO BE BONDED.
- 37. POWER & LIGHT POLES TO HAVE A 1m X 1m ISOLATION ZONE REGARDLESS OF LOCATION.
- 38. ALL INTER-ALLOTMENT PIPELINES TO HAVING RODDING EYES IMMEDIATELY DOWNSTREAM OF ALL SLOPE JUNCTIONS.
- 39. CONCRETE PATHS, DRIVEWAYS, & BATTLE-AXE HANDLES TO BE BONDED PENDING COMPLETION OF SERVICES IN ACCORDANCE WITH COUNCIL REQUIREMENTS AND AS DIRECTED BY THE PRINCIPAL
- 40. ALL MAJOR & NON-STANDARD STRUCTURES TO HAVE ENGINEERING CERTIFICATION.
- 41. HIGH EROSION AREAS. INCLUDING BATTERS TO BE STABILISED WITHIN 7 DAYS OF COMPLETION OF WORKS AND EARLIER IF DIRECTED BY THE SUPERINTENDENT.
- 42. ALL STABILISED WORKS ARE TO BE MAINTAINED UNTIL EXPIRY OF MAINTENANCE PERIOD.
- 43. ALL STRABILISED WORKS ARE TO BE MAINTAINED UNTIL EXPIRY OF MAINTENANCE PERIOD. OVERFLOW PATHS TO BE FORMED AT THE TIME OF CONSTRUCTION TO SUIT DESIGN ARI
- 44. VARIATIONS NEED TO BE APPROVED PRIOR TO COMMENCEMENT OF WORK. IF IN DOUBT, CONTACT ACOR CONSULTANTS


EARTHWORKS NOTES

- EARTHWORKS TO BE CARRIED OUT TO THE SATISFACTION OF COUNCIL'S AND RELEVANT AUSTRALIAN STANDARD AND GEOTECH ENGINEER. UNSOUND MATERIALS ARE TO BE REMOVED FROM ROADS AND LOTS AND TESTED PRIOR TO FILLING. THE CONTRACTOR IS TO PROVIDE PLANS OF TEST LOCATIONS AND TEST CERTIFICATES AS PER THE SPECIFICATION WHERE REQUIRED. THE CONTRACTOR MUST ENSURE COUNCIL APPROVAL OF MATERIALS, PRIOR TO DELIVERY TO SITE.
- 2. DEWATER AND REMOVE SLUDGE FROM EXISTING DAM ENSURE ALL DAM DEWATERING AND SLUDGE REMOVAL IS IN ACCORDANCE WITH SEPARATE REPORT BY OTHERS.
- 3. ALL EARTHWORKS TO BE APPROVED BY A GEOTECHNICAL ENGINEER TO LEVEL 1 MONITORING, SAMPLING, TESTING AND CERTIFICATION.
- 4. TOPSOIL FROM SITE FILLING AND REGRADING AREAS TO BE STRIPPED. STOCKPILED AND RESPREAD AS SHOWN ON PLAN. EXCESS MATERIAL TO BE CARTED OFFSITE TO APPROVED LOCATION. ALL SITE FILLING TO BE COMPACTED IN ACCORDANCE WITH AS3798 TO A MIN. OF 98% SMDD AT ±2% OF O.M.C. A GEOTECHNICAL CERTIFICATE FROM A N.A.T.A REGISTERED LABORATORY IS TO BE SUPPLIED BY CONTRACTOR.
- WHERE THE SLOPE OF THE NATURAL SURFACE EXCEEDS ONE IN FOUR (1:4) BENCHES ARE TO BE CUT TO PREVENT SLIPPING OF THE PLACED FILL MATERIAL AS REQUIRED BY THE DEVELOPER'S GEOTECH ENGINEER TO STANDARD PRACTICE.
- 6. ALL BATTERS ARE TO SCARIFIED TO ASSIST WITH ADHESION OF TOP SOIL TO BATTER FACE.
- PROVIDE MIN. 50mm 75mm TOPSOIL WITH COUCH GRASS TURF ON ALL FOOTPATHS. ALL BARE AREAS OTHER THAN FOOTPATHS TO BE SOWN WITH SEED, FERTILISED AND HAY MULCHED TO COUNCIL'S SPECIFICATION. GRASS / TURF TO BE MAINTAINED BY CONTRACTOR AT ALL TIMES INCLUDING PERIODS OF INSUFFICIENT RAIN.
- 8. THE CONTROL TESTING OF EARTHWORKS SHALL BE IN ACCORDANCE WITH THE GUIDELINES IN AUSTRALIAN STANDARD 3798-1990. WHERE IT IS PROPOSED TO USED TEST METHOD AS1289 EB.1 OR AS1289 EB2 TO DETERMINE THE FIELD DENSITY, A SAND REPLACEMENT METHOD SHALL BE USED TO CONFIRM THE RESULTS AS DIRECTED BY COUNCIL.
- 9. THE CONTRACTOR SHALL CONTROL SEDIMENTATION, EROSION AND POLLUTION DURING CONSTRUCTION IN ACCORDANCE WITH THE REQUIREMENTS OF COUNCIL AND APPROVED PLANS.
- 10. A 1.2 METER WIDE, CONTINUOUS STRIP OF COUCH GRASS SHALL BE PLACED BEHIND THE BACK OF ALL KERBS AND PERIMETER OF ALL INLET PITS IMMEDIATELY AFTER THE COMPLETION OF THE FOOTPATH GRADING AND CONSTRUCTION OF PITS RESPECTIVELY, MAINTAINED AND REPLACED AS REQUIRED DURING THE MAINTENANCE PERIOD. TURFING / LANDSCAPE GRASS SHALL ALSO BE PLACED TO THE FULL WIDTH OF ROAD SWALE DRAINS UPON COMPLETION.
- 11. SOIL AND SEDIMENT PROTECTION TO BE PROVIDED AND THOROUGHLY MAINTAINED AROUND DRAINAGE SYSTEM FOR THE DURATION OF WORKS. DIVERSION OF WATER AND THE PROTECTION OF WORKS IS THE CONTRACTORS RESPONSIBILITY.
- 12. LOTS REQUIRING FILL SHALL BE CONSTRUCTED TO LEVEL 1 SUPERVISION WITH TESTING AND DOCUMENTATION SUITABLE TO DETERMINE FUTURE LOT CLASSIFICATION.
- 13. CONTROLLED EARTHWORKS SHALL BE CERTIFIED BY A N.A.T.A REGISTERED LABROITORY. ALL TEST CERTIFICATION AND PLANS LOCATION TO BE SUBMITTED TO THE PRINCIPAL AND SHALL BE TO COUNCILS SATISFACTION

CIVIL LEGEND PROPOSED KERB AND GUTTER VEHICULAR CROSSING EASEMENT TO DRAIN WATER CONTROL LINE TEMPORARY SAFETY FENCE 56.2 FINISHED SURFACE CONTOUR MINOR FINISHED SURFACE CONTOUR MAJOR 60.5 EXISTING SURFACE CONTOUR **BATTER** STORMWATER DRAINAGE STRUCTURE WITH NUMBER (REFER STORMWATER DRAINAGE STRUCTURES SCHEDULE) STORMWATER DRAINAGE LINE, SIZE AND FLOW DIRECTION PROPOSED ROAD PAVEMENT PROPOSED FOOTPATH PAVEMENT PROPOSED LOT PROPOSED DRIVEWAY PAVEMENT RETAINING WALL

C) COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN BMN PROPERTIES PTY LTD ISSUE FOR DA 16.10.23 ROB VG ISSUE FOR DA 20.01.23 UF ISSUE FOR DA 13.12.22 UF 133 ALEXANDER STREET **CROWS NEST NSW 2065** Date Drawn Approved Description



Baulkham Hills NSW 2153 T +61 2 9634 6311 (O) (O) (O)

ACOR Consultants Pty Ltd
Unit 10, Level 1, No.1 Maitland Place


Project
RESIDENTIAL SUBDIVISION


4 FOREST ROAD


WARRIEWOOD. NSW 2102


NOTES AND LEGENDS


JUN 22 NOT TO SCALE 16.10.23











This drawing has been accignized an electronic state and artifully has been checked and approved by.					Client	
					North	BMN PROPERTIES PTY LTD
С	ISSUE FOR DA	16.10.23	ROB	VG		
В	ISSUE FOR DA	20.01.23	UF	VG		
Α	ISSUE FOR DA	13.12.22	UF	VG		133 ALEXANDER STREET
Issue	Description	Date	Drawn	Approved		CROWS NEST NSW 2065
-1 0	1cm at full size			20cm		

ICONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS


ACOR Consultants Pty Ltd
Unit 10, Level 1, No.1 Maitland Place


Project
RESIDENTIAL SUBDIVISION Baulkham Hills NSW 2153 T +61 2 9634 6311


4 FOREST ROAD

WARRIEWOOD, NSW 2102

TYPICAL DETAILS **JUN 22** 16.10.23 AS SHOWN







ACOR Consultants Pty Ltd
Unit 10, Level 1, No.1 Maitland Place

Project
RESIDENTIAL SUBDIVISION Baulkham Hills NSW 2153 T +61 2 9634 6311 4 FOREST ROAD WARRIEWOOD, NSW 2102

BULK EARTHWORKS SITE SECTION

SHEET 1 JUN 22 AS SHOWN

133 ALEXANDER STREET CROWS NEST NSW 2065

16.10.23 ROB

20.01.23 UF

13.12.22 UF

Date Drawn Approved

VG

VG

BMN PROPERTIES PTY LTD

not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN

ISSUE FOR DA

ISSUE FOR DA


ISSUE FOR DA


Issue Description

CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

NOT FOR CONSTRUCTION

16.10.23





SCALE 1:200 @ A1 SCALE 1:400 @ A3 ©COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd. This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN BMN PROPERTIES PTY LTD ISSUE FOR DA 16.10.23 ROB VG ISSUE FOR DA 20.01.23 UF VG 13.12.22 UF ISSUE FOR DA VG 133 ALEXANDER STREET CROWS NEST NSW 2065 Date Drawn Approved Issue Description CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

Baulkham Hills NSW 2153

<u>@</u> @

T +61 2 9634 6311

4 FOREST ROAD WARRIEWOOD, NSW 2102


ACOR Consultants Pty Ltd
Unit 10, Level 1, No.1 Maitland Place


Project
RESIDENTIAL SUBDIVISION


SITE SECTION SHEET 2

BULK EARTHWORKS

16.10.23 JUN 22 AS SHOWN NSW210416







NOT FOR CONSTRUCTION Drawing Title
BULK EARTHWORKS

CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS


T +61 2 9634 6311


Unit 10, Level 1, No.1 Maitland Place
Baulkham Hills NSW 2153


Project
RESIDENTIAL SUBDIVISION

SITE SECTION SHEET 5 16.10.23 JUN 22 AS SHOWN

	YRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserve used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.	ved. It must		CALE 1:200 (CALE 1:400 (8 12 16 20 metres
This drawi	ng has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN					Client
					North	BMN PROPERTIES PTY LTD
С	ISSUE FOR DA	16.10.23	ROB	VG		
В	ISSUE FOR DA	20.01.23	UF	VG		
Α	ISSUE FOR DA	13.12.22	UF	VG		133 ALEXANDER STREET
Issue	Description	Date	Drawn	Approved		CROWS NEST NSW 2065
-1 .0	1cm at full size			,20cm	1	







TYPICAL RETAINING WALL - SECTION (HEIGHT UP TO 8.1m MAX.)

NOT TO SCALE

RETAINING WALL NOTES


- RW1. ALL WORKMANSHIP SHALL COMPLY WITH AS 4679 AND AS 3700.
- RW2. RETAINING WALL FOOTINGS HAVE BEEN DESIGNED FOR AN ALLOWABLE BEARING PRESSURE AS NOTED ON DRAWINGS. THIS FOUNDATION MATERIAL SHALL BE UNIFORM AND BE APPROVED BY THE GEOTECHNICAL ENGINEER PRIOR TO THE PLACEMENT OF ANY FOOTING REINFORCEMENT.
- RW3. TEMPORARY BATTERS TO BE AS PER GEOTECHNICAL ENGINEERS REPORTS.
- RW4. PROVIDE WATERPROOFING MEMBRANES AS REQUIRED BY ARCHITECTURAL SPECIFICATIONS. DESIGN, EXTENT AND CERTIFICATION OF MEMBRANE IS TO BE PROVIDED BY WATERPROOFING SPECIALIST.
- RW5. RETAINING WALLS ARE DESIGNED BASED ON THE ASSUMPTION THAT A FUNCTIONING DRAINAGE SYSTEM IS EFFECTIVE IN REMOVING HYDRAULIC PRESSURE. PROVIDE CONTINUOUS AG DRAINS BEHIND THE ENTIRE EXTENT OF THE RETAINING WALL. THE DRAINAGE SYSTEM IS TO BE DESIGNED FOR LONG TERM PERFORMANCE EQUAL TO THAT OF THE DESIGN LIFE OF THE WALL. THE DESIGN AND DOCUMENTATION OF THIS SYSTEM IS BY OTHERS AND IS TO INCLUDE DETAILS OF CLEANOUT POINTS FOR THE DRAINAGE AND ACCESS / MAINTENANCE POINTS.
- RW6. BACKFILL BEHIND THE WALL IS TO BE CLASSIFIED AS FREE DRAINING GRANULAR MATERIAL. FREE DRAINING GRANULAR MATERIAL SHALL BE A NON-COHESIVE WELL GRADED GRANULAR MATERIAL COMPRISING SOUND STONE PARTICLES WHICH DO NOT BREAK DOWN UNDER COMPACTION WETTING OR EXPOSURE TO AIR. THE MATERIAL PROPERTIES SHALL COMPLY WITH THOSE SPECIFIED IN TABLE BELOW.

FREE DRAINING GRANULAR MATERIAL PROPERTIES					
PROPERTY	LIMIT	VALUE			
STONE SIZE	MAXIMUM	20 mm			
% PASSING 0.15 mm SIEVE	MAXIMUM	5 %			
PLASTICITY INDEX	MAXIMUM	8			

- RW7. PROVIDE GEOTEXTILE SEPARATION LAYER BETWEEN FREE DRAINING GRANULAR MATERIAL AND RETAINED FILL MATERIAL.
- RW8. COMPACTION OF BACKFILL BEHIND WALLS COMPACTION SHALL BE BY MECHANICAL PLATE VIBRATOR TO A MINIMUM OF 100% STANDARD COMPACTION. - BACKFILLING IS NOT TO TAKE PLACE UNTIL APPROVAL HAS BEEN GIVEN BY THE ENGINEER.
- RW9. WHERE EVER POSSIBLE, SURFACE WATER SHALL BE DIRECTED AWAY FROM THE TOP OF THE WALL AND NOT BE ALLOWED TO POND BEHIND THE TOP OF THE WALL OR ENTER THE SUBSURFACE DRAINAGE SYSTEM.

© COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN BMN PROPERTIES PTY LTD ISSUE FOR DA 16.10.23 ROB VG ISSUE FOR DA 20.01.23 UF VG 13.12.22 UF ISSUE FOR DA VG 133 ALEXANDER STREET CROWS NEST NSW 2065 Issue Description Date Drawn Approved



ACOR Consultants Pty Ltd
Unit 10, Level 1, No.1 Maitland Place

Project
RESIDENTIAL SUBDIVISION


Baulkham Hills NSW 2153 T +61 2 9634 6311


NOT FOR CONSTRUCTION **RETAINING WALL**

NOTES AND DETAILS

NOT TO SCALE RT 16.10.23 NOV 22

4 FOREST ROAD WARRIEWOOD, NSW 2102





VG

133 ALEXANDER STREET CROWS NEST NSW 2065

20.01.23 UF

13.12.22 UF

Date Drawn Approved

ISSUE FOR DA

ISSUE FOR DA

Issue Description

NOT FOR CONSTRUCTION


CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS


4 FOREST ROAD WARRIEWOOD, NSW 2102


T +61 2 9634 6311


ROAD DESIGN LONGITUDINAL SECTIONS SHEET 1

16.10.23 AS SHOWN JUN 22 C5.201









FILTER MEDIA SPECIFICATION:

THE FILTER MEDIA SHALL BE IN ACCORDANCE WITH THE FOLLOWING:

- pH BETWEEN 5.5 TO 7.5
- 2. ELECTRICAL CONDUCTIVITY (EC) < 1.2 dS/m
- 3. ORGANIC MATTER CONTENT < 5% w/w 4. ORTHOPHOSPHATE CONTENT =< 40 mg/kg
- TOTAL NITROGEN CONTENT = 400 mg/kg
- 6. TOTAL SILT & CLAY CONTENT (<0.05mm) < 3% w/w
- 7. MINIMUM HYDRAULIC CONDUCTIVITY AS DEFINED BY ASTM F1815-06 OF 200mm/h (ACTUAL, NOT PREDICTED)
- 8. MAXIMUM HYDRAULIC CONDUCTIVITY AS DEFINED BY ASTM F1815-06 OF 400mm/h (ACTUAL, NOT PREDICTED).

THE FILTER MEDIA SHALL BE WELL GRADED AND GENERALLY BE A LOAMY SAND AND BE FREE OF CONTAMINANTS SUCH AS RUBBISH, DELETERIOUS MATERIAL, TOXICANTS, DECLARED PLANTS AND WEEDS AND SHOULD NOT BE HYDROPHOBIC.

THE COARSE SAND TRANSITION LAYER SHALL BE OF A CLEAN WELL GRADED SAND/COARSE SAND MATERIAL CONTAINING LITTLE OR NO FINES.

THE DRAINAGE LAYER SHALL BE OF A CLEAN FINE GRAVEL CONSISTED OF 5-7 mm WASHED SCREENINGS.


BIO-RETENTION PLANTING PLAN:


ALL BATTER SLOPES ARE TO BE TURFED.

BIO-RETENTION BASIN FILTER MEDIA IS TO BE PLANTED OUT AT 5 PLANTS/ m² WITH SPECIES FROM THE FOLLOWING MIX:

- BAUMEA JUNCEA
- CAREX APPRESSA CAREX FASCICULARIS
- CYPERUS EXALTATUS CAREX POLYSTACHYUS GAHNIA SIEBERANA
- JUNCUS PRISMATOCARPUS JUNCUS USITATUS
- LOMANDRA LONGIFOLIA
- PASPALUM DISTICHUM SCHOENUS BREVIFOLIUS

FLUSHING POINTS TO BE PROVIDED AT END OF EVERY SUBSOIL DRAINAGE LINE






©COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN

BMN PROPERTIES PTY LTD ISSUE FOR DA 16.10.23 ROB ISSUE FOR DA 20.01.23 UF ISSUE FOR DA 13.12.22 UF 133 ALEXANDER STREET CROWS NEST NSW 2065 Date Drawn Approved Issue Description




Baulkham Hills NSW 2153 T +61 2 9634 6311 4 FOREST ROAD WARRIEWOOD, NSW 2102

ACOR Consultants Pty Ltd
Unit 10, Level 1, No.1 Maitland Place

Project
RESIDENTIAL SUBDIVISION

STORMWATER MANAGEMENT DETAILS


SHEET 2 16.10.23 **JUN 22** AS SHOWN



OCEANSAVE DESIGN TABLE

TO BE INSTALLED ONLINE THE TOTAL INLET PIPE FLOW RATE MUST BE LESS THAN THE SPECIFIED UNITS LISTED MAXIMUM TOTAL FLOW RATE; THE UNIT MUST BE PLACED OFFLINE WHERE THE INLET FLOW RATE EXCEEDS THIS VALUE.

TREATABLE FLOWRATE [L/s]	68
MAXIMUM TOTAL FLOWRATE [L/s]	368
WEIR HEIGHT [mm]	400



SITE SPECIFIC DATA REQUIREMENTS

TOTAL FLOWRATE THROUGH INLET [L/\$]

PIPE DATA:	I.L.	MA	TERIAL	DIAMET	ER
INLET PIPE	[][]	[]
OUTLET PIPE][]]
UPPER TANK WEI	7	ГВА			
LOWER TANK WE	IGHT		7	ГВА	

NOTE: TANK SUPPLIED IN TWO PARTS; PARTS A & B TO BE JOINED ON SITE

GENERAL NOTES

- 1. OCEANSAVE WATER QUALITY STRUCTURE SHALL BE IN ACCORDANCE WITH ALL DESIGN DATA AND INFORMATION CONTAINED IN THIS DRAWING. CONTRACTOR TO CONFIRM STRUCTURE MEETS REQUIREMENTS OF THE PROJECT.
- 2. PRECAST STRUCTURE SUPPLIED WITH CORE HOLES TO SUIT OUTER DIAMETER OF NOMINATED PIPE SIZE / MATERIAL.
- 3. PRECAST STRUCTURE SHALL MEET W80 WHEEL LOAD RATING ASSUMING A MAXIMUM EARTH COVER OF 2.0m AND A GROUND WATER ELEVATION AT, OR BELOW, THE OUTLET PIPE INVERT ELEVATION. ENGINEER TO CONFIRM ACTUAL GROUNDWATER ELEVATION.PRECAST STRUCTURE SHALL BE IN ACCORDANCE WITH AS3600.
- 4. ALL WATER QUALITY TREATMENT DEVICES REQUIRE PERIODIC MAINTENANCE. REFER TO OPERATION AND MAINTENANCE MANUAL FOR GUIDELINES AND ACCESS REQUIREMENTS.
- 5. SITE SPECIFIC PRODUCTION DRAWING WILL BE PROVIDED ON PLACEMENT OF ORDER.
- 6. DRAWING NOT TO SCALE.

INSTALLATION NOTES


- A. ANY SUB-BASE, BACKFILL DEPTH, AND/OR ANTI-FLOTATION PROVISIONS ARE SITE SPECIFIC DESIGN CONSIDERATION AND SHALL BE SPECIFIED BY THE SITE CIVIL ENGINEER.
- B. CONTRACTOR TO PROVIDE ALL EQUIPMENT WITH SUFFICIENT LIFTING AND REACH CAPACITY TO LIFT AND SET THE STRUCTURE (LIFTING DETAIL PROVIDED SEPARATELY).
- C. CONTRACTOR TO INSTALL AND LEVEL THE STRUCTURE, APPLY SEALANT TO ALL JOINTS AND TO PROVIDE, INSTALL AND GROUT INLET AND OUTLET PIPES.
- D. CONTRACTOR TO TAKE APPROPRIATE MEASURES TO PROTECT SCREEN & SEPARATION CYLINDER COMPONENTS DURING INSTALLATION



OCEAN PROTECT OCEANSAVE 0809 SPECIFICATION DRAWING

©COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN BMN PROPERTIES PTY LTD ISSUE FOR DA 16.10.23 ROB ISSUE FOR DA 20.01.23 UF ISSUE FOR DA 13.12.22 UF 133 ALEXANDER STREET CROWS NEST NSW 2065 Date Drawn Approved Issue Description



ACOR Consultants Pty Ltd
Unit 10, Level 1, No.1 Maitland Place


Project
RESIDENTIAL SUBDIVISION


Baulkham Hills NSW 2153 T +61 2 9634 6311

NOT FOR CONSTRUCTION STORMWATER MANAGEMENT DETAILS

4 FOREST ROAD WARRIEWOOD, NSW 2102

SHEET 3 16.10.23 **JUN 22** NOT TO SCALE





VELOCITY (m/s) PIPE FLOW (m3/s) ≪ 0 → PIPE GRADE (%) **←** 1.10 → Ø375 RCP Class 2 Ø375 Ø375 PIPE SIZE (mm) RCP Class 2 RCP Class 2 PIPE CLASS LENGTH (m) **←** 2.44 **→ ←** 6.82 → 12.00 5.00 DATUM R.L. 12.00 HYDRAULIC GRADE LINE 28.14 28.13 27.87 DEPTH TO INVERT 3.09 FROM DESIGN SURFACE INVERT LEVEL 27.22 27.05 26.91 27.46 19.91 19.89 19.37 DESIGN SURFACE LEVEL 23.00 29.01 2 EXISTING SURFACE LEVEL 29.01 23.00 CHAINAGE -1.81 0.00 0.00 0.00 LINE 12 LINE DR-09 LINE DR-EX

© COPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must

16.10.23 ROB

20.01.23 UF

13.12.22 UF

Date Drawn Approved

VG

VG

VG

not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN

С

Issue Description

ISSUE FOR DA

ISSUE FOR DA

ISSUE FOR DA

01\5

DR-EX)1 DR-EX)2

HGL SHOWN IS 5% AEP

12\1

CONSULTANTS ENGINEERS | MANAGERS | INFRASTRUCTURE PLANNERS | DEVELOPMENT CONSULTANTS

BMN PROPERTIES PTY LTD

133 ALEXANDER STREET CROWS NEST NSW 2065

T +61 2 9634 6311

Unit 10, Level 1, No.1 Maitland Place
Baulkham Hills NSW 2153

Project
RESIDENTIAL SUBDIVISION

Drawing Title
STORMWATER MANAGEMENT

NOT FOR CONSTRUCTION

16.10.23


DINAL SECTIONS AS SHOWN

	DRAINAGE L	
	SHEET 3	
	Drawn	Date
Γ ROAD	UF	JUN 22

4 FOREST ROAD WARRIEWOOD, NSW 2102		

4 FOREST ROAD
4 I ONLO I NOAD
WARRIEWOOD, NSW 2102
WARRICK COD, NOW 2102

OREST ROAD	
ARRIEWOOD, NSW 2102	
, -	



EROSION AND SEDIMENT CONTROL NOTES

GENERAL INSTRUCTIONS

- THIS SOIL AND WATER MANAGEMENT PLAN IS TO BE READ IN CONJUNCTION WITH OTHER ENGINEERING PLANS RELATING TO THIS DEVELOPMENT.
- CONTRACTORS WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE UNDERTAKEN AS INSTRUCTED IN THIS SPECIFICATION AND CONSTRUCTED FOLLOWING THE GUIDELINES OF "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION", DEPT OF HOUSING, (BLUE BOOK) 14TH EDITION.
- ALL SUBCONTRACTORS WILL BE INFORMED OF THEIR RESPONSIBILITIES IN REDUCING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE AREAS.

LAND DISTURBANCE INSTRUCTIONS

- DISTURBANCE TO BE NO FURTHER THAN 5 (PREFERABLY 2) METRES FROM THE EDGE OF ANY ESSENTIAL ENGINEERING ACTIVITY AS SHOWN ON APPROVED PLANS. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE ZONES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- ACCESS AREAS ARE TO BE LIMITED TO A MAXIMUM WIDTH OF 10 METRES THE SITE MANAGER WILL DETERMINE AND MARK THE LOCATION OF THESE ZONES ON-SITE. ALL SITE WORKERS WILL CLEARLY RECOGNISE THESE BOUNDARIES THAT, WHERE APPROPRIATE, ARE IDENTIFIED WITH BARRIER FENCING (UPSLOPE) AND SEDIMENT FENCING (DOWNSLOPE) OR SIMILAR MATERIALS.
- ENTRY TO LANDS NOT REQUIRED FOR CONSTRUCTION OR ACCESS IS PROHIBITED EXCEPT FOR ESSENTIAL THINNING OF PLANT GROWTH.
- WORKS ARE TO PROCEED IN THE FOLLOWING SEQUENCE:
- a. INSTALL ALL BARRIER AND SEDIMENT FENCING WHERE SHOWN ON THE PLAN.
- b. CONSTRUCT THE STABILISED SITE ACCESS.
- CONSTRUCT DIVERSION DRAINS AS REQUIRED.
- d. INSTALL MESH AND GRAVEL INLETS FOR ANY ADJACENT KERB INLETS.
- INSTALL GEOTEXTILE INLET FILTERS AROUND ANY ON-SITE DROP INLET PITS.
- UNDERTAKE ALL ESSENTIAL CONSTRUCTION WORKS ENSURING THAT ROOF AND/OR PAVED AREA STORMWATER SYSTEMS ARE CONNECTED TO PERMANENT DRAINAGE AS SOON AS PRACTICABLE.

CLEAR SITE AND STRIP AND STOCKPILE TOPSOIL IN LOCATIONS SHOWN ON THE PLAN.

- h. GRADE LOT AREAS TO FINAL GRADES AND APPLY PERMANENT STABILISATION (LANDSCAPING) WITHIN 20 DAYS OF COMPLETION OF CONSTRUCTION WORKS. REMOVE TEMPORARY EROSION CONTROL MEASURES AFTER THE PERMANENT LANDSCAPING HAS BEEN COMPLETED.
- ENSURE THAT SLOPE LENGTHS DO NOT EXCEED 80 METRES WHERE PRACTICABLE. SLOPE LENGTHS ARE DETERMINED BY SILTATION FENCING AND CATCH DRAIN SPACING. 6. ON COMPLETION OF MAJOR WORKS LEAVE DISTURBED LANDS WITH A SCARIFIED SURFACE TO ENCOURAGE WATER INFILTRATION AND ASSIST WITH KEYING TOPSOIL LATER.
- CONTRACTOR TO MANAGE THE ALIGNMENT OF CATCH DRAINS ON SITE AND TO ENSURE THAT CATCH DRAINS INTERCEPT THE SITE SURFACE RUNOFF AND DIRECT THE RUNOFF TOWARDS THE SEDIMENTATION BASINS.

SITE INSPECTION AND MAINTENANCE INSTRUCTIONS

- THE SITE SUPERINTENDENT WILL INSPECT THE SITE AT LEAST WEEKLY AND AT THE CONCLUSION OF EVERY STORM EVENT TO:
- a. ENSURE THAT DRAINS OPERATE PROPERLY AND TO EFFECT ANY NECESSARY REPAIRS
- REMOVE SPILLED SAND OR OTHER MATERIALS FROM HAZARD AREAS, INCLUDING LANDS CLOSER THAN 5 METRES FROM AREAS OF LIKELY CONCENTRATED OR HIGH VELOCITY FLOWS ESPECIALLY WATERWAYS AND PAVED AREAS.
- REMOVE TRAPPED SEDIMENT WHENEVER THE DESIGN CAPACITY OF THAT STRUCTURE HAS BEEN EXCEEDED.
- d. ENSURE REHABILITATED LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD AND TO INITIATE UPGRADING OR REPAIR AS NECESSARY.
- CONSTRUCT ADDITIONAL EROSION AND/OR SEDIMENT CONTROL WORKS AS MIGHT BECOME NECESSARY TO ENSURE THE DESIRED PROTECTION IS GIVEN TO DOWNSLOPE LANDS AND WATERWAYS. MAKE ONGOING CHANGES TO THE PLAN WHERE IT PROVES INADEQUATE IN PRACTICE OR IS SUBJECTED TO CHANGES IN CONDITIONS ON THE WORK-SITE OR ELSEWHERE IN THE CATCHMENT.
- MAINTAIN EROSION AND SEDIMENT CONTROL STRUCTURES IN A FULLY FUNCTIONING CONDITION UNTIL ALL EARTHWORK ACTIVITIES ARE COMPLETED AND THE SITE IS REHABILITATED.
- 2. THE SITE SUPERINTENDENT WILL KEEP A LOGBOOK MAKING ENTRIES AT LEAST WEEKLY, IMMEDIATELY BEFORE FORECAST RAIN AND AFTER RAINFALL. ENTRIES WILL INCLUDE:
- a. THE VOLUME AND INTENSITY OF ANY RAINFALL EVENTS.
- b. THE CONDITION OF ANY SOIL AND WATER MANAGEMENT WORKS.
- c. THE CONDITION OF VEGETATION AND ANY NEED TO IRRIGATE. d. THE NEED FOR DUST PREVENTION STRATEGIES.
- e. ANY REMEDIAL WORKS TO BE UNDERTAKEN. THE LOGBOOK WILL BE KEPT ON-SITE AND MADE AVAILABLE TO ANY AUTHORISED PERSON UPON REQUEST. IT WILL BE GIVEN TO THE PROJECT MANAGER AT THE CONCLUSION OF THE WORKS.

EROSION AND SEDIMENT CONTROL NOTES

SEDIMENT CONTROL INSTRUCTIONS

- SEDIMENT FENCES WILL BE INSTALLED AS SHOWN ON THE PLAN AND ELSEWHERE AT THE DISCRETION OF THE SITE SUPERINTENDENT TO CONTAIN SOIL AS NEAR AS POSSIBLE TO THEIR SOURCE.
- SEDIMENT FENCES WILL NOT HAVE CATCHMENT AREAS EXCEEDING 900 SQUARE METRES AND HAVE A STORAGE DEPTH OF AT LEAST 0.6 METRES.
- SEDIMENT REMOVED FROM ANY TRAPPING DEVICES WILL BE RELOCATED WHERE FURTHER POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS CANNOT OCCUR.
- 4. STOCKPILES ARE NOT TO BE LOCATED WITHIN 5 METRES OF HAZARD AREAS INCLUDING AREAS OF HIGH VELOCITY FLOWS SUCH AS WATERWAYS. PAVED AREAS AND DRIVEWAYS.
- WATER WILL BE PREVENTED FROM DIRECTLY ENTERING THE PERMANENT DRAINAGE SYSTEM UNLESS THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/OR WATER HAS BEEN TREATED BY AN APPROVED DEVICE. 6. TEMPORARY SEDIMENT TRAPS WILL REMAIN IN PLACE UNTIL AFTER THE LANDS THEY ARE PROTECTING ARE COMPLETELY REHABILITATED.
- ACCESS TO SITES SHOULD BE STABILISED TO REDUCE THE LIKELIHOOD OF VEHICLES TRACKING SOIL MATERIALS ONTO PUBLIC ROADS AND ENSURE ALL-WEATHER ENTRY/EXIT.

SOIL EROSION CONTROL INSTRUCTIONS


- EARTH BATTERS WILL BE CONSTRUCTED WITH AS LOW A GRADIENT AS PRACTICABLE BUT NO STEEPER, UNLESS OTHERWISE NOTED, THAN:
- a. 2(H):1(V) WHERE SLOPE LENGTH LESS THAN 12 METRES
- b. 2.5(H):1(V) WHERE SLOPE LENGTH BETWEEN 12 AND 16 METRES.
- c. 3(H):1(V) WHERE SLOPE LENGTH BETWEEN 16 AND 20 METRES.
- d. 4(H):1(V) WHERE SLOPE LENGTH GREATER THAN 20 METRES.
- ALL WATERWAYS, DRAINS, SPILLWAYS AND THEIR OUTLETS WILL BE CONSTRUCTED TO BE STABLE IN AT LEAST THE 1:20 YEAR ARI, TIME OF CONCENTRATION STORM EVENT.
- WATERWAYS AND OTHER AREAS SUBJECT TO CONCENTRATED FLOWS AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUNDCOVER C-FACTOR OF 0.05 (70% GROUND COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION. FLOW VELOCITIES ARE TO BE LIMITED TO THOSE SHOWN IN TABLE 5-1 OF "MANAGING URBAN STORMWATER -SOILS AND CONSTRUCTION", DEPT OF HOUSING 1998 (BLUE BOOK), FOOT AND VEHICULAR TRAFFIC WILL BE PROHIBITED IN THESE AREAS.
- STOCKPILES AFTER CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.1 (60% GROUND-COVER) WITHIN 10 WORKING DAYS FROM COMPLETION OF FORMATION.
- 5. ALL LANDS, INCLUDING WATERWAYS AND STOCKPILES, DURING CONSTRUCTION ARE TO HAVE A MAXIMUM GROUND-COVER C-FACTOR OF 0.15 (50% GROUND COVER) WITHIN 20 WORKING DAYS FROM INACTIVITY EVEN THOUGH WORKS MAY CONTINUE LATER.
- FOR AREAS OF SHEET FLOW USE THE FOLLOWING GROUND COVER PLANT SPECIES FOR TEMPORARY COVER: JAPANESE MILLET 20 KG/HA AND OATS 20 KG/HA.
- PERMANENT REHABILITATION OF LANDS AFTER CONSTRUCTION WILL ACHIEVE A GROUND-COVER C-FACTOR OF LESS THAN 0.1 AND LESS THAN 0.05 WITHIN 60 DAYS. NEWLY PLANTED LANDS WILL BE WATERED REGULARLY UNTIL AN EFFECTIVE COVER IS ESTABLISHED AND PLANTS ARE GROWING VIGOROUSLY. FOLLOW-UP SEED AND FERTILISER WILL BE APPLIED AS NECESSARY.
- RE-VEGETATION SHOULD BE AIMED AT RE-ESTABLISHING NATURAL SPECIES. NATURAL SURFACE SOILS SHOULD BE REPLACED AND NON-PERSISTANT ANNUAL COVER CROPS SHOULD BE USED.

WASTE CONTROL INSTRUCTIONS


- ACCEPTABLE BINS WILL BE PROVIDED FOR ANY CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHING, LIGHTWEIGHT WASTE MATERIALS AND LITTER. CLEARANCE SERVICES WILL BE PROVIDED AT LEAST WEEKLY. DISPOSAL OF WASTE WILL BE IN A MANNER APPROVED BT THE SITE SUPERINTENDENT.
- 2. ALL POSSIBLE POLLUTANT MATERIALS ARE TO BE STORED WELL CLEAR OF ANY POORLY DRAINED AREAS, FLOOD PRONE AREAS, STREAMBANKS, CHANNELS AND STORMWATER DRAINAGE AREAS. STORE SUCH MATERIALS IN A DESIGNATED AREA UNDER COVER WHERE POSSIBLE AND WITHIN CONTAINMENT BUNDS.
- 3. ALL SITE STAFF AND SUB-CONTACTORS ARE TO BE INFORMED OF THEIR OBLIGATION TO USE WASTE CONTROL FACILITIES PROVIDED.
- 4. ANY DE-WATERING ACTIVITIES ARE TO BE CLOSELY MONITORED TO ENSURE THAT WATER IS NOT POLLUTED BY SEDIMENT. TOXIC MATERIALS OR PETROLEUM PRODUCTS.
- PROVIDE DESIGNATED VEHICULAR WASHDOWN AND MAINTENANCE AREAS WHICH ARE TO HAVE CONTAINMENT BUNDS.

PREVIOUSLY LAID STRAW BALE STAKES DRIVEN 0.6M INTO THE GROUND DISTURBED AREA UNDISTURBED AREA 0.1m DEEP STRAW BALE SEDIMENT FILTER (ALTERNATE)


ANGLE FIRST STAKE TOWARDS




TEMPORARY CONSTRUCTION EXIT




GEOTEXTILE FILTER FABRIC DROP **INLET SEDIMENT TRAP**



SANDBAG KERB INLET SEDIMENT TRAP





GAP BETWEEN BAGS ACT AS SPILLWAY RUNOFF RUNOFF THREE LAYERS OF SANDBAGS WITH ENDS OVERLAPPE

SANDBAG SEDIMENT TRAP - AT OTHER THAN KERB SAG PIT

SANDBAG SEDIMENT TRAP DETAILS

EROSION AND SEDIMENT CONTROL NOTES


IMPORTANT NOTES:

- 1. THIS DRAWINGS IS FOR GUIDANCE PURPOSES ONLY THE SOIL AND EROSION CONTROLS ARE INDICATIVE AND REMAIN SUBJECT TO CONSTRUCTION METHODOLOGY - THE CONTRACTOR SHALL AT ALL TIMES REMAIN RESPONSIBLE FOR COMPLIANCE WITH ALL LAWS AND REGULATIONS PERTAINING TO SAFETY AND PROTECTION OF ENVIRONMENT
- 2. ALL SOIL AND EROSION CONTROLS TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH COUNCIL GUIDELINES AND CONDITIONS. ALL WORK TO BE IMPLEMENTED TO THE NSW "BLUE BOOK": MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION - VOLUME 14TH EDITION.
- 3. CONTRACTOR TO ENSURE THAT SEDIMENT IS NOT ALLOWED TO ENTER ADJACENT LOTS TO DOWNSTREAM STORMWATER SYSTEMS OR ANY PUBLIC ROAD OR ROAD RELATED AREA. ANY DAMAGE WHATSOEVER CAUSED THROUGH BREACH OF THIS CONDITION BY THE CONTRACTOR SHALL BE RECTIFIED SOLELY AT THE CONTRACTORS COST
- 4. THE CONTRACTOR IS TO REMOVE ANY SEDIMENT DEPOSITS OUTSIDE THE SITE BY THE END OF EACH WORKING DAY BY VACUUM SWEEPER TRUCKS.
- WHOLE OF SITE TO BE REVEGETATED WITH HYDROMULCH WITHIN FIVE DAYS OF REACHING FSL AND COMPLETION OF TRENCH WORKS TO "MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION VOL. 1" REQUIREMENTS.

CCOPYRIGHT of this design and plan is the property of ACOR Consultants Pty Ltd, ACN 079 306 246 ABN 40 079 306 246, all rights reserved. It must

not be used, modified, reproduced or copied wholly or in part without written permission from ACOR Consultants Pty Ltd.

This drawing has been assigned an electronic code that signifies the drawing has been checked and approved by: RAYMOND TAN **BMN PROPERTIES PTY LTD** ISSUE FOR DA 16.10.23 ROB VG ISSUE FOR DA 20.01.23 UF ISSUE FOR DA 13.12.22 UF 133 ALEXANDER STREET **CROWS NEST NSW 2065** Date Drawn Approved Description



ACOR Consultants Ptv Ltd | Project Unit 10, Level 1, No.1 Maitland Place | RESIDENTIAL SUBDIVISION

Baulkham Hills NSW 2153 T +61 2 9634 6311 (A) (A) (A)

4 FOREST ROAD VARRIEWOOD, NSW 2102

NOT FOR CONSTRUCTION

NOTES AND DETAILS

SOIL EROSION AND SEDIMENT CONTROL PLAN

JUN 22 NOT TO SCALE 16.10.23 C8.101