Pacific Pools Pty Ltd ABN 52 067 579 195 Builders License No 62686C 84 Third Road, Berkshire Park NSW 2765 Ph: 02 4572 5822 Fax: 02 4572 5199 Email: info@pacificpools.com.au www.pacificpools.com.au



STATEMENT OF ENVIRONMENTAL EFFECTS

Construction of a Concrete Swimming Pool at:

173 Wallumatta Road Newport NSW 2016 Lot Number: 200 DP Number: 13457

The above property – 173 Wallumatta Road, Newport is the subject property for the development application for the construction of an inground concrete swimming pool. The land is zoned E4 Environmental living and is used as such with an existing residential dwelling.

Compliance with Statutory & Council Code Requirements

The proposed pool will be built in accordance with the relevant Australian Standards and Council Codes in all aspects of construction and design.

Pool Position, Privacy & Views

The pool is situated at the back of the property behind the house. The pool is situated in between the house and 5.9m from the rear boundary fence which is minimum 1.8m high(to comply to AS1926.1-2012). It is 24.5m from the front boundary,9.3m from the North side boundary and 2m from the South side Boundary. The development is not visible from the street and will not obstruct the view from any street, public place, or reserve, nor will it impact neighboring houses privacy and/or views.

Impact to Existing Trees

The pool is positioned so as to have nil impact on any trees or existing landscaping. There are no tree canopies in the proximity of the excavation and pool position.

Pool Fencing

The pool fence and involved boundary fencing will comply with the Swimming Pool Act 1992 & Australian Standards 1926.1-2012.

Water Overflow & Splashing

Water from the pool will only be splashed on to the lawn.





Filtration

The filtration is positioned to provide little or no impact to the neighbors & will be enclosed as per Australian Standards regulations.

Bushfire

The proposed pool can only be considered an asset in regard to the threat of bushfire in the area. Materials used are noncombustible and the pool will provide a handy water supply for firefighting.

Flora & Fauna

Every precaution will be taken during construction to protect the existing flora and fauna. No plants will be removed, relocation will occur if necessary.

Soil Erosion

There is no evidence of the site being subject to soil erosion. Suitable sediment and erosion measures will be taken to minimize soil leaving the site.

Utility Services

Sydney Water requirements in regard to the filling of Swimming Pools will be met. A permit will be acquired at the required time.

Stormwater Drainage

Any surface water created from hard standing areas will remain on the property. No existing Stormwater drainage will be modified in any way.

Overland Flow

The overland flow will not be disturbed.

Flooding

There is no evidence to indicate that the property is subject to flooding.

Excavation Plan

The proposed development is for the construction of an inground concrete pool. All site and pool plans show the location of the single hole excavation which is the scope of works. There is no further information that could be provided on another document with this title.

Some excavated material shall be taken to a Council approved waste disposal location. And some will remain at the property.



Waste Management - Excavation Material

Some excavated material / clean fill shall be taken to a Council approved waste disposal location, yet to be determined.

Construction Waste Management

Other waste during the construction period will be minimal (ie < 1m3 each) of concrete and paving offcuts, and some plumbing refuse. Contractors shall remove these from site and recycle where possible, otherwise disposing of at an approved waste location, or at our office location into a waste bin provided by Bingo waste services.