
# **ANZAC VILLAGE MONTGOMERY CENTRE** NARRABEEN, NSW



SCALE 1:100

### DRAWING INDEX

GENERAL 241807-TTW-00-DR-CI-00001 241807-TTW-00-DR-CI-00003 241807-TTW-00-DR-CI-00404

SITEWORKS 241807-TTW-00-DR-CI-01101

EROSION AND SEDIMENT CONTROL 241807-TTW-00-DR-CI-02001 241807-TTW-00-DR-CI-02101

STORMWATER 241807-TTW-00-DR-CI-04001 241807-TTW-00-DR-CI-04101

PAVEMENT 241807-TTW-00-DR-CI-07101 241807-TTW-00-DR-CI-07501 241807-TTW-00-DR-CI-07502

0.0	20.0	40.0	60.0	80.0m
1:1000	) A1		1:2	000 A3







ANZAC VILLAGE MONTGOMERY CENTRE NARRABEEN, NSW

GENER COVEF INDEX

This drawing is copyright and is the property of TTW and must not be used without authorisation. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT NOTES AND LEGENDS

COVER SHEET & DRAWING INDEX GENERAL NOTES GENERAL ARRANGEMENT PLAN

SITEWORKS ALIGNMENT CONTROL AND GRADING PLAN

EROSION AND SEDIMENT CONTROL NOTES AND DETAILS EROSION AND SEDIMENT CONTROL PLAN

STORMWATER NOTES AND LEGEND SHEET 1 STORMWATER AND SUBSOIL DRAINAGE PLAN

PAVEMENT PLAN PAVEMENT DETAILS SHEET 1 PAVEMENT DETAILS SHEET 2

## NOT FOR CONSTRUCTION

		Scale at A1	Drawn		Designe	be	Approved	
RAL		1:1000	DA		JH		AH	
R SHEET & DRAWI	NG	Project No	Originator	Zone	Туре	Role	Sheet No	Rev
		T TOJECT NO	Originator	2016	Type	14016	0166(140.	1100
		241807	-TTW	-00-	-DR	-CI-	00001	-A
		16.12.2024	4 4·24 P	М				

#### GENERAL

- CONTRACTOR MUST VERIFY ALL DIMENSIONS AND EXISTING LEVELS ON SITE PRIOR TO COMMENCEMENT OF WORKS. ANY DISCREPANCIES TO BE REPORTED TO THE SUPERI 2 STRIP ALL TOPSOIL FROM THE CONSTRUCTION AREA. ALL STRIPPED TOPSOIL SHALL BE DISPOSED

- STRIP ALL TOPSOIL FROM THE CONSTRUCTION AREA. ALL STRIPPED TOPSOIL SHALL BE DISPOSED OF OFF-SITE UNLESS DIRECTED OTHERWISE. MAKE SMOOTH CONNECTION WITH ALL EXISTING WORKS. COMPACT SUBGRADE UNDER BUILDINGS AND PAVEMENTS TO MINIMUM 98% STANDARD MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.1.1. COMPACTION UNDER BUILDINGS TO EXTEND 2M MINIMUM BEYOND BUILDING FOOTPRINT.
- ALL WORK ON PUBLIC PROPERTY, PROPERTY WHICH IS TO BECOME PUBLIC PROPERTY, OR ANY 5
- ALL WORK ON PUBLIC PROPERTY, PROPERTY WHICH IS TO BECOME PUBLIC PROPERTY, OR ANY WORK WHICH IS TO COME UNDER THE CONTROL OF THE STATUTORY AUTHORITY; THE CONTRACTOR IS TO ENSURE THAT THE DRAWINGS USED FOR CONSTRUCTION HAVE BEEN APPROVED BY ALL RELEVANT AUTHORITIES PRIOR TO COMMENCEMENT SITE. ALL WORK ON PUBLIC PROPERTY, PROPERTY WHICH IS TO BECOME PUBLIC PROPERTY, OR ANY WORK WHICH IS TO COME UNDER THE CONTROL OF THE STATUTORY AUTHORITY IS TO BE CARRIED OUT IN ACCORDANCE WITH THE REQUIREMENTS OF THE RELEVANT AUTHORITY. THE CONTRACTOR SHALL OBTAIN THESE REQUIREMENTS FROM THE AUTHORITY. WHERE THE REQUIREMENTS OF THE AUTHORITY ARE DIFFERENT TO THE DRAWINGS AND SPECIFICATIONS, THE PROVIDENT AND THE AUTHORITY ARE DIFFERENT TO THE DRAWINGS AND SPECIFICATIONS.
- THE REQUIREMENTS OF THE AUTHORITY SHALL BE APPLICABLE.
- 7. FOR ALL TEMPORARY BATTERS REFER TO GEOTECHNICAL RECOMMENDATIONS

#### BOUNDARIES AND EASEMENTS

- 1. THE PROPERTY BOUNDARY AND EASEMENT LOCATIONS SHOWN ON TAYLOR THOMSON WHITTING NG'S HAVE BEEN BASED ON SURVEY
- TAYLOR THOMSON WHITTING MAKES NO GUARANTEES THAT THE BOUNDARY OR EASEMEN INFORMATION SHOWN IS CORRECT. TAYLOR THOMSON WHITTING WILL ACCEPT NO LIABILITIES FOR BOUNDARY INACCURACIES. THE CONTRACTOR/BUILDER IS ADVISED TO CHECK/CONFIRM ALL BOUNDARIES IN RELATION TO ALL PROPOSED WORK PRIOR TO THE COMMENCEMENT OF CONSTRUCTION. BOUNDARY INACCURACIES FOUND ARE TO BE REPORTED TO THE SUPERINTENDENT PRIOR TO CONSTRUCTION STARTING.

#### REFERENCE DRAWINGS

THESE DRAWINGS HAVE BEEN BASED FROM, AND TO BE READ IN CONJUNCTION WITH THE FOLLOWING CONSULTANTS DRAWINGS. ANY CONFLICT TO THE DRAWINGS MUST BE NOTIFIED IMMEDIATELY TO THE ENGINEER.

CONSULTANT	DRAWING TITLE	DRAWING NUMBER	REVISION	DATE
McNally Architects	Proposed Site Plan	A100	01	5/12/2024
Bee & Lethbridge	Survey	15445	00	March 2018

#### SURVEY

#### ORIGIN OF LEVELS DATUM OF LEVELS COORDINATE SYSTEM

- AHD Bee & Lethbridge
- TAYLOR THOMSON WHITTING DOES NOT GUARANTEE THAT THE SURVEY INFORMATION SHOWN ON THESE DRAWINGS IS ACCURATE AND WILL ACCEPT NO LIABILITY FOR ANY INACCURACIES IN THE SURVEY INFORMATION PROVIDED TO US FROM ANY CAUSE WHATSOEVER.

#### SITE WORKS

- ALL BASECOURSE MATERIAL TO COMPLY WITH RMS SPECIFICATION NO 3051 AND COMPACTED TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. ALL TRENCH BACKFILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT
- 2.
- ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACKFILLED WITH AN 3. APPROVED SELECT MATERIAL AND COMPACTED TO A MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1

#### UNDERGROUND SERVICES - WARNING

- THE LOCATIONS OF UNDERGROUND SERVICES SHOWN ON TAYLOR THOMSON WHITTINGS DRAWINGS HAVE BEEN PLOTTED FROM DIAGRAMS PROVIDED BY SERVICE AUTHORITIES. THIS
- DRAWINGS HAVE BEEN PLOTTED FROM DIAGRAMS PROVIDED BY SERVICE AUTHORITIES. THIS INFORMATION HAS BEEN PREPARED SOLELY FOR THE AUTHORITIES OWN USE AND MAY NOT NECESSARILY BE UPDATED OR ACCURATE. THE POSITION OF SERVICES AS RECORDED BY THE AUTHORITY AT THE TIME OF INSTALLATION MAY NOT REFLECT CHANGES IN THE PHYSICAL ENVIRONMENT SUBSEQUENT TO INSTALLATION. THE CONTRACTOR MUST CONFIRM THE EXACT LOCATION AND EXTENT OF SERVICES PRIOR TO CONSTRUCTION AND NOTIFY ANY CONFLICT WITH THE DRAWINGS IMMEDIATELY TO THE ENCINCERGUIDED WITHON FUT 3
- ENGINEER/SUPERINTENDENT THE CONTRACTOR IS TO GET APPROVAL FROM THE RELEVANT STATE SURVEY DEPARTMENT. TO
- THE CONTRACTOR IS TO GE APPROVAL FROM THE RELEVANT STATE SURVEY DEPARTMENT, TO REMOVE/ADJUST ANY SURVEY MARK. THIS INCLUDES BUT IS NOT LIMITED TO; STATE SURVEY MARKS (SSM), PERMANENT MARKS (PM), CADASTRAL REFERENCE MARKS OR ANY OTHER SURVEY MARK WHICH IS TO BE REMOVED OR ADJUSTED IN ANY WAY. TAYLOR THOMSON WHITTING PLANS DO NOT INDICATE THE PRESENCE OF ANY SURVEY MARK. THE CONTRACTOR IS TO UNDERTAKE THEIR OWN SEARCH.

#### KERBING

A ISSUED FOR DA

Rev Description

#### NCLUDES ALL KERBS, GUTTERS, DISH DRAINS, CROSSINGS AND EDGES.

- ALL KERBS, GUTTERS, DISH DRAINS AND CROSSINGS TO BE CONSTRUCTED ON MINIMUM 75mm GRANULAR BASECOURSE COMPACTED TO MINIMUM 98% MODIFIED MAXIMUM DRY DENSITY IN ACCORDANCE WITH AS 1289 5.2.1. EXPANSION JOINTS (EJ) TO BE FORMED FROM 10mm COMPRESSIBLE CORK FILLER BOARD FOR THE FULL DEPTH OF THE SECTION AND CUT TO PROFILE. EXPANSION JOINTS TO BE LOCATED AT DRAINAGE PITS, ON TANGENT POINTS OF CURVES AND ELSEWHERE AT 12M CENTRES EXCEPT FOR INFORM LEDDOWING THE SUPERIOR OF THE ADDITION TO LOCATIONS ON LADDO INTEGRAL KERBS WHERE THE EXPANSION JOINTS ARE TO MATCH THE JOINT LOCATIONS IN SLABS.
- WEAKENED PLANE, JOINTS TO BE MIN 3mm WIDE AND LOCATED AT 3M CENTRES EXCEPT FOR INTEGRAL KERBS WHERE WEAKENED PLANE JOINTS ARE TO MATCH THE JOINT LOCATIONS IN
- SLABS. 4. BROOMED FINISHED TO ALL RAMPED AND VEHICULAR CROSSINGS, ALL OTHER KERBING OR DISH DRAINS TO BE STEEL FLOAT FINISHED. 5. IN THE REPLACEMENT OF KERBS EXISTING ROAD PAVEMENT IS TO BE SAWCUT 900mm FROM LIP OF GUTTER UPON COMPLETION OF NEW KERBS, NEW BASE CORSE AND SURFACE IS TO BE LAID 900mm WIDE TO MATCH EXISTING MATERIALS AND THICKNESSES. EXISTING ALLOTMENT DRAINAGE PIPES ARE TO BE BUILT INTO THE NEW KERB WITH A 100mm DIA HOLE. EXISTING KERBS ARE TO BE
- COMPLETELY REMOVED WHERE NEW KERBS ARE SHOWN 0.0 20.0 40.0 60.0 80.0m

JH JH 16.12.202

Eng Draft Date Rev Description

#### 1:1000 A1 ·2000 A3

## RETAINING WALLS

- DRAINAGE SHALL BE PROVIDED AS SHOWN ON THE DRAINAGE DRAWINGS. BACKFILLING SHALL BE CARRIED OUT AFTER GROUT OR CONCRETE HAS REACHED A MINIMUM STRENGTH OF 0.85 F/C. BACKFILLING SHALL BE APPROVED GRANULAR MATERIAL COMPACTED IN LAYERS NOT EXCEEDING 200mm TO 95% STANDARD COMPACTION UNLESS NOTED OTHERWISE. PROVIDE WATERPROOFING TO BACK OF WALLS AS SPECIFIED OR NOTED.
- 4. WHERE RETAINING WALLS RELY ON CONNECTING STRUCTURAL ELEMENTS FOR STABILITY, DO NOT BACKFILL AGAINST THE WALL UNLESS IT IS ADEQUATELY PROPPED OR THE ELEMENTS HAVE BEEN CONSTRUCTED AND HAVE SUFFICIENT STRENGTH TO WITHSTAND THE LOADS.
- 5. FOR ALL TEMPORARY BATTERS OBTAIN GEOTECHNICAL ENGINEERS RECOMMENDATIONS.

#### BEFORE YOU DIG AUSTRALIA (BYDA)

- PUBLIC SERVICE UTILITY INFORMATION SHOWN ON PLAN HAS BEEN COMPLIED FROM INFORMATION RECEIVED FROM DIAL BEFORE YOU DIG INQUIRY, REFERENCE NUMBER No.3325120 OBTAINED ON 10.12.2024 UNLESS SPECIFICALLY SHOWN OTHERWISE, THIS LOCATION AND DEPTH
- OF SERVICES SHOWN ON THIS PLAN HAVE NOT BEEN VERIFIED. THE LOCATION OF SERVICES SHOWN ON THIS DRAWING HAVE BEEN PLOTTED AS ACCURATELY AS POSSIBLE FROM DIAGRAMS PROVIDED BY SERVICE AUTHORITIES AND SHOULD BE CONFIRMED BY SITE INSPECTION."

#### CONCRETE

PLACE CONCRETE OF THE FOLLOWING CHARACTERISTIC COMPRESSIVE STRENGTH fc IN ACCORDANCE WITH AS 1379. 2.

LOCATION	f'c MPa (28 DAYS)	SPECIFIED SLUMP	NOMINAL AGG. SIZE
KERBS	S20	80	20
RETAINING WALL FOOTINGS	S40	80	20

- USE TYPE 'GP' CEMENT, UNLESS OTHERWISE SPECIFIED.
- ALL CONCRETE SHALL BE SUBJECT TO PROJECT ASSESSMENT AND TESTING TO AS 1379 CONSOLIDATE BY MECHANICAL VIBRATION. CURE ALL CONCRETE SURFACES AS DIRECTED IN THE
- FOR ALL FALLS IN SLAB, DRIP GROOVES, REGLETS, CHAMFERS ETC. REFER TO ARCHITECTS
- FOR ALL FALLS IN SLAB, UKIP GROUVES, REGLETS, CHAINFERS ETC. REFER TO ARCHITECTS DRAWINGS AND SPECIFICATIONS. UNLESS SHOWN ON THE DRAWINGS, THE LOCATION OF ALL CONSTRUCTION JOINTS SHALL BE SUBMITTED TO ENGINEER FOR REVIEW. NO HOLES OR CHASES SHALL BE MADE IN THE SLAB WITHOUT THE APPROVAL OF THE ENGINEER.
- CONDUITS AND PIPES ARE TO BE FIXED TO THE UNDERSIDE OF THE TOP REINFORCEMENT LAYER.
- 10. SLURRY USED TO LUBRICATE CONCRETE PUMP LINES IS NOT TO BE USED IN ANY STRUCTURAL MEMBERS
- 11. ALL SLABS CAST ON GROUND REQUIRE SAND BLINDING WITH A CONCRETE UNDERLAY

#### CONCRETE FINISHING

- ALL EXPOSED CONCRETE PAVEMENTS ARE TO BE BROOMED FINISHED. ALL EDGES OF THE CONCRETE PAVEMENT INCLUDING KEYED AND DOWELLED JOINTS ARE TO BE FINISHED WITH AN EDGING TOOL.
- 3. CONCRETE PAVEMENTS WITH GRADES GREATER THAN 10 % SHALL BE HEAVILY BROOMED
- CARBORUNDUM TO BE ADDED TO ALL STAIR TREADS AND RAMPED CROSSINGS U.N.O.

#### FORMWORK

Eng Draft Date Rev Description

THE DESIGN, CERTIFICATION, CONSTRUCTION AND PERFORMANCE OF THE FORMWORK, FALSEWORK AND BACKPROPPING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR, PROPOSED METHOD OF INSTALLATION AND REMOVAL OF FORMWORK IS TO BE SUBMITTED TO THE SUPERINTENDENT FOR COMMENT PRIOR TO WORK BEING CARRIED OUT.

#### EROSION AND SEDIMENT CONTROL

- 1. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH:
- I OCAL ALITHORITY REQUIREMENTS
- EPA POLITION CONTROL MANUAL FOR URBAN STORMWATER, LANDCOM NSW MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION ("BLUE BOOK").
- EROSION AND SEDIMENT CONTROL DRAWINGS AND NOTES ARE PROVIDED FOR THE WHOLE OF THE WORKS. SHOULD THE CONTRACTOR STAGE THESE WORKS THEN THE DESIGN MAY BE REQUIRED TO BE MODIFIED. VARIATION TO THESE DETAILS MAY REQUIRE APPROVAL BY THE
- REQUIRED TO BE MODIFIED. VARIATION TO THESE DETAILS MAY REQUIRE APPROVAL BY THE RELEVANT AUTHORITIES. THE EROSION AND SEDIMENT CONTROL PLAN SHALL BE IMPLEMENTED AND ADAPTED TO MEET THE VARYING SITUATIONS AS WORK ON SITE PROGRESSES. MAINTAIN ALL EROSION AND SEDIMENT CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE LOCAL AUTHORITY. WHEN STORMWATER PITS ARE CONSTRUCTED PREVENT SITE RUNOFF ENTERING THE PITS WHI EGO ON FORDER ADD RED FOR THE MODIFIED FOR THE SATISFACTION OF THE SUPERINTERDENT AND THE LOCAL AUTHORITY.
- 3.
- UNLESS SILT FENCES ARE ERECTED AROUND PITS. MINIMISE THE AREA OF SITE BEING DISTURBED AT ANY ONE TIME

Eng Draft Date

- MINIMISE THE AREA OF SITE BEING DISTURBED AT ANY ONE TIME. PROTECT ALL STOCKPILES OF MATERIALS FROM SCOUR AND EROSION. DO NOT STOCKPILE LOOSE MATERIAL IN ROADWAYS, NEAR DRAINAGE PITS OR IN WATERCOURSES. ALL SOIL AND WATER CONTROL MEASURES ARE TO BE PUT BACK IN PLACE AT THE END OF EACH WORKING DAY, AND MODIFIED TO BEST SUIT SITE CONDITIONS. CONTROL WATER FROM UPSTREAM OF THE SITE SUCH THAT IT DOES NOT ENTER THE DISTURBED
- SITE. ALL CONSTRUCTION VEHICLES SHALL ENTER AND EXIT THE SITE VIA THE TEMPORARY
- CONSTRUCTION ENTRY/EXIT. ALL VEHICLES LEAVING THE SITE SHALL BE CLEANED AND INSPECTED BEFORE LEAVING
- MAIL VERICES LEAVING THE STIE OF ALL BE OLEANED AND INSPECTED BEFORE LEAVING.
   MAINTAIN ALL STORMWATER PIPES AND PITS CLEAR OF DEBRIS AND SEDIMENT. INSPECT STORMWATER SYSTEM AND CLEAN OUT AFTER EACH STORM EVENT.
   CLEAN OUT ALL EROSION AND SEDIMENT CONTROL DEVICES AFTER EACH STORM EVENT.

H LifeCare

#### SEQUENCE OF WORKS

- 1. PRIOR TO COMMENCEMENT OF EXCAVATION THE FOLLOWING SOIL MANAGEMENT DEVICES MUST BE INSTALLED.
- CONSTRUCT SILT FENCES BELOW THE SITE AND ACROSS ALL POTENTIAL RUNOFF SITES. CONSTRUCT TEMPORARY CONSTRUCTION ENTRY/EXIT AND DIVERT RUNOFF TO SUITABLE CONTROL SYSTEMS. CONSTRUCT MEASURES TO DIVERT UPSTREAM FLOWS INTO EXISTING STORMWATER SYSTEM. CONSTRUCT SEDIMENTATION TRAPS/BASIN INCLUDING OUTLET CONTROL AND OVERFLOW.

- 1.5. CONSTRUCT TURF LINED SWALES. PROVIDE SANDBAG SEDIMENT TRAPS UPSTREAM OF EXISTING PITS. 1.6.

2. CONSTRUCT GEOTEXTILE FILTER PIT SURROUND AROUND ALL PROPOSED PITS AS THEY ARE CONSTRUCTED

ON COMPLETION OF PAVEMENT PROVIDE SAND BAG KERB INLET SEDIMENT TRAPS AROUND PITS.
 PROVIDE AND MAINTAIN A STRIP OF TURF ON BOTH SIDES OF ALL ROADS AFTER THE CONSTRUCTION OF KERBS.

#### WATER QUALITY TESTING REQUIREMENTS

- 1. PRIOR TO DISCHARGE OF SITE STORMWATER, GROUNDWATER AND SEEPAGE WATER INTO COUNCIL'S STORMWATER SYSTEM, CONTRACTORS MUST UNDERTAKE WATER QUALITY TESTS IN CONJUNCTION WITH A SUITABLY QUALIFIED ENVIRONMENT CONSULTANT OUTLINING THE
- COMPLIANCE WITH THE CRITERIA OF THE AUSTRALIAN AND NEW ZEALAND GUIDELINES FOR FRESH AND MARINE WATER QUALITY (2000) IF REQUIRED SUBJECT TO THE ENVIRONMENTAL CONSULTANTS ADVICE, PROVIDE REMEDIAL
- MEASURES TO IMPROVE THE QUALITY OF WATER THAT IS TO BE DISCHARGED INTO COUNCILS MEASURES TO IMPROVE THE QUALITY OF WATER THAT IS TO BE DISCHARGED INTO COUNCILS STORM WATER DRAINAGE SYSTEM. THIS SHOULD INCLUDE COMMENTS FROM A SUITABLY QUALIFIED ENVIRONMENTAL CONSULTANT CONFIRMING THE SUITABILITY OF THESE REMEDIAL MEASURES TO MANAGE THE WATER DISCHARGED FROM THE SITE INTO COUNCILS STORM WATER DRAINAGE SYSTEM. OUTLINING THE PROPOSED, ONGOING MONITORING, CONTINGENC PLANS AND VALIDATION PROGRAM THAT WILL BE IN PLACE TO CONTINUALLY MONITOR THE IGENCY ..... WATER QUALITY TESTING THAT WILL BE UNDERTAKEN BY A SUITABLY QUALIFIED ENVIRONMENTAL CONSULTANT.

#### SAFETY AND DESIGN

- TAYLOR THOMSON WHITTING (NSW) PTY LTD OPERATES UNDER SAFE WORK AUSTRALIA'S CODE OF CONDUCT FOR THE SAFE DESIGN OF STRUCTURES.
- THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH THE TAYLOR THOMSON WHITTING TRANSFER OF INFORMATION LETTER AND CIVIL RISK AND SOLUTIONS REGISTER.
- 3. UNDER THE CODE OF CONDUCT IT IS THE CLIENT'S RESPONSIBILITY TO PROVIDE A COPY OF THE
- CIVIL RISK AND SOLUTIONS REGISTER TO THE PRINCIPAL CONTRACTOR. IT IS THE PRINCIPAL CONTRACTOR'S RESPONSIBILITY TO REVIEW THE HAZARDS AND RISKS IDENTIFIED DURING THE DESIGN PROCESS TO ENSURE A SAFE WORKPLACE IS MAINTAINED FOR THE CONSTRUCTION, MAINTENANCE AND EVENTUAL DEMOLITION OF THE CIVIL INFRASTRUCTURE.

#### SAFETY IN DESIGN

CONTRACTOR TO REFER TO APPENDIX B OF THE CIVIL SPECIFICATION FOR THE CIVIL RISK AND

4. GROUNDWATER

5. EXCAVATIONS

ENGINEER

REPORT

6. GROUND CONDITIONS

8 CONFINED SPACES

9. MANUAL HANDLING

11. SITE ACCESS/EGRESS

PERSONNEL AND PUBLIC 12. VEHICLE MOVEMENT

VEHICLE MOVEMENTS WHERE NECESSARY

HAZARDOUS MATERIALS

GEOTECHNICAL/ENVIRONMENTAL REPORT

- CONTRACTOR TO BE AWARE EXISTING SERVICES ARE LOCATED WITHIN THE SITE. LOCATION OF ALL SERVICES TO BE VERIFIED BY THE CONTRACTOR PRIOR TO COMMENCING WORKS CONTRACTOR TO CONFIRM WITH RELEVANT AUTHORITY REGARDING MEASURES TO BE TAKEN TO ENSURE SERVICES ARE PROTECTED OR PROCEDURES ARE IN PLACE TO DEMOLISH AND/OR RELOCATE
- 2. EXISTING STRUCTURES CONTRACTOR TO BE AWARE EXISTING STRUCTURES MAY EXIST WITHIN THE SITE. TO PREVENT DAMAGE TO EXISTING STRUCTURE(S) AND/OR PERSONNEL, SITE WORKS TO BE CARRIED OUT AS FAR AS PRACTICABLY POSSIBLE FROM EXISTING STRUCTURE(S).
- 3. EXISTING TREES CONTRACTOR TO BE AWARE EXISTING TREES EXIST WITHIN THE SITE WHICH NEED TO BE PROTECTED. TO PREVENT DAMAGE TO TREES AND/OR PERSONNEL, SITE WORKS TO BE CARRIED OUT AS FAR AS PRACTICABLY POSSIBLE FROM EXISTING TREES. ADVICE NEEDS TO BE SOUGHT FROM ARBORIST AND/OR LANDSCAPE ARCHITECT ON MEASURES REQUIRED TO PROTECT TREES.

CONTRACTOR TO BE AWARE GROUND WATER LEVELS ARE CLOSE TO EXISTING SURFACE LEVEL.

EACAVATIONS DEEP EXCAVATIONS DUE TO STORMWATER DRAINAGE WORKS IS REQUIRED. CONTRACTOR TO ENSURE SAFE WORKING PROCEDURES ARE IN PLACE FOR WORKS. ALL EXCAVATIONS TO BE FENCED OFF AND BATTERS ADEQUATELY SUPPORTED TO APPROVAL OF GEOTECHNICAL

CONTRACTOR TO BE AWARE OF THE SITE GEOTECHNICAL CONDITIONS. REFER TO GEOTECHNICAL

CONTRACTOR TO ENSURE ALL HAZARDOUS MATERIALS ARE IDENTIFIED PRIOR TO COMMENCING WORKS. SAFE WORKING PRACTICES AS PER RELEVANT AUTHORITY TO BE ADOPTED AND

CONFINED SPACES CONTRACTOR TO BE AWARE OF POTENTIAL HAZARDS DUE TO WORKING IN CONFINED SPACES SUCH AS STORMWATER PITS, TRENCHES AND/OR TANKS. CONTRACTOR TO PROVIDE SAFE WORKING METHODS AND USE APPROPRIATE PPE WHEN ENTERING CONFINED SPACES.

CONTRACTOR TO BE AWARE MANUAL HANDLING MAY BE REQUIRED DURING CONSTRUCTION.

CONTRACTOR TO BE AWARE SITE WORKS OCCUR IN CLOSE PROXIMITY TO ECOTPATHS AND ROADWAYS. CONTRACTOR TO ERECT APPROPRIATE BARRIERS AND SIGNAGE TO PROTECT SITE

CONTRACTOR TO SUPPLY AND COMPLY WITH TRAFFIC MANAGEMENT PLAN AND PROVIDE

ADEQUATE SITE TRAFFIC CONTROL INCLUDING A CERTIFIED TRAFFIC MARSHALL TO SUPERVISE

ANZAC VILLAGE

NARRABEEN, NSW

MONTGOMERY CENTRE

AND ASSESSMENTS ARE IN PLACE PRIOR TO COMMENCING WORKS.

CONSTRUCTION WORKS CONTAMINATING THE SURROUNDING ENVIRONMENT

CONTRACTOR TO TAKE APPROPRIATE MEASURES TO ENSURE MANUAL HANDLING PROCEDURES

CONTRACTOR TO ENSURE APPROPRIATE MEASURES ARE TAKEN TO PREVENT POLLUTANTS FROM

EXISTING ASBESTOS PRODUCTS & CONTAMINATED MATERIAL MAY BE PRESENT ON SITE.

APPROPRIATE PPE TO BE USED WHEN HANDLING ALL HAZARDOUS MATERIALS. REFER TO

TEMPORARY DE-WATERING MAY BE REQUIRED DURING CONSTRUCTION WORKS.

#### STORMWATER DRAINAGE

This drawing is copyright and is the property of TTW and must not be used without authorisation. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT NOTES AND LEGENDS

STORMWATER DESIGN CRITERI

- (A) AVERAGE EXCEEDANCE PROBABILITY: -- 1% AEP FOR ROOF DRAINAGE TO FIRST EXTERNAL PIT 5% AEP FOR PAVED AND LANDSCAPED AREAS
- (B) RAINFALL INTENSITIES :
- TIME OF CONCENTRATION: 5 MINUTES 1% AEP = 261 mm/hr 5% AEP = 198 mm/hr

- (C) RAINFALL LOSSES:
- IMPERVIOUS AREAS: IL = 1 mm PERVIOUS AREAS: IL = 41 mm CL = 0 mm/hr CL = 0.72 mm/hr

PIPES 300 DIA AND LARGER TO BE REINFORCED CONCRETE CLASS "-" APPROVED SPIGOT AND

PIPES 300 DIA AND DARGER TO BE REINFORCED CONCRETE CLASS - APPROVED SPIGOT AND SOCKET WITH RUBBER RING JOINTS U.N.O. PIPES UP TO 300 DIA MAY BE SEWER GRADE UPVC WITH SOLVENT WELDED JOINTS, SUBJECT TO APPROVAL BY THE ENGINEER EQUIVALENT STRENGTH VCP OR FRP PIPES MAY BE USED SUBJECT TO APPROVAL.

PRECAST PITS MAY BE USED EXTERNAL TO THE BUILDING SUBJECT TO APPROVAL BY ENGINEER. ENLARGERS, CONNECTIONS AND JUNCTIONS TO BE MANUFACTURED FITTINGS WHERE PIPES ARE LESS THAN 300 DIA WHERE SUBSOIL DRAINS PASS UNDER FLOOR SLABS AND VEHICULAR PAVEMENTS, UNSLOTTED

UPVC SEWER GRADE PIPE IS TO BE USED. GRATES AND COVERS SHALL CONFORM WITH AS 3996-2006, AND AS 1428.1 FOR ACCESS

REQUIREMENTS

 PIPES ARE TO BE INSTALLED IN ACCORDANCE WITH AS 3725. ALL BEDDING TO BE TYPE H2 U.N.O.
 CARE IS TO BE TAKEN WITH INVERT LEVELS OF STORMWATER LINES. GRADES SHOWN ARE NOT TO BE REDUCED WITHOUT APPROVAL

ALL STORMWATER PIPES TO BE 150 DIA AT 1.0% MIN FALL U.N.O.

SUBSOIL DRAINS TO BE SLOTTED FLEXIBLE UPVC U.N.O. ADOPT INVERT LEVELS FOR PIPE INSTALLATION (GRADES SHOWN ARE ONLY NOMINAL).

#### TENDER DOCUMENTATION

THESE DRAWINGS ARE PRELIMINARY DRAWINGS ISSUED FOR TENDER AS AN INDICATION OF THE THESE DRAWINGS ARE PRELIMINARY DRAWINGS ISSUED FOR TENDER AS AN INDICATION OF THE EXTENT OF WORKS ONLY. THEY ARE NOT A COMPLETE CONSTRUCTION SET OF DRAWINGS. TO DETERMINE THE FULL EXTENT OF WORK, THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH THE ARCHITECTURAL DRAWINGS AND OTHER CONTRACT DOCUMENTS. ALLOW FOR ALL ITEMS SHOWN ON ARCHITECTURAL AND OTHER DRAWINGS AS NOT ALL ITEMS ARE SHOWN ON THE STRUCTURAL/CIVIL WORKS DRAWINGS. SHOULD ANY AMBIGUITY, ERROR, OMISSIONS, DISCREPANCY, INCONSISTENCY OR OTHER FAULT EXIST OR SEEM TO EXIST IN THE DOCUMENTS, IMMEDIATELY NOTIFY IN WRITING TO THE SUPERINTENDENT

SUPERINTENDENT

RATES SHOWN ON THE DRAWINGS ARE FOR THE FINAL STRUCTURE/CIVIL WORKS IN PLACE AND DO NOT ALLOW FOR ANY WASTAGE, ROLLING MARGINS, OVER SUPPLY OR FABRICATION REQUIREMENTS. ETC.

#### SIGNS AND LINE MARKING

3.

1 PAVEMENT MARKING AND SIGN POSTING ON PUBLIC ROADS SHALL BE IN ACCORDANCE WITH THE PAVEMENT MARKING AND SIGN POSTING ON PUBLIC ROADS SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS OF THE RELEVANT ROAD AUTHORITY. THE CONTRACTOR SHALL OBTAIN THESE REQUIREMENTS FROM THE ROAD AUTHORITY. PAVEMENT MARKING AND SIGN POSTING TO BE IN ACCORDANCE WITH R.T.A. 'INTERIM GUIDE TO SIGNS AND MARKINGS'. CONTRACTOR IS TO PROVIDE GUIDE POSTS, SPACED IN ACCORDANCE WITH AS1742.2. THEY ARE TO DEFINITE IN HILL ROAD MAIL TO AND GUIDE TO THE AND A THE AND

CONTRACTOR IS OF PROVIDE GUIDE POSTS, SPACED IN ACCORDANCE WITH AST/42.2. THEY ARE TO BE LOCATED NEAR ALL HEAD WALLS AND PIPE OUTLETS. RAISED PAVEMENT MARKERS TO BE IN ACCORDANCE WITH AST742.2 WHERE EXISTING PAVEMENT MARKING CONFLICTS WITH PROPOSED, IT IS TO BE REMOVED. LANE WIDTHS DO NOT INCLUDE WIDTH OF GUTTER. LINE MARKING PLAN DOES NOT DEFINE BOUNDARIES. ERECT TEMPORARY SIGN 'CHANGED TRAFFIC CONDITIONS AHEAD' 120M AHEAD OF NEW WORK IN ROTH DIRECTIONS.


BOTH DIRECTIONS


 ESTABLISH THE LOCATION OF EXISTING UTILITY SERVICES AND LOCATE NEW SIGNS CLEAR OF THESE INSTALLATIONS. 10 THE SLOPED FACE OF THE SE MEDIAN KERBS WHICH ADJOIN THROUGH LANES ARE TO BE

- PAINTED WHITE IN LIEU OF AN 83 EOGE LINE. THE REFLECTIVE PAVEMENT MARKERS NORMALLY ASSOCIATED WHITH AN 83 EDGE LINE ARE TO BE LOCATED ON THE PAVEMENT ADJACENT TO THE
- 11. BICYCLE PAVEMENT MARKINGS AND SIGN POSTING TO BE IN ACCORDANCE WITH AUSTROADS STANDARDS.
- 12. THE DESIGN OF MAJOR DIRECTIONAL SIGN POSTING TO BE PREPARED AND ASSESSED BY THE RELAVENT ROAD AUTHORITY

## NOT FOR CONSTRUCTION

Drawing Title:	Scale at A1	Drawn		Design	ed	Approved	
GENERAL	N.T.S	DA		JH		AH	
NOTES	Project No	Originator	Zone	Туре	Role	Sheet No.	Rev
	241807	7 <del>-</del> TTW	-00-	DR	-CI-	00003	-A
	16.12.202	4 4:24 P	М				





#### EROSION AND SEDIMENT CONTROL NOTES

1. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH:

LOCAL AUTHORITY REQUIREMENTS,

LOCAL AUTHORITY REQUIREMENTS,
 EPA POLLUTION CONTROL MANUAL FOR URBAN STORMWATER,
 LANDCOM NSW - MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION ("BLUE BOOK").
2. EROSION AND SEDIMENT CONTROL DRAWINGS AND NOTES ARE PROVIDED FOR THE WHOLE OF THE
WORKS. SHOULD THE CONTRACTOR STAGE THESE WORKS THEN THE DESIGN MAY BE REQUIRED TO BE
MODIFIED. VARIATION TO THESE DETAILS MAY REQUIRE APPROVAL BY THE RELEVANT AUTHORITIES.
THE EROSION AND SEDIMENT CONTROL PLAN SHALL BE IMPLEMENTED AND ADAPTED TO MEET THE
VARYING SITUATIONS AS WORK ON SITE PROGRESSES.
3. THE EROSION & SEDIMENT CONTROL PLAN SHALL BE IMPLEMENTED AND ADAPTED TO MEET THE
VARYING SITUATIONS AS WORK ON SITE PROGRESSES.
3. THE EROSION & SEDIMENT CONTROL PLAN IS PREPARED FOR INFORMATION & PLANNING APPROVALS
ONLY. THE CONTRACTOR SHALL PREPARE THE CONSTRUCTION EROSION & SEDIMENT CONTROL PLAN
BASED ON THEIR WORKS STAGING & PROPOSED SITE FACILITIES.
4. MAINTAIN ALL EROSION AND SEDIMENT CONTROL PLAN
BASED TO THEIR WORKS STAGING A PREPORED FOR INFORMATION OF THE

4. MAINTAIN ALL EROSION AND SEDIMENT CONTROL DEVICES TO THE SATISFACTION OF THE

4. MAINTAIN ALL EROSION AND SEDIMENT CONTROL DEVICES TO THE SATISFACTION OF THE SUPERINTENDENT AND THE LOCAL AUTHORITY.
5. WHEN STORMWATER PITS ARE CONSTRUCTED PREVENT SITE RUNOFF ENTERING THE PITS UNLESS SILT FENCES ARE ERECTED AROUND PITS.
6. MINIMISE THE AREA OF SITE BEING DISTURBED AT ANY ONE TIME.
7. PROTECT ALL STOCKPILES OF MATERIALS FROM SCOUR AND EROSION. DO NOT STOCKPILE LOOSE MATERIAL IN ROADWAYS, NEAR DRAINAGE PITS OR IN WATERCOURSES.
8.41 SOUL MOUW AND WATER CONTROL MEASURES AND E TO RE DIT RACK IN IL ACE AT THE END OF EACH

8. ALL SOIL AND WATER CONTROL MEASURES ARE TO BE PUT BACK IN PLACE AT THE END OF EACH WORKING DAY, AND MODIFIED TO BEST SUIT SITE CONDITIONS. 9. CONTROL WATER FROM UPSTREAM OF THE SITE SUCH THAT IT DOES NOT ENTER THE DISTURBED

SITE. 10. ALL CONSTRUCTION VEHICLES SHALL ENTER AND EXIT THE SITE VIA THE TEMPORARY

ALL CONSTRUCTION VEHICLES STALL ENTER AND EAT THE STALL VIETHE FEW GRAVET
 ALL CONSTRUCTION ENTRY/VEXIT.
 ALL VEHICLES LEAVING THE SITE SHALL BE CLEANED AND INSPECTED BEFORE LEAVING.
 MAINTAIN ALL STORWARDER PIPES AND PITS CLEAR OF DEBRIS AND SEDIMENT. INSPECT
 STORWARDER SYSTEM AND CLEAN OUT AFTER EACH STORM EVENT.
 CLEAN OUT ALL EROSION AND SEDIMENT CONTROL DEVICES AFTER EACH STORM EVENT.

#### SEQUENCE OF WORKS


PRIOR TO COMMENCEMENT OF EXCAVATION THE FOLLOWING SOIL MANAGEMENT DEVICES MUST BE INSTALLED

- CONSTRUCT SILT FENCES BELOW THE SITE AND ACROSS ALL POTENTIAL RUNOFF SITES. CONSTRUCT TEMPORARY CONSTRUCTION ENTRY/EXIT AND DIVERT RUNOFF TO SUITABLE 1.1. 1.2. CONTROL SYSTEMS.
- CONSTRUCT MEASURES TO DIVERT UPSTREAM FLOWS INTO EXISTING STORMWATER SYSTEM. CONSTRUCT SEDIMENTATION TRAPS/BASIN INCLUDING OUTLET CONTROL AND OVERFLOW. CONSTRUCT TURF LINED SWALES. PROVIDE SANDBAG SEDIMENT TRAPS UPSTREAM OF EXISTING PITS. 1.3. 1.4.
- 1.5. 1.6.

- BACKFILL SOIL

2. CONSTRUCT GEOTEXTILE FILTER PIT SURROUND AROUND ALL PROPOSED PITS AS THEY ARE CONSTRUCTED.


ON COMPLETION OF PAVEMENT PROVIDE SAND BAG KERB INLET SEDIMENT TRAPS AROUND PITS.
 PROVIDE AND MAINTAIN A STRIP OF TURF ON BOTH SIDES OF ALL ROADS AFTER THE CONSTRUCTION OF KERBS.




1.


CRUSHED . . . ... . . . . MAXIMUM)


- PRIOR TO DISCHARGE OF SITE STORMWATER, GROUNDWATER AND SEEPAGE WATER INTO COUNCIL'S STORMWATER SYSTEM, CONTRACTORS MUST UNDERTAKE WATER QUALITY TESTS IN CONJUNCTION WITH A SUITABLY QUALIFIED ENVIRONMENT CONSULTANT OUTLINING THE FOLLOWING: -
- COMPLIANCE WITH THE CRITERIA OF THE AUSTRALIAN AND NEW ZEALAND GUIDELINES FOR FRESH AND MARINE WATER QUALITY (2000) IF REQUIRED SUBJECT TO THE ENVIRONMENTAL CONSULTANTS ADVICE, PROVIDE REMEDIAL MEASURES TO IMPROVE THE QUALITY OF WATER THAT IS TO BE DISCHARGED INTO COUNCILS STORM WATER DRAINAGE SYSTEM THIS SHOULD INCLUDE COMMENTS FROM A SUITABLY QUALIFIED ENVIRONMENTAL CONSULTANT CONFIRMING THE SUITABILITY OF THESE REMEDIAL MEASURES TO MANGE THE WATER DISCHARGED FROM THE SITE INTO COUNCILS STORM WATER DRAINAGE SYSTEM. OUTLINING THE PROPOSED, ONGOING MONITORING, CONTINGENCY PLANS AND VALIDATION PROGRAM THAT WILL BE IN PLACE TO CONTINUALLY MONITOR THE WATER QUALITY TESTING THAT WILL BE UNDERTAKEN BY A SUITABLY QUALIFIED ENVIRONMENTAL CONSULTANT.












MINIMUM OF 150mm INTO THE GROUND, ALTERNATIVELY

FABRIC ENSURING FABRIC IS TIGHT TO GROUND WIRE TIES ARE TO BE USED TO ATTACH SEDIMENT CONTROL Wirke He's ARE TO BE USED TO AT ACH SEDIMENT CONTROL FABRIC TO THE UPHILL SIDE OF STAR PICKETS.
 JOINS IN SEDIMENT CONTROL FABRIC TO OVERLAP A MINIMUM 150mm AND TO BE SUPPORTED BY A STAR PICKET.

BACKFILL OR AGGREGATE SHOULD BE PLACED ON TOE OF

NOT	FOR	COI	NS <sup>.</sup>	TR	UC	CTIO	Ν
ON AND SEDIMENT	Scale at A1 N.T.S	Drawn DA		Designed JH	i	Approved AH	
ROL NOTES AND DETA	<u>241807-</u> 16.12.2024			<sup>туре</sup> DR−	Role	Sheet No.	Rev -A







ENSURE SANDBAGS SURROUND

ENTIRE KERB INLET

This drawing is copyright and is the property of TTW and must not be used without authorisation. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT NOTES AND LEGENDS





This drawing is copyright and is the property of TTW and must not be used without authorisation. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT NOTES AND LEGENDS

SIZE REQUIREMENTS					
GOVERNED BY MAXIMUM PIPE DIAMETER					
A (M), B (M)					
350	100				
450	150				
600	300				
900	600				
1200 900					

SIZE REQUIREMENTS							
GOV	GOVERNED BY MAXIMUM DEPTH						
A	A B D						
350	350	450					
450	450	600					
600	600	900					
900	600	1200					
900	900	5400					
1200	1200	5400					

SIZE REQUIREMENTS						
MINIMUM WALL THICKNESS						
A (M), B (M) T						
350	125					
450	125					
600	125					
900	REFER MINIMUM WALL THICKNESS (A,B=900) TABLE					
1200	REFER MINIMUM WALL THICKNESS (A,B=1200) TABLE					

SIZE REQUIREMENTS					
MINIMUM WALL THICKNESS (A,B =900)					
D	Т				
1600	125				
2300	150				
3200	175				
4300	200				
5400	225				

SIZE REQUIREMENTS					
MINIMUM WALL THICKNESS (A,B =1200)					
D T					
1800	175				
2400	200				
3000	225				
3600	250				
4300	275				
5400	300				

0	200	400	600	800mm
1:10 A	1			1:20 A3
0	400	800	1200	1600mm
1:20 A	.1			1:40 A3
0.0	1000	2000	3000	4000mm
1:50 A	1		1	100 A3

NOTE THIS DETAIL IS TO BE READ IN CONJUNCTION WITH AS 3500.3, PLUMBING AND DRAINAGE, PART 3 STORMWATER DRAINAGE

## NOT FOR CONSTRUCTION

NOTES AND LEGEND

Project N Туре Sheet No Originator Zone Role 241807-TTW-00-DR-CI-04001-A


JH


AH


Rev


16.12.2024 4:25 PM

AS SHOWN DA











400

A ISSUED FOR DA

Rev Description

800

1200

1600mr

A1 1:40 A3



ANZAC VILLAGE MONTGOMERY CENTRE NARRABEEN, NSW This drawing is copyright and is the property of TTW and must not be used without authorisation. THIS DRAWING IS TO BE READ IN CONJUNCTION WITH ALL RELEVANT NOTES AND LEGENDS

## NOT FOR CONSTRUCTION

							<u> </u>	
	Scale at A1	Drawn		Design	ed	Approved		
1ENT	AS SHOW	N DA		JH		AH		
_S	Project No	Originator	Zone	Туре	Role	Sheet No.	Rev	
2	241807	241807-TTW-00-DR-CI-07502-A						
	16.12.2024	4:24 Pl	М					