


#### PIPEWORK SYMBOLS



PRWO PLANTER RAINWATER OUTLET

SRWO SPOON DRAIN RAINWATER OUTLET

# ABBREVIATIONS

FFL FINISH FLOOR LEVEL INVERT LEVEL

REDUCED LEVEL UPVC UNPLASTICIZED POLYVINIL CHLORIDE

NOT TO SCALE

UNLESS NOTED OTHERWISE SQUARE SQ

MILLIMETRES mm METRES

SQUARE METRES m3 CUBIC METRES

/sec PER SECOND

MINIMUM MAXIMUM

APPR APPROXIMATLY

DIA DIAMETER EX EXISTING

AHD AUSTRALIAN HEIGHT DATUM

## STORMWATER

GENERAL NOTES ALL IN ACCORDANCE WITH COUNCIL'S STORMWATER REQUIREMENTS

## PIPEWORK DESIGN


ALL PIPEWORK IS SIZED AND DESIGNED TO HANDLE A 1:100 YEAR EVENT RAINFALL


## PIPEWORK

ALL PIPEWORK TO BE 100mm @ 1% FALL (UNO)

## STORMWATER PIT SIZES

SICHWAIER FII SIZES					
MINIMUM INTERNAL MEASUREMENTS:					
DEPTH TO BASE OF CHAMBER	RECTANGULAR WIDTH LENGTH		CIRCULAR	LADDER / STEP IRON	
SMALLER THAN 600	450	450	600	NO	
601 TO 900	600	600	900	0 0	
901 TO 1200	600	900	1050	0 0	
GREATER THAN 1200	900	900	1050	YES	





SEDIMENTATION CONTROL DURING CONSTRUCTION

ISSUED FOR DA 07.02.24 REV DESCRIPTION DATE

JULIEN ROY

ARCHITECT HUGO HASKARD DRAFTING SERVICES

tel(02) 9997 1566 fax (02) 9997 3266

email: markus@itmdesign.com.au

t md es i g consulting hydraulic engineers
unit 6 / 3 apollo st, warriewood nsw 2102
po box 1438 mona vale nsw 1660

21 LINDLEY AVENUE

NARRABEEN

APPROVAL

DRAWING TITLE LEGEND, DETAILS AND SEDIMENTATION CONTROL

JOB No 23/163 1:200 @ A1 / 1:400 @ A3 DRAWING No DISCIPLINE REVISION HYD H-DA-00 A

10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

NOTES STORMWATER DA FOR GENERAL NOTES AND LEGEND DRAWING ONLY REFER TO DRAWING H - DA - 00 - NOT FOR CONSTRUCTION
- FINAL LOCATION OF ALL DOWNPIPES, PITS, RAINWATER OUTLETS
AND SUBSOIL PIPES TO BE CONFIRMED DURING CONSTRUCTION
CERTIFICATE STAGE OF THE PROPOSED DEVELOPMENT LANDSCAPING DRAINAGE ALL LANDSCAPED AREAS LOCATED ABOVE CONCRETE SLABS TO BE EQUIPPED WITH WATERPROOFING MEMBRANE, DRAINAGE CELL AND GEOFABRIC EXISTING DRAINAGE DURING DEMOLITION / CONSTRUCTION: ALLOW TO INVESTIGATE EXACT LOCATION, SIZE AND CONDITION OF ALL DRAINAGE PIPES. LIAISE WITH itm design TO DISCUSS THE FINDINGS. ALLOW TO REPLACE / UPGRADE AS REQUIRED. -INLET / ACCESS / SURCHARGE GRATE 600SQ ` -PIT 600SQ INLET-&-REMOVABLE TRASH SCREEN - 200mm HIGH BLUE METAL BED UNDER WEEP HOLES WEEP HOLES 20mm DIA @ 200mm CENTRE -SILT TRAP HANDLE-OUTLET BEHIND — TRASH SCREEN TO PROTECT THE OUTLET -& DOWNSTREAM DRAINAGE SYSTEM STAINLESS STEEL OR GALVANISED MESH SCREEN (MAXIMESH RH 3030 OR EQUIVALENT) PLACEMENT: PLACEMENT:
SCREEN MUST BE PLACED SO THAT THE
LONG AXIS OF THE OVAL SHAPED HOLES
ARE HORIZONTAL WITH THE PROTRUDING
LIP ANGLED UPWARDS AND
FACING DOWNSTREAM DETAIL 1: STW SILT ARRESTOR PIT 100 & TRASH SCREEN NTS TYPICAL NOTE: ---ALL SUBSOIL DRAINAGE PIPES TO BE 100mm DIA COMPLETE WITH 200mm BLUE METAL SURROUND WRAPPED IN GEOFABRIC. USE PVC PIPES WITH TOP HALF SLOTTED AND EXTENT TO BE CO - ORDINATED WITH: TYPICAL NOTE:

EMERGENCY OVERLAND

FLOW PATH - STRUCTURAL ENGINEER
- GEOTECHNICAL ENGINEER - LANDSCAPING CONSULTANT / CONTRACTOR - 600SQ SILT ARRESTOR PIT COMPLETE WITH: - TRASH SCREEN - SOIL CONDITIONS PREFABRICATED ABOVE GROUND -RAINWATER COLLECTION TANK (REFER TO DETAIL 1) COMPLETE WITH: 100mm DIA HIGH LEVEL OVERFLOW - 100mm DIA HIGH LEVEL OVERFLOW PIPE
- FIRST FLUSH SYSTEM
- INLET SCREEN
- ACCESS LID
- SLUDGE VALVE
- SWITCH OVER SYSTEM
- RE - USE PUMP AND CONTROLS
- BACKWASH FILTER
MIN. TOTAL CAPACITY: 1.575m3
(IN ACCORDANCE WITH THE BASIX REPORT) GARAGE BASIX REPORT) SUGGESTED: 2000 Itrs SLIMLINE (OR APPROVED EQUAL) 2.0m L x 0.62m D x 2.2m H www.asctanks.com.au TYPICAL NOTE:

DRAINAGE VOID COMPLETE
WITH MIN. 1% FALL TOWARDS
PIT. HIGHPOINTS TO BE MIN.
100mm LOWER THAN ADJACENT
STRUCTURAL FLOOR RL. PAY ALL FEES AND CHARGES. DISCHARGE TO EXISTING SWALE IN ACCORDANCE WITH TRENCH DRAIN -100mm W x 100mm D AUTHORITIES REQUIREMENTS. OPTION 1:

1x 150mm DIA DISCHARGE PIPE

OPTION 2:

3 x 100mm DIA DISCHARGE PIPES

(RECOMMENDED, BUT SUBJECT

TO COUNCIL APPROVAL) STW 100 STW 100 APPROVAL PROJECT DRAWING TITLE JULIEN ROY HUGO HASKARD 21 LINDLEY SUB FLOOR DRAFTING SERVICES AVENUE STORMWATER DRAINAGE NARRABEEN t md es i g JOB No 23/163 1:100 @ A1 / 1:200 @ A3 consulting hydraulic engineers
unit 6 / 3 apollo st, warriewood nsw 2102
po box 1438 mona vale nsw 1660 DRAWING No DISCIPLINE REVISION ISSUED FOR DA 07.02.24 HYD H-DA-01 A tel (02) 9997 1566 fax (02) 9997 3266 REV DESCRIPTION

email: markus@itmdesign.com.au

DATE

10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

LANDSCAPING DRAINAGE
ALL LANDSCAPED AREAS LOCATED ABOVE CONCRETE SLABS
TO BE EQUIPPED WITH WATERPROOFING MEMBRANE,
DRAINAGE CELL AND GEOFABRIC


DRAINAGE

DURING DEMOLITION / CONSTRUCTION: ALLOW TO INVESTIGATE

EXACT LOCATION, SIZE AND CONDITION OF ALL DRAINAGE PIPES.

LIAISE WITH itm design TO DISCUSS THE FINDINGS. ALLOW TO

REPLACE / UPGRADE AS REQUIRED.



APPROVAL



JULIEN ROY

HUGO HASKARD DRAFTING SERVICES

consulting hydraulic engineers
unit 6 / 3 apollo st, warriewood nsw 2102
po box 1438 mona vale nsw 1660
tel (02) 9997 1566 fax (02) 9997 3266
email: markus@itmdesign.com.au

PROJECT 21 LINDLEY AVENUE

NARRABEEN

GROUND FLOOR STORMWATER DRAINAGE


SCALE							JOB No	
1:100	0	A1 /	1:200	0	АЗ		23/	163
DISCIPLIN	٧E			DF	RAWING	No		REVISION
HYC	$\supset$			G	-{  <del>-</del>	) A - O	2	


07.02.24

DATE

ISSUED FOR DA

REV DESCRIPTION





STORMWATER DA DRAWING ONLY - NOT FOR CONSTRUCTION
- FINAL LOCATION OF ALL DOWNPIPES, PITS, RAINWATER OUTLETS
AND SUBSOIL PIPES TO BE CONFIRMED DURING CONSTRUCTION
CERTIFICATE STAGE OF THE PROPOSED DEVELOPMENT POOL LAWN DECK APPROVAL DRAWING TITLE HUGO HASKARD Drafting services JULIEN ROY 21 LINDLEY AVENUE ROOF STORMWATER DRAINAGE NARRABEEN consulting hydraulic engineers
unit 6 / 3 apollo st, warriewood nsw 2102
po box 1438 mona vale nsw 1660
tel (02) 9997 1566 fax (02) 9997 3266
email: markus@itmdesign.com.au

ISSUED FOR DA

10 20 30 40 50 60 70 80 90 100 110 120 130 140 150

REV DESCRIPTION

07.02.24

DATE

NOTES FOR GENERAL NOTES AND LEGEND REFER TO DRAWING H - DA - 00

23/163

REVISION

DRAWING NO
H-DA-05

1:100 @ A1 / 1:200 @ A3

DISCIPLINE

Read in conjunction with drawings H - DA - 00 to H - DA - 05 (all Revision 'A' / dated 05.02.2024) Proposed works: Alterations and additions (single dwelling)

consulting hydraulic engineers / 3 apollo street warriewood nsw 2102 tel(02) 9997 1566 email: info@itmdesign.com.au



#### Appendix 16 – On-site Detention Checklist

This checklist is to be used to determine the on-site stormwater disposal requirement for developments and must be completed and included with the submission of any development application for these works. Please read this form carefully for its notes, guidelines, definition and relevant policies.

For assistance and support, please contact Council's Development Engineering and Certification team on

1300 434 434.					
Part 1 Location	of the Property				
House Humber	21		Legal Property Descripti	on	
Street	Lindley Avenue		Lot	8	
Suburb	Narrabeen		Section	E	
Postcode	2101		DP	7090	
				•	
Part 2 Site Deta	aile				
Tart 2 One Deta	ans.				
		2	Total Site Area		1071m2
Pre-Development Impervious Area Post-Development Impervious					
	required for alteration				🗖
	levelopment located with il's Local Environmental		lished Flood Prone Land as	6	Yes □ No □
If yes, On-site stormwater Detention system (OSD) is not required and please proceed to part 5 of this checklist If no, please proceed to part 3 of this checklist.					
Part 3: Northern Beaches Stormwater Regions (refer to Map 2 of Northern Beaches Council's Water Management for Development policy)					
If the site of the development located within Region 1, please proceed to the part 4.1 of this checklist					
If the site of the development located within Region 2, please proceed to the part 4.2 of this checklist					
If the site of the development located within Region 3, please proceed to the part 4.3 of this checklist					
If the site of the de Management Spe		n Region 4	, please refer to Council's V	Varriew	ood Valley Water



#### Part 4 Determination of OSD Requirements

Part 4.1 Northern Beaches Stormwater Region 1				
Is the additional impervious area of the development more than 50 m <sup>2</sup> on a cumulative basis since February 1996?	Yes □ No □			
If yes, OSD is required and please refer to section 9.3.1 of Council's Water Management for Development Policy If no, OSD is not required and please proceed to the part 5 of this checklist				

Part 4.2 Northern Beaches Stormwater Region	າ 2
---------------------------------------------	-----

#### Part 4.2.1 Description of Work

Residential flat building, commercial, industrial, multiple occupancy development and subdivisions resulting in the creation of three lots or more, will require OSD in all case. Please provide a design in accordance with the section 9.3.2 of Council's Water Management for Development Policy. Any single residential building development, please proceed to part 4.2.2 of this checklist.

Part 4.2.2 Exemption					
Is the site area less th	Yes □ No □				
Does the site of the do to pass through a drai and gutter or natural of	Yes □ No □				
Is it an alternation and	Yes ☐ No ☐				
If yes to any of the ab If no to all the above of	No OSD required				
Part 4.2.3 Determination of OSD Requirements					
Calculation	a) Site area m² x 0.40 (40%) =	. m² Yes □ No □ .3.2 of Council's Water			



#### Part 4.3 Northern Beaches Stormwater Region 3 Part 4.3.1 Stormwater Zone In the region, the method of stormwater control to be applied shall depend on the location of the site. Please refer to Map 3 of Northern Beaches Council's Water Management for Development policy. If the site of the development located within stormwater zone 1, please proceed to the part 4.3.2 of this checklist If the site of the development located within stormwater zone 2, please provide a design in accordance with the section 9.3.3.3 of Council's Water Management for Development Policy. If the site of the development located within stormwater zone 3, please provide a design in accordance with the section 9.3.3.4 of Council's Water Management for Development Policy. If the site of the development located within stormwater zone 4, please provide a design in accordance with the section 9.3.3.5 of Council's Water Management for Development Policy. Part 4.3.2 Determination of OSD requirements in Stormwater Zone 1 Part 4.3.2.1 For A New Building Yes □ No □ 1) Exemption a) Is the site area less than 400? Yes □ No □ b) Is the post-development impervious area less than 190 m<sup>2</sup>? If yes to both questions, OSD is not required. If no to any of the above questions, please process to calculation 2) Calculation $m^2 \times 0.35 =$ $m^2 + 50 =$ b) Post- development impervious area m<sup>2</sup> OSD will not be required when (b) is less than 250 m<sup>2</sup> and (a) is greater than (b) Is OSD required for this development? Yes □ No □ If yes, provide a design in accordance with the section 9.3.3.2 of Council's Water Management for Development Policy. If no, OSD is not required and please proceed to part 5. Part 4.3.2.2 For Alterations and Additions If the current impervious area of the site is more than 60% of the site area, OSD will be required. Alternatively, please proceed to the next calculation section. 1) Calculation Is the post development impervious area increased by less than 50 m<sup>2</sup>? Yes $\square$ No $\square$ Is the post development impervious area less than 60% of the site area? Yes $\square$ No $\square$ If yes to both questions, OSD is not required. If no to any of the above questions, provide a design in accordance with section 9.3.3.2 of Council's Water Management for Development Policy



Part 5 Disposal of Stormwater		
Does the site fall naturally towards the street? Yes $\square$ No $\square$		
If yes, provide a design in accordance with section 5.1 of Council's Water Management for Development Policy.  If no, provide a design in accordance with section 5.5 of Council's Water Management for Development		
Policy.		

Definitions	
Designed to help you fill out this application	Site area: This refers to the area of the land bounded by its existing or proposed boundaries.  Impervious area: This refers to driveways, parking spaces, pathways, paved areas, hardstand areas, roofed areas, garages and outbuildings.  Pre Development Impervious area: This refers all impervious areas of the site before the development.  Post Development Impervious areas: This refers all the impervious areas within the site after the development is completed.