

## Engineering Referral Response

Application Number:	DA2020/1749
Date:	22/02/2021
To:	Lashta Haidari
Land to be developed (Address):	Lot 19 DP 27133 , 9 Ilya Avenue BAYVIEW NSW 2104

### Reasons for referral

This application seeks consent for the following:

- New Dwellings or
- Applications that require OSD where additional impervious area exceeds 50m2 or
- Alterations to existing or new driveways or
- Where proposals affect or are adjacent to Council drainage infrastructure incl. watercourses and drainage channels or
- Torrens, Stratum and Community Title Subdivisions or
- All new Commercial and Industrial and RFB Development with the exception of signage or
- Works/uses in flood affected areas

And as such, Council's development engineers are required to consider the likely impacts on drainage regimes.

### Officer comments

#### 28/01/2021

The new swimming pool will require excavation of nearly 1m deep and also the entire site is under Geotech Hazard area.

As per the DCP, full Geotech (Risk) Assessment is required.

#### 22/02/2021

- Applicant must install Rainwater tank of at least 890 liters.-BASIX Report.
- Applicant must include the Geotechnical Report prepared by CROZIER Geotechnical Consultants dated Feb, 2021,in to the construction plans.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

### Recommended Engineering Conditions:

**CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE**

**Stormwater Disposal**

The applicant is to demonstrate how stormwater from the new development within this consent is disposed of to an existing approved system or in accordance with Northern Beaches Council's Water Management for Development Policy. As per BASIX report, applicant must install a rainwater tank of at least 890 liters on the site. Details by an appropriately qualified and practicing Civil Engineer demonstrating that the existing approved stormwater system can accommodate the additional flows, or compliance with the Council's specification are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for disposal and stormwater management arising from development.

**Geotechnical Report Recommendations have been Incorporated into Designs and Structural Plans**

The recommendations of the risk assessment required to manage the hazards as identified in the Geotechnical Report prepared by CROZIER Geotechnical Consultants dated February, 2021 are to be incorporated into the construction plans. Prior to issue of the Construction Certificate, Form 2 of the Geotechnical Risk Management Policy for Pittwater (Appendix 5 of P21 DCP) is to be completed and submitted to the Accredited Certifier. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.

**Structural Adequacy and Excavation Work**

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required. All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer, except where site conditions permit the following:

- (a) maximum height of 900mm above or below ground level and at least 900mm from any property boundary, and
- (b) Comply with AS3700, AS3600 and AS1170 and timber walls with AS1720 and AS1170.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To provide public and private safety.

**CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK****Road Reserve**

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public safety.

**Site filling - Virgin Excavated Natural Material (VENM)**

Where site fill material is necessary, fill materials must:

1. Be Virgin Excavated Natural Material (VENM) only, as defined in: The Protection of the Environment Operations Act 1997

2. Be free of slag, hazardous, contaminated, putrescibles, toxic or radioactive excavated material and soil, rock or similar material. Putrescibles and non-putrescibles solid waste (including demolition material) is not permitted.
3. The Applicant shall provide certification by a N.A.T.A. approved laboratory to the Principal Certifying Authority for approval prior to importation of material.

Reason: To ensure protection of the natural environment.

## **CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE**

### **Stormwater Disposal**

The stormwater drainage works shall be certified as compliant with all relevant Australian Standards and Codes by a suitably qualified person. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any final Occupation Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater arising from the development.

### **Retaining wall**

The retaining wall works shall be certified as compliant with all relevant Australian Standards and Codes by a Structural Engineer. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any final Occupation Certificate.

Reason: Public and Private Safety

### **Geotechnical Certification Prior to Occupation Certificate**

The Applicant is to submit the completed Form 3 of the Geotechnical Risk Management Policy (Appendix 5 of P21 DCP) to the Principal Certifying Authority prior to issue of the Occupation Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.