



SEDIMENT CONTROL

NOTE:

Soil and Water Management Plan - Condition C.4 / DA 212/2018

soil and water management plan to comply with "Do it Right, Soil and Water Management for the Construction Industry" and "Managing Urban Stormwater - Soils and Construction".

all erosion and sediment control measures to be inspected and maintained daily by site foreman

minimise disturbed areas

all stockpiles to be clear from drains, gutters and footpaths

drainage to be connected to stormwater as soon as possible

roads and footpath to be swept daily

A 27/06/2024 ISSUE FOR DA

REVISION

PROJECT

**CONCEPT PLANS
PROPOSED NEW ENTRY & POOL**

**MALCOLM AND SUZANNE
STEINGOLD**

**32 RAYNER ROAD
WHALE BEACH**

PLAN - SITE

gja

greg jones architecture

M: 0400 044 277 PO BOX 699 AVALON BEACH NSW 2107

All work to be in accordance with local authorities building codes and standards, the BCA, NCC and all relevant current AUS / NZ standards. Do not scale from drawings. Use figured dimensions only. verify all dimensions on site before ordering materials or commencing construction.

Builder / Contractor to notify designer immediately of any discrepancies or errors in documentation. Workmanship shall be of the highest standard and to the satisfaction of the author. These plans remain the property of greg jones architecture and are subject to Copyright regulations.

1 site plan
1 : 200

DATE Issue Date DWG NO.
SCALE 1 : 200
DRAWN BY Author
CHECKED BY Checker

DA-101

A