PROPOSED DEVELOPMENT

638 PITTWATER ROAD, BROOKVALE

STORMWATER PLANS

GENERAL NOTES

- G1. THE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL ARCHITECTURAL DRAWINGS AND SPECIFICATIONS AND OTHER WRITTEN INSTRUCTIONS THAT MAY BE ISSUED.
- AND SPECIFICATIONS AND OTHER WRITTEN INSTRUCTIONS THAT MAY BE ISSUED.

 G2. DIMENSIONS SHALL NOT BE OBTAINED BY SCALING FROM THE DRAWINGS. REFER
- ARCHITECTS DRAWINGS FOR ALL DIMENSIONS.

 G3. REFER ANY DISCREPANCY TO THE ENGINEER/ARCHITECT.
- G4. MATERIALS AND WORKMANSHIP SHALL COMPLY WITH THE APPROPRIATE SAA SPECIFICATIONS OR CODE AND WITH THE REQUIREMENTS OF THE RELEVANT LOCAL AUTHORITY.
- G5. THE ALIGNMENT AND LEVEL OF ALL SERVICES SHOWN ARE APPROXIMATE ONLY. THE CONTRACTOR SHALL CONFIRM THE POSITION AND LEVEL OF ALL SERVICES PRIOR TO COMMENCEMENT OF CONSTRUCTION. ANY DAMAGE TO SERVICES SHALL BE RECTIFIED AT THE CONTRACTORS EXPENSE.
- G6. NO WORKS ARE TO COMMENCE UNTIL THE REQUIRED TREE REMOVAL PERMITS HAVE BEEN GRANTED BY RELEVANT LOCAL AUTHORITY, AND THE APPROPRIATE NOTICE OF INTENTION TO COMMENCE GIVEN.
- G7. ALL SERVICES, OR CONDUITS FOR SERVICING SHALL BE INSTALLED PRIOR TO COMMENCEMENT OF PAVEMENT CONSTRUCTION.
- G8. SUBSOIL DRAINAGE, COMPRISING 100 AGRICULTURE PIPE IN GEO-STOCKING TO BE PLACED AS SHOWN AND AS MAY BE DIRECTED BY THE SUPERINTENDENT. SUBSOIL DRAINAGE SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE RELEVANT LOCAL AUTHORITY
- CONSTRUCTION SPECIFICATION.

 G9. NO WORK IS PERMITTED WITHIN ADJOINING PROPERTIES WITHOUT WRITTEN PERMISSION FROM THE OWNERS OR RESPONSIBLE AUTHORITY.

DRAINAGE NOTES

- D1. ALL DRAINAGE OUTLET LEVELS SHALL BE CONFIRMED ON SITE, PRIOR TO CONSTRUCTION
- D2. ALL PIPES WITHIN THE PROPERTY TO BE MIN. 100 DIA UPVC @ 1% MIN. GRADE, UNO. D3. ALL PITS WITHIN THE PROPERTY ARE TO BE FITTED WITH "WELDLOK" OR APPROVED EQUIVALENT GRATES:
- LIGHT DUTY FOR LANDSCAPED AREAS
- HEAVY DUTY WHERE SUBJECTED TO VEHICULAR TRAFFIC
- D4. PITS WITHIN THE PROPERTY MAY BE CONSTRUCTED AS:
- 1) PRECAST STORMWATER PITS
 2) CAST INSITU MASS CONCRETE
- 3) CEMENT RENDERED 230mm BRICKWORK
- SUBJECT TO THE RELEVANT LOCAL AUTHORITY CONSTRUCTION SPECIFICATION.

 D5. ENSURE ALL GRATES TO PITS ARE SET BELOW FINISHED SURFACE LEVEL WITHIN THE
- PROPERTY. TOP OF PIT RL'S ARE APPROXIMATE ONLY AND MAY BE VARIED SUBJECT TO APPROVAL OF THE ENGINEER. ALL INVERT LEVELS ARE TO BE ACHIEVED.
- D6. ANY PIPES BENEATH RELEVANT LOCAL AUTHORITY ROAD TO BE RUBBER RING JOINTED RCP, UNO.
- D7. ALL PITS IN ROADWAYS ARE TO BE FITTED WITH HEAVY DUTY GRATES WITH LOCKING BOLTS AND CONTINUOUS HINGE.
- D8. PROVIDE STEP IRONS TO STORMWATER PITS GREATER THAN 1200 IN DEPTH.
- D9. TRENCH BACK FILL IN ROADWAYS SHALL COMPRISE SHARP, CLEAN GRANULAR BACK FILL IN ACCORDANCE WITH THE RELEVANT LOCAL AUTHORITY SPECIFICATION TO NON-TRAFFICABLE AREAS TO BE COMPACTED BY RODDING AND TAMPING USING A FLAT PLATE VIBRATOR.
- D10. WHERE A HIGH EARLY DISCHARGE (HED) PIT IS PROVIDED ALL PIPES ARE TO BE CONNECTED TO THE HED PIT, UNO.
- D11. DOWN PIPES SHALL BE A MINIMUM OF DN100 SW GRADE UPVC OR 100X100 COLORBOND/ZINCALUME STEEL, UNO.
- D12. COLORBOND OR ZINCALUME STEEL BOX GUTTERS SHALL BE A MINIMUM OF 450 WIDE X 150
- DEEP.
 D13. EAVES GUTTERS SHALL BE A MINIMUM OF 125 WIDE X 100 DEEP (OR OF EQUIVALENT AREA)
- COLORBOND OR ZINCALUME STEEL, UNO.
- D14. SUBSOIL DRAINAGE SHALL BE PROVIDED TO ALL RETAINING WALLS & EMBANKMENTS, WITH THE LINES FEEDING INTO THE STORMWATER DRAINAGE SYSTEM, UNO.

EARTHWORKS NOTES

- E1. THE EARTHWORKS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE PROJECT GEOTECHNICAL REPORT.
- E2. THE SITE OF THE WORKS SHALL BE PREPARED BY STRIPPING ALL EXISTING TOPSOIL, FILL AND VEGETATION.
- E3. SUBGRADE SHALL BE COMPACTED UNTIL A DRY DENSITY HAS BEEN ACHIEVED OF NOT LESS THAN 100% OF THE STANDARD MAXIMUM DRY DENSITY WHEN TESTED IN
- E4. THE EXPOSED SUBGRADE SHOULD BE PROOF ROLLED TO DETECT ANY SOFT OR WET AREAS WHICH SHOULD BE LOCALLY EXCAVATED AND BACK FILLED WITH SELECTED MATERIAL
- E5. THE BACK FILLING MATERIAL SHALL BE IMPORTED GRANULAR FILL OF LOW PLASTICITY, PREFERABLY CRUSHED SANDSTONE, AND TO BE PLACED IN LAYERS NOT EXCEEDING 150 LOOSE THICKNESS AND COMPACTED TO 98% OF STANDARD DRY DENSITY AT A MOISTURE CONTENT WITHIN 2% OF OPTIMUM.
- E6. SITE WORKS ARE TO BE BATTERED TO ADJACENT PROPERTY LEVELS.

ACCORDANCE WITH AS 1289 TESTS E.1.1. OR E.1.2.

- E7. STORMWATER MUST NOT BE CONCENTRATED ON TO AN ADJACENT PROPERTY.
 E8. AT NO TIME DURING OR AFTER CONSTRUCTION IS STORMWATER TO BE PONDED ON
- ADJOINING PROPERTIES.
 E9. THE SITE SHALL BE GRADED AND DRAINED SO THAT STORMWATER WILL BE DIRECTED
- AWAY FROM THE BUILDING PLATFORM.

 E10. STORMWATER DRAINAGE SHALL BE PROVIDED AND MAINTAINED THROUGHOUT THE COURSE OF CONSTRUCTION. ALL STORMWATER RUNOFF SHALL BE GRADED AWAY FROM THE SITE WORKS AND DISPOSED OF VIA SURFACE CATCHDRAINS AND STORMWATER
- COLLECTION PITS.
 E11. ALL SURFACE CATCH DRAINS SHALL BE GRADED AT 1% (1 IN 100) MINIMUM. THE GROUND SHALL GRADE AWAY FROM ANY DWELLING AT 5% (1 IN 20) FOR THE FIRST METRE THEN AT
- 2.5% (1 IN 40).

 E12. WHERE A CUT FILL PLATFORM IS USED THERE SHALL BE A MINIMUM BERM 1000 WIDE TO THE PERIMETER OF THE SITE WORKS WHICH SHALL BE SUPPORTED BY BATTERS OF 3:1 IN
- THE PERIMETER OF THE SITE WORKS WHICH SHALL BE SUPPORTED BY BATTERS OF 3:1 IN FILL.

 E13. ANY VERTICAL OR NEAR VERTICAL PERMANENT EXCAVATION (CUT) DEEPER THAN 600 IN

MATERIAL OTHER THAN ROCK SHALL BE ADEQUATELY RETAINED OR BATTERED AT A

- MINIMUM OF 3:1.

 E14. WHERE BATTERS CANNOT BE PROVIDED TO SUPPORT THE CUT OR FILL, THEY SHALL BE ADEQUATELY RETAINED.
- E15. RETAINING WALLS ARE TO BE CONSTRUCTED WITH ADEQUATE SUBSOIL DRAINAGE.

CONCRETE PAVEMENT

C1. SUBGRADE SHALL BE PREPARED AS OUTLINED IN EARTHWORKS.C2. PROVIDE JOINTING AT MINIMUM 6000 MAX. INTERVALS OR AS OTHERWISE SPECIFIED IN THE

C6. CONCRETE WORKS ARE TO BE CURED BY ONE OF THE FOLLOWING MEANS:

- DRAWINGS.

 C3. CONCRETE SHALL COMPRISE A MIN. COMPRESSIVE STRENGTH OF 32MPa AT 28 DAYS IN
- ACCORDANCE WITH THE RELEVANT LOCAL AUTHORITY SPECIFICATION, UNO.
- C4. ANY SUB-BASE MATERIAL SHALL BE COMPACTED AS OUTLINED IN EARTHWORKS.
 C5. CONCRETE KERB AND GUTTER SHALL COMPRISE A MINIMUM COMPRESSIVE STRENGTH OF 25MPa, UNO.
- i) WETTING TWICE DAILY FOR THE FIRST THREE DAYS;ii) USING AN APPROVED CURING COMPOUNDED FOR A MINIMUM OF 7 DAYS COMMENCING IMMEDIATELY AFTER POURING.

FLEXIBLE PAVEMENT NOTES

- F1. SUBGRADE SHALL BE PREPARED AS OUTLINED IN EARTHWORKS.
- F2. PAVEMENT MATERIAL SHALL CONSIST OF APPROVED OR RIPPED SANDSTONE, NATURAL GRAVEL OR FINE CRUSH ROCK AS PER THE RELEVANT COUNCIL AUTHORITY SPECIFICATION
- F3. PAVEMENT MATERIALS SHALL BE SPREAD IN LAYERS NOT EXCEEDING 150 AND NOT LESS 75 COMPACTED THICKNESS.
- F4. PAVEMENT MATERIALS SHALL BE SIZED AND OF A STANDARD OUTLINED IN AS1141.
 F5. CRUSHED OR RIPPED SANDSTONE SHALL BE MINUS 75 NOMINAL SIZE DERIVED FROM
- SOUND, CLEAN SANDSTONE FREE FROM OVERBURDEN, CLAY SEAMS, SHALE AND OTHER DELETERIOUS MATERIAL.
- F6. PAVEMENT MATERIALS SHALL BE COMPACTED BY SUITABLE MEANS TO SATISFY THE FOLLOWING MINIMUM SPECIFICATIONS (AS PER AS1289.2)

DESCRIPTION MEDIUM DENSITY RATIO
SUB-BASE 98% MOD
BASE COURSE 98% MOD
ASPHALTIC CONCRETE 97% MOD

- AND SUBJECT TO THE RELEVANT LOCAL AUTHORITY CONSTRUCTION SPECIFICATION.
- F7. TESTING FOR EACH LAYER SHALL BE UNDERTAKEN BY A N.A.T.A. REGISTERED LABORATORY IN ACCORDANCE WITH AS1289, AT NOT MORE THAN 50m INTERVALS AND A MINIMUM OF TWO PER LAYER. FURTHER FREQUENCY OF TESTING SHALL BE NO LESS THAN THAT REQUIRED BY AS3978.

PAVED AREAS NOTES

- A1. SUBGRADE SHALL BE PREPARED AS OUTLINED IN EARTHWORKS.
- A2. ALL PAVERS ARE TO BE PLACED IN ACCORDANCE WITH THE MANUFACTURER'S SPECIFICATION.
- A3. TRAFFICABLE AREAS:
- SUB-BASE TO BE 150 COMPACTED THICKNESS DGS75.
 SUB-BASE TO BE SUITABLY COMPACTED TO MEDIUM DENSITY 98% MOD.
 SUB-BASE TO EXTEND AT LEAST 200 BEYOND PAVED SURFACE.
- PAVERS TO BE 80 THICK INTERLOCKING PAVERS ON 50 SAND BEDDING.

 A4. NON TRAFFICABLE AREAS:

 SUB BASE AS PER TRAFFICABLE AREAS

EROSION AND SEDIMENT NOTES

B1. THIS PLAN TO BE READ IN CONJUNCTION WITH EROSION AND SEDIMENT CONTROL DETAILS AS ATTACHED.

PAVERS TO BE 60 INTERLOCKING PAVERS ON 50 SAND BEDDING (UNO).

- B2. THE CONTRACTOR SHALL IMPLEMENT ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES AS NECESSARY AND TO THE SATISFACTION OF THE RELEVANT LOCAL AUTHORITY PRIOR TO THE COMMENCEMENT OF AND DURING CONSTRUCTION. NO DISTURBANCE TO THE SITE SHALL BE PERMITTED OTHER THAN IN THE IMMEDIATE AREA OF THE WORKS AND NO MATERIAL SHALL BE REMOVED FROM THE SITE WITHOUT THE RELEVANT LOCAL AUTHORITY APPROVAL. ALL EROSION AND SEDIMENT CONTROL DEVICES TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH STANDARDS OUTLINED IN NSW DEPARTMENT OF HOUSING'S "MANAGING URBAN STORMWATER SOILS AND
- B3. TOPSOIL SHALL BE STRIPPED AND STOCKPILED OUTSIDE HAZARD AREAS SUCH AS DRAINAGE LINES. THIS TOPSOIL SHALL BE RESPREAD LATER ON AREAS TO BE REVEGETATED AND STABILISED ONLY, (I.E. ALL FOOTPATHS, BATTERS, SITE REGARDING AREAS, BASINS AND CATCHDRAINS). TOPSOIL SHALL NOT BE RESPREAD ON ANY OTHER AREAS UNLESS SPECIFICALLY INSTRUCTED BY THE SUPERINTENDENT. IF THEY ARE TO REMAIN FOR LONGER THAN ONE MONTH STOCKPILES SHALL BE PROTECTED FROM EROSION BY COVERING THEM WITH A MULCH AND HYDROSEEDING AND, IF NECESSARY, BY LOCATING BANKS OR DRAINS DOWNSTREAM OF A STOCKPILE TO RETARD SILT LADEN BUNGEF.
- B4. THE CONTRACTOR SHALL REGULARLY MAINTAIN ALL EROSION AND SEDIMENT CONTROL DEVICES AND REMOVE ACCUMULATED SILT FROM SUCH DEVICES SUCH THAT MORE THAN 60% OF THEIR CAPACITY IS LOST. ALL THE SILT IS TO BE PLACED OUTSIDE THE LIMIT OF WORKS. THE PERIOD FOR MAINTAINING THESE DEVICES SHALL BE AT LEAST UNTIL ALL DISTURBED AREAS ARE REVEGETATED AND FURTHER AS MAY BE DIRECTED BY THE SUPERINTENDENT OR COUNCIL.
- B5. LAY TURF STRIP (MIN 300 WIDE) ON 100 TOPSOIL BEHIND ALL KERB WITH 1000 LONG RETURNS EVERY 6000 AND AROUND STRUCTURES IMMEDIATELY AFTER BACKFILLING AS
- PER THE RELEVANT LOCAL AUTHORITY SPECIFICATION.

 THE CONTRACTOR SHALL GRASS SEED ALL DISTURBED AREAS WITH AN APPROVED MIX AS
- B7. SOON AS PRACTICABLE AFTER COMPLETION OF EARTHWORKS AND REGRADING.
 VEHICULAR TRAFFIC SHALL BE CONTROLLED DURING CONSTRUCTION CONFINING ACCESS
 WHERE POSSIBLE TO NOMINATED STABILISED ACCESS POINTS.
- WHEN ANY DEVICES ARE TO BE HANDED OVER TO COUNCIL THEY SHALL BE IN CLEAN AND STABLE CONDITION
- THE CONTRACTOR SHALL IMPLEMENT DUST CONTROL BY REGULAR WETTING DOWN (BUT NOT SATURATING) DISTURBED AREA.
- PROVIDE AND MAINTAIN SILT TRAPS AROUND ALL SURFACE INLET PITS UNTIL CATCHMENT IS REVEGETATED OR PAVED.
- B11. REVEGETATE ALL TRENCHES IMMEDIATELY UPON COMPLETION OF BACKFILLING.
 B12. ALL DRAINAGE PIPE INLETS TO BE CAPPED UNTIL:
 - DOWNPIPES CONNECTED
 PITS CONSTRUCTED AND PROTECTED WITH SILT BARRIER

EROSION AND SEDIMENT NOTES

MINIMUM PIPE COVER SHALL BE AS FOLLOWS

LOCATION	MINIMUM COVER	
NO SUBJECT TO VEHICLE LOADING	100mm SINGLE RESIDENTAL	
SUBJECT TO VEHICLE LOADING	450mm WHERE NOT IN A ROAD	
LINDED A SEALED DOAD	600	
UNDER A SEALED ROAD	600mm	
UNSEALED ROAD	750mm	
PAVED DRIVEWAY	100mm PLUS DEPTH OF CONCRETE	
SEE AS2032 INSTALLATION OF UPVC PIPES FOR FURTHER INFORMATION.		

CONCRETE PIPE COVER SHALL BE IN ACCORDANCE WITH AS3725-1989 LOADS ON BURIED CONCRETE PIPES, HOWEVER A MINIMUM COVER OF 450mm WILL APPLY.

WHERE INSUFFICIENT COVER IS PROVIDED, THE PIPE SHALL BE COVERED AT LEAST 50mm THICK OVERLAY AND SHALL BE PAVED WITH AT LEAST:

150mm REINFORCED CONCRETE WHERE SUBJECT TO HEAVY VEHICLE TRAFFIC

75mm THICKNESS OF BRICK OR 100mm OF CONCRETE PAVING WHERE SUBJECT

TO LIGHT VEHICLE TRAFFIC; OR

• 50mm THICK BRICK OR CONCRETE PAVING WHERE NOT SUBJECT TO VEHICLE TRAFFIC

PIT SIZES AND DESIGN

MINIMUM PIT SIZE (mm)
450 x 450
600 x 600 U.N.O
600 x 900 U.N.O
900 x 900 (WITH STEP IRON)

SYMBOLS

	DESCRIPTION
	DENOTE ON-SITE DETENTION TANK OR PUMP OUT TANK
	DENOTE ON-SITE DETENTION BASIN
	DENOTE ABSORPTION TRENCH
o DP	DENOTES DOWNPIPE
Ø100 💉	DENOTES 100mm DIA PVC (SEWER GRADE) AT 1% MIN. GRADE U.N.O
Ø150	DENOTES 150mm DIA PVC (SEWER GRADE) AT 1% MIN. GRADE U.N.O
Ø225	DENOTES 225mm DIA PVC (SEWER GRADE) AT 1% MIN. GRADE U.N.O
— G — G —	DENOTES AGG LINE
ss	DENOTES SEDIMENT FENCE
I₽ <mark>o</mark>	DENOTES INSPECTION OPENING WITH SCREW DOWN LID AT FINISH SURFACE LEVEL
Œ	DENOTES CLEANING EYE
	STORMWATER PIT - GRATED INLET
	STORMWATER PIT - SOLID COVER
	MAINTENANCE PIT
\bowtie	NON RETURN VALVE
FD	DENOTE ROUND FLOOR DRAINS
FD	DENOTE SQUARE FLOOR DRAINS
РВ	DENOTE PLANTER BOX DRAINS
	DENOTE GRATED DRAIN
RL 6.20	PROPOSED FINISH FLOOR LEVEL
>>>	DENOTE EXISTING OVERLAND FLOW PATH
	DENOTE RAINWATER TANK
O/F	DENOTE WATER OUTLET
RL	REDUCED LEVEL/SURFACE LEVELL
IL	INVERT LEVEL
TK	TOP OF KERB

SCHEDULE OF DRAWINGS

SHEET No	DESCRIPTION
COVER	GENERAL NOTES
SW01	SEDIMENT AND EROSION CONTROL PLAN
SW02	BASEMENT 3 DRAINAGE PLAN
SW03	BASEMENT 2 & 1 DRAINAGE PLAN
SW04	GROUND FLOOR DRAINAGE PLAN
SW05	OUTLET LONG SECTION & DRAINS MODEL RESULTS
SW06	STORMWATER SECTIONS AND DETAILS
SW07	WATER SENSITIVE URBANE DESIGN



ISSUE FOR DA

 C
 AMENDED AS PER COUNCIL'S RFI
 29-10-2019

 B
 ISSUED FOR DA
 29-11-2018

 A
 ISSUED FOR COORDINATION
 02-07-2018

 REVISION
 AMENDMENT
 ISSUE DATE



Phone: (02) 9745 5202
Fax: (02) 8004 7461
Email: Info@alphaengineering.com.au
Address: 24A Burleigh St,
Burwood NSW 2134

Burwood NSW 2134
Website: www.alphaengineering.com.au

COPYRIGHT THIS DRAWING REMAINS THE PROPERTY OF ALPHA

ENGINEERING & DEVELOPMENT AND MAY NOT BE ALTERED IN

ANY WAY WITHOUT ALPHA ENGINEERING'S WRITTEN CONSENT


Barry Rush & Associates Pty Ltd
Architects
Suite 25A, 2 Beattie Street, Balmain,
NSW, Australia, 2041
Phone: (612) 9555 8028 Fax: (612) 9810 0161
Email: info@barryrush.com.au
www.barryrush.com.au

ARCHITECT

PROJECT

PROPOSED DEVELOPMENT 638 PITTWATER ROAD, BROOKVALE GENERAL NOTES

SCALES
AS SHOWN
DM
PS
DRAWING NO.
A8256 - COVER
DESIGNED
DRAFTED
PS
APPROVED
REVISION
C



SEDIMENT AND EROSION CONTROL NOTES

SEDIMENT AND EROSION CONTROL SHALL BE EFFECTIVELY MAINTAINED AT ALL TIMES DURING THE COURSE OF CONSTRUCTION AND SHALL NOT BE REMOVED UNTIL THE SITE HAS BEEN STABILISED OR LANDSCAPED TO THE SUPERINTENDENT'S SATISFACTION. A SINGLE ALL WEATHER ACCESS WAY WILL BE PROVIDED AT THE FRONT OF THE PROPERTY CONSISTING OF 50-75 AGGREGATE OR SIMILAR MATERIAL AT A MINIMUM THICKNESS OF 150 LAID OVER NEEDLE-PUNCHED GEOTEXTILE FABRIC AND CONSTRUCTED PRIOR TO COMMENCEMENT OF WORKS.

THE CONTRACTOR SHALL ENSURE THAT NO SPOIL OR FILL ENCROACHES UPON ADJACENT AREAS FOR THE DURATION OF WORKS.

THE CONTRACTOR SHALL ENSURE THAT KERB INLETS AND DRAINS RECEIVING STORMWATER SHALL BE PROTECTED AT ALL TIMES DURING DEVELOPMENT. KERB INLET SEDIMENT TRAPS SHALL BE INSTALLED ALONG THE IMMEDIATE VICINITY ALONG THE STREET FRONTAGE. SEDIMENT FENCING SHALL BE SECURED BY POST (WHERE METAL STAR PICKETS ARE USED PLASTIC SAFETY CAPS SHALL BE USED) AT 2000 INTERVALS WITH GEOTEXTILE FABRIC EMBEDDED 200 IN SOIL. ALL TOPSOIL STRIPPED FROM THE SITE AND

STOCKPILED DOES NOT INTERFERE WITH DRAINAGE LINES AND STORMWATER INLETS AND WILL BE SUITABLY COVERED WITH AN IMPERVIOUS MEMBRANE MATERIAL AND SCREENED BY SEDIMENT FENCING. SOIL CONSERVATION NOTE:


PRIOR TO COMMENCEMENT OF CONSTRUCTION PROVIDE 'SEDIMENT FENCE,' 'SEDIMENT TRAP' AND WASHOUT AREA TO ENSURE THE CAPTURE OF WATER BORNE MATERIAL GENERATED FROM THE SITE. MAINTAIN THE ABOVE DURING THE COURSE OF CONSTRUCTION, AND CLEAR THE 'SEDIMENT TRAP AFTER EACH STORM.

SEDIMENT TRAP 1000 x 1000 WIDE 500 DEEP PIT, LOCATED AT THE LOWEST POINT TO THE TRAP SEDIMENT.

WASHOUT AREA

TO BE 1800 x 1800 ALLOCATED FOR THE WASHING OF TOOL & EQUIPMENT BOARD **FILTERING** SAND 100 PEG —

PROVIDE 'SEDIMENT FENCE ON DOWN SLOPE BOUNDARY AS SHOWN ON PLAN. FABRIC TO BE BURIED BELOW GROUND AT



STAKES DRIVEN 600 INTO THE GROUND WITH FIRST STAKE ANGLED TOWARDS PREVIOUSLY $^{\setminus}$


GEOTEXTILE FILTER FABRIC

LAID BALE FASTEN ON TOP EDGE DISTURBED AREA RUNOFF **UNDISTURBED AREA**

DRAINAGE AREA 0.5 HA. MAX. SLOPE GRADIENT 1:2 MAX. SLOPE LENGTH 50m.

VEHICLE ACCESS TO SITE

VEHICLE ACCESS TO THE BUILDING SITE SHOULD BE RESTRICTED TO A SINGLE POINT SO AS TO REDUCE THE



GENERAL NOTES

THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH OTHER CONSULTANTS' DRAWINGS AND SPECIFICATIONS AND WITH OTHER SUCH WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT. ANY DISCREPANCY SHALL BE REFERRED TO THE ENGINEER BEFORE PROCEEDING WITH THE WORK.

ALL DIMENSIONS ARE IN MILLIMETRES & ALL LEVELS ARE IN METRES, UNO (UNLESS NOTED OTHERWISE).

NO DIMENSION SHALL BE OBTAINED BY SCALING THE DRAWINGS.

ALL LEVELS AND SETTING OUT DIMENSIONS SHOWN ON THE DRAWINGS SHALL BE CHECKED ON SITE PRIOR TO THE COMMENCEMENT OF THE

DURING EXCAVATION WORK THE STRUCTURE SHALL BE MAINTAINED IN A STABLE AND NO PART SHALL BE OVERSTRESSED.

ALL WORK IS TO BE UNDERTAKEN IN ACCORDANCE WITH THE DETAILS SHOWN ON THE DRAWINGS & THE SPECIFICATION.

EXISTING SERVICES WHERE SHOWN HAVE BEEN PLOTTED FROM SUPPLIED DATA AND SUCH THEIR ACCURACY CAN NOT BE GUARANTEED. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO ESTABLISH THE LEVEL OF ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF

ALL SERVICE TRENCHES UNDER VEHICULAR PAVEMENTS SHALL BE BACK FILLED IN ACCORDANCE WITH THE REQUIREMENTS OF THE LOCAL

ALL TRENCH BACK FILL MATERIAL SHALL BE COMPACTED TO THE SAME DENSITY AS THE ADJACENT MATERIAL.

ON COMPLETION OF STORMWATER INSTALLATION, ALL DISTURBED AREAS MUST BE RESTORED TO ORIGINAL CONDITION, INCLUDING KERBS, FOOTPATHS, CONCRETE AREAS, GRAVEL AND GRASSED AREAS AND ROAD PAVEMENTS, UNLESS DIRECTED OTHERWISE.

CONTRACTOR TO OBTAIN ALL AUTHORITY APPROVALS UNLESS DIRECTED OTHERWISE.

STORMWATER DRAINAGE

THE STORMWATER DRAINAGE DESIGN HAS BEEN CARRIED OUT IN ACCORDANCE WITH AS/NZS 3500.3 - 1990 "STORMWATER DRAINAGE" & AS/NZS 3500.3.2-1998 "STORMWATER DRAINAGE - ACCEPTABLE SOLUTIONS".

ANY VARIATIONS TO THE NOMINATED LEVELS SHALL BE REFERRED TO ENGINEER IMMEDIATELY.

ANY VARIATIONS TO SPECIFIED PRODUCTS OR DETAILS SHALL BE

REFERRED TO THE ENGINEER FOR APPROVAL. DOWN PIPES SHALL BE A MINIMUM OF DN100 SW GRADE UPVC OR

100X100 COLORBOND/ZINCALUME STEEL, UNO.

OF 450 WIDE X 150 DEEP. EAVES GUTTERS SHALL BE A MINIMUM OF 125 WIDE X 100 DEEP (OR OF

BOX COLORBOND OR ZINCALUME STEEL. GUTTERS SHALL BE A MINIMUM

GEOTEXTILE FABRIC EQUIVALENT AREA) COLORBOND OR ZINCALUME STEEL.

STRAW BALE AND SUBSOIL DRAINAGE SHALL BE PROVIDED TO ALL RETAINING WALLS & EMBANKMENTS, WITH THE LINES FEEDING INTO THE STORMWATER SEDIMENT FILTER DRAINAGE SYSTEM.


BUILDING MATERIAL STOCKPILES

ALL STOCKPILES OF BUILDING MATERIAL SUCH AS SAND AND SOIL MUST BE PROTECTED TO PREVENT SCOUR AND FRESISHOULD NEVER BE PLACED IN THE STREET GUTTER WHERE THEY WILL WASH AWAY WITH THE FIRST RAINSTORM.



SANDBAG KERB SEDIMENT TRAP

IN CERTAIN CIRCUMSTANCES EXTRA SEDIMENT TRAPPING MAY



RUNOFF

www.dialbeforeyoudig.com.au

ISSUE FOR DA

PROJECT

PROPOSED DEVELOPMENT 638 PITTWATER ROAD, BROOKVALE

DRAWING TITLE

SEDIMENT AND EROSION **CONTROL PLAN**

SCALES	DESIGNED	DRAFTED
AS SHOWN	DM	PS
RAWING NO.	APPROVED	REVISION
A8256 - SW01	JM	С



AMENDED AS PER COUNCIL'S RFI

ISSUED FOR DA

ISSUED FOR COORDINATION

AMENDMENT

В

REVISION

Phone: (02) 9745 5202 (02) 8004 7461 Info@alphaengineering.com.au


Address: 24A Burleigh St, Burwood NSW 2134

Website: www.alphaengineering.com.au COPYRIGHT THIS DRAWING REMAINS THE PROPERTY OF ALPHA ENGINEERING & DEVELOPMENT AND MAY NOT BE ALTERED IN ANY WAY WITHOUT ALPHA ENGINEERING'S WRITTEN CONSENT

Barry Rush & Associates Pty Ltd Suite 25A, 2 Beattie Street, Balmain, NSW, Australia, 2041 Phone: (612) 9555 8028 Fax: (612) 9810 0161 Email: info@barryrush.com.au

www.barryrush.com.au

ARCHITECT



BASEMENT 3 DRAINAGE PLAN

1:200 @ A1

ALL DRAINAGE LINES SHALL BE UPVC (CLASS SH) STORMWATER DRAINAGE PIPE, UNO.

ALL DRAINAGE LINES SHALL BE LAID @ 1% FALL MIN, UNO. FIRST FLUSH RAINWATER DEVICES TO BE FITTED TO DRAINAGE LINES TO BUILDER'S DETAIL, TYPICAL MINIMUM EFFECTIVE EAVES GUTTER SIZE = 6700 mm^2

MINIMUM EFFECTIVE EAVES GUTTER SLOPE = 1:500

THE FOLLOWING SYMBOLS & ABBREVIATIONS HAVE BEEN USED:

DP = Ø150, UNO.

FD = FLOOR OUTLET , REFER TO DETAIL

SIP = SURFACE INLET PIT (NO LINTEL)

100Ø = Ø100 CHARGED LINE
IP = Ø150 INSPECTION POINT

WH = RAIN WATER HEAD

RWO = RAIN WATER OUTLET (300 x 300) FG = FLOOR GULLY Ø150

S P = RAINWATER SPREADER

RL 6.20 = PROPOSED FINISHED SURFACE LEVEL
HR = HEAD ROOM UNDER PIPE


BASEMENT SLAB TO HAVE 1% MIN. FALL TO INLET PIT AS PER AS2890 REQUIREMENT
 ALL BASEMENT PIT TO BE FITTED WITH HEAVY DUTY CLASS C GRATE & FRAME

PUMP DESIGN SUMMARY


CATCHMENT AREA = 0.00 m² (NO UNDER COVER AREA)
PUMP OUT TANK VOLUME PROVIDED = 4.0 m³ (MINIMUM VOLUME AS PER AS STANDARD)


PUMP HEAD = 4 m

PUMP RATE REQUIRED = 210 x 43.4 / 3600 = 3 l/s




SECTION - SUBSOIL DRAINAGE DETAILS





PUMP OUT TANK PLAN

1:50@ A1



DIAL BEFORE YOU DIG

ISSUE FOR DA

 C
 AMENDED AS PER COUNCIL'S RFI
 29-10-2019

 B
 ISSUED FOR DA
 29-11-2018

 A
 ISSUED FOR COORDINATION
 02-07-2018

 REVISION
 AMENDMENT
 ISSUE DATE



Phone: (02) 9745 5202 Fax: (02) 8004 7461 Email: Info@alphaengi

Email: Info@alphaengineering.com.au Address: 24A Burleigh St,

Burwood NSW 2134
Website: www.alphaengineering.com.au
COPYRIGHT THIS DRAWING REMAINS THE PROPERTY OF ALPHA

ENGINEERING & DEVELOPMENT AND MAY NOT BE ALTERED IN

ANY WAY WITHOUT ALPHA ENGINEERING'S WRITTEN CONSENT

ARCHITECT

Barry Rush & Associates Pty Ltd
Architects
Suite 25A, 2 Beattie Street, Balmain,
NSW, Australia, 2041
Phone: (612) 9555 8028 Fax: (612) 9810 0161

Email: info@barryrush.com.au


www.barryrush.com.au


PROJECT


PROPOSED DEVELOPMENT 638 PITTWATER ROAD, BROOKVALE

DRAWING TI	TLE
BASEMENT 3	DRAINAGE PLAN

SCALES	DESIGNED	DRAFTED
AS SHOWN	DM	PS
RAWING NO.	APPROVED	REVISION
A8256 - SW02	JM	С







BASEMENT 2 DRAINAGE PLAN

1:200 @ A1

ALL DRAINAGE LINES SHALL BE UPVC (CLASS SH) STORMWATER DRAINAGE PIPE, UNO.

ALL DRAINAGE LINES SHALL BE LAID @ 1% FALL MIN, UNO. FIRST FLUSH RAINWATER DEVICES TO BE FITTED TO DRAINAGE LINES TO BUILDER'S DETAIL, TYPICAL MINIMUM EFFECTIVE EAVES GUTTER SIZE = 6700 mm²

MINIMUM EFFECTIVE EAVES GUTTER SLOPE = 1:500

THE FOLLOWING SYMBOLS & ABBREVIATIONS HAVE BEEN USED:

DP = Ø150, UNO.

FD = FLOOR OUTLET, REFER TO DETAIL SIP = SURFACE INLET PIT (NO LINTEL)

100Ø = Ø100 CHARGED LINE

IP = Ø150 INSPECTION POINT RWH = RAIN WATER HEAD

RWO = RAIN WATER OUTLET (300 x 300)

= FLOOR GULLY Ø150 s P = RAINWATER SPREADER

RL 6.20 = PROPOSED FINISHED SURFACE LEVEL

• BASEMENT SLAB TO HAVE 1% MIN. FALL TO INLET PIT AS PER AS2890 REQUIREMENT

• ALL BASEMENT PIT TO BE FITTED WITH HEAVY DUTY CLASS C GRATE & FRAME

BASEMENT 1 DRAINAGE PLAN

1:200 @ A1

ALL DRAINAGE LINES SHALL BE UPVC (CLASS SH) STORMWATER DRAINAGE PIPE, UNO.

ALL DRAINAGE LINES SHALL BE LAID @ 1% FALL MIN, UNO. FIRST FLUSH RAINWATER DEVICES TO BE FITTED TO DRAINAGE LINES TO BUILDER'S DETAIL, TYPICAL MINIMUM EFFECTIVE EAVES GUTTER $SIZE = 6700 \text{ mm}^2$

MINIMUM EFFECTIVE EAVES GUTTER SLOPE = 1:500

THE FOLLOWING SYMBOLS & ABBREVIATIONS HAVE BEEN USED:

DP = \emptyset 150, UNO.

FD = FLOOR OUTLET, REFER TO DETAIL = SURFACE INLET PIT (NO LINTEL)

100Ø = Ø100 CHARGED LINE

= Ø150 INSPECTION POINT

RWH = RAIN WATER HEAD RWO = RAIN WATER OUTLET (300×300)

= FLOOR GULLY Ø150

S P = RAINWATER SPREADER

RL 6.20 = PROPOSED FINISHED SURFACE LEVEL

HR = HEAD ROOM UNDER PIPE

 BASEMENT SLAB TO HAVE 1% MIN. FALL TO INLET PIT AS PER AS2890 REQUIREMENT • ALL BASEMENT PIT TO BE FITTED WITH HEAVY DUTY CLASS C GRATE & FRAME



ISSUE FOR DA

AMENDED AS PER COUNCIL'S RFI 29-10-2019 29-11-2018 ISSUED FOR DA 02-07-2018 ISSUED FOR COORDINATION ISSUE DATI **AMENDMENT** REVISION



Phone: (02) 9745 5202 (02) 8004 7461

Info@alphaengineering.com.au Address: 24A Burleigh St, Burwood NSW 2134

Website: www.alphaengineering.com.au COPYRIGHT THIS DRAWING REMAINS THE PROPERTY OF ALPHA ENGINEERING & DEVELOPMENT AND MAY NOT BE ALTERED IN ANY WAY WITHOUT ALPHA ENGINEERING'S WRITTEN CONSENT

ARCHITECT

Email: info@barryrush.com.au

www.barryrush.com.au


Barry Rush & Associates Pty Ltd Architects Suite 25A, 2 Beattie Street, Balmain, NSW, Australia, 2041 Phone: (612) 9555 8028 Fax: (612) 9810 0161

PROJECT

PROPOSED DEVELOPMENT 638 PITTWATER ROAD, BROOKVALE

DRAWING TITLE BASEMENT 2 & 1 DRAINAGE PLAN

SCALES DRAFTED **DESIGNED AS SHOWN** APPROVED REVISION DRAWING NO. A8256 - SW03





www.dialbeforeyoudig.com.au

ISSUE FOR DA

AMENDED AS PER COUNCIL'S RFI 29-10-2019 ISSUED FOR DA 29-11-2018 ISSUED FOR COORDINATION 02-07-2018 **AMENDMENT** ISSUE DAT REVISION



Phone: (02) 9745 5202 (02) 8004 7461

Info@alphaengineering.com.au Address: 24A Burleigh St,

Burwood NSW 2134 Website: www.alphaengineering.com.au

COPYRIGHT THIS DRAWING REMAINS THE PROPERTY OF ALPHA

ENGINEERING & DEVELOPMENT AND MAY NOT BE ALTERED IN

ANY WAY WITHOUT ALPHA ENGINEERING'S WRITTEN CONSENT

Email: info@barryrush.com.au

www.barryrush.com.au

Barry Rush & Associates Pty Ltd Suite 25A, 2 Beattie Street, Balmain, NSW, Australia, 2041 Phone: (612) 9555 8028 Fax: (612) 9810 0161

PROPOSED DEVELOPMENT 638 PITTWATER ROAD, BROOKVALE

	DRAWING TITLE	
GROU	ND FLOOR DRAINAGE PLAN	

POST DEVELOPMENT

OSD TANK

Q_{POST} (I/s)

71


TOTAL

 Q_{POST} (I/s)

71

59

SCALES	DESIGNED	DRAFTED
AS SHOWN	DM	PS
AWING NO.	APPROVED	REVISION
A8256 - SW04	JM	С



www.barryrush.com.au


ENGINEERING & DEVELOPMENT


ISSUE DATE

AMENDMENT

REVISION

DESIGNED DRAFTED REVISION APPROVED DRAWING NO. A8256 - SW05







Phone: (02) 9745 5202
Fax: (02) 8004 7461
Email: Info@alphaengineering.com.au
Address: 24A Burleigh St,
Burwood NSW 2134

Burwood NSW 2134
Website: www.alphaengineering.com.au

R150N/C (NICKEL - BRONZE GRATE, CI LOWER BODY)

R150 S/C (316 STAINLESS STEEL GRATE, CI LOWER BODY)

COPYRIGHT THIS DRAWING REMAINS THE PROPERTY OF ALPHA ENGINEERING & DEVELOPMENT AND MAY NOT BE ALTERED IN ANY WAY WITHOUT ALPHA ENGINEERING'S WRITTEN CONSENT

ARCHITECT

Email: info@barryrush.com.au

www.barryrush.com.au

Barry Rush & Associates Pty Ltd Architects Suite 25A, 2 Beattie Street, Balmain, NSW, Australia, 2041 Phone: (612) 9555 8028 Fax: (612) 9810 0161 PROJECT

KEY JOINT-K.J.

SECTION - TYPICAL GRATED

DRAIN

1:20


PROPOSED DEVELOPMENT 638 PITTWATER ROAD, BROOKVALE

KEYWAY




ISSUE FOR DA

	DRAWING IIILI	=	
Γ	STORMWATER SEC DETAILS	CTIONS AN	ND
	SCALES AS SHOWN	DESIGNED DM	DRAFTED PS
	DRAWING NO.	APPROVED	REVISION
	A8256 - SW06	JM	С



MUSIC CATCHMENT PLAN
1:200 @ A1



MUSIC MODEL LAYOUT & RESULTS

NTS


SF CHAMBER NODE MODELLED WITH "k" VALUE SET TO 1

TOTAL SITE AREA = 2662 m^2

DRIVEWAY AREA = $29.30 \text{m}^2 (100\% \text{ IMP.})$



LANDSCAPE AREA = $202.43 \text{ m}^2 (100\% \text{ PER.})$




RESIDENTIAL AREA = $2417.55 \text{ m}^2 (100\% \text{ IMP.})$

Table 4 – General Stormwater Quality Requirements

Pollutant	Performance Requirements	
Total Phosphorous	65% reduction in the post development mean annual load ¹	
Total Nitrogen	45% reduction in the post development mean annual load ¹	
Total Suspended Solids	85% reduction in the post development mean annual load ¹	
Gross Pollutants	90% reduction in the post development mean annual load ¹ (for pollutants greater than 5mm in diameter)	
pH	6.5 - 8.5	
Hydrology	The post-development peak discharge must not exceed the pre-development peak discharge for flows up to the 2 year ARI	

WSUD REQUIREMENT

NTS



ISSUE FOR DA

 C
 AMENDED AS PER COUNCIL'S RFI
 29-10-2019

 B
 ISSUED FOR DA
 29-11-2018

 A
 ISSUED FOR COORDINATION
 02-07-2018

 REVISION
 AMENDMENT
 ISSUE DATE



Phone: (02) 9745 5202 Fax: (02) 8004 7461

nail: (02) 8004 7461 nail: Info@alphaengineering.com.au

Address: 24A Burleigh St,
Burwood NSW 2134
Website: www.alphaengineering.co

Website: www.alphaengineering.com.au

COPYRIGHT THIS DRAWING REMAINS THE PROPERTY OF ALPHA
ENGINEERING & DEVELOPMENT AND MAY NOT BE ALTERED IN
ANY WAY WITHOUT ALPHA ENGINEERING'S WRITTEN CONSENT

ARCHITECT 000

Barry Rush & Associates Pty Ltd Architects Suite 25A, 2 Beattie Street, Balmain, NSW, Australia, 2041 Phone: (612) 9555 8028 Fax: (612) 9810 0161

Email: info@barryrush.com.au

www.barryrush.com.au

PROJECT

PROPOSED DEVELOPMENT 638 PITTWATER ROAD, BROOKVALE

DRAWING TITLE
WATER SENSITIVE URBANE DESIGN

DESIGNED	DRAFTED
DM	PS
APPROVED	REVISION
JM	С
	DM APPROVED