



# Pittwater Council

## Construction Certificate No: CC 0545/06

Site Details: 109 & 111 Orchard Street, Warriewood  
Legal Description: Lot 3 & 4, DP 734891 & Lot 2, DP 715324  
Type of Development: Building Work  
Description: Construction of a private access way

**COPY**

Associated Development Consent No: N0457/05      Dated: 04/04/2006  
Modified: 22/12/06

Building Code of Australia Classification: Class 10b

Details of plans, documents or Certificates to which this Construction Certificate relates:

- Working Drawing No 4670-01 E (16/10/06), 4670-02 D (21/07/06), 4670-03 E (18/10/06), 4670-04 E (16/10/06), 4670-05 E (21/07/06), 4670-06 D (21/07/06), 4670-07 E (16/10/06), 4670-08 E (16/10/06), 4670-09 E (16/10/06), 4670-10 D (21/07/06), 4670-11 D (21/07/06), 4670-12 D (21/07/06), 4670-13 A (21/07/06), prepared by Patterson Britton & Partners Pty Ltd
- Certification from Patterson Britton & Partners Pty Ltd, dated 22/11/06
- Pittwater Council Approval (works in public road reserve), dated 19/10/06
- Form No 2 Geotechnical Risk Management, prepared by Jack Hodgson Consultants Pty Ltd / M Tooker, dated 28/11/06
- Waste Management Plan, prepared by Patterson Britton & Partners Pty Ltd, dated 21/07/06
- Pittwater Council Approval (consent operative), dated 02/11/06
- Pittwater Council Approval (construction phase – traffic management plan), dated 16/08/06
- Construction Phase – Traffic Management Plan, prepared by Patterson Britton & Partners Pty Ltd, dated 21/09/06

I hereby certify that the above plans, documents or Certificates satisfy:

- The relevant provisions of the Building Code of Australia, and
- The relevant conditions of Development Consent No: N0457/05

And, that work completed in accordance with the documentation accompanying the application for this certificate (and any modifications as verified by me and shown on that documentation) will comply with the requirements of the Environmental Planning and Assessment Regulation, referred to in section 81A(5) of the Environmental Planning and Assessment Act, 1979.

**Issued By: Wayne Treble**  
**Accreditation Number: Dept of Planning P0100**  
**Pittwater Council Consultant**  
**Building Surveyor**

**Date of Endorsement: 9 January 2007**

**Note:** You are reminded that pursuant to provisions of Clause 81A, you must nominate whether Council or an accredited certifier will be the principal certifying authority, also you must give notice to Council of your intention to commence work at least two days beforehand.



Environmental Compliance  
8am to 5.30pm Mon - Thurs, 8am to 5pm Fri  
Phone 9970 1111

9 January 2007

D M & V Bubalo  
107 Orchard Street  
WARRIEWOOD NSW 2102

**COPY**

Dear Wally

**Re: Construction Certificate CC0545/06  
Property: 109 & 111 Orchard Street, Warriewood**

Please find enclosed your approved Construction Certificate and stamped plans.

**Did you know that work is unable to commence until such time as a completed Notification of Commencement Form has been submitted to Council at least two (2) days prior to starting work? Not to do so is a breach of the Environmental Planning and Assessment Act, which would result in a Penalty Infringement Notice (on-the-spot fine) being issued to you and the builder.**

To assist you please find enclosed a "Notification of Commencement and Principal Certifying Authority Service Agreement" form to enable you to appoint Pittwater Council as your Principal Certifying Authority (PCA).

If appointed as the PCA, Council would engage the services of The Certification Group to carry out the various inspections as indicated in Part 6 of the enclosed "Notification of Commencement and Principal Certifying Authority Service Agreement" form and ultimately issue an Occupation Certificate for your development. Appointment and inspection fees are also detailed in the enclosed form.


Council will endorse your completed "Notice of Commencement and Principal Certifying Authority Service Agreement" form and return a copy to the applicant with advice as to the required critical stage and other inspections to be carried out on behalf of Council.

Council is committed to providing a quality service and would value your business in being appointed as the Principal Certifying Authority for your development.

Yours faithfully

**Development Compliance Group**

Per:



This form is valid from  
1<sup>st</sup> July 2006 to 30 June 2007



Pittwater Council  
PO Box 882  
Mona Vale NSW 1660  
Tel: (612) 9970 1111  
Fax: (612) 9970 7150

## NOTIFICATION OF COMMENCEMENT & PRINCIPAL CERTIFYING AUTHORITY SERVICE AGREEMENT

under Environmental Planning and Assessment Act 1979 sections 81A  
(2) (b) (ii) or (c), or (4) (b) (ii) or (c), 86 (1) and (2)

### About this form

- Use this form to appoint Pittwater Council as the Principal Certifying Authority (PCA) to carry out nominated inspections of the building / subdivision works and to issue the required Occupation Certificate
- This form must be submitted to Pittwater Council a minimum of two (2) days prior to the commencement of works.

### Who can complete this form?

- The owner of the property or the person having the benefit of the development consent.  
*Note: The builder or other contractor cannot complete this form unless they are also the owner of the property.*

### Applicant's Checklist

- Read this document ☐
- Complete pages 1, 2 & 3 ☐
- Sign on page 8 ☐
- Attach a copy of Owner Builder Permit or Home Owner Warranty Insurance Certificate. ☐

### Payment of fees

- Critical Stage Inspection fees (refer to Part 6e of this form) must be paid at the time of booking the inspection.

This form is valid from  
1<sup>st</sup> July 2006 to 30 June 2007

## 1. DEVELOPMENT INFORMATION

### 1a) DEVELOPMENT CONSENT

Development Application No: N0457/05	Determination Date: 04/04/2006
--------------------------------------	--------------------------------

### 1b) CONSTRUCTION CERTIFICATE

Construction Certificate No: CC0545/06	Date of Issue: 09/01/2007
--	---------------------------

### 1c) DEVELOPMENT DETAILS

Type of Work:  <input type="checkbox"/> New Building <input type="checkbox"/> Additions / Alterations <input type="checkbox"/> Subdivision	Brief description of development:
--	-----------------------------------

### 1d) SITE DETAILS

Unit/Suite:	Street No: 109 & 111	Street: Orchard Street
Suburb: Warriewood	Lot No: 2 & 3	Deposit /Strata Plan: 715324 & 734891

### 1e) VALUE OF PROPOSED DEVELOPMENT

Estimated value of proposed works: \$ .....
---

### 1f) DATE WORK IS TO COMMENCE

Minimum notice of two (2) days is required to be given prior to commencement of works.
Date of commencement: .....

## 2. APPLICANT DETAILS

**Note:** The builder or other contractor cannot complete this form unless they are also the owner of the property.

Name (owner):	
Postal Address:  .....  .....  .....	Phone (H/B): .....  Mobile: .....  Email: .....  Fax: .....



This form is valid from  
1<sup>st</sup> July 2006 to 30 June 2007

3. PRINCIPAL CERTIFYING AUTHORITY

PITTWATER COUNCIL

PO Box 882  
Mona Vale NSW 1660

Ph: 9970 1111  
Fax: 9970 7150

4. COMPLIANCE WITH DEVELOPMENT CONSENT

Have all conditions to be addressed prior to the commencement of works been satisfied?

☐ YES

☐ NO (see Note below)

**Note:** If **NO** work must not commence.

Please be aware that failure to address these conditions may leave you liable and in Breach of the Environmental Planning and Assessment Act 1979 (as amended). Penalties may include an on-the-spot fine and/or legal action.

If you are uncertain as to these requirements please contact Council's Development Compliance Group.

5. WHO WILL BE DOING THE BUILDING WORKS?

☐ Owner Builder

Owner Builders Permit No: .....

Copy of Owner Builders permit  
attached:

☐ YES

*If you are an Owner-Builder for the residential building work exceeding \$5000 you must apply for a permit at NSW Office of Fair Trading, 1 Fitzwilliam Street, Parramatta NSW 2150 Australia.  
Tel: 61 2 98950111 Fax: 61 2 9895 0222.*

OR

☐ Licensed Builder

Builder's License Number .....

Name of Builder: .....

Phone: .....

Contact person: .....

Mobile: .....

Address: .....

Fax: .....

Insurance Company:

Insurance Certificate attached:

☐ Yes

☐ No – statement attached & signed by each owner of the property that the reasonable market cost of the labour & materials to be used is less than \$12,000.

*If you are using a licensed builder for residential building work exceeding \$12,000 you must obtain Home Building Act Insurance. A certificate of insurance must be provided with this application.*

**6. RESPONSIBILITIES OF THE PRINCIPAL CERTIFYING AUTHORITY (PCA)**

**6a) Quality of Service:**

Pittwater Council will carry out PCA and inspection services in a professional manner and in accordance with the requirements of the Environmental Planning & Assessment Act 1979 and Council's Code of Conduct.

**6b) Site Signage:**

Pittwater Council will erect a sign on the site to advise the general public of the contact details of the PCA. The sign will be erected during the Commencement Inspection, on Council's acceptance of appointment as PCA.

**6c) Inspections:**

Pittwater Council officers will undertake the Critical Stage Inspections of the work during construction and prior to issuing an Occupation Certificate to ascertain compliance of specified stages of construction with the Development Consent, Construction Certificate, Building Code of Australia & relevant standards of construction. On appointment as the PCA, Pittwater Council will notify the applicant in writing of the Critical Stage & other Inspections.

**6d) Critical Stage and other inspections:**

The following stages of construction are required to be inspected by Council (as indicated by a ✓ in the relevant box).

**Note: Council's Development Compliance Officer will complete this section of the form.**

- ☒ Footing Inspection (prior to placement of concrete)
- ☒ Slab and other Steel Inspection (prior to placement of concrete)
- ☐ Frame Inspection (prior to fixing floor, wall & ceiling linings)
- ☐ Wet Area Waterproofing Inspection (prior to covering)
- ☒ Stormwater Inspection (prior to backfilling of trenches)
- ☐ Swimming Pool Safety Fence Inspection (prior to placement of water)
- ☒ Final Inspection (all works completed and prior to occupation of the building)



Office Use Only

**Note:** Should the building works be completed in parts & not all aspects of a Critical Stage Inspection be ready, additional inspections maybe required – with a further inspection fee payable.

*Eg: If two slabs are prepared at separate times, two separate inspection bookings and fees are required.*

**6e) Critical Stage and other inspection fees:**

An inspection fee is required for each inspection identified in Part 6d of this form. A separate inspection fee is required for each Critical Stage Inspection. Should works be either incomplete or incorrect at the time of inspection a further separate reinspection fee will be required.

Each inspection fee must be paid at the time of requesting the inspection.

**Critical Stage or other Inspection Fee current to 30 June 2007      \$210      (Code: HINR)**

**Final Inspection Fee Scale current to 30 June 2007      \$280      (Code: FOCC)**

*Please note that a failure to give correct notification of required inspections may result in the issuing of a Penalty Infringement Notice (PIN or on-the-spot fine) and/or a Notice and Order by Council and may result in refusal to issue an Occupation Certificate.*

**6f) Inspection Results:**

Pittwater Council will provide written confirmation to the applicant of the inspection results and indicate if satisfactory or if additional works are required prior to reinspection.

**7. RESPONSIBILITIES OF THE APPLICANT**

**7a) Inspections:**

A minimum of forty-eight (48) hours notice (excluding weekends and public holidays) must be given to Council to enable the specified stages of construction to be inspected as identified in Item 6 of this agreement.

Should an inspection be missed, the applicant must advise Council in writing (as soon as practicable after the event) of that fact, the circumstances causing the inspection to be missed and supporting documentation for Council's consideration. In such cases, the inspection fee, which would normally have been required, must still be paid.

The applicant must ensure that the Principal Contractor (Builder/Owner Builder) is advised of the required inspections and that the directions of Council's Development Compliance Officers are to be observed to ensure compliance with the Development Consent, Construction Certificate, Building Code of Australia and the terms of this agreement.

**7b) Booking of Inspections:**

The applicant shall request an inspection via Pittwater Council's Inspection Booking Hotline on **9970 1300**. A minimum of forty-eight (48) hours notice must be provided to Council to arrange for completion of the inspection.

At the time of requesting the inspection, Pittwater Council will confirm an inspection time and day, name of inspecting officer and mobile contact number.

Building works must **not** proceed to the subsequent stages of construction prior to obtaining a satisfactory inspection from Council for each stage of construction specified in Item 6d of this agreement.

7c) Site Signage:

The applicant is responsible to maintain the PCA signage provided by Pittwater Council at the site until the work is completed.

The applicant is responsible to ensure that the Owner Builder or Principal Contractor (Builder) provide a rigid durable sign at the site, visible from the public place and maintained at the site until the work is completed. Such a sign shall display: (a) the name, address and telephone number of the person; (b) an after-hours emergency telephone number for the person and (c) stating "Unauthorised Entry to the Site is Prohibited".

7d) Compliance with the Development Consent and Construction Certificate:

All works must be carried out in accordance with the terms and conditions of Council's Development Consent and the Construction Certificate and relevant provisions of the Building Code of Australia and Environmental Planning and Assessment Act 1979.

Development Consent and a Construction Certificate must be obtained for any amendments or variations to the development, prior to the commencement of the amendment or variation.

Works not in accordance with the approval and Building Code of Australia may result in the refusal to issue an Occupation Certificate. Council may also serve a Notice and Order to comply with the approval and/or the institution of legal proceedings.

7e) Structural Engineering and Other Specialist Details:

The following details are to be forwarded to the PCA prior to commencement of the relevant stage of construction (as identified by a ✓). The details are to be prepared by a suitably qualified person to confirm compliance with the relevant provisions of the BCA and Australian Standards:

**Note: Council's Development Compliance Officer will complete this section of the form.**

Office Use Only

- ☐ Timber framing details including bracing and tie-downs
- ☐ Roof construction or roof truss details
- ☐ Termite control measures
- ☐ Glazing details
- ☐ Mechanical ventilation details
- ☐ Wet area construction details
- ☐ Details of fire resisting construction
- ☐ Details of essential fire and other safety measures
- ☐ Sound transmission and insulation details
- ☐ Details of compliance with development consent conditions

No  
ticked:

Office Use Only

7f) Certification of Works:

To ensure compliance with the Construction Certificate and Building Code of Australia (BCA), the applicant is to provide certification, verifying that the following specialist matters (identified by a ✓) have been carried out.

Each certification must:

- reference the approved Construction Certificate number, property address, relevant provisions of the BCA, Australian Standards and approved drawings.
- be prepared by an accredited certifier or other suitably qualified & experienced person to the satisfaction of Pittwater Council.

**Note: Council's Development Compliance Officer will complete this section of the form.**

☒ Survey detailing building setbacks, reduced levels of floors & ridge by a registered surveyor

☐ Shoring and support for adjoining premises and structures by a structural engineer

☐ Contiguous piers or piling by a structural engineer

☐ Underpinning works by a structural engineer

☒ Structural engineering works by a structural engineer on all structural building elements –(i.e. footings, slabs, floor, wall & roof framing)

Office Use Only

☐ Retaining walls by a structural engineer

☒ Inspection and approval of all subsurface drains by the Geotechnical engineer before backfilling is completed

☒ Inspection and approval of all fill material by the Geotechnical engineer before backfilling is completed

☒ Stormwater drainage works by a hydraulic engineer and surveyor

☐ Landscaping works by the landscaper

☐ Condition of trees by an Arborist

☐ Mechanical ventilation by a mechanical engineer

☐ Termite control and protection by a licensed pest controller

☐ Waterproofing of wet areas by a licensed waterproofer or licensed builder

☐ Installation of glazing by a licensed builder

☐ Installation of smoke alarm systems by a licensed electrician

☐ Plumbing and Drainage Contractors certificate indicating that sewer/waste water system has been installed and completed in accordance with the Sydney Water requirements.

☐ Completion of construction requirements in a bush fire prone area by a competent person

☐ Completion of requirements listed in the BASIX Certificate by a competent person

☐ Fire resisting construction systems by a competent person

☐ Smoke hazard management systems by a competent person

☐ Essential fire safety and other safety measures by a competent person (Form 15a)

Office Use Only

- ☐ Completion of Bushland Management requirements by a suitably qualified person.
- ☐ Installation of Waste Water Management System by a suitably qualified person
- ☐ Installation of the inclined lift by a suitably qualified person
- ☐ Installation of sound attenuation measures by an acoustic engineer

7g) Occupation Certificate:

A *Final* Occupation Certificate must be obtained from the PCA prior to the occupation or use of a new building (or part of a building) or prior to the change of an existing building use/classification. An inspection fee is to be paid to the PCA in accordance with the fee scale in Part 6e of this agreement.

An application may be made to the PCA for an *Interim* Occupation Certificate, which will be considered in accordance with the provisions of the Environmental Planning and Assessment Act 1979 and conditions of development consent.

Only the Principal Certifying Authority can issue an Occupation Certificate and the Environmental Planning and Assessment Act 1979 contains penalty provisions for failing to obtain a required Occupation Certificate.

An application for an *Interim* or *Final* Occupation Certificate must be accompanied by a final or interim *fire safety certificates* as required by the EP&A Regulations, Clauses 80E or 80F for buildings other than Class 1 and 10.

7h) Miscellaneous requirements:

The applicant is required to ensure that valid public liability insurance cover to the value of \$10,000,000 (minimum) is held by the applicant and/or builder.

The applicant is required to notify Council, in writing, of any change in the details or address of the applicant or head contractor.

Pittwater Council may cancel the agreement if there is a breach of the agreement.

8. **YOUR SIGNATURE**

I accept the terms and conditions of this service agreement, including the associated payment of fees and appoint Pittwater Council as the Principal Certifying Authority for the subject development.

Signature: ..... Date: .....

9. **COUNCIL'S AGREEMENT TO APPOINTMENT**


The relevant details in Parts 6d, 7e & 7f of this agreement have been completed and I acknowledge the appointment of Pittwater Council as the Principal Certifying Authority.


Officer's name: ..... on behalf of Pittwater Council

Officer's signature: ..... Date: .....

**PRIVACY AND PERSONAL INFORMATION PROTECTION NOTICE**

Purpose of collection:	To enable Council to act as the Principal Certifying Authority for the development.
Intended recipients:	Pittwater Council staff
Supply:	The information is required by legislation
Consequence of Non-provision:	Your application may not be accepted, not processed or rejected for lack of information
Storage:	Pittwater Council will store details of this form in a register that can be viewed by the public.
Retention period:	Hard copies will be destroyed after 7 years and electronic records will be kept indefinitely.
Please contact Council if this information you have provided is incorrect or changes.	



Title:  <b>LANDSCAPE PLAN</b>  	Client:  <b>V,D AND M BUBALO</b>	Scale:  <b>1:1000</b>
	Project:  <b>7 &amp; 7A ORCHARD STREET</b>	Issue:  <b>A</b>
		Drawing No:  <b>05004</b>

FILE COPY

level 4  
104 Mount Street  
North Sydney 2060

PO Box 515  
North Sydney 2059  
Australia

telephone: (02) 9957 1619  
facsimile: (02) 9957 1291  
email: reception@patbrit.com.au  
ABN 89 003 220 228

**Patterson Britton  
& Partners Pty Ltd**

Newcastle Office  
8 Telford Street  
Newcastle East 2300

PO Box 668  
Newcastle 2300  
Australia

telephone: (02) 4928 7777  
facsimile: (02) 4926 2111  
email: mail@newcastle.patbrit.com.au

consulting engineers

lt467002mjs-bubalo cert letter.doc

W, D and M Bubalo  
107 Orchard Street  
WARRIEWOOD NSW 2102  
Fax 9970 8454

PITTWATER COUNCIL  
CC 0545/06

CC The Certification Group  
Attention Mr Wayne Treble  
Fax 9944 6330

Re

10 JAN 2007 Wednesday, 22 November 2006

Attention: Mr Wally Bubalo

Dear Sir

**107 ORCHARD STREET, WARRIEWOOD – ROAD AND SUBDIVISION WATER  
MANAGEMENT CERTIFICATION**

I refer to your request to provide a summary of the engineering documents produced by Patterson Britton & Partners (PBP) to date for both the access road and subdivision DA's at the above address.

It is understood that the above clarification is required to assist in the assessment of your Construction Certificate (CC) applications by the Certification Group (*ie on behalf of Pittwater Council*). In this regard we refer to the two letters from the Certification Group dated 8<sup>th</sup> November, 2006 (*Ref ADD INFO. 0546.06 and ADD INFO. 0545.06*).

In terms of engineering/water management related CC requirements:

- DA N0457/05 was utilised to determine CC requirements for the Access Road (*refer to Appendix F*); and
- DA N0152/02 was utilised to determine CC requirements for the subdivision (*refer to Appendix G*)

In summary, PBP have produced the following engineering related documentation to date:

1. Access Road design drawings – CC Issue (*refer to Appendix A*);
2. Subdivision stormwater management design drawings – CC Issue (*refer to Appendix B*);
3. CC Stage Water Management Report (*refer to Appendix C*);
4. Waste Management Plan – CC Issue (*refer to Appendix D*); and
5. Traffic Management Plan – CC Issue (*refer to Appendix E*).

Principals



Greg Britton BE MEngSc FIEAust Andrew Chitty BE MIEAust CPEng Peter Coltman BE MEngSc MIEAust  
Bruce Druery BE Dip Sc(Geol) M AppSc MIEAust Paul Harvey-Walker BE FIEAust David McConnell BSc MIEAust  
Joe Marson BE MEngSc FIEAust Andrew Patterson BE FIEAust Christopher Thomas BE MEngSc MIEAust  
Mark Tooker BSc(Eng) MEngSc FIEAust CPEng Michael Wright BE MEngSc MIEAust

Senior Associates

Steve Barrett Simon Batt BE MIEAust Paul Macinante BE MEnvEngSc MIEAust Ben Patterson BE MIEAust  
Marc Roberts BE Michael Shaw BE MIEAust CPEng

Associates

Stephen Aebi BE MIEAust Neville Boyes OMIEAust Scot Cranfield Cameron Druery BE MIEAust  
Adam Knight BE MIEAust CPEng Cameron Smith BE MEngSc MIEAust CPEng  
Alexandra Stone BE MIEAust Chris Yates BE MIEAust





In addition, PBP utilised the services of Geotechnique Pty Ltd to assist in geotechnical considerations for the proposed access road (*refer to report at **Appendix F***).

Based on the above documentation and in response to the Certification Group correspondence dated 8<sup>th</sup> November, 2006 we confirm the following:

**Access Road DA Conditions (DA N0457/05) – CC 0545/06**


- Condition B1 is understood to be satisfied by PBP document at **Appendix D** (*ie waste management plan*);
- We confirm a shared trench arrangement is proposed as shown on the Drawings at **Appendix A** to locate all new utility services for the lots below ground and clear of landscaping in accordance with Condition B3;
- Condition C5 is understood to be satisfied by PBP document at **Appendix A** (*ie detailed road design drawings*);
- Conditions C1 is understood to be satisfied by PBP document at **Appendix A** (*ie detailed road design drawings*);
- We herby certify that the engineering design and plans for road and drainage works comply with the requirements of Conditions C1, C2 and C3 – Michael Shaw CPEng MIEAust (1126270) NPER (*compliance with Condition C4*); and
- For assistance in compliance with Conditions C9 and C10 see attached Geotechnical report at **Appendix H**.

**Subdivision DA Conditions (DA N0152/02) – CC 0546/06**

- Condition B25, B26, B27 and B28 are understood to be satisfied by PBP document at **Appendix A** (*ie detailed road design drawings*);
- We herby certify that the engineering design and plans for road and drainage works comply with the requirements of Conditions B26, B27 and B28 – Michael Shaw CPEng MIEAust (1126270) NPER (*compliance with Condition B28a*);
- Condition B29 is understood to be satisfied by PBP document at **Appendix B** (*Drawing 4670-01-06*). Note we confirm all silt fences are proposed to be contained wholly within 107 Orchard St – see mark up on Drawing 4670-01-06;
- Condition B29a is also understood to be satisfied by the above document (*ie Drawing 4670-01-06 at **Appendix B***);
- Condition B29b is understood to be satisfied by PBP document at **Appendix E** (*ie traffic management plan*) and **Appendix B**;
- We herby certify that the water management report at **Appendix C** and associated plans complies with the requirements of Conditions B30, and B31 – Michael Shaw CPEng MIEAust (1126270) NPER (*compliance with Condition B32*);
- The drawings at **Appendix A** show that the works comply with Condition D31; and
- We confirm a shared trench arrangement is proposed as shown on the Drawings at **Appendix A** to locate all new utility services for the lots below ground and clear of landscaping in accordance with Condition D44.

We trust this information is satisfactory. Should you have any further enquiries, please do not hesitate to contact either Michael Shaw or myself on (02) 9957 1619.

Yours faithfully  
**PATTERSON BRITTON**



Mark Tooker  
Principal

Review / Verification by      Date

.....



Ross McWhirter, Project Leader - Warriewood Infrastructure  
8am to 5pm Mon - Fri  
Phone 9970 1207 Mobile 0419 629 007

19 October 2006

W D Bubalo  
7 Orchard Street  
**WARRIEWOOD NSW 2102**

Dear Sir,

**Re: Engineering Plans for Orchard Street and Access Road**

This correspondence refers to Clause C1 (second paragraph) of Consent No. N0457/05, and Clause B26 (second paragraph) of Consent No. N0152/02 requiring engineering plans and specifications within the public road reserve to be submitted and approved by Council prior to the issue of any Construction Certificate.

This advice refers to Orchard Street Access Road, Warriewood Civil Road Design prepared by Patterson Britton & Partners Pty Ltd: -

Drawing No. 4670, Sheet: -

01 Issue E, 02 Issue D, 03 Issue E, 04 Issue E, 05 Issue E, 06 Issue D, 07 Issue E,  
08 Issue E, 09 Issue E, 10 Issue D, 11 Issue D, 12 Issue D and 13 Issue A.

The Plans are satisfactory subject to the following:

- All Engineering Plans to be certified by an experienced Civil Engineer who is NPER accredited by the Institution of Engineers (Australia), in accordance with Condition C4 of Consent No. N0457/05 and Condition B28a of Consent No. N0152/02.

Yours faithfully

  
James Payne  
**MANAGER - URBAN INFRASTRUCTURE**

PITTWATER COUNCIL  
CC 0545106

Re  
10 JAN 2007

level 4  
104 Mount Street  
North Sydney 2060

PO Box 515  
North Sydney 2059  
Australia

telephone (02) 9957 1619  
facsimile (02) 9957 1291  
email: reception@patbrit.com.au  
A.C.N. 003 220 228  
A.B.N. 89 003 220 228

**Patterson Britton  
& Partners Pty Ltd**

Newcastle Office  
14 Telford Street  
Newcastle East 2300

PO Box 668  
Newcastle 2300  
Australia

telephone (02) 4928 7777  
facsimile (02) 4926 2111  
email: mail@newcastle.patbrit.com.au

**consulting engineers**

## **Waste Management Plan**

**DA No. N0457/05 and N0152/02  
Construction of Private Accessway and Subdivision of 7  
Orchard St into 10 lots**

**7 Orchard St, Warriewood Valley, NSW for WD & M Bubalo**

This waste management plan has been prepared in accordance with Appendix 4 of the Warriewood Valley Urban Land Release DCP 29 to demonstrate the following:

1. The volume and type of waste to be generated;
2. How waste is to be stored and treated on site;
3. How residual waste is to be disposed of; and
4. How ongoing waste management will operate.


### **1. Description of Proposed Works**

It is proposed that the existing property at 7 Orchard Rd, Warriewood Valley be subdivided into 10 individual lots and all associated infrastructure required to service the lots be constructed. In summary, this would entail the following works:

- Half width road construction along the private access road frontage of the lots as per PBP design Drawings contained in **Appendix A**;
- Half width reconstruction of the Orchard Road frontage as per PBP design Drawings contained in **Appendix A**;
- Provision of all utility infrastructure (ie gas, telecommunications, water, sewer and power) to serve the proposed new lots and to maintain connection to existing lots;
- Provision of all required stormwater management systems as per PBP report titled "Warriewood Valley 7&7A Orchard St (Part of Sector 10) - Water Management Report Construction Certificate Stage" (Issue 1 September 2005) and associated PBP design Drawings contained within **Appendix B**;
- Bulk earthworks within the new lots; and
- Demolition of existing structures within the new lots.

### **2. Volume and Type of Waste to be Generated by the Development**

The major component of waste to be generated by the proposed works is related to bulk earthworks activities.



RL  
10 JAN 2007

Bulk earthworks will be undertaken simultaneously within both the lots and proposed roadways (*ie on the lots and within Orchard Rd and the private accessway*).

In summary, the proposed roadworks will result in a net surplus of cut material which will have to be transported from the site to be disposed at an appropriate landfill facility (*ie Kimbriki*). Special fill material will also have to be brought into the site for construction of the road (*ie from Kimbriki*). However, within the proposed lot areas, cut and fill works will generally be undertaken without the need to import or export material from the site. Some of the suitable spoil generated by the proposed roadworks will also be used to fill areas within the lots themselves.

A summary of the proposed bulk earthworks for the site is as follows:

- Lots – minor regrading (*generally balanced cut and fill*), use of cut material from road works as fill for batters on western edge of lots and minor filling on southern lots;
- Road cut works – approximately 1000m<sup>3</sup>, of which 700m<sup>3</sup> is assumed to be clean and would be stockpiled for reuse on the lots as mentioned above. The remaining 300m<sup>3</sup> would need to be removed from the site and disposed of at Kimbriki;
- Road fill works – approximately 600m<sup>3</sup> of material is required for the batters on the east side of the road, 100m<sup>3</sup> would be used to fill the southern lots and 400m<sup>3</sup> of special fill (*ie base-course and sub-base material*) is required to be imported to construct the roads themselves;
- Hence, an estimated 300m<sup>3</sup> is proposed to be trucked out from the site and 400m<sup>3</sup> is proposed to be trucked in.

The 300m<sup>3</sup> of material to be removed from the site would consist of the old AC pavement and inert but unsuitable/uncompactable fill. The 400m<sup>3</sup> to be imported to the site would consist of recycled roadbase and basecourse material from Kimbriki.

In addition to the above, the following waste material is also likely to be generated as part of the roadworks:

- General Contractors waste (*ie litter, offcuts etc*); and
- Effluent from portable on site toilets.

For the minor demolition works to be undertaken on the lots themselves, the following waste products are likely to be produced:

- Bricks;
- Concrete;
- Timber;
- Asbestos sheeting; and
- Vegetation.

### **3. Waste Management Plan**

A summary of the proposed waste management plan for the proposed construction and ultimate stages of the project is as follows:

- It is proposed to promote waste minimisation for both the construction and ultimate stages of the development. This will be achieved by using at source waste separation, use of recycled materials in construction and disposal of materials to facilities that separate and sell for reuse (*ie Kimbriki tip*);

- Topsoil stripped from the areas of proposed road construction and lot earthworks will be stored on site, treated for weeds and reused again as topsoil at completion of all works;
- Any good quality roadbase and/or basecourse material found beneath the existing road will be separated and stored on site for potential reuse beneath the new roadways;
- Any hardwood timbers within the existing structures to be demolished will be separated and stored onsite for reuse. Those timbers not used will be taken to Kimbriki tip (*an approved recycling facility*) for reuse by others;
- Any existing concrete slabs to be demolished will be separated and taken to Kimbriki tip (*an approved recycling facility*) for processing and reuse as roadbase or aggregate;
- Any existing bricks obtained from demolition of existing structures will be separated and taken to Kimbriki tip (*an approved recycling facility*) for processing and reuse as drainage aggregate;
- Any Asbestos contained within the existing structures on site will be removed in accordance with the appropriate health guidelines and disposed of at an approved facility (*ie Kimbriki tip*);
- Any proposed waste storage containers utilised during the construction phase will be stored wholly within the development site (*ie not in the public road reserve*);
- On site portable toilet waste will be removed from the site and disposed of at an approved facility; and
- General contractors waste will be removed from the site and disposed of at an approved facility.

No substantial ongoing waste management issues are envisaged from the proposed works in the post construction phase other than quarterly removal of gross pollutants from the proposed street drainage litter baskets to be located near the southern end of the new accessway. This material would be disposed of at an approved facility.

This DA only involves subdivision of the lots and no ongoing waste management issues are envisaged to arise from the empty lots, until housing is constructed, which is not part of this DA.


We trust this information is satisfactory. Should you have any further enquiries, please do not hesitate to contact either Michael Shaw or myself on (02)9957 1619.

Yours faithfully

**PATTERSON BRITTON**

  
Mark Tooker  
Principal

Review / Verification by      Date

 21/7/06

**Wayne Treble**

---

**From:** nathan\_huon@pittwater.nsw.gov.au  
**Sent:** Thursday, 2 November 2006 10:46 AM  
**To:** wayne@thecgroup.com.au  
**Subject:** DA N0152/02

Wayne,

As per our discussion Council confirms that the deferred commencement condition on consent N0152/02 has been satisfied and the consent is operative.

For your information Ross McWhirter has confirmed via a file note on Council's datatworks records system the following:

*The letter to Barry L. Doyle dated 12 September 2005 provides evidence that the Deferred Commencement condition of Consent No. N0152/02 has been satisfied. The water management for the subdivision is to be in accordance with the Water Management Report prepared by Patterson Britton and Partners Pty Ltd. The report requires the stormwater from the site to be disposed through the stormwater drainage system constructed by Stockland. The necessary drainage infrastructure, easements and S88B Instruments are in place to cater for the 7 Orchard Street subdivision.*

Ross McWhirter

PROJECT LEADER WARRIEWOOD INFRASTRUCTURE

Regards

Nathan Huon

Project Manager (Land Release Projects)

This email and any materials contained or attached to it ("Contents") may contain confidential information. If you are not the intended recipient contact the sender immediately, delete the communication from your system and destroy any copies.

The contents may also be subject to copyright. Any unauthorised copying, disclosure or distribution of the contents is strictly prohibited.

Any views expressed in the contents are those of the individual sender, except where the sender specifically states them to be the views of Pittwater Council. Pittwater Council makes no implied or express warranty that the integrity of this communication has been maintained. The contents may contain errors, computer viruses or have been subject to interference in transmission.

Pittwater Council

[www.pittwater.nsw.gov.au](http://www.pittwater.nsw.gov.au)

This e-mail has been scanned for viruses by MCI's Internet Managed Scanning Services - powered by MessageLabs. For further information visit <http://www.mci.com>

PITTWATER COUNCIL COMMUNICATIONS  
CC 0545/06

KL  
10 JAN 2007

2/11/2006



**Pittwater  
Council**

ABN 61 340 837 871 Telephone (02) 9970 1111 Facsimile (02) 9970 7150  
Postal Address: P.O. Box 862, Mona Vale NSW 1660, DX 9018 Mona Vale

pittwater.nsw.gov.au e-mail: pittwater\_council@pittwater.nsw.gov.au

Business Hours:  
8.00am to 5.30pm, Monday to Friday

**DA No: N0152/02**

5 October 2006

MILEVA BUBALO  
107 ORCHARD STREET  
WARRIEWOOD NSW 2102

Dear Sir/Madam

Extension of Development Consent for subdivision of one lot into ten lots.

**7 ORCHARD STREET, WARRIEWOOD NSW 2102.**

Please be advised that an extension of the above Development Consent has been granted to 20/10/2007.

Yours faithfully

**Anna Williams  
PRINCIPAL DEVELOPMENT OFFICER**





**Pittwater  
Council**

ABN 61 340 837 871 Telephone (02) 9970 1111 Facsimile (02) 9970 7150  
Postal Address: P.O. Box 882, Mona Vale NSW 1660, DX 9018 Mona Vale

<http://www.pittwaterga.com.au> e-mail: [pittwater\\_council@pittwater.nsw.gov.au](mailto:pittwater_council@pittwater.nsw.gov.au)

Ross McWhirter, Project Leader - Warriewood Infrastructure  
8am to 5pm Mon - Fri  
Phone 9970 1207 Mobile 0419 629 007

12 September 2005

Barry L. Doyle  
64 Cassia Street  
DEE WHY NSW 2099

Dear Sir,

**Re: 7 Orchard Street, Warriewood**

Reference is made to your letter dated 23 March 2005 and Council's letter dated 30 March 2005 concerning stormwater drainage for Sector 10.

Council advises that the completed stormwater drainage works in Stages 4 and 5 of Sector 10 to facilitate external drainage of the subdivision at 7 Orchard Street have been completed and are satisfactory. The subdivision certificates also provide the drainage easements and Section 88B Instrument requirements necessary for stormwater drainage of 7 Orchard Street. Accordingly, Council has released the Subdivision Certificates for Stages 4 and 5.

Yours faithfully

*R. McWhirter*

Ross McWhirter  
**PROJECT LEADER - WARRIEWOOD INFRASTRUCTURE**

cc. Stockland Development Pty Ltd



Case Number: 76708

V & D & M Bubalo  
c/- Byrne & Associates Pty Ltd

Dear Applicant

**REVISED NOTICE OF REQUIREMENTS**  
for  
**SECTION 73 SUBDIVIDER/DEVELOPER COMPLIANCE CERTIFICATE**  
(Sydney Water Act 1994, Part 6, Division 9)

This Notice of Requirements letter supersedes the Notice letter issued on 9 May 2005

**Developer:** V & D & M Bubalo  
**Your reference:** 20516  
**Development address:** 7 Orchard Street Warriewood  
**Development description:** Residential subdivision of one lot into ten (10) Torrens Title lots  
**Consent No:** N0152/02 by Pittwater Council of 31 March 2005.  
**Your application:** 31 March 2005

Your attention is drawn to the requirements in this Notice that must be met before a Section 73 Subdivider/ Developer Compliance Certificate (the Certificate) can be issued. This Notice is given by Sydney Water on 26 May 2006 and the requirements are to apply for a year from that date after which the requirements will be updated on reapplication.

You must engage your current or another authorised Water Servicing Coordinator (the Coordinator) to manage the design and construction of the Water and Sewer works that you must provide, at your cost, to service your development. Upon your meeting of this and all other requirements, the Certificate will be issued to you by your Coordinator.

For a list of authorised Coordinators, either see [www.sydneywater.com.au](http://www.sydneywater.com.au) and refer to *Developing Your Land* under *Building Developing and Plumbing*, or call 13 20 92. Coordinators may provide you with a quote or advice regarding costs for their and other supplier's services/ works as well as other Sydney Water costs.

The Coordinator generally will be the single point of contact between you and Sydney Water and can answer any questions in the first instance you may have on Sydney Water's developer process and developer charges.

**SUMMARY OF REQUIREMENTS TO OBTAIN A CERTIFICATE:**

You must:

1. Engage a Coordinator prior to signing the enclosed Agreement.
2. Sign both copies of the enclosed Agreement and lodge with the Coordinator.
3. Consequent to signing the Agreement, build Water and Sewer works at your cost, pay associated charges and note advice on existing service availability.

PITWATER COUNCIL CO-ORDINATOR  
CC 0545/06

Re  
10 JAN 2007

Formatted

Deleted: we can update

Deleted: 1

SUMMARY OF REQUIREMENTS

4. Pay a total of \$75,981 in charges identified in Section 4.

Please Note:

- You need to obtain a Tax Invoice before you can pay this charge in person at a Sydney Water Customer Service Centre (located in the City, Wollongong and Katoomba). If you require an invoice, please contact your Coordinator.

5. Complete any special requirements detailed in Section 5.

**DETAILED REQUIREMENTS**

1. Water Servicing Coordinator

You must engage an authorised Coordinator to manage the design and construction of works that you must provide, at your cost, to service your development.

2. Major Works Agreement.

After you engage a Coordinator, you will need to sign and lodge both copies of the enclosed Major Works Agreement with your nominated Coordinator. The agreement identifies the responsibilities of Sydney Water, the Coordinator and you (the Developer) for your development's Water and Sewer construction. After execution by Sydney Water, one copy will be returned to your authorised Coordinator.

*Note: The authorisation of the Coordinator must be current at all times throughout the project.*

3. Water and Sewer works.

The water and sewer works you construct and pay for under the Agreement entered into must include extensions to Sydney Water's systems to ensure each lot in your development has:

- a frontage to a watermain to enable a separate connection and meter.
- a sewer main with a connection point within the boundary of each lot.

**Sydney Water's specific requirements for your project are:**

**Water**

An extension to the existing 100mm CICL diameter water main in Orchard Street is required to service lots 703 to 710. As the proposed water main is to be laid in a proposed Right of Carriageway, you will need to create an easement over the main in favour of Sydney Water. Details regarding the easement creation are set out in this letter in item 5 under Special Conditions.

Lot 701 and 702 have frontage to the existing 100mm CICL diameter water main in Orchard Street.

\*Each lot will require a separate 20mm connection, 20mm water service and 20mm water meter.

Currently the existing property (with three flats/dwellings) is connected to the existing water main via a 25mm connection and served by a 40mm water meter. \*This set-up will need to be adjusted to reflect the above arrangement for torrens title lots. Each of the existing dwellings will need to be reconnected to the existing/proposed water mains. A copy of your licensed plumbers signed Plumbing and Drainage Compliance Certificate will need to be submitted to Sydney Water when the work is satisfactory completed.

PITTSBURGH COUNCIL  
00 0545/06

KE  
10 JAN 2007

### Sewer

An extension to the existing 150mm PVCp sewers (constructed by the adjoining developer) to enable each lot of the subdivision to have a point of connection within their respective property boundaries. Each lot must have separate sewer house service lines wholly within their boundaries.

Please be aware that floor levels must be able to meet Sydney Water's soffit requirements for property connection and drainage.

- **Future Adjustments**

If the watermain/ sewer main located in the footway/ your property is found, after the issue of this notice, to require adjustment or deviation this work must be undertaken in conjunction with the abovementioned extension. The conditions of this notice will apply including engagement of a Coordinator, signing of an agreement, and completion at no cost to Sydney Water **prior to the issue of the Certificate** (see also section on building plan stamping). After the design has been completed and its nature and complexity considered, Sydney Water may require your lodgement of an appropriate security that will be refunded upon completion.

*Note: If construction must take place on neighbouring properties, written consent to enter for design/construction purposes must be obtained from the relevant property owners and tenants using Sydney Water's Permission to Enter form(s). Your Coordinator has copies of the form(s) that are also available on the Internet at the address as above and can negotiate on your behalf. All items on the form(s) must be addressed including payment of compensation and consideration of design and construction alternatives to avoid/minimise impacts. You will be responsible for all costs of mediation necessary to resolve disputes with affect property owners/tenants. Please allow sufficient time for entry issues to be concluded.*

In providing these works to Sydney Water you will need to pay project management, survey, design and construction costs **directly to your suppliers**. These costs may include Sydney Water charges for:

- Watermain shutdown and disinfection
- Connection of new mains to Sydney Water system(s)
- Design and construction audit fees
- **Contract administration on project finalisation**
- Creation or modification of Sydney Water interests in land (eg. easements)
- Further application fees for staged developments
- Redress under Sydney Water's Customer Contract.

Your Coordinator can advise you about these costs and how they may be quoted.

PITMAN'S COUNCIL COURT

00 0546/06

Rel  
10 JAN 2007

## 4. Developer charges.

Development Servicing Plan (DSP)	Basis of Calculation	Charge (\$) for Applicable period (26/05/06-30/06/06)	Charge (\$) for Applicable Period (01/07/06-25/05/07)
Warringah Water DSP Area	Residential Development Density >0-20 dwellings per ha band 10 dwellings @ \$871 = \$8,710 Less Credit of \$2,613 for previous payment/ use plus Upsizing	\$ 6,097	STBA
	Development Density >0-20 dwellings per ha band 10 dwellings @ \$192 = \$1,920 Less Credit of \$576 for previous payment/ use	\$ 1,344	STBA
Warriewood Sewer DSP Area	Residential Development Density >0-20 dwellings per ha band 10 dwellings @ \$6,765 = \$67,650 Less Credit of \$0 for previous payment/ use plus Upsizing	\$67,650	STBA
	Development Density >0-20 dwellings per ha band 10 dwellings @ \$89 = \$890 Less Credit of \$0 for previous payment/ use	\$ 890	STBA
Reticulation Recovery  13623WW	37 metres of 150mm PVCp sewer. The adjoining developer laid two sewer 'lead-outs' to service your property.	\$16,027	STBA
<b>DEVELOPER CHARGES TOTAL:</b> [OFFICE USE- Invoice Charges total- Developer \$73,747 and Upsizing \$ 2,234]		\$92,008	STBA

Notes:

## New IPART Determination:

- Sydney Water has commenced its five-yearly review of developer charges in accordance with IPART Determination No. 9 2000. Developer charges will be revised to take into account Sydney Water's latest capital expenditure projections as well as current development forecasts. The revised developer charges and associated DSP's will be placed on public exhibition for 30 working days in April/ May 2006. You will have the opportunity to comment on the new charges during this time. The new developer charges will then take effect from 1 July 2006.
- Some of the new charges may significantly decrease, others may increase and additional charges may be introduced. Consequently it may be to your advantage to consider when you will make payment. That is:
  - If payment is made before 1 July 2006, then Sydney Water must apply the charges quoted in this Notice; or
  - If payment is made on or after 1 July 2006, then:
    - If the new charges have decreased you will only have to pay the new lower charges that will be advised to you when you seek to make payment; or
    - If the new charges have increased and/or additional charges introduced then Sydney Water will apply the old lower charges, plus any CPI increase, for the remainder of the applicable period of this Notice. After that time, Sydney Water is required to apply the new higher and/ or additional charges when you re-apply.

Deleted: 1

Formatted: Bullets and Numbering

PHE WATER COUNCIL CONF

CC 0596/06

10 JAN 2007

Sydney Water is unable to advise possible new charges until the DSPs are exhibited in April/ May 2006, or to advise firm new charges until registration of the DSPs with IPART in June 2006. Contact your Coordinator for advice on charges during this period.

#### Annual CPI adjustment from 1 July:

- If you do not pay the charges identified in column 3 of the above table by 30 June (and as advised above), the total will be adjusted for inflation (based on the weighted average of the capital cities CPI for the 12 months to the end of the previous March) from 1 July for the balance of the 12 month period. The charge from 1 July is only shown in column 4 if the inflation figure is known.

Also:

- DSP charges** are a contribution towards the cost of systems (eg pipelines & treatment plants), which serve your development. They have been calculated using base developer charges that cannot be changed or waived by Sydney Water having been established in Plan(s), available on request, and registered with the Independent Pricing and Regulatory Tribunal (IPART) under its relevant Determination. For further details, and a copy of the IPART Act 1992 including section 31 that refers to arbitration rights, see the IPART web site [www.IPART.nsw.gov.au](http://www.IPART.nsw.gov.au). Costs of arbitration, if appropriate, are borne equally by you and Sydney Water irrespective of outcome.
- These charges are directly payable to Sydney Water.
- You must pay your DSP charge before you will be given permission to connect your development to Sydney Water's water/sewer systems.**
- Reticulation Recovery Charges** recover part of the cost of works that have been provided by Sydney Water or other developers that benefit your development. This charge has been calculated before your detailed designs are completed. If later design investigation shows your development will be connected to other main/s, the Reticulation Recovery charge may be varied and/or you may need to construct other works.

Deleted: Sydney

Deleted: 0

Deleted: review/

#### 5. Special requirements

- Creation of easement over water main**

Each water main to be constructed for purpose of the *approval* in land other than a dedicated public road or pathway must have an appropriate easement in favour of Sydney Water created at your cost.

Your Design Consultant must take this requirement into account when preparing the design for the works.

A *compliance certificate* in respect of the *approval* will not be granted until:-

- the water main(s) have been constructed; and
- adequate drainage facilities have been provided to allow for the flushing of the main by Sydney Water without the discharge of water onto private property (Sydney Water's rights in this regard must be incorporated in the Easement documentation); and
- a survey has been carried out, at your cost, prior to backfilling of trenches, to define the centreline of each water main; and
- all plans and documents relating to the easement have been approved by Sydney Water; and
- payment of Sydney Water's related costs have been made; and
- the required security has been lodged with Sydney Water in respect of each easement pending its registration.

PITTWATER COUNCIL CONF

CC 05/06

10 JAN 2007

Specific details with respect to each easement to be created may be obtained from Sydney Water's Group Property, 5<sup>th</sup> Floor, 115-123 Bathurst Street, Sydney, 2000.  
Ph: (02) 9350-5670 or (02) 9350-5647.

- **Provide a copy of the Plumbing and Drainage Compliance Certificate**

It will be necessary to provide a signed copy of the above Certificate to Sydney Water following the capping of the existing 25mm drilling, disconnection of the 40mm water meter and the reconnection of the existing dwellings to the existing/ proposed water mains. This work will need to be carried out by a licensed plumber.

#### **GENERAL INFORMATION**

- **Stamping and approval of your engineering and building plans.**

**While NOT a requirement for the Certificate**, you are reminded that, on development of each lot, building plans must be stamped and approved at either:

- a Quick Check agency (for an agency list either see [www.sydneywater.com.au](http://www.sydneywater.com.au), refer to Quick Check under *Building Developing and Plumbing* or call 13 20 92); or
- a Sydney Water Customer Service Centre.

Approval is required as construction/building works (eg earthworks, roadworks, drainage, landscaping, excavation, foundation works) may impact on existing Sydney Water assets (eg water, sewer and stormwater mains). Approval of the plans may take up to 21 days and the results may affect the construction/building activities.

Approval is required as construction/building works (eg earthworks, roadworks, drainage, landscaping, excavation, foundation works) may impact on existing Sydney Water assets (eg water and sewer mains). Approval of the plans may take up to 21 days and the results may affect these activities.

#### **POSSIBLE FUTURE COSTS**

Requirements in this Notice relate to your Certificate application and may not cover all aspects of Sydney Water's involvement with your development. During design and construction of your development other Sydney Water fees/requirements may be necessary, including:

- construction/building plan stamping fees including fees to ensure the protection of Sydney Water assets
- plumbing and drainage inspection costs for private service lines (including property service connection and/ or disconnection and inspection fees)
- council fire fighting requirements (if not catered for by your current Sydney Water main). You should investigate fire fighting facility requirements for your development as soon as possible, including a standard pressure inquiry to Sydney Water if needed.

---

**END OF NOTICE**

PITMAY & CO. COUNCIL  
CC 0546/06

Re  
10 JAN 2007

level 2  
104 Mount Street  
North Sydney 2060

PO Box 515  
North Sydney 2059  
Australia

telephone: (02) 9957 1619  
facsimile: (02) 9957 1291  
reception@patbrit.com.au  
ABN 89 003 220 228

**Patterson Britton  
& Partners Pty Ltd**

Newcastle Office  
8 Telford Street  
Newcastle East 2300

PO Box 668  
Newcastle 2300  
Australia

telephone: (02) 4928 7777  
facsimile: (02) 4926 2111  
mail@newcastle.patbrit.com.au

consulting engineers

lt467002mjs060713-bubalo cons traf man plan.doc

WD & M Bubalo  
7 Orchard Street  
Warriewood NSW 2102

PATTERSON BRITTON & PARTNERS  
CC 0545106

Friday, 21 July 2006

Attention: Mr W Bubalo

Dear Sir

10 JAN 2007

**DA N0457/05 & N0152/02 ORCHARD ST, WARRIWOOD – CONSTRUCTION PHASE  
TRAFFIC MANAGEMENT PLAN**

As requested following is the proposed construction phase traffic management plan for both the lot and accessway/Orchard Rd works proposed at the above site.

**1. Description of Works**

It is proposed that the existing property at 7 Orchard Rd, Warriewood Valley be subdivided into 10 individual lots and all associated infrastructure required to service the lots be constructed. In summary, this would entail the following works:

- Half width road construction along the private access road frontage of the lots as per PBP design Drawings contained in **Appendix A**;
- Half width reconstruction of the Orchard Road frontage as per PBP design Drawings contained in **Appendix A**;
- Provision of all utility infrastructure (ie gas, telecommunications, water, sewer and power) to serve the proposed new lots and to maintain connection to existing lots;
- Provision of all required stormwater management systems as per PBP report titled "Warriewood Valley 7&7A Orchard St (Part of Sector 10) - Water Management Report Construction Certificate Stage" (Issue 1 September 2005) and associated PBP design Drawings contained within **Appendix B**; and
- Bulk earthworks within the new lots.

**2. Proposed Earthworks**

Bulk earthworks will be undertaken simultaneously within both the lots and proposed roadways (ie on the lots and within Orchard Rd and the private accessway).

In summary, the proposed roadworks will result in a net surplus of cut material which will have to be transported from the site to be disposed at an appropriate landfill facility (ie Kimbriki).



**Principals**

Greg Britton BE MEngSc FIEAust Andrew Chitty BE MIEAust CPEng Peter Coltman BE MEngSc MIEAust  
Bruce Druery BE Dip Sc(Geol) M AppSc MIEAust Paul Harvey-Walker BE FIEAust David McConnell BSc MIEAust  
Joe Marson BE MEngSc FIEAust Andrew Patterson BE FIEAust Christopher Thomas BE MEngSc MIEAust  
Mark Tooker BSc(Eng) MEngSc FIEAust CPEng Michael Wright BE MEngSc MIEAust

**Senior Associates**

Steve Barrett Simon Batt BE MIEAust Paul Macinante BE MEnvEngSc MIEAust Ben Patterson BE MIEAust  
Marc Roberts BE Michael Shaw BE MIEAust CPEng

**Associates**

Stephen Aebi BE MIEAust Neville Boyes OMIEAust Scot Cranfield Cameron Druery BE MIEAust  
Tod Hall BA (Bio) MEM (Coastal) Grad Dip (Bus-HR) Adam Knight BE MIEAust CPEng  
Cameron Smith BE MEngSc MIEAust CPEng Alexandra Stone BE MIEAust Chris Yates BE MIEAust





10 JAN 2007

Special fill material will also have to be brought into the site for construction of the road (*ie from Kimbriki*). However, within the proposed lot areas, cut and fill works will generally be undertaken without the need to import or export material from the site. Some of the suitable spoil generated by the proposed roadworks will also be used to fill areas within the lots themselves.

A summary of the proposed bulk earthworks for the site is as follows:

- Lots – minor regrading (*generally balanced cut and fill*), use of cut material from road works as fill for batters on western edge of lots and minor filling on southern lots;
- Road cut works – approximately 1000m<sup>3</sup>, of which 700m<sup>3</sup> is assumed to be clean and would be stockpiled for reuse on the lots as mentioned above. The remaining 300m<sup>3</sup> would need to be removed from the site and disposed of at Kimbriki;
- Road fill works – approximately 600m<sup>3</sup> of material is required for the batters on the east side of the road, 100m<sup>3</sup> would be used to fill the southern lots and 400m<sup>3</sup> of special fill (*ie base-course and sub-base material*) is required to be imported to construct the roads themselves;
- Hence, an estimated 300m<sup>3</sup> is proposed to be trucked out from the site and 400m<sup>3</sup> is proposed to be trucked in.

### 3. Estimated Truck Movements and Proposed Route

The proposed destination for all waste disposal and supply of all new road construction materials is the Kimbriki Recycling and Waste Disposal Facility on Mona Vale Rd at Tumbledown Dick.

Assuming 20t trucks are used for the works, it is estimated that 20 truck movements per day over 3 days (*ie during Council stipulated working hours only of 7am to 5pm Monday – Friday and 7am to 1pm on Saturdays. No works to be undertaken on Sunday or Public Holidays*) would be required during the material disposal phase of the works and 20 truck movements per day for 4 days for the road fill import phase of the works. If road fill material is able to be stockpiled on the site during the excavation phase for the roadworks, then the number of truck movements could potentially be reduced by half with trucks dropping off waste and picking up base-course/sub-base material in the same trip.

Hence, the estimated worst case truck movements is predicted to be 20 trucks per day over 7 days, however it is suspected that the actual movements will be considerably less.

**Figure 1** shows the proposed truck route to and from the site to Kimbriki. This route has been selected as Council have advised that no truck movements are permitted along Garden St south of Mullet Creek and on Mona Vale Road between Tumbledown Dick and Mona Vale.

### 4. Maintaining Access to all Existing Lots in Orchard Road During The Works

So as to provide continued access to all existing properties during the works, a construction phase traffic management plan has been developed as shown in **Drawing 4670-13 at Appendix A**.

In summary the road works would be undertaken in two phases. The first phase would entail construction of parts of the accessway to the east of the existing bitumen pavement and the southern half of the orchard Road frontage. This would allow continued access to all existing

properties via the existing bitumen road. Following completion of the phase 1 works, all traffic would then be transferred to the new road constructed in Phase 1 whilst the areas to the west of the phase 1 works are completed.

Temporary traffic management signage, barricades and fencing would be used during both phases of the works as shown in **Drawing 4670-13 at Appendix A** so as to maintain safety during the works.

#### **5. Sediment, Erosion and Dust Control**


A sediment and erosion control strategy for the proposed road works is shown on **Drawing 4670-12 at Appendix A**.

A sediment and erosion control strategy for the proposed lot works is shown on **Drawing 4670-01-06 at Appendix B**.


Manual watering down of exposed earthworks areas would be undertaken for the purposes of dust control. In addition, all loads transported from the site would be covered and all fencing used around the perimeter of the works would incorporate a geotextile cover to assist in capture of dust.

We trust this information is satisfactory. Should you have any further enquiries, please do not hesitate to contact either Michael Shaw or myself on (02) 9957 1619.


Yours faithfully  
**PATTERSON BRITTON**

  
Mark Tooker  
Principal

Review / Verification by      Date

      21/7/06

PITWATER COUNCIL CONS  
00 0545/06


  
10 JAN 2007

**FIGURES**

PITTWATER COUNCIL CONSTRUCTION  
CC 0545/06

*Re*  
10 JAN 2007







---

## APPENDIX A

---

PITDWATER COUNCIL COMPTON  
CC 0545/06

*Re*  
10 JAN 2007






[illegible]

1. SOLE DRAINAGE AND SEWAGE CONTROL MEASURES SHALL BE IMPLEMENTED IN ACCORDANCE WITH THE STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION, 10TH EDITION, MARCH 2004.
2. THE STANDARD RECOMMENDED BY THE 1ST DEPARTMENT OF HIGHWAYS "RULE BOOK" TITLE "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION", 6TH EDITION, MARCH 2004.
3. THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL INFORM THEIR STAFF OF THEIR OBLIGATIONS UNDER THIS DRAINAGE AND SEWAGE CONTROL SECTION.
4. ALL DRAINAGE AND ALL SEWAGE CONTROL MEASURES SHALL BE INSTALLED AT ALL SLOPE CHANGES AND AT ALL POINTS WHERE THE ROADWAY CROSSES A DRAINAGE AREA.
5. SLEET SOCKS AND GEOTEXTILE FILTER FABRIC SHALL BE INSTALLED AT ALL DRAINAGE REST PITS.
6. ALL DRAINAGE AND SEWAGE CONTROL MEASURES ARE TO BE INSTALLED PRIOR TO COMPLETION OF CONSTRUCTION.
7. ALL SEWAGE CONTROL STRUCTURES SHALL BE INSPECTED AFTER EACH RAINFALL EVENT TO ENSURE THEY ARE NOT Clogged AND ALL TRAPPED SEWAGE TO BE REMOVED TO THE APPROPRIATE STORMDRAIN.
8. STABILISE ALL COMPLETED ROAD BATTERS WITH HYDROSEAL.

### CONSTRUCTION MATERIALS

1. MATERIALS AND WORKMANSHIP SHALL BE THE BEST OF THEIR RESPECTIVE KINDS, AND UNLESS OTHERWISE SPECIFIED, SHALL CONFORM TO THE RELEVANT AUSTRALIAN STANDARDS.
2. SUFFICIENT NOTICE SHALL BE GIVEN BY THE CONTRACTOR TO THE SUPERINTENDENT TO ENABLE AN APPROPRIATE INSPECTION OF THE MATERIALS ARE TO BE SUTAINLY STACKED TO FACILITATE EXAMINATION.
3. WHERE THE CONTRACTOR SUPPLIES MATERIALS OF A MIXED OR POOR QUANTITY, THE SUPERINTENDENT SHALL HAVE THE POWER TO REQUIRE THE CONTRACTOR TO PICK OUT AND STACK THE BEST AND TO HAVE THOSE UNREMARKABLE REMOVED FROM THE SITE OF THE WORKS.

[illegible]

REC'D - COMMUNITY  
00 0545106  
Re  
10 JAN 2007

[illegible]

**Patterson Britton  
& Partners Pty Ltd**  
consulting engineers


ORCHARD STREET ACCESS ROAD  
WARRIEWOOD

**GENERAL NOTES & SPECIFICATIONS**  
**SHEET 2 OF 2**  
**AND SHARED SERVICE TRENCH DETAIL**

Working No.	4670-03
due	D
Mod File No.	4670-02
Ref.(s)	









CC 0545/06

ACCESS ROAD TYPICAL SECTION  
HORIZONTAL 1:100  
VERTICAL 1:50

CUL-DE-SAC PLAN  
1:100



DRIVEWAY LONG SECTION  
SCALE HORIZONTAL 1:100  
SCALE VERTICAL 1:50
















CUL-DE-SAC KERB DEVELOPMENT  
SCALE HORIZONTAL 1:100  
SCALE VERTICAL 1:50

DRG STATUS: FOR CONSTRUCTION

Issue	Details of Issue	Drawn	Checked	Approved	Date
E	ISSUED FOR CONSTRUCTION	MS	MS	MS	21.07.06
D	CUL-DE-SAC KERB DEVELOPMENT	MS	MS	MS	18.07.06
B-1	ISSUED FOR TENDER	MS	MS	MS	18.07.06
B	ISSUED FOR APPROVALS	MS	MS	MS	18.07.06
A	ISSUED FOR REVIEW	MS	MS	MS	25.07.06

Client	V, D AND M BUBALO	Project	ORCHARD STREET ACCESS ROAD WARRIEWOOD
Consultant	Patterson Britton & Partners Pty Ltd consulting engineers	Drawn	MS
Check	MS	Approved	MS
Date	21.07.06	Issue	E
Code	4670-05	Code	4670-05
Scale	1:100	Scale	1:100

094606  
 Re  
 10 JAN 2007



PROPOSED RETAINING WALL

TRANSITION IV IN 4H BATTER TO PROPOSED RETAINING WALL



**DRG STATUS : FOR CONSTRUCTION**

Issue	Drawn	Checked	Approved	Date
D	ISSUED FOR CONSTRUCTION	MS	MS	21/07/06
C	ISSUED FOR CONSTRUCTION	MS	MS	08/11/05
B	ISSUED FOR APPROVALS	MS	MS	18/02/05
A	ISSUED FOR REVIEW	MS	MS	23/01/05





















DETAILS SHOWN IN THE JOINTS ARE THE PROPERTY OF THE CLIENT. THE DRAWING APPROVAL PROCESS DRAMAS ARE OWNED BY PATTERSON & PARTNERS. THE ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND IN THE REGISTER/TRANSITION FORM No. 5.2.2 HELD BY PATTERSON & PARTNERS.

**Patterson Britton & Partners Pty Ltd**  
 consulting engineers  
 Level 4  
 100/100 Pitt Street  
 Sydney NSW 2000  
 Telephone: (02) 977 1231  
 Fax: (02) 977 1232  
 A.C.N. 101 228 228

**V.D AND M BUSALO**  
 Project  
 ORCHARD STREET ACCESS ROAD  
 WARREWOOD

**ACCESS ROAD DESIGN CROSS SECTION SHEET 1 OF 3**  
 Drawing No. 4870-06  
 Issue D  
 Cad File No. 4870-06  
 Title

10 JAN 2007



**ACCESS ROAD**

V, D AND M BUBALO

§ 87(2)(b) § 87(2)(b)

2015  
 2014  
 2013  
 2012  
 2011  
 2010  
 2009  
 2008  
 2007  
 2006  
 2005  
 2004  
 2003  
 2002  
 2001  
 2000  
 1999  
 1998  
 1997  
 1996  
 1995  
 1994  
 1993  
 1992  
 1991  
 1990  
 1989  
 1988  
 1987  
 1986  
 1985  
 1984  
 1983  
 1982  
 1981  
 1980  
 1979  
 1978  
 1977  
 1976  
 1975  
 1974  
 1973  
 1972  
 1971  
 1970  
 1969  
 1968  
 1967  
 1966  
 1965  
 1964  
 1963  
 1962  
 1961  
 1960  
 1959  
 1958  
 1957  
 1956  
 1955  
 1954  
 1953  
 1952  
 1951  
 1950  
 1949  
 1948  
 1947  
 1946  
 1945  
 1944  
 1943  
 1942  
 1941  
 1940  
 1939  
 1938  
 1937  
 1936  
 1935  
 1934  
 1933  
 1932  
 1931  
 1930  
 1929  
 1928  
 1927  
 1926  
 1925  
 1924  
 1923  
 1922  
 1921  
 1920  
 1919  
 1918  
 1917  
 1916  
 1915  
 1914  
 1913  
 1912  
 1911  
 1910  
 1909  
 1908  
 1907  
 1906  
 1905  
 1904  
 1903  
 1902  
 1901  
 1900  
 1899  
 1898  
 1897  
 1896  
 1895  
 1894  
 1893  
 1892  
 1891  
 1890  
 1889  
 1888  
 1887  
 1886  
 1885  
 1884  
 1883  
 1882  
 1881  
 1880  
 1879  
 1878  
 1877  
 1876  
 1875  
 1874  
 1873  
 1872  
 1871  
 1870  
 1869  
 1868  
 1867  
 1866  
 1865  
 1864  
 1863  
 1862  
 1861  
 1860  
 1859  
 1858  
 1857  
 1856  
 1855  
 1854  
 1853  
 1852  
 1851  
 1850  
 1849  
 1848  
 1847  
 1846  
 1845  
 1844  
 1843  
 1842  
 1841  
 1840  
 1839  
 1838  
 1837  
 1836  
 1835  
 1834  
 1833  
 1832  
 1831  
 1830  
 1829  
 1828  
 1827  
 1826  
 1825  
 1824  
 1823  
 1822  
 1821  
 1820  
 1819  
 1818  
 1817  
 1816  
 1815  
 1814  
 1813  
 1812  
 1811  
 1810  
 1809  
 1808  
 1807  
 1806  
 1805  
 1804  
 1803  
 1802  
 1801  
 1800  
 1799  
 1798  
 1797  
 1796  
 1795  
 1794  
 1793  
 1792  
 1791  
 1790  
 1789  
 1788  
 1787  
 1786  
 1785  
 1784  
 1783  
 1782  
 1781  
 1780  
 1779  
 1778  
 1777  
 1776  
 1775  
 1774  
 1773  
 1772  
 1771  
 1770  
 1769  
 1768  
 1767  
 1766  
 1765  
 1764  
 1763  
 1762  
 1761  
 1760  
 1759  
 1758  
 1757  
 1756  
 1755  
 1754  
 1753  
 1752  
 1751  
 1750  
 1749  
 1748  
 1747  
 1746  
 1745  
 1744  
 1743  
 1742  
 1741  
 1740  
 1739  
 1738  
 1737  
 1736  
 1735  
 1734  
 1733  
 1732  
 1731  
 1730  
 1729  
 1728  
 1727  
 1726  
 1725  
 1724  
 1723  
 1722  
 1721  
 1720  
 1719  
 1718  
 1717  
 1716  
 1715  
 1714  
 1713  
 1712  
 1711  
 1710  
 1709  
 1708  
 1707  
 1706  
 1705  
 1704  
 1703  
 1702  
 1701  
 1700  
 1699  
 1698  
 1697  
 1696  
 1695  
 1694  
 1693  
 1692  
 1691  
 1690  
 1689  
 1688  
 1687  
 1686  
 1685  
 1684  
 1683  
 1682  
 1681  
 1680  
 1679  
 1678  
 1677  
 1676  
 1675  
 1674  
 1673  
 1672  
 1671  
 1670  
 1669  
 1668  
 1667  
 1666  
 1665  
 1664  
 1663  
 1662  
 1661  
 1660  
 1659  
 1658  
 1657  
 1656  
 1655  
 1654  
 1653  
 1652  
 1651  
 1650  
 1649  
 1648  
 1647  
 1646  
 1645  
 1644  
 1643  
 1642  
 1641  
 1640  
 1639  
 1638  
 1637  
 1636  
 1635  
 1634  
 1633  
 1632  
 1631  
 1630  
 1629  
 1628  
 1627  
 1626  
 1625  
 1624  
 1623  
 1622  
 1621  
 1620  
 1619  
 1618  
 1617  
 1616  
 1615  
 1614  
 1613  
 1612  
 1611  
 1610  
 1609  
 1608  
 1607  
 1606  
 1605  
 1604  
 1603  
 1602  
 1601  
 1600  
 1599  
 1598  
 1597  
 1596  
 1595  
 1594  
 1593  
 1592  
 1591  
 1590  
 1589  
 1588  
 1587  
 1586  
 1585  
 1584  
 1583  
 1582  
 1581  
 1580  
 1579  
 1578  
 1577  
 1576  
 1575  
 1574  
 1573  
 1572  
 1571  
 1570  
 1569  
 1568  
 1567  
 1566  
 1565  
 1564  
 1563  
 1562  
 1561

ITALS SHOWN IN THE ADJACENT ISSUE  
RECORDS INDICATE THE STAGES UNDERTAKEN  
IN DRAWING APPROVAL PROCESS DRAWINGS

100

[illegible]

Some

Q

EN CROSS SECTION  
SHEET 2 OF 3

11

Falconson Elliott  
& Partners Pty Ltd

0002 4040 2000  
0002 4040 2000

THE DRAWING APPROVAL PROCESS DRAWING TO BE ONLY TO BE USED WHEN APPROVED BY WATSON BRITTON & PARTNERS AND THEN

FOOKER	21.07.06
	06.11.03

	ISSUED FOR CONSTRUCTION	MS	ARG	MS
1				
2				
3				
4				
5				
6				
7				
8				
9				
10				
11				
12				
13				
14				
15				
16				
17				
18				
19				
20				
21				
22				
23				
24				
25				
26				
27				
28				
29				
30				
31				
32				
33				
34				
35				
36				
37				
38				
39				
40				
41				
42				
43				
44				
45				
46				
47				
48				
49				
50				
51				
52				
53				
54				
55				
56				
57				
58				
59				
60				
61				
62				
63				
64				
65				
66				
67				
68				
69				
70				
71				
72				
73				
74				
75				
76				
77				
78				
79				
80				
81				
82				
83				
84				
85				
86				
87				
88				
89				
90				
91				
92				
93				
94				
95				
96				
97				
98				
99				
100				

NOTES

**DRG STATUS: FOR CONSTRUCTION**


[illegible][illegible]

NOTES


PITTSWATER COUNCIL CON'S

00054506


10 JAN 2007




CH 205.00




CH 202.98




CH 200.00




CH 195.00




CH 190.00




CH 185.00




CH 180.00




CH 175.00




CH 170.00




CH 165.00




CH 160.00



CH 155.00



CH 207.57



DRG STATUS: FOR CONSTRUCTION


Issue	Design	Existing	Offset	Drawn	Checked	Approved	Date
D	MS	MS	MS	MS	MS	MS	21.07.06
C	MS	MS	MS	MS	MS	MS	08.11.06
B	MS	MS	MS	MS	MS	MS	15.02.05
A	MS	MS	MS	MS	MS	MS	25.01.05

BRITTON PATTERSON & PARTNERS PTY LTD  
CONSULTING ENGINEERS  
155 Mount Street  
Sydney NSW 2000  
Tel: (02) 9237 1271  
Fax: (02) 9237 1272  
A.C.N. 902 222 226

Client: V, D AND M BUSALO  
Project: ORCHARD STREET ACCESS ROAD  
WARREWOOD


Access Road  
DESIGN CROSS SECTION  
SHEET 3 OF 3

Drawing No: 4670-08  
Issue: D  
Date File No: 4670-08  
Rev'd: 0




SECTION 1:10

STANDARD GUTTER CROSSING (LAYBACK)




150mm KERB & GUTTER 1:10





STANDARD VEHICULAR CROSSING 1:25

TYPICAL ROAD PAVEMENT DETAIL



- NOTE
1. THE BASE COURSE MATERIAL CAN BE DGGSD OR RECYCLED CONCRETE SATISFYING THE REQUIREMENTS OF DGGSD STANDARD PROVIDED IN THE RITA 2001 SPECIFICATION. THE SUB-BASE MATERIAL CAN BE CRUSHED SANDSTONE OR RECYCLED CONCRETE SATISFYING THE REQUIREMENTS OF DGGSD STANDARD PROVIDED IN THE RITA 2001 SPECIFICATION.
  2. THE MINIMUM COMPACTION DRY DENSITY RATIO'S ARE AS FOLLOWS (AS1289.2.4.1-1993):
    - BASE COURSE 98% MODIFIED
    - SUB-BASE 95% MODIFIED
    - SUB-GRAD 90% STANDARD OR DENSITY RATIO OF 85%
  3. PAVEMENT SEARING COURSE TO CONSIST OF A 30mm THICK LAYER OF AC14 OVERLAIN BY A 20mm THICK LAYER OF AC14.
  4. FOR DETAILS OF THE REQUIRED ROAD PAVEMENT REFER TO PAVEMENT DESIGN REPORT PREPARED BY SITECHARGE PVT LTD.
- FOR JANUARY 2004



LEGEND

EXISTING SURFACE CONTOUR (1m INTERVAL)

PROPOSED SURFACE CONTOUR (0.5m INTERVAL)

25.0

PROPOSED SURFACE CONTOURS 1:300

DRG STATUS: FOR CONSTRUCTION

Issue	Details of Issues	Date	Chk'd	Appr'd
D	ISSUED FOR CONSTRUCTION	21.07.06	MS	MS
C	CUL-DE-SAC REVISED	08.11.05	MS	MS
B	ISSUED FOR APPROVALS	15.02.05	ARG	MS
A	ISSUED FOR REVIEW	25.07.05	ARG	MS

INITIALS SHOWN IN THE QUANTITY SCHEDULE RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED BY PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE DRAWING. THE DRAWING IS TO BE USED IN THE REGISTER/TRANSFERRAL FORM No.2.2.2. HELD BY PATTERSON BRITTON & PARTNERS


Project  
ORCHARD STREET ACCESS ROAD  
WARRIEWOOD

Client  
V. D AND M BUBALO

Consulting engineers  
Patterson Britton & Partners Pty Ltd  
consulting engineers  
120 Wilson Street  
North Sydney NSW 1585  
Telephone (02) 9617 1271  
Fax (02) 9617 1271  
Email: info@patterson.com.au  
A.C.N. 002 262 226


Drawing No. 4870-09  
Issue D  
Cadd File No. 4870-09  
Proj. No.

PROPOSED SURFACE CONTOURS AND PAVEMENT DESIGN



PITWATER COUNCIL CONSTRUCTION  
CC 0945/06

Re  
10 JAN 2007




PIT SCHEDULE

PIT	HEAST	WORTH	TYPE (RTA)
1/1	341050.448	827044.218	S&J (MIL 600x600) 3m UNITS - ON GRADE
2/1	341050.448	827054.207	S&J (MIL 600x600) 2.4m UNITS - S&J
3/1	341051.083	827048.282	900x900 DRAINAGE JUNCTION PIT - JUNCTION SEALED, HEAVY DUTY LID (CLASS D)

NOTES

1. INSTALL RIGAL ENHANCED PIT INSERT (RE LITTER BASKET) ON EQUIVALENT TO SUIT AT PITS 1/1 AND 2/1.

DRAINAGE PLAN  
1:100



DRG STATUS: TENDER, NOT FOR CONSTRUCTION

Rev	Issued For	By	Check'd	Date
0	ISSUED FOR CONSTRUCTION	MS	MS	21.07.06
1	QA-QE-SAC REVISED	MS	MS	08.11.05
2	ISSUED FOR APPROVALS	FC	MS	18.02.05
3	ISSUED FOR REVIEW	ARG	MS	25.01.06

NOTES SHOWN IN THE ADJACENT ISSUE SECOND INDICATES THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY VALID FOR THE STAGES UNDERTAKEN AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND IN THE REGISTER/TRANSMITTAL FORM HAS.2.2. HELD BY PATTERSON BRITTON & PARTNERS

Paterson Britton & Partners Pty Ltd  
consulting engineers  
104 South Street  
Melbourne VIC 3006  
Phone: (03) 9607 1211  
Fax: (03) 9607 1212  
Email: info@pbr.com.au  
A.C.N. 100 261 226

Client: V. D AND M BUBALO

Project: ORCHARD STREET ACCESS ROAD  
WARREWOOD

STORMWATER DRAINAGE PLAN

Drawing No: 4670-10  
Issue: D  
Cod File No: 4670-10  
Rev(s):

Re  
10 JAN 2007

**DRG STATUS: FOR CONSTRUCTION**

1. FLOWS SHOWN ARE FOR A 20yr ARI EVENT.

INITIALS SHOWN IN THE ADVANCE ISSUE RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR ORG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE ORG REGISTER TRANSMITTAL FORM No.5.2.2 HELD BY PATTERSON BRITTON & PARTNERS

level 4  
104 Mount Street  
North Sydney 2060

tel: 002 9057 1818  
fax: 002 9057 1291  
e-mail: reception @ jaffalife  
A.C.N. 003 220 226

**Patterson Britton  
& Partners Pty Ltd**  
consulting engineers

Client	V, D AND M BUBALO
Project	ORCHARD STREET A WARREWOOD

Type

## STORMWATER DRAINAGE LONGITUDINAL SECTIONS

Drawing No. 1670-11

**D**

4670-1

[illegible]

Choinage	Invert Level	Surface Level	HGL
0	17.200	18	17.352
	16.300		16.865
12.57	16.300	17.1	16.503
			16.397
20.79	EXISTING	16.85	15.778

Q20=237L/s  
375mm CLASS 2  
7.2%

Q20=246L/s  
375mm CLASS 2  
MIN. 8.0%

Q20=246L/s  
375mm CLASS 2  
APPROX. 11.8%


1/2 - R/A TYPE SAS (2m LIMIT)

1/2 - R/A TYPE SAS 2.4m LIMIT

Existing

1/2 - JUNCTION





10-JAN 2007

1. A SHAKER CRD IS TO BE INSTALLED AT THE MAIN EXIT POINT FOR ALL CONSTRUCTION VEHICLES.
2. ANY REMAINING SEDIMENT/CLAY THAT IS DEPOSITED ON ENCHARD ROAD DOWNSTREAM OF THE SHAKER CRD IS TO BE REMOVED FROM THE ROAD DAILY BY A SWEEP/EXCAVATION TRUCK.

POSTING SURFACE CONTAINMENT  
(in INTERVAL)

PROPOSED SURFACE CONTOUR  
0.0-m INTERVAL

POSTING ORANGE SNAPE

BAND BAGS

WATER AND GEOTECHNICAL FILTER  
(REFER TO PAG. 506-7 IN THE "BLUE BOOK")

MESH AND GRAVEL INFILTRATION FILTER (REFER TO PAG. 508-9 IN THE "BLUE BOOK")

CONVERSION DRAWN (REFER TO PAG. 508-9 IN THE "BLUE BOOK")

SEDIMENT POND (REFER TO PAG. 508-9 IN THE "BLUE BOOK")

POSSIBLE STORMWATER LOCATION (REFER TO PAG. 508-9 IN THE "BLUE BOOK")

**PROG STATUS: FOR CONSTRUCTION**

	D	C	B	A	MS	ANG	US	Date
ISSUED FOR CONSTRUCTION					MS	ANG	M. TOWNER	21.07.98
CAL-GE-SAC REVISED					MS	ANG		08.11.98
ISSUED FOR APPROVALS					PC	ANG		18.02.99
ISSUED FOR REVIEW					ANG	ANG		25.01.99
Details of sample					Don't	Don't	Approved	Data

INITIALS SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG REGISTER/TRANSFERRAL FORM No.3.2.2. HELD BY PATTERSON BRITTON & PARTNERS

**Patterson Britton  
& Partners Pty Ltd**  
consulting engineers

V. D AND M BUBALO

ORCHARD STREET ACCESS ROAD  
WARRIEWOOD

EROSION AND SEDIMENT CONTROL PLAN	Drawing No.	4670-12
	Issue	D
	Code File No.	4670-12
	Drawn by	

N:M670 BUBALOD rmgjM670-12.dwg, Layout1, 21/07/2006 2:59:16 PM



PITTSWATER COUNCIL CONST.

**DRG STATUS: FOR CONSTRUCTION**


[illegible]

RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG REGISTER/TRANSMITTAL FORM No.3.2.2.

**David A. Patterson**  
164 Mount Street  
North Sydney 2060  
Telephone (02) 9957 1919  
Facsimile (02) 9957 1261  
e-mail [da.patterson@pattall.com.au](mailto:da.patterson@pattall.com.au)  
A.C.N. 602 228 224

Client	V. D. AND M. BUBALO
Project	ORCHARD STREET ACCESS ROAD WARREWOOD

4670-13	Issue <b>A</b>	Code File No: 4670-1-
<p align="center"><b>CONSTRUCTION PHASE TRAFFIC MANAGEMENT PLAN</b></p>		
<p>Project (s)</p>		



10 JAN 2007

**DRG STATUS: FOR CONSTRUCTION**


Drawing No.	4670-13
Issue	A
Cad File No.	4670-13
Xref.(s)	

**APPENDIX B**

ENTER COUNTY CODE	
ENTER CC	0545106
ENTER NAME	
ENTER SIGNATURE	<i>ke</i>
ENTER DATE	10 JAN 2007

# WARRIEWOOD VALLEY, 7 & 7A ORCHARD ST. (PART OF SECTOR 10) STORMWATER MANAGEMENT

for  
V, D AND M BUBALO



LOCALITY PLAN  
BY

**DRAWING LIST:**

4470-01-01	TITLE SHEET, LOCALITY PLAN AND DRAWING LIST
4470-01-02	GENERAL NOTES & SPECIFICATIONS
4470-01-03	SITE PLAN
4470-01-04	DRAINAGE LONG SECTIONS
4470-01-05	DRAINAGE DETAILS
4470-01-06	SEWERAGE AND EROSION CONTROL PLAN

PITIWATER COUNCIL CONSENT

CC 05A5/06

KA

1-0 JAN 2007

DRG STATUS: FOR TENDER

DRG No.	DRG Description	DRG Status	DRG Date
4470-01-01	TITLE SHEET, LOCALITY PLAN AND DRAWING LIST	Issued	4470-01-01
4470-01-02	GENERAL NOTES & SPECIFICATIONS	Issued	4470-01-02
4470-01-03	SITE PLAN	Issued	4470-01-03
4470-01-04	DRAINAGE LONG SECTIONS	Issued	4470-01-04
4470-01-05	DRAINAGE DETAILS	Issued	4470-01-05
4470-01-06	SEWERAGE AND EROSION CONTROL PLAN	Issued	4470-01-06

DRG No.	DRG Description	DRG Status	DRG Date
4470-01-01	TITLE SHEET, LOCALITY PLAN AND DRAWING LIST	Issued	4470-01-01
4470-01-02	GENERAL NOTES & SPECIFICATIONS	Issued	4470-01-02
4470-01-03	SITE PLAN	Issued	4470-01-03
4470-01-04	DRAINAGE LONG SECTIONS	Issued	4470-01-04
4470-01-05	DRAINAGE DETAILS	Issued	4470-01-05
4470-01-06	SEWERAGE AND EROSION CONTROL PLAN	Issued	4470-01-06

DRG No.	DRG Description	DRG Status	DRG Date
4470-01-01	TITLE SHEET, LOCALITY PLAN AND DRAWING LIST	Issued	4470-01-01
4470-01-02	GENERAL NOTES & SPECIFICATIONS	Issued	4470-01-02
4470-01-03	SITE PLAN	Issued	4470-01-03
4470-01-04	DRAINAGE LONG SECTIONS	Issued	4470-01-04
4470-01-05	DRAINAGE DETAILS	Issued	4470-01-05
4470-01-06	SEWERAGE AND EROSION CONTROL PLAN	Issued	4470-01-06

DRG No.	DRG Description	DRG Status	DRG Date
4470-01-01	TITLE SHEET, LOCALITY PLAN AND DRAWING LIST	Issued	4470-01-01
4470-01-02	GENERAL NOTES & SPECIFICATIONS	Issued	4470-01-02
4470-01-03	SITE PLAN	Issued	4470-01-03
4470-01-04	DRAINAGE LONG SECTIONS	Issued	4470-01-04
4470-01-05	DRAINAGE DETAILS	Issued	4470-01-05
4470-01-06	SEWERAGE AND EROSION CONTROL PLAN	Issued	4470-01-06

DRG No.	DRG Description	DRG Status	DRG Date
4470-01-01	TITLE SHEET, LOCALITY PLAN AND DRAWING LIST	Issued	4470-01-01
4470-01-02	GENERAL NOTES & SPECIFICATIONS	Issued	4470-01-02
4470-01-03	SITE PLAN	Issued	4470-01-03
4470-01-04	DRAINAGE LONG SECTIONS	Issued	4470-01-04
4470-01-05	DRAINAGE DETAILS	Issued	4470-01-05
4470-01-06	SEWERAGE AND EROSION CONTROL PLAN	Issued	4470-01-06

4. NO TREES ARE TO BE REMOVED (UNLESS INDICATED ON THE DRAWINGS) WITHOUT THE SUPERINTENDENT'S CONSENT.
5. NO WORK IS TO BE UNDERTAKEN ON PRIVATE PROPERTY WITHOUT CONSENT FROM THE SUPERINTENDENT & THE PROPERTY OWNERS.
6. DO NOT SCALE FROM THESE DRAWINGS UNLESS NOTED OTHERWISE.
7. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.
8. IF THE CONTRACTOR HAS ANY QUESTION, REQUIRES CLARIFICATION OF OR DISAGREES WITH ANY OF THE DIMENSIONS SHOWN ON THESE DRAWINGS, THE CONTRACTOR SHALL ADVISE THE SUPERINTENDENT BEFORE PROCEEDING.
9. ALL MATERIALS AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE REQUIREMENTS AND SPECIFICATIONS OF THE BY-LAWS AND THE ORDINANCES OF THE RELEVANT BUILDING AUTHORITIES, EXCEPT WHERE VARYED BY THESE DRAWINGS.
10. ALL SETOUT DIMENSIONS SHOWN SHALL BE VERIFIED BY THE CONTRACTOR ON SITE BEFORE WORK COMMENCES.

6. CRACKS SHALL BE FILLER WATERS NECESSARY TO PREVENT SOCCORING OF THE TRENCH OR THE LINE FROM BLOWING ON THE TRENCH BOTTOM ON THE UNDER.
7. THE CONTRACTOR MUST ENSURE THAT ANY EXISTING STRUCTURES TO BE EXCAVATED OR TO BE EXCAVATED TRENCHES ARE SUPPORTED OR PROTECTED TO PREVENT DAMAGE TO OR MOVEMENT OF THESE STRUCTURES.
8. THE CONTRACTOR MUST LEAVE ALL STORMWATER DRAINAGE WORKS UNCOVERED UNTIL ANY TESTING DEEMED NECESSARY BY THE SUPERINTENDENT HAS BEEN PERFORMED.
9. PIPE LAYING SHALL BEGIN AT THE DOWNSTREAM END OF THE LINE WITH THE SHORTEST LENGTH OF THE PIPE FACING UPSTREAM. THE BARREL OF EACH PIPE SHALL BE IN A SLOPE WITH THE DOWNING MATERIAL.

17. ALL BACKFILL FOR STORMWATER DRAINAGE WORKS IS TO BE COMPACTED TO A MINIMUM OF 95% RELATIVE COMPACTION BY THE STANDARD PROCTOR METHOD. LAYERS NOT EXCEEDING 300mm LOOSE THICKNESS AND COMPACTED WITHOUT DAMAGING OR DISPLACING THE PREVIOUS.
18. ALL BACKFILL FOR STORMWATER PITS AND PPES SHALL BE COMPACTED TO AT LEAST 65% OF THE MAXIMUM DRY DENSITY AND GRADED IN ACCORDANCE WITH AS 3600 (2003).
19. UNLESS SPECIFIED OTHERWISE ALL DRAINAGE PITS TO BE CAST IN SITU. CHARGE OF CONCRETE TO BE USED SHALL HAVE ITS OWN TEST CERTIFICATE. REINFORCEMENT SHALL COMPLY WITH THE REQUIREMENTS OF ASTM. WELDED WIRE REINFORCING SHALL COMPLY WITH AS/NZS 4672.
20. CALVERSED STEEL STEP BARS AT SPACINGS OF 0.3m ARE REQUIRED ON ALL DRAINAGE PIT CREATED THAN 1.0m DEEP.

1000

26. JMWING ENDS SHALL BE THOROUGHLY CLEANED BEFORE THE JMWING IS MADE. JMWING SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS USING JOINTING SOLVENT AND PRIMER.
27. JMWING PIPES SHALL BE TRANSPORTED, HANDLED AND STACKED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
28. JMWING PIPE LAYING SHALL BEGIN AT THE DOWNSTREAM END OF THE LINE WITH THE SMOOTEST END OF THE PIPE FACING UPSTREAM. WHEN THE PIPES ARE Laid, THE DIAPER OF EACH PIPE SHALL BE IN CONTACT WITH THE BEDDING MATERIAL THROUGHOUT ITS FULL LENGTH.
29. THE JMWING PIPE ENDS SHALL BE THOROUGHLY CLEANED BEFORE THE JOINT IS MADE. JOINTING SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS DIRECTIONS USING JOINTING SOLVENT AND PRIMER.


5. TESTING AND ASSESSMENT FOR COMPLIANCE OF CONCRETE SHALL BE CARRIED OUT IN ACCORDANCE WITH BS 5400.
6. ALL REINFORCEMENT SHALL BE FULLY SUPPORTED BY PLASTIC TRIPED BARS SPACED AT 100mm.
7. ALL REINFORCEMENT SHALL BE CONTAINED BOTH ABOVE AND BELOW THE SLAB AT ALL INTERSECTIONS.
8. CHANGING OF ALL CONCRETE IS TO BE ACHIEVED BY KEEPING SURFACES CONTINUOUSLY WET FOR A PERIOD OF 7 DAYS, AND PREVENTION OF LOSS OF MATERIAL FOR A TOTAL OF 14 DAYS FOLLOWED BY A GRADUAL DRYING OF THE SURFACE. THE SURFACES MAY BE USED & PROTECTED FROM WEAR BY COVERING WITH 25mm SAND.
9. THE SUPERFICIENCY SHALL BE COVERED 24 HOURS AFTER THE REINFORCEMENT IS COVERED.

- 
- | Property                | 17N | 20  | 250 |
|-------------------------|-----|-----|-----|
| NUMBER OF RAYS IN GROUP | 17  | 17  | 17  |
| BAR GRADE AND TYPE      | N   | N   | N   |
| BAR DIAMETER IN mm      | 250 | 250 | 250 |
| NOMINAL STRENGTH IN MPa | 250 | 250 | 250 |
| NOMINAL DIAMETER IN mm  | 250 | 250 | 250 |


- |       |   |                                   |
|-------|---|-----------------------------------|
| LV    | : | LENGTH VARIES                     |
| CV    | : | COR. VARIES                       |
| EW    | : | EACH WAY                          |
| EF    | : | EACH FACE                         |
| SV    | : | SHAPE VARIES                      |
| BI    | : | BOTTOM REINFORCEMENT - LAD FIRST  |
| BT    | : | BOTTOM REINFORCEMENT - LAD SECOND |
| TI    | : | TOP REINFORCEMENT - LAD FIRST     |
| T2    | : | TOP REINFORCEMENT - LAD SECOND    |
| T & B | : | TOP AND BOTTOM                    |
| ALT.  | : | ALTERNATING BARS                  |

CONTRACTOR SHALL CALL:  
DIAL BEFORE  
YOU DIG 1100

PRIOR TO COMMENCEMENT OF WORK TO OBTAIN  
ALL CURRENT SERVICE AUTHORITY PLANS

 **DIAL 1100**  
BEFORE YOU DIG

Title	<div style="text-align: center;"> <b>JAN 2007</b>  <b>GENERAL NOTES</b>  <b>AND SPECIFICATIONS</b> </div>	Drawing No.	4570-01-02
		Name	C
		Contract No.	4570-01-02
		Scale	1"=1'-0"



- LEGEND**
- EXISTING SURFACE CONTOUR (1m INTERVAL)
  - PROPOSED DRAINAGE EASEMENT
  - PROPOSED STORMWATER PIPE
  - PROPOSED STORMWATER PIT
  - DISCHARGE CONTROL PIT WITH ORifice PLATE (REFER 4670-01-06 FOR DETAILS)
  - ATLANTIS DETENTION/FILTRATION TANK (REFER 4670-01-06 FOR DETAILS)
- NOTES**
1. DIT CHANGES FOR LOT 707 & 708
  2. DIT CHANGES FROM EACH LOT IS TO BE CONNECTED TO THE DETENTION TANKS VIA THE ATLANTIS FILTRATION UNIT.
  3. A MIN 24L RAIN WATER TANK IS TO BE INSTALLED BY OWNERS ON EACH LOT

**DRG STATUS: FOR TENDER**

Rev	Date	By	CHKD	Appr
C	05	P.N	M.S	M. TOSKER
B	05	A.G	M.S	M. TOSKER
A	05	A.G	M.S	M. TOSKER

**Client:** V. D AND M BUBALO

**Project:** 7 & 7A ORCHARD STREET  
STORMWATER MANAGEMENT DESIGN

**Consulting engineers:** Patterson, Britton & Partners Pty Ltd

**Drawing No.:** 4670-01-03

**Scale:** 1:250 (A3) 1:500 (A3)

**North Arrow:** [Symbol]

**Notes:** DETAILS SHOWN IN THE ADJACENT ISSUE ARE FOR INFORMATION ONLY. THE DRAWING APPROVAL PROCESS, DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY THE AUTHORITY. ANY CHANGES TO THE DRAWING MUST BE NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG HELD BY PATTERSON BRITTON & PARTNERS

CC 0545106  
Ra  
10 JAN 2007


for

10 JAN 2007

TANK No.	TANK SIZE	TANK HEIGHT	TANK VOL.	MIN BASE HL.	IN/EST.	POINT A	POINT B
					IN/EST.	IN/EST.	IN/EST.
011	4000x500	880	11.3	33.14	341008.90	341008.90	827087.90.328
012	4000x500	880	11.3	33.14	341008.90	341008.90	827087.90.328
013	4000x500	880	11.3	33.14	341008.90	341008.90	827087.90.328
014	3772x500	880	10.4	27.60	341008.90	341008.90	827087.90.328
015	3772x500	880	10.4	27.60	341008.90	341008.90	827087.90.328
016	3772x500	880	10.4	27.60	341008.90	341008.90	827087.90.328
017	4000x500	880	11.3	33.14	341008.90	341008.90	827087.90.328
018	3772x500	880	10.4	27.60	341008.90	341008.90	827087.90.328
019	4000x500	880	11.3	33.14	341008.90	341008.90	827087.90.328

**NOTES**

1. TANK CO-ORDINATES DEFINE THE SOUTH-WEST (POINT A) AND NORTH-EAST (POINT B) CORNERS OF EACH TANK.
2. ALL CO-ORDINATES ARE ON A LOCAL SYSTEM, REFER TO DWG. 4470-01-03 FOR DATUM.



C	ISSUED FOR TENDER
B	ISSUED FOR CC APPROVAL
A	ISSUED FOR REVIEW

DS	P.H	MS	Approved	Date
MS	MS	M. TOOKEN		22.06.05
MS	ARG	M. TOOKEN		08.06.05
ARG	ARG			30.06.05

INITIALS SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE STAGES UNDER TAKEN IN THE DRAFTING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE REGISTERED/TRANSMITTAL FORM No.5.2.2 HELD BY PATTERSON BRITTON & PARTNERS.

104 Mount Street  
 North Sydney 2060  
 Telephone (02) 9657 1418  
 Facsimile (02) 9657 1703  
 e-mail [info@pallit.com.au](mailto:info@pallit.com.au)  
 A.C.N. 663 229 228

**Patterson Britton  
& Partners Pty Ltd**  
consulting engineers

**Client** V. D. AND M. SUBALO

**Project** 7 & 7A ORCHARD STREET  
STORMWATER MANAGEMENT DESIGN

TIME	DRAINAGE LONG SECTIONS

4670-01-04	Issue C	Code File No. 4670-01-04
		Ref. (a)







OFFICIAL RECEIPT

30/06/2006 Receipt No 194921

TO D BUBALO M BUBALO V BUBALO

107 ORCHARD STREET  
WARRIEWOOD 2102

Applic	Reference	Amount
GL Re	SWBF-S94	\$4,327.05
GL Re	BUSHFIRE	
GL Re	SWCF-S94	\$26,722.36
GL Re	COMMUNITY	
GL Re	SWCL-S94	\$70,257.39
GL Re	CREEKLINE CORRIDOR	
GL Re	SWCM-S94	\$45,108.28
GL Re	CREEKLINE CORRIDOR	
GL Re	SWLS-S94	\$7,543.20
GL Re	LIBRARY	
GL Re	SWPC-S94	\$34,449.66
GL Re	PEDESTRIAN CYCLEWAY	
GL Re	SWPM-S94	\$8,887.83
GL Re	PLAN MANAGEMENT	
GL Re	SWPR-S94	\$99,515.01
GL Re	PUBLIC RECREATION	
GL Re	SWTT-S94	\$41,676.95
GL Re	TRAFFIC & TRANSPORT	

Total: \$338,487.73

Amounts Tendered	
Cash	\$0.00
Cheque	\$338,487.73
Db/Cr Card	\$0.00
Money Order	\$0.00
Agency Rec	\$0.00
Total	\$338,487.73
Rounding	\$0.00
Change	\$0.00
Nett	\$338,487.73

Printed 30/06/2006 1:17:27

Cashier PTaske

CONTRIBUTION BREAKDOWN (Warriewood Valley)

RE: - PLEASE ENSURE THAT PAYMENT IS SUBMITTED TO CASHIER WITH THIS FORM

2/52/02 (For Receipt Description)

2/10/04

DIVISION OF ONE LOT INTO TEN

ORCHARD STREET, WARRIEWOOD

(For Receipt Description)

Contribution Amount	Cashier Code	Account No.	Responsible Business Unit
1,676.95	SWTT	91310C1210000	Urban Infrastructure
5,108.28	SWCW	91317C1210000	Urban Infrastructure
1,257.39	SWCL	91303C1210000	Urban Infrastructure
1,722.36	SWCF	91316C1210000	Community & Library Services
1,515.01	SWPR	91312C1210000	Reserves & Recreation
1,449.66	SWPC	91311C1210000	Reserves & Recreation
1,327.05	SWBF	91314C1210000	Natural Resources
1,543.20	SWLS	91315C1210000	Community & Library Services
1,887.83	SWVP	91250C1210000	Urban Infrastructure
1,887.83	SWPM	91318C2210000	Urban Infrastructure

18,487.73

06.06

4981

SEND COMPLETED FORM AND A COPY OF THE RECEIPT TO PROJECT LEADER WARRIEWOOD INFRASTRUCTURE

PITMAN & CO PTASKE  
05/06/06

Re

10 JAN 2007 10 JAN 2007

Section 94 Contribution Breakdown (Warriewood Valley)

NOTE: - PLEASE ENSURE THAT PAYMENT IS SUBMITTED TO CASHIER WITH THIS FORM

DA Consent No.: No152/02 (For Receipt Description)

Consent Date: 20/10/04

DA Consent Description: SUBDIVISION OF ONE LOT INTO TEN

Property Address: 7 ORCHARD STREET, WARRIEWOOD (For Receipt Description)

S94 Subset	Contribution Amount	Cashier Code	Account No.	Responsible Business Unit
Traffic and Transport	\$41,676.95	SWTT	91310C1210000	Urban Infrastructure
Creekline corridor (works)	\$45,108.28	SWCW	91317C1210000	Urban Infrastructure
Creekline corridor (land)	\$70,257.39	SWCL	91303C1210000	Urban Infrastructure
Community Facilities	\$26,722.36	SWCF	91316C1210000	Community & Library Services
Public Recreation	\$99,515.01	SWPR	91312C1210000	Reserves & Recreation
Pedestrian Cycleway	\$34,449.66	SWPC	91311C1210000	Reserves & Recreation
Bushfire	\$4,327.05	SWBF	91314C1210000	Natural Resources
Library Services	\$7,543.20	SWLS	91315C1210000	Community & Library Services
Ponderosa Parade	\$	SWVP	91250C1210000	Urban Infrastructure
Plan Management	\$8,887.83	SWPM	91318C2210000	
Total Payment	\$338,487.73			

To be completed by Cashier

Date Paid: 30.06.06

Receipt Number: 194981

NOTE TO CASHIER: - PLEASE SEND COMPLETED FORM AND A COPY OF THE RECEIPT TO PROJECT LEADER WARRIEWOOD INFRASTRUCTURE

0545106  
10 JAN 2007

Rev.  
10 JAN 2007

# Pittwater Council

Telephone (02) 9970 1111

Facsimile (02) 9970 7150



## Facsimile

To: Wally Bubalo Address: 7 Orchard Street, Warriewood  
Fax: 9970 8454 Date: 19 May 2006  
From: Ross McWhirter Re: 7 Orchard Street subdivision  
CC: Pages: 1

☐ Urgent ☐ For Review ☐ Please Comment ☐ Please Reply

Message: - Revised Section 94 Contributions.

The revised Section 94 contributions applicable until 30 June 2006 are: -

ELEMENT	CONTRIBUTION per DWELLING	TOTAL CONTRIBUTION (7 dwellings)
Traffic and Transport	\$5,953.85	\$41,678.95
Creekline Corridor (Works)	\$6,444.04	\$45,108.28
Creekline Corridor (Land)	\$10,036.77	\$70,257.39
Community Facilities	\$3,817.48	\$26,722.36
Recreation and Open Space	\$14,216.43	\$99,515.01
Pedestrian and cycleway network	\$4,921.38	\$34,449.66
Bushfire protection	\$618.15	\$4,327.05
Library services	\$1,077.60	\$7,543.20
Plan Management	\$1,269.69	\$8,887.83
		\$338,487.73

Please contact the undersigned if you have any enquiries concerning this matter.

*R. McWhirter*

Ross McWhirter  
PROJECT LEADER WARRIEWOOD INFRASTRUCTURE


### CONFIDENTIALITY NOTICE TO RECIPIENTS EXTERNAL TO PITTWATER COUNCIL

The information in this facsimile is intended for the named recipient only. It may contain privileged and confidential information. If you are the intended recipient, you must not copy, distribute, take action in reliance on it, or disclose any details of the facsimile to any person, firm or corporation. If you have received this facsimile in error, please notify us immediately by reverse charge call and return the original to us by mail. We will reimburse you any costs you may incur in notifying us and returning the original facsimile to us.

# KYORA LANDSCAPES

Professional Landscape Design and Construction

www.kyora.com.au



21 November, 2006

Wayne Treble  
The Certification Group  
c/-

Dear Wayne

**Re: WD & M Bubalo, 7 Orchard Street, Warriewood  
Lot 3, DP 23863  
Development Application No: NO152/02**

Please be advised that the Landscaping plans have been prepared in accordance with conditions B45, B45a, B45b & D44, Development Control Plan No 29 – Warriewood Valley Urban Land Release, regarding the above property

For further clarification, please do not hesitate to contact me on the numbers below.

Yours sincerely,  
**KYORA LANDSCAPES**

**STUART MERCER**

PITTWATER COUNCIL COMMUNITY  
GO 05/15/06

10 JAN 2007



ABN: 17 435 110 096 Lic No: 119182C  
P.O. Box 343 NARRABEEN NSW 2101  
Ph: 9913 3999 Fax: 9913 3699 Mobile: 0418 979 059

**HIA member**  
the best in the business



level 4  
104 Mount Street  
North Sydney 2060

PO Box 515  
North Sydney 2059  
Australia

telephone: (02) 9957 1619  
facsimile: (02) 9957 1291  
email: reception@patbrit.com.au  
ABN: 69 003 220 228

**Patterson Britton  
& Partners Pty Ltd**

Newcastle Office  
8 Telford Street  
Newcastle East 2300

PO Box 668  
Newcastle 2300  
Australia

telephone: (02) 4928 7777  
facsimile: (02) 4926 2111  
email: mail@newcastle.patbrit.com.au

consulting engineers

\\487002mjs070105-bubalo cert cond B25 and B29.doc

The Certification Group  
PO Box 870  
Narrabeen, NSW, 2101  
Fax 9944 6330

CC Wally Bubalo  
Fax 9997 6090

Friday, 5 January 2007

Attention: Mr Wayne Treble

Dear Sir

#### BUBALO SITE ACCESS AND SEDIMENT/EROSION CONTROL CERTIFICATION

Further to your recent request we certify that the design undertaken for the above site complies with both Conditions B25 and B29 of DA Consent No. N0152/02.

We confirm that access to the site complies with the requirements of Pittwater Councils DCP No. 3 "Driveways and Internal Roadways and AS2890.1-1993: "Parking Facilities - Off Street Carparking".

We also confirm that the proposed sediment and erosion control plan/details for the site has been designed in accordance with the requirements of the NSW Department of Land and Water Conservation (Now DNR).

We trust this information is satisfactory. Should you have any further enquiries, please do not hesitate to contact me on (02) 9957 1619.

Yours faithfully  
**PATTERSON BRITTON**

Mark Tooker  
Principal

2007 JAN 01

Review / Verification by Date

*[Signature]* 5/1/2007

90/915000

#### Principals

Greg Britton BE MEngSc FIEAust Andrew Chitty BE MIEAust CPEng Peter Collman BE MEngSc MIEAust  
Bruce Drury BE Dip Sc(Geol) M AppSc MIEAust Paul Harvey-Walker BE FIEAust David McConnell BSc MIEAust  
Joe Marson BE MEngSc FIEAust Andrew Patterson BE FIEAust Christopher Thomas BE MEngSc MIEAust  
Mark Tooker BSc(Eng) MEngSc FIEAust CPEng Michael Wright BE MEngSc MIEAust

#### Senior Associates

Steve Barrett Simon Batt BE MIEAust Paul Macinante BE MEnvEngSc MIEAust Ben Patterson BE MIEAust  
Marc Roberts BE Michael Shaw BE MIEAust CPEng

#### Associates

Stephen Aebi BE MIEAust Neville Boyes OMIEAust Scot Cranfield Cameron Drury BE MIEAust  
Adam Knight BE MIEAust CPEng Cameron Smith BE MEngSc MIEAust CPEng  
Alexandra Stone BE MIEAust Chris Yates BE MIEAust





**Pittwater  
Council**

Postal Address: P.O. Box 882, Mona Vale NSW 1660, DX 9018 Mona Vale

pittwaterlga.com.au e-mail: pittwater\_council@pittwater.nsw.gov.au

James Payne, Manager - Urban Infrastructure  
8am to 5:30pm Mon - Thurs, 8am to 5pm Fri  
Phone 9970 1188

16 August 2006

W D & M Bubalo  
107 Orchard Street  
**WARRIEWOOD 2102**

Dear Sir

**Re: DA N0457/05 & N0152/02 Orchard Street Warriewood  
Construction Phase - Traffic Management Plan**

Council refers to construction phase, Traffic Management Plan as set out in the Patterson Britton & Partners Pty Ltd letter dated Friday, 21 July 2006.

Council is satisfied with the Traffic Management Plan as set out in the above referred correspondence.

This letter may be submitted with your application for a construction certificate for the works under the above referred development consent.

Yours faithfully

James Payne

**MANAGER - URBAN INFRASTRUCTURE**

PITTWATER COUNCIL CONVEYANCE  
CC 05/05/06

Re

10 JAN 2007



Pittwater Council

OFFICIAL RECEIPT

09/01/2007 Receipt No 208571

To D, M & B BUBALO

107 ORCHARD STREET  
WARRIEWOOD NSW 2102

Applic Reference	Amount
GL Re QLSL-Buil	\$875.00
1 X NO152/02	

Total: \$875.00

Amounts Tendered

Cash	\$0.00
Cheque	\$875.00
Db/Cr Card	\$0.00
Money Order	\$0.00
Agency Rec	\$0.00
Total	\$875.00
Rounding	\$0.00
Change	\$0.00
Nett	\$875.00

Printed 09/01/2007 9:40:02

Cashier JVisch

PITTWATER COUNCIL CCA  
CC 0595706

*A*  
10 JAN 2007

See reverse of form for instructions

## LEVY PAYMENT FORM

FORM NO.

OFFICE USE ONLY

PLEASE PRINT ALL DETAILS USING CAPITALS

Surname (if person)  
or Company/Organisation name

BUBALO

Given names (if person)

VLADO DRAGAN MILEVA

ABN (if applicable)

POSTAL ADDRESS

No. and street or PO Box

107 ORCHARD ST

WARRIEWOOD

Town/suburb

State

NSW

Postcode 2102

Bus. hours phone

0299706620

Number and street

107 ORCHARD ST

WARRIEWOOD

Town/suburb

State

NSW

Postcode 2102

Estimated start date

D 20 M 01 Y 2007

Estimated finish date

D 04 M 04 Y 2007

Local Council Area

PITTWATER

DA/CC/CDC No.

NO152/G2

Estimated value

of work (see note on back)

\$ 250,000.00

Levy

payable \$

875.00

If you have provided a CC above, please provide DA number here

Signature of Officer/Private Certifier

Name of Officer/Private Certifier

Date

D 01 M 01 Y 2007

Business hours phone

Department/Authority

Contract/DA No (circle which)

Levy payable

\$ 250,000.00

Contract

amount \$

Contact person (Print)

Contact person (Signature)

Phone number

Date

D 01 M 01 Y 2007

Any false or misleading information provided on this form may result in prosecution under Section 58A.

I hereby declare that the information provided on this form is true and correct to the best of my knowledge

Name VLADO BUBALO

Signature

V. Bubalo

Date

D 09 M 01 Y 2007

Exemption Approval Certificate No.

0545100001 2007

Building and Construction Industry Long Service Payments Corporation, Locked Bag 3000, Central Coast MC NSW 2252

Tel: 13 14 41 Fax: (02) 9287 5685 Email: levy@lspc.nsw.gov.au www.lspc.nsw.gov.au

ABN 93 646 090 808

Jan06/180


KE

10 JAN 2007

ORCHARD STREET ACCESS ROAD,  
WARRIEWOOD  
CIVIL ROAD DESIGN  
for  
V, D AND M BUBALO

COUNCIL  
FILE COPY  
054516

Kc  
10 JAN 2007



DRAWING LIST:

4670-01	TITLE SHEET, LOCALITY PLAN AND DRAWING LIST
4670-02	GENERAL NOTES & SPECIFICATIONS (SHEET 1 OF 2)
4670-03	GENERAL NOTES & SPECIFICATIONS (SHEET 2 OF 2) AND MISCELLANEOUS DETAILS
4670-04	SITE PLAN AND LONGITUDINAL SECTION
4670-05	CUL-DE-SAC KERB DEVELOPMENT AND ACCESS ROAD TYPICAL SECTION
4670-06	ACCESS ROAD DESIGN CROSS SECTIONS SHEET 1 OF 3
4670-07	ACCESS ROAD DESIGN CROSS SECTIONS SHEET 2 OF 3
4670-08	ACCESS ROAD DESIGN CROSS SECTIONS SHEET 3 OF 3
4670-09	PROPOSED SURFACE CONTOURS AND PAVEMENT/KERB DESIGN DETAILS
4670-10	STORMWATER DRAINAGE PLAN
4670-11	STORMWATER DRAINAGE LONGITUDINAL SECTIONS
4670-12	EROSION AND SEDIMENT CONTROL PLAN
4670-13	CONSTRUCTION PHASE TRAFFIC MANAGEMENT PLAN

Note: Construction Certificate only approves works consistent with Consent N0152/02

DRG STATUS : FOR CONSTRUCTION

E	RETAINING WALL DETAIL ADDED	MS	PC	MS	M. TOOKER	18.10.06	INITIALS SHOWN IN THE ADJACENT ISSUE	104 Mount Street North Sydney 2060 Telephone: (02) 9557 1015 Facsimile: (02) 9557 1041 Email: info@pattersonbritton.com.au ACN 003 200 226	Patterson Britton & Partners Pty Ltd consulting engineers	Client V, D AND M BUBALO	Title TITLE SHEET, LOCALITY PLAN AND DRAWING LIST	Drawing No. 4670-01
D	ISSUED FOR CONSTRUCTION	MS	ANG	MS	M. TOOKER	21.07.06	RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN THE ORIGINAL SIGNATURES CAN BE FOUND IN THE REVERSE SIDE OF THE ORIGINAL OF THE DRG					Issue E
C	CUL-DE-SAC REMOVED	MS	ANG	MS		04.11.05						
B	ISSUED FOR APPROVALS	PC	ANG	MS		18.02.05						
A	ISSUED FOR REVIEW	ANG	MS	MS		25.01.05						
Issue	Details of Issue	Date	Drawn	Checked	Approved	Date	HELD BY PATTERSON BRITTON & PARTNERS					Code Title No. 4670-01 Xref(s)

# FOR CONSTRUCTION

MS	ARC	MS
MS	ARC	MS
FC	ARC	MS
ARC	ARC	MS
Des'd	Dim	Chk'd

## SAFETY

1. ALL WORKS SHALL BE IN ACCORDANCE WITH PITVATER COUNCILS ALL-SPREAD CONSTRUCTION SPECIFICATION, DETAILS SHOWN ON THESE DRAWINGS, AND TO THE DIRECTION OF THE PROJECT MANAGER.
2. THESE DRAWINGS SHALL BE READ IN CONJUNCTION WITH ALL OTHER DRAWING SPECIFICATIONS AND WRITTEN INSTRUCTIONS AS MAY BE ISSUED DURING THE COURSE OF THE CONTRACT.
3. ALL SET OUT DIMENSIONS SHOWN SHALL BE VERIFIED BY THE CONTRACTOR AT SITE BEFORE WORK COMMENCES. DRAWINGS SHALL NOT BE SCALED FOR DIMENSIONS.
4. DURING CONSTRUCTION THE WORKS SHALL BE MAINTAINED IN A STABLE CONDITION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREVENTING ANY COLLAPSE OR SLIDING OF THE EARTHWORKS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR BRACING AND BATTERS SHALL BE PROVIDED BY THE CONTRACTOR TO KEEP THE WORKS AND EXCAVATIONS STABLE AT ALL TIMES.
5. ALL MATERIALS AND WORKMANSHIP USED IN THE CONSTRUCTION OF THIS STANDARD SHALL BE IN ACCORDANCE WITH ALL RELEVANT CURRENT AUSTRALIAN STANDARDS.
6. ALL DIMENSIONS ARE IN MILLIMETRES, UNLESS NOTED OTHERWISE.
7. DESIGN SERVICES HAVE BEEN PLOTTED FROM SUPPLIED DATA. THE CONTRACTOR IS RESPONSIBLE FOR VERIFYING THE DATA. THE CONTRACTOR'S RESPONSIBILITY TO ESTABLISH THE LOCATION OF THE EXISTING UTILITY SERVICES PRIOR TO COMMENCING WORK. ALL UTILITIES AND EXISTING SERVICES SHALL ALSO BE OBTAINED FROM THE RELEVANT SERVICE AUTHORITY PRIOR TO THE COMMENCEMENT OF WORK.
8. THE CONTRACTOR SHALL OBTAIN STOUT CO-ORDINATES FROM THE SUPERINTENDENT, AND ARRANGE ALL SURVEY SETOUT BY A REGISTERED SURVEYOR.
9. ALL NEW AND EXISTING SERVICES THAT CROSS EXISTING AND FUTURE ROADS, RAILWAYS, OR OTHER EXISTING SERVICES SHALL BE PROTECTED WITH DIBERO MATERIAL TO SURROUND THE SERVICE. THE CONTRACTOR SHALL PROVIDE A DENSITY RATIO, SUBJECT TO PRIOR APPROVAL FROM RELEVANT AUTHORITY.
10. ON COMPLETION OF SERVICES INSTALLATION, ALL DISTURBED AREAS SHALL BE RESTORED TO ORIGINAL CONDITION EXCEPT FOR PAVED AREAS, CONCRETE AREAS, GRAVEL AREAS, GRASSSED AREAS AND ROAD PAVEMENTS.
11. WHERE NEW WORK ADJUTS EXISTING, THE CONTRACTOR SHALL ENSURE THAT A SMOOTH EVEN PROFILE FREE FROM ADJUTS CHANGES, IS OBTAINED.
12. CARE TO BE TAKEN WHEN EXCAVATING NEAR ENERGY AUSTRALIA, ELECTRICITY, GAS, TELEPHONE AND CABLE SERVICES, NO MECHANICAL EXCAVATION TO BE USED WITHIN 10 METRES OF ANY OF THESE SERVICES AND ALL SERVICES HAND EXCAVATE IN THESE AREAS. LANE WITH RELEVANT AUTHORITY AS REQUIRED.
13. THE CONTRACTOR SHALL NOT DISTURB ANY EXISTING SURVEY BENCH MARKS OR SURVEY POINTS UNLESS INDICATED FOR REMOVAL WITHOUT LANDS DEPT APPROVAL IN WRITING.
14. THE CONTRACTOR TO FENCE AND SECURE SITE.
15. PUBLIC ROAD WORKS.
16. THE CONTRACTOR'S ACTION IS TO THE REQUIREMENTS OF PITVATER COUNCIL, WHERE THE WORKS ARE LOCATED IN ROAD RESERVE OR ACROSS THE PAVEMENT OF A PUBLIC ROADWAY OR FOOTPATH, THE CONTRACTOR SHALL OBTAIN A PERMIT GOVERNING THE USE OF PUBLIC AREAS AND COMPLY WITH ALL THE CONDITIONS COVERING THE ISSUANCE OF PERMITS. THE CONTRACTOR'S PERMITS ISSUED IN RESPECT OF PAVEMENT OPENINGS, THE CONTRACTOR SHALL OBTAIN DETAILS FROM COUNCIL, PAY ALL FEES, MEET ALL REQUIREMENTS AND CARRY OUT ALL WORKS AT NO EXTRA COST. ALL PAVEMENTS AND EXCAVATIONS TO BE UNDERMAINT BY THE CONTRACTOR. ALL TO PITVATER COUNCIL'S STANDARDS AND APPROVAL.
18. PAYMENT DESIGN REPORT BY GEOENGINEER, JANUARY 2006 - THE CONTRACTOR SHALL ENSURE THAT THEY ARE FAMILIAR WITH THE CONTENTS OF THIS REPORT.
17. ALL CONSTRUCTION WORK SHALL BE CARRIED OUT SO THAT AT ANY TIME THE ADJUTING PROPERTY OWNERS ARE NOT DEPRIVED OF AN ALL-WEATHER ACCESS OR SUBJECT TO ADDITIONAL OR POLLUTED STORM WATER RUNOFF DURING THE PERIOD OF CONSTRUCTION.
16. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPAIR OF ANY DAMAGE TO COUNCIL'S INFRASTRUCTURE, SUCH REPAIR OR REPAIRMENT SHALL BE CARRIED OUT IMMEDIATELY TO THE SATISFACTION OF COUNCIL.
15. THE CONTRACTOR IS TO PREPARE AND IMPLEMENT A TRAFFIC MANAGEMENT PLAN TO COUNCIL'S STANDARDS AND APPROVAL FOR ALL WORKS.
22. SITE SURVEY JANUARY 2004.
20. ASSOCIATES, DECEMBER 2004.

## QUALITY ASSURANCE

1. THE CONTRACTOR SHALL MAINTAIN AND MAINTAIN A QUALITY ASSURANCE SYSTEM INCLUDING THE RECORDS OF AS B002. THE QUALITY SYSTEM SHALL BE SUCH THAT RECORDS BE KEPT OF ALL ASPECTS AND STAGES OF THE WORK.
2. THE RECORDS FOR EACH CONSTRUCTION TASK SHALL BE STAGED AND REVIEWED TO THE SATISFACTION OF THE CONTRACTOR ADMINISTRATOR. THE PROGRAMS FOR APPROVAL SHALL BE SUBMITTED TO THE CONTRACTOR ADMINISTRATOR FOR APPROVAL AND WORK SHALL NOT COMMENCE UNTIL SUCH APPROVAL HAS BEEN GIVEN.
3. DURING THE COURSE OF CONSTRUCTION, THE CONTRACTOR SHALL MAINTAIN AVAILABLE TO THE CONTRACTOR ADMINISTRATOR AND SHALL HAVE SUCH RECORDS TO MAINTAIN RECORDS AS SPECIFIED WILL RESULT IN THE CONTRACTOR RE-INSPECTING COMPLETED WORKS IF INSTRUCTED TO DO SO BY THE CONTRACTOR ADMINISTRATOR.
4. AT THE COMPLETION OF EACH STAGE OF THE WORKS THE CONTRACTOR SHALL CERTIFY THAT THESE WORKS HAVE BEEN UNDER TAKEN AND COMPLETED IN ACCORDANCE WITH THE DRAWINGS, SPECIFICATION AND INSTRUCTIONS ISSUED DURING THE COURSE OF THE CONTRACT.

## EXISTING SERVICES AND FEATURES

1. THE CONTRACTOR SHALL ALLOW FOR THE CAPPING OFF EXCAVATION AND REMOVAL IF REQUIRED OF ALL EXISTING SERVICES IN AREAS AFFECTED BY THE WORKS WITHIN THE CONTRACT AREA AS SHOWN ON THE DRAWINGS AND SHALL BE RESPONSIBLE FOR THE REINSTATEMENT OF ALL TO REGULATORY AUTHORITY STANDARDS AND APPROVAL.
2. VARIATION EXISTING STORMWATER DRAINAGE FLOWS THROUGH THE SITE AT ALL TIMES. MAKE DUE ALLOWANCE FOR ALL SUCH FLOWS AT ALL TIMES.
3. PRIOR TO COMMENCEMENT OF ANY WORKS THE CONTRACTOR SHALL OBTAIN THE SUPERINTENDENT'S APPROVAL FOR HIS PROGRAMME FOR THE RELOCATION/CONSTRUCTION OF TEMPORARY SERVICES.
4. CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES AS REQUIRED TO MAINTAIN EXISTING SUPPLY TO BUILDINGS REMAINING IN OPERATION THROUGHOUT THE CONSTRUCTION PERIOD. THE TEMPORARY SERVICES SHALL BE SUPERINTENDENT. ONCE DIVISION IS COMPLETE AND THE WORKS ARE COMPLETED THE CONTRACTOR SHALL REMOVE ALL SUCH TEMPORARY SERVICES AND MAKE GOOD TO THE SATISFACTION OF THE SUPERINTENDENT.
5. INTERPRETATION TO SUPPLY OF EXISTING SERVICES SHALL BE DONE SO AS NOT TO CAUSE ANY INCURRING OF DAMAGE TO EXISTING SERVICES. IF ANY DAMAGE TO EXISTING SERVICES IS TO OBTAIN APPROVAL OF THE SUPERINTENDENT AT THE TIME OF REINSTATEMENT.

## GENERAL STORMWATER NOTES

1. ALL STORMWATER WORKS ARE TO BE UNDERPAVEMENT, GENERALLY IN ACCORDANCE WITH AS 3500 STORMWATER DRAINAGE.
2. UNLESS OTHERWISE APPROVED, ALL DRAINAGE PITS SHALL BE CLASS "2" SPOT AND SOCKET AND PIPES WITH RUBBER RING JOINTS.
3. A CONTRACTOR TO SUPPLY AND INSTALL ALL FITTINGS AND SPECIALS INCLUDING VARIOUS PIPE ADAPTORS TO ENSURE PROPER CONNECTION TO EXISTING PIPEWORK.
4. ALL CONNECTIONS TO EXISTING DRAINAGE PITS SHALL BE MADE IN A TRADESMAN-LIKE MANNER AND THE INTERNAL WALL OF THE PIT AT THE POINT OF ENTRY SHALL BE CELEST REINFORCED WITH A NON-SHRINK EPOXY GROUT TO ENSURE A SMOOTH FINISH.
5. PRECAST PITS SHALL NOT BE USED, ALL DRAINAGE PITS TO BE CAST IN-PLACE. PRECAST PITS SHALL NOT BE USED TO SLIT PROPOSED PITS.
6. STEP RINGS AT SPACINGS OF 0.3m ARE TO BE PROVIDED IN DRAINAGE PITS MORE THAN 1.2m DEEP.
7. PROVIDE A JOE LENGTH OF 1000L BARSOL DRAINAGE PIPE WEAPPED IN FABRIC SUECK AT UPSTREAM END OF EACH PIT.
8. ALL CONCRETE USED IN DRAINAGE PITS SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 40MPa.
9. THE EXCAVATED TRENCH WIDTH FOR PIPE LAYING MUST BE AT LEAST 300mm WIDER THAN THE OUTER DIAMETER OF THE PIPE. PIPES ARE TO BE LAID CENTRALLY WITHIN THE EXCAVATED TRENCH.
10. ALL PIPES ARE TO BE LAID ON A MINIMUM BEDDING OF 75mm OF SAND BEDDING IN ACCORDANCE WITH AS 5601.3. BEDDING SHALL BE COMPACTED TO AT LEAST 90% OF THE MAXIMUM DRY DENSITY.
11. BARSOL FOR STORMWATER PITS AND PIPES SHALL BE COMPACTED TO AT LEAST 90% OF THE MAXIMUM DRY DENSITY.
12. BARSOL MATERIAL SHALL BE INSPECTED AND APPROVED BY THE SUPERVISOR PRIOR TO LAYING AND COMPACTION.
13. BARSOL MATERIAL SHALL BE INSPECTED AND APPROVED BY THE SUPERVISOR PRIOR TO LAYING AND COMPACTION.

## GENERAL STORMWATER NOTES (cont.)

11. UNLESS SPECIFIED ALL DRAINAGE GRATES TO BE HEAVY DUTY GALVANISED MILD STEEL TO AS 3996.
12. CHAINS SHALL BE TONNED WHERE NECESSARY TO PREVENT SOCKETS, AND SHALL BE MADE OF GALVANISED STEEL TO AS 3996.
13. THE LINE FROM BEARING ON THE TRENCH BOTTOM ON THE UNDERLAY.
14. MATERIAL SHALL BE PLACED IN THE PINE SURROUND IN LAYERS NOT MORE THAN 200MM. LOOSE TECHNIQUES AND COMPACTED WITHOUT DAMAGING OR TEARING THE PAPERWORK.

## GENERAL COMPACTION NOTES

1. FURNISHED MATERIAL, DESIGNED BY THE SUPERINTENDENT AS UNDESIRABLE, MAY BE REMOVED AS DIRECTED BY THE SUPERINTENDENT AND THE REMOVED MATERIAL, SATISFYING THE REQUIREMENTS LISTED BELOW.
2. UNLESS OTHERWISE APPROVED OR SPECIFIED, ALL FILL MATERIAL SHALL BE FROM A SOURCE APPROVED BY THE SUPERINTENDENT AND SHALL COMPLY WITH THE FOLLOWING:
- a) FREE FROM ORGANIC AND PERISHABLE MATTER
  - b) MAXIMUM PARTICLE SIZE 75MM
  - c) PLASTICITY INDEX BETWEEN 25 AND 20%

3. SELECT FILL MATERIAL SHALL BE PLACED IN THICK LAYERS AND COMPACTED AT OPTIMUM MOISTURE.

5. THE CONTRACTOR SHALL PROGRAMME THE EARTHWORKS OPERATION SO THAT THE WORKING SURFACES SHALL BE GRADED DURING THE PERIOD OF CONSTRUCTION. THE SURFACE SHALL BE GRADED TO BE SUFFICIENTLY FIRM TO ALLOW THE SURFACE TO BE USED DURING THE PERIOD OF CONSTRUCTION. THE SURFACE SHALL BE GRADED TO BE SUFFICIENTLY FIRM TO ALLOW THE SURFACE TO BE USED DURING THE PERIOD OF CONSTRUCTION. THE SURFACE SHALL BE GRADED TO BE SUFFICIENTLY FIRM TO ALLOW THE SURFACE TO BE USED DURING THE PERIOD OF CONSTRUCTION.

## CONCRETE NOTES

- GENERAL
- G1. CARRY OUT ALL CONCRETE WORK IN ACCORDANCE WITH ASTM000 AND THE SPECIFICATION. KEEP A COPY OF THE DOCUMENTS ON SITE.
- G2. VERIFY ALL SETTING OUT DIMENSIONS WITH THE SUPERINTENDENT AND/OR THE SURVEYOR.

## CONCLUSION

- | PROPERTY CLASSIFICATION            | PROPOSED CONCRETE | MASS CONCRETE |
|------------------------------------|-------------------|---------------|
| EXPOSURE CLASSIFICATION            | 82, 80, 82        | 82, 80, 82    |
| DESIGN COMPRESSIVE STRENGTH        | 45 MPa            | 45 MPa        |
| COEFFICIENT OF THERMAL EXPANSION   | 0.00012           | 0.00012       |
| COEFFICIENT OF PERMEABILITY        | 35000/cm/s        | 35000/cm/s    |
| WATER / BINDER RATIO (W/B)         | 0.45              | 0.45          |
| SLURRY COVER TO REINFORCEMENT (mm) | 45 mm             | 45 mm         |
| MAXIMUM FINISH – TROWEL            | CLASS 2           | CLASS 2       |
| MAXIMUM COARSE AGGREGATE SIZE      | CLASS FLOAT       | CLASS FLOAT   |
|                                    | 20 mm             | 20 mm         |

## CONCRETE NOTES (cont.)

- C7. THE FINISHED CONCRETE SURFACE SHALL BE FREE OF CRACKS HAVING A CRACK WIDTH EQUAL TO OR GREATER THAN 0.1 mm AT TIME OF PRACTICAL COMPLETION. IF CRACKING EXCEEDS THIS LIMIT, THE CONTRACTOR SHALL MAKE CORRECTIVE ACTIONS TO THE SATISFACTION OF THE SUPERINTENDENT WHICH WOULD BE NECESSARY TO PREVENT FURTHER CRACKING OR TO REPAIR CRACKS WITH SLAVE/SLICK PLATE GEL OR OTHER WORKS.
- C8. TESTING AND ASSESSMENT FOR COMPLIANCE OF CONCRETE SHALL BE CARRIED OUT BY THE CONTRACTOR IN ACCORDANCE WITH AS 3600. SUBMIT ALL RESULTS TO THE SUPERINTENDENT.
- C9. ALL REINFORCEMENT SHALL BE PROPERLY SUPPORTED ON PLASTIC CHAIRS AT LEAST GREATER THAN 10mm CENTRES BOTH WAYS. PLASTIC TYPED STEEL CHAIRS SHALL NOT BE USED. BARS SHALL BE TIED AT ALTERNATE INTERSECTIONS.
- C10. MAINTAIN COVER TO REINFORCEMENT AT CHAMBERS, DEEP GROOVES, REINOLTS, ETC.
- C11. ALL CRACKS, CHASES OR EMBEDMENT OF PIPES OTHER THAN THOSE SHOWN ON THE STRUCTURAL DRAWINGS SHALL BE MADE IN CONCRETE MEMBERS WITHOUT THE PRIOR WRITTEN APPROVAL OF THE SUPERINTENDENT.
- C12. CONSTRUCTION JOINTS WHERE NOT SHOWN SHALL BE LOCATED TO THE APPROVAL OF THE SUPERINTENDENT.
- C13. DURING AND IMMEDIATELY FOLLOWING POURING, THE CONCRETE SHALL BE PROTECTED FROM WIND AND SLAT, AININGS AND WIND BREAKS ARE TO BE UTILISED FOR THIS PURPOSE.
- C14. CURING OF ALL CONCRETE IS TO BE ACHIEVED BY KEEPING SURFACES CONTINUOUSLY WET FOR A PERIOD OF 7 DAYS, AND PREVENTION OF LOSS OF MOISTURE FOR A TOTAL OF 14 DAYS FOLLOWED BY A GRADUAL DRYING OUT. POLYETHYLENE SHEETING OR WET HESSAL MAY BE USED IF PROTECTED FROM WIND AND/OR PLASTIC CURING AGENTS.
- C15. THE SUPERINTENDENT SHALL, BY ADVISORY NOTES FOR THE CONTRACTOR, REQUIRE INSPECTION AND CONCRETE SHALL NOT BE DELIVERED UNTIL APPROVAL IS OBTAINED.

**1000**

72. FINAL FINISHING INCLUDES FLOATING AND TEXTURING THE PAVEMENT AND SHALL COMMENCE ONLY AS SOON AS THE WATER SHEEN HAS LEFT THE PAVEMENT SURFACE AND NOT IN ANY AREA WHERE THERE IS FREE SURFACE WATER.

**CONCLUSIONS**

- UNLESS NOTED OTHERWISE ALL CONCRETE FORMWORK SHALL BE CLASS 2  
UNLESS INDICATED OTHERWISE.
6. THE DESIGN CERTIFICATION, CONSTRUCTION AND PERFORMANCE OF THE  
FORMWORK AND PLEASURE IS THE RESPONSIBILITY OF THE CONTRACTOR.  
7. A SAFE DESIGN AND CONSTRUCTION AND STRIPPING TIMES SHALL COMPLY WITH AS  
8. 10 AND 15 3600 UNLESS OTHERWISE NOTED OR APPROVED BY THE  
ENGINEER/DESIGNER.
9. DURING CONSTRUCTION SUPPORT PROPPING WILL BE REQUIRED WHERE  
LOADS FROM STACKED MATERIALS, FORMWORK AND OTHER SUPPORT SLABS  
OR BEAMS EXCEED THE DESIGN LOAD FOR THE ELEMENT OR SERVICEABLE  
STRENGTH OR SERVICEABILITY HAS BEEN ATTAINED THESE LOADS SHALL NOT EXCEED 28 DAY  
CURED UNPRESTRESSED LIVE LOADS.
10. THE FORMWORK SHALL NOT BE DESIGNED TO RELY ON RESTRAINT OR  
ADJUTANT FROM THE PERMANENT STRUCTURE WITHOUT THE PRIOR APPROVAL OF  
THE SUPERINTENDENT.


10 JAN 2007

00 0545/06

**GENERAL NOTES & SPECIFICATIONS**  
**SHEET 1 OF 2**


Drawing No.	4670-02
Issue	D
Code File No.	4670-02
Ref. (s)	









[illegible]


PRINCEWATER COUNCIL CONSTITUTION

CC 0545/06


10 JAN 2007




10 JAN 2007




CH 70.00




CH 65.00




CH 60.00




CH 55.00




CH 90.00




CH 85.00




CH 80.00




CH 75.00




CH 110.00




CH 105.00



CH 100.00



CH 95.00



A1

DRG STATUS: FOR CONSTRUCTION

E	CH 155 & 160 AMENDED	MS	PC	MS	L. TOOKER	18.10.06
D	ISSUED FOR CONSTRUCTION	MS	ARG	MS	L. TOOKER	21.07.06
C	CU-RE-SAC REVISED	MS	ARG	MS		08.11.05
B	ISSUED FOR APPROVALS	PC	ARG	MS		18.02.05
A	ISSUED FOR REVIEW	ARG	ARG	MS		23.01.05
Issue	Details of Issue	Date	Drawn	Checked	Approved	Date

NOTES SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATERSON BRITTON & PARTNERS AND THEN ORIGINAL SIGNATURES OF THE ENGINEER ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG MUST BE USED BY PATERSON BRITTON & PARTNERS.



Lead 4  
100 South Street  
North Sydney 2060  
Telephone 02 9557 3519  
Facsimile (02) 9557 1281  
www.pbr.com.au  
A.C.N. 000 220 226

Paterston  
Britton  
& Partners Pty Ltd  
consulting engineers

Client  
V, D AND M BUBALO  
Project  
ORCHARD STREET ACCESS ROAD  
WARREWOOD

Title  
ACCESS ROAD  
DESIGN CROSS SECTION  
SHEET 3 OF 3


Drawing No.  
4670-08  
Issue  
E  
Cod. File No.  
4670-06  
Scale (s)



10 JAN 2007  
Ke  
054506



- NOTE
1. THE BASE COURSE MATERIAL CAN BE DORZO OR RECYCLED CONCRETE SATISFYING THE REQUIREMENTS OF DORZO STANDARD PROVIDED THE SUB-BASE REQUIREMENTS OF DORZO STANDARD ARE OBSERVED. CONCRETE SATISFYING THE REQUIREMENTS OF DORZO STANDARD PROVIDED IN THE RVT 2001 SPECIFICATION.
2. THE MINIMUM COMPACTION DRY DENSITY RATIO'S ARE AS FOLLOWS (AST D698, 5.41-1993)
  - BASE COURSE: 98% STANDARD
  - SUB-BASE: 100% STANDARD
3. PAVEMENT WEARING COURSE TO CONSIST OF A 30mm THICK LAYER OF AC14 OVERLAIN BY A 20mm THICK LAYER OF AC10.
4. FOR DETAILS OF THE REQUIRED ROAD PAVEMENT REFER TO PAVEMENT DESIGN REPORT PREPARED BY GEOTECHNIQUE PVTY LTD, 14th JANUARY 2003.




PROPOSED SURFACE CONTOURS  
1:300

DRG STATUS : FOR CONSTRUCTION									
E	DRAWING TITLE ASSIGNED	MS	PC	MS	M. TOOKER	18.10.08	INITIALS SHOWN IN THE ADJACENT ISSUE		
D	ISSUED FOR CONSTRUCTION	MS	ARG	MS	M. TOOKER	21.07.08	RECORDS INDICATE THE STAGES UNDERTAKEN IN THE PREPARATION OF THIS DRAWING ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR EACH STATUS. THE REVERSE SIDE OF THE ORIGINAL OF THE ONE REGISTERED/TRANSFERRAL FORM No.5.2.2 HELD BY PATTERSON BRITTON & PARTNERS		
C	QUOTED FOR CONSTRUCTION	MS	ARG	MS		08.11.05			
B	ISSUED FOR APPROVALS	FC	ARG	MS		18.02.05			
A	ISSUED FOR REVIEW	ARG	ARG	MS		25.01.05			
	Details of Issues	Issue	Drawn	Checked	Approved	Date			
							Level 4 North Street North Sydney 2060 Telephone (02) 9697 1813 Telex (02) 9697 1781 Facsimile (02) 9697 1781 A/CN 003 503 836	Patterson Britton & Partners Pty Ltd consulting engineers	
		Client		Title					
		V, D AND M BUBALO		PROPOSED SURFACE CONTOURS AND PAVEMENT/KERB DESIGN DETAILS					
		Project		ORCHARD STREET ACCESS ROAD WARREWOOD					
		Drawing No.		4670-09					
		Issue		E					
		Code File No.		4670-08					
		Rev.(s)							




PITMAN ROUNDEL CO. LTD.  
00 0545/06

10 JAN 2007



PIT	WEAST	MANHOLE	TYPE (RTA)
1/1	341060.448	827064.218	S43 (MIN. 800mm) 3m LINT. - CM. GRADE
2/1	341056.751	827083.207	S45 (MIN. 1200mm) 2.4m LINT. - SAG
3/1	341051.083	827082.252	800mm DRAINAGE JUNCTION PIT - JUNCTION SEALED, HEAVY DUTY LD (CLASS D)

NOTES  
1. INSTALL MGA. ENVELOPE PIT INSET (IE LITTER BASKET) OR EQUIVALENT TO SUIT AT PITS 1/1 AND 2/1.



DRG STATUS : **TENDER, NOT FOR CONSTRUCTION**

Issue	Drawn	Chk'd	App'd	Date	Remarks
D	ISSUED FOR CONSTRUCTION	MS	MS	21.07.06	RECORDS INDICATE THE STAGES UNDERWENT IN THE DRAWING APPROVAL PROCESS. DRAWINGS WERE APPROVED BY THE CLIENT AND THE DESIGNER. THE DESIGNER'S SIGNATURE CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG. HELD BY PATRICKSON BRITTON & PARTNERS
C	DEL-DE-SAC REVIEWED	MS	MS	04.11.05	
B	ISSUED FOR APPROVALS	PC	MS	18.02.05	ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG. HELD BY PATRICKSON BRITTON & PARTNERS
A	ISSUED FOR REVIEW	ARG	MS	25.01.05	

Level 4  
100 Mount Street  
North Sydney 2060  
Telephone (02) 9587 1818  
Fax (02) 9587 1791  
Email [info@pbr.com.au](mailto:info@pbr.com.au)  
A/C N 803 220 228

**Patrickson Britton & Partners Pty Ltd**  
consulting engineers

Client  
**V, D AND M BUBALO**

Project  
**ORCHARD STREET ACCESS ROAD WARRIWOOD**


Title  
**STORMWATER DRAINAGE PLAN**

Drawing No.  
**4670-10**

Issue  
**D**

Coat Plate No.  
**4670-10**

A1






**4670-12**

2008-10-10

10 JAN 2007

0545706





**FILE COPY**

**MR W BUBALO**

**WARRIEWOOD VALLEY  
7&7A ORCHARD STREET  
(PART OF SECTOR 10)**

**Water Management Report  
Construction Certificate Issue**

**Issue No. 1  
SEPTEMBER 2005**

PITTWATER COUNCIL CONSTRUCTION CERTIFICATE	
Number:	CC 0545/06
This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.	
Endorsed by:	RC
Date:	10 JAN 2007

**Patterson Britton  
& Partners Pty Ltd**  
consulting engineers



MR W BUBALO

WARRIEWOOD VALLEY  
7&7A ORCHARD STREET  
(PART OF SECTOR 10)

Water Management Report  
Construction Certificate Issue

PITTWATER COUNCIL  
05/05/06

Issue No. 1  
SEPTEMBER 2005

Document Amendment and Approval Record

Issue	Description of Amendment	Prepared by [date]	Verified by [date]	Approved by [date]
1	CC Water Management Report	David Stone 6/9/05	Michael Shaw 6/9/05	Mark Tooker 7.9.05

Note: This document is preliminary unless it is approved by a principal of Patterson Britton & Partners.  
Document Reference: L:\4670 - 7&7A Orchard from Jan 03\vp4670dns050907-Bubalo cc wm report.doc  
Time and Date Printed: 7/02/02 1:14:56 PM

level 4  
104 Mount Street  
North Sydney 2060

PO Box 515  
North Sydney 2059  
Australia

telephone: (02) 9957 1619  
facsimile: (02) 9957 1291  
reception@patbrit.com.au  
ABN 89 003 220 228

Newcastle Office  
8 Telford Street  
Newcastle East 2300

PO Box 668  
Newcastle 2300  
Australia

telephone: (02) 4928 7777  
facsimile: (02) 4926 2111  
mail@newcastle.patbrit.com.au

**Patterson Britton  
& Partners Pty Ltd**

consulting engineers

10 JAN 2007

# TABLE OF CONTENTS

Page No.

<b>1</b>	<b>EXECUTIVE SUMMARY</b>	<b>1</b>
1.1	WATER MANAGEMENT PLAN	1
1.2	SECTOR 10 OWNERSHIP	2
1.3	CERTIFICATION	2
<b>2</b>	<b>INTRODUCTION</b>	<b>3</b>
<b>3</b>	<b>DESCRIPTION OF PROPOSED WATER MANAGEMENT MEASURES</b>	<b>4</b>
3.1	RAINWATER TANKS	4
3.2	ATLANTIS TANKS AND FILTRATION UNITS	4
3.3	WATER QUALITY CONTROL POND	5
<b>4</b>	<b>WATER CYCLE ASSESSMENT</b>	<b>6</b>
4.1	WATER CYCLE ASSESSMENT RESULTS	6
4.1.1	Existing Conditions	6
4.1.2	Post Development – No Water Management Practices	6
4.1.3	Post Development – Introduction of Water Management Practices	7
<b>5</b>	<b>WATER QUALITY ASSESSMENT</b>	<b>8</b>
5.1	MONITORING PLAN OBJECTIVES	8
5.2	SCOPE OF MONITORING PLAN	8
5.2.1	Monitoring Locations	8
5.2.2	Types of Monitoring	9
5.2.3	Water Quality Monitoring (Discrete Sampling)	9
5.2.4	Rapid Biological Assessment Monitoring	10
5.2.5	Sediment Toxicant Monitoring	10
5.2.6	SQUID Monitoring	10
5.2.7	Flow Gauging for Monitoring	10
5.2.8	Quality Assurance/Measurement Accuracy	11
5.3	MONITORING RESULTS	11
5.3.1	Water Quality Monitoring Results	11
5.3.2	Rapid Biological Assessment Monitoring Results	11
5.3.3	Bed Sediment Toxicant Monitoring Results	11
<b>6</b>	<b>WATER QUALITY MANAGEMENT</b>	<b>13</b>
6.1	CONSTRUCTION PHASE	13
6.2	POST DEVELOPMENT PHASE	13

re  
10 JAN 2007

# TABLE OF CONTENTS

	Page No.
6.2.1 Maintenance	14
6.2.2 Mosquito Risk Assessment	14
<b>7 STORMWATER QUANTITY MANAGEMENT</b>	<b>15</b>
7.1 INTEGRATED STRATEGY	15
7.2 STORMWATER DETENTION	15
7.2.1 Flood Flow Gauging	15
7.3 FLOOD MANAGEMENT	15
7.4 FLOOD EVACUATION	16
<b>8 REFERENCES</b>	<b>17</b>
<b>DRAWINGS</b>	
<b>FIGURES</b>	
<b>APPENDIX A – CC CHECKLIST</b>	
<b>APPENDIX B – CC ACCESS ROAD DRAWINGS</b>	
<b>APPENDIX C – SECTOR 10 (STOCKLAND) MONITORING RESULTS SUMMARY</b>	
<b>APPENDIX D – ATLANTIS CELLS</b>	

## LIST OF TABLES

10 JAN 2007

---

TABLE 1 –PRE CONSTRUCTION (7&7A ORCHARD ST) WATER QUALITY MONITORING RESULTS	12
--	----

# 1 EXECUTIVE SUMMARY

✓  
10 JAN 2007

This document is the Construction Certificate (CC) issue Water Management Report (WMR) for the proposed development of 7&7A Orchard Street (*part of Sector 10*), Warriewood Valley. It follows on from the Development Application (DA) issue water management report, detailing additional information gathered during the design process and where necessary recalibration of previously developed models.

Pittwater Councils "*Warriewood Valley Urban Release Water Management Specification*" (WMS), Feb 2001 has been utilised as the guiding document for preparation of the report, with detailed analysis of the following aspects of water management for the proposed development:

- Water cycle management;
- Water quality management;
- Flood protection; and
- Stormwater quantity management.

**Appendix A** includes a signed copy of Councils CC document checklist to confirm that all the tasks required of the above aspects have been undertaken.

The runoff quantity, water cycle, flooding and quality control measures proposed in the development satisfy Councils requirements detailed in their WMS.

## 1.1 WATER MANAGEMENT PLAN

The proposed development of 7&7A Orchard St (*Part of Sector 10*) provides a Water Management Plan (WMP) that is detailed in the **Drawings** and in summary incorporates the following:

- Stormwater retention and WSUD measures that include Atlantis infiltration/retention cells and rainwater tanks that allow achievement of the predevelopment runoff volume (*refer to Section 4 of this report titled "Description of Proposed Water Management Measures" for details*);
- A water quality control treatment train that consists of a major water quality control pond (WQCPI), Gross Pollutant Traps (GPT's) and other WSUD measures (*refer to Section 5 of this report titled "Water Quality Assessment" for details*);
- A detailed stormwater quality monitoring programme (*refer to Section 5 of this report titled "Water Quality Assessment" for details*);
- Stormwater Detention measures consisting of Atlantis Cell type detention tanks on each proposed lot to ensure downstream flows are maintained at predevelopment levels (*refer to Section 7 of this report titled "Stormwater Quantity Management" for details*); and
- Provision of a development that complies with both NSW floodplain management policy and Councils flood planning requirements (*including evacuation*) (*refer to Section 7.3 of this report titled "Flood Management" for details*).

## 1.2 SECTOR 10 OWNERSHIP


Sector 10 consists of a number of different landholders. 7&7A Orchard St is approximately 0.6ha out of a total of 13.9ha for the Sector as a whole.

The water management plan for Sector 10 previously developed for the Stockland component of the Sector also took into consideration the Sector wide implications for future water management. This has meant some of the various components of the Stockland water management plan have been sized to accommodate development of 7&7A Orchard Street.

The components of the Stockland development that have been sized to include development of 7&7A Orchard Street include the water quality control ponds (*WQCP's*) and GPT's. In addition, a significant proportion of the monitoring undertaken for the Stockland development also applies to this site.

## 1.3 CERTIFICATION

The contents of this report are certified by Michael Shaw, who is a registered NPER engineer with the Institution of Engineers, to comply with the requirements of Pittwater Council's Water Management Specification (*February 2002*).



10 JAN 2007

## 2 INTRODUCTION

The proposed development site (7 & 7A Orchard Street, Warriewood Valley) is part of Sector 10 and is included within the Warriewood Valley Urban Release Area, which has been identified for release for urban purposes by the Minister for Planning.

The site has a total area of approximately 6,068m<sup>2</sup> and has frontage to the southern side of Orchard Street at Warriewood. The site is bounded on the north by a private accessway and on the south by Stockland owned land (*refer to Figure 1 for details*). No creeks or major overland flow paths currently traverse or impact on the site.

Patterson Britton & Partners (PBP) has been engaged by Mr W Bubalo to prepare a Water Management Report relating to the impacts of the proposed development on water management issues. These issues include long-term hydrologic assessment (*water balance*), water quality assessment, flood attenuation, floodplain management and stormwater quantity management.

It should be noted that this report only applies to the land owned by Mr W Bubalo which is proposed to be subdivided into 10 residential lots. It does not relate to the proposed reconstruction of the adjacent private access road. Details of the access road design have been included in **Appendix B** for information purposes only.

This current report has been prepared for the Construction Certificate (CC) stage of the overall development process.

The Water Management Report has been prepared in accordance with Pittwater Council's publication "*Warriewood Valley Urban Land Release – Water Management Specification*" (February, 2001) (WMS).

A completed copy of the "*Documentation Checklist – Construction Certificate*", confirming that all tasks required by Council's WMS have been undertaken, is found at **Appendix A**.

### 3 DESCRIPTION OF PROPOSED WATER MANAGEMENT MEASURES

10 JAN 2007

A number of different water management measures are proposed to be used for this site. These measures are illustrated in the **Drawings** and described below and include:

- Rainwater Tanks;
- Atlantis Detention/Infiltration Tanks and Filtration Units; and
- A Water Quality Control Pond located in the downstream area of Sector 10.

#### 3.1 RAINWATER TANKS

A 2m<sup>3</sup> rainwater tanks is proposed to be installed on each lot (*ie a total volume of 20m<sup>3</sup>*). The location of the tanks on each of the lots will vary depending on the final form of the individual dwellings.

The rainwater tanks are to be installed such that only roof water is collected. The water from the tanks is to be used, as a minimum, for irrigation and toilet flushing purposes. A trickle top up and back flow prevention device are to be installed to Sydney Water's specifications.

While providing a retention function, the rainwater tanks also provide a detention function, as determined in the water cycle assessment (*refer to Section 4*). Studies have shown that at the beginning of a storm event the rainwater tanks will, on average, be only 58% full with the remainder being able to be included as effective detention..

When full, overflow from the rainwater tanks is to be directed to the Atlantis cell detention/infiltration tanks installed at the rear of each lot.

#### 3.2 ATLANTIS TANKS AND FILTRATION UNITS

Atlantis detention/infiltration tanks and filtration units are proposed to be installed at the low point of each lot (*refer to Drawing 4670-01-03*). The size of the tanks varies for each lot. A schedule of tank sizes is included in **Drawing 4670-01-04**.

All overflow from the rainwater tanks and other surface water runoff is to be directed to the Atlantis filtration units and tanks.

Each tank is to be installed with a filtration unit upstream to provide pre treatment and prevent clogging of the tanks and infiltration media. Filtration units are to be installed to the manufacturers and Patterson Britton & Partners specifications (*refer to Appendix D and Drawings 4670-01-02 and 05*).

The base of each tank is to be underlain by 50mm of sand and evenly spaced gravel trenches (*as detailed in Drawing 4670-01-05*) in order to enhance the infiltration capacity of the site.




Downstream of each tank is a Discharge Control Pit (*DCP*). These pits restrict the discharge from the site to the permissible site discharge (*PSD*) by using a discharge control plate or orifice. The *DCP*'s also include a surface grate to allow surface runoff not collected upstream of the Atlantis cells to be detained prior to discharge from the site. A trash screen is also to be installed over the orifice plate to prevent clogging.

Tank 'DT7', which benefits lots 707 and 708, is located within lot 709. This requires an easement to be established in Lot 709 for the benefit of these lots. The drainage lines running along the rear of all the lots (*ie Line 1 and Line 2*) will also require easements.

### 3.3 WATER QUALITY CONTROL POND

Water Quality Control Pond 1 (*WQCP1*) was constructed as part of the downstream Stockland development and was sized to provide stormwater treatment for the 7&7A Orchard Street development. For details of the construction of *WQCP1* refer to the CC Issue Water Management Report (*PBP, February 2002*) prepared for the Stockland Development. For details of the performance of *WQCP1* since construction, refer to monitoring results provided in **Appendix C** and also the 8<sup>th</sup> Quarter Post Subdivision Certificate Water Quality Monitoring Report (*PBP, November 2004*) prepared for the Stockland development. The results show that it is currently exceeding its performance targets.



## 4 WATER CYCLE ASSESSMENT

10 JAN 2007

An assessment of the water cycle for the site (*ie 7&7A Orchard St only*) was carried out at DA stage to ascertain the impact of the proposed development on runoff volume and baseflow. The existing water cycle was used as a basis of comparison for two development scenarios. The first scenario explored the impact of development where minimal management practices were introduced. The second scenario compares existing conditions with the proposed development layout where a suite of water management practices is proposed.

The DA water cycle model did not require amendment at CC stage as the detailed design shown in the **Drawings** has been undertaken to meet the outcomes of the earlier modelling by incorporating an equivalent suite of water management practices. All other assumptions made within the DA water cycle model remain valid.

To achieve the objective of the DA model the following stormwater retention volumes were required to, and have been incorporated into the design:

- Implementation of  $2\text{m}^3$  (2kL) rainwater tanks within each of the 10 proposed lots (*ie total capacity of  $20\text{m}^3$* ); and
- Provision of  $222.1\text{m}^3$  of Atlantis infiltration/detention tanks.

### 4.1 WATER CYCLE ASSESSMENT RESULTS

#### 4.1.1 Existing Conditions

The results indicated that 24% of total rainfall was converted to runoff for existing conditions.

For the years 1995 to 1998:

- The average annual rainfall volume falling on the site was  $8,876\text{m}^3$ ;
- The average annual volume of runoff from impervious surfaces was  $0\text{m}^3$ ;
- The average annual volume of pervious surface runoff was  $2,108\text{m}^3$ ; and
- The average annual volume of infiltration was  $1,820\text{m}^3$ .

The total runoff as a percentage of total rainfall (24%) is slightly lower than the percentage calculated in the IWMS (36%), however considering that the L&T IWMS model (NAM) simulated a 10 year period of rainfall for a much larger area with likely lower average infiltration rates than for this site, the result is considered acceptable.

#### 4.1.2 Post Development – No Water Management Practices

The results indicated that 56% of total rainfall was converted to runoff for the post development conditions without introduction of specific water volume reduction measures.

For the years 1995 to 1998:

- The average annual rainfall volume falling on the site was 8,876 m<sup>3</sup>;
- The average annual volume of runoff from impervious surfaces was 3,919 m<sup>3</sup>;
- The average annual volume of pervious surface runoff was 1,077 m<sup>3</sup>; and
- The average annual volume of infiltration was 898 m<sup>3</sup>.

Of particular interest is the increase in runoff volume from impervious surfaces and the decrease in infiltration volume.

#### 4.1.3 Post Development – Introduction of Water Management Practices

The results of the water balance indicated that 23% of total rainfall was converted to runoff for the post development conditions with the introduction of the above mentioned measures.

For the years 1995 to 1998:

- The average annual rainfall volume falling on the site was 8,876 m<sup>3</sup>;
- The average annual flow volume to the rainwater tanks was 2,351 m<sup>3</sup>, reuse demand was 1,646 m<sup>3</sup>, 1,151 m<sup>3</sup> of mains water was required and 1,859 m<sup>3</sup> of spilled to the infiltration systems;
- The average annual flow volume to the infiltration systems was 4,686 m<sup>3</sup>; and
- The average annual volume of infiltration was 2,430 m<sup>3</sup>.

Introduction of the proposed water management practices reduces the fraction of runoff from 56% to 23% of the total rainfall, which is 1% less than the runoff rate for existing conditions.

PITTWATER COUNCIL CO  
0545/06

10 JAN 2007

## 5 WATER QUALITY ASSESSMENT

10 JAN 2007

This section contains a description of the updated CC monitoring plan for the site including the results of additional sampling, undertaken since publication of the DA stage WMR.

### 5.1 MONITORING PLAN OBJECTIVES

Prior to urbanisation of Sector 10, a monitoring plan was developed for Stockland in accordance with Council's Water Management Specification (*February 2001*) and AS/NZ 5667.6: 1998 "*Water Quality Sampling – Guidance on Sampling of Rivers and Streams*". The Stockland monitoring plan was developed based on a sector wide approach and hence incorporates the Bubalo owned land (7&7A Orchard Street).

The objectives of the monitoring plan are to:-

- develop an understanding of the existing conditions present in the waterways within and adjacent to Sector 10;
- continually assess the quality of these waterways during the construction phase of Sector 10; and
- assess the impact of constructed water quality measures following construction to ensure the development is ecologically sustainable.

Monitoring undertaken prior to the development of Stockland's lots within Sector 10 was used to establish the pre-development quality of the waterways within and adjacent to Sector 10 (*termed "baseline data"*). This data was compared with post subdivision monitoring results of the Stockland development and will also be compared with the post subdivision results of the 7&7A Orchard Street development to determine whether pollution controls are operating adequately and if the water quality is improving.

During the development stage of 7&7A Orchard Street, implementation of the monitoring plan will allow early detection of any adverse impacts likely to risk the health of the public or the quality of downstream waterways such as Warriewood Wetlands.

### 5.2 SCOPE OF MONITORING PLAN

7&7A Orchard Street drains directly to the Stockland drainage system of Sector 10, which in turn leads to WQCP1. Discharge from WQCP1 then drains through Sector 12 to Warriewood Wetlands.

#### 5.2.1 Monitoring Locations

The primary waterway that was selected for monitoring as part of the Stockland monitoring programme for Sector 10 was Mullet Creek. This creek receives runoff in part from Sector 10 and then discharges into Warriewood Wetlands. Sampling locations for existing

conditions were selected at the downstream and upstream ends of this creek with relation to Sector 10 (*refer to Figure 1*).

A third internal sampling site was also monitored at the discharge point from Sector 10 into Sector 12 (*refer to Figure 1*).

As part of the post subdivision certificate water quality monitoring programme for the Stockland owned land, both the inlets and outlets from WQCP1 and WQCP 2 were monitored.

Currently no water body exists within or immediately adjacent to 7&7A Orchard Street. In addition to the Sector 10 monitoring, sampling has also been undertaken at the existing piped drainage discharge point to Mullet Creek (*refer to Figure 1, sampling site IS3*). This pipe currently drains the existing private access road and any upstream areas which also drain to this road. However, 7&7A Orchard Street does not currently drain to this point and the proposed lots are designed to drain through the Stockland development rather than to Mullet Creek.

Following development of 7&7A Orchard Street, a sampling site will be established at the piped discharge point from the proposed subdivision into the Stockland development (*refer to Figure 1, sampling site IS2*).

### 5.2.2 Types of Monitoring

The monitoring plan for Sector 10 (*including 7&7A Orchard Street*) consists of three main categories:-

- physico-chemical water quality monitoring;
- ecosystem/rapid biological assessment monitoring; and
- riparian sediment toxicant monitoring.

PATTON & PARTNERS  
10 JAN 2007

### 5.2.3 Water Quality Monitoring (Discrete Sampling)

The water quality monitoring component of the plan consists of:-

- dry weather sampling undertaken quarterly; and
- wet weather sampling undertaken for at least 3 events (*recording a rainfall depth greater than 20mm over the catchment in a 24 hour period*) spread evenly over the year and sampling throughout the rainfall event (*rising and falling limbs of storm hydrograph*).

10 JAN 2007

Samples are tested for the constituents listed in Council's WMS and reported to conform with Council's specification.

As mentioned above, discrete sampling of two dry weather events has already been undertaken at the access road discharge point to Mullet Creek. Following construction of 7&7A Orchard Street sampling will be undertaken at the discharge point of 7&7A Orchard Street into the Stockland development (*refer to Figure 1, sampling site IS2*).

#### 5.2.4 Rapid Biological Assessment Monitoring

Habitat monitoring has been undertaken as part of the Stockland development in Mullet Creek (*ie. at the location of the water sampling stations*).

As no natural aquatic systems exist on the site (*7&7A Orchard Street*), no additional rapid biological assessment has been or will be required.

#### 5.2.5 Sediment Toxicant Monitoring

Sampling and testing of bed sediment has already been undertaken in Mullet Creek as part of the Stockland development

As no natural waterways currently exist on the site (*7&7A Orchard Street*) no additional bed sediment sampling will be required.

#### 5.2.6 SQUID Monitoring

All Stockland constructed stormwater quality improvement devices (*SQUID's*) for Sector 10 have been monitored for 2 years since issue of the Stage 1 subdivision certificate. This has included:

- Measurement of volume/mass of material removed from GPT's and an assessment of its relative composition;
- Discrete sampling at the major inlets/outlets of the proposed WQCP; and
- Qualitative assessment of effectiveness of other proposed water quality control measures (*ie bio-retention swales*)

Following construction within 7&7A Orchard Street, the qualitative assessment for Stockland constructed devices will be extended to quarterly inspection of the proposed infiltration tanks within 7&7A Orchard Street (*for a 2 year period*).

#### 5.2.7 Flow Gauging for Monitoring

To assess the magnitude of wet weather events and determine the position of a particular sample within a storm event, both the rainfall depth and flood depth will be recorded. Rainfall depth data will be obtained from the BoM, whilst flood depths will be recorded at the closest available flood gauge to the site (*Garden Street crossing of Mullet Creek*).

The total depth of rainfall experienced during the event will allow PBP to determine if the event sampled will comply with Council's minimum 20mm depth over 24 hours criteria. A sustained length of record of the water levels at Garden Street will allow PBP to determine if the sample has been taken on either the rising or falling limb of the regional storm hydrograph.

PATTERSON BRITTON & PARTNERS  
CC 0545/06

### 5.2.8 Quality Assurance/Measurement Accuracy

All samples collected for the monitoring plan will be tested by a NATA certified laboratory. Copies of all original data testing certificates will be provided along with information detailing the collection and preservation status upon delivery at the laboratory. The laboratory testing detection limits will also be included on all test certificates.

## 5.3 MONITORING RESULTS

### 5.3.1 Water Quality Monitoring Results

Summary tables of the pre construction, construction and post subdivision water quality data from sampling undertaken for the Stockland development is included in **Appendix C**. **Table 1** contains data for the pre construction monitoring undertaken at the discharge point of the access road to Mullet Creek.

The results for the sample taken on 5 May 2005 are similar to results for previous monitoring of the Stockland upstream site in Mullet Creek as would be expected. However, results from 26 July 2005 show high levels of a number of pollutants when compared to previous monitoring and Councils objectives. Nutrient levels (*ie Total Nitrogen (TN) and Total Phosphorus (TP)*) were significantly higher than the previous monitoring and above Council's medium and long term goals. This is most likely due to external sources, which may include excess fertiliser application to land upstream.


The highly turbid nature of the sample could explain the high concentrations of copper, lead and zinc (*the values for these metals were all above Council's medium and long term objectives*). The high suspended solids concentration may indicate the bed sediments had been disturbed and pollutants stored in the sediments had been remobilised.

### 5.3.2 Rapid Biological Assessment Monitoring Results

For details of the rapid biological assessment monitoring results for Sector 10 refer to the Stockland water management reports (*DA to post sub-division issues*).

### 5.3.3 Bed Sediment Toxicant Monitoring Results

For details of the bed sediment toxicant monitoring results for Sector 10 refer to the Stockland water management reports (*DA to post sub-division issues*).



**Table 1 –Pre Construction (7&7A Orchard St) Water Quality Monitoring Results**

Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal*	5 May 2005	26 July 2005
						WSIS10A	WSBUB2
Total rain over 5 days preceding sampling	mm					0	0
Ammonia - N	mg/L	NS	<2.3	<0.3	<0.3	0.02	<i>1.30</i>
Total Nitrogen	mg/L	<1.6	SQ	<1.6	1.0	0.8	<b>8.2</b>
Nitrate	mg/L	NS	NS	NS	NS	0.06	<0.02
Nitrite	mg/L	NS	NS	NS	NS	<0.02	<0.02
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	0.8	<b>8.2</b>
Total Phosphorous	mg/L	<0.1	SQ	<0.1	0.04	0.05	<b>1.70</b>
Filterable Phosphorous	mg/L	NS	NS	NS	NS	<0.05	0.80
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.01	<0.01
Faecal Coliforms	cfu/100ml	<150	<1000	<150	<150	<i>980</i>	40
Suspended Solids	mg/L	<100	SQ	<20	<6	2	<b>430</b>
Turbidity (field)	NTU	NS	SQ	<50	<20	5	<b>105</b>
pH (field)	pH unit	NS	6.6-8	6.6-8	6.6-8	<b>8.76</b>	<b>8.54</b>
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat.	<90% s	2.91	2.54
Temperature (field)	°C	NS	SQ	SQ	SQ	19.7	19.2
Conductivity (field)	mS/cm	NS	NS	NS	NS	0.234	0.335
Salinity (field)	%	NS	NS	NS	NS	0	0
Arsenic	ug/L	NS	SQ	50%SQ	50	<2	5
Chromium	ug/L	NS	SQ	50%SQ	10	<5	<5
Copper	ug/L	NS	SQ	50%SQ	2	<5	<b>16</b>
Lead	ug/L	NS	SQ	50%SQ	1	<2	<b>27</b>
Mercury	ug/L	NS	SQ	50%SQ	0.1	<0.05	<0.05
Zinc	ug/L	NS	SQ	50%SQ	50	20	<b>120</b>
Organo chlorine Pesticides (OC)	mg/L	NS	SQ	50%SQ	NS	<21	<21
Organo phosphate Pesticides (OP)	mg/L	NS	SQ	50%SQ	NS	<220	<220
Phenols	mg/L	NS	SQ	50%SQ	NS	<170	<170
PAHs	mg/L	NS	SQ	50%SQ	NS	<17	<17
Hardness	mg/L	NS	NS	NS	NS	68	140
Chlorophyll A	mg/L	NS	15	15	10	<0.005	0.09
Oil and Grease	mg/L	NS	NS	NS	NS	<5	<5

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 – Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined achieve the short and medium-term water quality goal.

4. Figures in *italics* achieve the short-term water quality goal.

5. Figures in **Bold** do not achieve the short term goal or where SQ is the short term goal

6. Rainfall data obtained from Bureau of Meteorology.

7. NS – Not Specified by Council, SQ – Status Quo,



## 6 WATER QUALITY MANAGEMENT

fe

10 JAN 2007

This section contains a description of the updated CC water quality management plan for the site including a detailed description of the proposed measures and their management.

### 6.1 CONSTRUCTION PHASE

During bulk earthworks and construction for the proposed development, sediment and erosion control facilities will be constructed/installed in accordance with Council's specifications and with the requirements of the publication "*Managing Urban Stormwater – Soils and Construction*" (Landcom, 2004).

A sediment and erosion control plan has been developed for construction (*refer to Drawing 4670-01-06*) which outlines the strategies proposed to prevent excessive pollutant loads being exported from the site in runoff during and immediately following construction.

### 6.2 POST DEVELOPMENT PHASE

As required in Council's WMS, the objective of the water quality management strategy for the proposed development of Section 10 is to ensure a "*no net increase*" in pollutant loads discharged from the developed site compared to the existing conditions.

The proposed water quality management system for 7&7A Orchard Street consists of the following elements:

- the maximisation of pervious areas (*on each development lot*) so as to increase the infiltration potential;
- use of rainwater storage tanks for reuse in non-potable supply purposes and irrigation;
- use of Atlantis infiltration tanks (*described earlier in this report*);
- installation of Atlantis Purification Units (*refer to Appendix D for details*);
- utilisation of the Stockland constructed underground Gross Pollutant Traps (GPTs) – these have been sized to account for 7&7A Orchard Street; and
- utilisation of the Stockland constructed water quality control pond 1(WQCP1) – this has been sized to account for 7&7A Orchard Street

It has been estimated that the pollutant loads discharging from Sector 10 as a whole (*ie including 7&7A Orchard Street*) will be lower than for the existing site conditions, making a substantial contribution to long-term improvements in receiving water quality.

Post sub-division certificate stage water quality monitoring results for WQCP1 show that the wetland is achieving better than the design objective in terms of TN, TP and SS reduction (*refer to Appendix C for details*).

### 6.2.1 Maintenance

The maintenance program for all water quality control measures implemented with 7&7A Orchard Street is as follows:

- Periodic (*3 monthly*) inspection and removal of accumulated sediments and trash from the Atlantis purification units; and
- Yearly inspection and removal of accumulated sediments from rainwater tanks and the Atlantis infiltration units.

### 6.2.2 Mosquito Risk Assessment

An assessment of the mosquito risk for all water quality control measures implemented within 7&7A Orchard Street has been undertaken. The outcomes of the assessment have resulted in incorporation of the following design measures to minimise mosquito nuisance:

- Pre-screening all flows to both the rainwater and infiltration tanks;
- Regular maintenance of infiltration tanks to prevent blockage; and
- Providing a seal to all maintenance access points to both the rainwater and infiltration tanks.

PITTMAN COUNCIL COMM  
00 0545/06

*Re*  
10 JAN 2007

## 7 STORMWATER QUANTITY MANAGEMENT <sup>le</sup> 10 JAN 2007

### 7.1 INTEGRATED STRATEGY

The integrated strategy proposed for management of stormwater runoff quantity on the site is comprised of:

- source control which includes:
  - use of rainwater tanks ( $2\text{ m}^3/\text{lot}$  ( $20\text{m}^3$ ), of which 42% is counted as effective OSD storage –  $8.4\text{m}^3$ ) to reduce runoff volume, maximise non-potable supply/re-use and minimise peak flows discharging from individual allotments;
  - minimising impervious surfaces (*limited to 50% site wide*) to maximise infiltration potential and reduce runoff volumes;
  - the use of landscaping which encourages the maximisation of infiltration.
- the conveyance system which includes:
  - the proposed 20yr ARI piped drainage system (*effective detention storage volume =  $19.4\text{m}^3$* ) to reduce peak flow rates in events between the 20yr and 100yr ARI events;
- formal stormwater detention facilities to be incorporated at the downstream area of each lot which includes:
  - the proposed Atlantis Tank On site Detention system (*also utilised for infiltration purposes*) to provide a total detention volume of  $366\text{m}^3/\text{ha}$  or  $222.1\text{m}^3$  at a PSD of  $225\text{L/s/ha}$  or  $136.5\text{L/s}$  for the ten lot subdivision.

### 7.2 STORMWATER DETENTION

The proposed design achieves the requirements of the DA water management report, therefore no further detention modelling was required for the CC stage.

We confirm that CC design as shown in the **Drawings** results in post development outflows from 7&7A Orchard Street that are lower than for the base conditions model.

#### 7.2.1 Flood Flow Gauging

No waterways exist on the site (7&7A Orchard Street), hence no flood flow gauging was undertaken.

### 7.3 FLOOD MANAGEMENT

The Bubalo site is not flood impacted by any major water body (*creek or major overland flow path*). A stormwater easement was originally proposed on the southern boundary of the site to allow access for the upstream development (*ie Sector 10A*) to the Stockland piped drainage system for all flows up to the 20 year ARI event. Overland flows in excess of the 20 year ARI event were


proposed to drain directly to Mullet Creek. However, during design of the access road an existing drainage line was discovered at the end of the road, discharging directly to Mullet Creek. At the same time Lawson & Treloar also identified potential flooding problems at the downstream end of Sector 10 and the main access road to Sector 12. It was therefore decided to drain all upstream flows for all events directly to Mullet Creek. An easement to drain these flows to the Stockland drainage system is therefore no longer required.

Note that the road drainage, as illustrated in **Appendix B**, has been designed to convey the 100 year ARI flows to Mullet Creek

#### 7.4 FLOOD EVACUATION

The proposed development is sited well clear of the floodwaters of Mullet Creek in both the 100yr ARI and PMF events. Hence, all habitable floor levels will be sited clear of both the 100yr ARI and PMF events.

No flood evacuation strategy is therefore required for the site as it is not impacted by the PMF of Mullet Creek.



Re

10 JAN 2007

## 8 REFERENCES

---

Institution of Engineers, Australia

*"Australian Rainfall and Runoff, a Guide to Flood Estimation"* Canberra, 1987

Lawson & Treloar Pty Ltd

*"Integrated Water Management Strategy – Warriewood Valley"* November 1997

Report prepared for Pittwater Council

Patterson Britton & Partners

*"Water Management Report Sector 10*

*Warriewood Valley"* Issue 1, June 2001

Prepared for Stockland Trust Group

Patterson Britton & Partners

*"Water Management Report Sector 10*

*Warriewood Valley-Construction Certificate Issue"* Issue 7, February 2002

Prepared for Stockland Constructors

Patterson Britton & Partners

*"Post Subdivision Certificate Water Quality Monitoring Report Sector 10*

*Warriewood Valley"* Issue 1, January 2003

Prepared for Stockland Constructors

Pittwater Council

*"Flood Risk Management Policy for Pittwater Council"* 19 June 2001

Pittwater Council

*"Warriewood Valley Urban Land Release Water Management Specification"* February, 2001

PITTWATER COUNCIL CONSTRUCTION CERTIFICATE	
Number:	CC 0545/06
This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.	
Endorsed by:	<i>Re</i>
Date:	10 JAN 2007

---

## DRAWINGS


---

WARRIEWOOD VALLEY, 7 & 7A ORCHARD ST.  
(PART OF SECTOR 10)  
INTERALLOTMENT DRAINAGE DESIGN

for  
V, D AND M BUBALO

PITMAN CONSTRUCTION COMPANY  
000545106  
10 JAN 2007

- DRAWING LIST:
- 4670-01-01 TITLE SHEET, LOCALITY PLAN AND DRAWING LIST
  - 4670-01-02 GENERAL NOTES & SPECIFICATIONS
  - 4670-01-03 SITE PLAN
  - 4670-01-04 DRAINAGE LONG SECTIONS
  - 4670-01-05 DRAINAGE DETAILS
  - 4670-01-06 SEDIMENT AND EROSION CONTROL PLAN



DRG STATUS : PRELIMINARY, NOT FOR CONSTRUCTION

INITIALS SHOWN IN THE ADJACENT ISSUE				RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND IN THE RESPECTIVE TRANSMITTAL FORM N. & 2. THE DRG HELD BY PATTERSON BRITTON & PARTNERS				level 4 104 Mount Street North Sydney 2060 Telephone (02) 9667 1619 Facsimile (02) 9667 1261 email reception@pbr.com.au A.C.N. 003 280 228		Patterson Britton & Partners Pty Ltd consulting engineers		Client V, D AND M BUBALO	Title TITLE SHEET, LOCALITY PLAN AND DRAWING LIST	Drawing No. 4670-01-01		
												Project 7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				
RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND IN THE RESPECTIVE TRANSMITTAL FORM N. & 2. THE DRG HELD BY PATTERSON BRITTON & PARTNERS				Issue	4670-01-01											
				Issue	B											
				Cod File No.	4670-01-01											
				Xref(s)												



2. ALL LEVELS ARE IN TERMS OF AUSTRALIAN HEIGHT DATUM (AHD)  
ALL CO-ORDINATES ARE ON A LOCAL SYSTEM, REFER TO DWG.  
4870-01-03 FOR DATUM.

11. THE CONTRACTOR SHALL PROVIDE TEST CERTIFICATES FROM A N.A.T.A. APPROVED TESTING LABORATORY CERTIFYING THAT THE MATERIALS USED COMPLY WITH THE RELEVANT SPECIFICATIONS.
12. THE CONTRACTOR SHALL TAKE ALL PRECAUTIONS TO PROTECT EXISTING SERVICES, ANY SERVICE AUTHORITIES PROPERTY DAMAGED DURING THE COURSE OF THE CONTRACT SHALL BE REPAIRED AT THE CONTRACTORS EXPENSE.

1. ALL STORMWATER WORKS ARE TO BE UNDERTAKEN GENERALLY IN ACCORDANCE WITH AS 3500 (2003) STORMWATER DRAINAGE.

2. UNLESS NOTED OTHERWISE, ALL REINFORCED CONCRETE PIPES ARE TO BE CLASS 2 AND RUBBER RING JOINTED. RUBBER RINGS SHALL BE MANUFACTURED AND TESTED IN ACCORDANCE WITH ASTM44. THE EXCAVATED TRENCH WIDTH FOR PIPE LAYING MUST BE AT LEAST 400MM WIDER THAN THE OUTER DIAMETER OF THE PIPE. PIPES ARE TO BE Laid CENTRALLY WITHIN THE EXCAVATED TRENCH.
3. ALL PIPEWORK SHALL BE BEDDED ON A CONTINUOUS UNDERLAY OF SAND, NOT LESS THAN 100MM THICK IN CASE OF 150MM AND 200MM THICK IN CASE OF 300MM AND 400MM DIAMETER. THE SAND SHALL BE GRADED TO THE REQUIRED DENSITY AND SHALL BE GRADED EVENLY TO THE REQUIRED GRADIENT OF THE PIPELINE.
4. IN WET OR UNSTABLE GROUND CONDITIONS WHERE THE TRENCH BOTTOM REQUIRES FURTHER STABILIZING, AN ADDITIONAL BEDDING OF 200MM AND/OR 300MM NOMINAL SIZE AGGREGATE (AS DIRECTED BY THE SUPERINTENDENT), SHALL BE PLACED BELOW THE STANDARD BEDDING TO A DEPTH DETERMINED BY THE SUPERINTENDENT. WHEN ORDERED BY THE SUPERINTENDENT AN APPROVED FILTER FABRIC SHALL BE USED IN CONSULTATION WITH THE ADDITIONAL BEDDING.
5. THE BED AND HAUNCH MATERIAL SHALL BE COMPACTED FOR THE FULL WIDTH OF THE TRENCH BY A MINIMUM OF TWO PASSES OF A VIBRATING PLATE OR HAND TAMPING METHOD TO THE SATISFACTION OF THE SUPERINTENDENT.
6. CHASSES SHALL BE FORMED WHERE NECESSARY TO PREVENT SOCKETS, FLANGES OR THE LIKE FROM BEARING ON THE TRENCH BOTTOM OR THE UNDERLAY.

7. THE CONTRACTOR SHALL ENSURE THAT ANY EXISTING STRUCTURES LOCATED ADJACENT TO EXCAVATED TRENCHES ARE SUPPORTED OR PROTECTED TO PREVENT DAMAGE TO OR MOVEMENT OF THESE STRUCTURES
8. THE CONTRACTOR MUST LEAVE ALL STORMWATER DRAINAGE WORKS UNOBTAINED UNTIL ANY TESTING NEEDED IS NECESSARY BY THE SUPERINTENDENT HAS BEEN PERFORMED.
9. PIPE LAYING SHALL BEGIN AT THE DOWNSTREAM END OF THE LINE AND THE SOCKET ENDS OF THE PIPE FACING UPSTREAM, THE BARREL OF EACH PIPE SHALL BE IN CONTACT WITH THE BEDDING MATERIAL THROUGHOUT ITS FULL LENGTH.
10. FOR RUBBER RING JOINTS THE PIPE ENDS SHALL BE THOROUGHLY CLEANED BEFORE THE JOINT IS MADE. THE TWO PIPE SECTIONS SHALL THEN BE TIGHTLY JOINED WITH THEIR INNER SURFACES AT THE MANUFACTURER'S NOMINATED LAPPING GAPS.
11. LIFTING HOLES IN PIPES AND JOINTS SHALL BE PLUGGED WITH WOODEN PRECAST TAPERED PLUGS, OR TAPE SURROUNDS OR OTHER APPROVED MEANS FOR TO BACKFILL MATERIAL BEING PLACED.
12. CUTTING OPERATIONS FOR CONCRETE PIPES SHALL PROVIDE NEAT END SURFACES. THE CUT SURFACES SHALL BE GIVEN TWO COATS OF A SUPERINTENDENT APPROVED EPOXY PAINT.

Level 4  
104 Mount Street  
North Sydney 2060

telexphone (02) 9557 1618  
facsimile (02) 9557 1281  
e-mail [inception@patterson.com.au](mailto:inception@patterson.com.au)  
A.C.N. 003 220 228

**Patterson  
Birtton  
& Partners Pty Ltd**

**consulting engineers**

Client	V, D AND M BUBALO
Project	7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN

4670-01-02	Issue	B
Cod File No. 4670-01-02		
Xref.(s)		

13. JOINTS SHALL NOT BE MADE UNDERWATER. THE TRENCH SHALL BE DEWATERED TO FACILITATE JOINT MAKING AND INSPECTION. PRECAUTIONS SHALL BE TAKEN TO PREVENT EROSION OF JOINT MATERIAL BY MONING CURRENTS OF WATER.

14. COMPLETED JOINTS/MORTAR JOINTS SHALL BE KEPT DAMP AND PROTECTED FROM THE DIRECT RAYS OF SUN UNTIL BACKFILLING TAKES PLACE.
15. DRAINAGE LINES SHALL BE CONSTRUCTED TO THE TOLERANCES AS FOLLOWS:

PIPELINE GRADING	LINE TOLERANCE (mm)	LEVEL TOLERANCE (mm)
-LESS THAN 0.8%	50	10
-0.8% TO 1%	50	20
-GREATER THAN 1%	50	40
16. NOT WITHSTANDING THE TOLERANCES ABOVE EACH PIPE SHALL HAVE A MINIMUM FALL (APPROVED BY THE SUPERINTENDENT) IN THE DIRECTION OF FLOW.
17. ALL BACKFILL MATERIAL SHALL BE INSPECTED AND APPROVED BY THE SUPERINTENDENT PRIOR TO PLACING AND COMPACTION.
18. ALL BACKFILL FOR STORMWATER DRAINAGE WORKS IS TO BE COMPACTED IN LAYERS TO A MINIMUM OF 150mm TO LOOSE THICKNESS AND COMPACTED WITHOUT DAMAGING OR DISPLACING THE PIPEWORK.
19. ALL BACKFILL FOR STORMWATER PITS AND PIPES SHALL BE COMPACTED TO AT LEAST 95% OF THE MAXIMUM DRY DENSITY AND GRADED IN ACCORDANCE WITH AS 3500 (2003).
20. UNLESS SPECIFIED OTHERWISE ALL DRAINAGE PITS TO BE CAST IN SITU. THE GRADE OF CONCRETE SHALL BE 20 MPa COMPRESSED STRENGTH. THE MINIMUM STRENGTH OF 35 MPa STEEL REINFORCEMENT SHALL COMPLY WITH THE REQUIREMENTS OF AS1012. WELDED WIRE REINFORCING SHALL COMPLY WITH AS1038.
21. GALVANISED STEEL STEP IRONS AT SPACINGS OF 0.3m ARE REQUIRED IN ALL DRAINAGE PITS GREATER THAN 1.2m DEEP.
22. UNLESS SPECIFIED ALL DRAINAGE GRATES TO BE GALVANISED MILD STEEL TO AS 3598 AND CLASS B.

22. ALL CAST IN-SITU CONCRETE DRAINAGE PITS SHALL BE CONSTRUCTED TO THE FORMS AND DIMENSIONS SHOWN ON THE DRAWINGS. WHERE THE GROUND IS SOLOID THE SUPERINTENDENT MAY PERMIT THAT BACK FORMS NEED NOT BE USED IN THE CONSTRUCTION OF PITS. THE CONCRETE SHALL BE PLACED IN THE EARTH, WHERE THIS IS DONE, THE THICKNESS OF THE WALLS OF SUCH PITS SHALL BE NOTED ON THE DRAWINGS. ALL COSTS ASSOCIATED WITH THIS INCREASE IN THICKNESS SHALL BE BORNE BY THE CONTRACTOR.
23. ALL PRE-CAST PITS TO BE BOP PRE-CAST (OR APPROVED EQUIVALENT) WITH MINIMUM BASE HEIGHT OF 150MMAL (SEE ORDER CODE PTO-1150) AND THE MINIMUM NUMBER OF RISERS REQUIRED TO MAKE UP THE SPECIFIED PIT DEPTH.
24. uPVC PIPES SHALL CONFORM IN ALL RESPECTS WITH THE REQUIREMENTS OF AS1244. THE CLASS OF PIPES SHALL BE uPVC STORMWATER HO' DESIGNED FOR SOLVENT WELD SPIGOT AND SOCKET CONNECTION UNLESS NOTED OTHERWISE.
25. uPVC PIPES SHALL BE SUPPLIED WITH SUFFICIENT QUANTITIES OF SOLVENT FOR MAKING OF THE PIPE JOINTS.
26. uPVC PIPE ENDS SHALL BE THOROUGHLY CLEANED BEFORE THE JOINT IS MADE. JOINTING SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS USING JOINTING SOLVENT AND PRIMER.
27. uPVC PIPES SHALL BE TRANSPORTED, HANDLED AND STACKED IN ACCORDANCE WITH MANUFACTURERS RECOMMENDATIONS.
28. uPVC PIPE LAYING SHALL BEGIN AT THE DOWNSTREAM END OF THE LINE WITH THE DOWNSTREAM END OF THE PIPE FLANGE UPSTREAM. WHEN THE PIPES ARE Laid THE SLOPE OF EACH PIPE SHALL BE IN CONTACT WITH THE BEDDING MATERIAL THROUGHOUT ITS FULL LENGTH.
29. THE uPVC PIPE ENDS SHALL BE THOROUGHLY CLEANED BEFORE THE JOINT IS MADE. JOINTING SHALL BE IN ACCORDANCE WITH THE MANUFACTURERS DIRECTIONS USING JOINTING SOLVENT AND PRIMER.

**1. ALL ATLANTIS PRODUCTS ARE TO BE INSTALLED IN ACCORDANCE WITH THE MANUFACTURERS SPECIFICATIONS.**

2. FILTRATION UNIT TO BE ATLANTIS LARGE FILTRATION UNIT (PART No. 6003A) WITH ALUMINUM LO AND GEOTEXTILE BASKET.
3. ATLANTIS MATRIX TANK MODULES TO BE EITHER "DOUBLE MODULE" (PART No. 7000A) OR "TRIPLE MODULE" (PART No. 7000B) WITH A MINIMUM CRUSH STRENGTH OF 28.83/cm<sup>2</sup>.
4. MINIMUM ATLANTIS CELL BACKFILL COVER IN NON-TRAFFICABLE AREAS IS TO BE 500MM.
5. NON-WOVEN GEOTEXTILE TO BE PLACED AROUND ENTIRE PERIMETER OF FINISHED BLOCK OF ATLANTIS CELLS.
6. AT PENETRATIONS THROUGH THE OUTER GEOTEXTILE LAYER, ADDITIONAL CELL TO BE PLACED WITH MINIMUM OVERLAP OF 500MM BETWEEN ATLANTIS CELL & ORIENT OF INCOMING/OUTGOING PIPE.

1. EXCAVATION IN ROCK SHALL BE MINIMISED, WHERE THE DESIGN WOULD REQUIRE EXTENSIVE EXCAVATION IN ROCK, THE SUPERINTENDENT SHALL BE INFORMED PRIOR TO PROCEEDING.

2. ALL EXCAVATION WORKS ADJACENT TO EXISTING STRUCTURES OR IN UNSTABLE CONDITIONS MUST INCLUDE SHORING.
3. THE CONTRACTOR SHALL OBTAIN CURRENT SERVICE LOCATIONS FROM ALL RELEVANT AUTHORITIES PRIOR TO THE COMMENCEMENT OF WORKS.
4. WHERE EXCAVATION WORK IS REQUIRED IN THE VICINITY OF EXISTING SERVICES, THE CONTRACTOR SHALL LOCATE AND SUPPORT ALL SERVICES DURING THE WORKS.
5. WHERE EXCAVATED MATERIAL IS TO BE USED FOR FILLING, THE MATERIAL SHALL BE INSPECTED AND APPROVED BY THE SUPERINTENDENT PRIOR TO USE.
6. ALL WASTE MATERIALS SHALL BE DISPOSED OFF-SITE IN AN APPROPRIATE MANNER.

1. ALL WORKMANSHIP AND MATERIALS SHALL BE IN ACCORDANCE WITH AS 3600 CURRENT EDITION WITH AMENDMENTS, EXCEPT WHERE VARIED BY THE CONTRACT DOCUMENTS.


2. CONCRETE USED IN THE WORKS SHALL BE EITHER MASS CONCRETE OR REINFORCED CONCRETE AS NOTED ON THE DRAWINGS AND SHALL COMPLY WITH THE FOLLOWING REQUIREMENTS:

- | PROPERTY CLASSIFICATION              | REINFORCED CONCRETE | MASS CONCRETE      |
|--------------------------------------|---------------------|--------------------|
| MINIMUM 28 DAY COMPRESSIVE STRENGTH  | 82 MPa              | A1                 |
| MAXIMUM 28 DAY COMPRESSIVE STRENGTH  | 32 MPa              | 25 MPa             |
| COASTAL TYPE                         | GENERAL PURPOSE     | GENERAL PURPOSE    |
| WATER / BINDER RATIO ( MAX.)         | 0.40                | 0.40               |
| SLURRY COVER TO REINFORCEMENT (MIN.) | 40mm                | -                  |
| FINISHED SURFACE FINISH              | WOOD FLOAT          | GLASS 2 WOOD FLOAT |
3. THE FINISHED CONCRETE SHALL BE DENSE HOMOGENEOUS MASS COMPLETELY FILLING THE FORMWORK, THOROUGHLY EMBEDDING THE REINFORCEMENT AND FREE OF STONE POCKETS. CONCRETE SHALL BE COMPACTED WITH MECHANICAL VIBRATORS.
4. THE FINISHED CONCRETE SURFACE SHALL BE FREE OF CRACKS HAVING A CRACK WIDTH EQUAL TO OR GREATER THAN 0.1 mm AT THE OF PRACTICAL COMPLETION. IF CRACKING EXCEEDS THIS LIMIT, THE CONTRACTOR SHALL MAKE GOOD THE CRACKS TO THE SATISFACTION OF THE SUPERINTENDENT WHICH MUST COMPRISE REPLACEMENT OF THE CONCRETE ELEMENT OR SEALING THE CRACKS WITH SILANE/SILICA FUME GEL OR OTHER WORKS.

1. THE SUPERINTENDENT SHALL BE GIVEN 24 HOURS NOTICE FOR REINFORCEMENT INSPECTION AND CONCRETE SHALL NOT BE DELIVERED UNTIL FINAL APPROVAL IS OBTAINED.

- ## 2. REINFORCEMENTS SYMBOLS:

- |     |  |
|-----|--|
| N   | DENOTES GRADE 500 N BARS TO A5/NZS 4671 DUCTILITY CLASS N                      |
| R   | DENOTES GRADE 250 R HOT ROLLED PLAIN BARS TO AS 1302 DUCTILITY CLASS N         |
| SL  | DENOTES GRADE 500 L DEFORMED WELDED WIRE MESH TO A5/NZS 4671 DUCTILITY CLASS L |
| SN  | DENOTES GRADE 500 N DEFORMED WELDED WIRE MESH TO A5/NZS 4671 DUCTILITY CLASS N |
| LTM | DENOTES GRADE 500 L DEFORMED WIRE TRENCH MESH TO A5/NZS 4671 DUCTILITY CLASS L |



- | 17  | NUMBER OF BARS IN GROUP    |
|-----|----------------------------|
| N   | BAR GRADE AND TYPE         |
| 20  | NOMINAL BAR DIAMETER IN mm |
| 250 | MAXIMUM SPACING IN mm      |
| 17  |                            |
| N   |                            |
| 20  |                            |
| 250 |                            |

6. SPLICES IN REINFORCEMENT SHALL BE MADE ONLY IN POSITIONS SHOWN OR OTHERWISE APPROVED IN WRITING BY THE SUPERINTENDENT. LAPS SHALL BE IN ACCORDANCE WITH AS 3600 AND NOT LESS THAN THE DEVELOPMENT LENGTH FOR EACH BAR AND SHALL BE AS FOLLOWS:

BAR DIA	LAP LENGTH
12	400
16	500

7. JOGLES TO BARS SHALL BE 1 BAR DIAMETER OVER A LENGTH OF 12 BAR DIAMETERS.
8. FABRIC SHALL BE LAPPED 2 TRANSVERSE WIRES PLUS 50 mm. BOUNDED WIRE SHALL BE TIED TOGETHER AT 30 BAR DIAMETER CENTRES WITH 3 WRAPS OF 11 WIRE.
9. WHERE TRANSVERSE TIE BARS ARE NOT SHOWN PROVIDE N12-400 SPUCED WHERE NECESSARY AND LAP WITH MAIN BARS 400 mm U.N.O.
10. THE FOLLOWING NOTATIONS MAY HAVE BEEN USED ON THE DRAWINGS.

1. UNLESS NOTED OTHERWISE ALL CONCRETE FORMWORK SHALL BE FOR A CLASS 2 FINISH.

2. THE DESIGN CERTIFICATION, CONSTRUCTION AND PERFORMANCE OF THE FORMWORK AND FALSEWORK IS THE RESPONSIBILITY OF THE CONTRACTOR.
3. DESIGN AND CONSTRUCTION AND STRIPPING TIMES SHALL COMPLY WITH AS 3610 AND AS 3600 UNLESS OTHERWISE NOTED OR APPROVED BY THE SUPERINTENDENT.
4. DURING CONSTRUCTION, SUPPORT PROPPING WILL BE REQUIRED WHERE LOADS FROM STACKED MATERIALS, FORMWORK AND OTHER SUPPORTED SLABS INDUCE LOADS IN A SLAB OR BEAM WHICH EXCEED THE DESIGN LOAD FOR STRENGTH OR SERVICEABILITY AT THAT AGE. ONCE THE NOMINATED 28 DAY STRENGTH HAS BEEN ATTAINED, THESE LOADS SHALL NOT EXCEED THE DESIGN SUPERIMPOSED LIVE LOADS.
5. THE FORMWORK SHALL NOT BE DESIGNED TO RELY ON RESTRAINT OR SUPPORT FROM THE PERMANENT STRUCTURE WITHOUT THE PRIOR APPROVAL OF THE SUPERINTENDENT.

**1. UNLESS OTHERWISE SPECIFIED ALL EXCAVATIONS ARE TO BE REINSTATED TO THEIR EXISTING GROUND SURFACE LEVEL.**

1. UNLESS OTHERWISE SPECIFIED, ALL SURFACES ARE TO BE REINSTATED TO THE EXISTING SURFACE CONDITION (e.g., ROAD PAVEMENT, KERB AND GUTTER, GRASSSED VERGE OR FLOOPIUM).
2. IF FENCES ARE DAMAGED OR REMOVED DURING CONSTRUCTION THEY ARE TO BE REINSTATED AT THE COMPLETION OF THE WORKS AT THE CONTRACTOR'S EXPENSE.
3. ALL PAVEMENT RECONSTRUCTION TO BE IN ACCORDANCE WITH COUNCIL'S STANDARD SPECIFICATION, AUS-SPEC OR RTA SPECIFICATIONS AS DIRECTED BY THE SUPERINTENDENT.

ALL LEVELS ARE TO AUSTRALIAN  
HEIGHT DATUM

**CONTRACTOR SHALL CALL:  
DIAL BEFORE  
YOU DIG 1100**



0545/06

七

## GENERAL NOTES AND SPECIFICATIONS

10 JAN 2007


Drawing No.

**4670-01-02**

३३

4670-01-01





## PIT SCHEDULE


PT. No.	PT. SIZE	PT. DEPTH	PT. INVERT RL.	PT. TYPE	PT. LID	CORNER #	MC-EST	MC-GRTH
DCP1	900x600	1300	22.94	PRE-CAST	GALVANISED GRATE	71	341087.561	627097.4,2,40
2/1	900x600	1300	RETER LONG SECTION	PRE-CAST	SOLID COVER		341115.422	627097.1,5,65
3/1	900x600	1300	RETER LONG SECTION	PRE-CAST	SOLID COVER		341113.551	627093.3,3,39
4/1	900x600	1300	RETER LONG SECTION	PRE-CAST	SOLID COVER		341111.878	627093.7,0,59
5/1	900x600	1300	RETER LONG SECTION	PRE-CAST	SOLID COVER		341110.205	627092.0,7,84
6/1	900x600	1700	RETER LONG SECTION	CAST-IN-SITU	SOLID COVER		341109.560	627094.0,2,40
7/1	900x600	1700	RETER LONG SECTION	CAST-IN-SITU	SOLID COVER		341108.325	627094.3,3,39
8/1	900x600	1500	RETER LONG SECTION	CAST-IN-SITU	SOLID COVER		341103.325	627095.3,7,54
9/1	EXISTING	EXISTING	RETER LONG SECTION	EXISTING	SOLID COVER		341101.623	627093.7,1,54
10/1	EXISTING	EXISTING	RETER LONG SECTION	EXISTING	SOLID COVER		EXISTING	EXISTING
1/1	900x600	2000	RETER LONG SECTION	CAST-IN-SITU	GALVANISED GRATE		341105.188	627098.0,5,22
2/2	900x600	1700	RETER LONG SECTION	CAST-IN-SITU	GALVANISED GRATE		341103.701	627098.7,1,73
DCP2	900x600	1800	13.20	CAST-IN-SITU	GALVANISED GRATE	103	341102.504	627098.1,2,86
DCP3	900x600	1300	22.10	PRE-CAST	GALVANISED GRATE	71	341115.563	627097.3,9,25
DCP4	900x600	1300	21.30	PRE-CAST	GALVANISED GRATE	71	341111.845	627098.4,3,74
DCP5	900x600	1300	20.45	PRE-CAST	GALVANISED GRATE	77	341108.505	627098.5,0,25
DCP6	900x600	1500	18.40	PRE-CAST	GALVANISED GRATE	71	341108.287	627098.1,1,806
DCP7	900x600	1300	18.40	PRE-CAST	GALVANISED GRATE	77	341106.936	627098.0,4,22
DCP8	900x600	1500	12.50	CAST-IN-SITU	GALVANISED GRATE	77	341101.635	627098.3,7,98
DCP9	900x600	1800	12.50	CAST-IN-SITU	GALVANISED GRATE	75	341095.583	627098.3,4,21

1. REFER TO 4670-01-03 FOR DETAILS OF CAST-IN-SITU PITS.
2. ALL PIT LIDS TO BE A MINIMUM OF CLASS B ACCORDING TO AS 3986-1982.
3. PIT CO-ORDINATES ARE CENTRE OF LID.
4. ALL CO-ORDINATES ARE ON A LOCAL SYSTEM, REFER TO DWG. 4670-01-03 FOR DATUM.



# ATLANTIS DETENTION/FILTRATION TANK SCHEDULE

TANK No.	TANK SIZE	TANK HEIGHT	TANK VOL.	MIN BASE RL.	POINT A		POINT B	
					MEAST	MONTH	MEAST	MONTH
D1	4080x5480	880	16.3	23.14	34108.181	6270878.707	34108.477	6270878.329
D12	4080x5480	880	16.3	22.30	34108.181	6270878.703	34111.5	6270878.424
D13	4080x5480	880	16.3	21.52	34108.181	6270878.583	34111.089	6270860.362
D14	3812x6265	880	21.8	18.70	34102.472	6270873.686	34110.180	6270877.445
D15	3812x6265	880	21.8	18.70	34102.472	6270873.686	34108.172	6270861.131
D16	3812x6265	880	18.60	18.60	34108.671	6270867.124	34110.4	6270868.746
D17	4448x8220	1310	44.6	13.40	34108.671	6270867.124	34110.4	6270868.746
D18	4080x6550	880	24.7	12.50	34108.176	6270864.245	34102.453	6270864.044
D19	4080x6550	880	24.7	12.50	34108.176	6270864.245	34102.453	6270864.044

1. TANK CO-ORDINATES DEFINE THE SOUTH-WEST (POINT A) AND NORTH-EAST (POINT B) CORNERS OF EACH TANK.
2. ALL CO-ORDINATES ARE ON A LOCAL SYSTEM, REFER TO DMC 4670-01-03 FOR DATUM.




	Datum RL.				
PIPE INVERT	16.02	14.00			
NATURAL SURFACE	18.0		14.20 13.50		
			13.42 13.40		
			13.40 13.42		
			13.40 13.30		
			13.20		
CHAINAGE	0.00		18.87	21.16	28.81
					31.01
					32.98




**DRG STATUS: PRELIMINARY, NOT FOR CONSTRUCTION**

DRAINAGE LINE 1 LONG SECTION


[illegible]



Drawing No.	4670-01-05
Issue	B
Cod File No.	







PITTWATER COUNCIL CONSTRUCTION CERTIFICATE

Number: CC0545106

This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.

Endorsed by:

Date: 10 JAN 2007


7 4 9 7 9 1

D. P.

STABILISED SITE ACCESS  
POINT (SD6-14)

STABILISED SITE ACCESS  
POINT (SD6-14)

PASS 24  
RL 25.74 AND



1 0 4 8 2 1 9  
210

211

207 208 209

205

204

2221

206

704

705

706

707

709

710

316

305

SEDIMENT BASIN (SD6-3)  
SURFACE AREA = 12m<sup>2</sup>  
VOLUME = 10m<sup>3</sup>  
ASSUMED TYPE C SOIL

SEDIMENT BASIN (SD6-3)  
SURFACE AREA = 16m<sup>2</sup>  
VOLUME = 17m<sup>3</sup>  
ASSUMED TYPE C SOIL

DESIGNATED STOCKPILE

SILT FENCE (SD6-8)

LEGEND  
EXISTING SURFACE CONTOUR (1m INTERVAL)  
SILT FENCE  
SEDIMENT BASIN

DESIGNATED STOCKPILE  
MANAGING URBAN STORMWATER SOILS AND  
CONSTRUCTION' STANDARD DRAWING NUMBER  
(SD6-3)

NOTES  
1. ALL DEVICES TO BE INSTALLED AND MAINTAINED IN  
ACCORDANCE WITH THE NSW 'MANAGING URBAN STORMWATER  
SOILS AND CONSTRUCTION' HANDBOOK DATED MARCH 2004.  
2. ALL DISTURBED AREAS ARE TO BE STABILISED IMMEDIATELY  
UPON COMPLETION OF EARTHWORKS.

DRG STATUS : **PRELIMINARY, NOT FOR CONSTRUCTION**

INITIALS SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED. ANY CHANGES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG REGISTER/TRANSNATL FORM No.5.2.2				level 4 104 Mount Street North Sydney 2060 Telephone (02) 9957 1619 Facsimile (02) 9957 7361 email reception @patterson.com.au A.C.N. 003 220 225				Client V, D AND M BUBALO				Title SEDIMENT AND EROSION CONTROL PLAN				Drawing No. 4670-01-06			
Issue				Issue				Project				Issue				Cod File No.			
A				A				7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				A				4670-01-06			
ISSUED FOR CC APPROVAL				ISSUED FOR CC APPROVAL				7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				A				4670-01-06			
Details of Issue				Details of Issue				7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				A				4670-01-06			
Date				Date				7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				A				4670-01-06			
Approved				Approved				7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				A				4670-01-06			
Date				Date				7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				A				4670-01-06			
Approved				Approved				7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				A				4670-01-06			
Date				Date				7 & 7A ORCHARD STREET INTERALLOTMENT DRAINAGE DESIGN				A				4670-01-06			



PITTWATER COUNCIL CONSTRUCTION CERTIFICATE	
Number:	CC 0545106
This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.	
Endorsed by:	RA
Date:	10 JAN 2007

---

## FIGURES

---

000545106  
10 JAN 2007





PITTWATER COUNCIL CONSTRUCTION CERTIFICATE	
Number:	CC 0545/06
This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.	
Endorsed by:	<i>Plu</i>
Date:	10 JAN 2007

---

## APPENDIX A – CC CHECKLIST

---



Number: CC 0545106  
 Lawson & Treloar Pty Ltd

 This is a copy of submitted plans, documents or  
 Certificates associated with the issue of the  
 Construction Certificate

Date: 10 JAN 2007

## DOCUMENTATION CHECKLIST - HANDOVER

(Detach and include with submissions)

Section	Item	Requirement	Check (✓)
4.1	Water Cycle Assessment - Water Balance Modelling Pre & Post Development		
4.1.1	Stream Gauging, infiltration testing and use of local rainfall data for modelling		
4.2.1	Water Quality Monitoring Plan	♦♦♦♦♦♦♦♦	✓
4.2.1	Water Quality Monitoring Sites Shown on Plan (at least three)	♦♦♦♦♦♦♦♦	✓
4.2.1, 2, C	Water Quality Monitoring Data	♦♦♦♦♦♦♦♦	✓
4.2.1, 2, C	Assessment and interpretation of water quality monitoring data	♦♦♦♦♦♦♦♦	✓
4.2.1, 2, C	Assessment and interpretation of water quality monitoring data from SQID's	♦♦♦♦♦♦♦♦	✓
4.3	Water Quality Management Assessment - Load Modelling Pre and Post Development		
4.3.1, 3	Justification of assumptions for Event Mean Concentrations		
4.3.2	Identification of and details for Stormwater quality facilities		✓
4.3.2, 4.4.5	Mosquito Risk Assessment for both Watercourse and Water Quality/Quantity features	♦♦♦♦♦♦♦♦	✓
4.3.6, 4.6.5	Inspection and Cleaning Reports for SQID's and OSD	♦♦♦♦♦♦♦♦	✓
4.3.6	Management Plan for Stormwater Quality Improvement Devices	♦♦♦♦♦♦♦♦	✓
4.3.5	Environmental Management Plan (Soil and Water Aspects)		
4.3.4	Erosion and Sediment Control Plan		
4.4.3, 4, 5	Existing and Proposed Creek Corridor in plan with cross/long sections with flood levels		
4.4.4	Proposed Creek Corridor Planting Schedule		
4.4.5	Creek Corridor Vegetation Monitoring and Management Plan	♦♦ Note 1 ♦♦	NA
4.4.5	Vegetation and Creek Maintenance and Monitoring Reports	♦♦ Note 1 ♦♦	NA
4.5	Flood Analysis – existing and design conditions		
4.5.2	Compliance of structures and creek corridor with flood planning levels		
4.5.4	Details of Interim Flood Protection Works	♦♦♦♦♦♦♦♦	NA
4.6.3	Design Storm Hydrological Modelling of Site - Pre and Post Development		
4.6.3	On-Site Detention Facilities		
4.6.4	Stormwater Retention Facilities		
4.7	Stormwater Concept Drainage Plan		

### KEY:

	Preliminary Calculations/Assessment Required		Work as Executed Plans
	Concept Design Required	♦♦♦♦♦♦	Required/Reviewed/Updated
+++++	Detailed Assessment/Calculations/Design		Not required

Note 1 Even if the works are not to be constructed by the Applicant on the land to be transferred to Council under the Material Public Benefit Option in the Section 94 Plan, preliminary investigation for Rezoning and concept design at DA stage is required

Completed by Principal Certifier:

 Name: ..... Michael Shaw  
 Title: ..... Senior Associate CPEng, NPER  
 Organisation: ..... Paterson Britton + Partners  
 Signature: .....  
 Date: ..... 2/4/05



PITTWATER COUNCIL CONSTRUCTION CERTIFICATE

Number: CC 0545106

This is a copy of submitted plans, documents or  
Certificates associated with the issue of the  
Construction Certificate.

Endorsed by: ka

Date: 10 JAN 2007

---


## APPENDIX B – CC ACCESS ROAD DRAWINGS

---

ORCHARD STREET ACCESS ROAD,  
WARRIEWOOD  
CIVIL ROAD DESIGN  
for  
V, D AND M BUBALO

PROJECT RECORD COPY  
0575106

10 JAN 2007



DRAWING LIST:	
4670-01	TITLE SHEET, LOCALITY PLAN AND DRAWING LIST
4670-02	GENERAL NOTES & SPECIFICATIONS (SHEET 1 OF 2)
4670-03	GENERAL NOTES & SPECIFICATIONS (SHEET 2 OF 2)
4670-04	SITE PLAN AND LONGITUDINAL SECTION
4670-05	CUL-DE-SAC KERB DEVELOPMENT AND ACCESS ROAD TYPICAL SECTION
4670-06	ACCESS ROAD DESIGN CROSS SECTIONS SHEET 1 OF 3
4670-07	ACCESS ROAD DESIGN CROSS SECTIONS SHEET 2 OF 3
4670-08	ACCESS ROAD DESIGN CROSS SECTIONS SHEET 3 OF 3
4670-09	PROPOSED SURFACE CONTOURS AND PAVEMENT DESIGN
4670-10	STORMWATER DRAINAGE PLAN
4670-11	STORMWATER DRAINAGE LONGITUDINAL SECTIONS
4670-12	EROSION AND SEDIMENT CONTROL PLAN

DRG STATUS : **PRELIMINARY, NOT FOR CONSTRUCTION**

INITIALS SHOWN IN THE ADJACENT ISSUE	
C	ISSUED FOR TENDER
B	ISSUED FOR APPROVALS
A	ISSUED FOR REVIEW
Issue	Details of Issue
DS	DS
ARG	ARG
MS	MS
FC	FC
ARG	ARG
MS	MS
25.01.05	25.01.05
HELD BY PATTERSON BRITTON & PARTNERS	

Level 4 104 Mount Street North Sydney 2060 Telephone: (02) 9957 1613 Facsimile: (02) 9957 1231 e-mail: <a href="mailto:info@pbr.com.au">info@pbr.com.au</a> A.C.N. 003 220 228	<b>Patterson Britton &amp; Partners Pty Ltd</b> consulting engineers
--	---

Client V, D AND M BUBALO	Project ORCHARD STREET ACCESS ROAD WARRIEWOOD
-----------------------------	---

Title TITLE SHEET, LOCALITY PLAN AND DRAWING LIST
---

Drawing No. 4670-01	Issue C	Cad File No. 4670-01
------------------------	------------	-------------------------



ASPHALTIC CONCRETE NOTES

1. GENERAL
- A) MINERAL AGGREGATES TO COMPLY WITH CLAUSE 2.1 - MATERIALS OF R115 SPECIFICATION R116 "ASPHALT (DENSE AND OPEN GRADED)".
- B) MINERAL FILLERS TO COMPLY WITH AS2357-1980 MINERAL FILLS FOR "ASPHALT (DENSE AND OPEN GRADED)".
- C) BITUMEN BINDER SHALL COMPLY WITH R116 SPECIFICATION R116 - "ASPHALT (DENSE AND OPEN GRADED)".
2. MIX PROPORTIONS
- A) JOB MIX - 10mm & 14mm (AS SPECIFIED ON DRAWINGS) NOMINAL SIZE AGGREGATE MINIMUM BITUMEN CONTENT (%) BY MASS OF TOTAL MASS - 5.1%.
- B) MIX STABILITY - BETWEEN 16KN AND 36KN AS DETERMINED BY R116 TEST METHODS T605 AND T607.
- C) AIR VOIDS IN COMPACTED MIX - BETWEEN 4% AND 7% OF THE VOLUME OF THE MIX.
- D) VOIDS FILLED IN BINDER - 65-80% OF AIR VOIDS IN THE TOTAL MINERAL AGGREGATE FILLED BY BINDER IN ACCORDANCE WITH R116 TEST METHOD T605 AND T607.
3. PAVEMENT PREPARATION
- A) THE EXISTING SURFACE TO BE SEALED SHALL BE DRY AND BROOKE BEFORE COMMENCEMENT OF WORK TO ENSURE COMPLETE REMOVAL OF ALL SUPERFICIAL FOREIGN MATTER.
- B) ALL DEPRESSIONS OR UNEVEN AREAS ARE TO BE TACK-COATED AND BROUGHT UP TO GENERAL LEVEL OF PAVEMENT WITH ASPHALTIC CONCRETE BEFORE LAYING OF MAIN COURSE.
4. TACK COAT
- A) THE WHOLE OF THE AREA TO BE SHEETED WITH ASPHALTIC CONCRETE SHALL BE THOROUGHLY AND EVENLY COATED WITH RAPID SETTING BITUMEN COURING WITH R116 SPECIFICATION 3224, 3224, 3224 AND 3269. APPLICATION RATE FOR RESOAL BITUMEN SHALL BE 0.15 TO 0.30 LITRES/SQUARE METRE. APPLICATION SHALL BE BY MEANS OF A MECHANICAL SPRAYER WITH SPRAY BAR.
5. SPREADING
- A) ALL ASPHALTIC CONCRETE SHALL BE SPREAD WITH A SELF PROPELLED PAVING MACHINE.
- B) THE ASPHALTIC CONCRETE SHALL BE LAD AT A MIX TEMPERATURE AS SHOWN BELOW.
- C) ROAD SURFACE TEMPERATURE IN SHADE (ACC) MIX TEMPERATURES (CC) SHALL NOT EXCEED
- 10-15 150
- 15-25 145
- OVER 25 140
- C) ASPHALTIC CONCRETE SHALL NOT BE LAD WHEN THE ROAD SURFACE IS WET OR WHEN COLD WINDS CHILL THE MIX TO ADVERSELY AFFECT SPREADING AND COMPACTION.
6. JOINTS
- A) THE NUMBER OF JOINTS BOTH LONGITUDINAL AND TRANSVERSE SHALL BE KEPT TO A MINIMUM.
- B) THE DENSITY AND SURFACE FINISH AT JOINTS SHALL BE SIMILAR TO THOSE OF THE REMAINDER OF THE LAYER.
7. COMPACTION
- A) ALL COMPACTION SHALL BE UNDERTAKEN USING SELF PROPELLED ROLLERS.
- B) INITIAL ROLLING SHALL BE COMPLETED BEFORE THE MIX TEMPERATURE FALLS BELOW 105°C.
- C) SECONDARY ROLLING SHALL BE COMPLETED BEFORE THE MIX TEMPERATURE FALLS BELOW 80°C USE PNEUMATIC TYRED ROLLER.
- D) MINIMUM CHARACTERISTICS VALUE OF RELATIVE COMPACTION OF A LOT WHEN TESTED IN ACCORDANCE WITH CLAUSE 4.9 - COMPACTION OF R116 SPECIFICATION 116 "ASPHALT (DENSE AND OPEN GRADED)" SHALL BE 95%.
8. FINISHED PAVEMENT PROPERTIES
- A) FINISHED SURFACES SHALL BE SMOOTH DENSE AND TRUE TO SHAPE AND SHALL NOT VARY MORE THAN ALLOWED BY THE SPECIFIED PLAN LEVEL AT ANY POINT AND SHALL NOT DEVIATE FROM THE BOTTOM OF A GRADY 3M STRAIGHT EDGE LAD IN ANY DIRECTION BY MORE THAN 5MM.
9. THE PROPOSED 1m WIDE ROAD SHOULDER AT THE WESTERN EDGE OF THE NEW ROAD IS TO BE STABILISED WITH A FLUSH SEAL FINISH.

SOIL EROSION AND SEDIMENT CONTROL NOTES

1. SOIL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO THE STANDARD RECOMMENDED BY THE NSW DEPARTMENT OF HOUSING BLUE BOOK TITLE "MANAGING URBAN STORMWATER SOILS AND CONSTRUCTION", 4TH EDITION, MARCH 2004.
2. THE CONTRACTOR AND ALL SUBCONTRACTORS SHALL INFORM THEIR STAFF OF THEIR OBLIGATIONS UNDER THIS EROSION AND SEDIMENT CONTROL SECTION.
3. SILT SOCKS AND GEOTEXTILE FILTER FABRIC SHALL BE INSTALLED AT ALL DRAINAGE INLET PITS.
4. ALL EROSION AND SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED PRIOR TO COMMENCEMENT OF CONSTRUCTION.
5. ALL SEDIMENT CONTROL STRUCTURES SHALL BE INSPECTED AFTER EACH SIGNIFICANT EVENT FOR STRUCTURAL DAMAGE AND ALL TRAPPED SEDIMENT TO BE REMOVED TO THE APPROPRIATE STOCKPILE.
6. STABILISE ALL COMPLETED ROAD BATTERS WITH HYDROMULCH.

CONSTRUCTION MATERIALS

1. MATERIALS AND WORKMANSHIP SHALL BE THE BEST OF THEIR RESPECTIVE KINDS, AND, UNLESS OTHERWISE SPECIFIED, SHALL CONFORM TO THE RELEVANT AUSTRALIAN STANDARDS.
2. SUPERINTENDENT NOTICE SHALL BE GIVEN BY THE CONTRACTOR TO THE SUPERINTENDENT TO EVALUATE ANY MATERIALS THAT ARE BROUGHT ON THE SITE TO BE EXAMINED. ALL MATERIALS ARE TO BE SUITABLY STACKED TO FACILITATE EXAMINATION.
3. WHERE THE CONTRACTOR SUPPLIES MATERIALS OF A MIXED OR POOR QUALITY, THE SUPERINTENDENT SHALL HAVE THE POWER TO REQUIRE THE CONTRACTOR TO PICK OUT AND STACK THOSE MATERIALS WHICH IN HIS OPINION ARE SUITABLE FOR THE WORKS, AND TO HAVE THOSE UNSUITABLE REMOVED FROM THE SITE OF THE WORKS.

DRG STATUS : **PRELIMINARY, NOT FOR CONSTRUCTION**

Issue		Details of Issue		Issued	By	Checked	Approved	Date
C		ISSUED FOR TENDER		DS	ARG	MS		18.07.05
B		ISSUED FOR APPROVALS		FC	ARG	MS		18.02.05
A		ISSUED FOR REVIEW		ARG	ARG	MS		23.01.05
Issue		Details of Issue		Issued	By	Checked	Approved	Date

NOTES SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE CHANGES UNDERTAKEN IN THE DRAWING APPROVALS. CHANGES TO THE DRAWING APPROVALS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG HELD BY PATTERSON BRITTON & PARTNERS

Level 4  
100 York Street  
New Sydney 2000  
Telephone (02) 9557 1619  
Facsimile (02) 9557 1291  
Email reception@pbr.com.au  
A/CN 609 229 228

**Patterson Britton & Partners Pty Ltd**  
consulting engineers

Client  
**V. D AND M BUBALO**

Project  
**ORCHARD STREET ACCESS ROAD  
WARRIEWOOD**

Title  
**GENERAL NOTES & SPECIFICATIONS  
SHEET 2 OF 2**

Drawing No.  
**4670-03**

Issue  
**C**

Cad File No.  
**4670-02**

Xref(s)


PATTERSON BRITTON & PARTNERS  
NO 0545/06  
10 JAN 2007





DRG STATUS:	PRELIMINARY, NOT FOR CONSTRUCTION
-------------	-----------------------------------

SCALE HORIZONTAL 1:300  
SCALE VERTICAL 1:150

CHAINAGE	DEPTH (+ = CUT)	EXISTING SURFACE	DESIGN	VS LENGTH GRADE HORIZONTAL DATUM 15
0.00	0	24.15	24.15	
5.00	0	24.54	24.54	
10.00	0	24.93	24.92	
14.67	0	25.29	25.28	
15.00	0	25.31	25.31	
20.00	0.01	25.71	25.70	7.7%
25.00	0.02	26.1	26.08	
30.00	0.02	26.48	26.47	
32.12	-0	26.63	26.63	
32.54	-0.01	26.66	26.66	
35.00	0	26.84	26.84	
40.00	0.14	27.23	27.09	-1.1%
42.54	0.22	27.38	27.16	
45.00	0.31	27.51	27.20	
47.45	0.37	27.58	27.21	
50.00	0.45	27.84	27.18	
52.54	0.51	27.63	27.12	
55.00	0.51	27.55	27.04	
60.00	0.47	27.35	26.88	
65.00	0.43	27.15	26.72	-3.7%
70.00	0.37	26.93	26.56	
75.00	0.28	26.68	26.40	
80.00	0.19	26.43	26.24	
82.14	0.15	26.32	26.17	
85.00	0.11	26.19	26.08	
90.00	0.08	25.96	25.88	
92.14	0.07	25.86	25.79	
95.00	0.07	25.72	25.65	
100.00	0.06	25.44	25.38	
102.14	0.07	25.33	25.26	
105.00	0.08	25.17	25.09	
110.00	0.1	24.89	24.79	-0.8%
115.00	0.07	24.57	24.49	
120.00	0.05	24.24	24.19	
124.25	0.03	23.97	23.84	
125.00	0.02	23.92	23.89	
129.25	0.02	23.64	23.63	
130.00	0.02	23.59	23.58	
134.25	0.04	23.32	23.28	
135.00	0.05	23.27	23.23	
140.00	0.08	22.95	22.87	
145.00	0.12	22.63	22.51	
150.00	0.16	22.32	22.15	
155.00	0.21	22	21.79	
160.00	0.25	21.69	21.44	
165.00	0.29	21.36	21.08	
170.00	0.3	21.02	20.72	-2.5%
175.00	0.3	20.66	20.36	
180.00	0.3	20.3	20.00	
185.00	0.29	19.93	19.64	
190.00	0.27	19.55	19.28	
195.00	0.25	19.17	18.92	
200.00	0.18	18.75	18.57	
205.00	0.14	18.35	18.21	
210.00	0.15	18	17.85	
211.06	0.15	17.92	17.77	
213.45		17.68		







CUL-DE-SAC PLAN  
1:100

GRADE	DATUM 14	APPROX 8.7%	17.0%	APPROX 15.4%
DESIGN	18.00	17.85	17.62	17.52
EXISTING SURFACE	18.15	17.99	17.83	17.66
CHAINAGE	12.00	14.00	16.00	18.00

DRIVEWAY LONG SECTION  
SCALE HORIZONTAL 1:100  
SCALE VERTICAL 1:100



CUL-DE-SAC KERB DEVELOPMENT



DRG STATUS : **PRELIMINARY, NOT FOR CONSTRUCTION**

Issue	Details of Issue	Des'd	Drn	Chkd	Approved	Date	INITIALS SHOWN IN THE ADJACENT ISSUE	RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG REGISTER/TRANSMITTAL FORM No.5.2.2.	Client	Title	Drawing No.
C	ISSUED FOR TENDER	DS	ARG	MS		18.07.05	Level 4 104 Mount Street North Sydney 2060	Patterson Britton & Partners Pty Ltd	V, D AND M BUBALO	CUL-DE-SAC KERB DEVELOPMENT AND ACCESS ROAD TYPICAL CROSS SECTION	4670-05
B	ISSUED FOR APPROVALS	FC	ARG	MS		18.02.05	Telephone (02) 9937 9419 Email: info@pbr.com.au A.C.N. 603 220 228	consulting engineers	Project	ORCHARD STREET ACCESS ROAD WARRIEWOOD	C
A	ISSUED FOR REVIEW	ARG	ARG	MS		25.01.05					4670-05

[illegible]


level 4  
104 Mount Street  
North Sydney 2060  
Telephone: (02) 5667 1418  
Fax: (02) 5667 1411  
e-mail: [enquiry@patterson.com.au](mailto:enquiry@patterson.com.au)  
A.C.N. 003 220 228

**Patterson  
Britton  
& Partners Pty Ltd**  
consulting engineers

Client	V, D AND M BUBALO
Project	ORCHARD STREET ACCESS ROAD WARRIEWOOD

ACCESS ROAD  
DESIGN CROSS SECTION  
SHEET 1 OF 3

Drawing No.	4670-06
Issue	C
Code File No.	4670-06
Ver.(s)	


$$\frac{545}{2}$$

10 JAN 2007



A1

DRG STATUS: **PRELIMINARY, NOT FOR CONSTRUCTION**






















DETAILS OF ISSUE				DETAILS OF ISSUE			
Issue	Drawn	Checked	Approved	Date	Issue	Drawn	Checked
C	ISSUED FOR TENDER	DS	ARG	MS	18.07.05		
B	ISSUED FOR APPROVALS	FC	ARG	MS	18.07.05		
B	ISSUED FOR REVIEW	ARG	MS	25.01.05			

NOTES SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG HELD BY PATTERSON BRITTON & PARTNERS.

Project: **ORCHARD STREET ACCESS ROAD WARRIEWOOD**

Client: **V. D AND M BUBALO**

Issue: **C**  
Cdd File No.: **4670-06**  
Xref(s):





APPROX EXISTING RETAINING WALL  
CH 150.00  
CH 145.00  
CH 140.00  
CH 135.00  
CH 130.00  
CH 125.00  
CH 120.00  
CH 115.00  
CH 110.00  
CH 105.00  
CH 100.00  
CH 95.00  
CH 90.00  
CH 85.00  
CH 80.00  
CH 75.00  
CH 70.00  
CH 65.00  
CH 60.00  
CH 55.00

0545/06  
PL  
10 JAN 2007




A1

DRG STATUS : **PRELIMINARY, NOT FOR CONSTRUCTION**

INITIALS SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE STAGES UNDERGONE IN THE DESIGN AND APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG HELD BY PATTERSON BRITTON & PARTNERS										Model 4 104 Mount Street North Sydney 2060 Telephone (02) 9557 4132 Fax (02) 9557 4131 email: info@pb.com.au A.C.N. 003 220 228										Patterson Britton & Partners Pty Ltd consulting engineers										Client V, D AND M BUBALO										Title ACCESS ROAD DESIGN CROSS SECTION SHEET 3 OF 3										Drawing No. 4670-08										Issue C										Cod File No. 4670-06										Xref(s)																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																										
Issue	Details of Issue	Des'd	Dwn	Chkd	Approved	Date																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																																				




10 JAN 2007



TYPICAL ROAD PAVEMENT DETAIL

- NOTE
1. THE BASE COURSE MATERIAL CAN BE DGB20 OR RECYCLED CONCRETE SATISFYING THE REQUIREMENTS OF DGB20 STANDARD PROVIDED IN THE R1A 3051 SPECIFICATION. THE SUB-BASE MATERIAL CAN BE CRUSHED SANDSTONE OR RECYCLED CONCRETE SATISFYING THE REQUIREMENTS OF DGB40 STANDARD PROVIDED IN THE R1A 3051 SPECIFICATION.
  2. THE MINIMUM COMPACTION DRY DENSITY RATIOS ARE AS FOLLOWS (AS1729.5.4.1-1993):
    - BASE COURSE 95% STANDARD
    - SUB-BASE 95% STANDARD
    - SUB-GRADE 100% STANDARD OR DENSITY RATIO OF 85%
  3. PAVEMENT WEARING COURSE TO CONSIST OF A 30mm THICK LAYER OF AC14 OVERLAIN BY A 20mm THICK LAYER OF AC10.
  4. FOR DETAILS OF THE REQUIRED ROAD PAVEMENT REFER TO PAVEMENT DESIGN REPORT PREPARED BY GEOTECHNIQUE PTY LTD, 14th JANUARY 2004.



DRG STATUS: PRELIMINARY, NOT FOR CONSTRUCTION

Issue	Details of Issue	Date	Dim	CHK'd	Approved	Date
A	ISSUED FOR REVIEW	ARG	MS			25.01.05
B	ISSUED FOR APPROVALS	ARG	MS			18.02.05
C	ISSUED FOR TENDER	DS	MS			18.07.05

INITIALS SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS NOTED FOR DRG STATUS. THE ORIGINAL SIGNATURES CAN BE FOUND ON THE REVERSE OF THIS DRAWING. THE DRG IS HELD BY PATTERSON BRITTON & PARTNERS.

Level 4  
104 Mount Street  
North Sydney 2060  
Telephone (02) 9597 1519  
Facsimile (02) 9597 1291  
Email reception@patterson.com.au  
A.C.N. 003 220 228

Patterson Britton  
& Partners Pty Ltd  
consulting engineers

Client  
V, D AND M BUBALO


Project  
ORCHARD STREET ACCESS ROAD  
WARRIEWOOD

Drawing No.  
4670-09

Issue  
C


Cod File No.  
4670-09

Xref(s)



PITWATER COUNCIL COMMUNITY DEVELOPMENT  
05/05/06

10 JAN 2007



PIT SCHEDULE

PIT	WEAST	MINORTH	TYPE (RTA)
1/1	341060.448	6270846.218	SAS (MIN. 600x600)
2/1	341055.222	6270833.870	SAS (MIN. 1200x600)
3/1	341051.083	6270828.252	900x600 DRAINAGE JUNCTION BOX
1/2	341049.888	6270847.300	HEADWALL

DRAINAGE PLAN  
1:100

DRG STATUS : **PRELIMINARY, NOT FOR CONSTRUCTION**

Issue	Details of Issue	Drawn	Checked	Approved	Date
A	ISSUED FOR REVIEW	ARG	MS		25.01.05
B	ISSUED FOR APPROVALS	ARG	MS		18.02.05
C	ISSUED FOR TENDER	DS	MS		18.07.05

INITIALS SHOWN IN THE ADJACENT ISSUE RECORDS INDICATE THE STAGES UNDERTAKEN IN THE DRAWING APPROVAL PROCESS. DRAWINGS ARE ONLY TO BE USED WHEN APPROVED BY PATTERSON BRITTON & PARTNERS AND THEN ONLY AS ISSUED. THE ORIGINAL DRAWING SHALL BE KEPT ON THE REVERSE SIDE OF THE ORIGINAL OF THE DRG REGISTER/TRANSFERRAL FORM No.5.2.2. HELD BY PATTERSON BRITTON & PARTNERS

Level 4  
104 Mount Street  
North Sydney 2060  
Telephone (02) 9557 1616  
Facsimile (02) 9557 1291  
Email [info@pbr.com.au](mailto:info@pbr.com.au)  
A.C.N. 603 220 228

**Patterson Britton & Partners Pty Ltd**  
consulting engineers

Client  
**V, D AND M BUBALO**


Project  
**ORCHARD STREET ACCESS ROAD  
WARRIEWOOD**


Title  
**STORMWATER DRAINAGE PLAN**

Drawing No.  
**4670-10**

Issue  
**C**

Cod File No.  
**4670-10**





PITTWATER COUNCIL CONSTRUCTION CERTIFICATE	
Number:	CC0545/06
This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.	
Endorsed by:	<i>Re</i>
Date:	10 JAN 2007

---

## APPENDIX C – SECTOR 10 (STOCKLAND) MONITORING RESULTS SUMMARY

---



Table 1 – Pre Construction Water Quality Monitoring Results

Table 1 – Pre Construction Water Quality Monitoring Results																																					
Parameter	Units	Short-Term Goal	Medium-Term Goal	Long-Term Goal*	15-Sep-99 3:00 PM		21-Sep-99			11-Oct-99 3:30 PM		18-Oct-99 1:30 PM		20-Oct-99 2:30 PM		14-Jun-01 11:30 AM		11 October-01		7 Nov-01 1:17 to 6:21 PM (rising limb)			8 Nov-01 8:26 to 9:07AM (falling limb)			20 Nov-01 3:00PM (rising limb)			21 Nov-01 9:30AM (falling limb)			7 Jan-02 5:00AM (rising limb)			7 Jan-02 5:00PM (falling limb)		
					W1US	W1DS	W2US	W2DS	W3US	W3DS	W4US	W4DS	W5US	W5DS	W6I	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS	W6IUS
Total rain over 5 day's preced. sampling	mm				2.6	2.6	14.8	14.8	2.0	2.0	0.0	0.0	38.0	38.0	7.2	3.2	3.2	17.2	17.2	17.2	21.6	21.6	21.6	41.8	41.8	41.8	67.4	67.4	21.2	21.2	21.2	21.2	21.2	21.2	21.2	21.2	
Ammonia - N	mg/L	<2.3	<0.3	<0.3	0.039	0.087	0.022	0.060	0.047	0.16	0.031	0.082	0.025	0.042	0.014	-	-	0.04	0.02	0.01	0.12	0.05	0.03	0.015	0.027	0.026	0.018	0.012	0.047	0.017	0.034	0.24	0.043	0.038	0.28		
Total Nitrogen	mg/L	SQ	<1.6	1.0	0.953	0.610	0.464	1.08	0.66	1.01	0.50	0.79	0.76	0.49	1.9	-	-	0.54	0.66	1.34	0.53	0.79	1.92	0.42	0.37	0.49	0.58	0.37	0.8	0.84	0.87	2.5	0.63	0.62	2.7		
NOx	mg/L	NS	NS	NS	0.493	0.020	0.024	0.46	0.22	0.01	0.09	0.01	0.30	0.02	0.79	-	-	0.02	0.03	0.07	<0.01	0.01	0.01	-	-	-	-	-	-	-	-	-	-	-	-	1	
Filterable Phosphorous	mg/L	NS	NS	NS	0.014	0.037	0.02	0.07	<0.02	0.08	<0.05	0.079	0.065	0.052	0.069	-	-	0.044	0.05	0.235	0.035	0.031	0.125	<0.02	0.021	0.13	<0.02	0.025	0.11	<0.05	0.062	0.73	<0.05	<0.05	<0.05	1	
Non-Filterable Phosphorous	mg/L	NS	NS	NS	0.006	0.013	0.04	0.06	<0.02	0.11	<0.05	0.12	0.075	0.043	0.071	-	-	0.024	0.024	0.184	0.014	0.009	0.1	0.013	0.033	0.112	0.033	0.026	0.08	0.026	0.058	0.06	-	0.06	-		
Total Phosphorous	mg/L	SQ	<0.1	0.04	0.020	0.050	0.06	0.13	<0.02	0.19	<0.05	0.20	0.14	0.095	0.14	-	-	0.024	0.110	0.479	0.066	0.069	0.441	0.033	0.054	0.018	0.035	0.051	0.19	0.076	0.12	0.79	0.066	0.11	1.1		
Solids	mg/L	<1000	<1000	<1000	193	221	184	199	196	210	200	220	180	180	240	-	-	235	248	273	258	270	281	180	200	100	200	200	200	170	140	140	190	140	180	210	
Total Dissolved Solids	mg/L	<20	<6	<6	<2	<2	<2	<2	<2	6	2	11	4	4	12	-	-	3	6	10	4	4	13	<2	<2	12	2	<2	41	4	6	83	2	2	120		
Suspended Solids	mg/L	<20	<6	<6	<2	<2	<2	<2	<2	6	2	11	4	4	12	-	-	3	6	10	4	4	13	<2	<2	12	2	<2	41	4	6	83	2	2	120		
Turbidity	NTU	SQ	<50	<20	1.4	3.6	2.0	5.0	2.0	6.6	5.6	12	4.7	4.0	8.1	-	-	5.3	68.4	171.5	2.1	4.8	12.5	6	4	15	10	4	23	4	5	28	5	5	22		
Faecal Coliforms	cfu/100 ml	<1000	<150	<150	4	220	300	77	40	29	530	14	690	360	90	-	-	3200	6400	9000	550	1000	990	230	930	4700	450	530	6100	5500	15000	4500	2200	7500	870	-	
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	0.46	0.59	0.44	0.62	0.44	1.0	0.41	0.78	0.46	0.47	1.1	-	-	0.52	0.63	1.27	0.53	0.78	1.91	-	-	-	-	-	-	-	-	-	-	-	-	-	
pH	pH unit	6.6-8	6.6-8	6.6-8	7.4	6.8	7.6	7.3	7.0	6.4	7.2	6.7	7.4	6.7	7.4	-	-	6.37	6.42	6.84	6.42	6.49	6.89	7.4	6.8	7.4	7.4	6.9	7.3	6.7	6.4	6.6	6.8	6.7	6.7		
Dissolved Oxygen (field)	mg/L	SQ	<90% sat.	<90% s	-	-	-	2.51	5.14	0.26	4.78	0.13	-	1.70	2.0	-	-	1.4	2.6	1.6	1.0	0.8	1.5	-	-	-	-	-	-	-	-	-	-	-	-	-	
Temperature (field)	°C	SQ	SQ	SQ	-	-	-	9.1	21.1	19.1	22.4	20.3	-	17.2	18.1	-	-	17.47	17.59	16.86	16.39	16.48	15.6	17	17.1	16.5	18	18	17.4	18	19	20.3	17	17.1	17.1		
Arsenic	ug/L	SQ	50%SQ	50	-	-	-	-	-	-	-	-	-	-	-	<1	<1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Chromium	ug/L	SQ	50%SQ	10	-	-	-	-	-	-	-	-	-	-	-	<1	<1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Copper	ug/L	SQ	50%SQ	2	-	-	-	-	-	-	-	-	-	-	-	1	<1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Lead	ug/L	SQ	50%SQ	1	-	-	-	-	-	-	-	-	-	-	-	<0.1	<0.1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Mercury	ug/L	SQ	50%SQ	0.1	-	-	-	-	-	-	-	-	-	-	-	<0.1	<0.1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Zinc	ug/L	SQ	50%SQ	50	-	-	-	-	-	-	-	-	-	-	-	3.8	7.3	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Organo chlorine Pesticides (OC)	ug/L	SQ	50%SQ	NS	-	-	-	-	-	-	-	-	-	-	-	<0.01	<0.01	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Phenols	ug/L	SQ	50%SQ	NS	-	-	-	-	-	-	-	-	-	-	-	<0.1	<0.1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Organo phosphate Pesticides (OP)	ug/L	SQ	50%SQ	NS	-	-	-	-	-	-	-	-	-	-	-	<0.1	<0.1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Hardness	mg/L	NS	NS	NS	-	-	-	-	-	-	-	-	-	-	-	80	110	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	
Chlorophyll A	mg/L	15	15	10	-	-	-	-	-	-	-	-	-	-	-	0.001	0.002	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Council's WMS Table C2 – Feb 2001.

2. Figures in journal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined achieve the short and medium-term water quality goal.

4. Figures in *italics* achieve the short-term water quality goal.

5. Figures in **Bold** do not achieve the short term goal or where SQ is the short term goal

6. Rainfall data obtained from Bureau of Meteorology. Sampling Station – Observatory Hill.

7. NS – Not Specified by Council. SQ – Status Quo, IT – To be forwarded when available (not available at time of report publication). NR = Not Required by Council's WMS for wet weather sampling

PATTON & PARTNERS

09/01/07

10 JAN 2007

Table 2- Construction Stage Water Quality Monitoring Results

Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal*	8 Apr-02 (Dry)				17 Apr -02 4:00PM (rising limb)	18 Apr -02 10:00AM (falling limb)	28 May-02 1:30PM (rising limb)	29 May-02 9:00AM (falling limb)	3/7/02 Physical Properties (DRY)				28/10/02 (Dry)	
						Mullet Creek	WSDS100	DS of Internal Creek	DS of Internal Creek					DS of Internal Creek	Mullet Creek	Mullet Creek	Mullet Creek	Mullet Creek	US
Total rain over 5 days preceding sampling	mm					2.2	2.2	2.2	6.6	13.8	33.6	33.6	47.0	47	0	0			
Ammonia - N	mg/L	NS	<2.3	<0.3	<0.3	0.015	0.12	0.26	0.14	0.21	0.024	0.006	0.045	0.021	-	-	0.19	0.10	0.18
Total Nitrogen	mg/L	<1.6	SQ	<1.6	1.0	0.5	0.7	12	4.0	7.5	0.67	0.40	1.1	0.48	-	-	0.59	0.54	5.0
Nitrate	mg/L	NS	NS	NS	NS	0.094	<0.005	6.3	1.8	5.8	0.025	0.018	0.41	0.064	-	-	0.01	<0.005	3.5
Nitrite	mg/L	NS	NS	NS	NS	<0.005	0.008	2.7	0.22	1.2	<0.005	<0.005	0.015	<0.005	-	-	<0.005	<0.005	0.071
Filterable Phosphorous	mg/L	NS	NS	NS	NS	<0.05	0.09	0.05	<0.05	<0.05	<0.05	<0.05	<0.05	<0.05	-	-	0.027	0.043	<0.02
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	<0.05	0.08	0.26	0.49	0.071	<0.05	<0.05	<0.05	<0.05	-	-	-	-	-
Total Phosphorous	mg/L	<0.1	SQ	<0.1	0.04	<0.05	0.17	0.31	0.54	0.076	<0.05	0.053	0.083	0.063	-	-	0.097	0.17	0.043
Phosphate - Ortho as P	mg/L	NS	NS	NS	NS	0.007	0.021	0.03	0.016	0.009	0.009	0.007	0.014	0.01	-	-	0.014	0.012	<0.005
Total Dissolved Solids	mg/L	NS	<1000	<1000	<1000	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Suspended Solids	mg/L	<100	SQ	<20	<6	<2	8	550	570	17	6	4	14	4	-	-	7	10	40
Turbidity	NTU	NS	SQ	<50	<20	-	-	-	-	-	-	-	-	-	-	-	-	-	-
Faecal Coliforms	cfu/100m <sup>1</sup>	<150	<1000	<150	<150	50	40	420	24000	850	<10	<10	2900	120	-	-	20	470	<10
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	0.4	0.7	3.0	2.0	0.5	0.65	0.38	0.68	0.42	-	-	0.58	0.54	1.4
pH	pH unit	NS	6.6-8	6.6-8	6.6-8	-	-	-	-	-	-	-	-	-	-	-	7.96	7.2	6.5
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat	<90% s	-	-	-	-	-	-	-	-	-	-	-	11.7	2.2	-
Temperature (field)	°C	NS	SQ	SQ	SQ	-	-	-	-	-	-	-	-	-	-	-	8.4	9.0	-
Conductivity @25deg C		NS				-	-	0.67	0.43	0.56	0.33	0.30	0.31	0.28	0.4	0.4	0.33	0.37	0.58
Salinity (ppt)		NS				-	-	-	-	-	-	-	-	-	0.18	0.18	-	-	-
ORP (mV)		NS				-	-	-	-	-	-	-	-	-	110	92	-	-	-
Arsenic	ug/L	NS	SQ	50%SQ	50	-	-	0.008	NR	NR	NR	NR	NR	NR	-	-	<1	<1	<1
Chromium	ug/L	NS	SQ	50%SQ	10	-	-	0.016	NR	NR	NR	NR	NR	NR	-	-	<1	<1	<1
Copper	ug/L	NS	SQ	50%SQ	2	-	-	0.018	NR	NR	NR	NR	NR	NR	-	-	<1	<1	<1
Lead	ug/L	NS	SQ	50%SQ	1	-	-	0.048	NR	NR	NR	NR	NR	NR	-	-	<1	<1	<1
Mercury	ug/L	NS	SQ	50%SQ	0.1	-	-	<0.0001	NR	NR	NR	NR	NR	NR	-	-	<0.1	<0.1	-
Zinc	ug/L	NS	SQ	50%SQ	50	-	-	0.064	NR	NR	NR	NR	NR	NR	-	-	<1	1	-
Organo chlorine Pesticides (OC)	ug/L	NS	SQ	50%SQ	NS	-	-	<0.01 (apart from Dieldrin at 0.051)	NR	NR	NR	NR	NR	NR	-	-	<0.01	<0.01	-
Phenols	ug/L	NS	SQ	50%SQ	NS	-	-	<2.0	NR	NR	NR	NR	NR	NR	-	-	<2	<2	-
Organo phosphate Pesticides (OP)	ug/L	NS	SQ	50%SQ	NS	-	-	<0.1	NR	NR	NR	NR	NR	NR	-	-	<0.1	<0.1	-
Hardness	mg/L	NS	NS	NS	NS	-	-	200	NR	NR	NR	NR	NR	NR	-	-	89	100	-
Chlorophyll A	mg/L	NS	15	15	10	-	-	<0.001	NR	NR	NR	NR	NR	NR	-	-	-	-	-
Oil and Grease	mg/L	NS	NS	NS	NS	-	-	<5	NR	NR	NR	NR	NR	NR	-	-	<5	<5	-

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 - Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined achieve the short and medium-term water quality goal.

4. Figures in *italics* achieve the short-term water quality goal.

5. Figures in **Bold** do not achieve the short term goal or where SQ is the short term goal

6. Rainfall data obtained from Bureau of Meteorology.

7. NS - Not Specified by Council, SQ - Status Quo, TF - To be forwarded when available (not available at time of report publication), NR = Not Required by Council's WMS for wet weather sampling

Patterson Britton & Partners

page 8

10 JAN 2007



Table 3 – First Quarter Water Quality Monitoring Results

Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal	16-1-03 (Dry)		
						Mullet Creek		New Internal Site
						WSP1US	WSP1DS	WSP1IS
Total rain over 5 days preceding sampling	mm					0	0	0
Ammonia - N	mg/L	NS	<2.3	<0.3	<0.3	<0.1	0.3	<0.1
Total Nitrogen	mg/L	<1.6	SQ	<1.6	1.0	0.4	27	5.2
Nitrate	mg/L	NS	NS	NS	NS	0.04	0.09	4.7
Nitrite	mg/L	NS	NS	NS	NS	<0.005	<0.005	0.09
Oxidised Nitrogen	mg/L	NS	NS	NS	NS	0.04	0.09	4.8
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	0.4	27	0.4
Filterable Phosphorous	mg/L	NS	NS	NS	NS	<0.05	<0.05	<0.05
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	<0.05	0.1	<0.05
Total Phosphorous	mg/L	<0.1	SQ	<0.1	0.04	<u>&lt;0.05</u>	<u>0.1</u>	<u>&lt;0.05</u>
Phosphate – Ortho as P	mg/L	NS	NS	NS	NS	<0.05	<0.05	<0.05
Suspended Solids / NFR		<100	SQ	<20	<6	<1	2	4
Faecal Coliforms	cfu/100ml	<150	<1000	<150	<150	20	150	120
pH	pH unit	NS	6.6-8	6.6-8	6.6-8	-	-	-
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat.	<90% s	-	-	-
Temperature (field)	°C	NS	SQ	SQ	SQ	-	-	-
Conductivity @25deg C		NS	NS	NS		-	-	-
Salinity (g/L)		NS	NS	NS		0.1	0.7	0.2
ORP (mV)		NS	NS	NS		-	-	-
Arsenic	ug/L	NS	SQ	50%SQ	50	<1	<1	2
Chromium	ug/L	NS	SQ	50%SQ	10	<1	<1	<1
Copper	ug/L	NS	SQ	50%SQ	2	<1	<1	3
Lead	ug/L	NS	SQ	50%SQ	1	<1	<1	<1
Mercury	ug/L	NS	SQ	50%SQ	0.1	<0.1	<0.1	<0.1
Zinc	ug/L	NS	SQ	50%SQ	50	<1	<1	<1
Organo chlorine Pesticides (OC)	ug/L	NS	SQ	50%SQ	NS	<1	<1	<1
Phenols	ug/L	NS	SQ	50%SQ	NS	<1	<1	<1
Organo phosphate Pesticides (OP)	ug/L	NS	SQ	50%SQ	NS	<1	<1	<1
Hardness (CaCO <sub>3</sub> )	mg/L	NS	NS	NS	NS	60	110	140
Chlorophyll A	ug/L	NS	15	15	10	13	31	2
Oil and Grease	mg/L	NS	NS	NS	NS	<3	<3	<3
Total PAH's	mg/L	NS	NS	NS	NS	<0.02	<0.02	<0.02
ALGAL ID/Count	Cells/mL	NS	NS	NS	NS	380	1500	230

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 – Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined achieve the short and medium-term water quality goal.

4. Figures in *italics* achieve the short-term water quality goal.

5. Figures in **Bold** do not achieve the short term goal or where SQ is the short term goal

6. Rainfall data obtained from Bureau of Meteorology.

7. NS – Not Specified by Council, SQ – Status Quo, TF – To be forwarded when available (not available at time of report publication)

Table 4 – Second Quarter Water Quality Monitoring Results

Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal	17 February 2003 (Wet Weather Rising Limb)										18 February 2003 (Wet Weather Falling Limb)										21 February 2003 (Wet Weather)		21 March, 2003 (Dry Weather)		
						Mullet	Internal	WQCP1	WQCP2	WQCP2	Mullet	Internal	WQCP1	WQCP2	WQCP2	WSP41IN	WSP41OUT	WSP6US	Mullet	Internal										
Total rain over 5 days preceding sampling	mm					WSP2US	WSP2DS	WSP2IS	WSP21IN	WSP21OUT	WSP22IN	WSP22OUT	WSP3US	WSP3DS	WSP3IS	WSP31IN	WSP31OUT	WSP32IN	WSP32OUT	WSP41IN	WSP41OUT	WSP6US	WSP6DS	WSP6IS						
Ammonia - N	mg/L	NS	<2.3	<0.3	<0.3	0.4	0.1	0.1	0.1	0.1	<0.1	<0.1	0.7	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	<0.1	1.6	0.07	2.2						
Total Nitrogen	mg/L	<1.6	SQ	<1.6	1.0	1.0	1.6	7.1	2.4	1.0	1.5	1.0	2.0	2.2	6.1	2.6	0.7	1.0	1.4	<0.01	0.38	1.0	0.07	0.15						
Nitrate	mg/L	NS	NS	NS	NS	<0.01	<0.01	6.0	<0.01	0.03	0.13	<0.01	<0.01	<0.01	5.9	<0.01	0.03	0.23	<0.01	0.38	1.0	0.07	0.15							
Nitrite	mg/L	NS	NS	NS	NS	<0.005	<0.005	0.099	<0.005	<0.005	<0.005	<0.005	<0.005	<0.005	0.11	<0.005	<0.005	0.005	<0.005	0.016	<0.005	<0.005	0.12							
Oxidised Nitrogen	mg/L	NS	NS	NS	NS	<0.005	<0.005	6.1	<0.005	0.03	0.13	<0.005	<0.005	<0.005	6.0	<0.005	0.03	0.23	<0.005	0.4	1.0	0.07	0.15							
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	1.0	1.6	1.0	2.4	1.0	1.4	1.0	2.0	2.2	0.1	2.6	0.7	0.8	1.4	2.2	0.6	<1.0	2.0							
Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.1	0.2	0.2	0.1	0.07	0.05	0.05	0.08	0.1	0.05	0.1	0.05	0.07	0.08	0.3	<0.05	0.05	<0.05							
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.1	0.3	<0.1	0.3	<0.1	0.15	0.15	0.12	0.5	0.05	0.3	<0.05	<0.05	0.12	1.5	<0.1	0.01	0.07							
Total Phosphorous	mg/L	<0.1	SQ	<0.1	0.04	0.2	0.5	0.2	0.4	0.1	0.2	0.2	0.2	0.6	0.1	0.4	0.06	0.09	0.2	1.8	0.04	0.06	0.07							
Phosphate - Ortho as P	mg/L	NS	NS	NS	NS	0.06	0.31	<0.05	0.11	<0.05	<0.05	<0.05	0.05	0.39	0.05	0.16	<0.05	<0.05	<0.05	-	-	<0.05	<0.05							
Suspended Solids / NFR		<100	SQ	<20	<6	16	15	130	77	<1	62	130	19	23	51	100	2	22	85	1000	3	11	3							
Faecal Coliforms	cfu/100ml	<150	<1000	<150	<150	2200	6600	8400	2300	6900	7700	30	230	170	250	390	1400	10	40	30000	340	590	260							
pH	pH unit	NS	6.6-8	6.6-8	6.6-8	-	-	-	-	-	-	-	-	-	-	-	-	-	-	6.5	7	4.4	4.43							
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat.	<90% s	-	-	-	-	-	-	-	-	-	-	-	-	-	-	1.0	1.0	3.0	0.8							
Temperature (field)	°C	NS	SQ	SQ	SQ	-	-	-	-	-	-	-	-	-	-	-	-	-	-	7.0	7.0	19.3	19.6							
Conductivity @25deg C	us/cm	NS	NS	NS	NS	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	266	365							
Salinity (g/L)		NS	NS	NS	NS	0.2	0.3	0.2	0.1	0.1	0.2	0.2	0.2	0.3	0.2	0.1	0.1	0.2	0.2	0.1	0.1	0.2	0.3							
ORP (mV)		NS	NS	NS	NS															-	-	409	409							
Arsenic	ug/L	NS	SQ	50%SQ	50	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	5							
Chromium	ug/L	NS	SQ	50%SQ	10	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1							
Copper	ug/L	NS	SQ	50%SQ	2	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	4							
Lead	ug/L	NS	SQ	50%SQ	1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<0.1	<0.1							
Mercury	ug/L	NS	SQ	50%SQ	0.1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	2	48							
Zinc	ug/L	NS	SQ	50%SQ	50	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1							
Organic chlorine Pesticides (OC)	ug/L	NS	SQ	50%SQ	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1							
Phenols	ug/L	NS	SQ	50%SQ	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1							
Organic phosphate Pesticides (OP)	ug/L	NS	SQ	50%SQ	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1							
Hardness (CaCO3)	mg/L	NS	NS	NS	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	90	170							
Chlorophyll A	ug/L	NS	15	15	10	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<3	45							
Oil and Grease	mg/L	NS	NS	NS	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1							
Total PAH's	mg/L	NS	NS	NS	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1						
ALGAL ID/Count	Cells/mL	NS	NS	NS	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	0	740							

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 – Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined achieve the short and medium-term water quality goal.

4. Figures in *italics* achieve the short-term water quality goal.

5. Figures in **Bold** do not achieve the short term goal or where SQ is the short term goal

6. Rainfall data obtained from Bureau of Meteorology.

7. NS – Not Specified by Council, SQ – Status Quo, TR – To be forwarded when available (not available at time of report publication), NR = Not Required by Council's WMS for wet weather sampling

0545106

190 JAN 2007

Post Sub-Division Certificate Water  
Quality Monitoring Report  
Sector 10, Warriewood Valley

3rd Quarter Post Subdivision  
Certificate Results (May03-Jul03)

Re

10 JAN 2007

Table 5 – Third Quarter Water Quality Monitoring Results

Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal	16-7-03 (Dry)		
						Mullet Creek		New Internal Site
						WSP7US	WSP7DS	WSP7IS
Total rain over 5 days preceding sampling	mm							
Ammonia - N	mg/L	NS	<2.3	<0.3	<0.3	<0.01	0.01	<0.01
Total Nitrogen	mg/L	<1.6	SQ	<1.6	1.0	<u>1.2</u>	<u>1.2</u>	4
Nitrate	mg/L	NS	NS	NS	NS	0.61	0.09	3.53
Nitrite	mg/L	NS	NS	NS	NS	0.01	<PQL	0.07
Oxidised Nitrogen	mg/L	NS	NS	NS	NS	-	-	-
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	0.6	1.2	0.3
Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.01	0.03	0.05
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	<0.01	<0.01	0.01
Total Phosphorous	mg/L	<0.1	SQ	<0.1	0.04	0.02	0.04	<u>0.06</u>
Phosphate – Ortho as P	mg/L	NS	NS	NS	NS	-	-	-
Suspended Solids	mg/L	<100	SQ	<20	<6	<u>2</u>	<u>5</u>	<u>2</u>
Turbidity (field)	NTU	NS	SQ	50	20	<u>111</u>	<u>74.9</u>	SH
Faecal Coliforms	cfu/100ml	<150	<1000	<150	<150	<u>320</u>	<u>110</u>	20
pH	pH unit	NS	6.6-8	6.6-8	6.6-8	6.66	6.64	SH
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat.	<90% s	20	15.9	SH
Temperature (field)	°C	NS	SQ	SQ	SQ	11.73	11.98	SH
Conductivity @25deg C	ms/cm	NS	NS	NS	NS	0.4	0.4	SH
Salinity (g/kg)		NS	NS	NS	NS	<1	<1	<1
ORP (mV)		NS	NS	NS	NS	55	57	SH
Arsenic	ug/L	NS	SQ	50%SQ	50	2	3	3
Chromium	ug/L	NS	SQ	50%SQ	10	<5	<5	<5
Copper	ug/L	NS	SQ	50%SQ	2	<5	<5	<5
Lead	ug/L	NS	SQ	50%SQ	1	<2	<2	5
Mercury	ug/L	NS	SQ	50%SQ	0.1	<1	<1	<1
Zinc	ug/L	NS	SQ	50%SQ	50	<10	<10	20
Organo chlorine Pesticides (OC)	ug/L	NS	SQ	50%SQ	NS	<1	<1	-
Phenols	ug/L	NS	SQ	50%SQ	NS	<PQL	<PQL	<PQL
Organo phosphate Pesticides (OP)	ug/L	NS	SQ	50%SQ	NS	<10	<10	-
Hardness (CaCO <sub>3</sub> )	mg/L	NS	NS	NS	NS	79	68	150
Chlorophyll A	ug/L	NS	15	15	10	<5	<5	<5
Oil and Grease	mg/L	NS	NS	NS	NS	<5	6	12
Total PAH's	ug/L	NS	NS	NS	NS	<1	<1	-
ALGAL ID/Count	Cells/mL	NS	NS	NS	NS	702	265	139

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 – Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined achieve the short and medium-term water quality goal.

4. Figures in *italics* achieve the short-term water quality goal.

5. Figures in **Bold** do not achieve the short term goal or where SQ is the short term goal

7. NS – Not Specified by Council, SQ – Status Quo, TF – To be forwarded when available (not available at time of report publication), <PQL = Less than practical quantitation limit, SH – Too Shallow to take readings with equipment

Post Sub-Division Certificate Water  
Quality Monitoring Report  
Sector 10, Warriewood Valley

4th Quarter Post Subdivision  
Certificate Results (Aug03-Oct03)

Table 6 – Fourth Quarter Water Quality Monitoring Results

Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal	15-10-03 (Dry)		
						Mullet Creek		New Internal Site
						WSP8US	WSP8DS	WSP8IS
Total rain over 5 days preceding sampling	mm					32.8	32.8	32.8
Ammonia - N	mg/L	NS	<2.3	<0.3	<0.3	0.06	0.07	0.09
Total Nitrogen	mg/L	<1.6	SQ	<1.6	1.0	<u>1.2</u>	0.6	3.8
Nitrate	mg/L	NS	NS	NS	NS	0.46	<0.01	2.69
Nitrite	mg/L	NS	NS	NS	NS	0.01	<0.01	0.03
Oxidised Nitrogen	mg/L	NS	NS	NS	NS	-	-	-
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	0.8	0.6	1.2
Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.14	0.05	0.39
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.01	<0.01	<0.01
Total Phosphorous	mg/L	<0.1	SQ	<0.1	0.04	<u>0.15</u>	<u>0.06</u>	<u>0.40</u>
Phosphate – Ortho as P	mg/L	NS	NS	NS	NS	-	-	-
Suspended Solids	mg/L	<100	SQ	<20	<6	<u>13</u>	4	190
Turbidity (field)	NTU	NS	SQ	50	20	75	6	-
Faecal Coliforms	cfu/100ml	<150	<1000	<150	<150	90	160	370
pH	pH unit	NS	6.6-8	6.6-8	6.6-8	7.85	7.26	-
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat.	<90% s	6.62	1.83	-
Temperature (field)	°C	NS	SQ	SQ	SQ	15.2	14.8	-
Conductivity @25deg C	ms/cm	NS	NS	NS	NS	0.233	0.243	-
Salinity (g/kg)		NS	NS	NS	NS	0	0	-
ORP (mV)		NS	NS	NS	NS	-	-	-
Arsenic	ug/L	NS	SQ	50%SQ	50	<2	<2	4
Chromium	ug/L	NS	SQ	50%SQ	10	<5	<5	<5
Copper	ug/L	NS	SQ	50%SQ	2	<u>&lt;5</u>	<u>&lt;5</u>	2
Lead	ug/L	NS	SQ	50%SQ	1	<u>3</u>	<u>&lt;2</u>	<u>18</u>
Mercury	ug/L	NS	SQ	50%SQ	0.1	<1	<1	<1
Zinc	ug/L	NS	SQ	50%SQ	50	<10	<10	160
Organo chlorine Pesticides (OC)	ug/L	NS	SQ	50%SQ	NS	<1	<1	<1
Phenols	ug/L	NS	SQ	50%SQ	NS	<5	<5	<5
Organo phosphate Pesticides (OP)	ug/L	NS	SQ	50%SQ	NS	<10	<10	<10
Hardness (CaCO3)	mg/L	NS	NS	NS	NS	75	70	160
Chlorophyll A	ug/L	NS	15	15	10	10	<5	<5
Oil and Grease	mg/L	NS	NS	NS	NS	<3	<3	<3
Total PAH's	ug/L	NS	NS	NS	NS	<1	<1	<1
ALGAL ID/Count	Cells/mL	NS	NS	NS	NS	348	334	134

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 – Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined achieve the short and medium-term water quality goal.

4. Figures in *italics* achieve the short-term water quality goal.

5. Figures in **Bold** do not achieve the short term goal or where SQ is the short term goal

7. NS – Not Specified by Council, SQ – Status Quo, TF – To be forwarded when available (not available at time of report publication), <PQL = Less than practical quantitation limit, SH – Too Shallow to take readings with equipment

### Table 7 – Fifth Quarter Water Quality Monitoring Results

[illegible]

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 - Feb 2001.

**2. Figures in normal case satisfy any short, medium and long-term water quality goals**

3. Figures underlined do not achieve the long term water quality goal.

4. Figures in italics do not achieve the medium-term water quality goal.

**5. Figures in Bold do not achieve the short term goal**

6. Rainfall for Nov and Dec 2003 is from the Ingleside Rainfall Station, whilst Jan 04 is from Newport Bowling Club

7. NS - Not Specified by Council, SQ - Status Quo, IF - To be forwarded at time of report publication), <PQL = less than practical quantitation limit, SH - 100 Shallow to take readings with equipment, NR=Not required by specification in wet weather

PH: 0545 500 0000

10 JAN 2007

Table 8 – Sixth Quarter Water Quality Monitoring Results

Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal	15/4/04 Dry			15/4/04 Dry (Physical Only)			
						WSP12US	WSP12DS	WSP12IS	WQCP1 IN	WQCP1 OUT	WQCP2 IN	WQCP2 OUT
Total rain over 5 days preceding sampling	mm					0	0	0	0	0	0	0
Ammonia - N	mg/L	NS	<2.3	<0.3	<0.3	0.03	0.07	0.05	-	-	-	-
Total Nitrogen	mg/L	<1.6	SQ	<1.6	1.0	0.7	1.2	5.4	-	-	-	-
Nitrate	mg/L	NS	NS	NS	NS	0.06	<0.01	5.13	-	-	-	-
Nitrite	mg/L	NS	NS	NS	NS	<0.01	<0.01	0.07	-	-	-	-
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	0.6	1.2	0.1	-	-	-	-
Filterable Phosphorous	mg/L	NS	NS	NS	NS				-	-	-	-
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.01	0.02	<0.01	-	-	-	-
Total Phosphorous	mg/L	<0.1	SQ	<0.1	0.04	0.08	0.15	0.03	-	-	-	-
Suspended Solids	mg/L	<100	SQ	<20	<6	3	10	<1	-	-	-	-
Turbidity (field)	NTU	NS	SQ	50	20	4	8	SH	53	5	25	77
Faecal Coliforms	cfu/100ml	<150	<1000	<150	<150	40	30	60	-	-	-	-
pH	pH unit	NS	6.6-8	6.6-8	6.6-8	6.3	6.0	SH	6.96	6.51	6.99	6.92
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat	<90% sat	3.37	0.85	SH	4.11	5.12	5.88	8.31
Temperature (field)	°C	NS	SQ	SQ	SQ	17.8	18.1	SH	21.9	18.5	20.4	22.1
Conductivity	ms/cm	NS	NS	NS	NS	0.273	0.264	SH	0.078	0.117	0.142	0.115
Salinity (%)		NS	NS	NS	NS	0.01	0.01	SH	0	0	0	0
Arsenic	ug/L	NS	SQ	50%SQ	50	<2	4	2	-	-	-	-
Chromium	ug/L	NS	SQ	50%SQ	10	<5	<5	<5	-	-	-	-
Copper	ug/L	NS	SQ	50%SQ	2	<2	<2	<2	-	-	-	-
Lead	ug/L	NS	SQ	50%SQ	1	<1	<1	4	-	-	-	-
Mercury	ug/L	NS	SQ	50%SQ	0.1	<0.05	<0.05	<0.05	-	-	-	-
Zinc	ug/L	NS	SQ	50%SQ	50	<10	<10	<10	-	-	-	-
Organo chlorine Pesticides (OC)	ug/L	NS	SQ	50%SQ	NS	<1	<1	<1	-	-	-	-
Phenols	ug/L	NS	SQ	50%SQ	NS	<10	<10	<10	-	-	-	-
Organo phosphate Pesticides (OP)	ug/L	NS	SQ	50%SQ	NS	<10	<10	<10	-	-	-	-
Hardness (CaCO3)	mg/L	NS	NS	NS	NS	91	93	170	-	-	-	-
Chlorophyll A	ug/L	NS	15	15	10	<5	14	<5	-	-	-	-
Oil and Grease	mg/L	NS	NS	NS	NS	7	8	6	-	-	-	-
Total PAH's	ug/L	NS	NS	NS	NS	<1	<1	<1	-	-	-	-
ALGAL ID/Count	Cells/mL	NS	NS	NS	NS	-	-	-	-	-	-	-

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 – Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined do not achieve the long term water quality goal.

4. Figures in italics do not achieve the medium-term water quality goal.

5. Figures in bold do not achieve the short term goal

6. NS – Not Specified by Council, SQ – Status Quo, TF – To be forwarded when available (not available at time of report publication), SH – Too shallow to take readings with equipment

Post Sub-Division Certificate Water  
Quality Monitoring Report  
Sector 10, Warriewood Valley

8th Quarter Post Subdivision  
Certificate Results (Aug04-Nov04)

Re

10 JAN 2007

Table 9 – Seventh Quarter Water Quality Monitoring Results

Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal	8/7/04 Dry			8/7/04 Dry (Physical Only)			
						WSP13US	WSP13DS	WSP13IS	WQCP1 IN	WQCP1 OUT	WQCP2 IN	WQCP2 OUT
Total rain over 5 days preceding sampling	mm					0	0	0	0	0	0	0
Ammonia - N	mg/L	NS	<2.3	<0.3	<0.3	0.3	0.07	<0.01	-	-	-	-
Total Nitrogen	mg/L	<1.6	SQ	<1.6	1.0	0.7	1.0	5.2	-	-	-	-
Nitrate	mg/L	NS	NS	NS	NS	<0.01	<0.01	4.99	-	-	-	-
Nitrite	mg/L	NS	NS	NS	NS	<0.01	<0.01	0.04	-	-	-	-
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	0.7	1.0	<0.1	-	-	-	-
Filterable Phosphorous	mg/L	NS	NS	NS	NS				-	-	-	-
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	<0.01	0.01	<0.01	-	-	-	-
Total Phosphorous	mg/L	<0.1	SQ	<0.1	0.04	<u>0.06</u>	<u>0.11</u>	0.03	-	-	-	-
Suspended Solids	mg/L	<100	SQ	<20	<6	<u>7</u>	<u>12</u>	2	-	-	-	-
Turbidity (field)	NTU	NS	SQ	50	20	<u>74</u>	<u>70</u>	SH	21	25	10	30
Faecal Coliforms	cfu/100ml	<150	<1000	<150	<150	40	50	<u>160</u>	-	-	-	-
pH	pH unit	NS	6.6-8	6.6-8	6.6-8	7.2	6.8	SH	7.02	6.80	6.48	6.47
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat	<90% sat	1.17	1.32	SH	5.02	5.15	6.24	7.21
Temperature (field)	°C	NS	SQ	SQ	SQ	10.2	10.3	SH	20.1	21.5	20.4	22.1
Conductivity	ms/cm	NS	NS	NS	NS	0.234	0.277	SH	0.121	0.102	0.122	0.135
Salinity (%)		NS	NS	NS	NS	0.00	0.01	SH	0	0	0	0
Arsenic	ug/L	NS	SQ	50%SQ	50	<2	<2	<2	-	-	-	-
Chromium	ug/L	NS	SQ	50%SQ	10	<5	<5	<5	-	-	-	-
Copper	ug/L	NS	SQ	50%SQ	2	<2	<2	<2	-	-	-	-
Lead	ug/L	NS	SQ	50%SQ	1	<1	<1	6	-	-	-	-
Mercury	ug/L	NS	SQ	50%SQ	0.1	<0.05	<0.05	<0.05	-	-	-	-
Zinc	ug/L	NS	SQ	50%SQ	50	<10	<10	<10	-	-	-	-
Organo chlorine Pesticides (OC)	ug/L	NS	SQ	50%SQ	NS	<1	<1	<1	-	-	-	-
Phenols	ug/L	NS	SQ	50%SQ	NS	<10	<10	<10	-	-	-	-
Organo phosphate Pesticides (OP)	ug/L	NS	SQ	50%SQ	NS	<10	<10	<10	-	-	-	-
Hardness (CaCO3)	mg/L	NS	NS	NS	NS	57	85	140	-	-	-	-
Chlorophyll A	ug/L	NS	15	15	10	<5	<5	<5	-	-	-	-
Oil and Grease	mg/L	NS	NS	NS	NS	<5	<5	<5	-	-	-	-
Total PAH's	ug/L	NS	NS	NS	NS	<1	<1	<1	-	-	-	-
ALGAL ID/Count	Cells/mL	NS	NS	NS	NS	-	-	-	-	-	-	-

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 – Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined do not achieve the long term water quality goal.

4. Figures in italics do not achieve the medium-term water quality goal.

5. Figures in bold do not achieve the short term goal

6. NS – Not Specified by Council, SQ – Status Quo, TF – To be forwarded when available (not available at time of report publication), SH – Too shallow to take readings with equipment

Table 10 – Eighth Quarter Water Quality Monitoring Results

Table 10 – Eighth Quarter Water Quality Monitoring Results													16/08/04 – Wet Weather Rising Limb													17/08/04 – Wet Weather Falling Limb													18/10/04 Dry			
Parameter	Units	During Const.	Short-Term Goal	Medium-Term Goal	Long-Term Goal	WSP14US	WSP14D S	WSP14IS	WSP14WQ CPIN	WSP14W QCP1OUT	WSP14W QCP2IN	WSP14W QCP2OUT	WSP15US	WSP15DS	WSP15IS	WSP15WQ CPIN	WSP15WQ QCP1OUT	WSP15WQ QCP2IN	WSP15W QCP2OUT T	WSP16US	WSP16DS	WSP16IS																				
Total rain over 5 days preceding sampling	mm					14.4	14.4	14.4	14.4	14.4	14.4	14.4	48.6	48.6	48.6	48.6	48.6	48.6	48.6	48.6	33.2	33.2	33.2																			
Ammonia - N	mg/L	NS	2.3	0.3	0.3	<0.01	0.08	0.04	1.06	0.22	<0.01	<0.01	0.03	0.01	0.89	0.13	1.02	0.01	<0.01	0.1	0.06	0.12																				
Total Nitrogen	mg/L	1.6	SQ	1.6	1.0	0.7	1	2	2.6	1.4	1	0.5	1.8	1.2	2.6	1.2	2	1.6	1	2.2	1.4	2.0																				
Nitrate	mg/L	NS	NS	NS	NS	0.19	0.26	2.17	0.15	0.36	0.3	<0.01	0.73	0.33	0.67	0.16	0.18	0.51	0.2	0.85	0.36	1.06																				
Nitrite	mg/L	NS	NS	NS	NS	0.01	0.01	0.04	0.03	0.02	0.01	<0.01	0.02	0.01	0.03	0.02	0.02	0.01	<0.01	0.03	0.02	0.03																				
Total Kjeldahl Nitrogen	mg/L	NS	NS	NS	NS	0.5	0.7	0.9	2.6	1	0.8	0.5	1.2	0.8	1.8	1.2	1.8	1	0.8	1.2	1.0	1.0																				
Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.04	0.09	0.05	0.27	0.15	0.21	<0.01	0.15	0.05	0.29	0.3	0.29	0.16	0.22	0.13	0.02	0.07																				
Non-Filterable Phosphorous	mg/L	NS	NS	NS	NS	0.03	0.02	0.37	0.2	0.04	0.15	<0.01	0.67	0.21	0.18	0.42	0.15	0.23	0.16	0.11	0.1	0.15																				
Total Phosphorous	mg/L	0.1	SQ	0.1	0.04	0.02	0.11	0.42	0.47	0.19	0.36	<0.01	0.82	0.26	0.47	0.72	0.44	0.39	0.38	0.24	0.12	0.22																				
Suspended Solids	mg/L	100	SQ	20	6	2	10	62	58	20	80	11	20	12	110	72	33	79	84	2	5	30																				
Turbidity (field)	NTU	NS	SQ	50	20	22	36	SH	239	47	405	32	113	42	SH	340	235	198	372	53	13	SH																				
Faecal Coliforms	cfu/100ml	150	1000	150	150	2700	2100	2200	1200	310	1900	<10	6900	2600	1500	1500	1000	750	764	797	664	383	SH																			
pH (field)	pH unit	NS	6.6-8	6.6-8	6.6-8	7.76	7.45	SH	7.85	8.56	7.92	8.07	8.21	6.08	SH	7.71	5.56	7.35	7.99	11.9	15.5	15.5	SH																			
Dissolved Oxygen (field)	mg/L	NS	SQ	<90% sat	<90% sat	7.88	5.07	SH	6.70	4.57	7.86	9.00	11.4	11.4	SH	11.9	11.8	12.5	11.9	0.221	0.209	SH																				
Temperature (field)	°C	NS	SQ	SQ	SQ	12.2	12.3	SH	15.4	12.3	13.9	14.8	11.4	0.159	SH	0.095	0.096	0.150	0.071	0	0	SH																				
Conductivity (field)	ms/cm	NS	NS	NS	NS	0.185	0.158	SH	0.096	0.166	0.186	0.187	0	0	SH	0	0	0	0	<2	<2	<2																				
Salinity (field)	%	NS	NS	NS	NS	0	0	SH	0	0	0	0	0	0	SH	0	0	0	0	<5	<5	<5																				
Arsenic	ug/L	NS	SQ	50%SQ	50	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<2	<2	<2																				
Chromium	ug/L	NS	SQ	50%SQ	10	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1	<1																				
Copper	ug/L	NS	SQ	50%SQ	2	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<0.05	<0.05	<0.05																				
Lead	ug/L	NS	SQ	50%SQ	1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	10	10	40																				
Mercury	ug/L	NS	SQ	50%SQ	0.1	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1	<1																				
Zinc	ug/L	NS	SQ	50%SQ	50	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<50	<50	<50																				
Organo chlorine Pesticides (OC)	ug/L	NS	SQ	50%SQ	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<10	<10	<10																				
Phenols	ug/L	NS	SQ	50%SQ	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	68	62	80																				
Organo phosphate Pesticides (OP)	ug/L	NS	SQ	50%SQ	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<0.005	<0.005	0.005																				
Hardness (CaCO3)	mg/L	NS	NS	NS	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<5	<5	<5																				
Chlorophyll A	mg/L	NS	15	15	10	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	<1	<1	<1																				
Oil and Grease	mg/L	NS	NS	NS	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR																				
Total PAH's	ug/L	NS	NS	NS	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR																				
ALGAL ID		NS	NS	NS	NS	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	NR	0	Very low	Very Low																				

1. Long-Term water quality goals are derived from ANZECC, 1992 guidelines and Councils WMS Table C2 – Feb 2001.

2. Figures in normal case satisfy any short, medium and long-term water quality goals.

3. Figures underlined do not achieve the long term water quality goal.

4. Figures in italics do not achieve the medium-term water quality goal.

5. Figures in Bold do not achieve the short term goal.

6. Rainfall for Nov and Dec 2003 is from the Inglefild Rainfall Station, whilst Jan 04 is from Newport Bowling Club.

7. NS – Not Specified by Council, SQ – Status Quo, TF – To be forwarded when available (not available at time of report publication), <QL = Less than practical quantitation limit, SH – Too Shallow to take readings with equipment, NR=Not required by specification in wet weather

10 JAN 2007



PITTWATER COUNCIL CONSTRUCTION CERTIFICATE	
Number:	CC 0545/06
This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.	
Endorsed by:	Rh.
Date:	10 JAN 2007

---

## APPENDIX D – ATLANTIS CELLS

---



# Modular Underground Tank System

Infiltration

•


Detention

•

Rainwater

Harvesting


The Atlantis underground tank system is a modular sub surface system that can be constructed to hold any volume required. The sub surface location of the tank frees up space for landscaping or driveway use while also ensuring optimal conditions for retaining water is always maintained. All macro and micro pollutants are completely kept out of the system through an Atlantis Filtration Unit.




Matrix® tank module



Excavation



Installation of the Matrix® tank modules



This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.

Endorsed by:

**atlantis**  
Water Management

WATER COUNCIL CONSTRUCTION CERTIFICATE  
CC 0545/06  
This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.  
Endorsed by: *[Signature]*  
Date: 10 JAN 2007



## Atlantis® Filtration Unit

Pre filters stormwater **"at source"** allowing clean water to enter the Atlantis® Rainwater Tank system...

### The Atlantis® Filtration Unit

The Atlantis Filtration Unit is a pre-filter system specifically designed to capture gross pollutants, dissolved solids and silt from roofs and stormwater surface pits allowing clean water to enter the Atlantis Rainwater Tank system.


### How it Works!

The unit features a removable trash screen for easy cleaning, which ensures litter free water enters the tank system.

The unit also contains a filtration system that bio-remediates soluble stormwater contaminants. This filtration chamber provides primary macro and secondary biological water remediation. The unit delivers decontaminated water to the Atlantis Rainwater Tank System where tertiary remediation occurs continuously.

### Easy to Use!

The Atlantis Filtration Unit is user friendly, easy to install and provides years of trouble free service requiring low maintenance.




### Benefits:

- Filters stormwater **"at source"**
- Easy installation
- User friendly maintenance



Installation of Atlantis Filtration Unit in Warriewood Sub-Division, Sydney NSW.




An Atlantis® Filtration Unit installed into the garden area.


[www.atlantiscorp.com.au](http://www.atlantiscorp.com.au)









Atlantis Small Filtration Unit



Atlantis Large Filtration Unit



The Large Atlantis Filtration Unit features a lightweight Aluminium lid allowing easy access and long life durability.



The trash screen collects all gross pollutants and micro pollutants as small as 180 microns.



The removable trash screen features a long handle for easy maintenance.

## Atlantis® Filtration Units

Item No.	Description	Picture
60002	Small Filtration Unit (Single down Pipe) Suitable for single pipe applications of 12 l/sec. Size (W)480mm x (H)450mm	
60003	Large Filtration Unit (Multiple down Pipes) Suitable for flow situations of 20 l/sec. (150mm outlet pipe). Size (W)680mm x (H)880mm	

**Note:** The Atlantis® Matrix® Tank Modules are manufactured from high quality recycled materials, carefully selected and under strict quality control procedures. The strength could vary slightly due to raw material, country of manufacture, manufacturing process and external conditions.

**Safety Factors:** Engineers, designers and geotechnical engineers should design and calculate safety factors to serviceable limited state to suit specific project. In case of doubt, consult your nearest distributor or Atlantis.

**Disclaimer:** All information provided in this publication is correct to the best of the Company's Knowledge and is given out in Good Faith. This information is intended only as a general guide, no responsibility can be accepted for any errors, omissions or incorrect assumption. As each project is unique, and as Rebirth Pty Ltd, Atlantis Water Management, Atlantis Corporation Pty Ltd and its Distributors and Agents World Wide have no direct control over the methods employed by the User in Specifying, Installing or Supervising of its products hence no Responsibility is accepted by Rebirth Pty Ltd, Atlantis Water Management, Atlantis Corporation Pty Ltd and its Distributors and Agents World Wide. Users should satisfy themselves as to the suitability of the product for their purpose.

All product designs, and specification are subject to change without further notice. All Atlantis products are tested in approved NATA laboratories, and safe allowed tolerance should be practised in actual field, due to any unforeseen situations, onsite and on products. All material contained within this brochure is Copyright, and belongs to Rebirth Pty Ltd Australia. No part of this brochure may be reproduced or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without prior written permission of Rebirth Pty Ltd. Australia, Atlantis Water Management, Atlantis Corporation Pty Ltd. Copyright © 2002 by Rebirth Pty Ltd. Australia, Atlantis Water Management, Atlantis Corporation Pty Ltd. Australia.

**Atlantis Water Management**  
Rebirth Pty Ltd trading as Atlantis Water Management


Suite 401, 781 Pacific Highway Chatswood NSW, 2067 Australia

Phone • +61 2 9419 6000 Fax • 61 2 9419 6710

Email • [info@atlantiscorp.com.au](mailto:info@atlantiscorp.com.au) Web Site • [www.atlantiscorp.com.au](http://www.atlantiscorp.com.au)










Installing the tank modules.



Wrapping the tank in Geotextile.



The completed tank covered with free draining material.



Part No	Size in mm	Units per /m <sup>3</sup>	Strength	Flow Rate
70003	(L)685 x (H)450 x (W)408	8 boxes /m <sup>3</sup>	26.8 t / m <sup>2</sup>	2280 l /min
70004	(L)685 x (H)880 x (W)408	4.06 boxes /m <sup>3</sup>	26.8 t / m <sup>2</sup>	4560 l /min
70005	(L)685 x (H)1310 x (W)408	2.73 boxes /m <sup>3</sup>	26.8 t / m <sup>2</sup>	6840 l /min

(L) Length, (H) Height, (W) Width

**Note:** Atlantis® products are manufactured from high quality recycled materials, carefully selected and under strict quality control procedures. The strength could vary slightly due to raw material, country of manufacture, manufacturing process and external conditions.

**Safety Factors:** Engineers, designers and geotechnical engineers should design and calculate safety factors to a serviceable limited state to suit specific project. In case of doubt, consult your nearest distributor or Atlantis representative.

**Disclaimer:** All information provided in this publication is correct to the best knowledge of the company and is given out in good faith. This information is intended only as a general guide, no responsibility can be accepted for any errors, omissions or incorrect assumption. As each project is unique, and as Rebirth Pty Ltd, Atlantis Water Management, Atlantis Corporation Pty Ltd and its distributors and agents world wide have no direct control over the methods employed by the user in specifying, installing or supervising of its products hence no responsibility is accepted by Rebirth Pty Ltd, Atlantis

Water Management, Atlantis Corporation Pty Ltd and its distributors and agents world wide. Users should satisfy themselves as to the suitability of the product for their purpose.

All product designs, and specification are subject to change without further notice. All Atlantis® products are tested in approved NATA laboratories, and sale allowed tolerances should be practised in the actual field, to compensate for any unforeseen situations, onsite and on products. All material contained within this brochure is subject to copyright, and belongs to Rebirth Pty Ltd Australia. No part of this brochure may be reproduced or transmitted in any form or by any means, electronic, mechanical, photocopying, recording or otherwise, without prior written permission of Rebirth Pty Ltd, Australia, Atlantis Water Management, Atlantis Corporation Pty Ltd. Copyright © 2004 by Rebirth Pty Ltd, Australia, Atlantis Water Management, Atlantis Corporation Pty Ltd, Australia.

## Atlantis Water Management

3/19-21 Gibbes Street Chatswood NSW 2067 Australia

phone - (02) 9417 8344 email - info@atlantiscorp.com.au

fax - (02) 9417 8311 web - www.atlantiscorp.com.au

## Agent