

STORMWATER DRAINAGE NOTES:

1. ALL PIPES TO BE 100mm Ø UNLESS NOTED OTHERWISE.

5. ALL DOWN PIPES TO BE 100mm Ø UNLESS NOTED OTHERWISE.

REINFORCED WITH N12 AT 250 EACH WAY UNLESS NOTED OTHERWISE.

12. ALL LEVELS SHOWN ARE TO AHD UNLESS NOTED OTHERWISE.

SUBGRADE TO DIRECT GROUNDWATER AWAY FROM STRUCTURES.

CLASHES WITH THE PROPOSED DRAINAGE EASEMENT PIPE LINE.

CAN BE DRAINED TO AN ONSITE DISPERSAL SYSTEM.

THE ISSUE OF ANY CONSTRUCTION CERTIFICATE

THAT THE NOMINAL DIAMETER OF THE DOWNPIPE.

25mm ABOVE THE TOP OF THE FASCIA.

IL - INVERT LEVEL OF PIPE

CL - CENTRELINE OF ORIFICE

INV. - INVERT LEVEL OF PIT

TWL - TOP WATER LEVEL

35. THE FOLLOWING ABBREVIATIONS DENOTE:

FSL - FINISHED SURFACE LEVEL OR RL - REDUCED LEVEL

THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC

UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD

RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL

LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE

STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY

WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE

17. IF NOT INDICATED ON PLANS, PROVIDE LEAF CATCHERS TO ALL DOWNPIPES.

EXCAVATION OF TRENCHES, ARE TO BE PROVIDED IN ACCORDANCE WITH AS 3500.3.

POINT U.N.O AND BE CONSTRUCTED IN ACCORDANCE WITH AS3500.3 REQUIREMENTS.

14. ALL EXISTING EARTHENWARE PIPES TO BE UPGRADED TO uPVC.

GRANULAR MATERIAL AS SPECIFIED.

7. PROVIDE CLEANING EYES AT ALL DOWNPIPES.

WITH WORK.

DRAINAGE

IF REQUIRED.

DRAINAGE INTERCEPTION.

SYSTEM DRAINING THE SITE.

REQUIREMENTS.

2. ALL PIPES TO BE uPVC TO AS 1254-2002 UNLESS NOTED OTHERWISE. 3. ALL PIPES TO BE LAYED AT 1 % MINIMUM GRADE UNLESS NOTED OTHERWISE.

4. ALL PIPES SHALL BE LAID ON A 75mm SAND BED, COMPACTED TO 100% S.M.D.D. BELOW PAVEMENTS. (NO COMPACTION

REQUIRED BELOW LANDSCAPING). COVER TO SURFACE FROM TOP OF PIPE TO BE 300mm MINIMUM. BACKFILL TO BE

ADEQUATELY CONSOLIDATED AROUND PIPES BY METHOD OF RAMMING AND WATERING IN. TRENCHES TO BE FILLED WITH

8. ALL PITS TO BE CAST INSITU OR, IF PRECAST, APPROVED BY ENGINEER. CAST INSITU PITS TO HAVE 150mm THICK

11. PRIOR TO COMMENCING ANY SITE WORKS THE CONTRACTOR SHALL IMPLEMENT EROSION CONTROL MEASURES TO

APPROVED SEDIMENT AND EROSION CONTROL PLAN, EPA GUIDELINES AND COUNCIL SPECIFICATIONS. ALL MEASURES TO

15. ALL WORKS TO BE IN ACCORDANCE WITH AS 3500.3 NATIONAL PLUMBING DRAINAGE CODE PART 3 - STORMWATER

THAT IMPEDE THE NATURAL FLOW OF GROUNDWATER. THIS MAY ALSO INVOLVE TRENCHING INTO THE CLAY OR ROCK

18. EXISTING STORMWATER SYSTEM TO BE CHECKED AND UPGRADED AS REQUIRED IN ACCORDANCE WITH AS 3500.3

20. CONTRACTOR TO LOCATE ALL EXISTING SERVICES PRIOR TO EXCAVATION AND NOTIFY ENGINEER OF ANY POTENTIAL

ROOT SYSTEM. HAND DIGGING OF TRENCHES MAY BE NECESSARY. REFER ARBORISTS REPORT WHERE REQUIRED.

DISCHARGE ONLY. DO NOT CONNECT SUB-SOIL PIPES TO AREAS WITH HIGHER SURFACE LEVELS U.N.O.

27. GUTTER GUARDS MUST BE INSTALLED ON ALL GUTTERS TO MINIMISE DEBRIS ENTERING THE SYSTEM.

16. UNLESS NOTED OTHERWISE, SUB-SOIL DRAINS ARE TO BE INSTALLED IN ACCORDANCE WITH AS3500.3 ALONGSIDE WALLS

19. CARE SHOULD BE TAKEN WHEN UNDERTAKING WORKS IN THE VICINITY OF SELECTED TREES NOT TO DISTURB THE TREE

21. ALL SUB-SOIL DRAINAGE TO BE INSTALLED IN ACCORDANCE WITH THE STRUCTURAL AND GEOTECHNICAL REQUIREMENTS, AUSTRALIAN STANDARDS AS 3500.3 AND IS TO BE DIRECTED TO THE SITE DRAINAGE SYSTEM BY MEANS OF GRAVITY

22. ALL PIPES SHOWN ARE INDICATIVE ONLY AND MINIMUM CLEARANCES FROM THE EXTERNAL WALLS OF BUILDINGS. FOR THE

23. ANY COMPONENTS OF THE EXISTING SYSTEM PROPOSED TO BE RETAINED ARE TO BE CERTIFIED DURING CONSTRUCTION

TO BE IN GOOD CONDITION AND OF ADEQUATE CAPACITY TO CONVEY ADDITIONAL RUNOFF AND BE REPLACED OR UPGRADED

24. ANY CHARGED PIPES MUST BE A MINIMUM OF 100mm (UNLESS NOTED OTHERWSIE) WITH ALL JOINTS MUST BE SOLVENT

WELDED. A CLEANING EYE, OR FLUSH OUT POINT, MUST BE PROVIDED AT THE LOW POINT IN THE SYSTEM WITHIN A PIT THAT

25. PROVISION IS TO BE MADE FOR THE COLLECTION AND DISPOSAL IN AN APPROVED MANNER OF ANY OVERLAND FLOW OR

SUB-SURFACE FLOW ENTERING THE SUBJECT PROPERTY, OR CONCENTRATED AS A RESULT OF THE PROPOSED WORKS. ANY

28. ALL SUB-SOIL DRAINAGES, STRIP DRAINS AND DRAINAGE PITS SHALL DISCHARGE TO THE ESTABLISHED SITE DISCHARGE

29. OVERFLOW PATHS SHALL BE PROVIDED TO ALLOW FOR FLOWS IN EXCESS OF THE CAPACITY OF THE PIPE/DRAINAGE

APPROVAL UNDER SECTION 138 OF THE ROAD ACT 1993 MUST BE OBTAINED FROM COUNCIL FOR THOSE WORKS PRIOR TO

31. CONCEALED DOWNPIPES MUST BE INSTALLED IN ACCORDANCE WITH SECTION 4.5.6 OF AUSTRALIAN STANDARDS AS3500.3

OPENINGS OR OCCUPANCY OF A BUILDING, DO NOT CAUSE NUISANCE OR LEAD TO INJURY OF A PERSON. DO NOT INTERFERE

WITH THE STRUCTURAL INTEGRITY OF THE WALL OR COLUMN, AS CLOSE AS PRACTICABLE TO THE SUPPORTING STRUCTURE,

ARE PROTECTED FROM MECHANICAL DAMAGE, AT LEAST 100mm CLEAR OF ANY ELECTRICAL CABLE OR GAS PIPE, AT LEAST

50mm FROM ANY OTHER PIPEWORK OR SERVICE. CONCEALED DOWNPIPES TO HAVE INSPECTION OPENINGS THAT EXTEND TO THE FACE OF THE WALL OR SLAB FOR MAINTENANCE. SEAMS AND JOINTS TO BE WATERTIGHT. IF INSPECTION OPENINGS ARE REQUIRED FOR TESTING AND MAINTENANCE PURPOSES, INSPECTION OPENINGS SHALL HAVE A NOMINAL SIZE OF NOT LESS

33. SUPPORT SYSTEMS OF DOWNPIPES OR PIPEWORK MUST BE INSTALLED IN ACCORDANCE AUSTRALIAN STANDARDS AS3500.3

34. FOR CONCEALED EAVES GUTTERS, U.N.O THE TOP EDGE OF THE FASCIA SHOULD NOT BE LESS THAN 25mm BELOW THE

TOP OF THE BACK OF THE GUTTER, OR INTEGRAL FLASHING (TAIL) WITH THE TOP EDGE OF THE FLASHING NOT LESS THAN

30. WHERE ANY NEW STORMWATER DRAINAGE SYSTEM CROSSES THE FOOTPATH AREA WITHIN ANY ROAD, SEPERATE

REQUIREMENTS. BUILDER TO ENSURE LOCATIONS DO NOT RESTRICT NORMAL OPERATION OF DOORS, WINDOWS, ACCESS

32. WHERE A DOWNPIPE IS CONNECTED TO A SITE STORMWATER DRAIN LOCATED BELOW A SLAB-ON-GROUND, THE

CONNECTION OF A CONCEALED DOWNPIPE SHALL BE LOCATED ABOVE THE LEVEL OF THE FLOOR.

REDIRECTION OR TREATMENT OF FLOWS ENTERING THE PROPERTY SHALL NOT ADVERSELY AFFECT ANY OTHER PROPERTIES.

26. PREVENT ANY STORMWATER EGRESS INTO ADJACENT PROPERTIES BY CREATING PHYSICAL BARRIERS AND SURFACE

9. ALL PITS GREATER THAN 1000mm DEEP SHALL HAVE STEP IRONS AS PER COUNCIL STANDARDS.

10. ALL WORK TO BE IN ACCORDANCE WITH LOCAL COUNCIL STANDARDS AND SPECIFICATIONS.

REMAIN IN PLACE UNTIL COMPLETION AND STABILIZATION OF THE SITE TO COUNCIL SATISFACTION

13. ENSURE THAT ALL PITS AND STORMWATER PIPES ARE LOCATED CLEAR FROM TREE ROOT SYSTEMS.

6. DOWN PIPE LOCATIONS ARE INDICATIVE ONLY. LOCATIONS TO BE CONFIRMED WITH ARCHITECT PRIOR TO COMMENCEMENT

CONCRETE WALLS AND BASE. WALLS TO BE REINFORCED WITH 1 N12 TOP TIE UNLESS NOTED OTHERWISE. CAST INSITU PITS

GREATER THAN 1000 DEEP TO BE MINIMUM 900x600 AND TO HAVE 150mm THICK CONCRETE WALLS AND BASE. WALLS TO BE



CIVIL CONSULTING ENGINEERS

MULTI-DWELLING HOUSING DEVELOPMENT WITH BASEMENT CARPARK 439 CONDAMINE STREET, ALLAMBIE HEIGHTS

ONSITE DRAINAGE CALCULATIONS - NORTHERN BEACHES COUNCIL WATER MANAGEMENT POLICY (2021)

TOTAL SITE AREA	1,125 m ²
COUNCIL ZONE AREA	Region 2
DEVELOPMENT TYPE	RESIDENTIAL FLAT BUILDING
TOAL SITE IMPERVIOUS AREA (EXISTING)	$620~\text{m}^{-2}$ ($55\%~\text{IMPERVIOUS}$)
TOAL SITE IMPERVIOUS AREA (PROPOSED)	801 m 2 (71% IMPERVIOUS)
TOTAL INCREASE IN IMPERVIOUS AREA	$181 \text{ m}^2 > 50 \text{ m}^2$
RAINWATER VOLUME (BASIX) REQUIRED	0.8 m ³ (PER UNIT)
RAINWATER VOLUME PROVIDED	4.8 m ³ IN TOTAL

HYDRAULIC ANALYSIS CONFIRMS THAT OSD DELAYS SITE DISCHARGE, RESULTING IN A DETRIMENTAL ALIGNMENT WITH DOWNSTREAM FLOOD PEAKS, CONTRARY TO BEST FLOOD MANAGEMENT PRACTICES. REFER TO DESIGN STATEMENT FOR HYDROGRAPH COMPARISONS FROM THE MANLY LAGOON FLOODPLAIN RISK MANAGEMENT STUDY. THEREFORE, OSD IS NOT RECOMMENDED.

WATER SENSITIVE URBAN DESIGN TO NORTHERN BEACHES COUNCIL: WSUD & MUSIC MODELLING GUIDLINES

WSUD MUSIC SUMMARY		% REDUCTION OCEAN PROTECT	TARGET	
	TOTAL SUSPENDED SOLIDS (TSS)	86	85 %	
	TOTAL PHOSPHOROUS (TP)	68	65 %	
	TOTAL NITROGEN (TN)	59	45 %	
	GROSS POLUTANTS (GP)	95	90 %	

THE SUBSTITUTION OF AN "EQUIVALENT" DEVICE FOR THE STORMWATER TREATMENT MEASURE APPROVED UNDER THE DEVELOPMENT CONSENT MUST SUBMITTED TO THE PRINCIPAL CERTIFYING AUTHORITY FOR APPROVAL PRIOR TO INSTALLATION.

STORMWATER PUMPOUT (WET WELL PP1) CALCULATIONS TO AS3500.3

PROVIDE TWO CENTRIFUGAL DRAINAGE SUMP PUMPS WITH SINGLE-PHASE ELECTRIC MOTOR CAPABLE OF DISCHARGING 10.0 L/S EACH AGAINST A TOTAL HEAD OF (3.0m) WITH 10 STARTS PER HOUR MAXIMUM. CLÁSS 1 ZONE 2 CERTIFIED PUMPS FOR HAZARDOUS AREAS ARE REQUIRED SWITCHING SHALL PROVIDE FOR ALTERNATIVE OPERATION OF THE PUMPS, HIGH LEVEL SWITCH ON/OFF, 2ND PUMP, AND A RED LIGHT ALARM PLACED PERMANENTLY IN THE BASEMENT AREA ACTIVATED BY HIGH LEVEL SWITCH ON. FINAL PUMP OUT VOLUME AND PUMP DUTY IS SUBJECT TO DETAILED GEOTECHNICAL INFORMATION OBTAINED DURING EARTHWORKS AND EXCAVATION.

REQUIRED VOLUME:		
AREA DRAINING TO THE PUMPOUT	$TPIT = 63 m^2$	(DRIVEWAY AREA)
SEEPAGE AREA DRAINING TO THE	PUMPOUT PIT:	(BASEMENT)
SEEPAGE RATE (WALLS)	$= 1-5 L/min/m^2$	
SEEPAGE RATE (SLABS)	= 0.5-2 L/min/m2	
BASEMENT SEEPAGE RUNOFF	= 0.06 L/s	(TBC PRIOR TO CONSTI

= $[C \times I (100 \text{ YR}, 2 \text{ HR}) \times A / 3600] + \text{SEEPAGE RUNOFF}$ $= [(1.08 \times 50.6 \times 63) / 3600] + 0.06$ = 0.96 + 0.06

VOLUME ACCUMULATED (100 YEAR ARI, 2 HOUR STORM):

= 1.02 L/s

 $V_{100/120} = (1.02L/s \times 2hrs \times 3600s)/1000$ **VOLUME PUMPED IN 30 MINS:** WET WELL STORAGE CAPACITY $= (10.0L/s_x 0.5hrs_x 3600s)/1000$ $= 18.00 \text{ m}^3$ **VOLUME PUMPED IN 5 MINS:**

PROVIDE $V_{100/120} = 7.35$

 $= 3.00 \text{ m}^3$

ACCORDANCE WITH GEOTECHNICAL AND STRUCTURAL REQUIREMENTS

WET-WELL VOLUME AND SPECIFICATIONS TO BE CONFIRMED DURING TO CONSTRUCTION IN

 $= (10.0L/s \times 0.083hrs \times 3600s)/1000$

SURVEY NOTES:

1. THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN INVESTIGATED BY THE PROJECT SURVEY. THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. RTS CIVIL CONSLTING ENGINEERS PTY LTD DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE.

2. SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT THE ENGINEER. 3. REFERENCE SHOULD BE MADE DIRECTLY TO THE SURVEYOR BEFORE SETTING OUT.

PROPOSED IMPERVIOUS AREA: 801m² (71%) SCALE = 1 : 500

EXISTING UNDERGROUND SERVICES NOTES:

1. THE LOCATIONS OF UNDERGROUND SERVICES SHOWN IN THIS SET OF DRAWINGS HAVE BEEN PLOTTED FROM SURVEY INFORMATION AND SERVICE AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE.

2. RTS CIVIL CONSULTING ENGINEERS PTY LTD CANNOT GUARANTEE THE SERVICES INFORMATION SHOWN ON THESE DRAWINGS ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER.

3. CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ONSITE INCLUDING HAND EXCAVATION 4. CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT OF EXCAVATION WORKS.

5. CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH, PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES. 6. CONTRACTOR IS TO CONFIRM FINDINGS FOR THE LOCAL COUNCL OR SYDNEY WATER IN RELATION TO THE SEWER OR WATER MAINS LOCATED. CONFIRMATION OF MAINS IS REQUIRED PRIOR TO CONSTRUCTION. POSSIBLE CONFLICT OF SERVICES ARE TO BE REPORTED TO THE SUPERINTENDENT OR ENGINEER FOR FURTHER DIRECTIONS.

EXTERNAL NOTES:

1. ALL ACTIVITIES AND WORKS EXTERNAL TO THE SITE, OR THAT AFFECT PUBLIC ROADS, ARE TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL'S CODES AND STANDARDS.

2. PUBLIC FOOTPATHS SHALL BE RECONSTRUCTED TO THE SATISFACTION OF COUNCIL'S DIRECTOR OF ENGINEERING SERVICES. A ROAD OPENING PERMIT SHALL BE OBTAINED FOR ALL WORKS CARRIED OUT IN A PUBLIC OR COUNCIL CONTROLLED LAND.

3. RESTORATION OF LANDSCAPING, ROADS AND PATHS SHALL BE TO COUNCIL'S REQUIREMENTS. ALL OTHER RESTORATION SHALL BE TOTHE SATISFACTION OF THE AFFECTED PARTIES. 4. WHERE WORKS ARE UNDERTAKEN ON PUBLIC ROADS, ADEQUATE TRAFFIC CONTROL AND DIRECTIONS TO MOTORISTS SHALL BE PROVIDED BY OTHERS.


DRAWING SCHEDULE:

SW001 - COVER PAGE, NOTES & CALCULATIONS SHEET 1 OF 2 SW002 - COVER PAGE, NOTES & CALCULATIONS SHEET 2 OF 2

SE100 - SEDIMENT & EROSION CONTROL PLAN SE200 - SEDIMENT & EROSION CONTROL PLAN DETAILS SW100 - BASEMENT STORMWATER MANAGEMENT PLAN SW101 - GROUND STORMWATER MANAGEMENT PLAN

SW102 - SITE STORMWATER CATCHMENT PLAN SW200 - STORMWATER DRAINAGE DETAILS SHEET 1 OF 2

SW201 - STORMWATER DRAINAGE DETAILS SHEET 2 OF 2



MUSIC CALC SUMMARY

Project and Drawing Title:

www.dialbeforeyoudig.com.au

NO INVESTIGATION OF UNDERGROUND SERVICES HAS BEEN MADE. ALL RELEVANT AUTHORITIES SHOULD BE NOTIFIED PRIOR TO ANY EXCAVATION ON OR NEAR THE SITE

DEVELOPERS & EXCAVATORS MAY BE HELD FINANCIALLY RESPONSIBLE BY THE ASSET OWNER SHOULD THEY DAMAGE UNDERGROUND NETWORKS.

CARELESS DIGGING CAN: DIGGING CAN:

 CAUSE DEATH OR SERIOUS INJURY TO WORKERS AND THE GENERAL PUBLIC

INCONVENIENCE USERS OF ELECTRICITY. GAS, WATER AND COMMUNICATIONS

LEAD TO CRIMINAL PROSECUTION AND

DAMAGES CLAIMS

CAUSE EXPENSIVE FINANCIAL LOSSES

TO BUSINESS - CUT OFF EMERGENCY SERVICES

DELAY PROJECT COMPLETION TIMES WHILE THE DAMAGE IS REPAIRED

MINIMISE YOUR RISK AND DIAL

BEFORE YOU DIG. - TEL. 1100 ALL DIMENSIONS MUST BE VERIFIED ON SITE

BY BUILDER BEFORE COMMENCING WITH WORK.

OF THE DRAINAGE DISCHARGE PIPES.			COMMENCEMENT OF CONSTRUCTION.		
ORIC	SINAL				
				Issued for: DEVELOPMENT APPLICATION	Title:
				Approved by:	DESIGN
				R Milli	DRAWN
4	06.06.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M	Date: 06.06.25	CHECKED
v:	Date:	Description:	Reviewed:	Director Principal Engineer NER: 2570082 RPEQ: 17480 BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)	APPROVE

COUNCIL AND/OR PRIVATE CERTIFYING AUTHORITY APPROVAL FOR ALL WORKS CONTAINED ON THE FOLLOWING DRAWINGS MUST BE OBTAINED (DEVELOPMENT APPLICATION, CONSTRUCTION CERTIFICATE. AND OR COMPLYING DEVELOPMENT CERTIFICATE) PRIOR TO

21.05.202

R.M

S.M

R.M



CIVIL CONSULTING ENGINEERS STORMWATER • CIVIL • FLOOD MITIGATION

MUSIC MODEL SUMMARY

ABN: 81 615 065 588 Phone: 0490 507 300 Email: admin@rtscivil.com.au Web: rtscivil.com.au The document is produced by RTS Civil Consulting Engineers Ptv Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document

t:				
ROHANI	UT	HOLDINGS	PTY	LTD

WALSH ARCHITECTS

439 CONDAMINE STREET, ALLAMBIE HEIGHTS COVERPAGE, NOTES & CALCULATIONS SHEET 1 OF 2

Local Gourien.			
NORTHERN	BEACHES	COL	JNCIL
Project Number:	Drawing ID):	Issue:

Local Council

STORMWATER PUMP-OUT AND 'WET WELL' NOTES:

1. PUMPED SYSTEMS ARE FOR AREAS NORMALLY LESS THAN 2,000m2 WHERE IT IS NOT POSSIBLE FOR THE STORMWATER TO BE DISCHARGED BY GRAVITY THROUGH THE AVAILABLE GRAVITATIONAL POINT OF CONNECTION. ALL WORKS ARE TO BE IN ACCORDANCE WITH AS3500.3 - PLUMBING AND DRAINAGE: STORMWATER DRAINAGE - SECTION 9 - PUMPED SYSTEMS.

2. TO ENSURE THAT SEEPAGE WATER IS NOT BEING PUMPED CONTINUALLY OUT TO THE STREET, THE PUMPS IN THE BASEMENT OR LOWER LEVEL OF PROPERTY SHALL BE ADJUSTED TO PERMIT STORAGE IN THE SYSTEM PRIOR TO THE PUMPS SWITCHING ON (REFER DETAILS FOR STORAGE VOLUME AND LEVELS). THE PUMPS SHOULD THEN DISCHARGE ALL WATER SO THAT ONLY MINIMAL WATER REMAINS OVER THE PUMP INTAKE, AS REQUIRED BY THE MANUFACTURER.

3. THE PUMPS SHALL OPERATE ALTERNATELY TO LEVELS INDICATED ON THE SUPPLIED ENGINEERING DETAILS WITH BOTH PUMPS OPERATING IN UNISON AT THE LEVELS INDICATED (SYSTEM TO BE FITTED WITH ALARM SYSTEM - BY OTHERS). THE SECOND PUMP WILL BEING TO OPERATE IF THE WATER LEVEL CONTINUES TO RISE ABOVE THE MAXIMUM WATER LEVEL AFTER THE FIRST PUMP HAS COME ON. SIGNAGE IS TO BE DISPLAYED WITHIN THE LOW AREA OF THE BASEMENT INDICATING PERMIT ADDITIONAL STORAGE VOLUME IS EXPECTED (UP TO 200mm IN DEPTH) DURING A MAJOR STORM EVENT.

4. THE REQUIRED PUMPING RATE SHALL BE CALCULATED BASED ON AN ASSESSMENT OF THE EXPECTED INFLOW AND, WHERE APPROPRIATE, THE ALLOWABLE DISCHARGE RATE. HOWEVER, UNLESS NOTED OTHERWISE, THE MINIMUM PUMP CAPACITY OF A BASEMENT (BELOWGROUND) SYSTEM SHOULD NOT BE LESS THAN 10 L/s. 5. PUMPS SHALL BE IN DUPLICATE. THE MAXIMUM CAPACITY OF EACH PUMP SHALL BE SELECTED SO THAT THE CAPACITY OF THE SYSTEM RECEIVING THE DISCHARGE IS NOT EXCEEDED. THE PUMP CONTROLS SHALL BE SET UP TO ENABLE ALTERNATE PUMP OPERATION AT EACH START. IN THE EVENT THAT A PUMP FAILS TO OPERATE WHEN THE WATER LEVEL IN THE WET WELL REACHES THE PUMP START, THE OTHER PUMP SHALL BE ACTIVATED AND A VISIBLE ALARM INITIATED. IF BOTH PUMPS FAIL TO OPERATE AN AUDIBLE ALARM SHALL BE INITIATED IN ACCORDANCE WITH SECTION 8.3.7 OF AS3500.3. LOCATE HIGH AND LOW LEVEL ALARMS CLEAR OF INLETS TO PREVENT FALSE ALARMS. THE HIGH LEVEL ALARM SHOULD BE SET NO HIGHER THAN 100 MM ABOVE THE INVERT OF THE INLET PIPE, PROVIDED THAT FLOODING OF HABITABLE OR STORAGE AREAS AND VEHICLE GARAGES SHALL BE AVOIDED. WHERE FLOODING COULD OCCUR THE OVERFLOW AND HIGH-LEVEL ALARM SHALL BE LOWERED ACCORDINGLY TO PREVENT FLOODING.

6. THE MINIMUM WET WELL STORAGE BETWEEN THE HIGH AND LOW WORKING LEVELS EXPRESSED IN CUBIC METRES SHALL BE 1% OF THE CATCHMENT AREA IN m2 BUT IN ANY CASE SHALL NOT BE LESS THAN 3 m3, OR AS OTHERWISE DIRECTED OR APPROVED BY THE AUTHORITY HAVING JURISDICTION.

7. THE CAPACITY OF THE PUMPED SYSTEM (WET WELL) SHALL BE ACHIEVED BY A COMBINATION OF PUMP CAPACITY AND WET WELL STORAGE BETWEEN THE HIGH AND LOW WORKING LEVELS OF THE WET WELL. THE COMBINED EFFECTIVE STORAGE COMPRISING THE VOLUME ABLE TO BE PUMPED IN 30 MIN PLUS THE WET WELL STORAGE SHALL NOT BE LESS THAN THE VOLUME OF THE RUN-OFF FROM THE STORM OF ARI = 10 YEARS AND DURATION OF 120 MIN, OR AS OTHERWISE DIRECTED BY THE AUTHORITY HAVING JURISDICTION. 8. PUMPING EQUIPMENT SHALL BE SECURELY FIXED TO THE WET WELL USING CORROSION RESISTANT FIXINGS. 9. PUMPS SHALL BE FITTED WITH A GATE VALVE AND NON-RETURN VALVE ON THE DELIVERY SIDE OF EACH

10. PUMPS SHALL HAVE FLANGES OR UNIONS INSTALLED TO FACILITATE REMOVAL

11. PUMPS SHALL BE CONTROLLED SO AS TO LIMIT THE NUMBER OF STARTS PER HOUR TO WITHIN THE CAPACITY OF THE ELECTRICAL MOTORS AND EQUIPMENT, AND SHALL, AS FAR AS PRACTICABLE, EMPTY THE CONTENTS OF THE WET WELL AT EACH OPERATION.

12. PUMPS ARE TO OPERATE ONLY DURING HOURS SPECIFIED BY THE AUTHORITY HAVING JURISDICTION 13. VALUE OF HEAD IS TO BE CONFIRMED ONCE EXCAVATION COMPLETE AND PRIOR TO ORDERING PUMPS AND EQUIPMENT.

14. PUMP SPECIFICATIONS AND PRESSUE PIPE DIAMETER ARE TO BE DETERMINED BY THE PUMP MANUFACTURER. 15. PROVIDE LITTER SCREEN ABOVE PUMP SET.

16. ALL ELECTRICAL MOTORS AND EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH AS3000.

INSTALLATION OF PIPEWORK NEAR AND UNDER **BUILDINGS NOTES:**

THE FOLLOWING APPLY TO A DRAIN IN CLOSE PROXIMITY TO FOOTINGS OR FOUNDATIONS: 1. WHERE THE DRAIN PASSES UNDER A STRIP FOOTING, ITS ANGLE OF INTERSECTION WITH THE FOOTING IN THE HORIZONTAL PLANE SHALL BE NOT LESS THAN 45°, AND THE MINIMUM CLEARANCE BETWEEN THE TOP OF THE DRAIN TO THE UNDERSIDE OF THE FOOTING SHALL BE 25mm. . IF THE DRAIN IS LAID THROUGH FOOTINGS OR WALLS, OTHER THAN BELOW—GROUND EXTERNAL WALLS,

IT SHALL BE INSTALLED WITH AN ANNULAR SPACE OF NOT LESS THAN 25mm FILLED WITH A LINER OF FLEXIBLE MATERIAL.

3. THE DRAIN MAY BE LAID THROUGH BELOW-GROUND EXTERNAL WALLS, PROVIDEDa. TWO FLEXIBLE JOINTS ARE PROVIDED EXTERNALLY WITHIN 800mm OF THE EXTERNAL FACE OF THE WALL. AND SUCH JOINTS ARE NOT LESS THAN 600mm APART; AND

b.THE PENETRATION OF THE WALL IS MADE WATERTIGHT. 4. WHERE THE DRAIN IS TO BE LAID PARALLEL TO A FOOTING, THE TRENCH SHALL BE LOCATED AS

FOLLOWS: a. THE DRAIN SHALL BE LAID-

b. IN ACCORDANCE WITH NCC VOLUME TWO; AND

c. FOR SINGLE DWELLINGS, AS SHOWN IN FIGURE 6.2.8 OF AS3500.3.

INSPECTIONS BY ENGINEER

48 HOURS NOTICE IS REQUIRED BEFORE ANY SITE INSPECTION. ANY STRUCTURAL ELEMENT NOT INSPECTED BY RTS CIVIL WILL NOT BE CERTIFIED BY RTS CIVIL CONSULTING ENGINEERS PTY LTD. 1. BEARING STRATA OF ALL FOOTINGS PRIOR TO CONCRETE POUR BY GEOTECHNICAL ENGINEER.

2. ANY REINFORCEMENT PRIOR TO CONCRETE POUR. 3. TIMBER AND STEEL FRAMING PRIOR TO CLADDING OR LINING.

4. STEEL LINTELS AFTER INSTALLATION.

5. CONTACT YOUR PCA (PRINCIPAL CERTIFYING AUTHORITY) AS TO REQUIREMENTS FOR MANDATORY CRITICAL STAGE INSPECTIONS IN ACCORDANCE WITH REVISED EP&A ACT REGULATIONS EFFECTIVE JULY 1,

6. INSPECTION BY GEOTECHNICAL ENGINEER OVER 1.5m OF VERTICAL CUT THROUGH SANDSTONE BED ROCK TO PERMIT IDENTIFICATION OF DEFECTS AND REMEDIAL MEASURES INITIATED. 7. SCHEDULE OF CONSTRUCTION STAGES REQUIRING INSPECTION:

a. FOLLOWING PLACEMENT OF PIPE BEDDING MATERIAL. CONFIRM TRENCH/PIPE LOCATION, ADEQUACY OF

DEPTH OF COVER, BEDDING MATERIAL AND DEPTH. b. FOLLOWING JOINING OF PIPES AND CONNECTION TO COUNCIL'S STORMWATER SYSTEM.

THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC

UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD

RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL

LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE

STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY

WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE

OF THE DRAINAGE DISCHARGE PIPES.

c. FOR DISPERSION TRENCH SYSTEMS: -(i) FOLLOWING SET OUT TO CONFIRM LOCATION, LENGTH AND VOLUME OF STORAGE.

<u>INFILTRATION/ABSORPTION TRENCH NOTES (METHOD 1):</u>

1. EXCAVATE THE TRENCH ALONG A LEVEL SITE CONTOUR TO PROVIDE AT LEAST 100mm COVER OVER THE TOP OF THE LINER. 2. THE TRENCH FLOOR SHOULD BE LEVEL, EVENLY RAKED, AND HAVE NO LOW SPOTS WHICH WOULD ALLOW

3. ALLOW AT LEAST 75mm OVERLAP FOR EACH LENGTH OF EVERTRENCH.

4. IDEALLY, THREE SPREADER BARS (OPTIONAL) SHOULD BE FITTED INTO EACH STANDARD EVERTRENCH LINER, THE FIRST 220mm FROM THE INLET END, THEN EQUALLY SPACED ALONG THE EXCAVATION. 5. CUT THE PIPE ENTRY HOLE IN ONE TRENCH LINER END CAP. AN EASYDRAIN™ PIT BOSS MAY BE USED TO ENSURE A SECURE CONNECTION. FIT THE CAPS TO THE LINER AND CONNECT THE PIPING FROM THE SEPTIC TANK OR SULLAGE DISTRIBUTOR.

6. COVER THE EVERTRENCH WITH GEOTEXTILE FABRIC AND PLACE A QUANTITY OF 20-25mm AGGREGATE MATERIAL ALONG THE TRENCH LINER AND AT BOTH ENDS, SO THAT THE TOP OF THE LINER IS JUST COVERED. RAKE LEVEL

7. LAY GEOTEXTILE OVER THE AGGREGATE FOR THE FULL LENGTH OF THE TRENCH. 8. COVER THE GEOTEXTILE WITH A LAYER OF APPROVED SANDY LOAM AND LEAVE A MOUND FOR NATURAL COMPACTION. TURF MAY BE LAID OVER THE TRENCH AREA. DO NOT COMPACT THE TRENCH AREA OR EXPOSE

IT TO TRAFFIC. 9. THESE TRENCHES ARE GENERALLY LIMITED TO SITES WHERE SOIL IS CONSIDERED PERMEABLE ENOUGH TO "SOAK UP" THE EXPECTED AMOUNTS OF WASTE-WATER. THE TRENCH SHOULD BE WIDE ENOUGH TO ACCEPT THE SELECTED EVERTRENCH LINER AND DEEP ENOUGH SO THAT THE TOP OF THE SELECTED LINER IS AT LEAST 100mm BELOW THE SOIL SURFACE LEVEL.

10. TRENCH TO BE HAND DUG AROUND TREE ROOT SYSTEM IN ACCORDANCE WITH ARBORIST AND/OR LOCAL COUNCIL REQUIREMENTS. 11. A GEOTECHNICAL ENGINEERS REPORT OR RECOMMENDATIONS MAY BE REQUIRED FOR AREAS OF LOW SOIL

INFILTRATION RATES OR FOR LARGER DEVELOPMENTS. THE ENGINEER SHOULD BE NOTIFIEDDURING CONSTRUCTION AND EXCAVATION OF TRENCHES TO CONFIRM SUITABILITY OF SOILS 12. WHERE POSSIBLE, INSTALL HIGH LEVEL EMERGENCY OVERFLOW PIPE AND CONNECT TO SITE DRAINAGE SYSTEM OR NEAREST DISCHARGE POINT IN ACCORDANCE WITH AS3500.3.2 AND/OR COUNCIL REQUIREMENTS. 13. DO NOT CONNECT SUB-SOIL DRAINAGE LINES THAT ARE LESS THAN 150mm ABOVE THE SURFACE LEVEL

OF THE TRENCH. NOTIFY ENGINEER IF THE DEVELOPMENT HAS LOW LAYING SUB-SOIL DRAINAGE LINES..

TRANSPIRATION/DISPERSION TRENCH NOTES (METHOD 2):

1. EXCAVATE AN AREA 1800mm WIDE AND 300mm DEEP ALONG A LEVEL SITE CONTOUR. 2. EXCAVATE A CENTRAL TRENCH ALONG THE FULL LENGTH OF THE PREPARED AREA FOR THE SELECTED LINER. THE TOP OF THE LINER SHOULD BE LEVEL WITH THE BOTTOM OF THE PREPARED AREA. THE FLOOR SHOULD BE LEVEL, EVENLY RAKED, WITH NO LOW SPOTS.

3. CARRY OUT STEPS 3, 4, 5, 6 & 7 LISTED FOR METHOD 1 (ABSORPTION TRENCH). 4. COVER THE GEOTEXTILE AND FLOOR OF THE WIDER EXCAVATION WITH 100mm OF 10mm AGGREGATE, THEN

100mm OF COARSE SAND, AND FINALLY WITH SANDY LOAM. 5. LEAVE A MOUND FOR NATURAL COMPACTION. TURF MAY BE LAID OVER THE AREA. DO NOT COMPACT THE AREA OR EXPOSE IT TO TRAFFIC.

6. THIS METHOD ARE GENERALLY USED WHERE LOCAL SOIL CONDITIONS CANNOT COPE WITH THE VOLUME OF WASTE-WATER IN THE NORMAL NARROW ABSORPTION TRENCH SYSTEMS. TRANSPIRATION ENCOURAGES TREATED WASTE-WATER TO BE TAKEN UP BY PLANT ROOTS OVER A WIDE AREA, AS WELL AS PERMEATING THE SOIL, OFFERING ADDITIONAL SAFETY FOR SOIL ABSORPTION SYSTEMS. BEDS CONSIST OF STANDARD WIDTH TRENCHES THAT ARE DEEPER THAN NORMAL, WITH THE AREA ABOVE THE SELECTED TRENCH LINER OF MUCHGREATER WIDTH, AND FILLED WITH AGGREGATE TO ALLOW EASIER MOVEMENT OF MOISTURE.



LOCALITY PLAN NOT TO SCALE

RAINWATER HARVESTING REQUIREMENTS:

1. CONSIDERING THE ROOF CATCHMENT AREA, LOCATION OF PROPERTY, INTENDED USE OF RAINWATER AND GARDEN SIZE WE RECOMMEND PROVIDING A RAINWATER TANK FOR USE AS PER BASIX REQUIREMENTS, HCCRENS WATER SMART PRACTICE NOTE (N).4) AND THE NSW HEALTH REQUIRMENTS FOR NON DRINKING USE ONLY AS FOLLOWS:

2. THE TANKS PROVIDED WILL REDUCE PRESSURE ON COUNCIL'S STORMWATER INFRASTRUCTURE.

a) TO WATER GARDEN AREAS b) TO BASIX REQUIREMENTS

3. REFERENCES: COOMBES P.J. & KUCZERA G. (2001), "RAINWATER TANK DESIGN FOR WATER SUPPLY & STORMWATER MANAGEMENT." STORMWATER INDUSTRY ASSOCIATION REGIONAL CONFERENCE. PATRICK DUPONT & STEVE SHACKEL, "RAINWATER" AUSTRALIAN GOVERNMENT (2004), "GUIDANCE ON USE OF RAINWATER TANKS".

4. ALL CONNECTIONS TO PLUMBING AND RAINWATER TANKS TO BE IN ACCORDANCE WITH SYDNEY WATERS' GUIDE "INSTALLING A RAINWATER TANK" AVAILABLE AT www.sydneywater.com.au OR

FROM LOCAL COUNCIL GUIDLINES. 5. PROVIDE A DUAL SUPPLY SYSTEM AND BACKFLOW PREVENTION SYSTEM IN ACCORDANCE WITH 'BASIX-DESIGN GUIDE FOR SINGLE DWELLINGS' BY NSW DEPARTMENT OF

INFRASTRUCTURE, PLANING AND NATURAL RESOURCES AND AS3500.1. 6. IF NOT SPECIFIED ON PLANS, THE FIRST FLUSH SYSTEM IS TO HAVE A MINIMUM SIZE OF 20L PER 100m2 OF ROOF CATCHMENT AREA PRIOR TO ENTERING THE RAINWATER TANK. INDIVIDUAL SITE ANALYSIS IS REQUIRED IN HEAVILY POLLUTED AREAS TO DETERMINE IF LARGER VOLUMES OF FIRST FLUSH RAINWATER ARE TO BE DIVERTED. IF IN DOUBT, CHECK

WITH LOCAL HEALTH AUTHORITIES. 7. SCREENED DOWNPIPE RAINWATER HEAD OR OTHER SUITABLE LEAF AND DEBRIS DEVICE TO BE INSTALLED ON EACH DOWNPIPE. SCREEN MESH TO BE 4-6mm AND DESIGNED TO BE

8. FIRST FLUSH DEVICES, OR APPROVED ALTERATIVE, TO BE INSTALLED WITH AN AUTOMATED DIVERSION AND DRAINAGE SYSTEM, THAT IS, NO MANUAL DIVERSION AND DRAINAGE VALVES. REFER TYPICAL FLUSH OUT PIT FOR DETAILS. THIS SHOULD CATER FOR THE FIRST 1mm OF RAINFALL.

9. BEFORE PURCHASING MATERIALS OR PAINT TO BE USED ON ROOF CATCHMENT AREAS, THE MANUFACTURER'S RECOMMENDATIONS ON LABELS AND BROCHURES FOR RAINWATER TANK SUITABILITY TO BE READ AND ADHERED TO.

10. PRE-STORAGE PITS FOR UNDERGROUND RAINWATER STORAGE TANKS AND FLUSH OUT PITS MAY ASSIST IN LIMITING SILT. AND PREVENT VERMIN, INSECTS (INCLUDING MOSQUITOES) AND DEBRIS FROM ENTERING THE RAINWATER STORAGE AREA.

11. RAINWATER TANK TO BE WATER PROOFED IN ACCORDANCE WITH HB 230-200B 12. BUILDER OR PLUMBER TO ENSURE THE INSTALLATION OF THE RAINWATER TANK SYSTEM IS IN ACCORDANCE WITH THE RELEVANT AUSTRALIAN STANDARDS AND THE RAINWATER TANK DESIGN AND INSTALLATION HANDBOOK - HB 230-2008. IF IN DOUBT CONTACT ENGINEER. 13. NOISE EMISSIONS FROM ANY PUMPS DO NOT EXCEED 5dB(A) ABOVE AMBIENT BACKGROUND NOISE LEVEL MEASURED AT THE ALLOTMENT BOUNDARY.

14. AT THE COMPLETION OF THE WATER SERVICE INSTALLATION AND PRIOR TO HYDROSTATIC TESTING, THE SYSTEM SHALL BE THOROUGHLY FLUSHED TO REMOVE ANY FOREIGN MATTER. THE FLUSHING SHALL BE UNDERTAKEN IN ACCORDANCE WITH AS3500.1 REQUIREMENTS -APPENDIX I, PARAGRAPH I3 AND CONTINUE UNTIL THE FLUSHED WATER RUNS COMPLETELY CLEAR. THE SYSTEM SHALL THEN BE PRESSURE TESTED IN ACCORDANCE WITH CLAUSE

15. AT THE COMPLETION OF THE WATER SERVICE INSTALLATION THE RAINWATER STORAGE TANKS ARE TO BE TESTED IN ACCORDANCE WITH SECTION 16 OF AS3500.1.

SEDIMENT BASIN CALCULATIONS ACCORDING TO INTERNATIONAL EROSION CONTROL ASSOCIATION (IECA) 2008 AND BEST PRACTICE EROSION REQUIREMENTS

SEDIMENT BASIN SELECTION MINIMUM SETTLING AREA (As)

As = Ks He Q $= 3410 \times 1.2 \times (0.5 \times 0.026)$

TOTAL SETTLING VOLUME

 $V = 92.1 \times 0.6$ $= 53.2 \text{ m}^3$

 $= 92.1 \text{ m}^2$

As = AVERAGE SURFACE AREA OF SETTLING ZONE

Ks = SEDIMENT SETTLENT COEFFICIENT = 3410

He = HYDRAULIC EFFICIENCY CORRECTION FACTOR = 1.2

 $Q = DESIGN DISCHARGE = 0.5 \times Q1$

Q1 = 1 in 1 YEAR ARI DISCHARGE FOR SITE = 26 L/s

REDUCED SETTLING VOLUME DUE TO PUMP-OUT (DRAWDOWN):

 $= C \times I \times A$ $= 0.7 \times 0.093 \times 1394$ $= 91 \text{ m}^3/\text{hr}$ = V_{in} / T_{drawdown}

= 91 / 72 $= 1.26 \text{ m}^3/\text{hr}$ = 0.35 L/s

(PROVIDE MIN. PUMP OUT RATE WITH 7.5m PRESSUE HEAD) $(g \times (FINE SILT PARTICLE SIZE^2)(SEDIMENT DENSITY \times WATER DENSITY)$

 $(9.81 \times (0.0002^2)(2650 \times 1000)$ 18 x 0.001

18 x DYNAMIC VISCOSITY OF WATER

Vbasin_reduced = (V_{in} x T_{retention}) / T_{drawdown}

= 0.094 m/hr

 $= (91 \times 6) / 72$ = 7.6 m

Architect:

(PROVIDE MIN. VOLUME FOR 0.6m DEPTH)

SEDIMENT AND EROSION CONTROL NOTES:

1. SILT FENCE AND ASSOCIATED WORKS INCLUDING INTERCEPTOR DRAIN IS TO BE INSTALLED BEFORE THE COMMENCEMENT OF ANY EXCAVATION.

2. GEOTECHNICAL ENGINEER IS TO PROVIDE SITE STABILITY REQUIREMENTS. CUTS ARE TO BE EXECUTED TO THE REQUIRED LEVEL USING CONVENTIONAL EXCAVATION MACHINERY. AS A GUIDE, INITIALLY THE DEPTH OF FILL/CLAY IS TO BE ESTABLISHED TO ENSURE NEIGHBOURING PROPERTIES ARE NOT ADVERSELY AFFECTED. EARTH BATTERS TO BE A MAXIMUM SLOPE OF 1.0m VERT. TO 1.7m HORIZ. (AS PER GEOTECHNICAL REPORT). ANY BATTERS GREATER THAN 1.0m VERT. TO 1.7m HORIZ. ARE TO BE ADEQUATELY SHORED IN ACCORDANCE WITH GEOTECHNICAL ENGINEERS DETAILS AND INSTRUCTIONS. 3. ANY PERMANENT RETAINING STRUCTURE IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS.

4. ALL PERMANENT RETAINING STRUCTURES ARE TO BE COMPLETED WITH MINIMUM DELAY FOLLOWING EXCAVATION.

5. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSPECTED AND MAINTAINED DAILY BY SITE MANAGER.

6. CONTRCTOR TO MINIMISE DISTURBED AREAS.

7. ALL STOCKPILES TO BE CLEAR FROM DRAINS, GUTTERS AND FOOTPATHS.

8. DRAINAGE IS TO BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE. 9. ROADS AND FOOTPATH TO BE SWEPT DAILY.

10. CONSTRUCTION VEHICLES ARE TO LEAVE AND ENTER THE SITE OVER AN ALL WEATHER SURFACE CONSISTING OF COURSE CRUSHED STONE OR BLUE METAL CONSTRUCTED WITHIN THE FRONT SETBACK AREA OPPOSITE THE EXISTING FOOTPATH CROSSING UNLESS NOTED OTHERWISE.

11. EXCAVATION MACHINERY ARE TO BE UNLOADED AND LOADED UPON THIS ALL WEATHER SURFACE. CONCRETE PUMPS AND TRUCKS WILL ALSO UTILISE THE ALL WEATHER SURFACE FOR THEIR OPERATIONS 12. MATERIALS WILL BE UNLOADED UPON THE ALL WEATHER SURFACE WITHIN THE FRONT SETBACK AREA BY MEANS OF CRANES MOUNTED ON THE BACK OF DELIVERY TRUCKS OR UNLOADED BY HAND. A MOBILE CRANE MAY BE REQUIRED DURING THE CONSTRUCTION PROCESS.

13. SOME STOCKPILING OF TOPSOIL REMOVED FROM THE BUILDING AREA MAY BE STORED ON THE SITE DURING THE CONSTRUCTION WITHIN THE PROPERTY IN AN AREA ENCLOSED WITHIN THE SEDIMENT CONTROL FENCING.

14. ALL EXCAVATED & CONSTRUCTION MATERIALS, SHED, SKIP BINS, TEMPORARY WATER CLOSETS, SPOIL AND EQUIPMENT, ETC SHALL BE KEPT WITHIN THE PROPERTY. NO VEHICLES OR MACHINES SHALL BE KEPT WITHIN THE PROPERTY. NO VEHICLES OR MACHINES SHALL STAND ON COUNICIL FOOTPATHS FOR LARGE LENGTHS OF TIME.

15. ALL RUBBISH & RECYCLABLE MATERIAL SHALL BE STOCKPILED IN WASTE BINS IN THE AREA NOMINATED ON THE SITE PLAN WITHIN THE SITE BOUNDARY. PUBLIC PROPERTY SHALL BE KEPT FREE OF RUBBISH AND RECYCLABLES AT ALL TIMES ANY WASTE MATERIALS SHALL BE REGULARLY COLLECTED FROM THE SITE AND DISPOSED OF IN AN APPROPRIATE FASHION.

16. ANY BUILDING OR DEMOLITION WORKS INVOLVING ASBESTOS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE RELAVANT STANDARDS.

17. VEHICLES LEAVING THE SITE WILL DO SO VIA THE ALL WEATHER BALLAST DRIVEWAY MADE OF COURSE AGGREGATE OR SIMILLAR LOCATED WITHIN THE FRONT SETBACK AREA OF THE DEVELOPMENT ANY DIRT OR MATERIAL DEPOSITED ON THE ROAD RESERVE OR ROADWAY IS TO BE PROMPTLY CLEANED. 18. ANY EXCAVATED AREA REQUIRING SUPPORT WILL BE UNDERTAKEN BY THE OWNER USING

STRUCTURALLY APPROVED RETAINING STRUCTURES. 19. ADEQUATE SAFETY SIGNAGE MUST BE ERECTED IN A PROMINENT POSITION ON THE WORK SITE, WARNING OF UNAUTHORISED ENTRY TO WORK SITE AND INTENDING DANGERS.

20. SAFETY FENCES SHALL BE PROVIDED AROUND ALL BOUNDARIES UNLESS A CONTINUOUS STRUCTURALLY ADEQUATE FENCE PRESENTLY EXISTS. THE FENCING SHALL BE ADEQUATE TO RESTRICT PUBLIC ACCESS TO THE SITE WHEN BUILDING WORK IS NOT IN PROGRESS OR THE SITE IS UNOCCUPIED. 21. NOISE LEVELS SHALL NOT EXCEED COUNCIL REGULATION LEVELS. BUILDING AND DEMOLITION WORKS

SHALL ONLY BE CARRIED OUT BETWEEN HOURS AND DAYS SPECIFIED BY COUNCIL. 22. GEOTEXTILE FABRIC SHALL BE PLACED ON THE INSIDE OF THE SITE FENCING PRIOR TO SITE DISTURBANCE TO PREVENT SEDIMENT WASHING FROM CLEARED AND DISTURBED AREAS OF THE SITE INTO THE STORMWATER SYSTEM. DURING CONSTRUCTION, UNLESS OTHERWSIE NOTED, UNCONTAMINATED RUNOFF FROM CLEARED OR DISTURBED AREAS ARE TO BE DIRECTED TO A TEMPORARY SILT ARRESTOR PIT THAT SHALL BE PROVIDED WITHIN THE SITE AT THE STREET BOUNDARY PROCESSING SITE

STORMWATER BEFORE IT IS DISCHARGED TO THE STREET DRAINAGE SYSTEM OR WATERCOURSE. 23. ALL TOP SOIL STRIPPED & STOCKPILED ONSITE IS TO BE BE PLACED IN NOMINATED AREAS ON PLAN OR TO COUNCIL REQUIREMENTS. ALL DISTURBED AREAS ARE TO BE STABILISED UPON THE COMPLETION

OF BUILDING WORKS. 24. ALL SEDIMENT CONTROL STRUCTURES ARE TO BE CONTINUALLY MAINTAINED DURING CONSTRUCTION AND INSPECTED FOR STRUCTURAL DAMAGE AFTER EACH RAINFALL EVENT. WITH TRAPPED SEDIMEN

BEING REMOVED TO THE TOPSOIL STOCKPILE. 25. WHERE THERE IS THE POTENTIAL OF SITE EROSION TO PRODUCE EXCESSIVE SEDIMENT RUNOFF,

SUITABLE GEOTEXTILE BARRIERS SHALL BE PLACED TO ALLEVIATE THE RISK ACCORDINGLY. BARE SURFACES SHALL BE KEPT MOIST TO REDUCE DUST LEVELS. GEOTEXTILE FABRIC LOCATED ON THE INSIDE OF FENCES SHALL ALSO BE UTILISED FOR DUST CONTROL WHERE NECESSARY.

26. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH:

a) LOCAL AUTHORITY REQUIREMENTS

b) EPA - POLLUTION CONTROL MANUAL FOR URBAN STORMWATER

c) LANDCOM NSW - MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION ("BLUE BOOK") 27. PRIOR TO DISCHARGE OF SITE STORMWATER, GROUNDWATER AND SEEPAGE WATER INTO COUNCIL'S STORMWATER SYSTEM, CONTRACTORS MUST UNDERTAKE WATER QUALITY TESTS IN CONJUNCTION WITH A SUITABLY QUALIFIED ENVIRONMENT CONSULTANT OUTLING THE FOLLOWING:

a) COMPLIANCE WITH THE CRITERIA OF THE AUSTRALIAN AND NEW ZEALAND GUIDELINES FOR FRESH AND MARINE WATER QUALITY (2000)

b) IF SUBJECT TO THE ENVIRONMENTAL CONSULTANTS ADVICE, PROVIDE REMEDIAL MEASURES TO IMPROVE THE QUALITY OF WATER THAT IS TO BE DISCHARGED INTO COUNCIL'S STORMWATER DRAINAGE SYSTEM. THIS SHOULD INCLUDE COMMENTS FROM A SUITABLY QUALIFIED ENVIRONMENTAL CONSULTANT CONFIRMING THE SUITABILITY OF THESE REMEDIAL MEASURES TO MANAGE THE WATER DISCHARGED FROM THE SITE INTO COUNCIL'S STORMWATER DRAINAGE SYSTEM. OUTLINING THE PROPOSED, ONGOING MONITORING, CONTINGENCY PLANS AND VALIDATION PROGRAM THAT WILL BE IN PLACE TO CONTINUALLY MONITOR THE QUALITY OF WATER DISCHARGED FROM THE SITE. THIS SHOULD OUTLINE THE FREQUENCY OF WATER QUALITY TESTING THAT WILL BE UNDERTAKEN BY A SUITABLY QUALIFIED ENVIRONMENTAL

MINIMUM INTERNAL DIMENSIONS FOR STORMWATER AND INLET PITS AS3500.3 - TABLE 7.5.2.1 MINIMUM INTERNAL DIMENSIONS (mm) DEPTH TO RECTANGULAR CIRCULAR INVERT OF OUTLET Width Length Diameter Ø

< 450 350 < 600 600 450 450 > 600 < 900 900 600 600 > 900 < 1200 600 1000 900 > 1200 900 900 1000



A1 ORIG	SINAL		
Α	06.06.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M
Rev:	Date:	Description:	Reviewed:

Issued for: DEVELOPMENT APPLICATION Approved by: R.M DESIGN 1.05.2025 S.M 21.05.2025 DRAWN CHECKED R.M 06.06.2025 Rhys Mikhail Director | Principal Engineer | NER: 2570082 | RPEQ: 17480 APPROVED BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus

ABN: 81 615 065 588 Phone: 0490 507 300 Email: admin@rtscivil.com.au Web: rtscivil.com.au

CIVIL CONSULTING ENGINEERS STORMWATER . CIVIL . FLOOD MITIGATION

The document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or

liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document

ROHANI UT HOLDINGS PTY LTD

WALSH ARCHITECTS

Project and Drawing Title:

439 CONDAMINE STREET, ALLAMBIE HEIGHTS COVERPAGE, NOTES & CALCULATIONS SHEET 2 OF 2

NORTHERN BEACHES COUNCIL

Project Number: Drawing ID: 240803

EROSION CONTROL NOTES:

1. SILT FENCE AND ASSOCIATED WORKS INCLUDING INTERCEPTOR DRAIN IS TO BE INSTALLED BEFORE THE COMMENCEMENT OF ANY EXCAVATION.

2. CUTS TO BE EXECUTED TO THE REQUIRED LEVEL USING CONVENTIONAL EXCAVATION MACHINERY. INITIALLY THE DEPTH OF FILL/CLAY IS TO BE ESTABLISHED TO ENSURE NEIGHBOURING PROPERTIES ARE NOT ADVERSELY AFFECTED. EARTH BATTERS TO BE A MAXIMUM SLOPE OF 1.0 m VERT. TO 1.7 m HORIZ. (AS PER GEOTECHNICAL REPORT). ANY BATTERS GREATER THAN 1.0 m VERT. TO 1.7 m HORIZ. ARE TO BE ADEQUATELY SHORED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS.

3. ANY PERMANENT RETAINING STRUCTURE IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS.

4. ALL PERMANENT RETAINING STRUCTURES ARE TO BE COMPLETED WITH MINIMUM DELAY FOLLOWING EXCAVATION.

5. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSPECTED AND MAINTAINED DAILY BY SITE MANAGER.

6. CONTRCTOR TO MINIMISE DISTURBED AREAS.

7. ALL STOCKPILES TO BE CLEAR FROM DRAINS, GUTTERS AND FOOTPATHS. 8. DRAINAGE IS TO BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE.

9. ROADS AND FOOTPATH TO BE SWEPT DAILY.


SCHEDULE OF WORKS:

1. SILT FENCE AND ASSOCIATED WORKS INCLUDING INTERCEPTOR DRAIN IS TO BE INSTALLED BEFORE THE COMMENCEMENT OF ANY EXCAVATION.

2. CUTS TO BE EXECUTED TO THE REQUIRED LEVEL USING CONVENTIONAL EXCAVATION


MACHINERY. INITIALLY THE DEPTH OF FILL/CLAY IS TO BE ESTABLISHED TO ENSURE NEIGHBOURING PROPERTIES ARE NOT ADVERSELY AFFECTED. EARTH BATTERS TO BE A MAXIMUM SLOPE OF 1.0 m VERT. TO 1.7 m HORIZ. (AS PER GEOTECHNICAL REPORT). ANY BATTERS GREATER THAN 1.0 m VERT. TO 1.7 m HORIZ. ARE TO BE ADEQUATELY SHORED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS. 3. ANY PERMANENT RETAINING STRUCTURE IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS.

4. ALL PERMANENT RETAINING STRUCTURES ARE TO BE COMPLETED WITH MINIMUM DELAY FOLLOWING EXCAVATION.



SEDIMENT TRAP CONSTRUCTION SPECIFICATION:

- 1 SEDIMENT SHALL BE REMOVED AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
- 2 THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRED AS NEEDED.
- 3 CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN A MANNER, THAT EROSION AND WATER POLLUTION SHALL BE MINIMIZED.
- 4 THE SEDIMENT TRAP SHALL BE REMOVED AND THE AREA STABILIZED
- WHEN THE CONSTRUCTED DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.



SITE SEDIMENT & EROSION CONTROL PLAN

SCALE = 1 : 100

BEFORE YOU DIG

THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE

OF THE DRAINAGE DISCHARGE PIPES.

NOTE: PIT, PIPE & DOWNPIPE LOCATIONS ARE INDICATIVE ONLY & MAY VARY DUE TO CONSTRAINTS. IF IN DOUBT, ASK!

WARNING! CARE WHEN DIGGING AROUND TREE ROOTS. HAND DIGGING ONLY! MAY REQUIRE ARBORIST SUPERVISION.

A1 ORIG	SINAL			
				Iss
				App
				Dat
Α	06.06.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M	Rhy
Rev:	Date:	Description:	Reviewed:	Direc BEng

ed for: DEVELOPMENT APPLICATION	Title:	Initial:	Date:
roved by:	DESIGN	R.M	21.05.2025
e: 06.06.25 R. M. M. J. S. Mikhail	DRAWN	S.M	21.05.2025
	CHECKED	R.M	06.06.2025
or Principal Engineer NER: 2570082 RPEQ: 17480 (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)	APPROVED	R.M	06.06.2025



The document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document

	WALSH	ARCHITECTS	
Client:			

ROHANI UT HOLDINGS PTY LTD


Architect:

oject and L	Prawing litle:				
439	CONDAMINE	STREET,	ALLAMBIE		
HEIGHTS					

SEDIMENT & EROSION CONTROL PLAN

Local Council:		
NORTHERN	BEACHES COL	JNCIL
Project Number:	Drawing ID:	Issue:
240803	SE100	Α

NOT FOR CONSTRUCTION NOTE: ROCK LINE DISH DRAIN, JOINTS BETWEEN



ROCKS TO BE FILLED WITH MORTAR.

CATCH DRAIN - ROCK LINED

SCALE = N.T.S.

FENCING WIRE

TEMPORARY DISH DRAIN

DRAINAGE AREA 0.6 HA (MAX) SLOPE GRADIENT 1:2 (MAX)

TYPICAL TEMPORARY SEDIMENT (SILT) FENCE

1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL

2. DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND, 3 METRES

3. DIG A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.

5. FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS

WITH WIRE TIES or AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.

6. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm

SCALE = N.T.S.

SLOPE LENGTH 60m (MAX)

TO THE CONTOURS OF THE SITE.


4. BACKFILL TRENCH OVER BASE OF FABRIC.


WIRE OR STEEL MESH

DISTURBED AREA.

450ø GALVANISED CORRUGATED

HALF PIPE






GRAVEL KERB INLET SEDIMENT TRAP


SCALE = N.T.S.





NOTE: WHEEL WASH OR SPRAY MAY BE REQUIRED DURING WET WEATHER

TYPICAL TEMPORARY CONSTRUCTION ENTRY & EXIT DETAIL (TYPE 2)




NOTE: WHEEL WASH OR SPRAY MAY BE REQUIRED DURING WET WEATHER. GRAVEL SHALL BE CLEANED/REMOVED WHEN THE EXPOSED HEIGHT OF THE GRAVEL IS LESS THAN 30mm.

TYPICAL TEMPORARY CONSTRUCTION ENTRY & EXIT DETAIL (TYPE 1)

- 1. STRIP TOPSOIL AND LEVEL SITE.
- 2. COMPACT SUBGRADE AS REQUIRED. 3. COVER AREA WITH NEEDLE-PUNCHED GEOTEXTILE.
- 4. CONSTRUCT 200mm THICK PAD OVER GEOTEXTILE USING ROADBASE OR 30mm AGGREGATE. MINIMUM LENGTH 15 METRES OR TO BUILDING
- ALIGNMENT. MINIMUM WIDTH 3m.
- 5. CONSTRUCT HUMP IMMEDIATELY WITHIN BOUNDARY TO DIVERT
- WATER TO A SEDIMENT FENCE OR OTHER SEDIMENT TRAP. 6. OR CONSTRUCT A CATTLE GRID LOCATED AT ANY POINT WHERE
- TRAFFIC ENTERS OF LEAVES THE SITE.


THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE OF THE DRAINAGE DISCHARGE PIPES.



SEDIMENT TRAP SANDBAGS AT KERB INLETS

THREE LAYERS OF SANDBAGS WITH ENDS OVERLAPPED.

SCALE = N.T.S.




BLUE METAL —


1. ALL EROSION AND SEDIMENT CONTROL ARE MEASURES TO BE

2. CONTRACTOR TO MINIMISE DISTURBED AREAS WHERE POSSIBLE

INSPECTED AND MAINTAINED DAILY BY SITE MANAGER.








CATTLE GRID ENTRY & EXIT ALTERNATIVE SCALE = 1:20

1. EXCAVATE AREA APPROX. 3.3m WIDE BY 2.2m LENGTH. THE FLOOR OF THE EXCAVATION MUST BE FLAT, WITHOUT HIGH POINTS. AN EXCAVATED DEPTH OF 100mm ACCOMODATES A BEDDING LAYER 50mm THICK AND GRID SET DOWN OF 50mm. THE LATTER MINIMISES SILT UP OF GRID AND SLOWS DOWN TRAFFIC.

2. BEDDING MATERIAL SHALL BE SAND OR OTHER SUITABLE APPROVED MATERIAL. BEDDING MATERIAL SHALL BE EVENLY RAKED OVER FLOOR OR EXCAVATION TO A DEPTH SLIGHTLY MORE THAN 50mm. ENSURE BEDDING IS LEVEL IN BOTH DIRECTIONS.

3. LOWER CATTLE GRID ONTO THE PREPARED BASE. ENSURE THAT NO PART OF THE UNIT IS SITTING ON ANY HIGH POINTS.

4. BACKFILL AND COMPACT AROUND GRID. GRADE EXCAVATED ROAD MATERIAL UP TO GRID EACH SIDE TO FORM A RAMP. IF DEPRESSIONS OCCUR ON THESE RAMPS WITH USE, ADD ADDITIONAL MATERIAL.



TEMPORARY SEDIMENT BASIN (SETTLING POND) TYPICAL DETAILS SCALE = 1:20



A1 ORIGINAL Issued for: DEVELOPMENT APPLICATION Approved by: R.M DESIGN DRAWN S.M 06.06.25 STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION CHECKED R.M Rhys Mikhail Director | Principal Engineer | NER: 2570082 | RPEQ: 17480 Rev: Date: Description: Reviewed: APPROVED BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus

300

300

Date:		
21.05.2025		CIV
21.05.2025		STORM
06.06.2025	ABN: 81 615 065 588 Phone: 0490 507 300	Email:
	The decument is produced by PTC Civil Consulting Engineers D	tu Ita /DTC

VIL CONSULTING **GINEERS**

MWATER . CIVIL . FLOOD MITIGATION admin@rtscivil.com.au Web: rtscivil.com.au The document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or

liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document

Architect: WALSH ARCHITECTS

ROHANI UT HOLDINGS PTY LTD

Project and Drawing Title: 439 CONDAMINE STREET, ALLAMBIE HEIGHTS SEDIMENT & EROSION CONTROL


PLAN DETAILS

NORTHERN BEACHES COUNCIL

Project Number: Drawing ID: Issue: 240803

NOT FOR CONSTRUCTION





N/C

THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE OF THE DRAINAGE DISCHARGE PIPES.

WARNING! CARE WHEN DIGGING AROUND TREE ROOTS. HAND DIGGING ONLY! MAY REQUIRE ARBORIST SUPERVISION.

BASEMENT STORMWATER MANAGEMENT PLAN

SCALE = 1 : 100



A1	ORIGINAL	

				Issued for: DEVELOPMENT APPLICATION	Title:	Initial:	Date:
				Approved by:	DESIGN	R.M	21.05.2025
					DRAWN	S.M	21.05.2025
Α	06.06.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M	Date: 06.06.25 7\/////// Rhys Mikhail	CHECKED	R.M	06.06.2025
Rev:	Date:	Description:	Reviewed:	Director Principal Engineer NER: 2570082 RPEQ: 17480	APPROVED	P.M	06 06 2025



The document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or

,	WA	LSH	ARCHITEC	TS	
Client:					
ROHA	NI	UT	HOLDINGS	PTY	LTD

439 CONDAMINE STREET, ALLAMBIE HEIGHTS

BASEMENT
STORMWATER MANAGEMENT PLAN

Project and Drawing Title:


Local Council:		
NORTHERN	BEACHES (COUNCIL
Project Number:	Drawina ID:	lssue:

240803 |SW100|

NOT FOR CONSTRUCTION







WARNING! CARE WHEN DIGGING AROUND TREE ROOTS. HAND DIGGING ONLY! MAY REQUIRE ARBORIST SUPERVISION.

NOTE:

THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE OF THE DRAINAGE DISCHARGE PIPES.

GROUND STORMWATER MANAGEMENT PLAN

SCALE = 1 : 100





Α1	ORIG	INAL

				Issued for: DEVELOPMENT APPLICATION	Title:	Initial:	Date:
				Approved by:	DESIGN	R.M	21.05.2025
					DRAWN	S.M	21.05.2025
Α	06.06.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M	Rhys Mikhail	CHECKED	R.M	06.06.2025
Rev:	Date:	Description:	Reviewed:	Director Principal Engineer NER: 2570082 RPEQ: 17480 BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)	APPROVED	R.M	06.06.2025



The document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or

CIVIL CONSULTING
ENGINEERS

STORMWATER • CIVIL • FLOOD MITIGATION
Email: admin@rtscivil.com.au Web: rtscivil.com.au

Web: rtscivil.com.au

RV Ltd (RTS) solely for the benefit of and use by the

ROHANI UT HOLDINGS PTY LTD

439 CONDAMINE STREET, ALLAMBIE
HEIGHTS
GROUND
STORMWATER MANAGEMENT PLAN

Project and Drawing Title:

Local Council:

NORTHERN BEACHES COUNCIL

Project Number: Drawing ID: Issue:

240803

SW101



STORMWATER PIT NEW STORMWATER PIPE

STORMWATER PIPE FLOW DIRECTION STORMWATER PIPE TO RWT EXISTING STORMWATER PIPE

FLUSH-OUT LINE BOUNDARY LINE EXISTING SEWER MAIN

EXISTING OVERHEAD POWER LINES EXISTING ELECTRICITY LINE EXISTING WATER MAINS EXISTING TELECOMMUNICATIONS LINE

DP1

DENOTES DOWNPIPE DENOTES SIZE OF DOWNPIPE DOWNPIPE TO RWT DP2 DOWNPIPE TO SQID GD1 200mm MIN. GRATED STRIP DRAIN TO ARCHITECTS DETAIL

EXISTING GAS MAINS

GD2 100mm MIN. GRATED STRIP DRAIN TO ARCHITECTS DETAIL 200mm MIN. GRATED STRIP DRAIN TO ARCHITECTS DETAIL GD3 PP1 7,350L PUMP OUT PIT AH1 900x900 GRATED ACCESS HATCH

BD1 100ø/80 RAINWATER OUTLET (SPS TRUFLO) FD1 100ø/100 RAINWATER OUTLET (SPS TRUFLO) 1000/80 RAINWATER OUTLET WITH PLANTER ADAPTOR (SPS TRUFLO) PD1

O/F PROVIDE OVERFLOW SPS SCUPPER DRAIN 80mm RWT 800L (4,800L TOTAL) RAINWATER TANKS

O/F OVERFLOW POINT - TO ARCHITECTUARL DETAILS FDB1 100ømm BASEMENT PERIMETER DRAIN DR1 100mm MIN. WIDE INTERNAL OPEN DISH DRAIN

SQID1 1 x STORMFILTER BY OCEAN PROTECT SQID2 600x600 PIT WITH FILTER BY OCEAN PROTECT - SEE DETAILS

SQID3 PP1 WITH FILTER BY OCEAN PROTECT FFD INGROUND FIRST FLUSH DIVERTER

WSUD MUSIC MODELLING CATCHMENT DETAILS					
CATCHMENT	TREATMENT DEVICE	AREA			
IA1 - IMPERVIOUS AREA 1	SQID2/SQID1	471 m²			
PA1 - PERVIOUS AREA 1	SQID2/SQID1	180 m²			
RA1 — ROOF AREA 1	RWT/SQID1	126 m²			
RA2 — ROOF AREA 2	% OF RWT/SQID1	223 m²			
DA1 - DRIVEWAY AREA 1	SQID3/SQID1	62 m²			
BAYPASS AREAS	_	60 m²			

NOTE: PIT, PIPE & DOWNPIPE LOCATIONS ARE INDICATIVE ONLY & MAY VARY DUE TO CONSTRAINTS. IF IN DOUBT, ASK!

WARNING! CARE WHEN DIGGING AROUND TREE ROOTS. HAND DIGGING ONLY! MAY REQUIRE ARBORIST SUPERVISION.

THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE OF THE DRAINAGE DISCHARGE PIPES.



SITE STORMWATER CATCHMENT PLAN

SCALE = 1 : 150



Α	06.06.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION

Description:

A1 ORIGINAL

Rev: Date:

Issued for: DEVELOPMENT

Reviewed:

Issued for: DEVELOPMENT APPLICATION	Title:	Initial:	Date:
Approved by:	DESIGN	R.M	21.05.202
R Milli	DRAWN	S.M	21.05.202
Date: 06.06.25 7\	CHECKED	R.M	06.06.202
Director Principal Engineer NER: 2570082 RPEQ: 17480 BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)	APPROVED	R.M	06.06.202



The document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the

liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document

client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or

	1	WA	LSH	ARCHITEC	TS	
Clier	nt:					
	ROHA	NI	UT	HOLDINGS	PTY	LTD


Architect:


ject and D	Prawing Title:		
439	CONDAMINE	STREET, GHTS	ALLAMBIE
	1161	01113	

SITE STORMWATER CATCHMENT PLAN

Local Council:		
NORTHERN E	BEACHES COL	JNCII
Project Number:	Drawing ID:	Issue

240803 SW102 A





liability whatsoever to any third party arising out of any use or reliance by third party on the content of this documer