

## Natural Environment Referral Response - Riparian

<b>Application Number:</b>	DA2023/0718
<b>Proposed Development:</b>	Renovation of eleven (11) of the existing golf course greens, construction of one (1) new green and removal of trees.
<b>Date:</b>	14/08/2023
<b>To:</b>	Nick Keeler
<b>Land to be developed (Address):</b>	<p>Lot 1 DP 662920 , 52 Cabbage Tree Road BAYVIEW NSW 2104</p> <p>Lot 1 DP 19161 , 52 Cabbage Tree Road BAYVIEW NSW 2104</p> <p>Lot 5 DP 45114 , 52 Cabbage Tree Road BAYVIEW NSW 2104</p> <p>Lot 7 DP 45114 , 52 Cabbage Tree Road BAYVIEW NSW 2104</p> <p>Lot 6 DP 45114 , 52 Cabbage Tree Road BAYVIEW NSW 2104</p> <p>Lot A DP 339874 , 1825 Pittwater Road BAYVIEW NSW 2104</p> <p>Lot 1 DP 986894 , 1825 Pittwater Road BAYVIEW NSW 2104</p> <p>Lot 2 DP 986894 , 1825 Pittwater Road BAYVIEW NSW 2104</p> <p>Lot 3 DP 986894 , 1825 Pittwater Road BAYVIEW NSW 2104</p> <p>Lot 150 DP 1003518 , 1825 Pittwater Road BAYVIEW NSW 2104</p> <p>Lot 191 DP 1039481 , 1825 Pittwater Road BAYVIEW NSW 2104</p> <p>Lot 300 DP 1139238 , 1825 Pittwater Road BAYVIEW NSW 2104</p>

### Reasons for referral

This application seeks consent for the following:

- All Development Applications on land, and located within 40 metres of land, containing a watercourse, or
- All Development Applications on land containing a wetland, or located within 100m of land containing a wetland,
- All Development Applications on land that is mapped as “DCP Map Waterways and Riparian Land”.

And as such, Council's Natural Environment Unit officers are required to consider the likely impacts on drainage regimes.

### Officer comments

Supported.

This application was assessed in consideration of:

- Supplied plans and reports;
- State Environmental Planning Policy (Resilience and Hazards) 2021;
- Relevant LEP and DCP clauses;
- Northern Beaches Water Management for Development Policy.

The application has been assessed in consideration of the above noting that consent also has to be gained from NSW Department of Planning, Industry and Environment – Water under a controlled activity permit (approval is required under the provisions of the Water Management Act 2000).

The proposal seeks consent for the renovation of golf course greens, construction of a new green, and removal and replacement of trees. The site is in a floodplain area that drains to Pittwater estuary, and so must not significantly impact on the biophysical, hydrological or ecological integrity of the floodplain or Pittwater estuary, or on the quantity and quality of surface and ground water flows that these areas receive.

The documentation submitted for the project is considered satisfactory and the project impacts acceptable.

Sediment and erosion controls must be installed prior to any disturbance of soil on site and maintained until all work is complete and groundcover reestablished.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

#### **Recommended Natural Environment Conditions:**

### **CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE**

#### **Erosion and Sediment Control Plan**

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points
- Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Principal Certifier for approval prior to the issue of the Construction Certificate.

Reason: To protect the receiving environment.

## **CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK**

### **Installation and Maintenance of Sediment and Erosion Controls**

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: To protect the receiving environment.