



**PLANT SCHEDULE**

Botanical Name	Common Name	Height x Spread at Maturity (mm)	Pot Size	Qty
<b>TREES</b>				
<i>Banksia integrifolia</i>	Coastal Banksia	8000 x 6000	300mm	2
<b>GROUNDCOVERS</b>				
<i>Carpobrotus glaucescens</i>	Native Pigface	200 x 800	150mm	tba

**ESTABLISHMENT AND MAINTENANCE NOTES**

- Should the required soil depths in garden beds, as noted on plan, be unattainable without creating poor drainage (excavating into rock), consider building up soils depth by means of low retaining walls on top of rock outcrops.
- Imported topsoils should have low pH (pH<7) and be a high quality sandy loam.
- Irrigation by hand, with volume sufficient to soak root balls, will be required for first 6 months of establishment. This may be required on a weekly basis unless rain provides similar volume.
- Fertilise as for native plants (low Phosphorus).
- Mulch with quality leaf litter/woodchip mulch from native trees (no weed tree species), to a depth of 75mm, keeping mulch away from plant stems. Top up as required.

Client	DELMAR PRIVATE HOSPITAL		
Project	QUIRK STREET, DEE WHY		
Title	LANDSCAPE PLAN CARPARK AREA		
Date of Issue	Scale	Drawing No	
5.2.2014	1:100 @A1	LP01 C	
Reason for Issue			
SECTION 96			

Selena Hannan MAILDM  
 PO Box 4146, North Curl Curl, NSW 2099  
 Phone 02 8084 3031  
 Mobile 0403 041 187  
 Email selena.hannan@optusnet.com.au

