B

# SYMBOLS

Α

	—
RL	PIT SURFACE LEVEL
IL	INVERT LEVEL
ТК	TOP OF KERB
B.O.W	BOTTOM OF WALL
T.O.W	TOP OF WALL
SW SW	STORMWATER DRAINAGE PIPE
RWT	DOWNPIPE TO RAINWATER TANK
SW	OVERFLOW PIPE FROM RAINWATER TANK
	Ø100 SUBSOIL PIPE
— - s s - —	Ø100 SUBSOIL PIPE
<b>X</b> FW	FLOOR WASTE 150X150
⊗ FW	FLOOR WASTE 150Ø
Ø RWO	RAINWATER OUTLET 300Ø
🖉 PG	PLANTER GRATE
●DP	DOWN PIPE
•CO	CLEAN OUT
• IO	INSPECTION OPENING
●VD	VERTICAL DROP
●VR	VERTICAL RISER
$\bowtie$	CONCRETE COVER JUNCTION PIT
	GRATED INLET PIT
	WIDE GRATED DRAIN
$\langle \rangle$	OVERLAND FLOW PATH
<u> T</u>	CAST IN SLAB PIPE

# NOTES

1. ALL LINES ARE TO BE MIN. 100Ø UPVC @ MIN 1.0% GRADE UNLESS NOTED OTHERWISE.

С

- 2. IT IS THE CONTRACTORS RESPONSIBILITY TO LOCATE & LEVEL ALL EXISTING SERVICES PRIOR TO THE COMMENCEMENT OF ANY EARTHWORKS, ALL DESIGN LEVELS SHOWN ON PLAN SHALL BE VERIFIED ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORK.
- 4. ALL PITS IN DRIVEWAYS BE HEAVY DUTY GRATES. DIRECT SURFACE FLOW TO ALL GRATED SURFACE INLET PITS.
- ALL WORK DO BE DONE IN ACCORDANCE WITH AS/NZ 3500.3 (CURRENT EDITION), COUNCIL SPECIFICATIONS, RELEVANT VOLUME OF NCC (NATIONAL CONSTRUCTION CODE)
- 6. LOCATION OF DOWNPIPES & FLOOR WASTES ARE INDICATIVE ONLY. DOWNPIPE & FLOOR WASTE SIZE, LOCATION & QUANTITY TO BE DETERMINED BY BUILDER & IN ACCORDANCE WITH RELEVANT AUSTRALIAN STANDARDS.
- 7. THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ARCHITECTURAL, LANDSCAPE AND STRUCTURAL AND ALL OTHER RELEVANT CONSULTANT'S PLANS.
- 8. ALL RAINWATER TANKS TO BE FITTED WITH A FIRST FLUSH DEVICE TO PREVENT POTENTIAL CONTAMINANTS FROM ENTERING THE TANKS.
- 9. ANY DISCREPANCIES OR OMISSIONS SHALL BE REFERRED TO THE DESIGN ENGINEER FOR RESOLUTION.
- 10. ALL PITS OR GRATES IN TRAFFICABLE AREAS TO BE HEAVY DUTY.
- 11. ALL GUTTERS WILL BE FITTED WITH LEAF GUARDS AND SHOULD BE INSPECTED AND CLEANED TO ENSURE LEAF LITTER CANNOT ENTER THE DOWNPIPES
- 12. PROVIDE EMERGENCY OVERFLOW TO ALL PLANTER BOX AND BALCONIES.
- 13. ALL PITS WITH DEPTH MORE THAN 900mm MUST HAVE IRON STEPS AND TO BE BENCHED AND STREAMLINED
- 14. PROVIDE STORMWATER GRATE 200Wx200D AT THE BASE OF ALL MECHANICAL SHAFTS AND UNCOVERED STAIRS OR OPENINGS.
- 15. ENSURE ALL DRAINAGE WORKS ARE AWAY FROM TREE ROOTS
- 16. SERVICES SHOWN ON THESE PLANS HAVE BEEN LOCATED FROM INFORMATION SUPPLIED BY THE RELEVANT AUTHORITIES AND FIELD INVESTIGATION AND ARE NOT GUARANTEED COMPLETE NOR CORRECT. IT IS THE CLIENT AND CONTRACTOR'S RESPONSIBILITY TO LOCATE ALL PRIOR TO CONSTRUCTION.
- 17. ALL VARIATIONS TO THE WORKS AS SHOWN ON THE APPROVED DRAWINGS ARE TO BE CONFIRMED BY SMART STRUCTURES AUSTRALIA PRIOR TO COMMENCEMENT OF WORKS.
- 18. THE MINIMUM SIZES OF THE STORMWATER DRAINS SHALL NOT BE LESS THAN DN90 FOR CLASS 1 BUILDINGS AND DN100 FOR OTHER CLASSES OF BUILDING OR AS REQUIRED BY THE REGULATORY AUTHORITY
- 19. ALL STORMWATER DRAINAGE PITS IN GARDEN OR TURFED AREAS TO BE FITTED WITH PERFORATED GALVANISED STEEL MESH UNDER THE LIDS TO PREVENT DEBRIS ENTERING STORMWATER NETWORK.
- 20. PIPE INSTALLATION TO BE IN ACCORDANCE WITH THE REQUIREMENTS OF CURRENT AS3500.3 AND RELEVANT VOLUME OF NCC (NATIONAL CONSTRUCTION CODE). THIS IS CONTRACTOR'S RESPONSIBILITY TO CHECK IMPACT OF PIPE TRENCHING TO SURROUNDING STRUCTURAL AND NON STRUCTURAL ELEMENTS.

▲ 1 11( efore you di

IMPORTANT:

CONTRACTOR TO OBTAIN CURRENT SET OF "DIAL BEFORE YOU DIG" PLANS ON SITE ALL TIMES AND PRIOR TO CONSTRUCTION WORKS

					SCALE BARS
А	ISSUED FOR D.A.	31.05.22	J.E.	K.E.	
No.	Description	Date	Issued by	Checked by	

\_\_\_\_\_

# CONCEPT STORMWATER DRAWINGS FOR 27 GULLIVER STREET, BROOKVALE NSW 2100

ALL PIPES TO HAVE MIN 200mm COVER IF LOCATED WITHIN PROPERTY.

CLIENT:

ARCHITECT:

## AS 3500.3- TABLE 8.2 SIZE OF MINIMUM INTERNAL DIMENSIONS FOR STORMWATER AND INLET PITS

DEPTH OF	MINIMUM INTERNAL DIMENSIONS (mm)					
OUTLET	RECTANGU	CIRCULAR				
	WIDTH	LENGTH	DIAMETER			
≤600	450	450	600			
>600 ≤900	600	600	900			
>900 ≤1200	600	900	1000			
>1200	900	900	1000			

DRAWING NUMBER	

D00	COVER SHEE
D01	BASEMENT S
D02	GROUND FLO
D04	ROOF STORM
D05	POST DEVELO
D09	STORMWATE
D10	STORMWATE
D15	EROSION AND




WALSH ARCHITECTS

SUIT 2.04, L2, BLDG 3, 35 WATERLOO RD., MACQUARIE PARK, NSW, 2113 info@smartstructs.com.au | www.smartstructs.com.au DRAWING LIST


DRAWING NAME

T, LEGEND & DRAWING SCHEDULE
TORMWATER DRAINAGE PLAN
OOR STORMWATER DRAINAGE PLAN
/WATER DRAINAGE PLAN
OPMENT CATCHMENT PLAN
R DRAINAGE SECTIONS AND DETAILS SHEET 1
R DRAINAGE SECTIONS AND DETAILS SHEET 2
D SEDIMENT CONTROL PLAN AND DETAILS

DRAWING TITLE COVER SHEET, LEGEND & DRAWING SCHEDULE				PROJECT 27 GULLIVER STREET, BROOKVALE NSW 2100		
HEET NO. <b>D00</b>	REV.	SCALE @ A1	NORTH	PROJECT NO. <b>220098</b>		
esigned: <b>K.E.</b>	drawn: J.E.	AUTHORISED:		PROJECT START DATE: MAY 2022		



RAWING TITLE BASEMENT STORMWATER DRAINAGE PLAN			PROJECT 27 GULLIVER STREET, BROOKVALE NSW 2100		
ieet no. <b>D01</b>	rev.	SCALE @ A1 AS SHOWN	NORTH	PROJECT NO. 220098	
esigned: <b>K.E.</b>	drawn: J.E.	AUTHORISED:		PROJECT START DATE: MAY 2022	






RAWING IIILE
GROUND FLOOR STORMWATER
DRAINAGE PLAN

27 GULLIVER STREET, BROOKVALE NSW 2100

	-		
HEET NO. <b>D02</b>	rev. B	SCALE @ A1 AS SHOWN	NORTH
esigned: K.E.	drawn: J.E.	authorised:	

PROJECT NO. **220098** PROJECT START DATE: MAY 2022 5

\_\_\_\_\_



CLIENT
--------

(	G		


ROOF STORA	AWATER DRAI	NAGE PLAN	PROJECT 27 GULLIVER STREET, BROOKVALE NSW 2100				
HEET NO. <b>D04</b>	rev. B	SCALE @ A1 AS SHOWN	NORTH	PROJECT NO. <b>220098</b>			
esigned: K.E.	drawn: J.E.	AUTHORISED:		PROJECT START DATE: MAY 2022			

4

5

\_\_\_\_\_

Н





0	ST DEVELOPMENT CATCHMENT ANALTSIS.						
T/	AL SITE AREA:	594.58 m²					
E	A DRAINING TO OSD:	594.58 m <sup>2</sup>					
	ROOF	282.00 m <sup>2</sup>					
	HARDSTAND	186.00 m²	${}$				
	DRIVEWAY	20.93 m²					
	LANDSCAPE	105.65 m²					

	POST	DEVE	LOPM	ENT (	CATC	HMEN	T PLAN
--	------	------	------	-------	------	------	--------

DRAWING TITLE POST DEVELO	OPMENT CATO	CHMENT PLAN	PROJECT 27 GULLIVER STREET, BROOKVALE NSW 2100		
SHEET NO. <b>D05</b>	rev. B	SCALE @ A1 AS SHOWN	NORTH	PROJECT NO. <b>220098</b>	
designed: K.E.	drawn: J.E.	AUTHORISED: K.E.		PROJECT START DATE: MAY 2022	

## PUMP SPECIFICATIONS **STANDARD PUMP-OUT NOTES**

А

\_\_\_\_\_

2

\_\_\_\_\_

3

5


\_\_\_\_

THE PUMP-OUT SYSTEM IS DESIGNED TO WORK IN THE FOLLOWING MANNER

1. A LOW LEVEL FLOAT SHALL BE PROVIDED TO ENSURE THAT THE MINIMUM REQUIRED WATER LEVEL IS MAINTAINED WITHIN THE SUMP AREA OF THE BELOW GROUND TANK. IN THIS REGARD THIS FLOAT WILL FUNCTION AS AN OFF SWITCH FOR THE PUMP.

В

- 2. A SECOND FLOAT SHALL BE PROVIDED AT A HIGHER LEVEL, APPROXIMATELY 300mm ABOVE THE MINIMUM WATER LEVEL, WHEREBY THE PUMP WILL OPERATE & DRAIN THE TANK TO THE LEVEL OF THE LOW LEVEL FLOAT.
- 3. A THIRD FLOAT SHALL BE PROVIDED AT A HIGH LEVEL, WHICH IS APPROXIMATELY THE ROOF LEVEL OF THE BELOW GROUND TANK. THIS FLOAT SHOULD ACTIVATE THE ALARM.
- 4. AN ALARM SYSTEM SHALL BE PROVIDED WITH A FLASHING STROBE LIGHT & A PUMP FAILURE WARNING SIGN WHICH ARE TO BE LOCATED AT THE DRIVEWAY ENTRANCE TO THE BASEMENT LEVEL. THE ALARM SYSTEM SHALL BE PROVIDED WITH A BATTERY BACK-UP IN CASE OF POWER FAILURE.



PUMP WELL DETAILS AREA DRAINING TO SUMP =  $29.62m^2$ VOLUME BASED ON 100 YEAR ARI 2 HOUR INTENSITY INTENSITY = 50.80mm/hr  $Q = 1 \times 50.80 \text{ mm/hr} \times 29.62 \text{ m}^2 / 3600 = 0.418 \text{ L/s}$ VOLUME REQUIRED = 0.418 x (60x60x2) = 3.00m<sup>3</sup> MIN. VOLUME REQUIRED BY AS 3500= 3.00 m<sup>3</sup>

PUMP OUT RATE BASED ON 100 YEAR ARI 5 MIN INTENSITY = 278mm/hr


STORAGE PROVIDED 2.0x1.50x1.0m= 3.00 m<sup>3</sup>

Q = 1x278x29.62 / 3600 = 2.29L/s

DUAL KS-05 PUMP OR EQUIVALENT TO BE INSTALLED IN SUMP AND CONNECTED TO CONTROL PANEL WHICH WILL ALLOW FOR THE PUMPS TO OPERATE SIMULTANEOUSLY ON HIGH LEVEL ALARMS AT 2.29L/sec (PER PUMP) AT 3.70m HEAD


	_ Output		Output Outlet		Rated		Maximum		Weigh	Dimonsion		
Туре	Uu	ւրու	00	uer	Head C	apacity	Head	Capacity	weign		Dimension	
	HP	kW	mm	Inch	М	LPM	м	LPM	Kg	L(mm)	W(mm)	H(mm)
KS-03	1/3	0.25	40	1 1/2"	3	130	8	180	9	188	141	305
 KS-04	1/2	0.4	50	2"	5	150	8	220	11	208	140	359
KS-05	1/2	0.4	50	2"	5	160	10	260	14	230	156	375
KS-08	1	0.75	50	2"	6	240	13	380	21	290	180	425
KS-20	2	1.5	80	3"	10	300	16	600	31	278	182	475
KS-30	3	2.2	80	3"	10	500	18	800	42	390	250	450
KS-50	5	3.7	100	4"	10	800	21	1100	48	450	240	530
KS-75	7 1/2	5.6	100	4"	15	800	23	1300	60	550	310	590
KS-100	10	7.5	150	6"	18	900	25	1600	70	550	310	610

FLOW (L/M)



## PUMP OUT PIT PLAN VIEW SCALE NTS

# BASEMENT PUMP-OUT $AREA = 3.00m^{2}$ AVERAGE DEPTH = 1.00m VOLUME PROVIDED = $3.00 \text{m}^3$ VOLUME REQUIRED = $3.00 \text{m}^3$ TWL 29.60 RL 28.60 A. . . A. A .A .




## SCALE BARS 1:20 1:50 1:100 1:200 ISSUED FOR D.A. 27.06.22 J.E. K.E. В А ISSUED FOR D.A. 31.05.22 J.E. K.E. No. Date Issued by Checked by Description


С

D


SCALE N.T.S.












PLANTER GRATE DETAIL



	CLIENT:
2	-
5	
10	
20	ARCHITECT:
	WALSH ARCHITECTS



SUIT 2.04, L2, BLDG 3, 35 WATERLOO RD., MACQUARIE PARK, NSW, 2113 info@smartstructs.com.au | www.smartstructs.com.au G




### DRAWING TITLE PROJECT 27 GULLIVER STREET, BROOKVALE **STORMWATER DRAINAGE SECTIONS** NSW 2100 AND DETAILS SHEET 1 SHEET NO. REV. SCALE @ A1 NORTH PROJECT NO. 220098 D09 NTS PROJECT START DATE: AUTHORISED: DESIGNED: DRAWN: MAY 2022 K.E. K.E. J.E.

AS SHOWN

ON PLAN

CONCRETE INFILL TO -

CREATE MIN. DROP



\_\_\_\_\_

No.

Description

Date


Issued by Checked by








DRAWING TITLE			PROJECT		
STORMWATER DRAINAGE SECTIONS			27 GULLIVER STREET, BROOKVALE		
AND DETAILS SHEET 2			NSW 2100		
SHEET NO. <b>D10</b>	REV.	SCALE @ A1	NORTH	PROJECT NO. <b>220098</b>	
designed:	drawn:	AUTHORISED:	-	PROJECT START DATE:	
<b>K.E.</b>	J.E.	K.E.		MAY 2022	




## SYMBOLS



EXISTING LEVELS

SITE FENCE



Ø50 PUMP LINE

STABILISED SITE ACCESS



EXISTING STRUCTURE TO BE DEMOLISHED

DISCHARGE WATER THROUGH HAY BALES TO PREVENT EROSION

PUMP LINE

HOLDING TANK FILTRATION UNIT

MANUALLY ACTIVATED SUBMERSIBLE PUMP TO BE PLACED ON PLINTH AT MIN 600mm FROM INVERT OF STILLING POND. CONTRACTOR IS TO ENSURE SEDIMENT HAS SETTLED PRIOR TO PUMP OPERATION. SEDIMENT MATERIAL IS TO BE CLEARED REGULARLY AND SHALL NOT AT ANY TIME REACH THE LEVEL OF THE PUMP INTAKE.

GENERAL INSTRUCTIONS:

SWM01

THESE PLANS PRESENT A CONCEPTUAL SOIL AND WATER MANAGEMENT PLAN (SWMP) ONLY AND SHOWS A POSSIBLE WAY OF MANAGING SOIL AND EROSION. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE ESTABLISHMENT AND MANAGEMENT OF THE SITE AND PREPARING A DETAILED PLAN AND OBTAINING APPROVAL FROM THE RELEVANT AUTHORITY PRIOR TO THE COMMENCEMENT OF ANY WORKS.

SWM02 THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE ENGINEERING PLANS AND ANY OTHER PLANS, WRITTEN INSTRUCTIONS, SPECIFICATION OR DOCUMENTATION THAT MAY BE ISSUED AND RELATING TO DEVELOPMENT OF THE SUBJECT SITE.

SWM03 THE CONTRACTOR WILL ENSURE THAT ALL SOIL AND WATER MANAGEMENT WORKS ARE CONSISTENT WITH ' MANAGING URBAN STORMWATER - SOILS AND CONSTRUCTION' - ALSO KNOWN AS ' THE BLUE BOOK'.

SWM04 ALL BUILDERS AND SUB-CONTRACTORS SHALL BE INFORMED OF THEIR RESPONSIBILITIES IN MINIMISING THE POTENTIAL FOR SOIL EROSION AND POLLUTION TO DOWNSLOPE LANDS AND WATERWAYS.

EROSION CONTROL

SWM05 WATER SHALL BE PREVENTED FROM ENTERING THE PERMANENT DRAINAGE SYSTEM UNTIL SEDIMENT CONCENTRATION IS LESS THEN OR EQUAL TO 50MG/L, IE THE CATCHMENT AREA HAS BEEN PERMANENTLY LANDSCAPED AND/ OR ANY LIKELY SEDIMENT HAS BEEN FILTERED THROUGH AND APPROVED STRUCTURE.

SWM06 ANY SAND USED IN THE CONCRETE CURING PROCESS (SPREAD THE SURFACE WIL BE REMOVED AS SOON AS POSSIBLE AND WITHIN 10 WORKING DAYS FROM PLACEMENT.

SWM07 ACCEPTABLE RECEPTORS WILL BE CONSTRUCTED FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID WASHINGS, LIGHT-WEIGHT WASTE MATERIALS AND LITTER.

SWM08

'SEDIMENT' FENCING WILL BE INSTALLED AS INDICATED ON THE PLANS AND AT THE DIRECTION OF SITE SUPERINTENDENT TO ENSURE CONTAINMENT OF SEDIMENT. THE SEDIMENT FENCING WILL OUTLET OR OVERFLOW UNDER STABILISED CONDITIONS INTO THE SEDIMENT BASIN, TO SAFELY CONVEY WATER INTO A SUITABLE FILTERING SYSTEM SHOULD THE PORES IN THE FABRIC BLOCK.

SWM09

THE SEDIMENT BASINS WILL BE CONSTRUCTED WITH THE MINIMUM WET SEDIMENT CAPACITY OF CUM CUBIC METERS AND DESIGNED TO REMAIN STABLE IN AT LEAST THE 1 IN CDSE YEAR CRITICAL DURATION STORM EVENT. ARTIFICIAL FLOCCULATION OF THE FINER PARTICLES MAY NOT BE NECESSARY IN THIS INSTANCE.

## SWM10

STOCKPILES SHOULD NOT BE LOCATED WITHIN 5M OF TREES AND HAZARD AREAS, INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS, DRAINAGE LINES, PAVED AREAS AND DRIVEWAYS. WHERE THEY ARE WITHIN 5M FROM SUCH AREAS, SPECIAL SEDIMENT CONTROL MEASURES SHOULD BE TAKEN TO MINIMISE POSSIBLE POLLUTION TO DOWNSTREAM WATERS. MEASURE SHOULD ALSO BE APPLIED TO PREVENT THE EROSION OF THE STOCKPILE.

ALL CUT AND FILL BATTERS ARE TO BE SEEDED AND MULCHED WITHIN 14 DAYS OF COMPLETION OF FORMATION.

## SWM12

ANY EXISTING TREES WHICH FORM PART OF THE FINAL LANDSCAPING PLAN WILL BE PROTECTED FROM CONSTRUCTION ACTIVITIES BY -A. PROTECTING THEM WITH BARRIER FENCING OR SIMILAR MATERIALS INSTALLED OUTSIDE THE DRIP LINE, B. ENSURING THAT NOTHING IS NAILED TO THEM,

C. PROHIBITING PAVING GRADING SEDIMENT WASH OR PLACING OF STOCKPILES WITHIN THE DRIP LINE EXCEPT UNDER THE FOLLOWING CONDITIONS : 1. ENCROACHMENT ONLY OCCURS ON ONE SIDE AND NO CLOSER TO THE TRUNK THAN EITHER 1.5 METRES OR HALF THE DISTANCE BETWEEN THE OUTER EDGE OF THE DRIP LINE AND THE TRUNK, WHICH EVER IS THE GREATER, 2. A DRAINAGE SYSTEM THAT ALLOWS AIR AND WATER TO CIRCULATE THROUGH THE ROOT ZONE (E.G. A GRAVEL BED) IS PLACED UNDER ALL FILL LAYERS OF

- MORE THAN 300 MILLIMETRES DEPTH,
- 3. CARE IS TAKEN.

SWM13

KEPT MOIST (NOT WET) BY SPRINKLING WITH WATER TO KEEP DUST UNDER CONTROL

		SCALE BA	DC			
		SCALE DA	ко			
		1:20	0 0. <u>1 0.</u> 2	0.5	1	2
		1.20				
			0 0.25 0.5	1.25	2.5	5
		1:50				
		1:100	0 0.5 1	2.5	5	10
		1.100				
			0 1 2	5	10	20
		1:200				

А	ISSUED FOR D.A.	31.05.22	J.E.	K.E.
No.	Description	Date	Issued by	Checked by

# DURING WINDY WEATHER, LARGE DISTURBED UNPROTECTED AREAS SHOULD BE

CLIENT: ARCHITECT:

# **EROSION CONTROL NOTES**

- 1. ALL EROSION & SEDIMENT CONTROL MEASURES ARE TO BE INSTALLED AND MAINTAINED IN ACCORDANCE WITH 'MANAGING URBAN STORMWATER, 3RD EDITION' PRODUCED
- BY THE NSW DEPARTMENT OF HOUSING. 2. ALL EROSION AND SILTATION CONTROL DEVICES ARE TO BE PLACED PRIOR TO THE COMMENCEMENT OF ANY CONSTRUCTION AND REMOVED REGULARLY DURING
- CONSTRUCTION 3. ALL TREES ARE TO BE PRESERVED UNLESS INDICATED OTHERWISE ON THE ARCHITECT'S OR LANDSCAPE ARCHITECT'S DRAWINGS. EXISTING GRASS COVER SHALL BE MAINTAINED EXCEPT IN AREAS CLEARED FOR BUILDINGS, PAVEMENTS ETC- CONTRACTOR TO MINIMISE DISTURBED ARFAS
- 4. INSTALL TEMPORARY SEDIMENT BARRIERS TO ALL INLET PITS LIKELY TO COLLECT SILT LADDEN WATER
- 5. NOT WITHSTANDING DETAILS SHOWN, IT IS THE CONTRACTORS SOLE RESPONSIBILITY TO ENSURE THAT ALL SITE ACTIVITIES COMPLY WITH THE REQUIREMENTS OF THE CLEAN WATERS ACT.
- 6. ALL DISTURBED AREAS AND STOCKPILES TO BE STABILISED WITHIN 14 DAYS. ALL STOCKPILES TO BE CLEAR FROM DRAINS, GUTERS AND FOOTPATHS.
- 7. TOPSOIL TO BE STRIPPED, STOCKPILED AND RE-SPREAD ON COMPLETION OF EARTHWORKS. NONE TO BE REMOVED.
- 8. NO DISTURBANCE OF SITE PERMITTED OTHER THAN IMMEDIATE AREA OF THE WORKS.
- 9. DRAINAGE IS TO BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE. NON-COMPLIANCE MAY RESULT IN A \$1500 FINE

SWM14 TEMPORARY PROTECTION FROM EROSIVE FORCES WILL BE UNDERTAKEN ON LANDS WHERE FINAL SHAPING HAS NOT BEEN COMPLETED BUT WORKS ARE UNLIKELY TO PROCEED FOR PERIODS OF TWO MONTHS OR MORE (EG. ON TOP SOIL STOCKPILES). THIS MAY BE ACHIEVED WITH A VEGETATIVE COVER. A RECOMMENDED LISTING OF PLANT SPECIES FOR SOIL AND WATER MANAGEMENT NOTES:

**TEMPORARY COVER IS -**I) AUTUMN/WINTER SOWING -OATS/RYECORN AT 20KG/HA -JAPANESE MILLET AT 10KG/HA II) SPRING/SUMMER SOWING -JAPANESE MILLET AT 20KG/HA - OATS/RYECORN AT 10 KG/HA

## SWM15

DIVERSION BANKS/ CHANNELS WILL BE REHABILITATED AS SOON AS POSSIBLE AND WITHIN 5 WORKING DAYS FROM THEIR FINAL SHAPING. OTHER THAN IN THE WINTER MONTHS, SUITABLE MATERIALS'S INCLUDE TURF GRASSES SUCH S COUCH OR KIKUYU. DURING WINTER, OR AT OTHER TIMES WHEN TEMPORARY REHABILITATION (MORE THAN 3 MONTHS) IS REQUIRED. IT IS SUGGESTED THAT HESSIAN CLOTH IS USED BUT ONLY IF TACKED WITH APPROPRIATE PEGS AND AN ANIONIC BITUMEN EMULSION. FOOT AND VEHICULAR TRAFFIC SHOULD BE KEPT AWAY FROM THESE AREAS.

SWM16 UNDERTAKE SITE DEVELOPMENT WORKS IN ACCORDANCE WITH THE ENGINEERING PLANS. WHERE POSSIBLE, PHASE DEVELOPMENT SO THAT LAND DISTURBANCE IS CONFINED TO AREAS OF WORKABLE SIZE.

CONSTRUCTION SEQUENCE

### SWM1 WHERE PRACTICAL, THE SOIL EROSION HAZARD ON THE SITE SHOULD BE KEPT AS LOW AS POSSIBLE. TO THIS END, WORKS SHOULD BE UNDERTAKEN IN THE FOLLOWING SEQUENCE -

I) INSTALL INLET SEDIMENT TRAPS TO ALL GULLY PITS FRONTING THE SITE, II) INSTALL A 1.8M CHAIN WIRE FENCE AROUND THE BOUNDARIES AND ATTACH HESSIAN CLOTH OR SIMILAR TO IT ON THE WINDWARD SIDE (TIES AT THE TOP, CENTRE AND BOTTOM AND AT 1M INTERVALS OR AS INSTRUCTED BY THE SUPERINTENDENT).

III) INSTALL GEOFABRIC SEDIMENT FENCE AND SEDIMENT TRAPS AROUND ALL PERMANENT STORMWATER RETICULATION STRUCTURES AS SHOWN ON THE PLAN,

IV) CONSTRUCT STABILISED CONSTRUCTION ENTRANCE AS SHOWN ON THE PLAN OR TO LOCATION AS DETERMINED BY SUPERINTENDENT, V) INSTALL DIVERSION BANKS ALONG THE BOUNDARY WHERE REQUIRED, REHABILITATE DISTURBED LANDS DOWNSLOPE FROM THE BASINS WITHIN 20

WORKING DAYS, VI) ENSURE THAT THE SEDIMENT BASIN IS DIRECTED ONTO A TURFED AREA AND DRAINS TO A SUITABLE LOCATION. A TEMPORARY STORMWATER LINE MAY BE NECESSARY TO CONVEY THE FLOWS TO THIS LOCATION. CONSTRUCT DIVERSION CHANNELS AT THE BOUNDARY TO DRAIN INTO THE SEDIMENT BASIN

AS SHOWN ON PLANS VII) AT COMPLETION STABILISE SITE AND DECOMMISSION SEDIMENT BASIN AND ALL EROSION CONTROL DEVICES.

SWM18 TEMPORARY SOIL AND WATER MANAGEMENT STRUCTURES WILL BE REMOVED ONLY AFTER THE LANDS THEY ARE PROTECTING ARE REHABILITATED.

SWM19 FINAL SITE LANDSCAPING WILL BE UNDERTAKEN AS SOON AS POSSIBLE AND WITHIN 20 WORKING DAYS FROM COMPLETION OF CONSTRUCTION ACTIVITIES.

# SITE INSPECTION AND MAINTENANCE

**SWM 20** AT LEAST WEEKLY AND AFTER EVERY RAIN FALL EVENT, THE

CONTRACTOR WILL INSPECT THE SITE AND ENSURE THAT -I) DRAINS AND ALL SEDIMENT CONTROL DEVICES OPERATE EFFECTIVELY AND INITIATE REPAIR OR MAINTENANCE AS REQUIRED, II) RECEPTORS FOR CONCRETE AND MORTAR SLURRIES, PAINTS, ACID


WASHINGS, LIGHT-WIGHT WASTE MATERIALS AND LITTER ARE TO BE EMPTIED AS NECESSARY. DISPOSAL OF WASTE SHALL BE IN A MANOR APPROVED BY THE SUPERINTENDENT. III) SPILL SAND (OR OTHER MATERIALS) IS REMOVED FROM HAZARD AREAS,

INCLUDING LIKELY AREAS OF CONCENTRATED OR HIGH VELOCITY FLOWS SUCH AS WATERWAYS, GUTTERS, PAVED AREAS AND DRIVEWAYS, IV) SEDIMENT IS REMOVED FROM BASINS AND / OR TRAPS WHEN LESS

THAN 20M<sup>3</sup> OF TRAPPING CAPACITY REMAIN PER 1000M<sup>2</sup> OF DISTRIBUTED LANDS, AND OR LESS THAN 500 DEPTH REMAINS IN THE SETTLING ZONE. ANY COLLECTED SEDIMENT WILL BE DISPOSED IN AREAS WHERE FURTHER

POLLUTION TO DOWN SLOPE LANDS AND WATERWAYS IS UNLIKELY, V) REHABILITATED LANDS HAVE EFFECTIVELY REDUCED THE EROSION HAZARD AND INITIATE UPGRADING OR REPAIR AS APPROPRIATE.

SWM 21 THE CONTRACTOR SHALL PROVIDE ALL MONITORING CONTROL AND TESTING.





AUTHORISED:

K.E.


PROJECT START DATE:


MAY 2022















DESIGNED:

K.E.

DRAWN:

J.E.

WALSH ARCHITECTS

SUIT 2.04, L2, BLDG 3, 35 WATERLOO RD., MACQUARIE PARK, NSW, 2113 info@smartstructs.com.au | www.smartstructs.com.au