

10 December 2020

Tomasy Planning Pty Ltd , Birdwood Projects Pty Ltd PO Box 542 COLLAROY NSW 2097

Dear Sir/Madam

Application Number:DA2020/0432Address:Lot 1 DP 847020 , 9 - 11 Birdwood Avenue, COLLAROY NSW 2097Proposed Development:Construction of a Seniors Housing or Housing for Persons with a<br/>Disability and Strata Subdivision

Please find attached the Notice of Determination for the above mentioned Application.

Please be advised that a copy of the Assessment Report associated with the application is available on Council's website at www.northernbeaches.nsw.gov.au

Please read your Notice of Determination carefully and the assessment report in the first instance.

If you have any further questions regarding this matter please contact the undersigned on 1300 434 434 or via email quoting the application number, address and description of works to council@northernbeaches.nsw.gov.au

Regards,

Rodney Piggott Manager Development Assessments



# NOTICE OF DETERMINATION

Application Number:	DA2020/0432
Determination Type:	Development Application

# **APPLICATION DETAILS**

Applicant:	Tomasy Planning Pty Ltd Birdwood Projects Pty Ltd
	Lot 1 DP 847020 , 9 - 11 Birdwood Avenue COLLAROY NSW 2097
	Construction of a Seniors Housing or Housing for Persons with a Disability and Strata Subdivision

## **DETERMINATION - APPROVED**

Made on (Date)	09/12/2020
Consent to operate from (Date):	09/12/2020
Consent to lapse on (Date):	09/12/2025

# **Detail of Conditions**

The conditions, which have been applied to the consent, aim to ensure that the Environmental Impacts of Development are minimised and the Health and Safety of the community is maintained in accordance with the relevant standards and the Building Code of Australia.

# Note:

If the works are to be certified by a Private Certifying Authority, then it is the certifier's responsibility to ensure all outstanding fees and bonds have been paid to Council prior to the issue of the Construction Certificate or as otherwise specified by Consent conditions.



# DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

# 1. Approved Plans and Supporting Documentation

The development must be carried out in compliance (except as amended by any other condition of consent) with the following:

### a) Approved Plans

Architectural Plans - Endorsed with Council's stamp		
Drawing No.	Dated	Prepared By
DA.01	06.08.2020	edaa
DA.02	06.08.2020	edaa
DA.03	06.08.2020	edaa
DA.04	06.08.2020	edaa
DA.05	06.08.2020	edaa
DA.06	06.08.2020	edaa
DA.07	06.08.2020	edaa
DA.19	06.08.2020	edaa
DA.20	06.08.2020	edaa
Exterior Finishes/Palette	April 2020	

The Upper Ground Floor Plan and Roof Plan are to be in accordance with the following:

Architectural Plans - Endorsed with Council's stamp		
Drawing No.	Dated	Prepared By
SK.01	26.11.2020	edaa
SK.02	26.11.2020	edaa
SK.03	26.11.2020	edaa

Reports / Documentation – All recommendations and requirements contained within:		
Report No. / Page No. / Section No.	Dated	Prepared By
Operational Waste Management Plan	17 April 2020	Elephants Foot Recycling Solutions
Traffic and Parking Assessment Report	9 April 2020	Varga Traffic Planning Pty Ltd
Biodiversity Assessment	15 April 2020	Total Earth Care
BCA Compliance Capability Statement	8 April 2020	AED Group
Aboricultural Impact Assessment	April 2020	Tree Wise Men Australia Pty Ltd
Geotechnical Report into Acid Sulphate Soils	February 2020	Crozier Geotechnical Consultants
Geotechnical Report Site	October 2019	Crozier Geotechnical



		Consultants
Accessibility Design Review	6 April 2020	ABE Consulting

b) Any plans and / or documentation submitted to satisfy the Conditions of this consent.

c) The development is to be undertaken generally in accordance with the following:

Landscape Plans		
Drawing No.	Dated	Prepared By
LALP101/C	06.04.2020	Black Beetle
LALP102/C	06.04.2020	Black Beetle
LALP103/E	10.08.2020	Black Beetle
LALP104/C	10.08.2020	Black Beetle

Waste Management Plan		
Drawing No/Title.	Dated	Prepared By
DA.08	14 April 2020	edaa

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of Council and approved plans.

#### 2. Compliance with Other Department, Authority or Service Requirements

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department, Authority or Service	EDMS Reference	Dated
Ausgrid	Response Ausgrid Referral	25 May 2020
Transport for NSW	Response Transport for NSW	25 May 2020

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website <u>www.northernbeaches.nsw.gov.au</u>)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

#### 3. Approved Land Use

Nothing in this consent shall authorise the use of site/onsite structures/units/tenancies as detailed on the approved plans for any land use of the site beyond the definition of a *seniors housing means a building or place that is*—

(c) a group of self-contained dwellings,

and that is, or is intended to be, used permanently for-

(e) seniors or people who have a disability, or



- (f) people who live in the same household with seniors or people who have a disability, or
- (g) staff employed to assist in the administration of the building or place or in the provision of services to persons living in the building or place,

but does not include a hospital.

(development is defined by the Warringah Local Environment Plan 2011 (as amended) Dictionary)

Any variation to the approved land use and/occupancy of any unit beyond the scope of the above definition will require the submission to Council of a new development application.

Reason: To ensure compliance with the terms of this consent.

# 4. **Prescribed Conditions**

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
  - (i) showing the name, address and telephone number of the Principal Certifying Authority for the work, and
  - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
  - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.

- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
  - (i) in the case of work for which a principal contractor is required to be appointed:
    - A. the name and licence number of the principal contractor, and
    - B. the name of the insurer by which the work is insured under Part 6 of that Act,
  - (ii) in the case of work to be done by an owner-builder:
    - A. the name of the owner-builder, and
    - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.



- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
  - (i) protect and support the adjoining premises from possible damage from the excavation, and
  - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
  - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
  - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

### 5. General Requirements

 (a) Unless authorised by Council: Building construction and delivery of material hours are restricted to:

- 7.00 am to 5.00 pm inclusive Monday to Friday,
- 8.00 am to 1.00 pm inclusive on Saturday,
- No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

• 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (c) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of a final Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (d) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (e) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.



- (f) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (g) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (h) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (i) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (j) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (k) Prior to the commencement of any development onsite for:
  - i) Building/s that are to be erected
  - ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
  - iii) Building/s that are to be demolished
  - iv) For any work/s that is to be carried out
  - v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

- (I) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.
- (m) The works must comply with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice.
- (n) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.
  - (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

- (i) Swimming Pools Act 1992
- (ii) Swimming Pools Amendment Act 2009
- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety



- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
- (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
- (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
- (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

# FEES / CHARGES / CONTRIBUTIONS

# 6. Policy Controls

Northern Beaches 7.12 Contributions Plan 2019

A monetary contribution of \$81,150.00 is payable to Northern Beaches Council for the provision of local infrastructure and services pursuant to section 7.12 of the Environmental Planning & Assessment Act 1979 and the Northern Beaches Section 7.12 Contributions Plan 2019. The monetary contribution is based on a development cost of \$8,115,000.00.

The monetary contribution is to be paid prior to the issue of the first Construction Certificate or Subdivision Certificate whichever occurs first, or prior to the issue of the Subdivision Certificate where no Construction Certificate is required. If the monetary contribution (total or in part) remains unpaid after the financial quarter that the development consent is issued, the amount unpaid (whether it be the full cash contribution or part thereof) will be adjusted on a quarterly basis in accordance with the applicable Consumer Price Index. If this situation applies, the cash contribution payable for this development will be the total unpaid monetary contribution as adjusted.

The proponent shall provide to the Certifying Authority written evidence (receipt/s) from Council that the total monetary contribution has been paid.

The Northern Beaches Section 7.12 Contributions Plan 2019 may be inspected at 725 Pittwater Rd, Dee Why and at Council's Customer Service Centres or alternatively, on Council's website at www.northernbeaches.nsw.gov.au

This fee must be paid prior to the issue of the Construction Certificate. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To provide for contributions in accordance with the Contribution Plan to fund the provision of new or augmented local infrastructure and services.

#### 7. Security Bond



A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security are required to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, and details demonstrating payment are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at www.northernbeaches.nsw.gov.au).

Reason: To ensure adequate protection of Council's infrastructure.

 Construction, Excavation and Associated Works Security Bond (Road works) The applicant is to lodge a bond with Council of \$10 000 as security against any damage or failure to complete the construction of road pavement/shoulder reconstruction works as part of this consent.

Details confirming payment of the bond are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

# 9. Construction, Excavation and Associated Works Bond (Drainage works Birdwood Avenue)

The applicant is to lodge a bond of \$20,000 as security against any damage or failure to complete the construction of a inlet pit and 375mm RCP stormwater drainage line in Birdwood Place works as part of this consent ,

Details confirming payment of the bond are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

10. Construction, Excavation and Associated Works Bond (Maintenance for civil works)

The developer/applicant must lodge with Council a maintenance bond of \$5 000 for the construction of stormwater drainage works and footpath in the road reserve. The maintenance bond will only be refunded upon completion of the six month maintenance period, if work has been completed in accordance with the approved plans and to the satisfaction of Council. The maintenance bond is to be paid prior to Council issuing practical completion.

Reason: To ensure adequate protection of Council infrastructure.

# CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

# 11. On slab landscape planting and associated works

DA2020/0432



- a) Details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate indicating the proposed method of waterproofing to all internal walls and slab, and drainage of the concrete slab over which soil and planting is being provided.
- b) Landscape treatment details shall be submitted to the Certifying Authority prior to the issue of the Construction Certificate indicating the proposed soil volume, soil type, planting, automatic irrigation, services connections, and maintenance activity schedule.

c) The following soil depths are required in order to be counted as landscaping:

-300mm for lawn

-600mm for shrubs

-1metre for trees

Reason: To ensure appropriate and secure waterproofing and drainage is installed to direct water flow into the drainage system, and away from habitable areas.

# 12. Traffic Management and Control

The Applicant is to submit an application for Traffic Management Plan to Council for approval prior to issue of the Construction Certificate. The Traffic Management Plan shall be prepared to RMS standards by an appropriately certified person.

Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process.

#### 13. Amendments to the approved plans

The following amendments are to be made to the approved plans:

- Maximum fill of the rear ground level (rear boundary setback) of no more than RL10.88 this includes any retaining structures/walls (maximum RL10.88);
- Swimming pool finished coping level (maximum of RL11.1);
- Upper Roof RL15.08
- Lower Roof RL14.23
- Upper Ground Floor RL11.18

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the construction certificate.

Reason: To ensure development minimises unreasonable impacts upon surrounding land and compliance SEPP (HSPD) 2004.

# 14. Boundary Identification Survey

A boundary identification survey, prepared by a Registered Surveyor, is to be prepared in respect of the subject site.

The plans submitted for the Construction Certificate are to accurately reflect the property boundaries as shown on the boundary identification survey, with setbacks between the property boundaries and the approved works consistent with those nominated on the Approved Plans of this consent.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of any Construction Certificate.

Reason: To ensure all approved works are constructed within the subject site and in a manner anticipated by the development consent.



# 15. Stormwater Disposal Details

The Applicant is to provide a certification of drainage plans detailing the provision of on-site stormwater detention in accordance with Northern Beaches Council's WARRINGAH WATER MANAGEMENT POLICY PL850" and generally in accordance with the concept drainage plans prepared by Henry & HymasPty Ltd, drawing number

19685\_DA\_C000,19685\_DA\_C100, 19685\_DA\_C101, 19685\_DA\_C200, dated 24/03/2020. Detailed drainage plans are to be prepared by a suitably qualified Civil Engineer, who has membership to the Institution of Engineers Australia, National Professional Engineers Register (NPER) and registered in the General Area of Practice for civil engineering.

The drainage plans must address the following:

i. Site stormwater to be connected to proposed kerb inlet pit in front of the subject site in Birdwood Avenue.

ii. Subsurface flows are to be adequately collected and connected to Council's piped drainage system in Birdwood Avenue.

iii. Detailed drainage plans, including engineering certification, are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater and stormwater management arising from the development.

### 16. Submission Roads Act Application for Civil Works in the Public Road

The Applicant is to submit an application for Council approval for infrastructure works within Birdwood Avenue road reserve. Engineering plans for the new development works within the road reserve and this development consent are to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

The application is to include four (4) copies of Civil Engineering plans for the design of driveway crossing, footpath, reinstatement of exiting driveway crossing which are to be generally in accordance with the Council's specification for engineering works - AUS-SPEC #1. The plan shall be prepared by a qualified civil engineer. The design must include the following information:

- 1. 5.5 metre wide driveway crossing in accordance with Northern Beaches Council Drawing No. A4-3330/1N.
- 2. Reinstatement of all old driveway crossings to kerb and gutter, footpath and grass verge.
- 3. 1.5 metre concrete footpath along the entire frontage site. The footpath to extend from Pittwater Road up to the eastern boundary.Footpath to be located along the back of the kerb to allow for alignment with existing ground levels. Footpath alignment to be altered where required to avoid existing power poles.
- The footpath levels are to match the existing levels along the boundary of the site and adjoining property.
- 5. 1.2 metre lintel and grate kerb inlet pit in front of the subject site with a Ø 375mm RRJ RCP extension to the existing council pit downstream.

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

The Council approval is to be submitted to the Certifying Authority prior to the issue of the Construction Certificate



Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification.

# 17. Structural Adequacy and Excavation Work

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required. All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer, except where site conditions permit the following:

(a) maximum height of 900mm above or below ground level and at least 900mm from any property boundary, and

(b) Comply with AS3700, AS3600 and AS1170 and timber walls with AS1720 and AS1170.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To provide public and private safety.

### 18. Sub-Soil Seepage

The Applicant is to submit plans demonstrating that all sub-soil seepage drainage is discharged via a suitable silt arrester pit, directly to Council's nearest stormwater drainage line being the proposed kerb inlet pit in Birdwood Avenue and is to be carried out in accordance with relevant Australian Standards. (Note: At the time of determination the following (but not limited to) Standards applied:

- Australian/New Zealand Standard AS/NZS 3500.3 2003 Plumbing and drainage -Stormwater drainage
- Australian/New Zealand Standard AS/NZS 3500.3 2003 / Amdt 1 2006 Plumbing and drainage - Stormwater drainage.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure appropriate drainage and Stormwater management on site to protect amenity of residents.

# 19. Landscaping

50% of plants used in the landscaping for this development must be local native species as listed on Council's Native Plant Species Guide –

Narrabeen Ward. Five small-medium trees to replace the removed trees is also required.No Grevillea or Banksia hybrids are to be used in the landscaping for this development. Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Biodiversity conservation and management

# 20. **Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.



(Note: At the time of determination the following (but not limited to) Australian Standards applied:

(a) AS2601.2001 - Demolition of Structures\*\*

(b) AS4361.2 - Guide to lead paint management - Residential and commercial buildings\*\*

(c) AS4282:1997 Control of the Obtrusive Effects of Outdoor Lighting\*\*

(d) AS 4373 - 2007 'Pruning of amenity trees' (Note: if approval is granted) \*\*

(e) AS 4970 - 2009 'Protection of trees on development sites'\*\*

(f) AS/NZS 2890.1:2004 Parking facilities - Off-street car parking\*\*

(g) AS 2890.2 - 2002 Parking facilities - Off-street commercial vehicle facilities\*\*

(h) AS 2890.3 - 1993 Parking facilities - Bicycle parking facilities\*\*

(i) AS 2890.5 - 1993 Parking facilities - On-street parking\*\*

(j) AS/NZS 2890.6 - 2009 Parking facilities - Off-street parking for people with disabilities\*\*

(k) AS 1742 Set - 2010 Manual of uniform traffic control devices Set\*\*

(I) AS 1428.1 – 2009\* Design for access and mobility - General requirements for access – New building work\*\*

(m) AS 1428.2 – 1992\*, Design for access and mobility - Enhanced and additional requirements - Buildings and facilities\*\*

\*Note: The Australian Human Rights Commission provides useful information and a guide relating to building accessibility entitled "the good the bad and the ugly: Design and construction for access". This information is available on the Australian Human Rights Commission website www.hreoc.gov.au/disability rights /buildings/good.htm. <www.hreoc.gov.au/disability% 20rights%20/buildings/good.htm.>

\*\*Note: the listed Australian Standards is not exhaustive and it is the responsibility of the applicant and the Certifying Authority to ensure compliance with this condition and that the relevant Australian Standards are adhered to.)

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate. Reason: To ensure the development is constructed in accordance with appropriate standards. (DACPLC02)

# 21. External Finishes to Roof

The external finish to the roof shall have a medium to dark range in order to minimise solar reflections to neighbouring properties. Any roof with a metallic steel finish is not permitted.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure that excessive glare or reflectivity nuisance does not occur as a result of the development.

# 22. Sydney Water "Tap In"

The approved plans must be submitted to the Sydney Water Tap in service, prior to works commencing, to determine whether the development will affect any Sydney Water assets and/or easements. The appropriately stamped plans must then be submitted to the Certifying Authority demonstrating the works are in compliance with Sydney Water requirements.

Please refer to the website www.sydneywater.com.au for:



- "Tap in" details see http://www.sydneywater.com.au/tapin
- o Guidelines for Building Over/Adjacent to Sydney Water Assets.

Or telephone 13 000 TAP IN (1300 082 746).

Reason: To ensure compliance with the statutory requirements of Sydney Water.

### 23. **Requirements for Seniors Housing or Housing for Persons with a Disability**

The development is for the purposes of Seniors Housing or Housing for Persons with a Disability and is required to comply with all the standards specified in <u>Schedule 3</u> - "*Standards concerning accessibility and useability for hostels and self-contained dwellings*".

Details demonstrating compliance with the above requirement are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure public safety and equitable access for seniors or people with a disability. (DACPLC16)

### 24. Footpath Design

The applicant is to prepare civil drawings demonstrating construction of a footpath for the full length of the frontage site and linking up to the existing footpath on Pittwater Road.

The footpath design is to be constructed at a width 1.5m against the back of kerb (where possible).

This requirement is to be reflected on the Construction Certificate plans and any supporting documentation for the endorsement of the Certifying Authority prior to the release of the Construction Certificate.

Reason: To ensure the Quality of Access for the residents of the proposed development is provided in accordance with relevant standards (DACTRADC1)

#### 25. Mechanical Plant Location

Any mechanical plant associated with the dwelling house is to be located and/or acoustically treated so the noise from the machinery does not exceed 5dB(A) above the background ambient noise levels when measured at the nearest property boundary.

Details demonstrating compliance with this condition are to be submitted to the satisfaction of the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the acoustic amenity of the neighbouring residents.

## 26. Accessibility pathway/access gradients

Details of the accessibility pathway/access gradients demonstrating compliance with Clause 26 (2) Location and Access to Facilities of State Environmental Planning Policy (Housing for Seniors or People with a Disability) 2004 are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Ensure compliance with State Environmental Planning Policy (Housing for Seniors or People with a Disability) 2004



# 27. Vehicle Access & Parking

All internal driveways, vehicle turning areas, garages and vehicle parking space/ loading bay dimensions must be designed and constructed to comply with the relevant section of AS 2890 (Off-street Parking standards). Where disabled parking spaces are provided they must be in accordance with AS2890.6:2009

With respect to this, the following revision(s) must be undertaken;

All internal driveways and vehicle access ramps must have ramp grades and transitions complying with AS 2890.1. To ensure the gradient requirements and height clearances are satisfied, a driveway profile must be prepared for all internal ramps showing ramp lengths, grades, surface RL's and overhead clearances, taken from the crest of the ramp to the base. Plans prepared by a suitably qualified Engineer shall be submitted to the accredited certifier prior to the issue of a Construction Certificate.

Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicles. (DACTRCPCC1)

# 28. Visitor parking spaces located behind roller door

The installation of any security roller shutter for parking areas shall not restrict access to any designated visitor car parking space. In the event that the approved visitor car parking spaces are located behind any proposed security roller shutter, an intercom system is required to be installed to enable visitor access into the basement car parking area. This requirement is to be reflected on the Construction Certificate plans and any supporting documentation for the endorsement of the Certifying Authority prior to the release of the Construction Certificate.

Reason: To ensure visitor car parking is accessible to visitors. (DACTRCPCC2)

#### 29. Waste and Recycling Requirements

Details demonstrating compliance with Northern Beaches Development Control Plan – Part C9 Waste Management, including the required Northern Beaches Waste Management Plan, are to be submitted to and approved by the Certifying Authority prior to the issue of any Construction Certificate.

Note: If the proposal, when compliant with Northern Beaches Development Control Plan – Part C9 Waste Management, causes inconsistencies with other parts of the approval i.e. architectural or landscaped plans a modification(s) to the development may be required.

Reason: To ensure adequate and appropriate waste and recycling facilities are provided. (DACWTC01)

# 30. Waste Management Plan

A Waste Management Plan must be prepared for this development. The Plan must be in accordance with the Development Control Plan.

Details demonstrating compliance must be provided to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure that any demolition and construction waste, including excavated material, is



reused, recycled or disposed of in an environmentally friendly manner.

# CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

### 31. **Pre-Construction Dilapidation Report**

Dilapidation reports, including photographic surveys, of the following adjoining properties must be provided to the Principal Certifying Authority prior to any works commencing on the site (including demolition or excavation). The reports must detail the physical condition of those properties listed below, both internally and externally, including walls, ceilings, roof, structural members and other similar items.

Property / Properties:

- 7 Birdwood Avenue, Collaroy
- o 15 17 Birdwood Avenue, Collaroy
- o 7 Brissenden Avenue, Collaroy
- o 9 Brissenden Avenue, Collaroy
- 11 Brissenden Avenue, Collaroy

The dilapidation report is to be prepared by a suitably qualified person. A copy of the report must be provided to Council, the Principal Certifying Authority and the owners of the affected properties prior to any works commencing.

In the event that access for undertaking the dilapidation report is denied by an adjoining owner, the applicant must demonstrate, in writing that all reasonable steps have been taken to obtain access. The Principal Certifying Authority must be satisfied that the requirements of this condition have been met prior to commencement of any works.

Note: This documentation is for record keeping purposes and may be used by an applicant or affected property owner to assist in any action required to resolve any civil dispute over damage rising from the works.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the commencement of any works on site.

Reason: To maintain proper records in relation to the proposed development.

# 32. Public Liability Insurance - Works on Public Land

Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of, and approved works within Council's road reserve or public land, as approved in this consent. The Policy is to note, and provide protection for Northern Beaches Council, as an interested party and a copy of the Policy must be submitted to Council prior to commencement of the works. The Policy must be valid for the entire period that the works are being undertaken on public land.

Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land.

#### 33. **Tree trunk, branch and root protection**

(a)Existing trees which must be retained

i) All trees not indicated for removal in the Arboricultural Impact Assessment dated April 2020 prepared by Tree Wise Men

ii) Trees located on adjoining private land



# (b) Tree protection

i) No tree roots greater than 25mm diameter are to be cut from protected trees unless authorised by the Project Arborist on site.

ii) All structures are to bridge tree roots greater than 25mm diameter unless directed otherwise by the Project Arborist on site.

iii) All tree protection to be in accordance with the Arboricultural Impact Assessment dated April 2020 prepared by Tree Wise Men and AS4070-2009 Protection of trees on development sites, with particular reference to Section 4 Tree Protection Measures.

iv) All tree pruning within the subject site is to be in accordance with WDCP2011 Clause

E1 Private Property Tree Management and AS 4373 Pruning of amenity trees v) All tree protection measures, including fencing, are to be in place prior to commencement of works.

Reason: To ensure compliance with the requirement to retain and protect significant planting on the site.

# 34. **Project Arborist**

i) A Project Arborist with minimum qualification AQF Level 5 is to be appointed prior to commencement of works.

ii) The Project Arborist is to oversee all tree protection measures, removals and works adjacent to protected trees as outlined in the Arboricultural Impact Assessment dated April 2020 prepared by Tree Wise Men and AS4970-2009 Protection of trees on development sites.
iii) The Project Arborist is to ensure compliance as relevant with any other environmental requirements conditioned under this consent.

Reason: to ensure protection of vegetation proposed for retention on the site.

# 35. Installation and Maintenance of Sediment and Erosion Control

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004). Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site

# 36. **Demolition and Construction Traffic Management Plan**

Because of limited vehicle access, high pedestrian activity and parking demand, a Demolition Traffic Management Plan (DTMP) and Construction Traffic Management Plan (CTMP) shall be prepared by an RMS accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to commence any work.

The report must address following:-

• The proposed phases of demolition and construction works on the site, and the expected duration of each phase;

• The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken;

• Make provision for all construction materials to be stored on site, at all times;



• The proposed areas within the site to be used for the storage of excavated materials, construction materials and waste containers during the construction period;

• The proposed method of access to and egress from the site for construction vehicles, including access routes and truck rates through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed;

• The proposed method of loading and unloading excavation and construction machinery, excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site;

• Make provision for parking onsite for all Staff and Contractors.

• Temporary truck standing/ queuing locations in a public roadway / domain near the site are not permitted unless approved by Council prior.

• Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian traffic.

• The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure.

• Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees.

 Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the DTMP and CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site.

• The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site;

• Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council.

• The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent;

• Proposed protection for Council and adjoining properties;

• The location and operation of any on site crane; and

The DTMP & CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – "Manual of Uniform Traffic Control Devices", RMS' Manual – "Traffic Control at Work Sites".

All fees and charges associated with the review of this plan is to be in accordance with Council's Schedule of Fees and Charges and are to be paid at the time that the Demolition and Construction Traffic Management Plan are submitted.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. Confirming appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process in a manner that respects adjoining owner's property rights and protects amenity in the locality, without unreasonable inconvenience to the community. The DTMP and CTMP are intended to



minimise impact of construction activities on the surrounding community, in terms of vehicle traffic (including traffic flow and parking) and pedestrian amenity adjacent to the site. (DACTRDPC1)

# 37. Work Zones and Permits

Prior to commencement of the associated works, the applicant shall obtain a Work Zone Permit where it is proposed to reserve an area of road pavement for the parking of vehicles associated with a construction site. Separate application is required with a Traffic Management Plan for standing of construction vehicles in a trafficable lane.

Reason: To ensure Work zones and Permits are managed and monitored. (DACTRDPC2)

# CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

### 38. Road Reserve

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public safety.

#### 39. Survey Certificate

A survey certificate prepared by a Registered Surveyor at the following stages of construction:

(a) Commencement of perimeter walls columns and or other structural elements to ensure the wall or structure, to boundary setbacks are in accordance with the approved details.

(b) At ground level to ensure the finished floor levels are in accordance with the approved levels, prior to concrete slab being poured/flooring being laid.

(c) At completion of the roof frame confirming the finished roof/ridge height is in accordance with levels indicated on the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To determine the height of buildings under construction comply with levels shown on approved plans.

#### 40. Installation and Maintenance of Sediment Control

Prior to any works commencing on site, including demolition, sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004). Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site.

#### 41. Progress Certification (Road & Subdivision)

The applicant shall provide written certification is to be provided by a suitably qualified engineer upon completion and/or as and when requested by the Roads Authority for the following stages of works:



- (a) Silt and sediment control facilities
- (b) Laying of stormwater pipes and construction of pits

(\*\*To be tested by a recognised N.A.T.A. approved laboratory).

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure compliance of civil works with Council's specification for engineering works.

#### 42. Civil Works Supervision

The Applicant shall ensure all civil works approved in the Section 138 approval are supervised by an appropriately qualified and practising Civil Engineer.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority and/or Roads Authority.

Reason: To ensure compliance of civil works with Council's specification for engineering works.

### 43. Footpath Construction

The applicant shall construct 1.5 metre concrete footpath along the Birdwood Avenue frontage from Pittwater Road up to the eastern boundary. The works shall be in accordance with the following:

(a) All footpath works are to be constructed in accordance with Section 138 Road Act approval (b) Council is to inspect the formwork prior to pouring of concrete to ensure the works are in accordance with Section 138 Road Act approval for footpath. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure compliance of footpath works with Council's specification for engineering works.

#### 44. Notification of Inspections

Council's Development Engineer is to be given 48 hours notice when the works reach the following stages:

- (a) Installation of Silt and Sediment control devices
- (b) Prior to backfilling of pipelines
- (c) Prior to pouring of stormwater gully pits
- (d) Prior to pouring of kerb and gutter, driveway crossing
- (e) Subgrade level / basecourse level / subbase
- (f) Sealing road pavement

NOTE: Any inspections carried out by Council do not imply Council approval or acceptance of the work, and do not relieve the developer/applicant from the requirement to provide an engineer's certification.

Reason: To ensure new Council infrastructure is constructed in accordance with Auspec 1 Council's design and specification standards.

# 45. Traffic Control During Road Works

Lighting, fencing, traffic control and advanced warning signs shall be provided for the protection of the works and for the safety and convenience of the public and others in accordance with RMS Traffic Control At Work Sites Manual (http://www.rms.nsw.gov.au/business-



industry/partners-suppliers/documents/technical-manuals/tcws-version-4/tcwsv4i2.pdf) and to the satisfaction of the Roads Authority. Traffic movement in both directions on public roads, and vehicular access to private properties is to be maintained at all times during the works

Reason: Public Safety.

### 46. Vehicle Crossings

The Applicant is to construct one vehicle crossing 5.5 metres wide in accordance with Northern Beaches Council Drawing No A4-3330/ Normal and the driveway levels application approval. An Authorised Vehicle Crossing Contractor shall construct the vehicle crossing and associated works within the road reserve in plain concrete. All redundant laybacks and crossings are to be restored to footpath/grass. Prior to the pouring of concrete, the vehicle crossing is to be inspected by Council and a satisfactory "Vehicle Crossing Inspection" card issued.

A copy of the vehicle crossing inspection form is to be submitted to the Principal Certifying Authority.

Reason: To facilitate suitable vehicular access to private property.

### 47. Waste Management During Development

The reuse, recycling or disposal of waste during works must be done generally in accordance with the Waste Management Plan for this development.

Details demonstrating compliance must be submitted to the Principal Certifying Authority.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

# 48. Requirement to notify about new Acid Sulfate Soils evidence

Requirement to notify about new Acid Sulfate Soils evidence

Any new information revealed during excavation works that has the potential to alter previous conclusions about Acid Sulfate Soils shall be immediately notified to the Council and the Principal Certifying Authority prior to further commencement.

Reason: To protect the environment and private & public infrastructure

#### 49. Dewatering (if required)

Any water being discharged from the site to stormwater must not cause pollution as defined by the Protection of the Environment Operations act 1997 and must comply with NSW water quality guidelines.

During the development works any waters discharged from the premises into Council's stormwater system (eg excavation waters and storm waters following rain events) shall only occur subject to the submission and Council's written approval of a separate Dewatering application including a site specific Dewatering Mangement Plan.

Water must be discharged in a manner that does not cause public health and/or safety nuisances.

Reason: Environmental Protection



## 50. **Protection of sites of significance**

Should any Aboriginal sites be uncovered during the carrying out of works, those works are to cease and Council, the NSW Office of Environment and Heritage (OEH) and the Metropolitan Local Aboriginal Land Council are to be contacted.

Reason: Preservation of significant environmental features.

### 51. Installation and Maintenance of Sediment Control

Measures used for erosion and sediment control on building sites are to be adequately maintained at all times and must be installed in accordance with Council's Specifications for Erosion and Sediment Control. All measures shall remain in proper operation until all development activities have been completed and the site fully stabilised.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To protect the environment from the effects of sedimentation and erosion from development sites.

### 52. Implementation of Demolition Traffic Management Plan

All works and demolition activities are to be undertaken in accordance with the approved Demolition Traffic Management Plan (DTMP). All controls in the DTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate RMS accreditation. Should the implementation or effectiveness of the DTMP be impacted by surrounding major development not encompassed in the approved DTMP, the DTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved DTMP is to be kept onsite at all times and made available to the accredited certifier or Council on request.

Reason: To ensure compliance and Council's ability to modify the approved Construction Traffic Management Plan where it is deemed unsuitable during the course of the project. (DACTREDW1)

#### 53. Implementation of Construction Traffic Management Plan

All works and construction activities are to be undertaken in accordance with the approved Construction Traffic Management Plan (CTMP). All controls in the CTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate RMS accreditation. Should the implementation or effectiveness of the CTMP be impacted by surrounding major development not encompassed in the approved CTMP, the CTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved CTMP is to be kept onsite at all times and made available to Council on request.

Reason: To ensure compliance of the developer/builder in adhering to the Construction Traffic Management procedures agreed and are held liable to the conditions of consent. (DACTREDW2)

#### 54. Waste/Recycling Requirements (Waste Plan Submitted)

During demolition and/or construction the proposal/works shall be generally consistent with the submitted Waste Management Plan dated 6 April 2020.

Reason: To ensure waste is minimised and adequate and appropriate waste and recycling



facilities are provided. (DACWTE01)

# 55. Waste/Recycling Requirements (Materials)

During demolition and/or construction the following materials are to be separated for recycling – timber – bricks – tiles – plasterboard – metal – concrete, and evidence of disposal for recycling is to be retained on site.

Reason: To ensure waste is minimised and recovered for recycling where possible. (DACWTE02)

# CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

# 56. Landscape completion

Landscaping is to be implemented in accordance with the Landscape Plan LALP101, LALP102, LALP103, and LALP104, all issue C, prepared by Black Beetle Landscape Architecture, inclusive of the following conditions:

i) All tree and palm planting within the rear southern setback shall be deleted,

ii) Planting along the rear southern boundary shall be maintained at 2.5 metre maximum height above ground, and

iii) All Rhaphiolepis species proposed are to be deleted and replaced with a non self-seeding species of similar form and height.

Prior to the issue of an Occupation Certificate, a landscape report prepared by a landscape architect or landscape designer shall be submitted to the Certifying Authority, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: To maintain environmental amenity

#### 57. Condition of retained vegetation

Prior to the issue of an Occupation Certificate a report prepared by the Project Arborist shall be submitted to the Certifying Authority, assessing the health and impact of trees and vegetation required to be retained as a result of the proposed development, including the following information:

- a) Compliance to Arborist recommendations for tree protection and excavation works.
- b) Extent of damage sustained by vegetation as a result of the construction works.
- c) Any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: To ensure compliance with the requirement to retain and protect significant planting on development sites.

#### 58. Stormwater Disposal

The stormwater drainage works shall be certified as compliant with this consent, all relevant Australian Standards and Codes and Councils water management Policy by a suitably qualified civil engineer. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.



Reason: To ensure appropriate provision for the disposal of stormwater arising from the development.

# 59. **Post-Construction Dilapidation Report**

Post-Construction Dilapidation Reports, including photos of any damage evident at the time of inspection, must be submitted after the completion of works. The report must:

- Compare the post-construction report with the pre-construction report,
- Clearly identify any recent damage and whether or not it is likely to be the result of the development works,
- Should any damage have occurred, suggested remediation methods.

Copies of the reports must be given to the property owners referred to in the Pre-Construction Dilapidation Report Condition. Copies must also be lodged with Council.

Details demonstrating compliance with this condition are to be submitted to the Principal Certifying Authority prior to the issuing of any Occupation Certificate.

Reason: To maintain proper records in relation to the proposed development.

#### 60. Occupation of Seniors Housing or Housing for Persons with a Disability

A positive covenant pursuant to s88E of the Conveyancing Act 1919 is to be registered on the title of the land to which this development consent applies.

The covenant shall stipulate that Council is the sole authority to release or modify the covenant and that the development is only permitted to be occupied by persons detailed as follows:

(a) seniors or people who have a disability;

(b) people who live within the same household with seniors or people who have a disability;

(c) staff employed to assist in the administration of and provision of services to housing provided under this Policy.

(Note: Under State Environmental Planning Policy (Housing for Seniors or People with a Disability) 2004):

Seniors are people aged 55 or more years, people who are resident at a facility at which residential care (within the meaning of the Aged Care Act 1997 http://www.comlaw.gov.au/ of the Commonwealth) is provided and / or people who have been assessed as being eligible to occupy housing for aged persons provided by a social housing provider.

#### AND

People with a disability are people of any age who have, either permanently or for an extended period, one or more impairments, limitations or activity restrictions that substantially affect their capacity to participate in everyday life.)

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue any Interim / Final Occupation Certificate.

Reason: Statutory requirements. (DACPLB11)

# 61. Landscaping - swimming pools



Deleted

#### 62. **Reinstatement of Kerb**

The Applicant shall reinstate all redundant laybacks and vehicular crossings to conventional kerb and gutter, footpath or grassed verge as appropriate with all costs borne by the applicant.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the final Occupation Certificate.

Reason: To facilitate the preservation of on street parking spaces.

#### 63. **Post-Construction Dilapidation Report (Major Development)**

The applicant must bear the cost of all restoration works to Council's road, footpath and drainage assets damaged during the course of this development.

A Post Construction Dilapidation Report after the completion of all building works is to demonstrate that there is no damage to Council infrastructure prior to the refund of any security deposits.

Reason: To ensure security against possible damage to Council property.

#### 64. Certification of Civil Works and Works as Executed Data on Council Land

The Applicant shall submit a suitably qualified Civil Engineer's certification that the completed works have been constructed in accordance with this consent and the approved Section 138 plans. Works as Executed data certified by a registered surveyor prepared in accordance with Council's 'Guideline for preparing Works as Executed data (details overdrawn on a copy of the approved civil plans) for Council Assets' in an approved format shall be submitted to Council for approval prior to the release of any security deposits.

Reason: To ensure compliance of works with Council's specification for engineering works.

#### **Required Planting** 65.

Deleted

#### 66. Removal of All Temporary Structures/Material and Construction Rubbish

Once construction has been completed all silt and sediment fences, silt, rubbish, building debris, straw bales and temporary fences are to be removed from the site.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure bushland management. (DACPLF01)

#### 67. Garbage and Recycling Facilities

All internal walls of the storage area shall be rendered to a smooth surface, coved at the floor/wall intersection, graded and appropriately drained to the sewer with a tap in close proximity to facilitate cleaning.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.



Reason: To prevent pollution of the environment and to protect the amenity of the area. (DACPLF03)

### 68. House / Building Number

House/building number is to be affixed to the building to be readily visible from the public domain.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: Proper identification of buildings.

69. **Unit Numbering for Multi Unit Developments (Residential, Commercial and Industrial)** The units within the development are to be numbered in accordance with the Australia Post Address Guidelines

(https://auspost.com.au/content/dam/auspost\_corp/media/documents/Appendix-01.pdf).

In this regard, the numbering is to be as per the Unit Numbering for Multi Unit Development Table available on Council's website Unit Numbering for Multi-Unit Developments Form

External directional signage is to be erected on site at driveway entry points and on buildings and is to reflect the numbering in the table provided. Unit numbering signage is also required on stairway access doors and lobby entry doors.

It is essential that all signage throughout the complex is clear to assist emergency service providers in locating a destination within the development with ease and speed, in the event of an emergency.

Details are to be submitted with any Interim/Final Occupation Certificate or Strata Subdivision Certificate certifying that the numbering has been implemented in accordance with this condition and the Unit Numbering for Multi Unit Development Table.

Reason: To ensure consistent numbering for emergency services access.

#### 70. Waste Management Confirmation

Prior to the issue of a Final Occupation Certificate, evidence / documentation must be submitted to the Principal Certifying Authority that all waste material from the development site arising from demolition and/or construction works has been appropriately recycled, reused or disposed of generally in accordance with the approved Waste Management Plan.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

#### 71. Sydney Water

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Co-ordinator. Please refer to the Building Developing and Plumbing section of the web site www.sydneywater.com.au <<u>http://www.sydneywater.com.au</u>> then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Co-ordinator, since building



of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure compliance with the statutory requirements of Sydney Water.

# 72. Swimming Pool Requirements

The Swimming Pool shall not be filled with water nor be permitted to retain water until:

(a) All required safety fencing has been erected in accordance with and all other requirements have been fulfilled with regard to the relevant legislative requirements and relevant Australian Standards (including but not limited) to:

(i) Swimming Pools Act 1992;

- (ii) Swimming Pools Amendment Act 2009;
- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools

(b) A certificate of compliance prepared by the manufacturer of the pool safety fencing, shall be submitted to the Principal Certifying Authority, certifying compliance with Australian Standard 1926.

(c) Filter backwash waters shall be discharged to the Sydney Water sewer mains in accordance with Sydney Water's requirements. Where Sydney Water mains are not available in rural areas, the backwash waters shall be managed onsite in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system. Appropriate instructions of artificial resuscitation methods.

(d) A warning sign stating 'YOUNG CHILDREN SHOULD BE SUPERVISED WHEN USING THIS POOL' has been installed.

(e) Signage showing resuscitation methods and emergency contact

- (f) All signage shall be located in a prominent position within the pool area.
- (g) Swimming pools and spas must be registered with the Division of Local Government.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of an Interim / Final Occupation Certificate.

Reason: To protect human life (DACPLF09)

# 73. Certification of completion of requirements for Seniors Housing or Housing for Persons with a Disability

Details demonstrating that all stipulated requirements of this development consent for Seniors Housing or Housing for Persons with a Disability have been completed.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.



Reason: To ensure statutory requirements have been completed, public safety, and equitable access for seniors of people with a disability. (DACPLF12)

# 74. Fire Safety Matters

At the completion of all works, a Fire Safety Certificate will need to be prepared which references all the Essential Fire Safety Measures applicable and the relative standards of Performance (as per Schedule of Fire Safety Measures). This certificate must be prominently displayed in the building and copies must be sent to Council and Fire and Rescue NSW.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Interim / Final Occupation Certificate.

Each year the Owners must send to the Council and Fire and Rescue NSW, an annual Fire Safety Statement which confirms that all the Essential Fire Safety Measures continue to perform to the original design standard.

Reason: Statutory requirement under Part 9 Division 4 & 5 of the Environmental Planning and Assessment Regulation 2000.

#### 75. Footpath

A footpath linking the site (9 - 11 Birdwood Avenue) and Pittwater Road which is to be located on the southern side of Birdwood Avenue is to be constructed and finalised.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any Occupation Certificate.

Reason: To ensure the Quality of Access for the residents of the proposed development is provided in accordance with relevant standards (DACTRADC1)

# 76. Removal of Redundant Driveways

All redundant driveways shall be removed and reinstated to Council standard kerb and gutter. Suitably prepared plans shall be submitted to for an approval under and approved by Council. All costs associated with the works shall be borne by the applicant. A plan checking fee (amount to be advised) and lodgement of a performance bond may be required from the applicant prior to the release of the approval.

Reason: To maximise on-street car parking by removing driveways that are no longer needed in accordance with Council policy. (DACTRFPOC1)

#### 77. Public Domain Infrastructure

The applicant is to construct the footpath in accordance with the submitted civil drawings, to Council's satisfaction, prior to the release of any Occupation Certificate.

All necessary permits must be approved prior to the associated works commencing.



Additionally, the identified bus stops must be re-constructed to be DDA complaint. The applicant is to prepare drawings to demonstrate compliance. These drawings are to be submitted to and approved by Council prior to the works being undertaken. The works are to then be undertaken by the applicant, at no cost to Council, to the satisfaction of Council, prior to the release of any Occupation Certificate.

Further, any damages to road reserve shall be reinstated to Council standard. Suitably prepared plans shall be submitted to and approved approved by Council. All costs associated with the works shall be borne by the applicant.

A plan checking fee (amount to be advised) and lodgement of a performance bond may be required from the applicant prior to the release of the approval.

Reason: To provide the necessary infrastructure and maintain road reserve to the standards, prior to the tenants occupying the building so as to make safe. (DACTRFPOC2)

### 78. Waste and Recycling Facilities Certificate of Compliance

The proposal shall be constructed in accordance with Northern Beaches Development Control Plan – Part C9 Waste Management

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure waste and recycling facilities are provided. (DACWTF01)

# 79. Waste/Recycling Compliance Documentation

Evidence of disposal for recycling from the construction/demolition works shall be submitted to the Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure waste is minimised and recycled. (DACWTF02)

#### 80. Positive Covenant for Waste Services

A positive covenant shall be created on the title of the land requiring the proprietor of the land to provide access to the waste storage facilities prior to the issue of an Interim/Final Occupation Certificate. The terms of the positive covenant are to be prepared to Council's standard requirements, (available from Northern Beaches Council), at the applicant's expense and endorsed by Council prior to lodgement with the Department of Lands. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

Reason: To ensure ongoing access for servicing of waste facilities (DACWTF03)

# 81. Authorisation of Legal Documentation Required for Waste Services

The original completed request form (Department of Lands standard form 13PC) must be submitted to Council for authorisation prior to the issue of the Interim/Final Occupation Certificate. A copy of the work-as-executed plan (details overdrawn on a copy of the approved plan) must be included with the above submission. Where required by Council or the Certifying Authority, a Compliance Certificate shall also be provided in the submission to Council.

If Council is to issue the Compliance Certificate for these works, the fee is to be in accordance with Council's Fees and Charges.



Reason: To create encumbrances on the land. (DACWTF04)

# ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

#### 82. Waste Storage Area

Any doors fitted on the Waste Storage Area, pathway and access must be:

a) Able to be latched in an open position. b) Unobstructed by any locks and security devices.

The Waste storage area is a designated area to accommodate communal use waste and recycling bins. The Waste storage area:

a) must not be used to store any other items b) must be clear of any service and utilities infrastructure and related activities. (DACHEGOG1)

### 83. Noise Control

Noise from the operation of any plant or equipment at the premises shall comply with the noise provisions of the Protection of the Environment Operations Act, 1997.

Reason: For the protection of public health and amenity (DACHPBOC6)

#### 84. Height of vegetation

Any planting installed along the eastern and western boundaries of the site are to be maintained at height not exceeding six (6) metres, measured from the ground level adjacent to the trunk.

Any planting along the rear southern boundary shall be maintained at 2.5 metre maximum height above ground.

Reason: Protection of local amenity and maintenance of view corridors.

#### 85. Landscape maintenance

i) Trees shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilized as required at the time of planting.

ii) If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan.

Reason: To maintain local environmental amenity.

#### 86. **No Planting Environmental Weeds**

No environmental weeds are to be planted on the site. Information on weeds of the Northern Beaches can be found at the NSW WeedWise website (http://weeds.dpi.nsw.gov.au/).

Reason: Weed management.

# 87. Works to cease if item found

If any Aboriginal Engravings or Relics are unearthed all work is to cease immediately and the Aboriginal Heritage Office (AHO) and Office of Environment and Heritage (OEH) are to be notified.

Reason: To protect Aboriginal Heritage.



# 88. Dead or Injured Wildlife

If construction activity associated with this development results in injury or death of a native mammal, bird, reptile or amphibian, a registered wildlife rescue and rehabilitation organisation must be contacted for advice.

Reason: To mitigate potential impacts to native wildlife resulting from construction activity.

#### 89. Swimming pool filter, air-conditioning units and plant (noise)

The swimming pool filter and air-conditioning units are not create any noise which exceeds over 5dB(A) above the ambient background noise levels when measured from any property boundary.

Reason: Ensure reasonable acoustic amenity.

#### 90. Outdoor Lighting

All outdoor lighting is to be directed away from the adjoining property boundaries and must comply with AS/NZS 4282 'Control of obtrusive effects of outdoor lighting'.

Reason: To maintain the amenity of the adjoining properties.

#### 91. Accessibility of parking facilities

The parking facilities including visitor parking are to be accessible and identifiable at all times. Necessary signs and markings have to be maintained throughout the lifetime of the development.

Reason: To ensure residents, retailers and visitors are not forced to park on public streets when parking has been provided within the development. (DACTRGOG1)

#### 92. Parking Enclosure

No parking spaces or access thereto, shall be constrained or enclosed by any form of structure such as fencing, cages, walls, storage space, or the like, without prior consent from Council.

Reason: To ensure accessibility is maintained. (DACTRGOG2)



# **Right to Review by the Council**

You may request Council to review this determination of the application under Division 8.2 of the Environmental Planning & Assessment Act 1979. Any Division 8.2 Review of Determination application should be submitted to Council within 3 months of this determination, to enable the assessment and determination of the application within the 6 month timeframe.

NOTE: A fee will apply for any request to review the determination.

# **Right of Appeal**

If you are dissatisfied with this decision Division 8.3 of the Environmental Planning & Assessment Act 1979 may give you the right to appeal to the Land and Environment Court within 6 months after the date on which you receive this notice.

Signed

On behalf of the Consent Authority

Name Rodney Piggott, Manager Development Assessments


Date

09/12/2020



# GENERAL ADVICE Advisory Notes (General)

#### Where are you in the development process?



Note: The advice within this document is provided in good faith as a guide to assist applicants understand the broad process and will not detail every step or every requirement for demolition, building construction works or subdivision required or business operating requirements under New South Wales or Commonwealth Legislation. If you require clarification or have any questions, please contact your Certifier or Council's Planning and Development Enquiries Team.

The attached Notice of Determination includes conditions of consent which must be complied with.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)



# **Building Certification**

The Environmental Planning and Assessment Act 1979 provides that:

- Building work cannot occur unless a construction certificate has been issued;
- Occupation of building works cannot occur unless an occupation certificate has been issued
- Subdivision cannot be registered until a subdivision certificate has been issued
- Mandatory Inspection for building work must be completed

Please refer to process chart for more detail.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

### **Certification Services**

Construction Certificates / Occupation Certificates / Subdivision Certificates / Strata Certificates, can be issued by Council or an accredited private certifier (Note Council must be the Principal Certifying Authority (PCA) for subdivisions).

Council is well placed to provide Certification Services. Council can issue Construction Certificates and act as your Principle Certifying Authority at competitive rates. Please visit our web site www.northernbeaches.nsw.gov.au or speak to our Customer Service Officers if you have any further questions about our Certification Services or if you wish to use Council as your certifier.

# **Charges Associated with the Development Consent**

All bonds, fees, Development Contributions or the Long Service Levy detailed within the Notice of Determination are required to be paid prior to the issuing of any Construction Certificate.

#### Bonds are released after:

- 1. 'Final Occupation Certificate' has been received by Council; and
- 2. Final inspection by a Council Officer where:
  - the development is complete
  - o damage has not been caused to council assets during the works
  - o conditions of development consent have been met.

The bond will be released to the person or business who paid the bond to Council (The name that appears on the original receipt)

# Acceptable Form of Security Bonds

Council will accept bank guarantee (in a form acceptable to Council) in lieu of cash and is required prior to the issue of a construction certificate.

#### Modifications to the consent

If you seek to make any changes to the development (which may include internal / external configuration of the building, variation to facades, site layout or any changes to the proposed operation or use), the modifications may require the submission and approval of an application to modify the development consent prior to the issuing of a Construction Certificate and prior to the works being



carried out. The proposed changes should be discussed with the PCA.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

## Other Matters not detailed within the Notice of Determination

The Notice of Determination does not stipulate every requirement that must be completed to satisfy New South Wales and Commonwealth legislation.

You should check, as may be relevant, with other authorities including but not limited to:

- Workcover NSW for work safety and asbestos requirements
- Sydney Water Quick Check Agent for the provision of water and sewer services
- Energy & Gas suppliers for utility services
- Department of Fair Trading for advice about builders and licensing
- Building Professionals Board for advice about private certifiers
- NSW Roads and Maritime Services for works on state roads only
- Human Rights and Equal Opportunity Commission for access issues
- NSW Land and Property Information for Land Title matters
- Australia Post for the positioning and dimensions of mail boxes in new commercial and residential developments;

#### Dial Before You Dig

Underground assets may exist in the area that is subject to your application. In the interests of health and safety and in order to protect damage to third party assets please contact Dial before you dig at www.1100.com.au or telephone on 1100 before excavating or erecting structures (This is the law in NSW). If alterations are required to the configuration, size, form or design of the development upon contacting the Dial before You Dig service, an amendment to the development consent (or a new development application) may be necessary. Individuals owe asset owners a duty of care that must be observed when working in the vicinity of plant or assets. It is the individual's responsibility to anticipate and request the nominal location of plant or assets on the relevant property via contacting the Dial before you dig service in advance of any construction or planning activities.

#### **Telecommunications Act 1997 (Commonwealth)**

Telstra (and its authorised contractors) are the only companies that are permitted to conduct works on Telstra's network and assets. Any person interfering with a facility or installation owned by Telstra is committing an offence under the Criminal Code Act 1995 (Cth) and is liable for prosecution. Furthermore, damage to Telstra's infrastructure may result in interruption to the provision of essential services and significant costs. If you are aware of any works or proposed works which may affect or impact on Telstra's assets in any way, you are required to contact :Telstra's Network Integrity Team on Phone Number 1800810443.

(1) if the development is likely to disturb or impact upon telecommunications infrastructure, written confirmation from the service provider that they have agreed to the proposed works must be submitted



to the Principal Certifying Authority prior to the issue of a Construction Certificate or any works commencing, whichever occurs first; and

(2) The arrangements and costs associated with any adjustment to telecommunications infrastructure shall be borne in full by the applicant/developer.

#### Model

If you submitted a model with the application it must be collected from the Council offices within fourteen (14) days of the date of this determination. Models not collected will be disposed of by Council.

### Trade waste agreement

A Trade Waste Agreement must be obtained from Sydney Water prior to the discharge of trade wastewater to the sewer system. Trade wastewater is defined as 'discharge water containing any substance produced through industrial or commercial activities or operation on the premises'.

### Waste collection

Liquid and solid wastes generated on the site must be collected, transported and disposed of in accordance with the requirements of the Protection of the Environment Operations Act 1997. Records must be kept of all waste disposal from the site.

Material to be removed from the site must be source separated on site to maximise recycling, and the material disposed of to an appropriate disposal and recycling facility in accordance with the approved Waste Management Plan.

#### **Aboriginal Heritage**

If in undertaking excavation or works and any Aboriginal site or object is, or is thought to have been found, all works are to cease immediately and the applicant is to contact the Aboriginal Heritage Officer for Warringah Council, and the Cultural Heritage Division of the Department of Environment and Climate Change (DECC).

# **On-Site Sewage Management System**

This approval does not authorise the installation or operation of a new or modification of an existing onsite wastewater management system. An On-Site Sewage Management System must not be installed or operated unless an 'Approval to Install an On Site Sewage Management System' is obtained from Warringah Council.

#### **Cost of Works**

The applicant shall bear the cost of all works associated with the development that occurs on Council's property.

#### **Relocation of stormwater drainage**

Council is not responsible for the cost of relocating Council's stormwater drainage pipes through the subject property.

#### Tree preservation

Where tree work has not been approved by this Development Consent the developer is notified that a general Tree Preservation Order applies to all trees in the Northern Beaches Local Government Area. This order prohibits the ringbarking, cutting down, topping, lopping, pruning, transplanting, injuring, or wilful destruction of such trees except without the prior written consent of Council.

# Storage bins on footpath and roadway

Approval is required from Council prior to the placement of any storage bin on Council's footpath and/or roadway.



# Protection of Public Places

(1) If the work involved in the erection or demolition of a building:

(a) is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient; or

(b) building involves the enclosure of a public place,

a hoarding and site fencing must be erected between the work site and the public place.

(2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.

(3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.

(4) Any such hoarding, fence or awning is to be removed when the work has been completed.(5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained.

### **Road Opening Permit**

The developer/applicant is to obtain a "Road Opening Permit" from Council and pay all appropriate charges prior to commencement of any work on Council property. The developer/applicant shall be responsible for all public utilities and services in the area of the work, and as such shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.

#### **Special Permits**

Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development are to occur entirely on the property. The applicant, owner or builder must apply for specific permits available from Council. A minimum of forty-eight (48) hours notice is required for all permits except work zones, which may require additional assessment time.

• Permit for on-street mobile plant

Restrictions apply to the hours of operation and the area of operation for on street mobile plant equipment (for example cranes, concrete pumps, cherry pickers). Separate permits are required for each occasion and each piece of equipment. It is the responsibility of the applicant, owner and builder to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

Hoarding Permit

Permits are required to erect Class A, Class B and Class C hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

• Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given.



• Kerbside restrictions, work zones

Existing kerbside restrictions apply. An application must be made to Council for the alteration of existing kerbside restrictions or the provision of a construction zone. Other permits may include out of construction hours permits.

# Licensing requirements for removal of bonded asbestos

Anyone who removes, repairs or disturbs bonded asbestos must hold a bonded or a friable asbestos licence, or a demolition licence in accordance with Workcover requirements and the Occupational Health and Safety Act 2000.

### **Pool Access**

Access to pools are required to be restricted by a child resistant barrier in accordance with the regulations prescribed in all relevant Acts, Regulations and Australian Standards including:

- (i) Swimming Pools Act 1992;
- (ii) Swimming Pools Amendment Act 2012;
- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools

It is your responsibility as a land owner to ensure any fencing is maintained.

#### Dewatering

Where dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Department of Water and Energy. The bore license must be obtained prior to commencement of dewatering works.

# **Requirement to Notify about New Contamination Evidence**

Any new information revealed during works that has the potential to alter previous conclusions about site contamination or hazardous materials shall be immediately notified to Council and the Principal Certifying Authority.

#### **Flood Evacuation Plan**

If your site is on flood prone land you may wish to consider the preparation of a flood evacuation plan.

Generally a Flood Evacuation Plan would be prepared by suitably qualified Engineer (e.g. Hydraulic) with a number of years experience in flood management and who is eligible for Membership to the Australian Institute of Engineers.

Some matters that you may wish to consider (but not limited to) include:

- (i) a route of evacuation to higher ground and / or point of shelter
- (ii) depth of water for a Possible Maximum Flood event surrounding the building

(iii) details of 'last chance' evacuation water levels / times for evacuation prior to floodwaters surrounding the building

- (iv) provide details of flood warning systems and protocols
- (v) details of how this information will be distributed and people educated for users of the site.

You may seek to discuss this with the State Emergency Service of NSW.

# **Utility Service Requirements**

DA2020/0432



Where development requires the installation of, or the relocation of utility services being (but not limited to) gas, water, electricity and telecommunications, the installation of, or the relocation of utility services shall be conducted in accordance with the requirements of the relevant service provider / authority (unless stipulated by any other condition of the consent or will result in damage to threatened or endangered species defined under the Threatened Species Conservation Act 1995).

# Plant & Equipment Kept Within Site

All plant and equipment used in the erection of the building, including concrete pumps, wagons, lifts, mobile cranes, etc, shall be situated within the boundaries of the site and so placed that all concrete slurry, water, debris and the like shall be discharged onto the building site, and is to be contained within the site boundaries. This does not prevent any requirement to comply with the Protection of the Environment Operations Act.

# Lighting

Illumination of the site is to be arranged in accordance with the requirements of Australian Standard 4282 - 1997 Control of the obtrusive effects of outdoor lighting so as not to impact upon the amenity of the occupants of adjoining and nearby residential premises.

### **Silt and Sediment Control**

During any onsite demolition, excavation and construction works, the site should be maintained in accordance with "The Blue Book - Managing Urban Stormwater (MUS): Soils and Construction".

In managing the site provision shall be made throughout the period of works to prevent transmission of soil to the public road, drainage system, any riparian lands or off site in any manner. Upon completion of the development, any measures to prevent the transition of soil off site to remain in place until the site is stabilised.

A failure to prevent the transmission of silt and sediment and / or causing, water pollution, air pollution, noise pollution or land pollution may result in a breach of the Protection of the Environment Operations Act and orders, penalties and prosecutions may occur.

**Maintenance of Sediment and Erosion Control** Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain.

Reason: To avoid erosion and sedimentation impacts that will result in an adverse change in watercourse or riparian land condition

#### Installation and Maintenance of Sediment and Erosion Control

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: soils and construction (2004).

Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site

#### **Dividing Fences Act 1991**

The construction and maintenance of side boundary fences is to be agreed upon by all adjoining property owners of the fence. Works are to be in accordance with the Dividing Fences Act 1991.

# **OTHER MATTERS**



# **Child Care Centres**

A license to operate a child care centre must be obtained from the NSW Department of Community Services prior to the commencement of the use of the child care centre.

#### **Disability Access**

This decision does not ensure compliance with the Commonwealth Disability Discrimination Act 1992. Applicants are strongly advised to investigate their requirements under that Act

### **Food Premises**

Food premises are required to comply with the requirements of the Food Act 2003, the Food Standards Code and Australian Standards.

The proprietor of a food business must notify the NSW Food Authority of the details of the business. Notification may be done either online at www.foodnotify.nsw.gov.au or by lodging a completed NSW Food Authority notification form to the NSW Food Authority or Council.

### Wheel washing facility

All trucks leaving the site, having had access to unpaved or contaminated areas, shall depart via a wheel wash facility in order to prevent mud, dust or debris from being deposited on Council's roads. The wheel wash facility shall be constructed prior to any truck movements occurring. Water from the wheel wash facility must not cause pollution. Any direction of Council with regard to cleaning trucks or the clean up of road pavements adjoining the site shall be complied with immediately.

#### **Monitoring State of Roadways**

The applicant shall monitor the state of roadways leading to and from the site and shall take all necessary steps to clean up any adversely impacted road pavements as directed by Council.

#### Storage of Dangerous Goods

Prior to the storage of any "dangerous goods" on the premises, a copy of a license obtained from the Chemical Safety Branch of Work Cover Authority must be submitted to Council.

#### Storage of Flammable and Combustible Liquids

Flammable and combustible liquids must be stored in accordance with Australian Standard 1940 The Storage and Handling of Flammable and Combustible Liquids.

#### **Noise and Vibration**

The premises, including operation of vehicles, shall be conducted so as to avoid offensive noise or vibration and cause no interference to adjoining or nearby occupants. Special precautions must be taken to avoid nuisance in neighbouring residential areas, particularly from machinery, vehicles, warning sirens, public address systems and the like.

# Hairdressing/Beauty Treatment/ Skin penetration Requirements

The premises must comply with the following requirements before the commencement of business: i) A hand wash basin with warm water delivered through a common spout must be provided in the treatment area. The hand wash basin must be provided with liquid soap and paper towel. ii) The wall behind the hand wash basin from the floor to a height of 450mm above the top of the washbasin and from the centre of the washbasin to a distance of 140mm beyond each side of the wash basin, must be finished with a material that is durable, smooth, impervious to moisture and capable of being easily cleaned (eg tiles).

iii) The premises must be provided with washing, drainage, ventilation and lighting that are adequate for the carrying out of hairdressing/beauty treatment/skin penetration procedures.

iv) The floor coverings must be smooth and impervious.



v) All furniture, shelves and fittings must be constructed of, or covered with a material that is smooth, impervious to moisture and capable of being easily cleaned.

vi) Adequate lockers must be provided for the storage of employees clothing and personal effects.

vii) The premises must be provided with facilities that are adequate for the purpose of storing of hairdressing/beauty treatment/skin penetration appliance and utensils.

viii) The premises must be provided with a sink sullied with hot and cold water for washing equipment.

# **Food Premises Construction Requirements**

The food premises must comply with the following specific construction requirements:

Solid walls must be provided in all food handling areas (solid includes brick, cement and foam filled preformed panels);

ix) Walls in food preparation and wash up areas must be finished with a smooth and impervious surface to a height of at least 2 metres.

x) Hand wash basins must be provided with warm water delivered through a common spout with taps that are hands free operation;

xi) Coving with a radius of 25mm must be provided between all floor and wall joints in food handling areas;

xii) The open space between the top of the coolroom and the ceiling must be fully enclosed and kept insect and pest proof;

xiii) The coolroom must be able to be opened from the inside with out a key and fitted with an alarm that can only be operated from within the coolroom;

xiv) The doors to the toilet air lock and toilet compartment must be tight fitting and self closing;

xv) The rear external door must be self closing or be provided with a fly screen that is self closing;

xvi) Where cooking or extensive heating processes or such other processes as may be specified are carried out in food preparation areas, an approved mechanical ventilation system shall be installed and operated in accordance with AS 1668 part 1 & 2.

# Legionella Control

Cooling towers, warm water systems, water cooling systems must be registered with the Council. Details of registration are to be provided to the Council prior to operation.

# Pool/Spa Safety

Owners of properties with swimming pools and spa's must meet safety compliance and registration requirements. Provisions also apply when renting/selling properties. Details are available from the Division of Local Government.

# **Grease Trap**

Contact Sydney Water to determine what trade waste provisions you are required to provide to your food premises. Should a grease trap be required by Sydney Water, it must be located in an area that is easily accessible for the removal of waste water and must not be installed in any kitchen, food preparation or food stage area. The design and location of the grease trap should also not impede on any commercial right of way or pedestrian access.

# Bandicoot/Penguin

Long-nosed Bandicoots & Little Penguins – Best Practices for Residents Residents are encouraged to follow a number of *Best Practices* to assist with the protection and management of the endangered populations of Long-nosed Bandicoots and Little Penguins:

- Long-nosed Bandicoots, Little Penguins and other native animals should never be fed as it may cause them nutritional problems, hardship if supplementary feeding is stopped, and it may increase predation.
- Feral cats or foxes should never be fed or food left out where they can access it, such as rubbish bins without lids or pet food bowls, as these animals present a significant threat to Long-nosed Bandicoots, Little Penguins and other wildlife.
- The use of insecticides, fertilisers, poisons and/or baits should be avoided on the property.



Garden insects will be kept in low numbers if Long-nosed Bandicoots are present.

- When the North Head Long-nosed Bandicoot Recovery Plan is released it should be implemented where relevant.
- Dead Long-nosed Bandicoots or Little Penguins should be reported by phoning Manly Council on 9976 1500 or Department of Environment and Conservation on 9960 6266.
- Please drive carefully as vehicle related injuries and deaths of Long-nosed Bandicoots and Little Penguins have occurred in the area. Care should also be taken at night in the drive way when moving cars as bandicoots will seek shelter beneath vehicles.
- Cat/s and or dog/s that currently live on the property should be kept indoors at night to avoid disturbance/death of native animals. Ideally, when the current cat/s and/or dog/s that live on the property no longer reside on the property it is recommended that they not be replaced by new dogs or cats.
- Report all sightings of feral rabbits, feral or stray cats and/or foxes to N B Council.