

## Landscape Referral Response

<b>Application Number:</b>	DA2020/0707
<b>Date:</b>	03/09/2020
<b>Responsible Officer:</b>	Maxwell Duncan
<b>Land to be developed (Address):</b>	Lot 6 DP 749791 , 113 Orchard Street WARRIEWOOD NSW 2102

### Reasons for referral

This application seeks consent for the following:

- Construction / development works within 5 metres of a tree or
- New residential works with three or more dwellings. (RFB's, townhouses, seniors living, guesthouses, etc). or
- Mixed use developments containing three or more residential dwellings.
- New Dwellings or

### Officer comments

The development application proposal is for the

Council's Landscape Referral is assessed against the Pittwater Local Environment Plan clause RU2 Rural Landscape, and in particular the following Pittwater 21 DCP Controls:

- B4.22 Preservation of Trees and Bushland Vegetation
- C1.1 Landscaping
- D16 Warriewood Valley Locality

The site is located in the RU2 Rural Landscape zone, requiring development, amongst other objectives, to maintain the rural landscape character of the land.

224 existing trees are found within the site containing indigenous Sydney Turpentine Ironbark Forest. A Aboricultural Impact Assessment is provide with the application, and the development proposal will require the removal of thirty-two existing native trees due to development encroachment or poor health and condition, and seven are assessed as dead and should be removed regardless.

A Landscape Plan is provided with proposals for replanting of indigenous trees, shrubs, groundcovers and native grasses.

The landscape component of the proposal is acceptable subject to the recommended tree protection measures and completion of landscape works.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

### Recommended Landscape Conditions:

## CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

### **Tree protection measures - Project Arborist**

A Project Arborist with minimum AQF Level 5 in arboriculture shall be engaged to provide tree protection measures in accordance with Australian Standard 4970-2009 Protection of Trees on Development Sites.

The Project Arborist is to specify and oversee all tree protection measures such as tree protection fencing, trunk and branch protection, and ground protection.

The Project Arborist is to supervise all demolition, excavation and construction works near all trees to be retained, including construction methods near the existing trees to protect tree roots, trunks, branches and canopy. Where required, manual excavation is to occur ensuring no tree root at or >25mm (Ø) is damaged by works, unless approved by the Project Arborist.

The Project Arborist shall be in attendance and supervise all works as nominated in the Arboricultural Impact Assessment prepared by Ecological Consultants Pty Ltd, including:

- i) works in the vicinity of existing trees 5, 6, 144, 145, 147 as listed under section 3.2,
- ii) works in the vicinity of existing trees 45, 46, 60, 197, 198, 206, 207, 210 as listed under section 3.6,
- iii) works in the vicinity of existing trees 26, 27, 199, 212 as listed under section 3.7,
- iv) works in the vicinity of existing trees 52, 54, 67, 147, 150 as listed under section 3.9,
- v) works in the vicinity of existing trees 51, 71, 152 as listed under section 3.10,
- vi) works in the vicinity of existing trees 166, 167 as listed under section 3.14,
- vii) works in the vicinity of existing tree 15 as listed under section 3.15,
- viii) works in the vicinity of existing trees 17, 30, 52, 54, 60, 62 as listed under section 3.17,
- ix) works in the vicinity of existing trees 58, 65 as listed under section 3.18,
- x) works in the vicinity of existing trees 57, 58 as listed under section 3.19,
- xi) works in the vicinity of existing tree 56 as listed under section 3.20,
- xii) works in the vicinity of existing trees 11, 36, 171 as listed under section 3.21.

All tree protection measures specified must:

- a) be in place before work commences on the site, and
- b) be maintained in good condition during the construction period, and
- c) remain in place for the duration of the construction works.

The Project Arborist shall provide certification to the Certifying Authority that all recommendations listed for the protection of the existing tree(s) have been carried out satisfactorily to ensure no impact to the health of the tree(s). Photographic documentation of the condition of all trees to be retained shall be recorded, including at commencement, during the works and at completion.

Note: A separate permit or development consent may be required if the branches or roots of a protected tree on the site or on an adjoining site are required to be pruned or removed.

Reason: tree protection.

### **Tree removal within the property**

This consent approves the removal of the following trees within the property (as recommended in the Arboricultural Impact Assessment prepared by Ecological Consultants Pty Ltd):

- Tree number(s): 2, 5, 6, 32, 38, 39, 40, 41, 42, 43, 44, 53, 63, 64, 65, 66, 68, 69, 72, 73, 74, 75, 76, 77, 141, 142, 144, 147, 165, 167, 198, and 208.
- Dead trees: 50, 51, 139, 140, 143, 161, and 162.

The following Exempt Species do not require Council consent for removal:

- Tree number(s): 1 and 77.

Reason: to enable authorised building works

Note: Any request to remove a tree approved for retention under the development application is subject to a Section 4.55 modification application, or an assessment by an Arborist with minimum AQF Level 5 in arboriculture that determines that the tree presents an imminent risk to life or property.

## CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

### Tree and vegetation protection

a) Existing trees and vegetation shall be retained and protected, including:

- i) all trees and vegetation within the site, excluding exempt trees and vegetation under the relevant planning instruments of legislation,
- ii) all trees and vegetation located on adjoining properties,
- iii) all road reserve trees and vegetation.

b) Tree protection shall be undertaken as follows:

- i) tree protection shall be in accordance with Australian Standard 4970-2009 Protection of Trees on Development Sites, including the provision of temporary fencing to protect existing trees within 5 metres of development,
- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist with minimum AQF Level 5 in arboriculture
- iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
- vii) should either or all of v), vi) and vii) occur during site establishment and construction works, an Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Certifying Authority,
- viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of Australian Standard 4970-2009 Protection of Trees on Development Sites,
- ix) the activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site
- x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with Australian Standard 4373-2007 Pruning of Amenity Trees.
- xi) the tree protection measures specified in this clause must: i) be in place before work commences on the site, and ii) be maintained in good condition during the construction period, and iii) remain in place for the duration of the construction works.

c) Tree protection shall specifically be undertaken in accordance with the recommendations in the Arboricultural Impact Assessment prepared by Ecological Consultants Pty Ltd, as listed in the following sections:

- section 3 - Development Impacts
- section 4 - Conclusions and Recommendations
- appendix 5 - General guidance notes for protecting trees on development sites

The Certifying Authority must ensure that:

d) The activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites, do not occur within the tree protection zone of any tree, and any temporary access to, or location of scaffolding within the tree protection zone of a protected tree, or any other tree to be retained on the site during the construction, is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.

Note: All street trees within the road verge and trees within private property are protected under Northern Beaches Council development control plans, except where Council's written consent for removal has been obtained. The felling, lopping, topping, ringbarking, or removal of any tree(s) is prohibited.

Reason: tree and vegetation protection.

### **Condition of trees**

During the construction period the applicant is responsible for ensuring all existing trees required to be retained are maintained in a healthy and vigorous condition. This is to be done by ensuring that all identified tree protection measures are adhered to, or by seeking arboricultural advice from an Arborist with minimum AQF Level 5 in arboriculture during the works. In this regard all protected trees shall not exhibit:

- i) a general decline in health and vigour,
- ii) damaged, crushed or dying roots due to poor pruning techniques,
- iii) more than 10% loss or dieback of roots, branches and foliage,
- iv) mechanical damage or bruising of bark and timber of roots, trunk and branches,
- v) yellowing of foliage or a thinning of the canopy untypical of its species,
- vi) an increase in the amount of deadwood not associated with normal growth,
- vii) an increase in kino or gum exudation,
- viii) inappropriate increases in epicormic growth that may indicate that the plants are in a stressed condition,
- ix) branch drop, torn branches and stripped bark not associated with natural climatic conditions.

Any mitigating measures and recommendations required by the Arborist are to be implemented.

The owner of the adjoining allotment of land is not liable for the cost of work carried out for the purpose of this clause.

Reason: Protection of trees.

## **CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE**

### **Landscape completion**

Landscaping is to be implemented in accordance with the Landscape Concept Plan DA08, revision E, prepared by Tony McLain Architect.

Prior to the issue of an Occupation Certificate, a landscape report prepared by a landscape architect or landscape designer shall be submitted to the Certifying Authority, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: environmental amenity.

**Condition of retained vegetation - Project Arborist**

Prior to the issue of an Occupation Certificate, a report prepared by the project arborist shall be submitted to the Certifying Authority, assessing the health and impact on all existing trees required to be retained, including the following information:

- a) compliance to any Arborist recommendations for tree protection generally and during excavation works,
- b) extent of damage sustained by vegetation as a result of the construction works,
- c) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: tree protection.

**ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES**

**Environmental and priority weed control**

All weeds are to be removed and controlled in accordance with the NSW Biosecurity Act 2015.

Reason: preservation of environmental amenity.

**Landscape maintenance**

If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components. Trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilized as required at the time of planting.

If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan.

Reason: to maintain local environmental amenity.