

STORMWATER DRAINAGE NOTES:

1. ALL PIPES TO BE 100mm Ø UNLESS NOTED OTHERWISE.

2. ALL PIPES TO BE uPVC TO AS 1254-2002 UNLESS NOTED OTHERWISE. 3. ALL PIPES TO BE LAYED AT 1 % MINIMUM GRADE UNLESS NOTED OTHERWISE.

4. ALL PIPES SHALL BE LAID ON A 75mm SAND BED, COMPACTED TO 100% S.M.D.D. BELOW PAVEMENTS. (NO COMPACTION REQUIRED BELOW LANDSCAPING), COVER TO SURFACE FROM TOP OF PIPE TO BE 300mm MINIMUM, BACKFILL TO BE ADEQUATELY CONSOLIDATED AROUND PIPES BY METHOD OF RAMMING AND WATERING IN. TRENCHES TO BE FILLED WITH GRANULAR MATERIAL AS SPECIFIED.

5. ALL DOWN PIPES TO BE 100mm Ø UNLESS NOTED OTHERWISE. 6. DOWN PIPE LOCATIONS ARE INDICATIVE ONLY. LOCATIONS TO BE CONFIRMED WITH ARCHITECT PRIOR TO COMMENCEMENT WITH WORK

7. PROVIDE CLEANING EYES AT ALL DOWNPIPES

8. ALL PITS TO BE CAST INSITU OR, IF PRECAST, APPROVED BY ENGINEER. CAST INSITU PITS TO HAVE 150mm THICK CONCRETE WALLS AND BASE. WALLS TO BE REINFORCED WITH 1 N12 TOP TIE UNLESS NOTED OTHERWISE. CAST INSITU PITS GREATER THAN 1000 DEEP TO BE MINIMUM 900x600 AND TO HAVE 150mm THICK CONCRETE WALLS AND BASE. WALLS TO BE REINFORCED WITH N12 AT 250 EACH WAY UNLESS NOTED OTHERWISE. 9. ALL PITS GREATER THAN 1000mm DEEP SHALL HAVE STEP IRONS AS PER COUNCIL STANDARDS.

10. ALL WORK TO BE IN ACCORDANCE WITH LOCAL COUNCIL STANDARDS AND SPECIFICATIONS.

11. PRIOR TO COMMENCING ANY SITE WORKS THE CONTRACTOR SHALL IMPLEMENT EROSION CONTROL MEASURES TO APPROVED SEDIMENT AND EROSION CONTROL PLAN, EPA GUIDELINES AND COUNCIL SPECIFICATIONS. ALL MEASURES TO REMAIN IN PLACE UNTIL COMPLETION AND STABILIZATION OF THE SITE TO COUNCIL SATISFACTION.

12. ALL LEVELS SHOWN ARE TO AHD UNLESS NOTED OTHERWISE.

13. ENSURE THAT ALL PITS AND STORMWATER PIPES ARE LOCATED CLEAR FROM TREE ROOT SYSTEMS. 14. ALL EXISTING EARTHENWARE PIPES TO BE UPGRADED TO uPVC.

15. ALL WORKS TO BE IN ACCORDANCE WITH AS 3500.3: 2018 NATIONAL PLUMBING DRAINAGE CODE PART 3 - STORMWATER DRAINAGE.

16. UNLESS NOTED OTHERWISE, SUB-SOIL DRAINS ARE TO BE INSTALLED IN ACCORDANCE WITH AS3500.3 ALONGSIDE WALLS THAT IMPEDE THE NATURAL FLOW OF GROUNDWATER. THIS MAY ALSO INVOLVE TRENCHING INTO THE CLAY OR ROCK SUBGRADE TO DIRECT GROUNDWATER AWAY FROM STRUCTURES.

17. IF NOT INDICATED ON PLANS, PROVIDE LEAF CATCHERS TO ALL DOWNPIPES. 18. EXISTING STORMWATER SYSTEM TO BE CHECKED AND UPGRADED AS REQUIRED IN ACCORDANCE WITH AS 3500.3: 2018.

19. CARE SHOULD BE TAKEN WHEN UNDERTAKING WORKS IN THE VICINITY OF SELECTED TREES NOT TO DISTURB THE TREE ROOT SYSTEM. HAND DIGGING OF TRENCHES MAY BE NECESSARY. REFER ARBORISTS REPORT WHERE REQUIRED.

20. CONTRACTOR TO LOCATE ALL EXISTING SERVICES PRIOR TO EXCAVATION AND NOTIFY ENGINEER OF ANY POTENTIAL CLASHES WITH THE PROPOSED DRAINAGE EASEMENT PIPE LINE. 21. ALL SUB-SOIL DRAINAGE TO BE INSTALLED IN ACCORDANCE WITH THE STRUCTURAL AND GEOTECHNICAL REQUIREMENTS,

AUSTRALIAN STANDARDS AS 3500.3: 2018 AND IS TO BE DIRECTED TO THE SITE DRAINAGE SYSTEM BY MEANS OF GRAVITY DISCHARGE ONLY. DO NOT CONNECT SUB-SOIL PIPES TO AREAS WITH HIGHER SURFACE LEVELS U.N.O.. 22. ALL PIPES SHOWN ARE INDICATIVE ONLY AND MINIMUM CLEARANCES FROM THE EXTERNAL WALLS OF BUILDINGS, FOR THE

EXCAVATION OF TRENCHES, ARE TO BE PROVIDED IN ACCORDANCE WITH AS 3500.3: 2018. 23. ANY COMPONENTS OF THE EXISTING SYSTEM PROPOSED TO BE RETAINED ARE TO BE CERTIFIED DURING CONSTRUCTION TO BE IN GOOD CONDITION AND OF ADEQUATE CAPACITY TO CONVEY ADDITIONAL RUNOFF AND BE REPLACED OR UPGRADED IF REQUIRED.

24. ANY CHARGED PIPES MUST BE A MINIMUM OF 100mm (UNLESS NOTED OTHERWSIE) WITH ALL JOINTS MUST BE SOLVENT WELDED. A CLEANING EYE, OR FLUSH OUT POINT, MUST BE PROVIDED AT THE LOW POINT IN THE SYSTEM WITHIN A PIT THAT CAN BE DRAINED TO AN ONSITE DISPERSAL SYSTEM.

25. PROVISION IS TO BE MADE FOR THE COLLECTION AND DISPOSAL IN AN APPROVED MANNER OF ANY OVERLAND FLOW OR SUB-SURFACE FLOW ENTERING THE SUBJECT PROPERTY. OR CONCENTRATED AS A RESULT OF THE PROPOSED WORKS. ANY REDIRECTION OR TREATMENT OF FLOWS ENTERING THE PROPERTY SHALL NOT ADVERSELY AFFECT ANY OTHER PROPERTIES. 26. PREVENT ANY STORMWATER EGRESS INTO ADJACENT PROPERTIES BY CREATING PHYSICAL BARRIERS AND SURFACE

DRAINAGE INTERCEPTION. 27. GUTTER GUARDS MUST BE INSTALLED ON ALL GUTTERS TO MINIMISE DEBRIS ENTERING THE SYSTEM.

28. ALL SUB-SOIL DRAINAGES. STRIP DRAINS AND DRAINAGE PITS SHALL DISCHARGE TO THE ESTABLISHED SITE DISCHARGE POINT U.N.O AND BE CONSTRUCTED IN ACCORDANCE WITH AS3500.3: 2018 REQUIREMENTS.

29. OVERFLOW PATHS SHALL BE PROVIDED TO ALLOW FOR FLOWS IN EXCESS OF THE CAPACITY OF THE PIPE/DRAINAGE SYSTEM DRAINING THE SITE.

30. WHERE ANY NEW STORMWATER DRAINAGE SYSTEM CROSSES THE FOOTPATH AREA WITHIN ANY ROAD, SEPERATE APPROVAL UNDER SECTION 138 OF THE ROAD ACT 1993 MUST BE OBTAINED FROM COUNCIL FOR THOSE WORKS PRIOR TO THE ISSUE OF ANY CONSTRUCTION CERTIFICATE

31. CONCEALED DOWNPIPES MUST BE INSTALLED IN ACCORDANCE WITH SECTION 4.5.6 OF AUSTRALIAN STANDARDS AS3500.3: 2018 REQUIREMENTS. BUILDER TO ENSURE LOCATIONS DO NOT RESTRICT NORMAL OPERATION OF DOORS, WINDOWS, ACCESS OPENINGS OR OCCUPANCY OF A BUILDING, DO NOT CAUSE NUISANCE OR LEAD TO INJURY OF A PERSON. DO NOT INTERFERE WITH THE STRUCTURAL INTEGRITY OF THE WALL OR COLUMN. AS CLOSE AS PRACTICABLE TO THE SUPPORTING STRUCTURE, ARE PROTECTED FROM MECHANICAL DAMAGE, AT LEAST 100mm CLEAR OF ANY ELECTRICAL CABLE OR GAS PIPE, AT LEAST 50mm FROM ANY OTHER PIPEWORK OR SERVICE. CONCEALED DOWNPIPES TO HAVE INSPECTION OPENINGS THAT EXTEND TO THE FACE OF THE WALL OR SLAB FOR MAINTENANCE. SEAMS AND JOINTS TO BE WATERTIGHT. IF INSPECTION OPENINGS ARE REQUIRED FOR TESTING AND MAINTENANCE PURPOSES, INSPECTION OPENINGS SHALL HAVE A NOMINAL SIZE OF

NOT LESS THAT THE NOMINAL DIAMETER OF THE DOWNPIPE. 32. WHERE A DOWNPIPE IS CONNECTED TO A SITE STORMWATER DRAIN LOCATED BELOW A SLAB-ON-GROUND, THE CONNECTION OF A CONCEALED DOWNPIPE SHALL BE LOCATED ABOVE THE LEVEL OF THE FLOOR.

33. SUPPORT SYSTEMS OF DOWNPIPES OR PIPEWORK MUST BE INSTALLED IN ACCORDANCE AUSTRALIAN STANDARDS AS3500.3: 2018 REQUIREMENTS. 34. FOR CONCEALED EAVES GUTTERS, U.N.O THE TOP EDGE OF THE FASCIA SHOULD NOT BE LESS THAN 25mm BELOW THE

TOP OF THE BACK OF THE GUTTER, OR INTEGRAL FLASHING (TAIL) WITH THE TOP EDGE OF THE FLASHING NOT LESS THAN 25mm ABOVE THE TOP OF THE FASCIA. 35. THE FOLLOWING ABBREVIATIONS DENOTE:

FSL – FINISHED SURFACE LEVEL OR RL – REDUCED LEVEL

IL - INVERT LEVEL OF PIPE

INV. – INVERT LEVEL OF PIT - CENTRELINE OF ORIFICE CL

TWL - TOP WATER LEVEL

NOTE:

THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE OF THE DRAINAGE DISCHARGE PIPES.

94-	-90	

TOTAL SITE AREA
COUNCIL ZONE AREA
DEVELOPMENT TYPE
TOAL SITE IMPERVIOUS ARE
TOAL SITE IMPERVIOUS ARE
TOTAL INCREASE IN IMPERV

RAINWATER VOLUME (BASIX) RAINWATER VOLUME PROVIDE

HYDRAULIC ANALYSIS CONFIRMS THAT OSD DELAYS SITE DISCHARGE, RESULTING IN A DETRIMENTAL ALIGNMENT WITH DOWNSTREAM FLOOD PEAKS, CONTRARY TO BEST FLOOD MANAGEMENT PRACTICES REFER TO DESIGN STATEMENT FOR HYDROGRAPH COMPARISONS FROM THE MCCARRS CREEK, MONA VALE AND BAYVIEW FLOOD STUDY (2017). THEREFORE, OSD IS NOT RECOMMENDED.

WSUD MUSIC SUMMARY

TOTAL SUSPENDED SOLIDS TOTAL PHOSPHOROUS (TP) TOTAL NITROGEN (TN)

GROSS POLUTANTS (GP)

THE	5
ST	C
TH	E
PRI	١

	_				
	_				
	-	-	-		-
	-				-
					-
	-		-		-
	_				_
	_				_
	_			-	_
	_				
	_				
	N	orth	8 So	uth F	20
	_				
	_				-
	_				-
	_				-
	_				_
	_				_
	_		in an		
	_	Ime	rviou	is Ar	e
	_				_
	_				
1					

NOTE:				
COUNCIL AND/OR PRIVATE CERTIFYING AUTHORITY APPROVAL FOR				
ALL WORKS CONTAINED ON THE FOLLOWING DRAWINGS MUST BE				
OBTAINED (DEVELOPMENT APPLICATION, CONSTRUCTION CERTIFICATE,				
AND/OR COMPLYING DEVELOPMENT CERTIFICATE) PRIOR TO				
COMMENCEMENT OF CONSTRUCTION.				

A1 ORIC	GINAL						
				Issued for: DEVELOPEMENT APPLICATION	Title:	Initial:	Date:
				Approved by:	DESIGN	R.M	15.04.2025
				Date : 16.05.25 Rhys Mikhail Director Principal Engineer NER: 2570082 RPEQ: 17480 BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus) AP	DRAWN	S.M	15.04.2025
Α	16.05.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M		CHECKED	R.M	16.05.2025
Rev:	Date:	Description:	Reviewed:		APPROVED	R.M	16.05.2025

NOT FOR CONSTRUCTION



CIVIL CONSULTING ENGINEERS



PROPOSED RESIDENTIAL FLAT BUILDING -96 PARK STREET & 4 KUNARI PLACE, MONA VALE

ONSITE DRAINAGE CALCULATIONS - NORTHERN BEACHES COUNCIL WATER MANAGEMENT POLICY (2021)

· ·	·
	3,071 m ²
	Region 1
	RESIDENTIAL FLAT BUILDING
(EXISTING)	1,610 m 2 (52% IMPERVIOUS)
(PROPOSED)	1,911 m 2 (62% IMPERVIOUS)
OUS AREA	301 m 2 > 50 m 2
REQUIRED	10.0 m ³
Ð	16.0 m ³ IN TOTAL

WATER SENSITIVE URBAN DESIGN TO NORTHERN BEACHES COUNCIL: WSUD & MUSIC MODELLING GUIDLINES

	% REDUCTION OCEAN PROTECT	% REDUCTION ATLAN	TARGET
(TSS)	88	85 %	85 %
	68	83 %	65 %
	62	71 %	45 %
	100	100 %	90 %

NOTE:

SUBSTITUTION OF AN "EQUIVALENT" DEVICE FOR THE DRMWATER TREATMENT MEASURE APPROVED UNDER DEVELOPMENT CONSENT MUST SUBMITTED TO THE NCIPAL CERTIFYING AUTHORITY FOR APPROVAL PRIOR TO INSTALLATION.

STORMWATER PUMPOUT (WET WELL PP1) CALCULATIONS TO AS3500.3 PROVIDE TWO CENTRIFUGAL DRAINAGE SUMP PUMPS WITH SINGLE-PHASE ELECTRIC MOTOR CAPABLE OF DISCHARGING 10.0 L/S EACH AGAINST A TOTAL HEAD OF (3.0m) WITH 10 STARTS PER HOUR MAXIMUM. CLASS 1 ZONE 2 CERTIFIED PUMPS FOR HAZARDOUS AREAS ARE REQUIRED SWITCHING SHALL PROVIDE FOR ALTERNATIVE OPERATION OF THE PUMPS, HIGH LEVEL SWITCH ON/OFF, 2ND PUMP, AND A RED LIGHT ALARM PLACED PERMANENTLY IN THE BASEMENT AREA ACTIVATED BY HIGH LEVEL SWITCH ON. FINAL PUMP OUT VOLUME AND PUMP DUTY IS SUBJECT TO DETAILED GEOTECHNICAL INFORMATION OBTAINED DURING EARTHWORKS AND EXCAVATION. REQUIRED VOLUME: AREA DRAINING TO THE PUMPOUT PIT = 63 m^2 (DRIVEWAY AREA) SEEPAGE AREA DRAINING TO THE PUMPOUT PIT: (BASEMENT) SEEPAGE RATE (WALLS) $= 1-5 L/min/m^{2}$ SEEPAGE RATE (SLABS) $= 0.5 - 2 L/min/m^{2}$ BASEMENT SEEPAGE RUNOFF = 0.23 L/s (TBC PRIOR TO CONSTRUCTION) = $[C \times | (100 \text{ YR}, 2 \text{ HR}) \times A / 3600] + \text{SEEPAGE RUNOFF}$ Q = [(1.08 x 50.6 x 63) / 3600] + 0.23 = 0.96 + 0.23= 1.19 L/s VOLUME ACCUMULATED (100 YEAR ARI, 2 HOUR STORM): $= (1.19L/s_x 2hrs \times 3600s)/1000$ V_{100/120} $= 8.54 \text{ m}^3$ WET WELL STORAGE CAPACITY VOLUME PUMPED IN 30 MINS: $= V_{100/120} - PC_{30} = 0.00 m^{3}$ $= (10.0L/s \times 0.5hrs \times 3600s)/1000$ $= 18.00 \text{ m}^3$ PROVIDE V_{100/120} = 8.54 m VOLUME PUMPED IN 5 MINS: $= (10.0L/s \times 0.083hrs \times 3600s)/1000$ $= 3.00 \text{ m}^{3}$ WET-WELL VOLUME AND SPECIFICATIONS TO BE CONFIRMED DURING TO CONSTRUCTION IN ACCORDANCE WITH GEOTECHNICAL AND STRUCTURAL REQUIREMENTS.



Client:

MONA VALE CENTRAL PTY LTD

STORMWATER . CIVIL . FLOOD MITIGATION

ABN: 81 615 065 588 Phone: 0490 507 300 Email: admin@rtscivil.com.au Web: rtscivil.com.au

he document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or

liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.



SURVEY NOTES:

1. THE EXISTING SITE CONDITIONS SHOWN ON THE FOLLOWING DRAWINGS HAVE BEEN INVESTIGATED BY THE PROJECT SURVEY. THE INFORMATION IS SHOWN TO PROVIDE A BASIS FOR DESIGN. RTS CIVIL CONSLTING ENGINEERS PTY LTD DOES NOT GUARANTEE THE ACCURACY OR COMPLETENESS OF THE SURVEY BASE.

2. SHOULD DISCREPANCIES BE ENCOUNTERED DURING CONSTRUCTION BETWEEN THE SURVEY DATA AND ACTUAL FIELD DATA, CONTACT THE ENGINEER. 3. REFERENCE SHOULD BE MADE DIRECTLY TO THE SURVEYOR BEFORE SETTING OUT.

EXISTING UNDERGROUND SERVICES NOTES:

I. THE LOCATIONS OF UNDERGROUND SERVICES SHOWN IN THIS SET OF DRAWINGS HAVE BEEN PLOTTED FROM SURVEY INFORMATION AND SERVICE AUTHORITY INFORMATION. THE SERVICE INFORMATION HAS BEEN PREPARED ONLY TO SHOW THE APPROXIMATE POSITIONS OF ANY KNOWN SERVICES AND MAY NOT BE AS CONSTRUCTED OR ACCURATE. 2. RTS CIVIL CONSULTING ENGINEERS PTY LTD CANNOT GUARANTEE THE SERVICES INFORMATION SHOWN ON THESE DRAWINGS ACCURATELY INDICATES THE PRESENCE OR ABSENCE OF SERVICES OR THEIR LOCATION AND WILL ACCEPT NO LIABILITY FOR INACCURACIES IN THE SERVICES INFORMATION SHOWN FROM ANY CAUSE WHATSOEVER. 3. CONTRACTORS SHALL TAKE DUE CARE WHEN EXCAVATING ONSITE INCLUDING HAND EXCAVATION WHERE NECESSARY. 4. CONTRACTORS ARE TO CONTACT THE RELEVANT SERVICE AUTHORITY PRIOR TO COMMENCEMENT

OF EXCAVATION WORKS. 5. CONTRACTORS ARE TO UNDERTAKE A SERVICES SEARCH, PRIOR TO COMMENCEMENT OF WORKS ON SITE. SEARCH RESULTS ARE TO BE KEPT ON SITE AT ALL TIMES. 6. CONTRACTOR IS TO CONFIRM FINDINGS FOR THE LOCAL COUNCL OR SYDNEY WATER IN RELATION TO THE SEWER OR WATER MAINS LOCATED. CONFIRMATION OF MAINS IS REQUIRED PRIOR TO CONSTRUCTION. POSSIBLE CONFLICT OF SERVICES ARE TO BE REPORTED TO THE SUPERINTENDENT OR ENGINEER FOR FURTHER DIRECTIONS.

EXTERNAL NOTES:

1. ALL ACTIVITIES AND WORKS EXTERNAL TO THE SITE, OR THAT AFFECT PUBLIC ROADS, ARE TO BE CARRIED OUT IN ACCORDANCE WITH COUNCIL'S CODES AND STANDARDS. 2. PUBLIC FOOTPATHS SHALL BE RECONSTRUCTED TO THE SATISFACTION OF COUNCIL'S DIRECTOR OF ENGINEERING SERVICES. A ROAD OPENING PERMIT SHALL BE OBTAINED FOR ALL WORKS CARRIED OUT IN A PUBLIC OR COUNCIL CONTROLLED LAND. 3. RESTORATION OF LANDSCAPING, ROADS AND PATHS SHALL BE TO COUNCIL'S REQUIREMENTS. ALL OTHER RESTORATION SHALL BE TOTHE SATISFACTION OF THE AFFECTED PARTIES. 4. WHERE WORKS ARE UNDERTAKEN ON PUBLIC ROADS, ADEQUATE TRAFFIC CONTROL AND DIRECTIONS TO MOTORISTS SHALL BE PROVIDED BY OTHERS.

DRAWING SCHEDULE:

SHEET 1 OF 2

SW001 - COVERPAGE, NOTES & CALCULATIONS SHEET 1 OF 2 SW002 - COVERPAGE, NOTES & CALCULATIONS SHEET 2 OF 2 SE100 - SEDIMENT & EROSION CONTROL PLAN SE200 - SEDIMENT & EROSION CONTROL PLAN DETAILS SW100 - BASEMENT 2 STORMWATER MANAGEMENT PLAN SW101 - BASEMENT 1 STORMWATER MANAGEMENT PLAN SW102 - LEVEL 2 STORMWATER MANAGEMENT PLAN SW103 - SITE STORMWATER CATCHMENT PLAN SW200 - STORMWATER DRAINAGE DETAILS SHEET 1 OF 3 SW201 - STORMWATER DRAINAGE DETAILS SHEET 2 OF 3 SW202 - STORMWATER DRAINAGE DETAILS SHEET 3 OF 3 www.dialbeforeyoudig.com.au FORE YOU DI NO INVESTIGATION OF UNDERGROUND SERVICES HAS BEEN MADE. ALL RELEVANT AUTHORITIES SHOULD BE NOTIFIED PRIOR TO ANY EXCAVATION ON OR NEAR THE SITE DEVELOPERS & EXCAVATORS MAY BE HELD FINANCIALLY RESPONSIBLE BY THE ASSET OWNER SHOULD THEY DAMAGE UNDERGROUND NETWORKS CARELESS DIGGING CAN: DIGGING CAN: - CAUSE DEATH OR SERIOUS INJURY TO WORKERS AND THE GENERAL PUBLIC INCONVENIENCE USERS OF ELECTRICITY, GAS, WATER AND COMMUNICATIONS - LEAD TO CRIMINAL PROSECUTION AND DAMAGES CLAIMS - CAUSE EXPENSIVE FINANCIAL LOSSES TO BUSINESS CUT OFF EMERGENCY SERVICES - DELAY PROJECT COMPLETION TIMES WHILE THE DAMAGE IS REPAIRED MINIMISE YOUR RISK AND DIAL BEFORE YOU DIG. - TEL. 1100 ALL DIMENSIONS MUST BE VERIFIED ON SITE BY BUILDER BEFORE COMMENCING WITH WORK. Local Council: NORTHERN BEACHES 94-96 PARK STREET & 4 KUNARI PLACE, MONA VALE Project Number: Drawing ID: lssue: COVERPAGE, NOTES & CALCULATIONS **SW00** 250302

STORMWATER PUMP-OUT AND 'WET WELL' NOTES:

1. PUMPED SYSTEMS ARE FOR AREAS NORMALLY LESS THAN 2,000m2 WHERE IT IS NOT POSSIBLE FOR THE STORMWATER TO BE DISCHARGED BY GRAVITY THROUGH THE AVAILABLE GRAVITATIONAL POINT OF CONNECTION. ALL WORKS ARE TO BE IN ACCORDANCE WITH AS3500.3 - PLUMBING AND DRAINAGE: STORMWATER DRAINAGE - SECTION 9 - PUMPED SYSTEMS.

2. TO ENSURE THAT SEEPAGE WATER IS NOT BEING PUMPED CONTINUALLY OUT TO THE STREET. THE PUMPS IN THE BASEMENT OR LOWER LEVEL OF PROPERTY SHALL BE ADJUSTED TO PERMIT STORAGE IN THE SYSTEM PRIOR TO THE PUMPS SWITCHING ON (REFER DETAILS FOR STORAGE VOLUME AND LEVELS). THE PUMPS SHOULD THEN DISCHARGE ALL WATER SO THAT ONLY MINIMAL WATER REMAINS OVER THE PUMP INTAKE, AS REQUIRED BY THE MANUFACTURER.

3. THE PUMPS SHALL OPERATE ALTERNATELY TO LEVELS INDICATED ON THE SUPPLIED ENGINEERING DETAILS WITH BOTH PUMPS OPERATING IN UNISON AT THE LEVELS INDICATED (SYSTEM TO BE FITTED WITH ALARM SYSTEM - BY OTHERS). THE SECOND PUMP WILL BEING TO OPERATE IF THE WATER LEVEL CONTINUES TO RISE ABOVE THE MAXIMUM WATER LEVEL AFTER THE FIRST PUMP HAS COME ON. SIGNAGE IS TO BE DISPLAYED WITHIN THE LOW AREA OF THE BASEMENT INDICATING PERMIT ADDITIONAL STORAGE VOLUME IS EXPECTED (UP TO 200mm IN DEPTH) DURING A MAJOR STORM EVENT.

4. THE REQUIRED PUMPING RATE SHALL BE CALCULATED BASED ON AN ASSESSMENT OF THE EXPECTED INFLOW AND, WHERE APPROPRIATE, THE ALLOWABLE DISCHARGE RATE. HOWEVER, UNLESS NOTED OTHERWISE, THE MINIMUM PUMP CAPACITY OF A BASEMENT (BELOWGROUND) SYSTEM SHOULD NOT BE LESS THAN 10 L/s. 5. PUMPS SHALL BE IN DUPLICATE. THE MAXIMUM CAPACITY OF EACH PUMP SHALL BE SELECTED SO THAT THE CAPACITY OF THE SYSTEM RECEIVING THE DISCHARGE IS NOT EXCEEDED. THE PUMP CONTROLS SHALL BE SET UP TO ENABLE ALTERNATE PUMP OPERATION AT EACH START. IN THE EVENT THAT A PUMP FAILS TO OPERATE WHEN THE WATER LEVEL IN THE WET WELL REACHES THE PUMP START. THE OTHER PUMP SHALL BE ACTIVATED AND A VISIBLE ALARM INITIATED. IF BOTH PUMPS FAIL TO OPERATE AN AUDIBLE ALARM SHALL BE INITIATED IN ACCORDANCE WITH SECTION 8.3.7 OF AS3500.3. LOCATE HIGH AND LOW LEVEL ALARMS CLEAR OF INLETS TO PREVENT FALSE ALARMS. THE HIGH LEVEL ALARM SHOULD BE SET NO HIGHER THAN 100 MM ABOVE THE INVERT OF THE INLET PIPE, PROVIDED THAT FLOODING OF HABITABLE OR STORAGE AREAS AND VEHICLE GARAGES SHALL BE AVOIDED. WHERE FLOODING COULD OCCUR THE OVERFLOW AND HIGH-LEVEL ALARM SHALL BE LOWERED ACCORDINGLY TO PREVENT FLOODING.

6. THE MINIMUM WET WELL STORAGE BETWEEN THE HIGH AND LOW WORKING LEVELS EXPRESSED IN CUBIC METRES SHALL BE 1% OF THE CATCHMENT AREA IN m2 BUT IN ANY CASE SHALL NOT BE LESS THAN 3 m3, OR AS OTHERWISE DIRECTED OR APPROVED BY THE AUTHORITY HAVING JURISDICTION.

7. THE CAPACITY OF THE PUMPED SYSTEM (WET WELL) SHALL BE ACHIEVED BY A COMBINATION OF PUMP CAPACITY AND WET WELL STORAGE BETWEEN THE HIGH AND LOW WORKING LEVELS OF THE WET WELL. THE COMBINED EFFECTIVE STORAGE COMPRISING THE VOLUME ABLE TO BE PUMPED IN 30 MIN PLUS THE WET WELL STORAGE SHALL NOT BE LESS THAN THE VOLUME OF THE RUN-OFF FROM THE STORM OF ARI = 10 YEARS AND DURATION OF 120 MIN, OR AS OTHERWISE DIRECTED BY THE AUTHORITY HAVING JURISDICTION. 8. PUMPING EQUIPMENT SHALL BE SECURELY FIXED TO THE WET WELL USING CORROSION RESISTANT FIXINGS. 9. PUMPS SHALL BE FITTED WITH A GATE VALVE AND NON-RETURN VALVE ON THE DELIVERY SIDE OF EACH PUMP

10. PUMPS SHALL HAVE FLANGES OR UNIONS INSTALLED TO FACILITATE REMOVAL 11. PUMPS SHALL BE CONTROLLED SO AS TO LIMIT THE NUMBER OF STARTS PER HOUR TO WITHIN THE CAPACITY OF THE ELECTRICAL MOTORS AND EQUIPMENT, AND SHALL, AS FAR AS PRACTICABLE, EMPTY THE CONTENTS OF THE WET WELL AT EACH OPERATION.

12. PUMPS ARE TO OPERATE ONLY DURING HOURS SPECIFIED BY THE AUTHORITY HAVING JURISDICTION 13. VALUE OF HEAD IS TO BE CONFIRMED ONCE EXCAVATION COMPLETE AND PRIOR TO ORDERING PUMPS AND EQUIPMENT.

14. PUMP SPECIFICATIONS AND PRESSUE PIPE DIAMETER ARE TO BE DETERMINED BY THE PUMP MANUFACTURER.

15. PROVIDE LITTER SCREEN ABOVE PUMP SET. 16. ALL ELECTRICAL MOTORS AND EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH AS3000.

INSTALLATION OF PIPEWORK NEAR AND UNDER **BUILDINGS NOTES:**

THE FOLLOWING APPLY TO A DRAIN IN CLOSE PROXIMITY TO FOOTINGS OR FOUNDATIONS: 1. WHERE THE DRAIN PASSES UNDER A STRIP FOOTING. ITS ANGLE OF INTERSECTION WITH THE FOOTING IN THE HORIZONTAL PLANE SHALL BE NOT LESS THAN 45', AND THE MINIMUM CLEARANCE BETWEEN THE TOP OF THE DRAIN TO THE UNDERSIDE OF THE FOOTING SHALL BE 25mm 2. IF THE DRAIN IS LAID THROUGH FOOTINGS OR WALLS, OTHER THAN BELOW-GROUND EXTERNAL WALLS,

IT SHALL BE INSTALLED WITH AN ANNULAR SPACE OF NOT LESS THAN 25mm FILLED WITH A LINER OF FLEXIBLE MATERIAL. 3. THE DRAIN MAY BE LAID THROUGH BELOW-GROUND EXTERNAL WALLS, PROVIDED-

a. TWO FLEXIBLE JOINTS ARE PROVIDED EXTERNALLY WITHIN 800mm OF THE EXTERNAL FACE OF THE WALL, AND SUCH JOINTS ARE NOT LESS THAN 600mm APART; AND b.THE PENETRATION OF THE WALL IS MADE WATERTIGHT.

4. WHERE THE DRAIN IS TO BE LAID PARALLEL TO A FOOTING. THE TRENCH SHALL BE LOCATED AS FOLLOWS:

a. THE DRAIN SHALL BE LAID-

b. IN ACCORDANCE WITH NCC VOLUME TWO; AND c. FOR SINGLE DWELLINGS, AS SHOWN IN FIGURE 6.2.8 OF AS3500.3.

INSPECTIONS BY ENGINEER

48 HOURS NOTICE IS REQUIRED BEFORE ANY SITE INSPECTION. ANY STRUCTURAL ELEMENT NOT INSPECTED BY RTS CIVIL WILL NOT BE CERTIFIED BY RTS CIVIL CONSULTING ENGINEERS PTY LTD. 1. BEARING STRATA OF ALL FOOTINGS PRIOR TO CONCRETE POUR BY GEOTECHNICAL ENGINEER.

2. ANY REINFORCEMENT PRIOR TO CONCRETE POUR. 3. TIMBER AND STEEL FRAMING PRIOR TO CLADDING OR LINING.

4. STEEL LINTELS AFTER INSTALLATION.

5. CONTACT YOUR PCA (PRINCIPAL CERTIFYING AUTHORITY) AS TO REQUIREMENTS FOR MANDATORY

CRITICAL STAGE INSPECTIONS IN ACCORDANCE WITH REVISED EP&A ACT REGULATIONS EFFECTIVE JULY 1. 2004. 6. INSPECTION BY GEOTECHNICAL ENGINEER OVER 1.5m OF VERTICAL CUT THROUGH SANDSTONE BED

ROCK TO PERMIT IDENTIFICATION OF DEFECTS AND REMEDIAL MEASURES INITIATED. 7. SCHEDULE OF CONSTRUCTION STAGES REQUIRING INSPECTION:

a. FOLLOWING PLACEMENT OF PIPE BEDDING MATERIAL. CONFIRM TRENCH/PIPE LOCATION, ADEQUACY OF

DEPTH OF COVER, BEDDING MATERIAL AND DEPTH. b. FOLLOWING JOINING OF PIPES AND CONNECTION TO COUNCIL'S STORMWATER SYSTEM.

c. FOR DISPERSION TRENCH SYSTEMS: -

(i) FOLLOWING SET OUT TO CONFIRM LOCATION, LENGTH AND VOLUME OF STORAGE.

INFILTRATION/ABSORPTION TRENCH NOTES (METHOD 1):

TOP OF THE LINER. "PONDING".

3. ALLOW AT LEAST 75mm OVERLAP FOR EACH LENGTH OF EVERTRENCH. TANK OR SULLAGE DISTRIBUTOR.

COVERED. RAKE LEVEL

IT TO TRAFFIC.

LEAST 100mm BELOW THE SOIL SURFACE LEVEL. COUNCIL REQUIREMENTS

CONSTRUCTION AND EXCAVATION OF TRENCHES TO CONFIRM SUITABILITY OF SOILS. 12. WHERE POSSIBLE, INSTALL HIGH LEVEL EMERGENCY OVERFLOW PIPE AND CONNECT TO SITE DRAINAGE

TRANSPIRATION/DISPERSION TRENCH NOTES (METHOD 2):

LEVEL, EVENLY RAKED, WITH NO LOW SPOTS. 3. CARRY OUT STEPS 3, 4, 5, 6 & 7 LISTED FOR METHOD 1 (ABSORPTION TRENCH) 100mm OF COARSE SAND, AND FINALLY WITH SANDY LOAM. AREA OR EXPOSE IT TO TRAFFIC. WIDTH. AND FILLED WITH AGGREGATE TO ALLOW EASIER MOVEMENT OF MOISTURE.



	L	(
•		

NOTE:					
THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE OF THE DRAINAGE DISCHARGE PIPES.		COUNCI ALL W OBTAINE ANI	NOTE: L AND/OR PRIVATE CERTIFYING AUTHORITY A ORKS CONTAINED ON THE FOLLOWING DRAWIN D (DEVELOPMENT APPLICATION, CONSTRUCTIO O/OR COMPLYING DEVELOPMENT CERTIFICATE) COMMENCEMENT OF CONSTRUCTION.	PPROVAL FOR IGS MUST BE IN CERTIFICATE PRIOR TO	-, ,
A1 ORIGINAL					
			Issued for: DEVELOPEMENT APPLICATION	Title:	Initial:
			Approved by:	DESIGN	R

A1 ORIC	GINAL	-					
				Issued for: DEVELOPEMENT APPLICATION	Title:	Initial:	Date:
				Approved by:	DESIGN	R.M	15.04.202
				Date : 16.05.25 R . Mini Rhys Mikhail	DRAWN	S.M	15.04.202
А	16.05.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M		CHECKED	R.M	16.05.202
Rev:	Date:	Description:	Reviewed:	Director Principal Engineer NER: 2570082 RPEQ: 17480 BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)	APPROVED	R.M	16.05.202

NOT FOR CONSTRUCTION

- 1. EXCAVATE THE TRENCH ALONG A LEVEL SITE CONTOUR TO PROVIDE AT LEAST 100mm COVER OVER THE
- 2. THE TRENCH FLOOR SHOULD BE LEVEL, EVENLY RAKED, AND HAVE NO LOW SPOTS WHICH WOULD ALLOW
- 4. IDEALLY, THREE SPREADER BARS (OPTIONAL) SHOULD BE FITTED INTO EACH STANDARD EVERTRENCH LINER, THE FIRST 220mm FROM THE INLET END, THEN EQUALLY SPACED ALONG THE EXCAVATION. 5. CUT THE PIPE ENTRY HOLE IN ONE TRENCH LINER END CAP. AN EASYDRAIN™ PIT BOSS MAY BE USED TO ENSURE A SECURE CONNECTION. FIT THE CAPS TO THE LINER AND CONNECT THE PIPING FROM THE SEPTIC
- 6. COVER THE EVERTRENCH WITH GEOTEXTILE FABRIC AND PLACE A QUANTITY OF 20-25mm AGGREGATE MATERIAL ALONG THE TRENCH LINER AND AT BOTH ENDS, SO THAT THE TOP OF THE LINER IS JUST
- 7. LAY GEOTEXTILE OVER THE AGGREGATE FOR THE FULL LENGTH OF THE TRENCH. 8. COVER THE GEOTEXTILE WITH A LAYER OF APPROVED SANDY LOAM AND LEAVE A MOUND FOR NATURAL COMPACTION. TURF MAY BE LAID OVER THE TRENCH AREA. DO NOT COMPACT THE TRENCH AREA OR EXPOSE
- 9. THESE TRENCHES ARE GENERALLY LIMITED TO SITES WHERE SOIL IS CONSIDERED PERMEABLE ENOUGH TO "SOAK UP" THE EXPECTED AMOUNTS OF WASTE-WATER. THE TRENCH SHOULD BE WIDE ENOUGH TO ACCEPT THE SELECTED EVERTRENCH LINER AND DEEP ENOUGH SO THAT THE TOP OF THE SELECTED LINER IS AT
- 10. TRENCH TO BE HAND DUG AROUND TREE ROOT SYSTEM IN ACCORDANCE WITH ARBORIST AND/OR LOCAL 11. A GEOTECHNICAL ENGINEERS REPORT OR RECOMMENDATIONS MAY BE REQUIRED FOR AREAS OF LOW SOIL
- INFILTRATION RATES OR FOR LARGER DEVELOPMENTS. THE ENGINEER SHOULD BE NOTIFIEDDURING
- SYSTEM OR NEAREST DISCHARGE POINT IN ACCORDANCE WITH AS3500.3.2 AND/OR COUNCIL REQUIREMENTS. 13. DO NOT CONNECT SUB-SOIL DRAINAGE LINES THAT ARE LESS THAN 150mm ABOVE THE SURFACE LEVEL OF THE TRENCH. NOTIFY ENGINEER IF THE DEVELOPMENT HAS LOW LAYING SUB-SOIL DRAINAGE LINES ..
- 1. EXCAVATE AN AREA 1800mm WIDE AND 300mm DEEP ALONG A LEVEL SITE CONTOUR. 2. EXCAVATE A CENTRAL TRENCH ALONG THE FULL LENGTH OF THE PREPARED AREA FOR THE SELECTED LINER. THE TOP OF THE LINER SHOULD BE LEVEL WITH THE BOTTOM OF THE PREPARED AREA. THE FLOOR SHOULD BE
- 4. COVER THE GEOTEXTILE AND FLOOR OF THE WIDER EXCAVATION WITH 100mm OF 10mm AGGREGATE, THEN
- 5. LEAVE A MOUND FOR NATURAL COMPACTION. TURF MAY BE LAID OVER THE AREA. DO NOT COMPACT THE
- 6. THIS METHOD ARE GENERALLY USED WHERE LOCAL SOIL CONDITIONS CANNOT COPE WITH THE VOLUME OF WASTE-WATER IN THE NORMAL NARROW ABSORPTION TRENCH SYSTEMS. TRANSPIRATION ENCOURAGES TREATED WASTE-WATER TO BE TAKEN UP BY PLANT ROOTS OVER A WIDE AREA, AS WELL AS PERMEATING THE SOIL, OFFERING ADDITIONAL SAFETY FOR SOIL ABSORPTION SYSTEMS. BEDS CONSIST OF STANDARD WIDTH TRENCHES THAT ARE DEEPER THAN NORMAL. WITH THE AREA ABOVE THE SELECTED TRENCH LINER OF MUCHGREATER

OCALITY PLAN NOT TO SCALE

RAINWATER HARVESTING REQUIREMENTS:

1. CONSIDERING THE ROOF CATCHMENT AREA, LOCATION OF PROPERTY, INTENDED USE OF RAINWATER AND GARDEN SIZE WE RECOMMEND PROVIDING A RAINWATER TANK FOR USE AS PER BASIX REQUIREMENTS, HCCRENS WATER SMART PRACTICE NOTE (N).4) AND THE NSW HEALTH REQUIRMENTS FOR NON DRINKING USE ONLY AS FOLLOWS: a) TO WATER GARDEN AREAS b) TO BASIX REQUIREMENTS

2. THE TANKS PROVIDED WILL REDUCE PRESSURE ON COUNCIL'S STORMWATER INFRASTRUCTURE.

3. REFERENCES: COOMBES P.J. & KUCZERA G. (2001), "RAINWATER TANK DESIGN FOR WATER SUPPLY & STORMWATER MANAGEMENT." STORMWATER INDUSTRY ASSOCIATION REGIONAL CONFERENCE. PATRICK DUPONT & STEVE SHACKEL, "RAINWATER" AUSTRALIAN GOVERNMENT (2004), "GUIDANCE ON USE OF RAINWATER TANKS".

4. ALL CONNECTIONS TO PLUMBING AND RAINWATER TANKS TO BE IN ACCORDANCE WITH SYDNEY WATERS' GUIDE "INSTALLING A RAINWATER TANK" AVAILABLE AT www.sydneywater.com.au OR

FROM LOCAL COUNCIL GUIDLINES. 5. PROVIDE A DUAL SUPPLY SYSTEM AND BACKFLOW PREVENTION SYSTEM IN ACCORDANCE WITH 'BASIX-DESIGN GUIDE FOR SINGLE DWELLINGS' BY NSW DEPARTMENT OF INFRASTRUCTURE, PLANING AND NATURAL RESOURCES AND AS3500.1.

6. IF NOT SPECIFIED ON PLANS, THE FIRST FLUSH SYSTEM IS TO HAVE A MINIMUM SIZE OF 20L PER 100m2 OF ROOF CATCHMENT AREA PRIOR TO ENTERING THE RAINWATER TANK. INDIVIDUAL SITE ANALYSIS IS REQUIRED IN HEAVILY POLLUTED AREAS TO DETERMINE IF LARGER VOLUMES OF FIRST FLUSH RAINWATER ARE TO BE DIVERTED. IF IN DOUBT, CHECK WITH LOCAL HEALTH AUTHORITIES.

7. SCREENED DOWNPIPE RAINWATER HEAD OR OTHER SUITABLE LEAF AND DEBRIS DEVICE TO BE INSTALLED ON EACH DOWNPIPE. SCREEN MESH TO BE 4-6mm AND DESIGNED TO BE SELF-CLEANING.

8. FIRST FLUSH DEVICES, OR APPROVED ALTERATIVE, TO BE INSTALLED WITH AN AUTOMATED DIVERSION AND DRAINAGE SYSTEM, THAT IS, NO MANUAL DIVERSION AND DRAINAGE VALVES. REFER TYPICAL FLUSH OUT PIT FOR DETAILS. THIS SHOULD CATER FOR THE FIRST 1mm OF RAINFALL.

9. BEFORE PURCHASING MATERIALS OR PAINT TO BE USED ON ROOF CATCHMENT AREAS. THE MANUFACTURER'S RECOMMENDATIONS ON LABELS AND BROCHURES FOR RAINWATER TANK SUITABILITY TO BE READ AND ADHERED TO.

10. PRE-STORAGE PITS FOR UNDERGROUND RAINWATER STORAGE TANKS AND FLUSH OUT PITS MAY ASSIST IN LIMITING SILT, AND PREVENT VERMIN, INSECTS (INCLUDING MOSQUITOES) AND DEBRIS FROM ENTERING THE RAINWATER STORAGE AREA.

11. RAINWATER TANK TO BE WATER PROOFED IN ACCORDANCE WITH HB 230-200B 12. BUILDER OR PLUMBER TO ENSURE THE INSTALLATION OF THE RAINWATER TANK SYSTEM IS IN ACCORDANCE WITH THE RELEVANT AUSTRALIAN STANDARDS AND THE RAINWATER TANK DESIGN AND INSTALLATION HANDBOOK - HB 230-2008. IF IN DOUBT CONTACT ENGINEER. 13. NOISE EMISSIONS FROM ANY PUMPS DO NOT EXCEED 5dB(A) ABOVE AMBIENT

BACKGROUND NOISE LEVEL MEASURED AT THE ALLOTMENT BOUNDARY. 14. AT THE COMPLETION OF THE WATER SERVICE INSTALLATION AND PRIOR TO HYDROSTATIC TESTING. THE SYSTEM SHALL BE THOROUGHLY FLUSHED TO REMOVE ANY FOREIGN MATTER. THE FLUSHING SHALL BE UNDERTAKEN IN ACCORDANCE WITH AS3500.1 REQUIREMENTS -APPENDIX I. PARAGRAPH 13 AND CONTINUE UNTIL THE FLUSHED WATER RUNS COMPLETELY CLEAR. THE SYSTEM SHALL THEN BE PRESSURE TESTED IN ACCORDANCE WITH CLAUSE 16.3.1.

15. AT THE COMPLETION OF THE WATER SERVICE INSTALLATION THE RAINWATER STORAGE TANKS ARE TO BE TESTED IN ACCORDANCE WITH SECTION 16 OF AS3500.1.

SEDIMENT BASIN CALCULATIONS ACCOR CONTROL ASSOCIATION (IECA) 2008 AND B	DING TO INTERNATIONAL EROSION EST PRACTICE EROSION REQUIREMENTS					
SEDIMENT BASIN SELECTION	TYPE C As = Ks He O					
	$= 3410 \times 1.2 \times (0.5 \times 0.026)$ $= 92.1 \text{ m}^2$					
TOTAL SETTLING VOLUME	$V = 92.1 \times 0.6$ = 53.2 m ³					
As = AVERAGE SURFACE AREA OF SETTLING ZO Ks = SEDIMENT SETTLENT COEFFICIENT = 3410 He = HYDRAULIC EFFICIENCY CORRECTION FACT Q = DESIGN DISCHARGE = $0.5 \times Q1$ Q1 = 1 in 1 YEAR ARI DISCHARGE FOR SITE =	WHERE: As = AVERAGE SURFACE AREA OF SETTLING ZONE Ks = SEDIMENT SETTLENT COEFFICIENT = 3410 He = HYDRAULIC EFFICIENCY CORRECTION FACTOR = 1.2 Q = DESIGN DISCHARGE = 0.5 x Q1 Q1 = 1 in 1 YEAR ARI DISCHARGE FOR SITE = 26 L/s					
REDUCED SETTLING VOLUME DUE TO PUMP-OUT	Γ (DRAWDOWN):					
$V_{in} = C \times I \times A = 0.7 \times 0.093 \times 3071 = 200 m^{3}/hr$						
$Q_{pump} = V_{in} / T_{drawdown}$ $= 200 / 72$ $= 2.78 m^{3}/hr$						
$V_{\text{settling}} = \frac{0.77 \text{ L/s}}{(\text{PROVIDE MIN. PUMP OUT RATE WITH 3.0m PRESSUE HEAD)}$ $V_{\text{settling}} = \frac{(\text{g x (FINE SILT PARTICLE SIZE}^2)(\text{SEDIMENT DENSITY x WATER DENSITY})}{18 \text{ x DYNAMIC VISCOSITY OF WATER}}$ $= \frac{(9.81 \text{ x } (0.0002^2)(2650 \text{ x } 1000)}{18 \text{ x } 0.001}$						
= 0.094 m/hr						
$= (200 \times 6) / 72$						
$= 16.7 \text{m}^3$ (PROVIDE MIN. VOL	UME FOR 0.6m DEPTH)					

Architect: Project and Drawing Title: **CIVIL CONSULTING** WALSH ARCHITECTS 94-96 PARK STREET & **ENGINEERS** 4 KUNARI PLACE, MONA VALE STORMWATER • CIVIL • FLOOD MITIGATION Client: COVERPAGE, NOTES & CALCULATIONS ABN: 81 615 065 588 Phone: 0490 507 300 Email: admin@rtscivil.com.au Web: rtscivil.com.au MONA VALE CENTRAL PTY LTD SHEET 2 OF 2 The document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or ability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.

SEDIMENT AND EROSION CONTROL NOTES:

1. SILT FENCE AND ASSOCIATED WORKS INCLUDING INTERCEPTOR DRAIN IS TO BE INSTALLED BEFORE THE COMMENCEMENT OF ANY EXCAVATION.

2. GEOTECHNICAL ENGINEER IS TO PROVIDE SITE STABILITY REQUIREMENTS. CUTS ARE TO BE EXECUTED TO THE REQUIRED LEVEL USING CONVENTIONAL EXCAVATION MACHINERY. AS A GUIDE, INITIALLY THE DEPTH OF FILL/CLAY IS TO BE ESTABLISHED TO ENSURE NEIGHBOURING PROPERTIES ARE NOT ADVERSELY AFFECTED. EARTH BATTERS TO BE A MAXIMUM SLOPE OF 1.0m VERT. TO 1.7m HORIZ. (AS PER GEOTECHNICAL REPORT). ANY BATTERS GREATER THAN 1.0m VERT. TO 1.7m HORIZ. ARE TO BE ADEQUATELY SHORED IN ACCORDANCE WITH GEOTECHNICAL ENGINEERS DETAILS AND INSTRUCTIONS.

3. ANY PERMANENT RETAINING STRUCTURE IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS. 4. ALL PERMANENT RETAINING STRUCTURES ARE TO BE COMPLETED WITH MINIMUM DELAY FOLLOWING

EXCAVATION. 5. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSPECTED AND MAINTAINED DAILY BY SITE MANAGER.

6. CONTRCTOR TO MINIMISE DISTURBED AREAS.

7. ALL STOCKPILES TO BE CLEAR FROM DRAINS, GUTTERS AND FOOTPATHS. 8. DRAINAGE IS TO BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE.

ROADS AND FOOTPATH TO BE SWEPT DAILY.

10. CONSTRUCTION VEHICLES ARE TO LEAVE AND ENTER THE SITE OVER AN ALL WEATHER SURFACE CONSISTING OF COURSE CRUSHED STONE OR BLUE METAL CONSTRUCTED WITHIN THE FRONT SETBACK AREA OPPOSITE THE EXISTING FOOTPATH CROSSING UNLESS NOTED OTHERWISE.

11. EXCAVATION MACHINERY ARE TO BE UNLOADED AND LOADED UPON THIS ALL WEATHER SURFACE. CONCRETE PUMPS AND TRUCKS WILL ALSO UTILISE THE ALL WEATHER SURFACE FOR THEIR OPERATIONS. 12. MATERIALS WILL BE UNLOADED UPON THE ALL WEATHER SURFACE WITHIN THE FRONT SETBACK AREA BY MEANS OF CRANES MOUNTED ON THE BACK OF DELIVERY TRUCKS OR UNLOADED BY HAND. A MOBILE CRANE MAY BE REQUIRED DURING THE CONSTRUCTION PROCESS. 13. SOME STOCKPILING OF TOPSOIL REMOVED FROM THE BUILDING AREA MAY BE STORED ON THE SITE

DURING THE CONSTRUCTION WITHIN THE PROPERTY IN AN AREA ENCLOSED WITHIN THE SEDIMENT CONTROL FENCING. 14. ALL EXCAVATED & CONSTRUCTION MATERIALS, SHED, SKIP BINS, TEMPORARY WATER CLOSETS, SPOIL

AND EQUIPMENT, ETC SHALL BE KEPT WITHIN THE PROPERTY. NO VEHICLES OR MACHINES SHALL BE KEPT WITHIN THE PROPERTY. NO VEHICLES OR MACHINES SHALL STAND ON COUNICIL FOOTPATHS FOR LARGE LENGTHS OF TIME.

15. ALL RUBBISH & RECYCLABLE MATERIAL SHALL BE STOCKPILED IN WASTE BINS IN THE AREA NOMINATED ON THE SITE PLAN WITHIN THE SITE BOUNDARY. PUBLIC PROPERTY SHALL BE KEPT FREE OF RUBBISH AND RECYCLABLES AT ALL TIMES ANY WASTE MATERIALS SHALL BE REGULARLY COLLECTED FROM THE SITE AND DISPOSED OF IN AN APPROPRIATE FASHION. 16. ANY BUILDING OR DEMOLITION WORKS INVOLVING ASBESTOS SHALL BE CARRIED OUT IN ACCORDANCE

WITH THE RELAVANT STANDARDS. 17. VEHICLES LEAVING THE SITE WILL DO SO VIA THE ALL WEATHER BALLAST DRIVEWAY MADE OF COURSE AGGREGATE OR SIMILLAR LOCATED WITHIN THE FRONT SETBACK AREA OF THE DEVELOPMENT. ANY DIRT OR MATERIAL DEPOSITED ON THE ROAD RESERVE OR ROADWAY IS TO BE PROMPTLY CLEANED. 18. ANY EXCAVATED AREA REQUIRING SUPPORT WILL BE UNDERTAKEN BY THE OWNER USING

STRUCTURALLY APPROVED RETAINING STRUCTURES. 19. ADEQUATE SAFETY SIGNAGE MUST BE ERECTED IN A PROMINENT POSITION ON THE WORK SITE, WARNING OF UNAUTHORISED ENTRY TO WORK SITE AND INTENDING DANGERS

20. SAFETY FENCES SHALL BE PROVIDED AROUND ALL BOUNDARIES UNLESS A CONTINUOUS STRUCTURALLY ADEQUATE FENCE PRESENTLY EXISTS. THE FENCING SHALL BE ADEQUATE TO RESTRICT PUBLIC ACCESS TO THE SITE WHEN BUILDING WORK IS NOT IN PROGRESS OR THE SITE IS UNOCCUPIED. 21. NOISE LEVELS SHALL NOT EXCEED COUNCIL REGULATION LEVELS. BUILDING AND DEMOLITION WORKS SHALL ONLY BE CARRIED OUT BETWEEN HOURS AND DAYS SPECIFIED BY COUNCIL. 22. GEOTEXTILE FABRIC SHALL BE PLACED ON THE INSIDE OF THE SITE FENCING PRIOR TO SITE

DISTURBANCE TO PREVENT SEDIMENT WASHING FROM CLEARED AND DISTURBED AREAS OF THE SITE INTO THE STORMWATER SYSTEM. DURING CONSTRUCTION, UNLESS OTHERWSIE NOTED, UNCONTAMINATED RUNOFF FROM CLEARED OR DISTURBED AREAS ARE TO BE DIRECTED TO A TEMPORARY SILT ARRESTOR PIT THAT SHALL BE PROVIDED WITHIN THE SITE AT THE STREET BOUNDARY PROCESSING SITE

STORMWATER BEFORE IT IS DISCHARGED TO THE STREET DRAINAGE SYSTEM OR WATERCOURSE. 23. ALL TOP SOIL STRIPPED & STOCKPILED ONSITE IS TO BE BE PLACED IN NOMINATED AREAS ON PLAN OR TO COUNCIL REQUIREMENTS. ALL DISTURBED AREAS ARE TO BE STABILISED UPON THE COMPLETION OF BUILDING WORKS.

24. ALL SEDIMENT CONTROL STRUCTURES ARE TO BE CONTINUALLY MAINTAINED DURING CONSTRUCTION AND INSPECTED FOR STRUCTURAL DAMAGE AFTER EACH RAINFALL EVENT, WITH TRAPPED SEDIMENT BEING REMOVED TO THE TOPSOIL STOCKPILE.

25. WHERE THERE IS THE POTENTIAL OF SITE EROSION TO PRODUCE EXCESSIVE SEDIMENT RUNOFF, SUITABLE GEOTEXTILE BARRIERS SHALL BE PLACED TO ALLEVIATE THE RISK ACCORDINGLY. BARE SURFACES SHALL BE KEPT MOIST TO REDUCE DUST LEVELS. GEOTEXTILE FABRIC LOCATED ON THE INSIDE OF FENCES SHALL ALSO BE UTILISED FOR DUST CONTROL WHERE NECESSARY.

26. ALL WORK SHALL BE GENERALLY CARRIED OUT IN ACCORDANCE WITH:

a) LOCAL AUTHORITY REQUIREMENTS b) EPA - POLLUTION CONTROL MANUAL FOR URBAN STORMWATER

c) LANDCOM NSW - MANAGING URBAN STORMWATER: SOILS AND CONSTRUCTION ("BLUE BOOK") 27. PRIOR TO DISCHARGE OF SITE STORMWATER, GROUNDWATER AND SEEPAGE WATER INTO COUNCIL'S STORMWATER SYSTEM. CONTRACTORS MUST UNDERTAKE WATER QUALITY TESTS IN CONJUNCTION WITH A SUITABLY QUALIFIED ENVIRONMENT CONSULTANT OUTLING THE FOLLOWING:

a) COMPLIANCE WITH THE CRITERIA OF THE AUSTRALIAN AND NEW ZEALAND GUIDELINES FOR FRESH AND MARINE WATER QUALITY (2000)

b) IF SUBJECT TO THE ENVIRONMENTAL CONSULTANTS ADVICE, PROVIDE REMEDIAL MEASURES TO IMPROVE THE QUALITY OF WATER THAT IS TO BE DISCHARGED INTO COUNCIL'S STORMWATER DRAINAGE SYSTEM. THIS SHOULD INCLUDE COMMENTS FROM A SUITABLY QUALIFIED ENVIRONMENTAL CONSULTANT CONFIRMING THE SUITABILITY OF THESE REMEDIAL MEASURES TO MANAGE THE WATER DISCHARGED FROM THE SITE INTO COUNCIL'S STORMWATER DRAINAGE SYSTEM. OUTLINING THE PROPOSED, ONGOING MONITORING, CONTINGENCY PLANS AND VALIDATION PROGRAM THAT WILL BE IN PLACE TO CONTINUALLY MONITOR THE QUALITY OF WATER DISCHARGED FROM THE SITE. THIS SHOULD OUTLINE THE FREQUENCY OF WATER QUALITY TESTING THAT WILL BE UNDERTAKEN BY A SUITABLY QUALIFIED ENVIRONMENTAL CONSULTANT.

MINIMUM INTERNAL DIMENSIONS FOR STORMWATER AND INLET PITS AS3500.3 - TABLE 7.5.2.1					
	MINIMUM	INTERNAL DIMENSION	IS (mm)		
DEPTH TO INVERT OF OUTLET	RECTA	ANGULAR	CIRCULAR		
	Width	Length	Diameter ø		
<u><</u> 450	350	350	-		
<u>≤</u> 600	450	450	600		
> 600 <u><</u> 900	600	600	900		
> 900 <u><</u> 1200	600	900	1000		
> 1200	900	900	1000		



NORTHERN BEACHES

Local Council:

Project Number:

250302

Drawing ID:

SW002

Issue:

NOTES: 1. U.N.O REFER TO THE COVERPAGE 001 SERIES FOR DETAILED NOTES AND CALCULATIONS. 2. ALL DIMENSIONS SHALL BE VERIFIED ONSITE BY BUILDER BEFORE COMMENCING WITH WORK. - STARR PICKET TO HOLD



SEDIMENT TRAP CONSTRUCTION SPECIFICATION:

- 1 SEDIMENT SHALL BE REMOVED AND THE TRAP RESTORED TO ITS ORIGINAL DIMENSIONS WHEN THE SEDIMENT HAS ACCUMULATED TO 1/2 THE DESIGN DEPTH OF THE TRAP. REMOVED SEDIMENT SHALL BE DEPOSITED IN A SUITABLE AREA AND IN SUCH A MANNER THAT IT WILL NOT ERODE.
- 2 THE STRUCTURE SHALL BE INSPECTED AFTER EACH RAIN AND REPAIRED AS NEEDED.
- 3 CONSTRUCTION OPERATIONS SHALL BE CARRIED OUT IN A MANNER, THAT EROSION AND WATER POLLUTION SHALL BE MINIMIZED.
- 4 THE SEDIMENT TRAP SHALL BE REMOVED AND THE AREA STABILIZED WHEN THE CONSTRUCTED DRAINAGE AREA HAS BEEN PROPERLY STABILIZED.

SCHEDULE OF WORKS:

1. SILT FENCE AND ASSOCIATED WORKS INCLUDING INTERCEPTOR DRAIN IS TO BE INSTALLED BEFORE THE COMMENCEMENT OF ANY EXCAVATION. 2. CUTS TO BE EXECUTED TO THE REQUIRED LEVEL USING CONVENTIONAL EXCAVATION MACHINERY. INITIALLY THE DEPTH OF FILL/CLAY IS TO BE ESTABLISHED TO ENSURE NEIGHBOURING PROPERTIES ARE NOT ADVERSELY AFFECTED. EARTH BATTERS TO BE A MAXIMUM SLOPE OF 1.0 m VERT. TO 1.7 m HORIZ. (AS PER GEOTECHNICAL REPORT). ANY BATTERS GREATER THAN 1.0 m VERT. TO 1.7 m HORIZ. ARE TO BE ADEQUATELY SHORED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS. 3. ANY PERMANENT RETAINING STRUCTURE IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS. 4. ALL PERMANENT RETAINING STRUCTURES ARE TO BE COMPLETED WITH MINIMUM DELAY FOLLOWING EXCAVATION.

EROSION CONTROL NOTES:

1. SILT FENCE AND ASSOCIATED WORKS INCLUDING INTERCEPTOR DRAIN IS TO BE INSTALLED BEFORE THE COMMENCEMENT OF ANY EXCAVATION. 2. CUTS TO BE EXECUTED TO THE REQUIRED LEVEL USING CONVENTIONAL EXCAVATION MACHINERY. INITIALLY THE DEPTH OF FILL/CLAY IS TO BE ESTABLISHED TO ENSURE NEIGHBOURING PROPERTIES ARE NOT ADVERSELY AFFECTED. EARTH BATTERS TO BE A MAXIMUM SLOPE OF 1.0 m VERT. TO 1.7 m HORIZ. (AS PER GEOTECHNICAL REPORT). ANY BATTERS GREATER THAN 1.0 m VERT. TO 1.7 m HORIZ. ARE TO BE ADEQUATELY SHORED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS. 3. ANY PERMANENT RETAINING STRUCTURE IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS.

4. ALL PERMANENT RETAINING STRUCTURES ARE TO BE COMPLETED WITH MINIMUM DELAY FOLLOWING EXCAVATION.

5. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSPECTED AND MAINTAINED DAILY BY SITE MANAGER. 6. CONTRCTOR TO MINIMISE DISTURBED AREAS.

7. ALL STOCKPILES TO BE CLEAR FROM DRAINS, GUTTERS AND FOOTPATHS. 8. DRAINAGE IS TO BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE.

9. ROADS AND FOOTPATH TO BE SWEPT DAILY.

NOTE: THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE OF THE DRAINAGE DISCHARGE PIPES.	
A1 ORIGINAL	

NOTE:	PIT, MAY	PIPE VARY	& DO DUE	WNPIF TO C	PE LO ONST	CATIO RAINT	NS S. II	ARE F IN	INDICAT DOUBT,	IVE ONLY ASK!	&

TR

S

ARK

PROVIDE SANG BAGS & INLET PROTECTION TO ALL STREET

DRAINAGE PITS

 \geq

VARNING! CARE WHEN DIGGING AROUND TREE ROOTS. HAND DIGGING ONLY! MAY REQUIRE ARBORIST SUPERVISION.

AT ORIG	JINAL						
				Issued for: DEVELOPEMENT APPLICATION	Title:	Initial:	Date:
				Approved by:	DESIGN	R.M	15.04
				R Milling	DRAWN	S.M	15.04
А	16.05.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M	Rhys Mikhail	CHECKED	R.M	16.05
Rev:	Date:	Description:	Reviewed:	Director Principal Engineer NER: 2570082 RPEQ: 17480 BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)	APPROVED	R.M	16.05







<u>NOTES</u> 1. U.N DETAIL 2. ALL BUILDE	: .0 REFER TO .ED NOTES / . DIMENSION ER BEFORE (D THE COVERPAGE 001 SERIES FOR AND CALCULATIONS. S SHALL BE VERIFIED ONSITE BY COMMENCING WITH WORK.			
<u>LE(</u>	<u>GEND</u>				
	S	STORMWATER PIT NEW STORMWATER PIPE STORMWATER PIPE FLOW DIRECTION STORMWATER PIPE TO RWT EXISTING STORMWATER PIPE FLUSH-OUT LINE BOUNDARY LINE EXISTING SEWER MAIN EXISTING SEWER MAIN EXISTING OVERHEAD POWER LINES EXISTING ELECTRICITY LINE EXISTING WATER MAINS EXISTING TELECOMMUNICATIONS LINE EXISTING GAS MAINS			
	DP1 DP2 GD1 GD2 PP1 AH1 AH2 BD1 FD1 PD1 O/F RW0 RWT1 RWT2-RWT3 O/F FDB1 DR1 SQID SQID3-SQIE FFD	DENOTES DOWNPIPE DOWNPIPE TO SWID DOWNPIPE TO SWID 200mm MIN. GRATED STRIP DRAIN TO ARCHITECTS DETAIL 100mm MIN. GRATED STRIP DRAIN TO ARCHITECTS DETAIL 90.000 (PUMP OUT PIT 900.300 GRATED ACCESS HATCH 300.300 GRATED ACCESS HATCH 300.300 GRATED ACCESS HATCH 300.300 GRATED ACCESS HATCH 300.400 RAINWATER OUTLET (SPS TRUFLO) 1000/80 RAINWATER OUTLET (SPS TRUFLO) 10000/80 RAINWATER OUTLET (SPS TRUFLO) 10000/80 RAINWATER OUTLET (SPS TRUFLO) 1000000 MIN, WDE INTERNAL OPEN DISH DRAIN 3 × ATLAN FILTERS WITHIN 1800A1800 PIT OR 1 × STORMUTER BY ATLAN OR OCCAN PROTECT – SEE DETAILS INGROUND FIRST FLUSH DIVERTER 1000000 MIN HUTH HELL 1000000 MIN HUTH HELL 1000000 MIN HUTH HELL 1000000 MIN HUTH HELL 1000000 MIN HUTH HELL 10000000 MIN HUTH HELL 10000000 MIN HUTH HELL 10000000 MIN HUTH HELL 1000000000 MIN HUTH HELL 10000000 MIN HUTH HELL 100000000000000000000000000000000000	FDB1	AUNAR 1,30 35 00 BAMP 150	
		EXISTING COUNCIL KERB INLET PIT RL. 12.82 A.H.		FDB	
THE UTL RE LOCA STO WORKS	E BUILDER/C ILITY SERVIC ESERVE PRIC TIONS AND ORMWATER E S TO ENSUR C	NOTE: CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC CES WITHIN THE SITE, FOOTPATH AREA AND ROAD R TO THE COMMENCEMENT OF ANY WORKS. ALL LEVELS OF SERVICES SHALL BE REPORTED TO THE INGINEER PRIOR TO THE COMMENCEMENT OF ANY E THAT THERE ARE NO OBSTRUCTIONS IN THE LINE F THE DRAINAGE DISCHARGE PIPES.	VE ONLY & ASK! AND DIGGING		
A1 ORIG	INAL			ᅬ	
		Issued for: DEVELOPEMENT APPLICATION	Title:	Initial:	Date:
			DESIGN	R.M	15.04.
A	16.05.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION R.M Date : 16.05.25 K.	CHECKED	S.M	15.04.
		Rhvs Mikhail	UNLONED	г . .М	1 10.00.

Director | Principal Engineer | NER: 2570082 | RPEQ: 17480

BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)

APPROVED

R.M

Reviewed:

Rev:

Date:

Description:





	<u>NOTES</u> 1. U.N DETAIL 2. ALL	: .O REFER TO .ED NOTES ANI . DIMENSIONS :	THE COVERPAGE 001 SERIES FOR D CALCULATIONS. SHALL BE VERIFIED ONSITE BY						
		<u>GEND</u>	MMENCING WITH WORK.						
		S	STORMWATER PIT NEW STORMWATER PIPE STORMWATER PIPE FLOW DIRECTION STORMWATER PIPE TO RWT EXISTING STORMWATER PIPE FLUSH-OUT LINE BOUNDARY LINE EXISTING SEWER MAIN EXISTING OVERHEAD POWER LINES EXISTING ELECTRICITY LINE EXISTING WATER MAINS EXISTING TELECOMMUNICATIONS LINE EXISTING GAS MAINS						
	THE UTL RE LOCA	DP1 DP2 GD1 GD2 PP1 AH1 AH2 BD1 FD1 O/F RW0 RW11 RWT2-RWT3 O/F FDB1 DR1 SQID1 SQID3-SQID5 FFD SQID3-SQID5 FFD	DENOTES DOWNPIPE DENOTES SIZE OF DOWNPIPE DOWNPIPE TO SQID 200mm MIN. GRATED STRIP DRAIN TO ARCHIT 9,000L PUMP OUT PIT 900x900 GRATED ACCESS HATCH 300x300 GRATED INSPECTION LID 100ø/80 RAINWATER OUTLET (SPS TRUFLO) 250ø/100 RAINWATER OUTLET (SPS TRUFLO) 100ø/80 RAINWATER OUTLET (SPS TRUFLO) 100ø/80 RAINWATER OUTLET WITH PLANTER A PROVIDE OVERFLOW SPS SCUPPER DRAIN 80m RAINWATER OUTLET 4,300L (800W × 3300L × 2020H) RAINWATER 2x6,000L (950W × 4000L × 2020H) RAINWATER 0VERFLOW POINT – TO ARCHITECTUARL DETAIL 100ørm BASEMENT PERIMETER DRAIN 100mm MIN. WIDE INTERNAL OPEN DISH DRAIN 3 × ATLAN FILTERS WITHIN 1800x1800 PIT OR 1 × STORMFILTER BY OCEAN PROTECT RWT1–RWT3 PIT WITH FILTER BY ATLAN OR OCEAN PROTECT INGROUND FIRST FLUSH DIVERTER WITACTOR SHALL LOCATE ALL EXISTING PUBLIC S WITHING THE STER STILSH DIVERTER WITACTOR SHALL LOCATE ALL EXISTING PUBLIC 10.000 FIRST FLUSH DIVERTER WITACTOR SHALL LOCATE ALL EXISTING PUBLIC 10.0000 FIRST FLUSH DIVERTER WITACTOR SHALL SCOTPATH AREA AND ROAD FIRST FLUSH DIVERTER WITACTOR SHALL LOCATE ALL EXISTING PUBLIC S WITHIN FOR SALL AND OF OF ANY WORKS ALL VELS OF SERVICES SHALL BE REPORTED TO THE STERMENT OF ANY ORKS. ALL VELS OF SERVICES SHALL BE REPORTED TO THE STERMENT FLUSH DIVERTER	ECTS DETAIL ECTS DETAIL DAPTOR (SPS TRUF M TANK R TANKS S T - SEE DETAILS	our states a, 52 a) b) c, a, b, b) c, a, b, b, b) c, a, b, b, b) c, a, b, b, b) c, a, b,	B.O. B.O. B.O. B.O. B.O. B.O. B.O. B.O.	FD1	AUMAR 1.30 35 6 5 6 7 7 7 7 7 7 7 7 7 7 7 7 7	
	WORKS	S TO ENSURE OF	THAT THERE ARE NO OBSTRUCTIONS IN THE LINE THE DRAINAGE DISCHARGE PIPES.	WARNING!	CARE WHEN DIGGING AROU ONLY! MAY REQUIRE ARE	JND TREE ROOTS. I BORIST SUPERVISIO	HAND DIGGING N.		
,	A1 ORIG	INAL			Issued for: DEVELOPEME	NT APPLICATION	Title:	Initial:	Date:
				_	Approved by:	<u>л</u>	DESIGN	R.M	15.04
					\mathcal{R}	Milai	DRAWN	S.M	15.04
-		16.05.25			Date : 16.05.25 🏾 🎊 . 🕯	mul			

R.M

Reviewed:

Rhys Mikhail .

Director | Principal Engineer | NER: 2570082 | RPEQ: 17480

BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)

CHECKED

APPROVED

R.M

R.M

A 16.05.25

Date:

Description:

Rev:

STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION





<u>NOTES</u> 1. U.N DETAIL 2. ALL BUILDE	: .0 REFER TO .ED NOTES / . DIMENSION ER BEFORE /	D THE COVERPAGE 001 SERIES FOR AND CALCULATIONS. S SHALL BE VERIFIED ONSITE BY COMMENCING WITH WORK.			
<u>LE(</u>	<u>GEND</u>				
	С – С – С – С – С – С – С – С – С – С –	STORMWATER PIT NEW STORMWATER PIPE STORMWATER PIPE FLOW DIRECTION STORMWATER PIPE TO RWT EXISTING STORMWATER PIPE FLUSH-OUT LINE BOUNDARY LINE EXISTING SEWER MAIN EXISTING OVERHEAD POWER LINES EXISTING ELECTRICITY LINE EXISTING WATER MAINS EXISTING TELECOMMUNICATIONS LINE EXISTING GAS MAINS			
	DP1 DP2 GD1 GD2 PP1 AH1 AH2 BD1 FD1 PD1 O/F RW0 RWT1 RWT2-RWT O/F FDB1 DR1 SQID1 SQID3-SQIE FFD	DENDES DOWNPRE DOWNPRE TO SWIT DOWNPRE TO SWIT	BD1 BD1 BD1 CON BD1 CON BD1 CON BD1 CON BD1 CON BD1 CON BD1 CON BD1 CON CON CON CON CON CON CON CON	GD2 98 GD2 98 GD2 98 GD2 98 GD2 98 FD PIT 11.00 10.40 LAR TO DIP DNAL DRAIN OMS RETAIL	I FL
THE UTL RE LOCA STO	E BUILDER/C ILITY SERVIC SERVE PRIC TIONS AND DRMWATER E	NOTE: CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC DES WITHIN THE SITE, FOOTPATH AREA AND ROAD R TO THE COMMENCEMENT OF ANY WORKS. ALL LEVELS OF SERVICES SHALL BE REPORTED TO THE INGINEER PRIOR TO THE COMMENCEMENT OF ANY	/E ONLY & ASK!]	
WORK	S TO ENSUR	E THAT THERE ARE NO OBSTRUCTIONS IN THE LINE F THE DRAINAGE DISCHARGE PIPES. WARNING! CARE WHEN DIGGING AROUND TREE ROOTS. HA ONLY! MAY REQUIRE ARBORIST SUPERVISION.	AND DIGGING		
A1 ORIG		Issued for DEVELOPEMENT APPLICATION	Title	Initial	Date
		Approved by:	DESIGN	R.M	15.04.
			DRAWN	S.M	15.04
A	16.05.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION R.M Date : 16.05.25 K. MMM	CHECKED	R.M	16.05.

Director | Principal Engineer | NER: 2570082 | RPEQ: 17480

BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)

APPROVED

R.M

Reviewed:

Rev:

Date:

Description:

NOT FOR CONSTRUCTION





94–96 PARK STREET & 4 KUNARI PLACE, MONA VALE LEVEL 2 STORMWATER MANAGEMENT PLAN Local Council: NORTHERN BEACHES

Project Number:

250302



Drawing ID:

SW102

lssue:

Α



<u>GEND</u>		-					
	STORMWATER P	it Fr pipf					
	STORMWATER P	IPE FLOW DIRE	CTION				
	STORMWATER P	IPE TO RWT					
	EXISTING STORM	IWATER PIPE					
	BOUNDARY LINE	L.					
— s ——	EXISTING SEWER	R MAIN					
— OHP———	EXISTING OVERH	IEAD POWER L	INES				
— E ——	EXISTING ELECT	RICITY LINE				North & South !	Roof to
— т ——	EXISTING WATER	OMMUNICATION	S LINE				
	EXISTING GAS N	AINS					
100ø	DENOTES DOWN					Imprison A	rea 1 /
DP1	DOWNPIPE TO R	WT					cart
DP2	DOWNPIPE TO S	SQID					
GD1	200mm MIN. GF	RATED STRIP D	RAIN TO ARCHITE	CTS DETAIL			
GD2	100mm MIN. GF	RATED STRIP D	RAIN TO ARCHITE	CTS DETAIL			
AH1	9,000L POMP C	D ACCESS HA	ТСН			+++	
AH2	300×300 GRATE	D INSPECTION	LID				
BD1	1000/80 RAINW	ATER OUTLET	(SPS TRUFLO)				
FD1	2500/100 RAIN	WATER OUTLET	(SPS TRUFLO)		2)		
	PROVIDE OVERE	IOW SPS SCUE	PPFR DRAIN 80mr	MAPTOR (SPS TRUFL) m))		
RWO	RAINWATER OUT	ILET					
RWT1	4,300L (800W >	< 3300L × 202	20H) RAINWATER ⁻	TANK			
RWT2-RWT3	2x6,000L (950V	V x 4000L x 2	020H) RAINWATER	R TANKS			
U/F FDB1	100ømm BASEM	II – IU ARCH IFNT PFRIMFTF	R DRAIN	.5	PONER () POLE		
DR1	100mm MIN. WI	DE INTERNAL (OPEN DISH DRAIN				
SQID1	3 x ATLAN FILT	ERS WITHIN 18	300×1800 PIT OR				
SOID	1 x STORMFILTE	R BY OCEAN	PROTECT		ō 	GRID HATCHING	; DE
	PIT WITH FILTER	BY ATLAN O	R OCEAN PROTEC	T – SEE DETAILS		PERVIC	ч SUS
FFD	INGROUND FIRS	T FLUSH DIVER	TER		dно 	POOL WATER	≀ SI
eatment Train Effect	iveness - LPOD 85/65/	45		23	dH0 -		C
		Sources	Residual Load	% Reduction			-
Flow (ML/yr)		2.29	1.84	19.4	⇒	den	
Total Suspende	d Solids (kg/yr)	264	37.4	85.9		OHP	*
Total Phosphor	us (kg/yr)	0.545	0.0927	83	- HO	OHP	
Total Nitrogen ((kg/yr)	4.94	1.39	71.8	,		
Gross Pollutant	s (kg/yr)	47.4	0	100			
				B	HE L		
					p 🙀 📗		

	Sources	Residual Load	% Reduction
Flow (ML/yr)	2.33	1.89	19
Total Suspended Solids (kg/yr)	236	28.5	87.9
Total Phosphorus (kg/yr)	0.529	0.17	67.9
Total Nitrogen (kg/yr)	4.86	1.83	62.3
Gross Pollutants (kg/yr)	47.4	0	100

MUSIC MODEL RESULTS (O.P)

NOTE: THE BUILDER/CONTRACTOR SHALL LOCATE ALL EXISTING PUBLIC UTLILITY SERVICES WITHIN THE SITE, FOOTPATH AREA AND ROAD RESERVE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ALL LOCATIONS AND LEVELS OF SERVICES SHALL BE REPORTED TO THE STORMWATER ENGINEER PRIOR TO THE COMMENCEMENT OF ANY WORKS TO ENSURE THAT THERE ARE NO OBSTRUCTIONS IN THE LINE OF THE DRAINAGE DISCHARGE PIPES.

PA2

NOTE: PIT, PIPE & DOWNPIPE LOCATIONS ARE INDICATIVE ONLY & MAY VARY DUE TO CONSTRAINTS. IF IN DOUBT, ASK!

WARNING! CARE WHEN DIGGING AROUND TREE ROOTS. HAND DIGGING ONLY! MAY REQUIRE ARBORIST SUPERVISION.

A1 ORIC	SINAL						
				Issued for: DEVELOPEMENT APPLICATION	Title:	Initial:	Date:
				Approved by:	DESIGN	R.M	15.04.2
				R Millin	DRAWN	S.M	15.04.2
Α	16.05.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M	Date : 16.05.25 7 \	CHECKED	R.M	16.05.2
Rev:	Date:	Description:	Reviewed:	Director Principal Engineer NER: 2570082 RPEQ: 17480 BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)	APPROVED	R.M	16.05.2

B



			Architect:		Project and Drawing Title:
2025		CIVIL CONSULTING	WALSH	ARCHITECTS	94-96 P
2025		ENGINEERS STORMWATER • CIVIL • FLOOD MITIGATION			4 KUNARI P
2025	■ ABN: 81 615 065 588 Phone: 0490 507 30) Email: admin@rtscivil.com.au Web: rtscivil.com.au	Client: MONA VALE	CENTRAL PTY LTD	SITE STORMWAT
2025	The document is produced by RTS Civil Consulting Engineers client in accordance with the terms and conditions of RTS. liability whatsoever to any third party arising out of any use	Pty Ltd (RTS) solely for the benefit of and use by the RTS does not and shall not assume any responsibility or or reliance by third party on the content of this document.			

WSUD MUSIC MODE	WSUD MUSIC MODELLING CATCHMENT DETAILS						
CATCHMENT	TREATMENT DEVICE	AREA					
IA1 – IMPERVIOUS AREA 1	SQID4	458 m²					
IA2 – IMPERVIOUS AREA 2	SQID4	160 m²					
IA3 – IMPERVIOUS AREA 3	SQID5	121 m²					
IA4 – IMPERVIOUS AREA 4	SQID3	5 m²					
PA1 – PERVIOUS AREA 1	SQID5	558 m²					
PA2 – IMPERVIOUS AREA 2	SQID4	446 m²					
RA1 – ROOF AREA 1	SQID2	438 m²					
RA2 – ROOF AREA 2	SQID2	225 m²					
RA3 – ROOF AREA 3	SQID2	597 m²					
DA1 – DRIVEWAY AREA 1	SQID3	63 m²					
RA2 – ROOF AREA 2	SQID2	225 m²					

TER CATCHMENT PLAN

250302 |SW103| A





				Issued for: DEVELOPEMENT APPLICATION
				Approved by:
				Data + 16.05.25
А	16.05.25	STORMWATER MANAGEMENT PLAN FOR DA SUBMISSION	R.M	Rhys Mikhail
Rev:	Date:	Description:	Reviewed:	Director Principal Engineer NER: 2570082 RPEQ: 17480

NOTES:

CHECKED R.M 16.05. APPROVED R.M 16.05.

S.M

DRAWN

BEng (Civil) Hons MIEAust CPEng NER RPEQ APEC IntPE(Aus)

NOT FOR CONSTRUCTION

	-			
Date:			Architect:	Project and Drawing Title:
15.04.2025		CIVIL CONSULTING	WALSH ARCHITECTS	94—96 F
15.04.2025		ENGINEERS STORMWATER • CIVIL • FLOOD MITIGATION		4 KUNARI F
16.05.2025	ABN: 81 615 065 588 Phone: 0490 507 300) Email: admin@rtscivil.com.au Web: rtscivil.com.au	MONA VALE CENTRAL PTY LTD	STORMWATER
16.05.2025	The document is produced by RTS Civil Consulting Engineers client in accordance with the terms and conditions of RTS. I liability whatsoever to any third party arising out of any use	Pty Ltd (RTS) solely for the benefit of and use by the RTS does not and shall not assume any responsibility or or reliance by third party on the content of this document.		SHE

PARK STREET & PLACE, MONA VALE DRAINAGE DETAILS EET 2 OF 3

Project Number: SW201 250302

Drawing ID:

NORTHERN BEACHES

Local Council:



lssue:

Α

RL 2.75



NOTES:

NOT FOR CONSTRUCTION









		Architect:	Project and Drawing Title:
.2025		WALSH ARCHITECTS	94-96
.2025	ENGINEERS STORMWATER • CIVIL • FLOOD MITIGATION	Olicate	4 KUNARI I
.2025	ABN: 81 615 065 588 Phone: 0490 507 300 Email: admin@rtscivil.com.au Web: rtscivil.com.au		STORMWATER
.2025	The document is produced by RTS Civil Consulting Engineers Pty Ltd (RTS) solely for the benefit of and use by the client in accordance with the terms and conditions of RTS. RTS does not and shall not assume any responsibility or liability whatsoever to any third party arising out of any use or reliance by third party on the content of this document.	WORA VALL CENTRAL I IT EID	SHE