
Certificate number: **0002389617-01** Certificate Date: 08 Feb 2018 ★ Star rating: 5.1



BERS Pro v4.3.0.0 (3.13) cannot be used to model 'roof windows'. Roof windows are 'openable or fixed windows in a roof' and do not have a shaft, as distinct from skylights which incorporate a built-in shaft and are not ventilated. BERS Pro v4.3 can only model skylights. If a roof window is present on the floor plan then this certificate is not valid

Assessor details

Accreditation

VIC/BDAV/12/1441 number:

Name: Ian Fry

Organisation: Frys Energywise

Email: comply@frysenergywise.com.au

Phone: 02 9899 2825

Declaration The Assessor has provided design

of interest: advice to the Applicant BERS Pro v4.3.0.2b (3.13) Software:

BDAV AAO:

Overview

Dwelling details

Street: Unit 16, 79 Cabbage Tree Road

Suburb: Bayview

State: Postcode: 2104 **NSW** NCC Class: **New Dwelling 1A** Type:

NatHERS

climate zone: 56 Lot/DP

number: 20/632081 Exposure: Suburban

Key construction and insulation materials

(see following pages for details)

Construction: Fibro Cavity Panel Direct Fix

Corrugated Iron

Suspended Timber Floor

Insulation: **R2.5** wall insulation

> R4.1 ceiling insulation R2.5 floor insulation

BRD-001-01 A ESS Sliding Window Glazing:

(52mm) SG 3CIr

Net floor area (m²)

Conditioned: 118.0 Unconditioned: 49.0 Garage: 42.0 TOTAL: 168.0


Annual thermal performance loads (MJ/m²)

Heating: 41.6 Cooling: 23.4 TOTAL: 65.0

Plan documents

Plan ref/date: Lot 20, 79 Cabbage Tree Road

Prepared by:



Ceiling penetrations

(see following pages for details)

Sealed: Unsealed: 0

TOTAL:** 0 **NOTE: This total is the maximum number of ceiling penetrations allowed to a ceiling (under a roof) for this certificate. If this number is exceded in construction then this certificate IS NOT VALID and a new certificate is required. Loss of ceiling insulation for the penetrations listed has been taken into account with the rating.

Principle downlight type: Unknown

Window selection default windows only

Note on allowable window values: Only a 5% tolerance to the nominated SHGC window values shown on page 2 can be used with this rating.

Note: Only a +/- 5% SHGC tolerance is allowed with this rating.

NB: This tolerance ONLY applies to SHGC, the U-value can always be lower but not higher than the values stated on page 2.

If any of windows selected are outside the 5% tolerance then this certificate is no longer valid and the dwelling will need to be rerated to confirm compliance.

Scan to access this certificate online and confirm this is valid.



Certificate number: 0002389617-01 Certificate Date: 08 Feb 2018





Building features

Window ID	Window type	U-value	SHGC
BRD-001-01 A	BRD-001-01 A ESS Sliding Window (52mm) SG 3Clr	6.4	0.76
BRD-041-01 A	BRD-041-01 A SIG Fixed Lite Externally Glazed (125mm) SG 4Clr	6.2	0.74
BRD-063-01 A	BRD-063-01 A SIG Fixed Lite (67mm) SG 4Clr	6.0	0.78
BRD-033-01 A	BRD-033-01 A ESS Sliding Door (80mm) SG 4Clr	6.2	0.74
BRD-064-03 A	BRD-064-03 A SIG Fixed Lite (67mm) DG 4Sn-6Ar-4	3.1	0.49

Window schedule

Location	Window ID	Window no.	Height (mm)	Width (mm)	Orientation	Outdoor shade
Bedroom 1	BRD-001-01 A	n/a	1350	1800	S	No Shading
Ensuite 1	BRD-041-01 A	n/a	900	900	S	No Shading
Bath	BRD-041-01 A	n/a	900	900	S	No Shading
Bedroom 2	BRD-001-01 A	n/a	1350	1800	N	No Shading
Kitchen/Living	BRD-063-01 A	n/a	2400	450	N	No Shading
Kitchen/Living	BRD-063-01 A	n/a	2400	450	N	No Shading
Kitchen/Living	BRD-033-01 A	n/a	2400	1800	N	No Shading
Kitchen/Living	BRD-033-01 A	n/a	2400	1800	E	No Shading
Kitchen/Living	BRD-041-01 A	n/a	2400	900	E	No Shading
Kitchen/Living	BRD-033-01 A	n/a	2400	3600	S	No Shading
Kitchen/Living	BRD-001-01 A	n/a	1350	1800	S	No Shading
Kitchen/Living	BRD-064-03 A	n/a	450	14210	N	No Shading

ID	Window type				U-value	SHGC
None Present						
Roof window	and skylight sch	edule				
Location	ID	Roof window/skylight	Area (m²)	Orientation	Outdoor shade	Indoor shade/diffuser

ID	Wall type		Insulation		,	Wall wrap or foi
EW-1	Fibro Cavity F	anel Direct Fix	Foil, Anti-glare R2.5	e one side + Bulk	Insulation	Yes
EW-2	Fibro Cavity F	Panel Direct Fix	No insulation			No
External wal	l schedule					
Location	ID	Width (mm)	Height (mm)	Orientation	Fixed Shade	e Eaves (mm)
Bedroom 1	EW-1	600	2660	E	No	13200
Bedroom 1	EW-1	200	2661	Е	No	600
Bedroom 1	EW-1	4100	2660	S	No	600
Ensuite 1	EW-1	1895	2660	S	No	600
Ensuite 1	EW-1	595	2661	S	No	1400

Certificate number: 0002389617-01 Certificate Date: 08 Feb 2018 ★ Star rating:



Bath	EW-1	2190	2660	S	No	600
Bedroom 2	EW-1	595	2661	N	No	2700
Bedroom 2	EW-1	3500	2660	N	No	600
Bedroom 2	EW-1	600	2660	Е	No	6100
Kitchen/Living	EW-1	3295	2660	N	No	1200
Kitchen/Living	EW-1	2500	2660	Е	No	2800
Kitchen/Living	EW-1	2200	2660	N	No	3700
Kitchen/Living	EW-1	6600	2660	Е	No	600
Kitchen/Living	EW-1	4700	2660	S	No	2800
Kitchen/Living	EW-1	3195	2661	S	No	600
Garage	EW-2	7100	2660	N	No	600
Garage	EW-2	1500	2660	Е	No	600
Garage	EW-2	600	2661	Е	No	10200

Internal wall type				
Wall type	Area (m²)	Insulation	Wall wrap or foil	
IW-1 - Shaft liner party wall with plaster	34.0	Bulk Insulation both sides of shaft liner R2	No	
IW-2 - Cavity wall, direct fix plasterboard, single gap	82.0	No insulation	No	
IW-3 - Cavity wall, direct fix plasterboard, single gap	30.0	Bulk Insulation, No Air Gap R2	No	

Floors					
Location	Construction	Area (m²)	Sub floor ventilation	Added insulation	Covering
Bedroom 1	Suspended Timber Floor 100mm	16.9	Open	Bulk Insulation, Gap to Floor R2.5	Carpet 10mm
Ensuite 1	Suspended Timber Floor 19mm	7.1	Open	Bulk Insulation, Gap to Floor R2.5	Ceramic Tiles 8mm
Bath	Suspended Timber Floor 19mm	7.2	Open	Bulk Insulation, Gap to Floor R2.5	Ceramic Tiles 8mm
Bedroom 2	Suspended Timber Floor 19mm	17.1	Open	Bulk Insulation, Gap to Floor R2.5	Carpet 10mm
Corridor/Laundr	Suspended Timber Floor 19mm	20.6	Open	Bulk Insulation, Gap to Floor R2.5	Ceramic Tiles 8mm
Kitchen/Living	Suspended Timber Floor 19mm	56.6	Open	Bulk Insulation, Gap to Floor R2.5	Ceramic Tiles 8mm
Garage	Suspended Concrete Slab 19mm	42.1	Enclosed	No Insulation	Bare

^{*} Nationwide House Energy Rating Scheme (NatHERS) is an initiative of the Australian, state and territory governments. For more details see www.nathers.gov.au

Certificate number: **0002389617-01** Certificate Date:

08 Feb 2018





Building features continued

Location	Construction	Added insulation	Roof space above
Bedroom 1	Plasterboard	Bulk Insulation R4.1	Yes
Ensuite 1	Plasterboard	Bulk Insulation R4.1	Yes
Bath	Plasterboard	Bulk Insulation R4.1	Yes
Bedroom 2	Plasterboard	Bulk Insulation R4.1	Yes
Corridor/Laundr	Plasterboard	Bulk Insulation R4.1	Yes
Kitchen/Living	Plasterboard	Bulk Insulation R4.1	Yes
Garage	Plasterboard	No insulation	Yes

Ceiling penetrations				
Location	Number	Туре	Diameter (mm) Sealed/unsealed	
None Present	t			

Ceiling fans			
Location	Number	Diameter (mm)	
None Present			

Roof type		
Construction	Added Roof color insulation	
Corrugated Iron	Bulk, Reflective Medium Side Down, Anti- glare Up R1.3	



Additional information	

Explanatory notes

About this report

Residential energy ratings address the quality of the building fabric i.e. walls, windows, floors and roof/ceilings. Ratings do not cover the energy or water efficiency of appliances including heating and cooling, hot water, dishwashers, ovens, fridges, TVs etc. or solar panel or water tank requirements. The efficiency or specification of these items is generally covered by other regulations, standards or guidelines.

General Information

A NatHERS House Energy Rating is a comprehensive, dynamic computer modelling evaluation of the floorplans, elevations and specifications to predict an energy load of a home. Not all of us use our homes in the same way, so ratings are generated using standard assumptions. This means homes can be compared across the country.

The actual energy consumption of your home may vary significantly from the predicted energy load figures in the report depending on issues such as the size of your household and your personal preferences, e.g. in terms of heating or cooling.

While the figures are an indicative guide to energy use, they can be used as a reliable guide for comparative purposes between different house designs and for demonstrating that the design meets the required regulatory compliance.

Homes that are energy efficient use less energy, are warmer in winter, cooler in summer and cost less to run. The higher the star rating the more energy efficient.

This NatHERS House Energy Rating report was carefully prepared by your assessor on the basis of comprehensive modelling using standard procedures to rate your home using the underlying engine developed by the Australian Commonwealth Scientific and Industrial Research Organisation (CSIRO).

All information relating to energy loads presented in this report is based on a range of standard assumptions in order to allow for comparisons with reports prepared for other homes and to demonstrate minimum regulatory compliance.

The standard assumptions include figures for occupancy, indoor air temperature and are based on a unique climate file for your region.

Accredited Assessors

To ensure you get a high-quality, professional NatHERS House Energy Rating report, you should always use an accredited assessor, accredited assessors are members of a professional body called an Assessor Accrediting Organisation (AAO).

AAOs have specific quality assurance processes in place and continuing professional development requirements to maintain a high and consistent standard of assessments across the country. Non-accredited assessors do not have this level of quality assurance or any on-going training requirements.

If you have any questions or concerns about this report, please direct them to your assessor in the first instance.

If your assessor is unable to address your questions or concerns, please contact their AAO listed under 'assessor details'. You can also find a range of information about accredited assessors on the AAO websites.

Disclaimer

The energy values quoted are for comparison purposes only; they are not a prediction of actual energy use. This rating only applies to the floor plan, construction details, orientation and climate as submitted and included in the attached drawing set that bears a stamp with the same number as this certificate. Changes to any of these details could affect the rating.

Contact

For more information on the Nationwide House Energy Rating Scheme (NatHERS), visit www.nathers.gov.au For more information on energy efficient design and insulation visit www.yourhome.gov.au

^{*} Nationwide House Energy Rating Scheme (NatHERS) is an initiative of the Australian, state and territory governments. For more details see www.nathers.gov.au