



northern
beaches
council

12 September 2018

2dpd Pty Ltd
PO Box 7005
WARRINGAH MALL NSW 2100

Dear Sir/Madam

Application Number: DA2017/1183
Address: Lot 1 DP 710661 , 2 Delmar Parade, DEE WHY NSW 2099
Proposed Development: Demolition works and construction of a Mixed Use Development, comprising retail shops and shop top housing

Please find attached the Notice of Determination for the above mentioned Application.

Please be advised that a copy of the Assessment Report associated with the application is available on Council's website at www.northernbeaches.nsw.gov.au

Please read your Notice of Determination carefully and the assessment report in the first instance.

If you have any further questions regarding this matter please contact the undersigned on 1300 434 434 or via email quoting the application number, address and description of works to council@northernbeaches.nsw.gov.au

Regards,

A handwritten signature in blue ink, appearing to read 'Peter Robinson', with a long horizontal flourish extending to the right.

Peter Robinson
Executive Manager Development Assessment

NOTICE OF DETERMINATION

Application Number:	DA2017/1183
Determination Type:	Development Application

APPLICATION DETAILS

Applicant:	2dpd Pty Ltd
Land to be developed (Address):	Lot 1 DP 710661 , 2 Delmar Parade DEE WHY NSW 2099
Proposed Development:	Demolition works and construction of a Mixed Use Development, comprising retail shops and shop top housing

DETERMINATION - APPROVED

Consent Authority	Sydney Planning Panel - North
Made on (Date)	12/09/2018
Consent to operate from (Date):	12/09/2018
Consent to lapse on (Date):	12/09/2023

Detail of Conditions

The conditions, which have been applied to the consent, aim to ensure that the Environmental Impacts of Development are minimised and the Health and Safety of the community is maintained in accordance with the relevant standards and the Building Code of Australia.

Note:

If the works are to be certified by a Private Certifying Authority, then it is the certifier's responsibility to ensure all outstanding fees and bonds have been paid to Council prior to the issue of the Construction Certificate or as otherwise specified by Consent conditions.

DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

1. **Approved Plans and Supporting Documentation**

The development must be carried out in compliance (except as amended by any other condition of consent) with the following:

a) Approved Plans

Architectural Plans - Endorsed with Council's stamp		
Drawing No.	Dated	Prepared By
DA0-01, DA1-02, DA1-04, DA1-06, DA1-07(Revision 2)	9/07/2018	Marchese Partners
DA1.01, DA1.03, (Revision 1)	1/12/2017	Marchese Partners
DA1.05 - Demolition Plan (Revision 1)	1/12/2017	Marchese Partners
DA-201, DA2-02, DA2-03, DA2-04, DA2-05, DA2-06, DA2-07, DA2-08, DA2-09, DA2-10 (Revision 2)	9/07/2018	Marchese Partners
DA3-01, DA3-02, DA3-03, DA3-04, DA3-05, DA3-06, DA3-07, DA3-08, DA3-09, DA3-10 (Revision 2)	9/07/2018	Marchese Partners
DA4-01, DA4 -02, DA4-03, DA4-04, DA4-05, DA4-06 (Revision 2)	9/07/2018	Marchese Partners
DA6-01, DA6-02 (Revision 2)	9/07/2018	Marchese Partners
DA8-01, DA8-02, -Exterior Finishes (Revision 1)	01/12/2017	Marchese Partners
DA9-08, DA9-09 Storage Plan (Revision 2)	9/07/2018	Marchese Partners
DA9-13 (Revision 2)	9/07/2018	Marchese Partners

Reports / Documentation – All recommendations and requirements contained within:		
Report No. / Page No. / Section No.	Dated	Prepared By
Arboricultural Impact Assessment	November 2017	Urban Forestry Australia
BCA Assessment Report (DA Stage)	30 November 2017	BCA Logic
Geotechnical Report	January 2016	Douglas Partners
Construction Management Plan	24 November 2017	Marchese Partners
Acoustic Report	15/12/2017	Acoustic Logic

b) Any plans and/or documentation submitted to satisfy the Conditions of this consent.

c) The development is to be undertaken generally in accordance with the following:

Landscape Plans		
Drawing No.	Dated	Prepared By

Landscape Proposal (issue A)	Revised on 26/06/2018	David Louden
------------------------------	-----------------------	--------------

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of the Council and approved plans. (DACPLB01)

2. Amendments to the approved plans

The following amendments are to be made to the approved plans:

- a) Units 45, 46 and 47 are to have exclusive use of the open terrace area immediately in front of those units which form part of the Level 4 podium facing Pittwater Road. In this regard, those areas are to form an extension of the private open space areas for the units. The remainder of the landscaped and paved terrace areas on this part of Level 4 are to be for communal use. Suitable screens are to be erected to ensure that the private spaces are separate to the communal spaces and privacy is afforded to the individual apartments.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the construction certificate.

Reason: To ensure privacy is maintained for residential apartments and communal space is clearly delineated within the development.

(DACPLB02)

3. Compliance with Other Department, Authority or Service Requirements

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department, Authority or Service	EDMS Reference	Dated
Ausgrid	Response Ausgrid Referral	18/12/2017
Roads and Maritime Services (RMS)	Response RMS Referral	13 August 2018

(NOTE: For a copy of the above-referenced document/s, please see Application Tracking on Council's website www.northernbeaches.nsw.gov.au)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of the other Department, Authority or Bodies. (DACPLB02)

4. No Approval for any Signage

No approval is granted under this Development Consent for signs (as defined under Warringah Local Environment Plan 2011 and State Environmental Planning Policy No. 64). A separate Development Application for any signs (other than exempt and signs permitted under Complying Development) must be submitted for the approval prior to the erection or display of any such signs.

Reason: Control of signage. (DACPLB06)

5. Prescribed Conditions



- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (i) showing the name, address and telephone number of the Principal Certifying Authority for the work, and
 - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (iii) stating that unauthorised entry to the work site is prohibited.Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.
- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
 - (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
 - (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and
 - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.
- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
 - (i) protect and support the adjoining premises from possible damage from the excavation, and
 - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
 - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.



Reason: Legislative Requirement (DACPLB09)

6. **General Requirements**

(a) Unless authorised by Council:

Building construction and delivery of material hours are restricted to:

- 7.00 am to 5.00 pm inclusive Monday to Friday,
- 8.00 am to 1.00 pm inclusive on Saturday,
- No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of a final Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (c) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (d) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (e) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (f) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (g) No building, demolition, excavation or material of any nature and no hoist, plant and machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (h) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (i) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (j) Prior to the commencement of any development onsite for:



- i) Building/s that are to be erected
- ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
- iii) Building/s that are to be demolished
- iv) For any work/s that is to be carried out
- v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

(k) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.

- (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

- (i) Swimming Pools Act 1992
 - (ii) Swimming Pools Amendment Act 2009
 - (iii) Swimming Pools Regulation 2008
 - (iv) Australian Standard AS1926 Swimming Pool Safety
 - (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
 - (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
- (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
 - (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
 - (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community. (DACPLB10)

7. Development to be within site boundaries

The development (excluding awnings) must be constructed wholly within the boundaries of the premises. No portion of the proposed structure shall encroach onto the adjoining properties. Gates must be installed so they do not open onto any footpath.

Reason: To ensure the development is constructed within the development site. (DACPLBOC1)

8. Policy Controls

Northern Beaches Council Contributions Plan 2018

The proposal is subject to the application of Council's Section 7.12 Development Contributions Plan.

The following monetary contributions are applicable:

Northern Beaches Council Contributions Plan 2018		
Contribution based on a total development cost of \$ 20,303,314.00		
Contributions	Levy Rate	Payable
Total Section 7.12 Levy	0.95%	\$ 192,881.48
Section 7.12 Planning and Administration	0.05%	\$ 10,151.66
Total	1%	\$ 203,033.14

The amount will be adjusted at the time of payment according to the quarterly CPI (Sydney - All Groups Index). Please ensure that you provide details of this Consent when paying contributions so that they can be easily recalculated.

This fee must be paid prior to the issue of the Construction Certificate. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To provide for contributions in accordance with Northern Beaches Council Contributions Plan 2018.

9. Security Bond

A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, details demonstrating payment are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at www.northernbeaches.nsw.gov.au).

Reason: To ensure adequate protection of Council's infrastructure.

10. Construction, Excavation and Associated Works Bond (Drainage)

A Bond of \$1,000 as security against any damage or failure to complete the construction of Stormwater drainage works as part of this consent.

Reason: Protection of Council's Infrastructure

11. **Construction, Excavation and Associated Works Bond (Crossing / Kerb)**

A Bond of \$100,000 as security against any damage or failure to complete the construction of any vehicular crossings, kerb and gutter and any footpath works required as part of this consent.

Reason: Biodiversity/Vegetation Conservation and Management

Reason: Protection of Council's Infrastructure

12. **Construction, Excavation and Associated Works Bond (Failure to Remove Waste)**

A bond of \$10,000 as security against damage to Council's road(s) fronting the site caused by the transport and disposal of materials and equipment to and from the site.

Reason: Protection of Council's Infrastructure

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

13. **Pump-Out System Design for Stormwater Disposal**

The design of the pump-out system for stormwater disposal will be permitted for drainage of basement areas only, and must be designed in accordance with Council's Stormwater Drainage Policy. Engineering details demonstrating compliance with this requirement and certified by an appropriately qualified and practising hydraulic engineer.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure adequate provision is made for the discharge of stormwater from the excavated parts of the site. (DACENC04)

14. **Waste Room Design**

The door access to the residential bin room shall not open on to the driveway. The layout of the bin room shall be reconfigured to ensure users are not walking out into a driveway. Appropriate pedestrian paths within the basement should also be established to guide pedestrians along the safest route. Plans shall be prepared by a suitably qualified person incorporating these requirements.

The plan is to be submitted to and approved by the Council's Traffic Engineer and Waste Officer prior to the issue of the Construction Certificate.

Reason: To improve the safety of pedestrians and ensure the design requirements do not impact other aspects of the building (DACENC06)

15. **Stormwater Disposal**

Plans indicating all details relevant to the collection and disposal of stormwater from the site, buildings, paved areas and where appropriate adjacent catchments, shall be submitted prior to the issue of the Construction Certificate. The plans must indicate the provision of a rainwater tank in accordance with the BASIX certificate.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the

issue of the Construction Certificate.

Reason: To ensure appropriate provision for disposal and stormwater management and compliance with the BASIX requirements, arising from the development. (DACENC07)

16. **Submission Roads Act Application for Civil Works in the Public Road**

An Application for Works to be Approved within Council Roadway, including engineering plans is to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

The application is to include four (4) copies of Civil Engineering plans for the design of the retaining walls through the nature strip and driveway crossing which are to be generally in accordance with the Development Application and Council's specification for engineering works - AUS-SPEC #1 and/ or Council's Minor Works Policy. The plan shall be prepared by a qualified structural engineer. The design must include the following information:

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification.

17. **On-site Stormwater Detention**

An On-site Stormwater Detention system must be designed and constructed in accordance with Council's current On-site Stormwater Detention Technical Specification, and generally in accordance with the concept drainage plans prepared by Taylor Consulting Engineers, drawing number 36317-1A, 2A & 3, dated November 2017.

Detailed drainage plans are to be prepared by a suitably qualified Civil Engineer, who has a membership to the Institution of Engineers Australia, National Professional Engineers Register (NPER) and registered in the General Area of Practice for civil engineering.

The drainage plans must address the following:

i. Provision to safely convey flows through the site to the street in the event of a failure or blockage

ii. Detailed drainage plans, including engineering certification confirming the above requirements, have been satisfied and complying with Council's current On-site Stormwater Detention Technical Specification, are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater and stormwater management arising from the development. (Special condition) (DACENC20)

18. **Structural Adequacy and Excavation Work**

Excavation work is to ensure the stability of the soil material of adjoining properties, the protection of adjoining buildings, services, structures and / or public infrastructure from damage using underpinning, shoring, retaining walls and support where required.



All retaining walls are to be structurally adequate for the intended purpose, designed and certified by a Structural Engineer, except where site conditions permit the following:

- (a) maximum height of 900mm above or below ground level and at least 900mm from any property boundary, and
- (b) comply with AS3700, AS3600 and AS1170 and timber walls with AS1720 and AS1170.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: Safety. (DACENC19)

19. Shoring of Adjoining Property

Should the proposal require shoring to support an adjoining property or Council land, owner's consent for the encroachment onto the affected property owner shall be provided with the engineering drawings. Council approval is required if temporary rock anchors are to be used within Council land.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure that owners consent is obtained for ancillary works, and to ensure the protection of adjoining properties and Council land. (DACENCO5)

20. Engineering Details

Civil engineering details of the proposed excavation/landfill are to be submitted to the Accredited Certifier or Council with the Construction Certificate application. Each plan/sheet is to be signed by a qualified practising Civil Engineer who has corporate membership of the Institution of Engineers Australia (M.I.E) or who is eligible to become a corporate member and has appropriate experience and competence in the related field.

Reason: To ensure excavation and landfill are completed to an appropriate standard and conducted in a safe manner.

21. Construction Management Program

An application of Traffic Control is to be submitted to Council for approval. Management Program shall be prepared to RMS standard by an appropriately certified person. An approval is to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process in a manner that respects adjoining owner's property rights and protects amenity in the locality, without unreasonable inconvenience to the community (DACENCPCC4)

22. Flood

In order to protect property and occupants from flood risk, the following is required:

Building Components and Structural Soundness – C1

All new development shall be designed and constructed as flood compatible buildings in accordance with Reducing Vulnerability of Buildings to Flood Damage: Guidance on Building in Flood Prone Areas, Hawkesbury-Nepean Floodplain Management Steering Committee (2006).

Building Components and Structural Soundness – C2

All new development must be designed and constructed to ensure structural integrity up to the Flood Planning Level, taking into account the forces of floodwater, wave action, flowing water with debris, buoyancy and immersion. A structural certification shall be provided confirming the above.

Building Components and Structural Soundness – C3

All new electrical equipment, power points, wiring, fuel lines, sewerage systems or any other service pipes and connections must be waterproofed and/or located above the Flood Planning Level.

Storage of Goods – D1

Hazardous or potentially polluting materials shall not be stored below the Flood Planning Level unless adequately protected from floodwaters in accordance with industry standards.

Flood Emergency Response – E2

Appropriate access to a shelter in place refuge above the Probable Maximum Flood level should be available from all areas of the new development.

Floor Levels – F1

New floor levels within the development shall be set at or above the Flood Planning Level of 28.1m AHD.

Car parking – G3

All access, ventilation and any other potential water entry points, including entry ramp crests to the basement car park shall be at or above the Flood Planning Level of 28.1m AHD.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To protect the building from flooding in accordance with Council and NSW Government policy. (DACNEC09)

23. **Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards. (DACPLC02)

24. **External Finishes to Roof**

The external finish to the roof shall have a medium to dark range (BCA classification M and D) in order to minimise solar reflections to neighbouring properties. Any roof with a metallic steel finish is not permitted.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure that excessive glare or reflectivity nuisance does not occur as a result of the

development. (DACPLC03)

25. Geotechnical Report

A Geotechnical Report and certificate shall be prepared by an appropriately qualified Geotechnical Engineer certifying that the existing rock formations and substrate on the site are capable of withstanding:

- a) The proposed loads to be imposed,
- b) The extent of the proposed excavation, including any recommendations for shoring works that may be required to ensure the stability of the excavation,
- c) Protection of adjoining properties,
- d) The provision of appropriate subsoil drainage during and upon completion of construction works.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the structural integrity of the subject site and adjoining sites during the excavation process. (DACPLCPC1)

26. Treatment of Southern (front) Elevation

The external wall south of Units 9, 22 and 36, and the ground level fire passage beneath are to be treated with a suitable design, colours and textures, generally in the form of horizontal and vertical banding (or similar).

The treatment is to be designed in a manner consistent with the building and is not to present as a blank façade from any public or private domain. The final design is to be approved by Council's Manager Development Assessment and is to be incorporated into the architectural plans prior to the release of the Construction Certificate.

Reason: To ensure the aesthetic quality of the approved development enhances the streetscape. (DACPLCPC2)

27. Submission of Engineering Plans (standard from development engineers).

Engineering plans are to be submitted to the Certifying Authority for approval. The submission is to include four (4) copies of Civil Engineering plans for the design of:

- Median island along Delmar Parade to restrict right turn movements in and out of the access dri

These are to be generally in accordance with the civil design approved with the Development Application and Council's specification for engineering works - AUS-SPEC #1 and or Council's

Minor Works Policy. Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Section 138 and/or 139 applications are to be submitted to Council for Local Traffic Committee approval.

Reason: To ensure compliance with Council's specification for engineering works.
(DACTRCPC1)

28. Construction Traffic Management Plan.

As a result of the site constraints, limited vehicle access and parking, a Construction Traffic Management Plan (CTMP) and report shall be prepared by an RMS accredited person and submitted to and approved by the certifying authority prior to issue of any Construction Certificate.

The CTMP must address following:-

- The proposed phases of construction works on the site, and the expected duration of each construction phase;
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken;
- Make provision for all construction materials to be stored on site, at all times;
- The proposed areas within the site to be used for the storage of excavated materials, construction materials and waste containers during the construction period;
- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed;
- The proposed method of loading and unloading excavation and construction machinery, excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site;
- Make provision for parking onsite. All Staff and Contractors are to use the basement parking once available.
- Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site are not permitted unless approved by Council prior.
- Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian traffic.
- The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site.
- The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site;



- Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council.
- The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent;
- Proposed protection for Council and adjoining properties;
- The location and operation of any on site crane; and

The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – “Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. Confirming appropriate measures have been considered for site access, storage and the operation of the site during all phases of the construction process in a manner that respects adjoining owner’s property rights and protects amenity in the locality, without unreasonable inconvenience to the community. The CTMP is intended to minimise impact of construction activities on the surrounding community, in terms of vehicle traffic (including traffic flow and parking) and pedestrian amenity adjacent to the site. (DACTRCPC2)

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

29. **Public Liability Insurance - Works on Public Land**

Any person or contractor undertaking works on public land must take out Public Risk Insurance with a minimum cover of \$20 million in relation to the occupation of, and approved works within Council’s road reserve or public land, as approved in this consent. The Policy is to note, and provide protection for Northern Beaches Council, as an interested party and a copy of the Policy must be submitted to Council prior to commencement of the works. The Policy must be valid for the entire period that the works are being undertaken on public land.

Reason: To ensure the community is protected from the cost of any claim for damages arising from works on public land. (DACEND01)

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

30. **Property Boundary Levels**

The property boundary levels shall match the existing levels except where modified for the vehicular crossing. The applicant shall design and construct having regard for the existing levels. No approval is granted for any change to existing property alignment levels to accommodate the development.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To maintain the existing profile of the nature strip/road reserve. (DACENE01)

31. **Surveyor’s Report**

A Registered Surveyor’s identification report indicating the finished ground floor levels to a nominated fixed datum point are in accordance with the levels indicated on the approved plans.

A Surveyor's Report is to be provided for confirmation prior to pouring of the slab or construction of the floor platform.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure the height of buildings under construction comply with levels shown on approved plans. (DACENE04)

32. Vehicle Crossings

The provision of a vehicle crossing 5.4 metres wide in accordance with Northern Beaches Council Drawing No A4-3330/1N and specifications. An Authorised Vehicle Crossing Contractor shall construct the vehicle crossing and associated works within the road reserve in plain concrete. All redundant laybacks and crossings are to be restored to footpath/grass. Prior to the pouring of concrete, the vehicle crossing is to be inspected by Council and a satisfactory "Vehicle Crossing Inspection" card issued.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To facilitate suitable vehicular access to private property. (DACENE05)

33. Maintenance of Road Reserve

The public footways and roadways adjacent to the site shall be maintained in a safe condition at all times during the course of the work.

Reason: Public Safety. (DACENE09)

34. Traffic Control During Road Works

Lighting, fencing, traffic control and advanced warning signs shall be provided for the protection of the works and for the safety and convenience of the public and others in accordance with RMS Traffic Control At Work Sites Manual (<http://www.rms.nsw.gov.au/business-industry/partnerssuppliers/documents/technical-manuals/tcws-version-4/tcwsv4i2.pdf>) and to the satisfaction of the Principal Certifying Authority. Traffic movement in both directions on public roads, and vehicular access to private properties is to be maintained at all times during the works.

Reason: Public Safety. (DACENE11)

35. Noise and Vibration

The construction of the development and preparation of the site, including operation of vehicles, must be conducted so as to avoid unreasonable noise or vibration and not cause interference to adjoining or nearby occupations

Reason: To ensure the amenity of the surrounding area for residents

36. Site Fencing

The site must be fenced throughout construction and must comply with WorkCover New South Wales requirements and be a minimum of 1.8m in height.

Reason: To ensure public safety.



37. Stormwater Connection

Where connection to Council's nearest stormwater drainage system is required, the applicant shall connect the pipeline in accordance with Council's specification for engineering works and shall reconstruct all affected kerb and gutter, bitumen reinstatements, adjust all vehicular crossings for paths, grass verges and household stormwater connections to suit the kerb and gutter levels. All works shall be undertaken at the applicant's cost, and upon completion certified by an appropriately qualified and practicing Civil Engineer. Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To ensure compliance of drainage works with Council's specification for engineering works. (DACENEDW2)

38. Waste Management During Development

The reuse, recycling or disposal of waste during works must be done generally in accordance with the Waste Management Plan for this development.

Details demonstrating compliance must be submitted to the Principal Certifying Authority.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

39. Installation and Maintenance of Sediment Control

Measures used for erosion and sediment control on building sites are to be adequately maintained at all times and must be installed in accordance with Council's Specifications for Erosion and Sediment Control. All measures shall remain in proper operation until all development activities have been completed and the site fully stabilised.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To protect the environment from the effects of sedimentation and erosion from development sites.

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

40. Authorisation of Legal Documentation Required for On-site Stormwater Detention

The original completed request forms (Department of Lands standard forms 13PC and/or 13RPA) must be submitted to Council, with a copy of the Works-as-Executed plan (details overdrawn on a copy of the approved drainage plan), hydraulic engineers certification and Compliance Certificate issued by an Accredited Certifier in Civil Works.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To create encumbrances on the land. (DACENF01)

41. Registration of Encumbrances for On-site Stormwater Detention

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction for on-site storm water detention as to user is to be submitted.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To identify encumbrances on land. (DACENF02)

42. **Reinstatement of Kerb**

All redundant laybacks and vehicular crossings shall be reinstated to conventional kerb and gutter, footpath or grassed verge as appropriate with all costs borne by the applicant.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To facilitate the preservation of on street parking spaces. (DACENF03)

43. **Restriction as to User for On-site Stormwater Detention**

A restriction as to user shall be created on the title over the on-site stormwater detention system, restricting any alteration to the levels and/or any construction on the land. The terms of such restriction are to be prepared to Council's standard requirements, (available from Warringah Council), at the applicant's expense and endorsed by Council prior to lodgement with the Department of Lands. Warringah Council shall be nominated as the party to release, vary or modify such restriction.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure modification to the on-site stormwater detention structure is not carried without Council's approval. (DACENF04)

44. **Stormwater Disposal**

The stormwater drainage works shall be certified as compliant with Council's Stormwater Drainage from Low Level Properties Technical Specification and all relevant Australian Standards and Codes by a NPER Civil Engineer registered with Engineer's Australia.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater arising from the development. (DACENF05)

45. **Positive Covenant for the Maintenance of Stormwater Pump-out Facilities**

A Positive Covenant (under the provisions of Section 88B of the Conveyancing Act 1919) is to be created on the property title to ensure the on-going maintenance of the stormwater pump-out facilities on the property being developed.

Warringah Council shall be nominated in the instrument as the only party authorised to release, vary or modify the instrument. Warringah Council's delegate shall sign these documents prior to the submission to the Land & Property Information Department.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure adequate provision is made for the stormwater pump out system to be maintained to an appropriate operational standard. (DACENF11)

46. **Positive Covenant for On-site Stormwater Detention**

A positive covenant shall be created on the title of the land requiring the proprietor of the land to maintain the on-site stormwater detention structure in accordance with the standard



requirements of Council. The terms of the positive covenant are to be prepared to Council's standard requirements, (available from Warringah Council), at the applicant's expense and endorsed by Warringah Council's delegate prior to lodgement with the Department of Lands. Warringah Council shall be nominated as the party to release, vary or modify such covenant.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure ongoing maintenance of the on-site stormwater detention system.
(DACENF12)

47. Removal of All Temporary Structures/Material and Construction Rubbish

Once construction has been completed all silt and sediment fences, silt, rubbish, building debris, straw bales and temporary fences are to be removed from the site.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure bushland management. (DACPLF01)

48. Garbage and Recycling Facilities

All internal walls of the storage area shall be rendered to a smooth surface, coved at the floor/wall intersection, graded and appropriately drained to the sewer with a tap in close proximity to facilitate cleaning.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To prevent pollution of the environment and to protect the amenity of the area.
(DACPLF03)

49. Unit Numbering for Multi Unit Developments (Residential, Commercial and Industrial)

The units within the development are to be numbered in accordance with the Australia Post Address Guidelines
(https://auspost.com.au/content/dam/auspost_corp/media/documents/Appendix-01.pdf).

In this regard, the numbering is to be as per the Unit Numbering for Multi Unit Development Table available on Council's website
(<https://www.northernbeaches.nsw.gov.au/sites/default/files/documents/pdf-forms/unit-numbering-multi-unit-developments-residential-commercial-and-industrial-form/unit-numbering-multi-unit-developments-residential-commercial-and-industrial-form.pdf>).

External directional signage is to be erected on site at driveway entry points and on buildings and is to reflect the numbering in the table provided. Unit numbering signage is also required on stairway access doors and lobby entry doors.

It is essential that all signage throughout the complex is clear to assist emergency service providers in locating a destination within the development with ease and speed, in the event of an emergency.

Details are to be submitted with any Interim/Final Occupation Certificate or Strata Subdivision Certificate certifying that the numbering has been implemented in accordance with this condition

and the Unit Numbering for Multi Unit Development Table.

Reason: To ensure consistent numbering for emergency services access. (DACPLF05)

50. **Waste Management Confirmation**

Prior to the issue of a Final Occupation Certificate, evidence / documentation must be submitted to the Principal Certifying Authority that all waste material from the development site arising from demolition and/or construction works has been appropriately recycled, reused or disposed of generally in accordance with the approved Waste Management Plan.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

51. **Sydney Water**

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Co-ordinator. Please refer to the Building Developing and Plumbing section of the web site www.sydneywater.com.au <<http://www.sydneywater.com.au>> then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Co-ordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure compliance with the statutory requirements of Sydney Water. (DACPLF08)

52. **Loading Dock Management Plan.**

A Loading Dock Management Plan shall be prepared by the applicant and submitted to and approved by Council prior to the issue of any Occupation Certificate. The Plan will need to demonstrate how loading dock will be managed to ensure that there will be only one vehicle entering and exiting the loading dock access in any period and how safe servicing arrangements including waste collection will be undertaken without interrupting general traffic. Vehicle queuing on public road(s) is not permitted.

Reason: To ensure safe servicing of the site (DACTRFPOC1)

53. **Footpath Construction.**

The footpath, in accordance to Council's standard specifications, shall be constructed along the property frontage to Council's satisfaction. Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any Occupation Certificate.

Reason: To provide pedestrian access to and from the property. (DACTRFPOC2)

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

54. **Allocation of Spaces**

Car parking spaces provided shall be provided, made accessible and maintained at all times. The spaces shall be allocated as follows:



- o 73 - Residential
- o 15 - Residential - Visitors (including 1 Disabled Space)
- o 21 - Retail/commercial (including 1 disabled space)

Car-parking provided shall be used solely in conjunction with the uses contained within the development. Each car parking space allocated to a particular unit/tenancy shall be line marked and numbered or signposted to indicate the unit/tenancy to which it is allocated.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim/final Occupation Certificate.

Reason: To ensure that adequate parking facilities to service the development are provided on site. (DACPLG01)

55. Vehicle Egress Signs

Appropriate sign(s) shall be provided and maintained within the site at the point(s) of vehicular egress to compel all vehicles to come to a complete stop before proceeding onto the public way.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure pedestrian safety. (DACPLG03)

56. Visitors Sign

A sign, legible from the street, shall be permanently displayed to indicate that visitor parking is available on the site and the visitor car parking spaces shall be clearly marked as such.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any interim / final Occupation Certificate.

Reason: To ensure that visitors are aware that parking is available on site and to identify those spaces to visitors. (DACPLG04)

57. Hours of Operation

The hours of operation for the retail component of the development are to be restricted to:

- o Monday to Friday – 7 am - 10 pm
- o Saturday –7am -11pm
- o Sunday and Public Holidays – 7 am - 9 pm

Upon expiration of the permitted hours, all service (and entertainment) shall immediately cease, no patrons shall be permitted entry and all customers on the premises shall be required to leave within the following 30 minutes.

Reason: Information to ensure that amenity of the surrounding locality is maintained. (DACPLG08)

58. Commercial Waste Collection (DACPLG18)

Waste and recyclable material, generated by this premises, must not be collected between the hours of 10pm and 6am on any day.

Reason: To protect the acoustic amenity of surrounding properties.(DACPLG18)

59. **Loading and Unloading**

All loading and unloading of vehicles and the delivery of goods must be carried out wholly within the site.

Reason: To ensure that deliveries can occur safely within the site and does not adversely affect traffic or pedestrian safety and amenity. (DACPLG20)

60. **Deliveries**

No deliveries, loading or unloading associated with the premises are to take place between the hours of 10 pm and 6am on any day.

Reason: To protect ensure the acoustic amenity of surrounding properties. (DACPLG21)

61. **Commercial Waste and Recycling Storage**

Commercial waste and recycling material/storage bins must be stored in a separate area to the residential waste and recycling material/storage bins.

Reason: To ensure that commercial waste and residential waste is not mixed and is properly managed. (DACPLG25)

62. **Amenity**

The implementation of this development shall not adversely affect the amenity of the neighbourhood or interfere unreasonably with the comfort or repose of a person who is outside the premises by reason of the emission or discharge of noise, fumes, vapour, odour, steam, soot, ash, dust, waste water, waste products, grit, oil or other harmful products.

Reason: To ensure the surrounding area and people within the neighbourhood are not affected adversely and to ensure compliance with the *Protection of the Environment Operations Act 199* (DACPLGOG1)

CONDITIONS THAT MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF ANY STRATA SUBDIVISION OR SUBDIVISION CERTIFICATE

63. **Certification of Utility Services**

The provision of all utilities/services and/or street lighting are to be certified by the relevant authority(s) and/or authorised contractor.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of the Subdivision Certificate.

Reason: To ensure services have been provided in accordance with the relevant authorities requirements. (DACENH15)

64. **On-Site Stormwater Detention Compliance Certification**

Prior to issue of a subdivision certificate the on-site stormwater detention (OSD) system must be certified by a consulting engineer and include a "works as executed" (WAE) drawing certified by a registered surveyor and overdrawn in red on a copy of the approved OSD system plans. Additionally a Compliance Certificate is to be issued by an Accredited Certifier in Civil Works

registered with the Institute of Engineers Australia, stating that the works are in accordance with the approved plans.

Reason: To ensure stormwater disposal is constructed to standard specifications AUSPEC 1. (DACENH21)

65. **Right of Access (through-site vehicle link)**

A right of access (under the provisions of Section 88B of the Conveyancing Act) is to be created on the final plan of subdivision and the accompanying 88B instrument to ensure a through-site vehicle access within the ground level to No. 814 -816 Pittwater Road, Dee Why (Avis site) as detailed on the approved plans.

The terms of the right of way (available from Northern Beaches Council), are to be prepared by a registered surveyor to Northern Beaches Council's standard requirements at the applicant's expense.

Activation of the through site link will only occur upon redevelopment and physical commencement of a mixed-use development on 814-816 Pittwater Rd Dee Why (Avis Site).

Details demonstrating compliance with this condition are to be submitted to the Principal Certifying Authority prior to the issue of any Subdivision Certificate.

Reason: To allow the reasonable development of the neighbouring site. (DACENH23)

66. **Title Encumbrances**

All easements, rights of the carriageway, positive covenants and restrictions as to user as indicated on the plans and required by this consent are to be created on the title naming Northern Beaches Council as the sole authority empowered to release or modify.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Subdivision Certificate.

Reason: To ensure proper management of land. (DACENHS14)

Right to Review by the Council

You may request Council review the determination of the application under Section 82A of the Environmental Planning & Assessment Act 1979 if it is NOT integrated or designated development. Any request to review the application must be made and determined within 6 months from the date of determination.

NOTE: A fee will apply for any request to review the determination.

Right of Appeal

If you are dissatisfied with this decision Section 97 of the Environmental Planning & Assessment Act 1979 may give you the right to appeal to the Land and Environment Court within 6 months after the date on which you receive this notice.

Signed On behalf of the Consent Authority



Name Peter Robinson
 Executive Manager Development Assessment


Date 12/09/2018

NOTE: Signed by Northern Beaches Council in accordance with the Environmental Planning and Assessment Act 1979 and EP&A Regulation 2000 as determined by the Sydney North Planning Panel on 12/09/2018.



GENERAL ADVICE
Advisory Notes (General)

Where are you in the development process?



Note: The advice within this document is provided in good faith as a guide to assist applicants understand the broad process and will not detail every step or every requirement for demolition, building construction works or subdivision required or business operating requirements under New South Wales or Commonwealth Legislation. If you require clarification or have any questions, please contact your Certifier or Council's Planning and Development Enquiries Team.

The attached Notice of Determination includes conditions of consent which must be complied with.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

Building Certification

The Environmental Planning and Assessment Act 1979 provides that:

- Building work cannot occur unless a construction certificate has been issued;
- Occupation of building works cannot occur unless an occupation certificate has been issued
- Subdivision cannot be registered until a subdivision certificate has been issued
- Mandatory Inspection for building work must be completed

Please refer to process chart for more detail.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

Certification Services

Construction Certificates / Occupation Certificates / Subdivision Certificates / Strata Certificates, can be issued by Council or an accredited private certifier (Note Council must be the Principal Certifying Authority (PCA) for subdivisions).

Council is well placed to provide Certification Services. Council can issue Construction Certificates and act as your Principle Certifying Authority at competitive rates. Please visit our web site www.northernbeaches.nsw.gov.au or speak to our Customer Service Officers if you have any further questions about our Certification Services or if you wish to use Council as your certifier.

Charges Associated with the Development Consent

All bonds, fees, (s94A) Development Contributions or the Long Service Levy detailed within the Notice of Determination are required to be paid prior to the issuing of any Construction Certificate.

Bonds are released after:

1. 'Final Occupation Certificate' has been received by Council; and
2. Final inspection by a Council Officer where:
 - o the development is complete
 - o damage has not been caused to council assets during the works
 - o conditions of development consent have been met.

The bond will be released to the person or business who paid the bond to Council (The name that appears on the original receipt)

Acceptable Form of Security Bonds

Council will accept bank guarantee (in a form acceptable to Council) in lieu of cash and is required prior to the issue of a construction certificate.

Modifications to the consent

If you seek to make any changes to the development (which may include internal / external configuration of the building, variation to facades, site layout or any changes to the proposed operation or use), the modifications may require the submission and approval of an application to modify the development consent prior to the issuing of a Construction Certificate and prior to the works being

carried out. The proposed changes should be discussed with the PCA.

(Note: A failure to gain approval prior to the works being carried out is a serious breach of the Environmental Planning & Assessment Act 1979 which attracts penalties and may also result in legal action.)

Other Matters not detailed within the Notice of Determination

The Notice of Determination does not stipulate every requirement that must be completed to satisfy New South Wales and Commonwealth legislation.

You should check, as may be relevant, with other authorities including but not limited to:

- Workcover NSW for work safety and asbestos requirements
- Sydney Water – Quick Check Agent for the provision of water and sewer services
- Energy & Gas suppliers for utility services
- Department of Fair Trading for advice about builders and licensing
- Building Professionals Board for advice about private certifiers
- NSW Roads and Maritime Services for works on state roads only
- Human Rights and Equal Opportunity Commission for access issues
- NSW Land and Property Information for Land Title matters
- Australia Post for the positioning and dimensions of mail boxes in new commercial and residential developments;

Dial Before You Dig

Underground assets may exist in the area that is subject to your application. In the interests of health and safety and in order to protect damage to third party assets please contact Dial before you dig at www.1100.com.au or telephone on 1100 before excavating or erecting structures (This is the law in NSW). If alterations are required to the configuration, size, form or design of the development upon contacting the Dial before You Dig service, an amendment to the development consent (or a new development application) may be necessary. Individuals owe asset owners a duty of care that must be observed when working in the vicinity of plant or assets. It is the individual's responsibility to anticipate and request the nominal location of plant or assets on the relevant property via contacting the Dial before you dig service in advance of any construction or planning activities.

Telecommunications Act 1997 (Commonwealth)

Telstra (and its authorised contractors) are the only companies that are permitted to conduct works on Telstra's network and assets. Any person interfering with a facility or installation owned by Telstra is committing an offence under the Criminal Code Act 1995 (Cth) and is liable for prosecution. Furthermore, damage to Telstra's infrastructure may result in interruption to the provision of essential services and significant costs. If you are aware of any works or proposed works which may affect or impact on Telstra's assets in any way, you are required to contact Telstra's Network Integrity Team on Phone Number 1800810443.

(1) if the development is likely to disturb or impact upon telecommunications infrastructure, written confirmation from the service provider that they have agreed to the proposed works must be submitted

to the Principal Certifying Authority prior to the issue of a Construction Certificate or any works commencing, whichever occurs first; and

(2) The arrangements and costs associated with any adjustment to telecommunications infrastructure shall be borne in full by the applicant/developer.

Model

If you submitted a model with the application it must be collected from the Council offices within fourteen (14) days of the date of this determination. Models not collected will be disposed of by Council.

Trade waste agreement

A Trade Waste Agreement must be obtained from Sydney Water prior to the discharge of trade wastewater to the sewer system. Trade wastewater is defined as 'discharge water containing any substance produced through industrial or commercial activities or operation on the premises'.

Waste collection

Liquid and solid wastes generated on the site must be collected, transported and disposed of in accordance with the requirements of the Protection of the Environment Operations Act 1997. Records must be kept of all waste disposal from the site.

Material to be removed from the site must be source separated on site to maximise recycling, and the material disposed of to an appropriate disposal and recycling facility in accordance with the approved Waste Management Plan.

Aboriginal Heritage

If in undertaking excavation or works and any Aboriginal site or object is, or is thought to have been found, all works are to cease immediately and the applicant is to contact the Aboriginal Heritage Officer for Warringah Council, and the Cultural Heritage Division of the Department of Environment and Climate Change (DECC).

On-Site Sewage Management System

This approval does not authorise the installation or operation of a new or modification of an existing on-site wastewater management system. An On-Site Sewage Management System must not be installed or operated unless an 'Approval to Install an On Site Sewage Management System' is obtained from Warringah Council.

Cost of Works

The applicant shall bear the cost of all works associated with the development that occurs on Council's property.

Relocation of stormwater drainage

Council is not responsible for the cost of relocating Council's stormwater drainage pipes through the subject property.

Tree preservation

Where tree work has not been approved by this Development Consent the developer is notified that a general Tree Preservation Order applies to all trees in the Northern Beaches Local Government Area. This order prohibits the ringbarking, cutting down, topping, lopping, pruning, transplanting, injuring, or wilful destruction of such trees except without the prior written consent of Council.

Storage bins on footpath and roadway

Approval is required from Council prior to the placement of any storage bin on Council's footpath and/or roadway.



Protection of Public Places

(1) If the work involved in the erection or demolition of a building:

- (a) is likely to cause pedestrian or vehicular traffic in a public place to be obstructed or rendered inconvenient; or
- (b) building involves the enclosure of a public place,

a hoarding and site fencing must be erected between the work site and the public place.

(2) If necessary, an awning is to be erected, sufficient to prevent any substance from, or in connection with, the work falling into the public place.

(3) The work site must be kept lit between sunset and sunrise if it is likely to be hazardous to persons in the public place.

(4) Any such hoarding, fence or awning is to be removed when the work has been completed.

(5) No access across public reserves or parks is permitted.

Note: Prior to the erection of any temporary fence or hoarding over property owned or managed by Council, written approval must be obtained.

Road Opening Permit

The developer/applicant is to obtain a "Road Opening Permit" from Council and pay all appropriate charges prior to commencement of any work on Council property. The developer/applicant shall be responsible for all public utilities and services in the area of the work, and as such shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.

Special Permits

Unless otherwise specifically approved in writing by Council, all works, processes, storage of materials, loading and unloading associated with the development are to occur entirely on the property. The applicant, owner or builder must apply for specific permits available from Council. A minimum of forty-eight (48) hours notice is required for all permits except work zones, which may require additional assessment time.

- Permit for on-street mobile plant

Restrictions apply to the hours of operation and the area of operation for on street mobile plant equipment (for example cranes, concrete pumps, cherry pickers). Separate permits are required for each occasion and each piece of equipment. It is the responsibility of the applicant, owner and builder to take whatever steps are necessary to ensure that the use of any equipment does not violate adjoining property owner's rights.

- Hoarding Permit

Permits are required to erect Class A, Class B and Class C hoardings. If an 'A' Class hoarding is to alienate a section of Council's property, that section will require a permit for the occupation of Council's property.

- Storage of building materials and building waste containers (skips) on Council's property

Permits to utilise Council property for the storage of building materials and building waste containers (skips) are required for each location. Failure to obtain the relevant permits will result in the building materials or building waste containers (skips) being impounded by Council with no additional notice being given.

- Kerbside restrictions, work zones

Existing kerbside restrictions apply. An application must be made to Council for the alteration of existing kerbside restrictions or the provision of a construction zone. Other permits may include out of construction hours permits.

Licensing requirements for removal of bonded asbestos

Anyone who removes, repairs or disturbs bonded asbestos must hold a bonded or a friable asbestos licence, or a demolition licence in accordance with Workcover requirements and the Occupational Health and Safety Act 2000.

Pool Access

Access to pools are required to be restricted by a child resistant barrier in accordance with the regulations prescribed in all relevant Acts, Regulations and Australian Standards including:

- (i) Swimming Pools Act 1992;
- (ii) Swimming Pools Amendment Act 2012;
- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools

It is your responsibility as a land owner to ensure any fencing is maintained.

Dewatering

Where dewatering works are required on the development site during construction, the developer/applicant must apply for and obtain a bore license from the NSW Department of Water and Energy. The bore license must be obtained prior to commencement of dewatering works.

Requirement to Notify about New Contamination Evidence

Any new information revealed during works that has the potential to alter previous conclusions about site contamination or hazardous materials shall be immediately notified to Council and the Principal Certifying Authority.

Flood Evacuation Plan

If your site is on flood prone land you may wish to consider the preparation of a flood evacuation plan.

Generally a Flood Evacuation Plan would be prepared by suitably qualified Engineer (e.g. Hydraulic) with a number of years experience in flood management and who is eligible for Membership to the Australian Institute of Engineers.

Some matters that you may wish to consider (but not limited to) include:

- (i) a route of evacuation to higher ground and / or point of shelter
- (ii) depth of water for a Possible Maximum Flood event surrounding the building
- (iii) details of 'last chance' evacuation water levels / times for evacuation prior to floodwaters surrounding the building
- (iv) provide details of flood warning systems and protocols
- (v) details of how this information will be distributed and people educated for users of the site.

You may seek to discuss this with the State Emergency Service of NSW.

Utility Service Requirements

Where development requires the installation of, or the relocation of utility services being (but not limited to) gas, water, electricity and telecommunications, the installation of, or the relocation of utility services shall be conducted in accordance with the requirements of the relevant service provider / authority (unless stipulated by any other condition of the consent or will result in damage to threatened or endangered species defined under the Threatened Species Conservation Act 1995).

Plant & Equipment Kept Within Site

All plant and equipment used in the erection of the building, including concrete pumps, wagons, lifts, mobile cranes, etc, shall be situated within the boundaries of the site and so placed that all concrete slurry, water, debris and the like shall be discharged onto the building site, and is to be contained within the site boundaries. This does not prevent any requirement to comply with the Protection of the Environment Operations Act.

Lighting

Illumination of the site is to be arranged in accordance with the requirements of Australian Standard 4282 - 1997 Control of the obtrusive effects of outdoor lighting so as not to impact upon the amenity of the occupants of adjoining and nearby residential premises.

Silt and Sediment Control

During any onsite demolition, excavation and construction works, the site should be maintained in accordance with "The Blue Book - Managing Urban Stormwater (MUS): Soils and Construction".

In managing the site provision shall be made throughout the period of works to prevent transmission of soil to the public road, drainage system, any riparian lands or off site in any manner. Upon completion of the development, any measures to prevent the transition of soil off site to remain in place until the site is stabilised.

A failure to prevent the transmission of silt and sediment and / or causing, water pollution, air pollution, noise pollution or land pollution may result in a breach of the Protection of the Environment Operations Act and orders, penalties and prosecutions may occur.

Maintenance of Sediment and Erosion Control Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain.

Reason: To avoid erosion and sedimentation impacts that will result in an adverse change in watercourse or riparian land condition

Installation and Maintenance of Sediment and Erosion Control

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: soils and construction (2004).

Techniques used for erosion and sediment control on site are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and the site is sufficiently stabilised with vegetation.

Reason: To protect the surrounding environment from the effects of sedimentation and erosion from the site

Dividing Fences Act 1991

The construction and maintenance of side boundary fences is to be agreed upon by all adjoining property owners of the fence. Works are to be in accordance with the Dividing Fences Act 1991.

OTHER MATTERS

Child Care Centres

A license to operate a child care centre must be obtained from the NSW Department of Community Services prior to the commencement of the use of the child care centre.

Disability Access

This decision does not ensure compliance with the Commonwealth Disability Discrimination Act 1992. Applicants are strongly advised to investigate their requirements under that Act

Food Premises

Food premises are required to comply with the requirements of the Food Act 2003, the Food Standards Code and Australian Standards.

The proprietor of a food business must notify the NSW Food Authority of the details of the business. Notification may be done either online at www.foodnotify.nsw.gov.au or by lodging a completed NSW Food Authority notification form to the NSW Food Authority or Council.

Wheel washing facility

All trucks leaving the site, having had access to unpaved or contaminated areas, shall depart via a wheel wash facility in order to prevent mud, dust or debris from being deposited on Council's roads. The wheel wash facility shall be constructed prior to any truck movements occurring. Water from the wheel wash facility must not cause pollution. Any direction of Council with regard to cleaning trucks or the clean up of road pavements adjoining the site shall be complied with immediately.

Monitoring State of Roadways

The applicant shall monitor the state of roadways leading to and from the site and shall take all necessary steps to clean up any adversely impacted road pavements as directed by Council.

Storage of Dangerous Goods

Prior to the storage of any "dangerous goods" on the premises, a copy of a license obtained from the Chemical Safety Branch of Work Cover Authority must be submitted to Council.

Storage of Flammable and Combustible Liquids

Flammable and combustible liquids must be stored in accordance with Australian Standard 1940 The Storage and Handling of Flammable and Combustible Liquids.

Noise and Vibration

The premises, including operation of vehicles, shall be conducted so as to avoid offensive noise or vibration and cause no interference to adjoining or nearby occupants. Special precautions must be taken to avoid nuisance in neighbouring residential areas, particularly from machinery, vehicles, warning sirens, public address systems and the like.

Hairdressing/Beauty Treatment/ Skin penetration Requirements

The premises must comply with the following requirements before the commencement of business:

- i) A hand wash basin with warm water delivered through a common spout must be provided in the treatment area. The hand wash basin must be provided with liquid soap and paper towel.
- ii) The wall behind the hand wash basin from the floor to a height of 450mm above the top of the washbasin and from the centre of the washbasin to a distance of 140mm beyond each side of the wash basin, must be finished with a material that is durable, smooth, impervious to moisture and capable of being easily cleaned (eg tiles).
- iii) The premises must be provided with washing, drainage, ventilation and lighting that are adequate for the carrying out of hairdressing/beauty treatment/skin penetration procedures.
- iv) The floor coverings must be smooth and impervious.

- v) All furniture, shelves and fittings must be constructed of, or covered with a material that is smooth, impervious to moisture and capable of being easily cleaned.
- vi) Adequate lockers must be provided for the storage of employees clothing and personal effects.
- vii) The premises must be provided with facilities that are adequate for the purpose of storing of hairdressing/beauty treatment/skin penetration appliance and utensils.
- viii) The premises must be provided with a sink sullied with hot and cold water for washing equipment.

Food Premises Construction Requirements

The food premises must comply with the following specific construction requirements:

Solid walls must be provided in all food handling areas (solid includes brick, cement and foam filled preformed panels);

- ix) Walls in food preparation and wash up areas must be finished with a smooth and impervious surface to a height of at least 2 metres.
- x) Hand wash basins must be provided with warm water delivered through a common spout with taps that are hands free operation;
- xi) Coving with a radius of 25mm must be provided between all floor and wall joints in food handling areas;
- xii) The open space between the top of the coolroom and the ceiling must be fully enclosed and kept insect and pest proof;
- xiii) The coolroom must be able to be opened from the inside with out a key and fitted with an alarm that can only be operated from within the coolroom;
- xiv) The doors to the toilet air lock and toilet compartment must be tight fitting and self closing;
- xv) The rear external door must be self closing or be provided with a fly screen that is self closing;
- xvi) Where cooking or extensive heating processes or such other processes as may be specified are carried out in food preparation areas, an approved mechanical ventilation system shall be installed and operated in accordance with AS 1668 part.1 & 2.

Legionella Control

Cooling towers, warm water systems, water cooling systems must be registered with the Council. Details of registration are to be provided to the Council prior to operation.

Pool/Spa Safety

Owners of properties with swimming pools and spa's must meet safety compliance and registration requirements. Provisions also apply when renting/selling properties. Details are available from the Division of Local Government.

Grease Trap

Contact Sydney Water to determine what trade waste provisions you are required to provide to your food premises. Should a grease trap be required by Sydney Water, it must be located in an area that is easily accessible for the removal of waste water and must not be installed in any kitchen, food preparation or food stage area. The design and location of the grease trap should also not impede on any commercial right of way or pedestrian access.

Bandicoot/Penguin

Long-nosed Bandicoots & Little Penguins – Best Practices for Residents Residents are encouraged to follow a number of *Best Practices* to assist with the protection and management of the endangered populations of Long-nosed Bandicoots and Little Penguins:

- Long-nosed Bandicoots, Little Penguins and other native animals should never be fed as it may cause them nutritional problems, hardship if supplementary feeding is stopped, and it may increase predation.
- Feral cats or foxes should never be fed or food left out where they can access it, such as rubbish bins without lids or pet food bowls, as these animals present a significant threat to Long-nosed Bandicoots, Little Penguins and other wildlife.
- The use of insecticides, fertilisers, poisons and/or baits should be avoided on the property.



Garden insects will be kept in low numbers if Long-nosed Bandicoots are present.

- When the North Head Long-nosed Bandicoot Recovery Plan is released it should be implemented where relevant.
- Dead Long-nosed Bandicoots or Little Penguins should be reported by phoning Manly Council on 9976 1500 or Department of Environment and Conservation on 9960 6266.
- Please drive carefully as vehicle related injuries and deaths of Long-nosed Bandicoots and Little Penguins have occurred in the area. Care should also be taken at night in the drive way when moving cars as bandicoots will seek shelter beneath vehicles.
- Cat/s and or dog/s that currently live on the property should be kept indoors at night to avoid disturbance/death of native animals. Ideally, when the current cat/s and/or dog/s that live on the property no longer reside on the property it is recommended that they not be replaced by new dogs or cats.
- Report all sightings of feral rabbits, feral or stray cats and/or foxes to N B Council.