

Natural Environment Referral Response - Riparian

| Application Number: | DA2021/1135 | |
|---------------------|-------------|--|
| | | |
| Date: | 30/07/2021 | |

| Date: | 30/07/2021 |
|---------------------------------|---|
| То: | Gareth David |
| Land to be developed (Address): | Lot 3 DP 1196894 , 6 Guwara Road DUFFYS FOREST NSW 2084 |

Reasons for referral

This application seeks consent for the following:

- All Development Applications on land, and located within 40 metres of land, containing a watercourse, or
- All Development Applications on land containing a wetland, or located within 100m of land containing a wetland,
- All Development Applications on land that is mapped as "DCP Map Waterways and Riparian Land".

And as such, Council's Natural Environment Unit officers are required to consider the likely impacts on drainage regimes.

Officer comments

This application has been assessed against legislation and policy relating to waterways, drainage regimes and groundwater.

An erosion and sediment control plan is required. Sediment and erosion controls must be installed prior to any disturbance of soil on site and maintained until all work is complete and groundcover reestablished.

As the property adjoins National Park, and the application proposes to increase impervious area by more than 50m^2 a filtration device must be installed to capture organic matter and coarse sediments prior to discharge of stormwater from the site, and maintained throughout the life of the development.

This application, subject to conditions, is recommended for approval as it is unlikely to have an adverse effect on waterways, drainage regimes or groundwater if conditions are adhered to.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Natural Environment Conditions:

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION

DA2021/1135 Page 1 of 3



CERTIFICATE

Erosion and Sediment Control Plan

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points
- Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment.

Water Quality Management

The applicant must install a sub-surface drainage absorption system that has the capacity to capture all stormwater runoff from the property for infiltration prior to the boundary of the property with National Park. This system must be designed to capture coarse and fine sediments and nutrients prior to discharge of stormwater from the land. All stormwater treatment measures must make provision for convenient and safe regular inspection, periodic cleaning, and maintenance. Non-compliant systems may result in a referral to the NSW Office of Environment and Heritage.

Details demonstrating compliance are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Installation and Maintenance of Sediment and Erosion Controls

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

DA2021/1135 Page 2 of 3



Reason: Protection of the receiving environment.

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

Works as Executed Drawings - Stormwater Treatment Measures

Works as Executed Drawings for the stormwater treatment measures must be prepared in accordance with Council's Guideline for Preparing Works as Executed Data for Council Stormwater Assets.

The drawings shall be submitted to the Principal Certifying Authority prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

Maintenance of Stormwater Treatment Measures

Stormwater treatment measures must be maintained at all times in accordance with manufacturer's specifications and as necessary to achieve the required stormwater quality targets for the development.

Northern Beaches Council reserves the right to enter the property and carry out appropriate maintenance of the device at the cost of the property owner.

Reason: Protection of the receiving environment.

DA2021/1135 Page 3 of 3