
### NO

ALL DIMENSIONS SHOULD BE VERIFIED ON SITE BY THE BUILDER WHO WILL BE RESPONSIBLE FOR THE ACCURATE SETTING OUT OF THE JOB

ALL CONSTRUCTION IS TO COMPLY WITHTHE RELEVANT BUILDING CODES AND LOCAL COUNCIL REQUIREMENTS

ALL DIMENSIONS THAT RELATE TO SITE BOUNDARIES AND EASEMENTS ARE SUBJECT TO VERIFICATION BY A SITE SURVEY ROOF WATER AND SUBSOIL DRAINAGE TO BE DISPODED OF IN THE APPROVED MANNER OR AS DIRECTED DOWN PIPE LOCATION TO BE DETERMINED BY THE ROOF PLUMBER ELECTRICAL, POWER AND LIGHT OUTLETS TO BE DETERMINED BY THE OWNER STRUCTURAL DETAIL AND DESIGN TO BE APPROVED BY A STRUCTURAL ENGINEER ANY ADDITIONAL DETAILING SHALL BE RESOLVED BETWEEN THE OWNER AND THE BUILDER ALL LEVELS TO AUSTRALIAN HEIGHT DATUM



northern beaches council

THIS PLAN IS TO BE READ IN CONJUNCTION WITH THE CONDITIONS OF DEVELOPMENT CONSENT

MOD2022/0220

14.4.21 DELETE SECONDARY DWELLING / REDUCE FRONT DECK

12.5.20 POOL DECK DELETED/ CONDITIONS OF CONSENT FOR C.C.

10-12-14 MODIFICATION TO DA NO 263/14


2411 14 REDUCE ROOF TO DECK / DELETE CABANA ROOF PERGOLA IN LIEU.


## PROPOSED ALTERATIONS & ADDITIONS

WISEMAN RESIDENCE 63 MARINE PARADE AVALON BEACH MARCH 2019 (MOD APRIL 2022)

DWG 0319 1/5 SHIMDESIGN architectural design and drafting k2shimeld@gmail.com









THIS PLAN IS TO BE READ IN
CONJUNCTION WITH
THE CONDITIONS OF DEVELOPMENT
CONSENT

MOD2022/0220

90 J 2400 J 90 4770 J 90 7440 1750

D. 14.4.2020 DELETE SECONDARY DWELLING FREE STANDING DOUBLE GARAGE IN LIEU RETAIN EXISTING ENTRY, STAIR, RUMPUS ROOM AND BATHROOM.

# PROPOSED ALTERATIONS & ADDITIONS

WISEMAN RESIDENCE 63 MARINE PARADE AVALON BEACH MARCH 2019 (MOD APRIL 2022)

DWG 0319 2/5 SHIMDESIGN architectural design and drafting k2shimeld@gmail.com



3000

1500


72.

4300


THIS PLAN IS TO BE READ IN
CONJUNCTION WITH
THE CONDITIONS OF DEVELOPMENT
CONSENT

beaches

MOD2022/0220



14700 AS EXISTING





THIS PLAN IS TO BE READ IN
CONJUNCTION WITH
THE CONDITIONS OF DEVELOPMENT
CONSENT

MOD2022/0220

### NATIONAL CONSTRUCTION REQUIREMENTS

PEST CONTROL TO COMPLY WITH NCC PART 3.1.3 AS3660.1-2000/20014
BATHROOM WINDOW GLAZING TO BE TOUGHENED GLASS
STAIR CONSTRUCTION TO COMPLY WITH NCC PART 3.9.1
BALUSTRADES AND HANDRAILS TO COMPLY WITH NCC PART 3.9
SMOKE ALARMS AS INDICATED ON PLAN TO COMPLY WITH NCC PART 3.7.2

#### **BASIX NOTE:**

SWIMMING POOL TO BE OUTDOORS, CAPACITY NOT GREATER THAN 16 KILOLITRES , TO HAVE POOL COVER AND POOL PUMP TIMER AND SOLAR HEATING WITH GAS BOOSTER

SPA CAPACITY NOT GREATER THAN 2.7 KILOLITRES, MUST HAVE SPA COVER AND SPA PUMP TIMER. SPA HEATER TO BE GAS

A RAINWATER TANK WITH MINIMUM 1181LTS CAPACITY TO BE INSTALLED, COLLECTING AT LEAST 256 M2 OF ROOF AREA OF RAINWATER RUNOFF AND CONNECTED TO AT LEAST ONE TAP LOCATED WITHIN 10M OF THE EDGE OF THE POOL/SPA

EXTERNAL FRAMED WEATHERBOARD CLAD WALLS TO HAVE MIN. R1.3 INSULATION (R1.7 INC. CONSTRUCTION) SUSPENDED FLOOR WITH ENCLOSED SUBFLOOR TO HAVE MIN. R0.6 INSULATION (R1.30 INC. CONSTRUCTION) ROOF WITH DARK SOLAR ABSORPTANCE TO HAVE FOIL SARKING AND CEILINGS WITH R3.0 CEILING INSULATION

BATHROOM AND KITCHEN TAPS AND SHOWER TO HAVE MINIMUM 3 STAR RATING/MAX 9LTRS PER MINUTE TOILETS TO HAVE MINIMUM 3 STAR RATING, MAXIMUM 4 LTR FLUSH
MINIMUM 40% NEW OR ALTERED LIGHT FITTINGS TO BE FLUORESCENT, COMPACT FLURO OR LED LAMPS.
WINDOWS 1- 21 IN ACCORDANCE WITH BASIX CERTIFICATE A 184304- 03 DATED 4 AUGUST 2022

