

## DEVELOPMENT APPLICATION ASSESSMENT REPORT

<b>Application Number:</b>	DA2022/0977
----------------------------	-------------

<b>Responsible Officer:</b>	Phil Lane
<b>Land to be developed (Address):</b>	Lot 55 DP 28663, 64 Dolphin Crescent AVALON BEACH NSW 2107
<b>Proposed Development:</b>	Construction of a swimming pool
<b>Zoning:</b>	C4 Environmental Living
<b>Development Permissible:</b>	Yes
<b>Existing Use Rights:</b>	No
<b>Consent Authority:</b>	Northern Beaches Council
<b>Land and Environment Court Action:</b>	No
<b>Owner:</b>	Jessica Alexandra Zukowski
<b>Applicant:</b>	Paul Norman

<b>Application Lodged:</b>	21/06/2022
<b>Integrated Development:</b>	No
<b>Designated Development:</b>	No
<b>State Reporting Category:</b>	Residential - Alterations and additions
<b>Notified:</b>	01/07/2022 to 15/07/2022
<b>Advertised:</b>	Not Advertised
<b>Submissions Received:</b>	0
<b>Clause 4.6 Variation:</b>	Nil
<b>Recommendation:</b>	Approval

<b>Estimated Cost of Works:</b>	\$ 95,000.00
---------------------------------	--------------

### PROPOSED DEVELOPMENT IN DETAIL

The applicant seeks development consent for rear yard swimming pool and associated works, including removal of two (2) trees.

### ASSESSMENT INTRODUCTION

The application has been assessed in accordance with the requirements of the Environmental Planning and Assessment Act 1979 and the associated Regulations. In this regard:

- An assessment report and recommendation has been prepared (the subject of this report) taking into account all relevant provisions of the Environmental Planning and Assessment Act 1979, and the associated regulations;
- A site inspection was conducted and consideration has been given to the impacts of the

- development upon the subject site and adjoining, surrounding and nearby properties;
- Notification to adjoining and surrounding properties, advertisement (where required) and referral to relevant internal and external bodies in accordance with the Act, Regulations and relevant Development Control Plan;
- A review and consideration of all submissions made by the public and community interest groups in relation to the application;
- A review and consideration of all documentation provided with the application (up to the time of determination);
- A review and consideration of all referral comments provided by the relevant Council Officers, State Government Authorities/Agencies and Federal Government Authorities/Agencies on the proposal.

## SUMMARY OF ASSESSMENT ISSUES


Pittwater 21 Development Control Plan - D1.9 Side and rear building line

Pittwater 21 Development Control Plan - D1.14 Landscaped Area - Environmentally Sensitive Land

## SITE DESCRIPTION

<b>Property Description:</b>	Lot 55 DP 28663 , 64 Dolphin Crescent AVALON BEACH NSW 2107
<b>Detailed Site Description:</b>	<p>The property is known as 64 Dolphin Crescent, Avalon Beach and has a legal description of Lot 55 in Deposited Plan 28663. The site is characterised by a gentle slope to the southeast, has a total site area of 696.8m<sup>2</sup> and is currently occupied by single storey residence. The property is located on the northwestern side of Dolphin Crescent, and is surrounded by residential properties to the north, west and south, and Coral Reserve to the southeast.</p> <p>The site is located within the C4 Environmental Living zone and accommodates a single storey dwelling house and carport with landscaped gardens.</p>

Map:



## SITE HISTORY

**N0331/12** - Alterations and additions to the existing dwelling, carport and swimming pool approved 21 January 2013

**Mod2018/0096** - Modification of consent N0331/12 for the alterations and additions to the existing dwelling carport and swimming pool approved 15 May 2018.

## ENVIRONMENTAL PLANNING AND ASSESSMENT ACT, 1979 (EPAA)

The relevant matters for consideration under the Environmental Planning and Assessment Act, 1979, are:

Section 4.15 Matters for Consideration	Comments
Section 4.15 (1) (a)(i) – Provisions of any environmental planning instrument	See discussion on “Environmental Planning Instruments” in this report.
Section 4.15 (1) (a)(ii) – Provisions of any draft environmental planning instrument	There are no current draft environmental planning instruments.
Section 4.15 (1) (a)(iii) – Provisions of any development control plan	Pittwater 21 Development Control Plan applies to this proposal.
Section 4.15 (1) (a)(iiia) – Provisions of any planning agreement	None applicable.
Section 4.15 (1) (a)(iv) – Provisions of the Environmental Planning and Assessment Regulation 2021 (EP&A Regulation 2021)	Part 4, Division 2 of the EP&A Regulation 2021 requires the consent authority to consider "Prescribed conditions" of development consent. These matters have been addressed via a condition of consent.  Clause 29 of the EP&A Regulation 2021 requires the

Section 4.15 Matters for Consideration	Comments
	<p>submission of a design verification certificate from the building designer at lodgement of the development application. This clause is not relevant to this application.</p> <p>Clauses 36 and 94 of the EP&amp;A Regulation 2021 allow Council to request additional information. No additional information was requested in this case.</p> <p>Clause 61 of the EP&amp;A Regulation 2021 requires the consent authority to consider AS 2601 - 1991: The Demolition of Structures. This matter has been addressed via a condition of consent.</p> <p>Clauses 62 and/or 64 of the EP&amp;A Regulation 2021 requires the consent authority to consider the upgrading of a building (including fire safety upgrade of development). This matter has been addressed via a condition of consent.</p> <p>Clause 69 of the EP&amp;A Regulation 2021 requires the consent authority to consider insurance requirements under the Home Building Act 1989. This matter has been addressed via a condition of consent.</p> <p>Clause 69 of the EP&amp;A Regulation 2021 requires the consent authority to consider the provisions of the Building Code of Australia (BCA). This matter has been addressed via a condition of consent.</p>
Section 4.15 (1) (b) – the likely impacts of the development, including environmental impacts on the natural and built environment and social and economic impacts in the locality	<p>(i) <b>Environmental Impact</b> The environmental impacts of the proposed development on the natural and built environment are addressed under the Pittwater 21 Development Control Plan section in this report.</p> <p>(ii) <b>Social Impact</b> The proposed development will not have a detrimental social impact in the locality considering the character of the proposal.</p> <p>(iii) <b>Economic Impact</b> The proposed development will not have a detrimental economic impact on the locality considering the nature of the existing and proposed land use.</p>
Section 4.15 (1) (c) – the suitability of the site for the development	The site is considered suitable for the proposed development.
Section 4.15 (1) (d) – any submissions made in accordance with the EPA Act or EPA Regs	See discussion on “Notification & Submissions Received” in this report.
Section 4.15 (1) (e) – the public interest	No matters have arisen in this assessment that would

Section 4.15 Matters for Consideration	Comments
	justify the refusal of the application in the public interest.

## EXISTING USE RIGHTS

Existing Use Rights are not applicable to this application.

## BUSHFIRE PRONE LAND

The site is not classified as bush fire prone land.

## NOTIFICATION & SUBMISSIONS RECEIVED

The subject development application has been publicly exhibited from 01/07/2022 to 15/07/2022 in accordance with the Environmental Planning and Assessment Act 1979, Environmental Planning and Assessment Regulation 2000 and the Community Participation Plan.

As a result of the public exhibition of the application Council received no submissions.

## REFERRALS

Internal Referral Body	Comments
Landscape Officer	<p>The development application is for the construction of a new rear swimming pool and associated works, as described and illustrated in the Reports and Plans. A Landscape Plan (calculation plan only) and a Arboricultural Impact Assessment accompany the application and are assessed as part of this Landscape Referral.</p> <p>Council's Landscape Referral is assessed against the Pittwater Local Environment Plan clause C4 zone Environmental Living, and the following Pittwater 21 DCP controls (but not limited to):</p> <ul style="list-style-type: none"> <li>• B4.22 Preservation of Trees and Bushland Vegetation</li> <li>• C1.1 Landscaping</li> <li>• D1 Avalon Locality</li> </ul> <p>The site is located in the C4 Environmental Living zone, requiring development to achieve a scale integrated with the landform and landscape, and to minimise impact on the natural environment, including the retention of natural landscape features and existing trees, to satisfy the landscape objectives of the C4 Environmental Living zone.</p> <p>The existing property consists of established gardens with trees, palms and vegetation, and the proposal retains the landscape setting and thus maintains the intent of the C4 land use in terms of landscape outcome. An existing native tree is preserved in the front of the property and existing native trees in the rear are also preserved. Two Exempt Species palm trees require removal as identified in the Arboricultural Impact Assessment for the proposed works and these do not require Council consent for management or removal under the exempt provisions of the DCP. The Arboricultural Impact Assessment</p>



Internal Referral Body	Comments
	submitted provides tree protection measures for the existing trees and palms to be retained, as identified in the Arboricultural Impact Assessment.  Screen shrub planting to assist with privacy is required along the southern boundary to the extent of the proposed swimming pool and paved surrounds, as either retained existing planting or new screen planting, and conditions shall be imposed.
NECC (Bushland and Biodiversity)	The development will require removal of two Bangalow Palms that are within the proximity of the proposed pool. While a portion of the rear yard is mapped as Biodiversity (clause 7.6) and Wildlife Corridor (B4.6) under the Pittwater LEP and P21 DCP, the development is proposed in the area of least impact on the wildlife corridor and there will be no significant net loss of native vegetation. Therefore the development is designed, sited and will be managed to avoid any significant adverse environmental impact.

External Referral Body	Comments
Ausgrid: (SEPP Infra.)	The proposal was referred to Ausgrid who provided a response stating that the proposal is acceptable subject to compliance with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice. These recommendations will be included as a condition of consent.

## ENVIRONMENTAL PLANNING INSTRUMENTS (EPIs)\*

All, Environmental Planning Instruments (SEPPs, REPs and LEPs), Development Controls Plans and Council Policies have been considered in the merit assessment of this application.

In this regard, whilst all provisions of each Environmental Planning Instruments (SEPPs, REPs and LEPs), Development Controls Plans and Council Policies have been considered in the assessment, many provisions contained within the document are not relevant or are enacting, definitions and operational provisions which the proposal is considered to be acceptable against.

As such, an assessment is provided against the controls relevant to the merit consideration of the application hereunder.

## State Environmental Planning Policies (SEPPs) and State Regional Environmental Plans (SREPs)

### SEPP (Transport and Infrastructure) 2021

#### Ausgrid

Section 2.48 of Chapter 2 requires the Consent Authority to consider any development application (or an application for modification of consent) for any development carried out:

- within or immediately adjacent to an easement for electricity purposes (whether or not the electricity infrastructure exists).
- immediately adjacent to an electricity substation.
- within 5.0m of an overhead power line.

- includes installation of a swimming pool any part of which is: within 30m of a structure supporting an overhead electricity transmission line and/or within 5.0m of an overhead electricity power line.

Comment:

The proposal was referred to Ausgrid who raised no objections, subject to conditions which have been included in the recommendation of this report.

## **SEPP (Resilience and Hazards) 2021**

### **Chapter 2 – Coastal Management**

The site is subject to Chapter 2 of the SEPP. Accordingly, an assessment under Chapter 2 has been carried out as follows:

#### **Division 3 Coastal environment area**

##### **2.10 Development on land within the coastal environment area**

- 1) Development consent must not be granted to development on land that is within the coastal environment area unless the consent authority has considered whether the proposed development is likely to cause an adverse impact on the following:
  - a) the integrity and resilience of the biophysical, hydrological (surface and groundwater) and ecological environment,
  - b) coastal environmental values and natural coastal processes,
  - c) the water quality of the marine estate (within the meaning of the Marine Estate Management Act 2014), in particular, the cumulative impacts of the proposed development on any of the sensitive coastal lakes identified in Schedule 1,
  - d) marine vegetation, native vegetation and fauna and their habitats, undeveloped headlands and rock platforms,
  - e) existing public open space and safe access to and along the foreshore, beach, headland or rock platform for members of the public, including persons with a disability,
  - f) Aboriginal cultural heritage, practices and places,
  - g) the use of the surf zone.

Comment:

The proposed development is not considered likely to cause an adverse impact on the integrity and resilience of the biophysical, hydrological (surface and groundwater) and ecological environment, coastal environmental values and natural coastal processes, the water quality of the marine estate, native vegetation and fauna and their habitats, public open space or aboriginal cultural heritage.

- 2) Development consent must not be granted to development on land to which this clause applies unless the consent authority is satisfied that:
  - a) the development is designed, sited and will be managed to avoid an adverse impact

- referred to in subsection (1), or
- b) if that impact cannot be reasonably avoided—the development is designed, sited and will be managed to minimise that impact, or
  - c) if that impact cannot be minimised—the development will be managed to mitigate that impact.

Comment:

The development is designed, sited and will be managed to avoid an adverse impact referred to in subclause (1).

## **Division 4 Coastal use area**

### **2.11 Development on land within the coastal use area**

- 1) Development consent must not be granted to development on land that is within the coastal use area unless the consent authority:
  - a) has considered whether the proposed development is likely to cause an adverse impact on the following:
    - i) existing, safe access to and along the foreshore, beach, headland or rock platform for members of the public, including persons with a disability,
    - ii) overshadowing, wind funnelling and the loss of views from public places to foreshores,
    - iv) foreshores,
    - v) the visual amenity and scenic qualities of the coast, including coastal headlands, Aboriginal cultural heritage, practices and places, cultural and built environment heritage, and
  - b) is satisfied that:
    - i) the development is designed, sited and will be managed to avoid an adverse impact referred to in paragraph (a), or
    - ii) if that impact cannot be reasonably avoided—the development is designed, sited and will be managed to minimise that impact, or
    - iii) if that impact cannot be minimised—the development will be managed to mitigate that impact, and
  - c) has taken into account the surrounding coastal and built environment, and the bulk, scale and size of the proposed development.

Comment:

The proposed development is not considered likely to cause an adverse impact on safe access to and along the foreshore, overshadowing, wind funnelling and the loss of views from public places to foreshores, the visual amenity and scenic qualities of the coast, including coastal headlands, or cultural and built environment heritage.

## **Division 5 General**

### **2.12 Development in coastal zone generally—development not to increase risk of coastal hazards**

Development consent must not be granted to development on land within the coastal zone unless the consent authority is satisfied that the proposed development is not likely to cause increased risk of coastal hazards on that land or other land.



Comment:

The proposed development is not likely to cause increased risk of coastal hazards on that land or other land.

As such, it is considered that the application complies with the requirements of Chapter 2 of the State Environmental Planning Policy (Resilience and Hazards) 2021.

## **Chapter 4 – Remediation of Land**

Sub-section 4.6 (1)(a) of Chapter 4 requires the Consent Authority to consider whether land is contaminated. Council records indicate that the subject site has been used for residential purposes for a significant period of time with no prior land uses. In this regard it is considered that the site poses no risk of contamination and therefore, no further consideration is required under sub-section 4.6 (1)(b) and (c) of this Chapter and the land is considered to be suitable for the residential land use.

### **Pittwater Local Environmental Plan 2014**

Is the development permissible?	Yes
After consideration of the merits of the proposal, is the development consistent with:	
aims of the LEP?	Yes
zone objectives of the LEP?	Yes

### Principal Development Standards

Standard	Requirement	Proposed	% Variation	Complies
Height of Buildings:	8.5m	1.64m	N/A	Yes

### Compliance Assessment

Clause	Compliance with Requirements
Part 1 Preliminary	Yes
1.9A Suspension of covenants, agreements and instruments	Yes
Part 4 Principal development standards	Yes
4.3 Height of buildings	Yes
Part 5 Miscellaneous provisions	Yes
5.10 Heritage conservation	Yes
5.21 Flood planning	Yes
Part 7 Additional local provisions	Yes
7.1 Acid sulfate soils	Yes
7.2 Earthworks	Yes
7.6 Biodiversity protection	Yes
7.10 Essential services	Yes

### **Pittwater 21 Development Control Plan**

#### Built Form Controls

Built Form Control	Requirement	Proposed	% Variation*	Complies
Front building line	6.5m	26.87m	N/A	Yes
Rear building line	6.5m	3.79m	41.7%	No
Side building line	2.5m (north)	13.02m	N/A	Yes
	1m (south)	1.2m	N/A	Yes
Building envelope	3.5m (north)	Within envelope	N/A	Yes
	3.5m (south)	Within envelope	N/A	Yes
Landscaped area	60% (417.3m <sup>2</sup> )	50.3% (349.8m <sup>2</sup> )	16.2%	No

### Compliance Assessment

Clause	Compliance with Requirements	Consistency Aims/Objectives
Section A Shaping Development in Pittwater	Yes	Yes
A1 Introduction	Yes	Yes
A1.7 Considerations before consent is granted	Yes	Yes
A4 Localities	Yes	Yes
A4.1 Avalon Beach Locality	Yes	Yes
Section B General Controls	Yes	Yes
B1 Heritage Controls	Yes	Yes
B1.3 Heritage Conservation - General	Yes	Yes
B1.4 Aboriginal Heritage Significance	Yes	Yes
B3 Hazard Controls	Yes	Yes
B3.6 Contaminated Land and Potentially Contaminated Land	Yes	Yes
B4 Controls Relating to the Natural Environment	Yes	Yes
B4.6 Wildlife Corridors	Yes	Yes
B5 Water Management	Yes	Yes
B5.13 Development on Waterfront Land	Yes	Yes
B6 Access and Parking	Yes	Yes
B6.3 Off-Street Vehicle Parking Requirements	Yes	Yes
B8 Site Works Management	Yes	Yes
B8.1 Construction and Demolition - Excavation and Landfill	Yes	Yes
B8.3 Construction and Demolition - Waste Minimisation	Yes	Yes
B8.4 Construction and Demolition - Site Fencing and Security	Yes	Yes
B8.5 Construction and Demolition - Works in the Public Domain	Yes	Yes
Section C Development Type Controls	Yes	Yes
C1 Design Criteria for Residential Development	Yes	Yes
C1.1 Landscaping	Yes	Yes
C1.2 Safety and Security	Yes	Yes
C1.3 View Sharing	Yes	Yes
C1.4 Solar Access	Yes	Yes

Clause	Compliance with Requirements	Consistency Aims/Objectives
C1.5 Visual Privacy	Yes	Yes
C1.6 Acoustic Privacy	Yes	Yes
C1.7 Private Open Space	Yes	Yes
C1.9 Adaptable Housing and Accessibility	Yes	Yes
C1.12 Waste and Recycling Facilities	Yes	
C1.13 Pollution Control	Yes	Yes
C1.14 Separately Accessible Structures	Yes	Yes
C1.17 Swimming Pool Safety	Yes	Yes
C1.24 Public Road Reserve - Landscaping and Infrastructure	Yes	Yes
C1.25 Plant, Equipment Boxes and Lift Over-Run	Yes	Yes
Section D Locality Specific Development Controls	Yes	Yes
D1 Avalon Beach Locality	Yes	Yes
D1.1 Character as viewed from a public place	Yes	Yes
D1.4 Scenic protection - General	Yes	Yes
D1.5 Building colours and materials	Yes	Yes
D1.8 Front building line	Yes	Yes
D1.9 Side and rear building line	No	Yes
D1.14 Landscaped Area - Environmentally Sensitive Land	No	Yes
D1.15 Fences - General	Yes	Yes

### Detailed Assessment

#### **D1.9 Side and rear building line**

##### Description of non-compliance

The control requires a rear setback distance of 6.5m. The swimming pool is setback 3.79m, represent a variation of 41.7% to the rear setback control.

The underlying outcomes of the control are addressed as follows:

##### Merit consideration

*To achieve the desired future character of the Locality.*

##### Comment:

The proposed development as to be modified is consistent with Clause A4.1 Avalon Beach Locality of the P21 DCP, which details the desired future character of the site's locality.

*The bulk and scale of the built form is minimised.*

##### Comment:

Bulk and scale is minimised in that the proposed swimming pool is low-lying and are well integrated into the dense vegetation and boundary planting in the rear setback area. This ensures the proposal does not result in unreasonable visual impact or imposition on the principal dwelling of adjacent sites.

*Equitable preservation of views and vistas to and/or from public/private places.*

Comment:

The proposed development as to be modified does not obstruct any views or vistas to or from public or private places.

*To encourage view sharing through complimentary siting of buildings, responsive design and well-positioned landscaping.*

Comment:

As above, the proposed development as to be modified allows for view sharing in that its siting and design does not obstruct and views or vistas.

*To ensure a reasonable level of privacy, amenity and solar access is provided within the development site and maintained to residential properties.*

Comment:

The proposed development as to be modified is compliant in relation to amenity and solar access. Visual privacy will continue to be protected by existing fencing and evergreen screen vegetation maintained along the side and rear boundaries. The swimming pool which encroach the rear setback control are considered to be transitional areas and will not generally be used as habitable spaces.

*Substantial landscaping, a mature tree canopy and an attractive streetscape.*

Comment:

The proposed development maintains the existing landscape character of the site and is not considered to adversely impact the streetscape.

*Flexibility in the siting of buildings and access.*

Comment:

The proposed development allows for suitable flexibility in siting of buildings without resulting in any unreasonable impacts.

*Vegetation is retained and enhanced to visually reduce the built form.*

Comment:

The proposal does not result in any unreasonably adverse impacts to existing on-site vegetation, and the application has been reviewed by Council's Biodiversity and Landscape Officers, who are supportive of the proposal, subject to existing conditions of consent.

*A landscaped buffer between commercial and residential zones is achieved.*

Comment:

Not applicable. The subject site does not adjoin commercial land.

Having regard to the above assessment, it is concluded that the proposed development is consistent with the relevant objectives of PDCA 2014 and the objectives specified in s1.3 of the Environmental Planning and Assessment Act, 1979. Accordingly, this assessment finds that the proposal is supported, in this particular circumstance.

## **D1.14 Landscaped Area - Environmentally Sensitive Land**

### Description of non-compliance

Clause D1.14 of the Pittwater 21 DCP requires a minimum of 60% (417.3sqm) of the site area to be landscaped area.

The development as to be modified proposes 44.3% (308.1sqm) inclusive of areas provided as impervious landscape treatments of up to 6% (41.7sqm) of the total site area, the total landscaped area

is increased to 349.8sqm (50.3%).

#### Merit Consideration

With regards to the consideration for a variation, the development is considered against the underlying objectives of the control as follows:

- *To achieve the desired future character of the Locality.*

#### Comment:

The development as to be modified will allow for sufficient off-street parking for the occupants whilst maintaining a sufficient area of pervious lawn area. The development is therefore considered to achieve the desired future character of the locality.

- *To bulk and scale of the built form is minimised.*

#### Comment:

The proposed modifications are located at ground floor level and are integrated into the existing landscape setting, therefore ensuring that the bulk and scale of the built form is minimised.

- *A reasonable level of amenity and solar access is provided and maintained*

#### Comment:

The development as to be modified is appropriately sited within the context of the site, and is bordered by vegetation which acts as a screening mechanism between the subject site and adjoining properties such that reasonable amenity can be maintained. No unreasonable impacts upon solar access is likely to occur.

- *Vegetation is retained and enhanced to visually reduce the built form.*

#### Comment:

Two (2) trees (exempt species) are to be removed and Council's Landscape Officer has provided comments and appropriate conditions to ensure that this merit consideration is maintained and satisfied.

- *Conservation of natural vegetation and biodiversity.*

#### Comment:

No native vegetation or wildlife species will adversely be affected by the proposed works.

- *Stormwater runoff is reduced, preventing soil erosion and siltation of natural drainage channels.*

#### Comment:

The proposed development retains significant areas of soft landscaping, thereby assisting with prevention of runoff, soil erosion, and siltation.

- *To preserve and enhance the rural and bushland character of the area.*

Comment:

The development will maintain the bush land character of the area given the modest size of the proposal and the established landscaping within the site that is to be retained.

- *Soft surface is maximised to provide for infiltration of water to the water table, minimise run-off and assist with stormwater management.*

Comment:

The site contains a significant portion of pervious surface which allows for the infiltration of water to the water table, minimises run-off and also assists with stormwater management.

Having regard to the above assessment, it is concluded that the proposed development is consistent with the relevant objectives of PDCP 2014 and the objectives specified in s1.3 of the Environmental Planning and Assessment Act, 1979. Accordingly, this assessment finds that the proposal is supported, in this particular circumstance.

## **THREATENED SPECIES, POPULATIONS OR ECOLOGICAL COMMUNITIES**

The proposal will not significantly affect threatened species, populations or ecological communities, or their habitats.

## **CRIME PREVENTION THROUGH ENVIRONMENTAL DESIGN**

The proposal is consistent with the principles of Crime Prevention Through Environmental Design.

## **POLICY CONTROLS**

### **Northern Beaches Section 7.12 Contributions Plan 2022**

As the estimated cost of works is less than \$100,001.00 the policy is not applicable to the assessment of this application.

## **CONCLUSION**

The site has been inspected and the application assessed having regard to all documentation submitted by the applicant and the provisions of:

- Environmental Planning and Assessment Act 1979;
- Environmental Planning and Assessment Regulation 2000;
- All relevant and draft Environmental Planning Instruments;
- Pittwater Local Environment Plan;
- Pittwater Development Control Plan; and
- Codes and Policies of Council.

This assessment has taken into consideration the submitted plans, Statement of Environmental Effects,



all other documentation supporting the application and public submissions, and does not result in any unreasonable impacts on surrounding, adjoining, adjacent and nearby properties subject to the conditions contained within the recommendation.

In consideration of the proposal and the merit consideration of the development, the proposal is considered to be:

- Consistent with the objectives of the DCP
- Consistent with the zone objectives of the LEP
- Consistent with the aims of the LEP
- Consistent with the objectives of the relevant EPIs
- Consistent with the objects of the Environmental Planning and Assessment Act 1979

It is considered that the proposed development satisfies the appropriate controls and that all processes and assessments have been satisfactorily addressed.

## RECOMMENDATION

THAT Council as the consent authority grant Development Consent to DA2022/0977 for Construction of a swimming pool on land at Lot 55 DP 28663, 64 Dolphin Crescent, AVALON BEACH, subject to the conditions printed below:

## DEVELOPMENT CONSENT OPERATIONAL CONDITIONS

### 1. Approved Plans and Supporting Documentation

The development must be carried out in compliance with the endorsed stamped plans and documentation listed below, except as amended by any other condition of consent:

#### a) Approved Plans

Architectural Plans - Endorsed with Council's stamp		
Drawing No.	Dated	Prepared By
P1	March 2022	Right Angle Design & Drafting
P2	March 2022	Right Angle Design & Drafting
P3	March 2022	Right Angle Design & Drafting
P4	March 2022	Right Angle Design & Drafting
P5	March 2022	Right Angle Design & Drafting

Reports / Documentation – All recommendations and requirements contained within:		
Report No. / Page No. / Section No.	Dated	Prepared By

Geotechnical Assessment	11 May 2022	Ascent Geo
Arborist Impact Assessment Report	26 May 2022	Urban Arbor

b) Any plans and / or documentation submitted to satisfy the Conditions of this consent.

c) The development is to be undertaken generally in accordance with the following:

<b>Waste Management Plan</b>		
<b>Drawing No/Title.</b>	<b>Dated</b>	<b>Prepared By</b>
Waste Management Plan	7 May 2022	Paul Norman

In the event of any inconsistency between conditions of this consent and the drawings/documents referred to above, the conditions of this consent will prevail.

Reason: To ensure the work is carried out in accordance with the determination of Council and approved plans.

## 2. **Compliance with Other Department, Authority or Service Requirements**

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

<b>Other Department, Authority or Service</b>	<b>EDMS Reference</b>	<b>Dated</b>
Ausgrid	Response Ausgrid Referral	1 July 2022

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website [www.northernbeaches.nsw.gov.au](http://www.northernbeaches.nsw.gov.au))

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

## 3. **Prescribed Conditions**

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
  - (i) showing the name, address and telephone number of the Principal Certifying Authority for the work, and
  - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
  - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.
- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifying Authority for the development to which the

work relates (not being the Council) has given the Council written notice of the following information:

- (i) in the case of work for which a principal contractor is required to be appointed:
  - A. the name and licence number of the principal contractor, and
  - B. the name of the insurer by which the work is insured under Part 6 of that Act,
- (ii) in the case of work to be done by an owner-builder:
  - A. the name of the owner-builder, and
  - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifying Authority for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
  - (i) protect and support the adjoining premises from possible damage from the excavation, and
  - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
  - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
  - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

#### 4. **General Requirements**

- (a) Unless authorised by Council:  
Building construction and delivery of material hours are restricted to:
  - 7.00 am to 5.00 pm inclusive Monday to Friday,
  - 8.00 am to 1.00 pm inclusive on Saturday,
  - No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether

the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (c) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of a final Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (d) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (e) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (f) Prior to the release of the Construction Certificate, payment of the Long Service Levy is required. This payment can be made at Council or to the Long Services Payments Corporation. Payment is not required where the value of the works is less than \$25,000. The Long Service Levy is calculated on 0.35% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
- (g) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (h) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (i) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (j) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.) or on the land to be developed shall be removed or damaged during construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (k) Prior to the commencement of any development onsite for:
  - i) Building/s that are to be erected
  - ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
  - iii) Building/s that are to be demolished
  - iv) For any work/s that is to be carried out
  - v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

- (l) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall

notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.

- (m) The works must comply with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice.
- (n) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.
  - (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;
 

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

    - (i) Swimming Pools Act 1992
    - (ii) Swimming Pools Amendment Act 2009
    - (iii) Swimming Pools Regulation 2018
    - (iv) Australian Standard AS1926 Swimming Pool Safety
    - (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
    - (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
  - (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
  - (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
  - (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

## FEES / CHARGES / CONTRIBUTIONS

### 5. Security Bond

A bond (determined from cost of works) of \$2,000 and an inspection fee in accordance with Council's Fees and Charges paid as security are required to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, and details demonstrating payment are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at [www.northernbeaches.nsw.gov.au](http://www.northernbeaches.nsw.gov.au)).

Reason: To ensure adequate protection of Council's infrastructure.

## **CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE**

### **6. Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.

### **7. Surrender of Consent**

The applicant shall surrender to Council Development Consent No: N0331/12 in accordance with the requirements of the Environmental Planning and Assessment Act 1979.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To prevent inconsistencies between consent applying the site

### **8. Sydney Water "Tap In"**

The approved plans must be submitted to the Sydney Water Tap in service, prior to works commencing, to determine whether the development will affect any Sydney Water assets and/or easements. The appropriately stamped plans must then be submitted to the Certifying Authority demonstrating the works are in compliance with Sydney Water requirements.

Please refer to the website [www.sydneywater.com.au](http://www.sydneywater.com.au) for:

- "Tap in" details - see <http://www.sydneywater.com.au/tapin>
- Guidelines for Building Over/Adjacent to Sydney Water Assets.

Or telephone 13 000 TAP IN (1300 082 746).

Reason: To ensure compliance with the statutory requirements of Sydney Water.

## **CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK**

### **9. Tree and Vegetation Protection**

a) Existing trees and vegetation shall be retained and protected, including:

- i) all trees and vegetation within the site not approved for removal,
- ii) all trees and vegetation located on adjoining properties,
- iii) all road reserve trees and vegetation.

b) Tree protection shall be undertaken as follows:

- i) tree protection shall be in accordance with Australian Standard 4970-2009 Protection of Trees on Development Sites, including the provision of temporary fencing to protect existing trees



within 5 metres of development,

- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist with minimum AQF Level 5 in arboriculture,
- iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
- vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist to the Certifying Authority,
- viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of Australian Standard 4970-2009 Protection of Trees on Development Sites,
- ix) the activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
- x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with Australian Standard 4373-2007 Pruning of Amenity Trees,
- xi) the tree protection measures specified in this clause must: i) be in place before work commences on the site, and ii) be maintained in good condition during the construction period, and iii) remain in place for the duration of the construction works.

c) Tree protection shall specifically be undertaken in accordance with the recommendations in the Arboricultural Impact Assessment, as listed in the following sections:

- i) section 10 Recommendations
- ii) section 11 Tree Protection Requirements
- iii) section 12 Construction Hold Points for Tree Protection

The Certifying Authority must ensure that:

- d) The arboricultural works listed in c) are undertaken and certified by an Arborist as compliant to the recommendations of the Arboricultural Impact Assessment.
- e) The activities listed in section 4.2 of Australian Standard 4970-2009 Protection of Trees on Development Sites, do not occur within the tree protection zone of any tree, and any temporary access to, or location of scaffolding within the tree protection zone of a protected tree, or any other tree to be retained on the site during the construction, is undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of that standard.

Note: All street trees within the road verge and trees within private property are protected under Northern Beaches Council development control plans, except where Council's written consent for removal has been obtained. The felling, lopping, topping, ringbarking, or removal of any tree (s) is prohibited.

Reason: Tree and vegetation protection.

## 10. Survey Certificate

A survey certificate prepared by a Registered Surveyor is to be provided demonstrating all perimeter walls columns and or other structural elements, floor levels and the finished roof/ridge height are in accordance with the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority.

Reason: To demonstrate the proposal complies with the approved plans.

## **CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE**

### **11. Required Screen Planting**

Screen shrub planting along the southern boundary to the extent of the proposed swimming pool and paved surrounds, as either retained existing planting or new screen planting, and in accordance with the following:

- i) selected new planting is to comprise of native species capable of attaining a height of 3.0m metres at maturity,
- ii) plants are to be installed at minimum 1 metre intervals and be of a minimum container size of 200mm at planting in a garden bed prepared with a suitable free draining soil mix and minimum 50mm depth of mulch.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to the issue of any Occupation Certificate.

Reason: To maintain environmental amenity.

### **12. New Vegetation Planting**

Any landscaping is to incorporate a minimum 60% locally native vegetation species as a proportion of the total number of plants. Locally native species are to be consistent with the Pittwater Ward species list within the Native Plant Species Guide available on Council's website.

Details demonstrating compliance are to be provided to the Principal Certifying Authority prior to issue of the Occupation Certificate.

Reason: To ensure compliance with the requirement to retain and protect native planting on the site.

### **13. No Weeds Imported On To The Site**

No Priority or environmental weeds (as specified in the Northern Beaches Local Weed Management Plan 2019 – 2023) are to be imported on to the site prior to or during construction works.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority prior to issue of any Occupation Certificate.

Reason: To reduce the risk of site works contributing to spread of Priority and environmental weeds.

### **14. Swimming Pool Requirements**

The Swimming Pool shall not be filled with water nor be permitted to retain water until:

- (a) All required safety fencing has been erected in accordance with and all other requirements

have been fulfilled with regard to the relevant legislative requirements and relevant Australian Standards (including but not limited) to:

- (i) Swimming Pools Act 1992;
- (ii) Swimming Pools Amendment Act 2009;
- (iii) Swimming Pools Regulation 2008
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools

(b) A certificate of compliance prepared by the manufacturer of the pool safety fencing, shall be submitted to the Principal Certifying Authority, certifying compliance with Australian Standard 1926.

(c) Filter backwash waters shall be discharged to the Sydney Water sewer mains in accordance with Sydney Water's requirements. Where Sydney Water mains are not available in rural areas, the backwash waters shall be managed onsite in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system. Appropriate instructions of artificial resuscitation methods.

(d) A warning sign stating '**YOUNG CHILDREN SHOULD BE SUPERVISED WHEN USING THIS POOL**' has been installed.

(e) Signage showing resuscitation methods and emergency contact

(f) All signage shall be located in a prominent position within the pool area.

(g) Swimming pools and spas must be registered with the *Division of Local Government*.

Details demonstrating compliance are to be submitted to the Certifying Authority prior to the issue of an Interim / Final Occupation Certificate.

Reason: To protect human life.

#### **ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES**

15. **Swimming Pool/Spa Motor Noise**

The swimming pool / spa motor shall not produce noise levels that exceed 5dB(A) above the background noise when measured from the nearest property boundary.

Reason: To ensure that the development does not impact on the acoustic privacy of surrounding residential properties.

In signing this report, I declare that I do not have a Conflict of Interest.

**Signed**



**Phil Lane, Principal Planner**

The application is determined on 01/08/2022, under the delegated authority of:



**Adam Richardson, Manager Development Assessments**