

SUITE 2.02, 1 CHANDOS STREET
ST LEONARDS NSW 2065
PH: (02) 9490 9600 FAX: (02) 9438 1224
EMAIL: info@richmondross.com.au

STORMWATER MANAGEMENT PLAN FOR PROPOSED REDEVELOPMENT AT 40 MYOORA ROAD, TERREY HILLS NSW 2084

Job Ref: 230300

Date: May 2025

Revision: D

Prepared By:



Andrew Kabalan

BEng (Civil) (Hons), GradIEAust

Checked By:



Harshad Varsani

BEng (Civil) (Hons), MIEAust

PRINCIPALS: MAGDA WEGNER BSc(Eng) MSc(Eng)
NICK MITCHELL, BSc, BE (Hons), FIEAust, CPEng
STUART PIPER, B.Arch (Hons), Grad Dip Prop (Hons), MAIPM, CPPM, MAIA, ARB NSW



CONTENTS

1.0	INTRODUCTION.....	2
2.0	SITE LOCATION AND DESCRIPTION	2
3.0	DEVELOPMENT PROPOSAL	3
4.0	EXISTING STORMWATER NETWORK.....	3
5.0	PROPOSED STORMWATER NETWORK.....	3
6.0	STORMWATER QUANTITY MANAGEMENT	4
6.1.	On-site Stormwater Detention (OSD)	4
7.0	STORMWATER QUALITY MANAGEMENT	4
7.1.	Gross Pollutant Traps (GPT).....	5
7.2.	Filter Cartridges	5
7.3.	Permeable Paving.....	5
7.4.	Water Quality Outcome – MUSIC Model	5
8.0	OVERLAND FLOW PATHS	6
9.0	CONCLUSION	7
	APPENDIX A – MUSIC MODEL.....	8
	APPENDIX B – DRAINS MODEL RESULTS (1%, 2%, 5% AND 20% AEP)	9
B.1	- 1% AEP	9
B.2	- 2% AEP	10
B.3	- 5% AEP	11
B.4	- 20% AEP	12
	APPENDIX C – TRUEGRID GRAVEL FILL INSTALLATION PROFILE.....	13

1.0 INTRODUCTION

Richmond and Ross Pty Ltd, Consulting Engineers, have been engaged to prepare a Stormwater Management Plan for the proposed development at 40 Myoora Road, Terrey Hills, NSW 2084. No responsibility to third parties under the law of contract, tort or otherwise for any loss or damage is accepted.

The purpose of this assessment is to provide advice with respect to stormwater management for the proposed development. The results of this study are limited to this scope.

This assessment has been prepared by reviewing published topographic maps, physical land survey, hydraulic and hydrological calculations, available Ariel photography of the site and in accordance with Northern Beaches Council Policies below:

- Water Management for Development Policy 2021
- WSUD & MUSIC Modelling Guidelines 2016

2.0 SITE LOCATION AND DESCRIPTION

The subject site is located at 40 Myoora Road, Terrey Hills, NSW 2084 lot 180 of DP752017. The total area of the lot is approximately 1.6Ha (15,802m²). The current site generally slopes to the Northwest towards Myoora Road. There are existing kerb inlet pits located along Myoora Road as part of Council's stormwater network.



Figure 1. Site Boundary Satellite View (Extract from Nearmap)

3.0 DEVELOPMENT PROPOSAL

The plan is to develop the current lot into a single storey hospitality development with basement car park and vehicular access from Myoora Road, three separate restaurant areas with total GFA of approx. 3,000m² and ancillary office to support operation of restaurants, as well as outdoor landscaping and children's play area. The total impervious area (buildings, pathways, roofs, and carparks) is approximately 7,100m² accounting for 45% of the total site area. The remaining area will be pervious landscaping.




Figure 2. Proposed Development Plan (Extract from Architectural Plan)

4.0 EXISTING STORMWATER NETWORK

The site currently drains via surface overland flow towards Myoora Road. There are two council owned kerb inlet pits located in front of the site along Myoora Road, one of which is connected to an existing Council owned stormwater channel which Council has requested the proposed stormwater system to connect to.

5.0 PROPOSED STORMWATER NETWORK

It is proposed to construct a new stormwater network to convey stormwater from the site on the following principles:

- A new network of pits and pipes is proposed to convey the runoff from the site to a stormwater treatment train prior to exiting the site towards the existing kerb inlet pit that connects to an existing underground Council owned Stormwater channel. The underground network has been sized for 1% AEP storm event.
- The On-Site Detention (OSD) Tank has been sized and designed to meet Council's requirements for storage and permissible site discharge for the proposed development based on pre- vs post-development flows. See stormwater quantity management in section 6 for more details.
- The proposed roof area is approx. 2,200m². All runoff from the roof will be directed to the stormwater network for treatment and storage.
- A system consisting of Ocean Guard pit inserts and StormFilter Cartridges is proposed to treat the stormwater runoff prior to discharge from the site. Analysis from MUSIC indicates the treatment targets are achieved by the proposed treatment train. See stormwater quality management in section 7 for more details.

6.0 STORMWATER QUANTITY MANAGEMENT

6.1 On-site Stormwater Detention (OSD)

The proposed development site is subject to On-Site Detention (OSD) requirements as per the Northern Beaches Council – Water Management for Development Policy. The subject site is located in region 2 and therefore OSD requirements were taken from section 9.3.2 - Onsite Stormwater disposal Requirements Region 2 – Central Catchments of the policy. Given that the site is not a single dwelling and is larger than 1,200 m² in area, a full computation Method using DRAINS was created in line with section 9.3.2.5 of the policy. Pre- and post-development flows were calculated using the Horton/ILSAX method in DRAINS as per Section 9.9.1 of the policy for the 20%, 5% and 1% AEP storm events.

Based on analysis in DRAINS, the required OSD volume was calculated to be 185m³. A combination of two stage orifices and weirs is used to control the peak discharge rate from the OSD tank. It should be noted that flows (9.9 L/s (0.9 L/s/cartridge)) from the StormFilter treatment devices bypass the orifice and weir. The discharge from the orifice and weir has been adjusted to ensure the combined discharge is within acceptable rates.

As per Council requirements, the total pipe flow from the site to Council drainage must not exceed the maximum 20% AEP pre-development runoff. However Council has requested that all the proposed stormwater system be connected to an existing Council owned Stormwater channel with no surcharge and therefore the stormwater system has been designed to capture all flows via piped connection up to the 1% AEP storm event. Council also required the total piped and overland discharge to be less than the 1% AEP pre-development runoff. The total discharge is 727 L/s which is less than the 1% AEP pre-development runoff of 898 L/s (Full results can be seen in Table 1). The flows for the 1% AEP storm event from DRAINS can be seen below in figure 4, see Appendix B for 2%, 5% and 20% AEP flows.




Figure 4. 1% AEP Flows through Detention Tank (Extract from DRAINS)

Table 1. Pre- and post-development flows (Calculated in DRAINS)

Storm Event (AEP)	Total Flow (L/s)		Reduction (%)
	Pre-development	Post-development	
1%	898	897.9	0.01
2%	757	684.9	9.5
5%	640	359.9	5.6
20%	355	329.9	9.3

7.0 STORMWATER QUALITY MANAGEMENT

A stormwater treatment train is proposed based on Northern Beaches Council's Water Management for Development Policy 2021 – section 4: Protecting the Environment and WSUD & MUSIC Modelling Guidelines 2016 for the development within the site boundary. Based on Table 5 – General Stormwater Quality requirements, the following reduction percentage targets were used in the MUSIC Model. Total Suspended Solids (TSS): 85%, Total Phosphorus (TP): 60%, Total Nitrogen (TN): 45% and Gross Pollutants (GP): 90%. The stormwater treatment train comprises of the following components.

7.1. Gross Pollutant Traps (GPT)

Ocean Guard pit inserts are proposed in all inlet pits that directly collect stormwater. The stormwater is filtered via direct screening through the filtration bag liner ensuring that any debris larger than the openings in the filtration bag are captured and retained. During large storm events the water elevation in the filtration bag can rise and peak flows are internally bypassed through slots created in the flow diverter which has no moving parts that may prematurely fail. At the end of the storm event debris and stormwater rest at the base of the filtration bag where the stored material will start to dry until the next storm event.

A system is proposed using 14 x OceanGuard GPTs (One in each inlet pit).

7.2. Filter Cartridges

The StormFilter, used on site, is a stormwater treatment system using rechargeable, self-cleaning media-filled cartridges to absorb and retain required level of pollutants from stormwater runoff including total suspended solids, hydrocarbons, nutrients, soluble heavy metals, and other common pollutants. The filter cartridges clean stormwater through a passive filtration system and removes pollutants.

A system is proposed using 5 x 690mm-PSorb StormFilter Cartridges, installed within a 9.5m² StormFilter Treatment Chamber within the OSD Tank.

7.3. Permeable Paving

As per Council request, permeable paving has been proposed for a portion of the carparking area in place of the previously proposed concrete hardstand to meet WSUD requirements. As described by the manufacturer, infiltration of storm water runoff through the pavement surface will provide a degree of suspended solids removal followed by additional removal of colloidal solids and soluble pollutants in the aggregate subbase and sub soils. Sorption of metals to colloidal solids and within the pavement void matrix is another removal function. Soluble organic pollutants adsorbed within the pavement void matrix and the open graded aggregate subbase will be exposed to biodegradation over time.

TRUEGRID permeable pavement has been proposed for a rough area of 2,500m² of the car parking area. See Appendix C for typical profile and sections and architectural drawings for full extent.

7.4. Water Quality Outcome – MUSIC Model

A MUSIC model was prepared for the proposed treatment train. The model was prepared using pluviograph data provided by the software manufacturer. See figure 5 below for treatment train as modelled in MUSIC and shown in Appendix A for more details. The meteorological data utilised in the modelling was extracted from the Pluviograph Rainfall Data toolkit from eWater at the closest rainfall station detailed as follows:

Station No: 066142

Station Name: Duffy's Forest (Namba Rd)




Figure 5. Treatment train and pollution removal as modelled in MUSIC

	Sources	Residual Load	% Reduction
Flow (ML/yr)	7.54	7.54	0
Total Suspended Solids (kg/yr)	1650	234	85.8
Total Phosphorus (kg/yr)	2.98	0.94	68.4
Total Nitrogen (kg/yr)	16.1	8.79	45.5
Gross Pollutants (kg/yr)	155	4.97	96.8

Figure 6. Treatment train effectiveness as modelled in MUSIC

The overall pollutant removal for the site has been summarised in Table 2 below. An improvement in discharged water quality can be expected by installing the proposed treatment train.

Table 2 Treatment levels for the site

	SOURCES	RESIDUAL LOAD	% REDUCTION	
			Target	Actual
Total Suspended Solids [TSS] (kg/yr)	1650	234	85.0	85.8
Total Phosphorus [TP] (kg/yr)	2.98	0.94	65.0	68.5
Total Nitrogen [TN] (kg/yr)	16.1	8.79	45.0	45.5
Gross Pollutants [GP] (kg/yr)	155	4.97	90.0	96.4

8.0 OVERLAND FLOW PATHS


If storms higher than the design storm occur, the site is graded to allow an overland flow path to form which protects the buildings. Overland flows will exit the site via Myoora Road towards the existing council stormwater pit which connects to the existing Council channel. Overflow from the proposed OSD will exit the tank via the lowest grated lid of the tank and overtop the kerb towards the same council stormwater pit in Myoora Road

9.0 CONCLUSION

A system has been proposed for the control of stormwater on the subject site, which considers the requirements for water pollution control and water sensitive urban design.

The proposed system will result in adequate environment protection and reduction in water pollutant loads based on modelling. We believe the system satisfies the requirements of the Northern Beaches Council.


APPENDIX A – MUSIC MODEL



APPENDIX B – DRAINS MODEL RESULTS (1%, 2%, 5% AND 20% AEP)


B.1 - 1% AEP

Results for median storm in critical 1% AEP ensembles
using Lite hydraulic model.




B.2 - 2% AEP

Results for median storm in critical 2% AEP ensembles
using Lite hydraulic model.




B.3 - 5% AEP

Results for median storm in critical 5% AEP ensembles
using Lite hydraulic model.



B.4 - 20% AEP

Results for median storm in critical 20% AEP ensembles
using Lite hydraulic model.




APPENDIX C – TRUEGRID GRAVEL FILL INSTALLATION PROFILE


NOTES:

1. SUB-BASE DEPTH AND PREPARATION IS DEPENDENT ON SITE CONDITIONS PLUS LOADING REQUIREMENTS.
2. TRUEGRID PRO PLUS PRODUCTS DESIGNED FOR LOAD CAPACITIES OF 8,000 PSI PER SQ. M TRUEGRID PRODUCTS STRENGTHEN WITH FILL MATERIAL.
3. TRUEGRID PRO PLUS PRODUCTS ARE SUFFICIENTLY RATED FOR H-20 /HS-20 LOADING AND GREATER.
4. GEODRID MESH OR GEOFABRIC MAY BE REQUIRED BETWEEN SUB-GRADE & SUB-BASE FOR CERTAIN SOILS AND SITE SPECIFIC REQUIREMENTS.
5. INCREASE SUB-BASE DEPTH FOR INCREASED STORM WATER DETENTION.
6. NO STAKING NECESSARY WITH TRUEGRID PRO PLUS WHEN SLOPE IS BELOW 10 DEGREES. ASSESS PROJECT, AS NEEDED.
7. FINAL ENGINEERED CROSS SECTION AGGREGATES AND DEPTH SHOULD ALLOW FOR EXPECTED INFILTRATION RATES, STORAGE CAPACITIES, OUTLET FLOW RATES, AND OTHER SITE SPECIFIC CONDITIONS AND LOAD REQUIREMENTS.
8. THIS CROSS SECTION IS FOR INFORMATION ONLY.

TRUEGRID FILL MATERIAL 46MM DEPTH	
INDUSTRIAL YARDS/ HARDSTANDS	14-19mm diameter clean, washed angular rock with a 10 mm surcharge of aggregate to assist with large vehicle turning.
SLOPED DRIVEWAYS	14-19 mm diameter clean, washed angular rock.
PUBLIC CAR PARKS	10-14 mm diameter clean, washed angular rock with fill rock, level to the top of cells.
DISABILITY ACCESSIBLE PATHWAYS	5-7mm diameter clean, washed angular rock with fill rock, level to the top of cells.



TRUEGRID BLOCK REFERENCE VIEW
PREASSEMBLED & DELIVERED IN 61CM X 61CM SHEET. RECONFIGURED AS NEEDED AND EXTRA TOOLING OR ACCESSORIES REQUIRED



GRAVEL FILL MEDIUM LOAD TRUEGRID PRO PLUS

APPLICATION:

PARKING LOT, RV PARKING,
PARKING PADS, DRIVEWAYS

A: 21/7 Activity Cres Molendinar, QLD 4214
P: 1 300 796 018
E: sales@truegridpaver.com.au
W: www.truegridpaver.com.au



1300 796 018
TRUEGRIDPAVER.com.au

CLIENT / PROJECT		APPROVAL INFORMATION		TRUEGRID DRIVE ON SURFACE	
UNLESS OTHERWISE SPECIFIED, DIMENSIONS ARE IN MM.		DRAWN BY: H. GOODMAN		DATE: 19/03/2024	
PROPRIETARY DESIGN RIGHTS NOTICED: THIS DESIGN WAS ORIGINATED BY AND IS THE EXCLUSIVE PROPERTY OF TRUEGRID. IT IS DISCLOSED IN CONFIDENCE WITH THE UNDERSTANDING THAT NO REPRODUCTION OR OTHER USE OF THE INFORMATION IS AUTHORIZED WITHOUT SPECIFIC AGREEMENT IN WRITING BY TRUEGRID.		CHECKED BY: H. GOODMAN		DATE: 19/03/2024	
DO NOT SCALE DRAWING		APPROVED BY: P. GOODMAN		DATE: 19/03/2024	
DRAWING NUMBER: TG-GRV-ML		SCALE: 1:5		SHEET: 1 OF 1	


REV	DESCRIPTION	DRAWN	CHECKED	APPROVED	DATE
00	UPDATED TRUEGRID STANDARDS	HG	HG	PG	19/03/2024

REVISION


NOTES:

- SUB-BASE DEPTH AND PREPARATION IS DEPENDENT ON SITE CONDITIONS PLUS LOADING REQUIREMENTS.
- TRUEGRID PRO PLUS PRODUCTS DESIGNED FOR LOAD CAPACITIES OF 8,000 PER SQ. M TRUEGRID PRODUCTS STRENGTHEN WITH FILL MATERIAL.
- TRUEGRID PRO PLUS PRODUCTS ARE SUFFICIENTLY RATED FOR H-20 /HS-20 LOADING AND GREATER.
- GEOGRID MESH OR GEOFABRIC MAY BE REQUIRED BETWEEN SUB-GRADE & SUB-BASE FOR CERTAIN SOILS AND SITE SPECIFIC REQUIREMENTS.
- INCREASE SUB-BASE DEPTH FOR INCREASED STORM WATER DETENTION.
- NO STAKING NECESSARY WITH TRUEGRID PRO PLUS WHEN SLOPE IS BELOW 10 DEGREES. ASSESS PROJECT, AS NEEDED.
- FINAL ENGINEERED CROSS SECTION AGGREGATES AND DEPTH SHOULD ALLOW FOR EXPECTED INFILTRATION RATES, STORAGE CAPACITIES, OUTLET FLOW RATES, AND OTHER SITE SPECIFIC CONDITIONS AND LOAD REQUIREMENTS.
- THIS CROSS SECTION IS FOR INFORMATION ONLY.

TRUEGRID FILL MATERIAL 46MM DEPTH	
INDUSTRIAL YARDS/ HARDSTANDS	14-19mm diameter clean, washed angular rock with a 10 mm surcharge of aggregate to assist with large vehicle turning.
SLOPED DRIVEWAYS	14-19 mm diameter clean, washed angular rock.
PUBLIC CAR PARKS	10-14 mm diameter clean, washed angular rock with fill rock, level to the top of cells.
DISABILITY ACCESSIBLE PATHWAYS	5-7mm diameter clean, washed angular rock with fill rock, level to the top of cells.



TRUEGRID BLOCK REFERENCE VIEW
PREASSEMBLED & DELIVERED IN 61CM X 61CM SHEET. RECONFIGURED AS NEEDED AND EXTRA TOOLING OR ACCESSORIES REQUIRED



POINT OUTFLOW OR
OUTFLOW TO CITY SYSTEM

A: 21/7 Activity Cres Molendinar, QLD 4214
P: 1 300 796 018
E: sales@truegridpaver.com.au
W: www.truegridpaver.com.au



1300 796 018
TRUEGRIDPAVER.COM.AU

CLIENT / PROJECT		APPROVAL INFORMATION		TRUEGRID DRIVE ON SURFACE	
UNLESS OTHERWISE SPECIFIED, DIMENSIONS ARE IN MM		DRAWN BY: H. GEDIMAN		DATE: 19/03/2024	
PROPRIETARY DESIGN RIGHTS NOTICED: THIS DESIGN WAS ORIGINATED BY AND IS THE EXCLUSIVE PROPERTY OF TRUEGRID. IT IS DISCLOSED IN CONFIDENCE WITH THE UNDERSTANDING THAT NO REPRODUCTION OR OTHER USE OF THE INFORMATION IS AUTHORIZED WITHOUT SPECIFIC AGREEMENT IN WRITING BY TRUEGRID.		CHECKED BY: H. GEDIMAN		DATE: 19/03/2024	
APPROVED BY: P. GEDIMAN		DATE: 19/03/2024		TRUEGRID GRAVEL FILL INSTALLATION PERFORATED PIPE	
DO NOT SCALE DRAWING		SIZE: D		DRAWING NUMBER: TG-GRV-PP	
		WEIGHT:		SCALE: IS	
				SHEET: 1 OF 1	

05	MODIFIED PIPE & TRENCH	HG	HG	PG	19/03/2024
REV		DRAWN	CHECKED	APPROVED	DATE

REVISION