

18 June 2024



Royal Motor Yacht Club Broken Bay Nsw
46 Prince Alfred Parade
NEWPORT NSW 2106

Dear Sir/Madam

Application Number: DA2023/0951
Address: Lot 5 DP 4689 , 46 Prince Alfred Parade, NEWPORT NSW 2106
Lot 6 DP 110670 , 46 Prince Alfred Parade, NEWPORT NSW 2106
Lot 262 DP 752046 , 46 Prince Alfred Parade, NEWPORT NSW 2106
Lot 329 DP 824292 , 46 Prince Alfred Parade, NEWPORT NSW 2106
Proposed Development: Alterations and additions to the Royal Motor Club Broken Bay

Please find attached the Notice of Determination for the above mentioned Application.

You should thoroughly read the Notice of Determination and be aware of any conditions imposed that affect the development and guide the next steps in the process before you can commence works and/or the use.

A copy of the Assessment Report associated with this application is available to view in the Planning and Development > Application Search section of Council's website at www.northernbeaches.nsw.gov.au

If you have any questions regarding the decision or the conditions, please contact Council to speak to the assessment officer or the undersigned on 1300 434 434 or via email quoting the Application number, property address and the description of works to council@northernbeaches.nsw.gov.au

Regards,



Steven Findlay
Manager Development Assessments

NOTICE OF DETERMINATION OF A DEVELOPMENT APPLICATION

Application Number:	DA2023/0951 PAN-351508
Applicant:	Royal Motor Yacht Club Broken Bay Nsw 46 Prince Alfred Parade NEWPORT NSW 2106
Property:	Lot 5 DP 4689 46 Prince Alfred Parade NEWPORT NSW 2106 Lot 6 DP 110670 46 Prince Alfred Parade NEWPORT NSW 2106 Lot 262 DP 752046 46 Prince Alfred Parade NEWPORT NSW 2106 Lot 329 DP 824292 46 Prince Alfred Parade NEWPORT NSW 2106
Description of Development:	Alterations and additions to the Royal Motor Club Broken Bay
Determination:	Approved Consent Authority: Northern Beaches Local Planning Panel
Date of Determination:	13/06/2024
Date from which the consent operates:	18/06/2024
Date on which the consent lapses:	18/06/2029

Under section 4.18(1) of the EP&A Act, notice is given that the above development application has been determined by the granting of consent using the power in section 4.16(1)(a) of the EP&A Act, subject to the conditions specified in this notice.

Reasons for approval

The development proposal meets the Objects of the Environmental Planning and Assessment Act 1979, contained in Section 1.3, having considered the relevant provisions under s.4.15 of the aforementioned Act. Consequently, the development is considered to be in the public interest, subject to conditions.

Community views

The application was notified in accordance with Council's Community Participation Plan and the Environmental Planning and Assessment Regulation 2021. Any submissions received representing community views were considered as part of the assessment of the application. Conditions of consent included within this Notice of Determination have been applied to ensure that the development satisfies the Objects of the Environmental Planning and Assessment Act and will not result in unacceptable environmental impacts.

Request a review of the determination

If you are dissatisfied with this determination, you may request a review of the determination:

- You do not have the right to request a review of the determination under section 8.3 of the EP&A Act if you are excluded from those developments listed under Section 8.2(2) of the EP&A Act.
- You may request a review of the consent authority's decision under section 8.3(1) of the EP&A Act. The application must be made to the consent authority within 6 months from the date that you received the original determination notice provided that an appeal under section 8.7 of the EP&A Act has not been disposed of by the Court.

Rights to appeal

You have a right under section 8.7 of the EP&A Act to appeal to the Court within 6 months after the date on which the determination appealed against is notified or registered on the NSW planning portal.

Objector's right of appeal against the determination

An objector who is dissatisfied with the consent authority's determination to grant consent, in relation to Designated Development only has the right to appeal to the Court against the determination under section 8.8 of the EP&A Act within 28 days after the date that the objector was notified of the determination appealed against.

Dictionary

The Dictionary at the end of this consent defines words and expressions for the purposes of this determination.

Signed On behalf of the Consent Authority



Name Steven Findlay, Manager Development Assessments

Date 13/06/2024

Terms and Reasons for Conditions

Under section 88(1)(c) of the EP&A Regulation, the consent authority must provide the terms of all conditions and reasons for imposing the conditions other than the conditions prescribed under section 4.17(11) of the EP&A Act. The terms of the conditions and reasons are set out below.

GENERAL CONDITIONS

1. Approved Plans and Supporting Documentation

Development must be carried out in accordance with the following approved plans (stamped by Council) and supporting documentation, except where the conditions of this consent expressly require otherwise.

Approved Plans				
Plan Number	Revision Number	Plan Title	Drawn By	Date of Plan
DA003	G	Demolition - Ground Floor Plan	MCHP Architects	11 March 2024
DA004	C	Demolition - First Floor Plan	MCHP Architects	22 February 2023
DA005	C	Demolition - Second Floor Plan	MCHP Architects	22 February 2023
DA006	H	Proposed Overall Site - Roof Plan	MCHP Architects	11 March 2024
DA007	I	Proposed Partial Site - Roof Plan	MCHP Architects	11 March 2024
DA008	J	Proposed Partial Site - Ground Floor Plan	MCHP Architects	11 March 2024
DA009	J	Proposed - Ground Floor Plan	MCHP Architects	11 March 2024
DA010	H	Proposed - First Floor Plan	MCHP Architects	8 March 2024
DA011	F	Proposed - Second Floor Plan	MCHP Architects	8 March 2024
DA012	B	Proposed - Second Floor Plan 2	MCHP Architects	22 February 2023
DA017	E	Proposed - North Elevation	MCHP Architects	2 May 2024
DA018	E	Proposed - South Elevation	MCHP Architects	5 March 2024
DA019	D	Proposed - East Elevation	MCHP Architects	5 March 2024
DA020	D	Proposed - West Elevation	MCHP Architects	2 May 2024
DA021	E	Proposed - Section 01	MCHP Architects	8 March 2024
DA022	E	Proposed - Section 02	MCHP Architects	8 March 2024
DA023	E	Proposed - Section 03	MCHP Architects	8 March 2024

DA029	C	Finishes Schedule 1 - Materials and Colours	MCHP Architects	8 March 2024
DA030	C	Finishes Schedule 2	MCHP Architects	8 March 2024
DA031	C	Finishes Schedule 3	MCHP Architects	8 March 2024
DA-101	D	Landscape Plan	Landart	13 March 2024

Approved Reports and Documentation			
Document Title	Version Number	Prepared By	Date of Document
Plan of Management - Operational	-	Planning Ingenuity	22 May 2024
Acoustic Report	1.1	Acoustic Directions	1 March 2023
Geotechnical Investigation Report	1	Douglas Partners	14 July 2023
Acid Sulfate Soil Management Plan	-	JK Environments	16 March 2023
Unexpected Finds Protocol	-	JK Environments	17 March 2023
Preliminary Site Investigation and Acid Sulfate Soil Assessment	Final	JK Environments	25 January 2023
BCA and DDA Compliance Statement	-	Blackett Maguire + Goldsmith	10 March 2023
Estuarine Risk Management Report	-	Horton Coastal Engineering	26 April 2023
Arboricultural Impact Appraisal and Method Statement	-	Naturally Trees	9 November 2023
Addendum to Arborist Report	-	Naturally Trees	18 March 2024
Waste Management Plan - Royal Motor Yacht Club	-	-	-
Operational Waste Management Plan	B	Elephants Foot Consulting	17 February 2023
Crime Risk Assessment Report	M220260	Planning Ingenuity	15 May 2024

In the event of any inconsistency between the approved plans, reports and documentation, the approved plans prevail.

In the event of any inconsistency with the approved plans and a condition of this consent, the condition prevails.

Reason: To ensure all parties are aware of the approved plans and supporting documentation

that applies to the development.

2. Compliance with Other Department, Authority or Service Requirements

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department, Authority or Service	EDMS Reference	Dated
Ausgrid	Ausgrid Referral Response - Underground Cables	29 August 2023
Ausgrid	Ausgrid Referral Response - Overhead Cables	29 August 2023
NSW Police	Referral - NSW Police - 46 Prince Alfred Parade Newport	5 December 2023

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website www.northernbeaches.nsw.gov.au)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

3. Prescribed Conditions

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (i) showing the name, address and telephone number of the Principal Certifier for the work, and
 - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been completed.
- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the following information:
 - (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
 - (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and

- B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
- (i) protect and support the adjoining premises from possible damage from the excavation, and
 - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
 - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

4. **General Requirements**

- (a) Unless authorised by Council:
Building construction and delivery of material hours are restricted to:
- 7.00 am to 5.00 pm inclusive Monday to Friday,
 - 8.00 am to 1.00 pm inclusive on Saturday,
 - No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (c) At all times after the submission the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of an Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (d) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be

maintained in a safe and clean state until such time as new construction works commence.

- (e) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (f) Prior to the release of the Construction Certificate, payment of the following is required:
 - i) Long Service Levy - Payment should be made to Service NSW (online or in person) or alternatively to Northern Beaches Council in person at a Customer Service Centre. Payment is not required where the value of the works is less than \$250,000. The Long Service Levy is calculated on 0.25% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
 - ii) Section 7.11 or Section 7.12 Contributions Plan – Payment must be made to Northern Beaches Council. Where the subject land to which the development is proposed is subject to either a Section 7.11 or 7.12 Contributions Plan, any contribution to which the development is liable under the respective plan that applies is to be paid to Council. The outstanding contribution will be indexed at time of payment in accordance with the relevant Contributions Plan.
 - iii) Housing and Productivity Contribution - Payment must be made on the NSW Planning Portal for development to which this contribution applies. The amount payable is subject to indexation at the time of payment.
- (g) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (h) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (i) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (j) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.), on the land to be developed, or within adjoining properties, shall be removed or damaged during excavation or construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.
- (k) Prior to the commencement of any development onsite for:
 - i) Building/s that are to be erected
 - ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
 - iii) Building/s that are to be demolished
 - iv) For any work/s that is to be carried out
 - v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

- (l) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.
- (m) The works must comply with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice.
- (n) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.
 - (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:
 - (i) Swimming Pools Act 1992
 - (ii) Swimming Pools Amendment Act 2009
 - (iii) Swimming Pools Regulation 2018
 - (iv) Australian Standard AS1926 Swimming Pool Safety
 - (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
 - (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.
 - (2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.
 - (3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.
 - (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

FEES / CHARGES / CONTRIBUTIONS

5. Policy Controls

Northern Beaches Section 7.12 Contributions Plan 2022

A monetary contribution of \$102,000.00 is payable to Northern Beaches Council for the provision of local infrastructure and services pursuant to section 7.12 of the Environmental Planning & Assessment Act 1979 and the Northern Beaches Section 7.12 Contributions Plan (as amended).

The monetary contribution is based on a development cost of \$10,200,000.00.

The total amount payable will be adjusted at the time the payment is made, in accordance with the provisions of the Northern Beaches Section 7.12 Contributions Plan (as amended).

Details demonstrating compliance, by way of written receipts issued by Council, are to be submitted to the Certifier prior to issue of any Construction Certificate or, if relevant, the Subdivision Certificate (whichever occurs first).

A copy of the Contributions Plan is available for inspection at 725 Pittwater Road, Dee Why or on Council's website at Northern Beaches Council - Development Contributions.

Reason: To provide for contributions in accordance with the Contribution Plan to fund the provision of new or augmented local infrastructure and services.

6. **Security Bond**

A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security are required to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, and details demonstrating payment are to be submitted to the Certifier prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is located on Council's website at www.northernbeaches.nsw.gov.au).

Reason: To ensure adequate protection of Council's infrastructure.

7. **Construction, Excavation and Associated Works Security Bond(s)**

The applicant is to lodge a bond with Council for the following:

Security Bond

As security against damage to Council's roads fronting the site caused by the transport and disposal of materials and equipment to and from the site a bond of \$25000

Details confirming payment of the bond(s) are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

BUILDING WORK – BEFORE ISSUE OF A CONSTRUCTION CERTIFICATE

8. **Footing Design Near Trees to be Retained**

a) footing structural layout plans for the works including the new retaining wall and service/egress pathway shall be developed in co-ordination with an Arborist with AQF minimum Level 5 qualifications in arboriculture, and a qualified Structural Engineer, following a non-destructive tree root investigation (if deemed necessary by the Arborist), complying with clause 3.3.4 of AS 4970-2009 Protection of trees on development sites, near existing tree(s) 2 and 4 to locate critical tree roots and recommend footing design and locations for the construction works.

b) the Arborist shall review, comment, recommend design revision as required and approve the footing layout, to ensure the locations of footings will be manageable in terms of tree protection measures.

c) the Arborist shall submit certification to the Certifier that the locations of the footings are accepted.

d) the agreed footing structural layout plans shall be submitted to the Certifier for approval prior to the issue of a Construction Certificate.

Reason: Tree protection.

9. **Stormwater Disposal**

The applicant is to demonstrate how stormwater from the new development within this consent is disposed of to an existing approved system or in accordance with Northern Beaches Council's Water Management for Development Policy. Stormwater shall be conveyed from the site to existing stormwater drainage system. Details by an appropriately qualified and practicing Civil or Hydraulic Engineer demonstrating that the existing approved stormwater system can accommodate the additional flows, or compliance with Council's policy are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for disposal of stormwater management arising from the development.

10. **Construction Environment Management Plan**

A Construction Environmental Management Plan (CEMP) must be prepared in accordance with the environmental risks and mitigation methods. The CEMP must identify and appropriately manage invasive species (e.g. *Caulerpa taxifolia*).

An induction plan for site personnel must be prepared and implemented that addresses the CEMP. Induction records must be maintained and available onsite at all times.

The CEMP and site induction plan must be submitted to the Principal Certifier for approval prior to the issue of the Construction Certificate.

Reason: To protect native vegetation, wildlife, habitats and receiving waterways.

11. **Erosion and Sediment Control Plan**

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and

Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points
- Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment.

12. **Detailed Design of Stormwater Treatment Measures - Major**

A certificate from a Civil Engineer, stating that the stormwater treatment measures have been designed in accordance with the stormwater plan from Martens rev A 09.02.23 and Council's Water Management for Development Policy.

The certificate shall be submitted to the Certifier prior to the release of the Construction Certificate.

Reason: Protection of the receiving environment.

13. **Construction Traffic Management Plan**

A Construction Traffic Management Plan (CTMP) and report shall be prepared by a Transport for NSW accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to issue of any Construction Certificate.

The CTMP must address following:

- The proposed phases of construction works on the site, and the expected duration of each construction phase
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken
- Make provision for all construction materials to be stored on site, at all times
- The proposed areas within the site to be used for the storage of construction materials and waste containers during the construction period
- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes
- Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian safety
- The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure

- The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site

The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – “Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

A copy of the approved CTMP must be kept on-site at all times while work is being carried out.

The development is to be undertaken in accordance with the Construction Traffic Management Plan approved by Northern Beaches Council Traffic Team.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems.

14. **Vehicle Access & Parking**

Details must be provided for Council's review of the signposting of the upper car park to support the proposed one-way directional pavement arrows. 'NO ENTRY' and 'ONE WAY' signs must be provided at selected locations within the carpark to guide motorists.

The amended plans do not show any shuttle bus parking. Hence, the architectural plans must be updated to show dedicated locations for shuttle bus parking sized to accommodate the shuttle buses in use by the club.

page 9 of the architectural plans note that modification of the pedestrian path adjacent to the accessible parking spaces will be undertaken. Additional details for this work must be provided to ensure compliance with relevant standards.

Plans for the above must be provided to Councils Traffic Engineer for review and once approved submitted to the Principal Certifier prior to the issue of a Construction Certificate

Reason: To ensure adequate provision is made for parking safely, for manoeuvring, pedestrian access and parking of vehicles.

15. **Amended Operational Plan of Management**

Prior to the issue of the Construction Certificate an amended Operational Plan of Management is to be approved by Council which includes:

- How the numbers of patrons will be managed to prevent the maximum approved capacity being exceeded, and contains:
 - a) Procedures for the management of the number of patrons for each of the spaces and the premises as a whole to ensure that the maximum capacity will not be exceeded.
 - b) A statement that no additional events will be held in any of the function rooms at the same time as any of the following club events:
 - Opening of the sailing season;
 - Timber Boat Show;
 - New Years Eve (PM functions), and
 - Christmas Day.
- A requirement that when the second floor function room is being utilised, the doors to the outside terrace are closed, to minimise noise egress.

- Details of the locations to be serviced by a shuttle bus as referenced in section 6.2 (f) Operational Plan of Management dated 22 May 2024 prepared by Planning Ingenuity.

Reason: To ensure that the premises operates consistent with the proposed development and does not adversely affect neighbourhood amenity.

16. **Geotechnical Report Recommendations have been Incorporated into Designs and Structural Plans**

The recommendations of the risk assessment required to manage the hazards as identified in the Geotechnical Report referenced in Condition 1 of this consent are to be incorporated into the construction plans.

Prior to issue of the Construction Certificate, Form 2 of the Geotechnical Risk Management Policy for Pittwater (Appendix 5 of P21 DCP) is to be completed and submitted to the Certifier.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of a Construction Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.

17. **Boundary Identification Survey**

A boundary identification survey, prepared by a Registered Surveyor, is to be prepared in respect of the subject site.

The plans submitted for the Construction Certificate are to accurately reflect the property boundaries as shown on the boundary identification survey, with setbacks between the property boundaries and the approved works consistent with those nominated on the Approved Plans of this consent.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of any Construction Certificate.

Reason: To ensure all approved works are constructed within the subject site and in a manner anticipated by the development consent.

18. **Building Code of Australia & Disability Discrimination Act Upgrade requirements and Fire Safety Upgrade**

The Building Code of Australia and Disability Discrimination Act works and measures to upgrade the building as detailed and recommended in the Building Code of Australia Disability Discrimination Act Report prepared by Blackett Maguire & Goldsmith dated 10/3/2023, are to be considered as part of the assessment of the Construction Certificate.

Details demonstrating compliance are to be provided to the Certifying Authority prior to the issue of the Construction Certificate.

Reason: To ensure adequate provision is made for Health, Amenity, access and Fire safety for building occupant health and safety.

19. **Mechanical Plant**

A suitably qualified acoustic consultant is to be engaged to assess and provide recommended acoustic treatments for all mechanical plant and equipment proposed for the rooftop prior to construction certificate. Details demonstrating compliance are to be submitted to the

Certifier prior to the issue of the Construction Certificate.

Reason: To protect the noise amenity of the area.

20. **Mechanical ventilation Plans**

Where Mechanical ventilation is required to be installed in the food premises ,prior to any Construction Certificate (CC) being issued, detailed plans must be submitted to and approved by the Principle certifier that demonstrate compliance with the following:

- Australian Standard (AS) 1668.2 “The use of ventilation and air-conditioning in buildings - Mechanical ventilation in buildings”; and
- Any external exhaust discharge must be above the roofline and discharged in a manner that is not likely to cause an amenity impact.

These plans are to be prepared by a suitably qualified person.

Reason: To ensure that the installed mechanical ventilation complies with the requirements of the Australian Standard 1668.2 and to prevent amenity impacts.

21. **Pre-Commencement Dilapidation Report**

The applicant must prepare and submit a dilapidation report providing an accurate record of the existing condition of adjoining public property and public infrastructure (including roads, gutter, footpaths, etc). A copy of the report must be provided to Council, any other owners of public infrastructure and the owners of adjoining and affected private properties.

The dilapidation report must be submitted to Council for written approval and the written approval is then to be submitted to the Certifier prior to the issue of the any Construction Certificate and the commencement of any works including demolition.

Reason: Protection of Council’s infrastructure during construction.

22. **Estuarine Hazard Design Requirements**

All development or activities must be designed and constructed such that they will not increase the level of risk from estuarine processes for any people, assets or infrastructure in surrounding properties; they will not adversely affect estuarine processes; they will not be adversely affected by estuarine processes.

Reason: To minimise risks associated with coastal hazards for development in an estuarine environment.

23. **Estuarine Planning Level Requirements**

An Estuarine Planning Level (EPL) of 2.32m AHD has been adopted by Council for the subject site and shall be applied to all development proposed below this level as follows:

1. All structural elements below 2.32m AHD shall be of flood compatible materials;
2. All electrical equipment, wiring, fuel lines or any other service pipes and connections must be located either above 2.32m AHD or waterproofed to this level; and
3. The storage of toxic or potentially polluting goods, chemicals or materials, which may be hazardous or pollute the waterway, is not permitted below 2.32m AHD.
4. All interior power supplies (including electrical fittings, outlets and switches) must be located at or above 2.32m AHD. All exterior power supplies (including electrical

fittings, outlets and switches) shall be located at or above 2.32m AHD to avoid the likelihood of contact with splashing waves and spray.

Reason: To ensure vulnerable components of the development are built at the appropriate level.

24. **Compliance with Estuarine Risk Management Report**

The development is to comply with all recommendations of the approved Estuarine Risk Management Report prepared by Horton Coastal Engineering Pty. Ltd. dated 26 April 2023 and these recommendations are to be incorporated into construction plans and specifications and maintained over the life of the development.

Reason: To minimise potential hazards associated with development in an estuarine habitat.

25. **Structural Engineering for Estuarine Risk**

Structural engineering design for the development shall be prepared, with input as necessary from a chartered professional engineer with coastal engineering as a core competency, to ensure that for its design life taken to be 60 years as justified and accepted by Council, the development is able to withstand the wave impact forces and loadings identified in the approved Estuarine Risk Management Report prepared by Horton Coastal Engineering Pty. Ltd. dated 26 April 2023.

The potential for component fatigue (wear and tear) should be recognised for the less severe, but more frequent, wave impact loadings.

Reason: To ensure structural engineering is prepared by an appropriately qualified professional

26. **Compliance with Standards**

The development is required to be carried out in accordance with all relevant Australian Standards.

Details demonstrating compliance with the relevant Australian Standard are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To ensure the development is constructed in accordance with appropriate standards.

27. **External Finishes to Roof**

The external finish to the roof shall have a Solar Absorptance (SA) greater than 0.46 in accordance with the requirements of the BASIX Certificate to minimise solar reflections to neighbouring properties. Any roof with a metallic steel or reflective finish is not permitted.

Green roofs and areas where solar panels (PV) are installed are excluded from conforming to the SA range.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the construction certificate.

Reason: To ensure that excessive glare or reflectivity nuisance does not occur as a result of the development.

28. **Glazing Reflectivity**

All proposed west-facing glazing shall have a low reflectivity index.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To minimise glare and reflectivity impacts.

29. **Sydney Water "Tap In"**

The approved plans must be submitted to the Sydney Water Tap in service, prior to works commencing, to determine whether the development will affect any Sydney Water assets and/or easements. The appropriately stamped plans must then be submitted to the Certifier demonstrating the works are in compliance with Sydney Water requirements.

Please refer to the website www.sydneywater.com.au for:

- o "Tap in" details - see <http://www.sydneywater.com.au/tapin>
- o Guidelines for Building Over/Adjacent to Sydney Water Assets.

Or telephone 13 000 TAP IN (1300 082 746).

Reason: To ensure compliance with the statutory requirements of Sydney Water.

30. **Waste and Recycling Requirements**

Details demonstrating compliance with Northern Beaches Waste Management Guidelines, are to be submitted to and approved by the Certifier prior to the issue of any Construction Certificate.

If the proposal, when compliant with the Northern Beaches Waste Management Guidelines, causes inconsistencies with other parts of the approval i.e. architectural or landscaped plans, a modification(s) to the development may be required.

Reason: To ensure adequate and appropriate waste and recycling facilities are provided.

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

31. **Project Arborist**

a) a Project Arborist with minimum AQF Level 5 in arboriculture shall be engaged prior to any commencement of works on site to provide tree protection measures in accordance with AS 4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment.

b) the Project Arborist shall be in attendance and supervise all works as nominated in the Arboricultural Impact Assessment, and in particular:

- i) tree protection measures under section 4 Arboricultural Method Statement (Plan TMP01 is outdated and as such on site arboricultural advice takes precedence), and Appendix 8 Schedule of works and responsibilities,
- ii) all works in the tree protection zone of trees 1, 2, and 4.

c) All tree protection measures specified must:

- i) be in place before work commences on the site, and
- ii) be maintained in good condition during the construction period, and
- iii) remain in place for the duration of the construction works.

d) the Project Arborist shall provide certification to the Certifier that all tree protection measures

under AS 4970-2009 have been satisfied, and the recommendations listed for the protection of the existing tree(s) have been carried out satisfactorily to ensure no impact to the health of the tree(s). Photographic documentation of the condition of all trees to be retained shall be recorded, including at commencement, during the works and at completion.

Note: any potential impact to trees as assessed by the Project Arborist will require redesign of any approved component to ensure existing trees upon the subject site and adjoining properties are preserved and shall be the subject of a modification application where applicable.

Reason: Tree protection.

32. **Tree Removal Within the Property**

a) this consent approves the removal of existing trees on the subject site as listed below:

i) tree 3 - *Corymbia maculata*, and tree 5 - *Plumeria rubra*.

b) a qualified AQF level 5 Arborist shall identify these trees on site and tag or mark prior to removal.

Reason: To enable authorised development works.

33. **Demolition Traffic Management Plan**

As a result of the site constraints, limited vehicle access and parking, a Demolition Traffic Management Plan (DTMP) shall be prepared by an suitably accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to commencing any demolition work.

Due to heavy traffic congestion throughout the area, truck movements will be restricted during the major commuter peak times being 8.00-9.30am and 4.30-6.00pm.

The DTMP must:-

- Make provision for all construction materials to be stored on site, at all times.
- The DTMP is to be adhered to at all times during the project.
- Specify construction truck routes and truck rates. Nominated truck routes are to be distributed over the surrounding road network where possible.
- Provide for the movement of trucks to and from the site, and deliveries to the site. Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site is not permitted unless prior approval is granted by Council's Traffic Engineers.
- Include a Traffic Control Plan prepared by an TfNSW accredited traffic controller for any activities involving the management of vehicle and pedestrian traffic.
- Specify that a minimum fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measures.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes, structures proposed on the footpath areas (hoardings, scaffolding or temporary shoring) and extent of tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the DTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities. These communications must be documented and submitted to Council prior to work commencing on site.

- Specify spoil management process and facilities to be used on site.
- Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of demolition. At the direction of Council, the applicant is to undertake remedial treatments such as patching at no cost to Council.

The DTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – “Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Demolition Traffic Management Plan is submitted.

Reason: This condition is to ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. The DTMP is intended to minimise impact of construction activities on the surrounding community, in terms of vehicle traffic (including traffic flow and parking) and pedestrian amenity adjacent to the site.

DURING BUILDING WORK

34. **Acid Sulfate Soils**

All excavation, construction and associated works must be conducted in accordance with the approved Acid Sulfate Soil Management Plan titled Acid Sulfate Soil Management Plan dated 16 March 2023 ref. no. E35645Plet-ASSMP prepared by JK Environments.

Reason: To ensure management of potential acid sulfate soils.

35. **Requirement to notify about new Acid Sulfate Soils evidence**

Any new information revealed during excavation works that has the potential to alter previous conclusions about Acid Sulfate Soils shall be immediately notified to the Council and the Principal Certifier and a report be obtained from a suitably qualified person. Any recommendations provided by the report are to be complied with during works.

Reason: To protect the environment.

36. **Site Contamination - Acid Sulfate Soils**

All stockpiles of potentially contaminated soil must be stored in a secure area in a way that is not likely to cause pollution or be a public health risk.

All contaminated soil removed from the site must be disposed of at a waste facility that can lawfully receive that waste and must be done in accordance with all relevant Acts, Regulations and Guidelines.

Copies of all test results and disposal dockets must be retained by whom? for at least 3 years and be made available to authorised Council officers on request.

Note: The following Acts and Guidelines applied at the time of determination:

- i) Protection of the Environment Operations Act 1997;
- ii) Environment Protection Authority, Waste Classification Guidelines (2014);
- iii) Water Quality Australia, National Acid Sulfate Soils Guidance (2018); and
- iv) Acid Sulfate Soil Advisory Committee, Acid Sulfate Soil Manual (1998).

Reason: To protect environment and public health.

37. Tree and Vegetation Protection

a) existing trees and vegetation shall be retained and protected, including:

- i) all trees within the site not approved for removal, including trees and vegetation nominated for retention on the approved Plans,
- ii) all trees and vegetation located on adjoining properties,
- iii) all trees and vegetation within the road reserve.

b) tree protection shall be undertaken as follows:

- i) tree protection shall be in accordance with AS 4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment,
- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
- vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist/Project Arborist to the Principal Certifier,
- viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS 4970-2009 Protection of trees on development sites,
- ix) the activities listed in section 4.2 of AS 4970-2009 Protection of trees on development sites, shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
- x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with AS 4373-2007 Pruning of amenity trees,
- xi) the tree protection measures specified in this clause must: be in place before work commences on the site, be maintained in good condition during the construction period, and remain in place for the duration of the construction works.

c) the Principal Certifier must ensure that:

- i) If activated, the arboricultural works listed in a) and b) are undertaken and certified by an Arborist/Project Arborist as complaint to AS 4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment.

Reason: Tree and vegetation protection.

38. Condition of Trees

- a) during the construction period the applicant is responsible for ensuring all existing trees required to be retained are maintained in a healthy and vigorous condition. This is to be done by ensuring that all identified tree protection measures are adhered to, or by seeking arboricultural advice from an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture during the works. In this regard all protected trees shall not exhibit:
 - i) a general decline in health and vigour,

- ii) damaged, crushed or dying roots due to poor pruning techniques,
- iii) more than 10% loss or dieback of roots, branches and foliage,
- iv) mechanical damage or bruising of bark and timber of roots, trunk and branches,
- v) yellowing of foliage or a thinning of the canopy untypical of its species,
- vi) an increase in the amount of deadwood not associated with normal growth,
- vii) an increase in kino or gum exudation,
- viii) inappropriate increases in epicormic growth that may indicate that the plants are in a stressed condition,
- ix) branch drop, torn branches and stripped bark not associated with natural climatic conditions.

b) any mitigating measures and recommendations required by the Arborist/Project Arborist are to be implemented.

c) the owner of the adjoining allotment of land is not liable for the cost of work carried out for the purpose of this clause.

Reason: Protection of trees.

39. **Wildlife Protection**

If construction activity associated with this development results in injury or displacement of a native mammal, bird, reptile or amphibian, a licensed wildlife rescue and rehabilitation organisation must be contacted for advice.

Reason: To protect native wildlife.

40. **Protection of Habitat Features**

All natural landscape features, including any rock outcrops, native vegetation and/or watercourses, are to remain undisturbed during the construction works, except where affected by necessary works detailed on approved plans.

Reason: To protect wildlife habitat.

41. **Road Reserve**

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public safety.

42. **Aquatic environment protection**

Environmental safeguards are to be used during construction to protect the aquatic environment. Appropriate methods must be installed and secured to ensure damage to the aquatic environment is minimised. Actions and recommendations of the aquatic ecology report must be followed.

Reason: To protect the aquatic environment.

43. **Dewatering Management**

The groundwater/tailwater to be discharged must be compliant with the General Terms of Approval/Controlled Activity permit issued by WaterNSW (if applicable), Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) (Blue Book), Council's Compliance and Enforcement Policy and legislation including Protection of the Environment Operations Act 1997 and Contaminated Lands Act 1997.

Surface water and rainwater: A Council dewatering permit application must be made for expected multiple instances or continuous dewatering of the site sediment and erosion controls measures.
Groundwater: A permit from Council is required for any dewatering of groundwater.

All approvals, water discharges and monitoring results are to be documented and kept on site. Copies of all records shall be provided to the appropriate regulatory authority, including Council, upon request.

Reason: Protection of the receiving environment and groundwater resources.

44. Installation and Maintenance of Sediment and Erosion Controls

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: Protection of the receiving environment.

45. Implementation of Demolition Traffic Management Plan

All works and demolition activities are to be undertaken in accordance with the approved Demolition Traffic Management Plan (DTMP). All controls in the DTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the DTMP be impacted by surrounding major development not encompassed in the approved DTMP, the DTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved DTMP is to be kept onsite at all times and made available to the accredited certifier or Council on request.

Reason: To ensure compliance and Council's ability to modify the approved Construction Traffic Management Plan where it is deemed unsuitable during the course of the project.

46. Implementation of Construction Traffic Management Plan

All works and construction activities are to be undertaken in accordance with the approved Construction Traffic Management Plan (CTMP). All controls in the CTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the CTMP be impacted by surrounding major development not encompassed in the approved CTMP, the CTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved CTMP is to be kept onsite at all times and made available to Council on request.

Reason: To ensure compliance of the developer/builder in adhering to the Construction Traffic Management procedures agreed and are held liable to the conditions of consent.

47. Removing, Handling and Disposing of Asbestos

Any asbestos material arising from the demolition process shall be removed and disposed of in accordance with the following requirements:

- o Work Health and Safety Act;
- o Work Health and Safety Regulation;
- o Code of Practice for the Safe Removal of Asbestos [NOHSC:2002 (1998)];
- o Guide to the Control of Asbestos Hazards in Buildings and Structures [NOHSC: 3002 (1998);
- o Clause 42 of the Protection of the Environment Operations (Waste) Regulation 2005; and
- o The demolition must be undertaken in accordance with Australian Standard AS2601 – The Demolition of Structures.

Reason: For the protection of the environment and human health.

48. Geotechnical Requirements

All recommendations (if any) included in the Geotechnical Report referenced in Condition 1 of this consent are required to be complied with during works.

Reason: To ensure geotechnical risk is mitigated appropriately.

49. Demolition Works - Asbestos

Demolition works must be carried out in compliance with WorkCover Short Guide to Working with Asbestos Cement and Australian Standard AS 2601 2001 The Demolition of Structures.

The site must be provided with a sign containing the words DANGER ASBESTOS REMOVAL IN PROGRESS measuring not less than 400 mm x 300 mm and be erected in a prominent visible position on the site. The sign is to be erected prior to demolition work commencing and is to remain in place until such time as all asbestos cement has been removed from the site and disposed to a lawful waste disposal facility.

All asbestos laden waste, including flat, corrugated or profiled asbestos cement sheets must be disposed of at a lawful waste disposal facility. Upon completion of tipping operations the applicant must lodge to the Principal Certifier, all receipts issued by the receiving tip as evidence of proper disposal.

Adjoining property owners are to be given at least seven (7) days' notice in writing of the intention to disturb and remove asbestos from the development site.

Reason: To ensure the long term health of workers on site and occupants of the building is not put at risk unnecessarily.

50. Survey Certificate

A survey certificate prepared by a Registered Surveyor at the following stages of construction:

(a) Commencement of perimeter walls columns and or other structural elements to ensure the wall or structure, to boundary setbacks are in accordance with the approved details.

(b) At ground level to ensure the finished floor levels are in accordance with the approved levels, prior to concrete slab being poured/flooring being laid.

(c) At completion of the roof frame confirming the finished roof/ridge height is in accordance with levels indicated on the approved plans.

Details demonstrating compliance are to be submitted to the Principal Certifier.

Reason: To determine the height of buildings under construction comply with levels shown on approved plans.

51. **Waste Management During Development**

The reuse, recycling or disposal of waste during works must be done generally in accordance with the Waste Management Plan for this development.

Details demonstrating compliance must be submitted to the Principal Certifier.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

52. **Unexpected Finds Protocol**

The Unexpected Finds Protocol prepared by JKEvironments dated 17 March 2023, ref; E35645Plet2-UFP is to be complied with during the demolition and construction phase of the development.

Reason: To ensure unexpected finds are managed appropriately to minimize contamination.

53. **Aboriginal Heritage**

If in undertaking excavations or works any Aboriginal site or object is, or is thought to have been found, all works are to cease immediately and the applicant is to contact the Aboriginal Heritage Officer for Northern Beaches Council, and the Cultural Heritage Division of the Department of Planning and Environment.

Any work to a site that is discovered to be the location of an Aboriginal object, within the meaning of the National Parks and Wildlife Act 1974, requires a permit from the Director of the Department of Planning and Environment.

Reason: Aboriginal Heritage Protection.

54. **Waste/Recycling Requirements (Waste Plan Submitted)**

During demolition and/or construction the proposal/works shall be generally consistent with the submitted Waste Management Plan.

Reason: To ensure waste is minimised and adequate and appropriate waste and recycling facilities are provided.

55. **Waste/Recycling Requirements (Materials)**

During demolition and/or construction the following materials are to be separated for recycling: timber, bricks, tiles, plasterboard, metal, concrete, and evidence of disposal for recycling is to be retained on site.

Reason: To ensure waste is minimised and recovered for recycling where possible.

BEFORE ISSUE OF THE OCCUPATION CERTIFICATE

56. **Fire Safety Matters**

At the completion of all works, a Fire Safety Certificate will need to be prepared which

references all the Essential Fire Safety Measures applicable and the relative standards of Performance (as per Schedule of Fire Safety Measures). This certificate must be prominently displayed in the building and copies must be sent to Council and Fire and Rescue NSW.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of a part Occupation Certificate or Occupation Certificate. Each year the Owners must send to the Council and Fire and Rescue NSW, an annual Fire Safety Statement which confirms that all the Essential Fire Safety Measures continue to perform to the original design standard.

Reason: Statutory requirement under Parts 10, 11 & 12 of the Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021.

57. **Acid Sulfate Soil Management Confirmation**

Details demonstrating compliance with the approved Acid Sulfate Soil Management Plan titled Acid Sulfate Soils Management Plan dated 16 March 2023 ref. no. E35645Plet-ASSMP prepared by JK Environmenta is to be submitted to the satisfaction of the principal certifier prior to the issue of the occupation certificate.

Reason: To ensure management of potential acid sulfate soils.

58. **Mechanical Plant**

All recommendations within the acoustic report prepared for the mechanical plant and equipment are to be implemented into the development according to the acoustic report.

All fans and ductwork in the kitchen must be resiliently hung with a static deflection exceeding 10 mm.

Kitchen supply and return ductwork must be lined with a minimum of 50 mm thick insulation (minimum 11 kg/m³).

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure mechanical plant has been acoustically treated to protect the noise amenity of the area.

59. **Landscape Completion**

a) landscape works are to be implemented in accordance with the approved Landscape Plan(s) (drawing DA-101 Issue D by Landart dated 13/03/24), and inclusive of the following conditions:

- i) landscape works are to be contained within the legal property boundaries,
- ii) planting shall be installed as indicated on the approved Landscape Plan(s) unless otherwise imposed by any conditions,
- iii) one *Tristaniopsis laurina* shall be installed in Landscaped Area 3 (LA-3) and one *Tristaniopsis laurina* shall be installed in Landscaped Area 4 (LA-4),
- iv) one *Corymbia maculata* shall be installed within the property boundaries to replace tree 3,
- v) all tree planting shall be a minimum pre-ordered planting size of 75 litres or as otherwise scheduled if greater in size; meet the requirements of Natspec - Specifying Trees; planted into a prepared planting hole 1m x 1m x 600mm depth generally, backfilled with a sandy loam mix or approved similar, mulched to 75mm depth minimum and maintained, and watered until established; and shall be located at least 3.0 metres from or more, at least 1.5 metres from

common boundaries; and located either within garden bed or within a prepared bed within lawn,

- vi) mass planting shall be installed at minimum 1 metre intervals (or less) for shrubs of a minimum 200mm container size at planting or as otherwise scheduled if greater in size, and at minimum 4 plants per metre square for groundcovers of a minimum 140mm container size at planting or as otherwise scheduled if greater in size, and shall be in a garden bed prepared with a suitable free draining soil mix and minimum 75mm depth of mulch,
- vii) all proposed tree planting shall be positioned in locations to minimise significant impacts on neighbours in terms of blocking winter sunlight to living rooms, private open space and where the proposed location of trees may otherwise be positioned to minimise any significant loss of views from neighbouring and nearby dwellings and from public spaces,
- viii) where swimming pools are part of the development works, selected planting shall comply with the planting and care requirements of AS1926.1 for a non-climbable zone.

b) prior to the issue of an Occupation Certificate, details (from a landscape architect, landscape designer or qualified horticulturalist) shall be submitted to the Principal Certifier, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

60. Condition of Retained Vegetation

- a) prior to the issue of an Occupation Certificate, a report prepared by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall be submitted to the Principal Certifier, assessing the health and impact on all existing trees required to be retained on the approved Plans or as listed in the Arboricultural Impact Assessment, including the following information:
 - i) compliance to any Arborist recommendations for tree protection generally and during excavation works,
 - ii) extent of damage sustained by vegetation as a result of the construction works,
 - iii) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: Tree and vegetation protection.

61. No Weeds Imported On To The Site

No Priority or environmental weeds (as specified in the Northern Beaches Local Weed Management Plan) are to be imported on to the site prior to or during construction works.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to issue of any Occupation Certificate.

Reason: To reduce the risk of site works contributing to spread of Priority and environmental weeds.

62. Stormwater Disposal

The stormwater drainage works shall be certified as compliant with all relevant Australian Standards and the approved construction certificate stormwater management plans by the design engineer. Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater arising from the development.

63. Certification for the Installation of Stormwater Treatment Measures

A certificate from a Civil Engineer, who has membership to Engineers Australia and the

National Engineers Register must be provided, stating that the stormwater treatment measures have been installed in accordance with the approved construction certificate plans prepared. The certificate must confirm that stormwater treatment measures are completed, online, in good condition and are not impacted by sediment. Vegetated measures must exhibit an 80 percent survival rate of plantings.

The certificate shall be submitted to the Principal Certifier prior to the release of an Occupation Certificate.

Reason: Protection of the receiving environment.

64. Positive Covenant, Restriction as to User and Registration of Encumbrances for Stormwater Treatment Measures

A positive covenant shall be created on the title of the land requiring the proprietor of the land to maintain the stormwater treatment measures in accordance with the standard requirements of Council, the manufacturer and as required by the Stormwater Treatment Measures Operation and Maintenance Plan.

A restriction as to user shall be created on the title over the stormwater treatment measures, restricting any alteration to the measures.

The terms of the positive covenant and restriction as to user are to be prepared to Council's standard requirements (available from Council) at the applicant's expense and endorsed by the Northern Beaches Council's delegate prior to lodgement with the Department of Lands. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction as to user is to be submitted to the Principal Certifier prior to the issue of the Occupation Certificate.

Reason: To identify encumbrances on land, ensure ongoing maintenance, and ensure modification to the stormwater treatment measures is not carried out without Council's approval.

65. Stormwater Treatment Measures Operation and Maintenance Plan

An Operation and Maintenance Plan is to be prepared to ensure the proposed stormwater treatment measures remain effective.

The Plan must be attached to the Positive Covenant (and the community or strata management statement if applicable) and contain the following:

1. Detail on the stormwater treatment measures:
 - a) Work as executed drawings
 - b) Intent of the stormwater treatment measures including modelled pollutant removal rates
 - c) Site detail showing catchment for each device
 - d) Vegetation species list associated with each type of vegetated stormwater treatment measure
 - e) Impervious area restrictions to maintain the water balance for the site

- f) Funding arrangements for the maintenance of all stormwater treatment measures
 - g) Identification of maintenance and management responsibilities
 - h) Maintenance and emergency contact information
2. Maintenance schedule and procedure - establishment period of one year following commissioning of the stormwater treatment measure:
- a) Activity description, and duration and frequency of visits
- Additionally for vegetated devices:
- b) Monitoring and assessment to achieve an 80 percent survival rate for plantings
 - c) Management of weeds, pests and erosion, with weed and sediment cover limited to a maximum of 5 percent of the total area of the stormwater treatment measure
3. Maintenance schedule and procedure - ongoing
- a) Activity description, and duration and frequency of visits
 - b) Routine maintenance requirements
 - c) Work Health and Safety requirements
 - d) Waste management and disposal
 - e) Traffic control (if required)
 - f) Renewal, decommissioning and replacement timelines and activities of all stormwater treatment measures (please note that a DA may be required if an alternative stormwater treatment measure is proposed)
 - g) Requirements for inspection and maintenance records, noting that these records are required to be maintained and made available to Council upon request.

Details demonstrating compliance shall be submitted to the Principal Certifier prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment.

66. **Works as Executed Drawings - Stormwater Treatment Measures**

Works as Executed Drawings for the stormwater treatment measures must be prepared in accordance with Council's Guideline for Preparing Works as Executed Data for Council Stormwater Assets.

The drawings shall be submitted to the Principal Certifier prior to the release of the Occupation Certificate.

Reason: Protection of the receiving environment.

67. **Disabled Parking Spaces**

Where disabled parking spaces are provided they must be in accordance with AS2890.6:2009.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure compliance with Australian Standards.

68. Operational Management Plan

An Amended Operational Management Plan (OMP) is required to be prepared and submitted to Council detailing the operation of the development. The OMP shall include, but not be limited to the following:

- Vehicle access and egress.
- Through-site circulation of vehicle movements.
- Management of car parking areas.
- The location and content of directional signage.
- Complaints management.
- Noise management.
- Truck delivery times and methods of control to manage the sequencing of the loading docks.
- Waste management.

The following changes to the submitted Operational Plan of Management are also required:

- provide further clarification on Section 6.2 (c) which states that, "Some access to the car park will be limited to Licence Plate Recognition (LPR) for members and a full time security guard will be present during the hours of 9pm to 5am 7 days per week. There is a plan to continue Licence Plate Recognition (LPR) to the whole carpark in the future." The purpose of the above to be outlined and confirmation that it will not impact upon the ability of visitors to access parking within the site.
- Section 6.2 (d) which relates to loading must be amended as there is no loading area, neither existing nor proposed, with the area currently used for loading/unloading of goods being sited on a boat ramp which by definition means that the loading/unloading of goods could only occur when the ramp is not being used for the launching or retrieval of watercraft.
- provide further clarification in the Plan or Management outlining which areas of the lower carpark will be made available for patrons and visitors to park. This is essential for clarity and to ensure that adequate provision is made for parking for events. If there are spaces that will remain unavailable these should be shown on marked up plan. In addition, Council requires that a 'parking marshal' should be present at the boom gate during events or other peak operating times in addition to 'signage' to assist patrons unfamiliar the carpark and to provide guidance to the nearest available parking.

An amended Plan of Management is to be lodged with Council for review and approval, and details demonstrating compliance with the above are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure that the development operates with minimum disruption to the surrounding area.

69. Geotechnical Certification Prior to Occupation Certificate

The Applicant is to submit the completed Form 3 of the Geotechnical Risk Management Policy (Appendix 5 of P21 DCP) to the Principal Certifier prior to issue of the Occupation Certificate.

Reason: To ensure geotechnical risk is mitigated appropriately.

70. Waste Management Confirmation

Prior to the issue of an Occupation Certificate, evidence / documentation must be submitted to

the Principal Certifier that all waste material from the development site arising from demolition and/or construction works has been appropriately recycled, reused or disposed of generally in accordance with the approved Waste Management Plan.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

71. **Post-Construction Dilapidation Report (Major Development)**

The applicant must bear the cost of all restoration works to Council's road, footpath and drainage assets damaged during the course of this development.

A Post Construction Dilapidation Report after the completion of all building works is to demonstrate that there is no damage to Council infrastructure prior to the refund of any security deposits.

Reason: To ensure security against possible damage to Council property.

72. **Construction Material - Acoustic Treatment**

Barriers for the north-facing sections of the outdoor ground floor casual dining area, pool terrace, and rooftop terrace must be installed as specified in Section 5 and Figure 4 of the Acoustic Report dated 1 March 2023, Ref 230301 RMYCN v1.1, prepared by Acoustic Directions.

The barriers must be constructed of a solid material of not less than 12 kg/m². They can be transparent acrylic or glass as required. However, advice should be sought from a structural engineer in relation to wind loads and support.

Acoustic absorption at least 50 mm thick (minimum flow resistivity 7000 Rayls/m) must be fixed to the ceiling and wall areas of the ground-floor casual dining area and first-floor terrace as specified in Section 5 and Figure 4 of the above acoustic report, to reduce noise levels. Architectural finishes and mounting options can be discussed as required.

Details demonstrating compliance are to be submitted to the Principal Certifier.

Reason: To ensure the premises is suitably constructed to ensure the noise amenity of the area.

73. **Kitchen Design, construction and fit out of food premises certification**

Prior to the issuing of any occupation certificate, certification is to be provided to the Principal Certifier by a suitably qualified person demonstrating that the design, construction and fit out of food premises kitchen is compliant with the requirements of AS 4674 Design, construction and fit out of food premises.

Reason: To ensure that the kitchen complies with Australian Standard design requirements.

74. **Mechanical Ventilation certification**

Where Mechanical ventilation is required to be installed in the food premises it must comply with the following:

- Australian Standard (AS) 1668.2 "The use of ventilation and air-conditioning in buildings - Mechanical ventilation in buildings"; and
- Any external exhaust discharge must be above the roofline and discharged in a manner that is not likely to cause an amenity impact.

Certification is to be provided to the Principal Certifier prepared by a suitably qualified person to demonstrate that the mechanical ventilation complies with the above requirements.

Reason: To ensure that the installed mechanical ventilation complies with the requirements of the Australian Standard 1668.2 and to prevent amenity impacts.

75. **Sydney Water**

A Section 73 Compliance Certificate under the Sydney Water Act 1994 must be obtained from Sydney Water Corporation.

Application must be made through an authorised Water Servicing Co-ordinator. Please refer to the Building Developing and Plumbing section of the web site www.sydneywater.com.au <<http://www.sydneywater.com.au>> then refer to “Water Servicing Coordinator” under “Developing Your Land” or telephone 13 20 92 for assistance.

Following application a “Notice of Requirements” will advise of water and sewer infrastructure to be built and charges to be paid. Please make early contact with the Co-ordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure compliance with the statutory requirements of Sydney Water.

76. **Waste/Recycling Compliance Documentation**

Evidence of disposal for recycling from the construction/demolition works shall be submitted to the Principal Certifier prior to the issue of an Occupation Certificate.

Reason: To ensure waste is minimised and recycled.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

77. **Noise Controls**

Amplification for music on the rooftop terrace will be provided by a small portable system and will cease at **10:00 pm**. The musical content shall be background accompaniment rather than foreground i.e. music levels must not exceed 77 dB (LAeq) when measured at 10 m on axis to the loudspeaker.

The rooftop terrace loudspeaker must be positioned close to the internal function space, no higher than 2 m, and face due-south or west as specified in Section 5 and Figure 4 of the Acoustic Report prepared by Acoustic Directions, Report Ref.: 230301 RMYCN v1.1, dated 1 March 2023.

When the second-floor function room is being utilised, the doors are to be closed to minimise noise egress to the outdoor terrace, particularly if there is a live musician situated inside the function area.

The ground-floor casual dining area must not operate after **10:00pm**.

The doors between the internal area of the club and the outdoor and semi-outdoor areas are to remain closed except for ingress and egress of customers and staff.

Rubbish, especially glass, shall not be disposed externally between 10:00 pm and 7:00 am (8:00 am on Sundays and public holidays).

Reason: To ensure acoustic compliance in an operational situation.

78. **Deliveries and waste service collections**

Deliveries and waste service collections shall not occur after 10pm and before 6am on any day.

Reason: Reason: To minimise the impacts of noise on neighbouring premises.

79. **Landscape Maintenance**

a) if any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components.

b) trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilised as required at the time of planting.

c) if any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plan(s) and any conditions of consent.

d) the approved landscape planted areas, whether containing lawn, gardens or planters shall in perpetuity remain as planting under the development consent, and shall not be replaced with any hard paved surfaces or structures.

Reason: To maintain local environmental amenity.

80. **Maintenance of Stormwater Treatment Measures - Major**

Stormwater treatment measures must be maintained at all times in accordance with the Stormwater Treatment Measure Operation and Maintenance Plan, manufacturer's specifications and as necessary to achieve the required stormwater quality targets for the development.

Vegetated stormwater treatment measures must maintain an 80 percent survival rate of plantings and limit weed cover to no more than 10 percent of the total area of the stormwater treatment measure.

Where replacement cartridges or other necessary components for the system become unavailable, an alternative system is required to be retrofitted into the development to achieve an equivalent pollutant reduction outcome. Evidence supporting the replacement must be retained on site and made available to Council as required.

Northern Beaches Council reserves the right to enter the property and carry out appropriate maintenance of the device at the cost of the property owner.

Reason: Protection of the receiving environment.

81. **Patron Capacity**

The maximum number of patrons within the premises at any time is to be no more than 302 (282 patrons as per Table 1 of the Operational Plan of Management dated 22 May 2024 as referenced in Condition 1, plus 20 patrons for the wellness facility). This includes the lounge and bar, dining and kitchen, function rooms (including roof terrace), outdoor swimming pool

area, providore, wellness facility, and other licensed areas.

Reason: To ensure that the premises operates consistent with the proposed development and does not adversely affect neighborhood amenity.

82. Operational Plan of Management

The Operational Plan of Management as approved by Council shall be complied with at all times.

Reason: To ensure the premises operates in a manner which is safe and does not adversely affect neighbourhood amenity.

83. Compliance with Estuarine Risk Management Report

The development is to comply with all recommendations of the approved Estuarine Risk Management Report prepared by Horton Coastal Engineering Pty. Ltd. dated 26 April 2023 and these recommendations are to be maintained over the life of the development.

Reason: To ensure preservation of the development and the estuarine environment

84. Hours of Operation

The hours of operation are to be restricted to:

- Monday to Thursday – 8:00am to 10:00pm
- Saturday, Sunday and Public Holidays – 8:00am to 12:00am midnight

Upon expiration of the permitted hours, all service (and entertainment) shall immediately cease and no patrons shall be permitted entry. All patrons on the premises shall be required to leave within the following 15 minutes, with the exception of patrons waiting inside the venue (other than in any restricted area) for collection by a taxi or courtesy bus.

Reason: Information to ensure that amenity of the surrounding locality is maintained.

General advisory notes

This consent contains the conditions imposed by the consent authority which are to be complied with when carrying out the approved development. It is an offence under the EP&A Act to carry out development that is not in accordance with this consent. However, this consent is not an exhaustive list of all obligations which may relate to the carrying out of the development under the EP&A Act, EP&A Regulation and other legislation.

Some of these additional obligations are set out in the Conditions of development consent: advisory notes, which has been uploaded to the NSW Planning Portal as a separate document. The consent should be read together with the advisory notes to ensure the development is carried out lawfully.

Dictionary

The following terms have the following meanings for the purpose of this determination (except where

the context clearly indicates otherwise):

Approved plans and documents means the plans and documents endorsed by the consent authority, a copy of which is included in this notice of determination.

AS means Australian Standard published by Standards Australia International Limited and means the current standard which applies at the time the consent is issued.

Building work means any physical activity involved in the erection of a building.

Certifier means a council or a person that is registered to carry out certification work under the Building and Development Certifiers Act 2018.

Construction certificate means a certificate to the effect that building work completed in accordance with specified plans and specifications or standards will comply with the requirements of the EP&A Regulation and Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021.

Council means Northern Beaches Council.

Court means the Land and Environment Court of NSW.

EPA means the NSW Environment Protection Authority.

EP&A Act means the Environmental Planning and Assessment Act 1979.

EP&A Regulation means the Environmental Planning and Assessment Regulation 2021.

Independent Planning Commission means Independent Planning Commission of New South Wales constituted by section 2.7 of the EP&A Act.

Local planning panel means Northern Beaches Local Planning Panel.

Occupation certificate means a certificate that authorises the occupation and use of a new building or a change of building use for an existing building in accordance with this consent.

Principal certifier means the certifier appointed as the principal certifier for building work or subdivision work under section 6.6(1) or 6.12(1) of the EP&A Act respectively.

Site work means any work that is physically carried out on the land to which the development the subject of this development consent is to be carried out, including but not limited to building work, subdivision work, demolition work, clearing of vegetation or remediation work.

Stormwater drainage system means all works and facilities relating to: the collection of stormwater, the reuse of stormwater, the detention of stormwater, the controlled release of stormwater, and connections to easements and public stormwater systems.

Strata certificate means a certificate in the approved form issued under Part 4 of the Strata Schemes Development Act 2015 that authorises the registration of a strata plan, strata plan of subdivision or notice of conversion.

Subdivision certificate means a certificate that authorises the registration of a plan of subdivision under Part 23 of the Conveyancing Act 1919.

Subdivision works certificate means a certificate to the effect that subdivision work completed in accordance with specified plans and specifications will comply with the requirements of the EP&A Regulation.

Sydney district or regional planning panel means Sydney North Planning Panel. Some of these additional obligations are set out in the Conditions of development consent: advisory notes, which has been uploaded to the NSW Planning Portal as a separate document. The consent should be read together with the Conditions of development consent: advisory notes to ensure the development is carried out lawfully.

The approved development must be carried out in accordance with the conditions of this consent. It is an offence under the EP&A Act to carry out development that is not in accordance with this consent.