


- RAINWATER RE-USE TANKS:**
- CONSIDERING THE ROOF CATCHMENT AREA, LOCATION OF PROPERTY, INTENDED USE OF RAINWATER AND GARDEN SIZE WE RECOMMEND PROVIDING A RAINWATER TANK FOR USE AS PER BASIX REQUIREMENTS, SYDNEY WATER AND NSW HEALTH REQUIREMENTS FOR NON DRINKING USE ONLY AS FOLLOWS:  
a) TO WATER GARDEN AREAS b) WASHING CARS c) CONNECT TO M.C.  
d) CONNECT TO WASHING MACHINE. e) USED IN HOT WATER SYSTEMS.  
f) FILLING SWIMMING POOLS, SPAS AND ORNAMENTAL PONDS.
  - THE TANKS PROVIDED WILL REDUCE PRESSURE ON COUNCIL'S STORMWATER INFRASTRUCTURE.
  - REFERENCES:  
COOMBS P.J. & KUCZERA G. (2001), "RAINWATER TANK DESIGN FOR WATER SUPPLY & STORMWATER MANAGEMENT." STORMWATER INDUSTRY ASSOCIATION REGIONAL CONFERENCE.  
PATRICK DUPONT & STEVE SHACKEL, "RAINWATER"  
AUSTRALIAN GOVERNMENT (2004), "GUIDANCE ON USE OF RAINWATER TANKS"  
4. ALL CONNECTIONS TO PLUMBING AND RAINWATER TANKS TO BE IN ACCORDANCE WITH SYDNEY WATERS' GUIDE "INSTALLING A RAINWATER TANK"  
AVAILABLE AT [www.sydneywater.com.au](http://www.sydneywater.com.au)
  - PROVIDE A DUAL SUPPLY SYSTEM AND BACKFLOW PREVENTION SYSTEM IN ACCORDANCE WITH "BASIX-DESIGN GUIDE FOR SINGLE DWELLINGS" BY NSW DEPARTMENT OF INFRASTRUCTURE, PLANNING AND NATURAL RESOURCES.
  - IF NOT SPECIFIED ON PLANS, THE FIRST FLUSH SYSTEM IS TO HAVE A MINIMUM SIZE OF 20L PER 100m<sup>2</sup> OF ROOF CATCHMENT AREA PRIOR TO ENTERING THE RAINWATER TANK. INDIVIDUAL SITE ANALYSIS IS REQUIRED IN HEAVILY POLLUTED AREAS TO DETERMINE IF LARGER VOLUMES OF FIRST FLUSH RAINWATER ARE TO BE DIVERTED. IF IN DOUBT, CHECK WITH LOCAL HEALTH AUTHORITIES.
  - SCREENED DOWNPIPE RAINWATER HEAD OR OTHER SUITABLE LEAF AND DEBRIS DEVICE TO BE INSTALLED ON EACH DOWNPIPE. SCREEN MESH TO BE 4-6mm AND DESIGNED TO BE SELF-CLEANING.
  - FIRST FLUSH DEVICES, OR APPROVED ALTERNATIVE, TO BE INSTALLED WITH AN AUTOMATED DIVERSION AND DRAINAGE SYSTEM, THAT IS, NO MANUAL DIVERSION AND DRAINAGE VALVES. REFER TYPICAL FLUSH OUT PIT FOR DETAILS.
  - BEFORE PURCHASING MATERIALS OR PAINT TO BE USED ON ROOF CATCHMENT AREAS, THE MANUFACTURER'S RECOMMENDATIONS ON LABELS AND BROCHURES FOR RAINWATER TANK SUITABILITY TO BE READ AND ADHERED TO.
  - PRE-STORAGE PITS FOR UNDERGROUND RAINWATER STORAGE TANKS AND FLUSH OUT PITS MAY ASSIST IN LIMITING SILT, AND PREVENT VERMIN, INSECTS (INCLUDING MOSQUITOES) AND DEBRIS FROM ENTERING THE RAINWATER STORAGE AREA.
  - BUILDER/PLUMBER TO ENSURE THE INSTALLATION OF THE RAINWATER TANK SYSTEM IS IN ACCORDANCE WITH THE RELEVANT AUSTRALIAN STANDARDS AND THE RAINWATER TANK DESIGN AND INSTALLATION HANDBOOK - HB 230-2008. IF IN DOUBT CONTACT ENGINEER.
  - RAINWATER TANK TO BE WATER PROOFED IN ACCORDANCE WITH HB 230-2008


LEGEND	
DPI •	100mm Ø DOWNPIPE (uPVC SEWER GRADE) DISCHARGE TO RWT VIA A CHARGED SYSTEM
DPI •	50mm Ø uPVC DOWNPIPE DISCHARGE TO DISPERSION TRENCH
DPI •	100mm Ø uPVC DOWNPIPE DISCHARGE TO BOUNDARY/FLUSH OUT PIT
RHD □	RAINHEAD - REFER DETAIL
BGI □	BOX GUTTER - REFER DETAIL
PD ⊙	PLANTER DRAIN - REFER DETAIL
FD ⊞	FLOOR DRAIN - REFER DETAIL
⊗ • E	SPREADER
— & —	EMERGENCY OVERFLOW WEIR WEIRS TO BE INSTALLED TO AS3500.3 MIN. 2x500 SPITTERS OR 300x50 CUT
⊙	INSPECTION OPENING
== > ==	50 Ø uPVC
— > —	NEW STORMWATER PIPE
— > —	STORMWATER PIPE FALL DIRECTION IN CHARGED SYSTEMS
— > —	STORMWATER PIPE FLOW DIRECTION
— ⊞ —	PIT
— ⊞ —	STORMWATER PIT
— ⊞ —	GRADED DRAIN
— ⊞ —	GDI - 150 MIN DEPTH x 150 WIDE GRADED DRAIN
RWT 1, RWT 2	RAINWATER TANKS TO COLLECT ALL DPI DOWNPIPES. RWT 1 = 5000 L RWT 2 = 5000 L
NOTE: ALL DRAINAGE LINES ARE INDICATIVE ONLY. LOCATION MAY VARY DUE TO CONSTRAINTS.	

**NOTE:**  
ALL DOWN PIPES TO DISCHARGE INTO RAINWATER RE-USE TANK IN ACCORDANCE WITH AS 3500.3

**NOTE:**  
ALL PIPE WORK IN CHARGED SYSTEM TO BE 100mm Ø uPVC SEWER GRADE PIPES WITH ALL JOINTS PRESSURE SEALED TO 500mm ABOVE INLET LEVEL OF RAINWATER TANK.




TANK INSTALLATION AS PER MANUFACTURERS DETAILS  
**TYPICAL SECTION OF IN-GROUND RWT**  
SCALE = N.T.S.



**TYPICAL SURFACE/FLUSH OUT PIT DETAIL**  
SCALE = 1 : 20

AI				DOCUMENT CERTIFICATION				NB Consulting Engineers		Architect:		Project:		Date:		Design:		Drawn:	
				Date: 29/3/19				STRUCTURAL - CIVIL - STORMWATER - REMEDIAL		WATERSHED DESIGN		PROPOSED RESIDENCE		MARCH 2019		CF		MC	
29-03-2019				B				A.C.N. 076 121 616 A.B.N. 24 076 121 616				5A HILLTOP CRESCENT FAIRLIGHT							
26-03-2019				A				Sydney: Ph: (02) 9984 7000 Fax: (02) 9984 7444		Client:		STORMWATER MANAGEMENT		Job No:		190101		D02	
				Issue:				Suite 207, 30 Fisher Road Dee Why N.S.W. 2099		MONIQUE AND ANDREW THOMPSON		GROUND FLOOR - DRAINAGE PLAN		Drawing No:		B			
Date:				Description:				Gold Coast: Ph: (07) 5631 4744											
				By:				Unit 8, 1726 Gold Coast Highway Burleigh Heads QLD 4220											
				Review:				E: nb@nbconsulting.com.au W: www.nbconsulting.com.au											

NB Consulting Engineers




UPPER FLOOR - DRAINAGE PLAN  
SCALE = 1 : 100

DENOTES EXTENT OF ATLANTIS DRAINAGE SYSTEM (OR SIMILAR APPROVED) INSTALLATION TO MANUFACTURER'S SPECIFICATIONS AND IN ACCORDANCE WITH AS3500.3


**NOTE: BOX GUTTERS**

ALL BOX GUTTER SYSTEMS SHOWN ON THESE PLANS ARE TO BE INSTALLED STRICTLY IN ACCORDANCE WITH THE ASSOCIATED DETAILS. IF ANY CHANGE TO THE BOX GUTTER CONFIGURATION IS PROPOSED, NOTIFY THE ENGINEER FOR RE-DESIGN. IF THE INSTALLED BOX GUTTER DOES NOT STRICTLY COMPLY WITH OUR DESIGN, CERTIFICATION OF THE HYDRAULIC SYSTEM MAY BE REFUSED.



RAINHEAD RHD1, RHD2 AND BOX GUTTER DETAIL


SCALE = NTS



REFER TO MANUFACTURERS SPECIFICATION FOR SPS DRAINAGE OUTLETS

STANDARD PLANTER DRAIN - 'PD'


SCALE = 1 : 10



STANDARD FLOOR DRAIN - 'FD'


SCALE = 1 : 10

OR TO ARCHITECTS DETAIL



ROOF AND TERRACE - DRAINAGE PLAN

SCALE = 1 : 100




**NOTE: DISPERSION TRENCH**

1. DISPERSION TRENCH TO BE LAID ON A LEVEL CONTOUR.
2. GROUND LEVEL ABOVE TRENCH MUST BE LEVEL SO AS TO EVENLY DISPERSE WATER DOWN HILL OF THE TRENCH

DISPERSION TRENCH LONGITUDINAL SECTION

NOT TO SCALE



SECTION X-X

NOT TO SCALE

ISSUED FOR D.A. SUBMISSION ONLY NOT FOR CONSTRUCTION

IF IN DOUBT ASK

AI

Date:	Issue:	Description:	By:	Review:
29-03-2019	B	REVISE DRAINAGE	CF	MW
26-03-2019	A	ISSUED FOR DA SUBMISSION	MC	MW

**DOCUMENT CERTIFICATION**

Date: 29/3/19  
Stewart McGeady  
B.E.(Civil), MIE Aust.  
(Director NB Consulting Engineers)  
The copyright of this drawing remains with Northern Beaches Consulting Engineers Pty Ltd. Trading as NB Consulting Engineers

**NB Consulting Engineers**


STRUCTURAL - CIVIL - STORMWATER - REMEDIAL  
A.C.N. 076 121 616 A.B.N. 24 076 121 616  
Sydney: Ph: (02) 9984 7000 Fax: (02) 9984 7444  
Suite 207, 30 Fisher Road Dee Why N.S.W. 2099  
Gold Coast: Ph: (07) 5631 4744  
Unit 8, 1726 Gold Coast Highway Burleigh Heads QLD 4220  
E: nb@nbconsulting.com.au W: www.nbconsulting.com.au

Architect:	WATERSHED DESIGN
Client:	MONIQUE AND ANDREW THOMPSON

Project:	PROPOSED RESIDENCE 5A HILLTOP CRESCENT FAIRLIGHT
Drawing Title:	STORMWATER MANAGEMENT DRAINAGE PLANS

Date:	Design:	Drawn:
MARCH 2019	CF	MC
Job No:	Drawing No:	Issue:
190101	D03	B


NB Consulting Engineers



SEDIMENT AND EROSION CONTROL PLAN

SCALE = 1 : 100


DRAINAGE AREA 0.6HA. MAX. SLOPE GRADIENT 1:2 MAX. SLOPE LENGTH 60M MAX.



SEDIMENT FENCE - OPTION 1


CONSTRUCTION NOTES:

1. CONSTRUCT SEDIMENT FENCE AS CLOSE AS POSSIBLE TO PARALLEL TO THE CONTOURS OF THE SITE.
2. DRIVE 1.5 METRE LONG STAR PICKETS INTO GROUND, 3 METRES APART.
3. DIG A 150mm DEEP TRENCH ALONG THE UPSLOPE LINE OF THE FENCE FOR THE BOTTOM OF THE FABRIC TO BE ENTRENCHED.
4. BACKFILL TRENCH OVER BASE OF FABRIC.
5. FIX SELF-SUPPORTING GEOTEXTILE TO UPSLOPE SIDE OF POSTS WITH WIRE TIES or AS RECOMMENDED BY GEOTEXTILE MANUFACTURER.
6. JOIN SECTIONS OF FABRIC AT A SUPPORT POST WITH A 150mm OVERLAP.



SEDIMENT FENCE - OPTION 2

SCALE = N.T.S.




TYPICAL TEMPORARY CONSTRUCTION ENTRY/EXIT DETAIL

CONSTRUCTION NOTES:

1. STRIP TOPSOIL AND LEVEL SITE.
2. COMPACT SUBGRADE.
3. COVER AREA WITH NEEDLE-PUNCHED GEOTEXTILE.
4. CONSTRUCT 200mm THICK PAD OVER GEOTEXTILE USING ROADBASE or 30mm AGGREGATE. MINIMUM LENGTH 15 METRES OR TO BUILDING ALIGNMENT. MINIMUM WIDTH 3 METRES.
5. CONSTRUCT HUMP IMMEDIATELY WITHIN BOUNDARY TO DIVERT WATER TO A SEDIMENT FENCE or OTHER SEDIMENT TRAP.

SCHEDULE OF WORKS:

1. SILT FENCE AND ASSOCIATED WORKS INCLUDING INTERCEPTOR DRAIN IS TO BE INSTALLED BEFORE THE COMMENCEMENT OF ANY EXCAVATION.
2. CUTS TO BE EXECUTED TO THE REQUIRED LEVEL USING CONVENTIONAL EXCAVATION MACHINERY. INITIALLY THE DEPTH OF FILL/CLAY IS TO BE ESTABLISHED TO ENSURE NEIGHBOURING PROPERTIES ARE NOT ADVERSELY AFFECTED. EARTH BATTERS TO BE A MAXIMUM SLOPE OF 1.0 m VERT. TO 1.7 m HORIZ. (AS PER GEOTECHNICAL REPORT). ANY BATTERS GREATER THAN 1.0 m VERT. TO 1.7 m HORIZ. ARE TO BE ADEQUATELY SHORED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS.
3. ANY PERMANENT RETAINING STRUCTURE IS TO BE CONSTRUCTED IN ACCORDANCE WITH THE ENGINEERS DETAILS AND INSTRUCTIONS.
4. ALL PERMANENT RETAINING STRUCTURES ARE TO BE COMPLETED WITH MINIMUM DELAY FOLLOWING EXCAVATION.



SANDBAG KERB INLET SEDIMENT TRAP


SCALE = N.T.S.

NOTES:

1. ALL EROSION AND SEDIMENT CONTROL MEASURES TO BE INSPECTED AND MAINTAINED DAILY BY SITE MANAGER.
2. MINIMISE DISTURBED AREAS.
3. ALL STOCKPILES TO BE CLEAR FROM DRAINS, GUTTERS AND FOOTPATHS.
4. DRAINAGE IS TO BE CONNECTED TO STORMWATER SYSTEM AS SOON AS POSSIBLE.
5. ROADS AND FOOTPATH TO BE SWEEPED DAILY.


GENERAL NOTES :

1. CONSTRUCTION VEHICLES ARE TO LEAVE AND ENTER THE SITE OVER AN ALL WEATHER SURFACE CONSISTING OF COURSE CRUSHED STONE OR BLUE METAL CONSTRUCTED WITHIN THE FRONT SETBACK AREA OPPOSITE THE EXISTING FOOTPATH CROSSING UNLESS NOTED OTHERWISE.
2. EXCAVATION MACHINERY ARE TO BE UNLOADED AND LOADED UPON THIS ALL WEATHER SURFACE. CONCRETE PUMPS AND TRUCKS WILL ALSO UTILISE THE ALL WEATHER SURFACE FOR THEIR OPERATIONS.
3. MATERIALS WILL BE UNLOADED UPON THE ALL WEATHER SURFACE WITHIN THE FRONT SETBACK AREA BY MEANS OF CRANES MOUNTED ON THE BACK OF DELIVERY TRUCKS OR UNLOADED BY HAND. IT IS NOT ENVISAGED THAT A MOBILE CRANE WILL BE REQUIRED DURING THE CONSTRUCTION PROCESS.
4. SOME STOCKPILING OF TOPSOIL REMOVED FROM THE BUILDING AREA MAY BE STORED ON THE SITE DURING THE CONSTRUCTION WITHIN THE PROPERTY IN AN AREA ENCLOSED WITHIN THE SEDIMENT CONTROL FENCING.
5. ALL EXCAVATED & CONSTRUCTION MATERIALS, SHED, SKIP BINS, TEMPORARY WATER CLOSETS, SPOIL AND EQUIPMENT, ETC SHALL BE KEPT WITHIN THE PROPERTY. NO VEHICLES OR MACHINES SHALL BE KEPT WITHIN THE PROPERTY. NO VEHICLES OR MACHINES SHALL STAND ON COUNCIL FOOTPATHS FOR LARGE LENGTHS OF TIME.
6. ALL RUBBISH & RECYCLABLE MATERIAL SHALL BE STOCKPILED IN WASTE BINS IN THE AREA NOMINATED ON THE SITE PLAN WITHIN THE SITE BOUNDARY. PUBLIC PROPERTY SHALL BE KEPT FREE OF RUBBISH AND RECYCLABLES AT ALL TIMES ANY WASTE MATERIALS SHALL BE REGULARLY COLLECTED FROM THE SITE AND DISPOSED OF IN AN APPROPRIATE FASHION.
7. ANY BUILDING / DEMOLITION WORKS INVOLVING ASBESTOS SHALL BE CARRIED OUT IN ACCORDANCE WITH THE RELEVANT STANDARDS.
8. VEHICLES LEAVING THE SITE WILL DO SO VIA THE ALL WEATHER BALLAST DRIVEWAY MADE OF COURSE AGGREGATE OR SIMILAR LOCATED WITHIN THE FRONT SETBACK AREA OF THE DEVELOPMENT. ANY DIRT OR MATERIAL DEPOSITED ON THE ROAD RESERVE OR ROADWAY IS TO BE PROMPTLY CLEANED.
9. ANY EXCAVATED AREA REQUIRED SUPPORT WILL BE UNDERTAKEN BY THE OWNER USING STRUCTURALLY APPROVED RETAINING STRUCTURES.
10. ADEQUATE SAFETY SIGNAGE MUST BE ERECTED IN A PROMINENT POSITION ON THE WORK SITE, WARNING OF UNAUTHORISED ENTRY TO WORK SITE AND INTENDING DANGERS.
11. SAFETY FENCES SHALL BE PROVIDED AROUND ALL BOUNDARIES UNLESS A CONTINUOUS STRUCTURALLY ADEQUATE FENCE PRESENTLY EXISTS. THE FENCING SHALL BE ADEQUATE TO RESTRICT PUBLIC ACCESS TO THE SITE WHEN BUILDING WORK IS NOT IN PROGRESS OR THE SITE IS UNOCCUPIED.
12. NOISE LEVELS SHALL NOT EXCEED COUNCIL REGULATION LEVELS. BUILDING AND DEMOLITION WORKS SHALL ONLY BE CARRIED OUT BETWEEN HOURS AND DAYS SPECIFIED BY COUNCIL.
13. GEOTEXTILE FABRIC SHALL BE PLACED ON THE INSIDE OF THE SITE FENCING PRIOR TO SITE DISTURBANCE TO PREVENT SEDIMENT WASHING FROM CLEARED AND DISTURBED AREAS OF THE SITE INTO THE STORMWATER SYSTEM DURING CONSTRUCTION UNCONTAMINATED RUNOFF FROM CLEARED OR DISTURBED AREAS IS TO BE DIRECTED TO A TEMPORARY SILT ARRESTOR PIT THAT SHALL BE PROVIDED WITHIN THE SITE AT THE STREET BOUNDARY PROCESSING SITE STORMWATER BEFORE IT IS DISCHARGED TO THE STREET DRAINAGE SYSTEM OR WATERCOURSE.
14. ALL TOP SOIL STRIPPED & STOCKPILED ON SITE IS TO BE PLACED IN NOMINATED AREAS ON PLAN. ALL DISTURBED AREAS ARE TO BE STABILISED UPON THE COMPLETION OF BUILDING WORKS.
15. ALL SEDIMENT CONTROL STRUCTURES ARE TO BE CONTINUALLY MAINTAINED DURING CONSTRUCTION AND INSPECTED FOR STRUCTURAL DAMAGE AFTER EACH RAINFALL EVENT, WITH TRAPPED SEDIMENT BEING REMOVED TO THE TOPSOIL STOCKPILE.
16. WHERE THERE IS THE POTENTIAL OF SITE EROSION TO PRODUCE EXCESSIVE SEDIMENT RUNOFF SUITABLE GEOTEXTILE BARRIERS SHALL BE PLACED TO ALLEVIATE THE RISK ACCORDINGLY. BARE SURFACES SHALL BE KEPT MOIST TO REDUCE DUST LEVELS. GEOTEXTILE FABRIC LOCATED ON THE INSIDE OF FENCES SHALL ALSO BE UTILISED FOR DUST CONTROL WHERE NECESSARY.



REMOVABLE HAY BALE DETAIL

SCALE = N.T.S.



REMOVABLE HAY BALE DETAIL

SCALE = N.T.S.



NOTE:

NO INVESTIGATION OF UNDERGROUND SERVICES HAS BEEN MADE. ALL RELEVANT AUTHORITIES SHOULD BE NOTIFIED PRIOR TO ANY EXCAVATION ON OR NEAR THE SITE

DEVELOPERS & EXCAVATORS MAY BE HELD FINANCIALLY RESPONSIBLE BY THE ASSET OWNER SHOULD THEY DAMAGE UNDERGROUND NETWORKS.

CARELESS DIGGING CAN:

- CAUSE DEATH OR SERIOUS INJURY TO WORKERS AND THE GENERAL PUBLIC
- INCONVENIENCE USERS OF ELECTRICITY, GAS, WATER AND COMMUNICATIONS
- LEAD TO CRIMINAL PROSECUTION AND DAMAGES CLAIMS
- CAUSE EXTENSIVE FINANCIAL LOSSES TO BUSINESS
- CUT OFF EMERGENCY SERVICES
- DELAY PROJECT COMPLETION TIMES WHILE THE DAMAGE IS REPAIRED

MINIMISE YOUR RISK AND DIAL BEFORE YOU DIG. - TEL. 1100

ISSUED FOR D.A. SUBMISSION ONLY NOT FOR CONSTRUCTION

IF IN DOUBT ASK

DOCUMENT CERTIFICATION				Architect:		Project:		Date:	Design:	Drawn:
Date: 27/3/19 Stewart McGeady B.E.(Civil), MIE Aust. (Director NB Consulting Engineers)				WATERSHED DESIGN		PROPOSED RESIDENCE 5A HILLTOP CRESCENT FAIRLIGHT		MARCH 2019	CF	MC
26-03-2019 A ISSUED FOR DA SUBMISSION				Client:		Drawing Title:		Job No:	Drawing No:	Issue:
Date: Issue: Description:				MONIQUE AND ANDREW THOMPSON		SEDIMENT AND EROSION CONTROL PLAN AND DETAILS		190101	D04	A
By: Review:				Unit 8, 1726 Gold Coast Highway Burleigh Heads QLD 4220 E: nb@nbconsulting.com.au W: www.nbconsulting.com.au						