



eiaustralia

Contamination | Remediation | Geotechnical

PALMDEV PTY LTD



Additional Geotechnical Investigation

1112-1116 Barrenjoey Road, Palm Beach NSW



E25203.G04_Rev1
8 August 2024

Document Control

Report Title: Additional Geotechnical Investigation

Report No: E25203.G04_Rev1

Copies	Recipient
1 Soft Copy (PDF – Secured, issued by email)	William Allen Palmdev Pty Ltd Level 3, 17 Castlereagh Street SYDNEY NSW 2000
2 Original (Saved to Digital Archives) <small>(\\Pahlei\$07 - Projects\E25203_Palmdev_Palm Beach_GI\05_Deliverables\Work in Progress\G04 - AGI\E25203.G04_Rev1 - Additional Geotechnical Investigation Report.docx)</small>	EI Australia Suite 6.01, 55 Miller Street, PYRMONT NSW 2009

Author	Technical Reviewer		
			
Kaiyu Xu Geotechnical Engineer	Stephen Kim Senior Geotechnical Engineer		
Revision	Details	Date	Amended By
	Original	11 July 2024	
1	Updated recommendations	8 August 2024	KX

© 2024 EI Australia (EI) ABN: 42 909 129 957

This report is protected by copyright law and may only be reproduced, in electronic or hard copy format, if it is copied and distributed in full and with prior written permission by EI.

Table of Contents

	Page Number
1. INTRODUCTION	1
1.1 Background	1
1.2 Proposed Development	1
1.3 Objectives	2
1.4 Scope of Works	2
1.5 Constraints	3
2. SITE DESCRIPTION	4
2.1 Site Description and Identification	4
2.2 Local Land Use	5
2.3 Regional Setting	5
3. INVESTIGATION RESULTS	7
3.1 Stratigraphy	7
3.2 Groundwater Observations	8
3.2.1 <i>Groundwater Levels</i>	8
3.2.2 <i>Rising Head Test</i>	9
3.3 Test Results	9
4. RECOMMENDATIONS	11
4.1 Geotechnical Issues	11
4.2 Dilapidation Surveys	11
4.3 Demolition Considerations	11
4.4 Excavation Methodology	11
4.4.1 <i>Excavation Assessment</i>	11
4.4.2 <i>Excavation Monitoring</i>	13
4.5 Groundwater Considerations	14
4.5.1 <i>Seepage Analysis</i>	14
4.6 Excavation Retention	15
4.6.1 <i>Support Systems</i>	15
4.6.2 <i>Excavation adjacent to TfNSW Assets</i>	16
4.6.3 <i>Retaining Wall Design Parameters</i>	16
4.7 Slope Stability and Landslide Risk	18
4.7.1 <i>Geotechnical Hazard Risk Zone</i>	18
4.7.1 <i>Risk Assessment</i>	18
4.8 Foundations	19
4.8.1 <i>Shallow Footings in Rock</i>	19
4.8.2 <i>Pile Footings</i>	19
4.9 Basement Floor Slab	19

5. FURTHER GEOTECHNICAL INPUTS	20
6. STATEMENT OF LIMITATIONS	21
REFERENCES	22
ABBREVIATIONS	22

Schedule of Tables

Table 1-1	Auger Drilling and Rock Coring Depths	2
Table 2-1	Summary of Site Information	4
Table 2-2	Summary of Local Land Use	5
Table 2-3	Topographic and Geological Information	5
Table 3-1	Summary of Subsurface Conditions	7
Table 3-2	RLs of Top of Units in Boreholes (mAHD)	8
Table 3-3	Summary of Ground Water Observation	8
Table 3-4	Summary of Long-Term Groundwater Monitoring	9
Table 3-5	Summary of Soil Laboratory Test Results	10
Table 4-2	Geotechnical Design Parameters	17

Appendices

FIGURES

- Figure 1 Site Locality Plan
- Figure 2 Borehole Location Plan

APPENDIX A – BOREHOLE LOGS AND EXPLANATORY NOTES

APPENDIX B – CROSS SECTIONS

APPENDIX C – LABORATORY CERTIFICATES

APPENDIX D – VIBRATION LIMITS

APPENDIX E – IMPORTANT INFORMATION

1. Introduction

1.1 Background

At the request of Palmdev Pty Ltd (the Client), EI Australia (EI) has carried out an Additional Geotechnical Investigation (AGI) for the proposed development at 1112-1116 Barrenjoey Road, Palm Beach NSW (the Site).

This AGI report has been prepared to assist in the preparation of designs for the proposed development. The investigation has been carried out in accordance with the agreed scope of works outlined in EI's proposal referenced P19388.5_Rev2, dated 26 September 2023.

EI has previously completed the following reports for this site:

- Geotechnical Investigation (GI), referenced E25203.G03_Rev2, dated 7 December 2021. The boreholes and groundwater monitoring wells installed as part of the GI were utilised in this AGI report.
- Groundwater Monitoring Report No. 1, referenced E25203.G11.01, dated 28 February 2024;
- Groundwater Take Assessment (GTA), referenced E25203.G12_Rev2, dated 8 August 2024;
- Landslide Risk Assessment (LRA), referenced E25203.G14, dated 8 August 2024; and
- Construction Methodology Report, referenced E25203.G15, dated 8 August 2024.

1.2 Proposed Development

The following documents, supplied by the Client, were used to assist with the preparation of this GI report:

- Architectural drawings prepared by Koichi Takada Architects – Project at 1112-1118 Barrenjoey Road, Palm Beach, Drawing Nos. A0001, A0010 to A0013, A0019, A0022, A0050, A0051, A0099 to A0105, A0200 to A0203, A0300 to A0305, and A0320, latest revision I, dated 31 July 2024;
- Structural drawings prepared by M&G Consulting Engineers Pty Ltd – Job No. 5598, Drawing Nos. S010, S011, S015 and S020, Issue 1, dated 7 August 2024; and
- Site survey plan prepared by Beveridge Williams – Project No. 2101343, Drawing Ref. 2101343, Version B, dated 6 September 2021. The datum in the survey plan is in Australian Height Datum (AHD), hence all Reduced Levels (RL) mentioned in this report are henceforth in AHD.

Based on the provided documents, EI understands that the proposed development involves the demolition of the existing site structures and the construction of a four-storey mixed-use building overlying a single-level basement. The basement is proposed to have a Finished Floor Level (FFL) of RL -1.22m to -2.4m Australian Height Datum (AHD). A Bulk Excavation Level (BEL) range between RL -1.5m and -2.7m AHD is assumed for the construction which includes allowance for a concrete basement slab. To achieve the BEL, an excavation depth varying from 4.3m (towards west of site) to 15.6m (towards east of site) Below Existing Ground Level (BEGL) is expected. Locally deeper excavations may be required for footings, service trenches, crane pads, and lift overrun pits.

1.3 Objectives

The objective of the AGI was to assess site surface and subsurface conditions at seven borehole locations, and to provide geotechnical advice and recommendations addressing the following:

- Dilapidation Surveys;
- Excavation methodologies and monitoring requirements;
- Groundwater considerations;
- Vibration considerations;
- Excavation support requirements, including preliminary geotechnical design parameters for retaining walls and shoring systems;
- Building foundation options, including:
 - Preliminary design parameters.
 - Earthquake loading factor in accordance with AS1170.4:2007.
- The requirement for additional geotechnical works.

1.4 Scope of Works

The scope of works for the AGI included:

- Preparation of a Work Health and Safety Plan;
- Review of relevant geological maps for the project area and [previous reports];
- Site walkover inspection by a Geotechnical Engineer to assess topographical features and site conditions;
- Scanning of proposed borehole locations for buried conductive services using a licensed service locator with reference to Dial Before You Dig (DBYD) plans;
- Auger drilling of BH201M and BH202M by a track-mounted drill rig using solid flight augers equipped with a 'Tungsten-Carbide' (T-C) bit. BH203M was drilled for groundwater monitoring well installation only. Additionally, hand auger drilling of BH204M was completed in a difficult access location. The boreholes were auger drilled to depths as shown in **Table 1-1** below:

Table 1-1 Auger Drilling and Rock Coring Depths

Borehole ID	Auger Drilling		Rock Coring	
	Depth (m)	RL (m AHD)	Depth (m)	RL (m AHD)
BH201M	3.0	-1.80	15.49	-14.29
BH202M	3.22	-0.82	12.52	-10.12
BH203M	6.00	-4.50	-	-
BH204M	1.12	11.78	16.58	-3.68

- Standard Penetration Testing (SPT) was carried out (as per AS 1289.6.3.1-2004), where possible, during auger drilling of the boreholes to assess soil strength/relative densities;
 - Measurements of groundwater seepage/levels, where possible, in the augered sections of the boreholes during and shortly after completion of auger drilling;
 - The strength of the bedrock in the augered sections of the boreholes was assessed by observation of the auger penetration resistance using a T-C drill bit and examination of the recovered rock cuttings. It should be noted that rock strengths assessed from augered boreholes are approximate and strength variances can be expected;
 - The approximate surface levels shown on the borehole logs were interpolated from spot levels shown on the supplied survey plan. Approximate borehole locations are shown on **Figure 2**;
- Continuation of M, BH201M, BH202M, BH204M using NMLC diamond coring techniques to termination depths shown above in **Table 1-1**. The rock core photographs are presented in **Appendix A**;
 - All four boreholes were converted groundwater monitoring wells to allow for long-term groundwater monitoring.
 - The rock cores were carefully boxed and photographed on site;
 - Soil and rock samples were sent to STS Geotechnics Pty Ltd (STS) and SGS Australia (SGS), which are National Australian Testing Authority (NATA) accredited laboratories, for testing and storage and
 - Preparation of this AGI report.

EI's Geotechnical Engineer was present full-time onsite to set out the borehole locations, direct the testing and sampling, log the subsurface conditions and record groundwater levels.

1.5 Constraints

The AGI was limited by the intent of the investigation and the presence of existing site structures. The discussions and advice presented in this report are intended to assist in the preparation of designs for the proposed development. Further geotechnical inspections should be carried out during construction to confirm the geotechnical and groundwater models, and the preliminary design parameters provided in this report.

2. Site Description

2.1 Site Description and Identification

The site identification details and associated information are presented in **Table 2-1** below while the site locality is shown on **Figure 1**. An aerial photograph of the site is presented in **Plate 1** below.

Table 2-1 Summary of Site Information

Information	Detail
Street Address	1112-1116 Barrenjoey Road, Palm Beach NSW
Lot and Deposited Plan (DP) Identification	Lot 21 in DP 571298
Brief Site Description	<p>At the time of our investigation, the previous single-storey commercial building situated in the north-western section of the site and the car park located in the south-western area of the site had already been demolished and cleared for archaeological investigation.</p> <p>The north-eastern part of the site was occupied by a two-storey residential building, which seemed to be in fair condition as assessed through a cursory inspection of the exterior walls. A densely vegetated slope of about 25-30° is located within the south-eastern quadrant of the site, which is supported by a brick retaining wall of 0.5m to 2.0m height to the south and west.</p>
Site Area	The site area is approximately 1362m ² (based on the provided survey plan referenced above).



Plate 1: Aerial photograph of the site (source: Nearmap, accessed 24/10/2023)

2.2 Local Land Use

The site was situated within an area of commercial and residential use. Current uses on surrounding land at the time of our presence on site are described in **Table 2-2** below. For the sake of this report, the site boundary adjacent to Barrenjoey Road shall be adopted as the western site boundary.

Table 2-2 Summary of Local Land Use

Direction Relative to Site	Land Use Description
North	Property at No. 1120 Barrenjoey Road, a two-level residential building with concrete driveway. The main house has an offset of about 0.5m from the northern site boundary and appeared to be in fair condition. No. 1120 Barrenjoey Road is on a similar elevation to the site. No basements were observed at this property.
East	Properties at No. 21A and 23 Palm Beach Road, two separate two-to-three storey residential building with concrete driveway. The two properties are on a higher elevation to the site.
South	A bent concrete driveway of No. 1110, 1110A and 1110B Barrenjoey Road, abutting the western half of the southern site boundary. A moderately vegetated slope of about 25-30° connecting to the slope at the south-eastern quadrant of the site is retained by a rendered retaining wall of height from about 0.5m to 2.0m above the bent concrete driveway. No. 1110, 1110A and 1110B Barrenjoey Road is on a slightly higher slope elevation to the site. Large sandstone boulders were observed at this property. Beyond the driveway is property at No. 1108 Barrenjoey Road, a two-storey commercial building with brick paved driveway and concrete carpark. No basements were observed at this property.
West	Barrenjoey Road, a two-lane, asphalt paved road. Beyond this is an asphalt paved carpark.

2.3 Regional Setting

The site topography and geological information for the locality is summarised in **Table 2-3** below.

Table 2-3 Topographic and Geological Information

Attribute	Description
Topography	The site is located on the high east side of the road with steeply (18° to 25°) west dipping topography with site levels varying from R.L. 15.0m at the south-eastern site corner to R.L. 2.3m at the south-western site corner.
Regional Geology	Information on regional sub-surface conditions, referenced from the Department of Mineral Resources Geological Map Sydney 1:100,000 Geological Series Sheet 9130 (DMR 1983) indicates the site to be underlain by Newport Formation (Rnn) and Garie Formation, which consists of interbedded laminite, shale, and quartz, to lithic-quartz sandstone, and minor red claystone.




Plate 2: Excerpt of geological map showing location of site.

3. Investigation Results

3.1 Stratigraphy

For the development of a site-specific geotechnical model, the stratigraphy observed in the previous GI (2021) and the AGI has been grouped into five geotechnical units. A summary of the subsurface conditions across the site, interpreted from the assessment results, is presented in **Table 3-1** below. More detailed descriptions of subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**. The details of the methods of soil and rock classifications, explanatory notes and abbreviations adopted on the borehole logs are also presented in **Appendix A**.

Table 3-1 Summary of Subsurface Conditions

Unit	Material ²	Depth to Top of Unit (m BEGL) ¹	RL of Top of Unit (m AHD) ¹	Observed Thickness (m)	Comments
1	Fill/ Topsoil	Surface to 0.13	2.31 to 12.92	0.3 to 1.33	Concrete pavements of 130mm thickness observed in BH102 only. Low plasticity sandy clay fill/topsoil observed in BH101M and BH204M. Silty sand fill observed in BH102, BH103, BH104M and BH202M. Fill was assessed, based on our observations during drilling to be poorly to moderately compacted;
2a	Marine Soil	0 to 0.50	1.24 to 2.01	1.0 to 2.93	Fine to medium grained, loose sand/silty sand, becoming dense with depth. SPT N values range from 2 to 32;
2b	Residual Soil	1.5 to 3.0	-0.5 to 0.9	1.35 to 6.87	Encountered in BH102, BH201M and BH202M. Low to high plasticity sandy clay/ clayey sand, stiff/dense to hard with trace ironstone gravels. SPT values ranged from 25 to harmer bounce;
3	Very Low Strength Sandstone/ Laminite	0.47 to 6.4	-3.9 to 12.03	1.3 to 8.5	Distinctly weathered, very low strength sandstone and laminite comprising of sandstone, claystone and siltstone, with frequent extremely weathered seams. Extremely weathered sandstone with bands of medium strength ironstone observed in BH103 and BH104M. In BH204M, observed low strength sandstone with ironstaining, and very low strength claystone.
4	Low to Medium Strength Laminite	5.2 to 11.5	-10.3 to 7.3	- ³	Distinctly weathered, low to medium strength laminite comprising of siltstone and sandstone. Not observed in BH101M and BH102.

Note 1 Approximate depth and level at the time of our assessment. Depths and levels may vary across the site.

Note 2 For more detailed descriptions of the subsurface conditions, reference should be made to the borehole logs attached to **Appendix A**.

Note 3 Observed up to termination depth in BH201M, BH202M and BH204M.

A summary of the RL of the top of the stratigraphy units in each borehole is provided in **Table 3-2** below. Borehole cross sections are also presented at the end of this report in **Appendix B**.

Table 3-2 RLs of Top of Units in Boreholes (mAHD)

Unit	BH101M	BH102	BH103	BH104M	BH201M	BH202M	BH204M
1 - Fill	2.4	2.37	11.2	12.5	1.20	2.4	12.9
2a – Marine Soil	2.1	2.0	-	-	1.20	1.9	-
2b - Residual Soil	-	-0.5	-	-	-0.45	0.9	-
3 – Very Low Strength Sandstone/Laminite	-0.83	-3.9	10.2	12.03	-1.76	-0.82	11.78
4 – Low to Medium Strength Laminite	NE	NE	3.82	7.30	-10.26	-6.45	7.27

Note: Unit 4 was not encountered (NE) in BH101M and BH102, and is inferred to be present beneath the termination depth of these boreholes.

3.2 Groundwater Observations

3.2.1 Groundwater Levels

Groundwater seepage was observed during anger drilling in BH102, BH201M, BH202M, and BH203M between RL -0.5m to RL 0.7m AHD. Following the borehole completion, groundwater monitoring wells were installed in BH101M, BH104M, BH201M, BH202M, BH203M and BH204M.

Following the installation of all monitoring wells, groundwater level measurements were taken within these wells. The recorded groundwater levels are detailed in **Table 3-3** below.

Table 3-3 Summary of Ground Water Observation

Monitoring Well ID	Measurement Date	Depth to Groundwater (m BEGL)	Groundwater Level (RL m AHD)
BH101M	8 September 2023	1.15	1.16
BH104M	14 November 2023	8.79	3.71
BH201M	24 October 2023	1.06	0.18
BH202M	24 October 2023	1.58	0.82
BH203M	24 October 2023	0.79	1.71
BH204M	24 October 2023	5.63	7.27
	14 November 2023	5.20	7.70

A continuous groundwater monitoring data logger was installed for within BH101M. The long-term groundwater monitoring at BH101M during the period of 11 June 2021 to 8 September

2021 showed fairly consistent groundwater levels with minimal fluctuation between RL 1.38m to RL 1.08m.

Additional groundwater data loggers were installed within BH201M, BH202M, BH203M and BH204M during the period from 24 October 2023 to 22 February 2024 for long-term monitoring. Summary of groundwater levels are shown in **Table 3-4** below.

Table 3-4 Summary of Long-Term Groundwater Monitoring

Monitoring Well ID	Highest Groundwater RL (m AHD)	Lowest Groundwater RL (m AHD)
BH201M	0.78	0.12
BH202M	2.01	1.49
BH203M	1.88	1.52
BH204M	9.47	7.03

3.2.2 Rising Head Test

A Rising Head Test was completed on 24 October and 14 November 2023 in the monitoring well installed in BH104M, and BH201M to BH204M. The following procedure was adopted:

- The groundwater level within the well was initially recorded;
- The well was purged using a PVC bailer / an electrical groundwater pump;
- The rising groundwater level within the temporary well was measured at various time intervals for 1 hour.

The results were then used to estimate the permeability of the screened stratum the using the Hvorslev Method based on the borehole geometry. The estimated permeability was estimated for the following:

- Unit 2b Residual Soil is calculated to be approximately 2.5×10^{-6} m/s.
- Unit 3 and 4 laminite bedrock is calculated to be approximately 1.0×10^{-6} m/s.

3.3 Test Results

Two soil samples were selected for laboratory testing to assess the following:

- Soil aggressivity (pH, chloride and sulfate content and electrical conductivity).
- Atterberg Limits and Linear Shrinkage.

A summary of the soil test results is provided in **Table 3-5** below. Laboratory test certificates are presented in **Appendix C**.

Table 3-5 Summary of Soil Laboratory Test Results

Test/ Sample ID	BH101M _0.5-0.95	BH102_3 .0-3.45	BH201M _0.5-0.95	BH201M _1.65- 1.95	BH202M _1.5-1.95	BH202M _2.5-2.6	BH204M _0.2-0.3	BH204M _0.8-0.9	
Unit	2a	2b	2a	2b	2b	2b	1	1	
Material Description ¹	Silty SAND	Silty CLAY	SAND	Sandy CLAY	Clayey SAND	Clayey SAND	Silty CLAY	Silty CLAY	
Aggressivity	Chloride Cl (ppm)	18	110	22	-	-	26	-	5.8
	Sulfate SO ₄ (ppm)	22	63	40	-	-	29	-	31
	pH	5.7	4.8	8.7	-	-	5.3	-	5.2
	Electrical Conductivity (µS/cm)	27	130	92	-	-	38	-	22
Moisture Content (%)	9.2	34.3	13.1	14.9	16.4	15.1	26.8	21.6	
Atterberg Limits	Liquid Limit (%)	-	-	-	32	34	-	51	-
	Plastic Limit (%)	-	-	-	19	22	-	23	-
	Plasticity Index (%)	-	-	-	13	12	-	28	-
Linear Shrinkage (%)	-	-	-	7.0	6.0	-	12.0	-	

Note 1 More detailed descriptions of the subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**.

The assessment indicated high permeability soil was present above and below the groundwater table. In accordance with Tables 6.4.2(C) and 6.5.2(C) of AS 2159:2009 'Piling – Design and Installation', the results of the pH, chloride and sulfate content and electrical conductivity of the soil provided the following exposure classifications:

- 'Moderate' to 'Mild' for buried concrete structural elements; and
- 'Mild' to 'Non-Aggressive' for buried steel structural elements.

57 selected rock core samples were tested by STS to estimate the Point Load Strength Index (IS₅₀) values to assist with rock strength assessment. The results of the testing are summarised on the attached borehole logs.

The point load strength index tests correlated reasonably well with our field assessments of rock strength. The approximate Unconfined Compressive Strength (UCS) of the rock core, estimated from correlations with the point load strength index test results, varied from <1 MPa to 22.0 MPa.

4. Recommendations

4.1 Geotechnical Issues

Based on the results of the assessment, we consider the following to be the main geotechnical issues for the proposed development:

- Presence of loose sands;
- Basement excavation and retention to limit lateral deflections and ground loss as a result of excavations, resulting in damage to nearby structures;
- Highly variable subsurface conditions;
- Rock excavation;
- Slope stability and landslide Risk;
- Groundwater within the depth of the excavation;
- Existing footings of neighbouring properties; and
- Foundation design for building loads.

4.2 Dilapidation Surveys

Prior to excavation and construction, we recommend that detailed dilapidation surveys be carried out on all structures and infrastructures surrounding the site that falls within the zone of influence of the excavation to allow assessment of the recommended vibration limits and protect the client against spurious claims of damage. The zone of influence of the excavation is defined by a distance back from the excavation perimeter of twice the total depth of the excavation. The reports would provide a record of existing conditions prior to commencement of the work. A copy of each report should be provided to the adjoining property owner who should be asked to confirm that it represents a fair assessment of existing conditions. The reports should be carefully reviewed prior to demolition and construction.

4.3 Demolition Considerations

Care should be taken during demolition, particularly the concrete pavement, to avoid damaging neighbouring structures and infrastructures. Demolition of concrete slabs, pavement and floor slabs may require breaking into smaller size prior to disposal offsite. We recommend that saw cut slots be provided near adjoining buildings to reduce the risk of vibrations being transferred to nearby structures and infrastructures. If possible, the concrete slabs should be removed using hydraulic equipment rather than impact hammers.

4.4 Excavation Methodology

4.4.1 Excavation Assessment

Prior to any excavation commencing, we recommend that reference be made to the Safe Work Australia Excavation Work Code of Practice, dated January 2020.

To reach the Bulk Excavation Level (BEL) between RL -1.5m and -2.7m, the excavation depth will vary, ranging from 4.3 meters (towards the western side of the site) to 15.6 meters (towards the eastern side of the site) below the Existing Ground Level (BEGL).

Based on the borehole logs, the proposed basement excavations will therefore extend through Unit 1 to Unit 3 towards the portion below the slope to the west, and all Units towards east of the site as outlined in **Table 3-1** above. As such, an engineered retention system must be installed prior to excavation commencing.

Units 1, 2a and 2b could be excavated using buckets of conventional earthmoving Hydraulic Excavators, particularly if fitted with 'Tiger Teeth'. Excavation of Unit 3 to Unit 4 (where encountered) may present hard or heavy ripping, or "hard rock" excavation conditions. Ripping would require a high capacity and heavy bulldozer for effective production. Wear and tear should also be allowed for. The use of a smaller size bulldozer will result in lower productivity and higher wear and tear, and this should be allowed for. Alternatively, hydraulic rock breakers, rock saws, ripping hooks or rotary grinders could be used, though productivity would be lower and equipment wear increased, and this should be allowed for.

The primary issues associated with the excavation will be controlling the groundwater and provide adequate support to adjoining structures/infrastructures. Groundwater is expected to be encountered during excavation. Therefore, to allow for the construction of the basement slab, lift pits and service trenches in 'dry' condition, temporary dewatering will be required. In this regards, it is anticipated that the groundwater table will be maintained at a depth of about 1 m below the bulk excavation level and potentially deeper around lift pits or working platforms (if required).

Dewatering has the potential to cause some drawdown and ground settlement below the adjoining sites; the extent of the drawdown depends upon the depth to which the cut-off system is installed and the pumping operations. Outlets into the stormwater system will require Council approval.

Should rock hammers be used for the excavation of the bedrock, excavation should commence away from the adjoining structures and the transmitted vibrations monitored to assess how close the hammer can operate to the adjoining structures while maintaining transmitted vibrations within acceptable limits. To fall within these limits, we recommend that the size of rock hammers do not exceed a medium sized rock hammer, say 900 kg, such as a Krupp 580, and be trialled prior to use. The transmitted vibrations from rock hammers should be measured to determine how close each individual hammer can operate to the adjoining buildings.

The vibration measurements can be carried out using either an attended or an unattended vibration monitoring system. An unattended vibration monitoring system must be fitted with an alarm in the form of a strobe light or siren or alerts sent directly to the site supervisor to make the plant operator aware immediately when the vibration limit is exceeded. The vibration monitor must be set to trigger the alarm when the overall Peak Particle Velocity (PPV) exceeds set limits outlined by a vibration monitoring plan. Reference should be made to **Appendix C** for a guide to acceptable limits of transmitted vibrations.

If it is found that the transmitted vibrations by the use of rock hammers are unacceptable, then it would be necessary to change to a smaller excavator with a smaller rock hammer, or to a rotary grinder, rock saws, jackhammers, ripping hooks, chemical rock splitting and milling machines. Although these are likely to be less productive, they would reduce or possibly eliminate risks of damage to adjoining properties through vibration effects transmitted via the ground. Such equipment would also be required for detailed excavation, such as footings or service trenches, and for trimming of faces. Final trimming of faces may also be completed using a grinder attachment rather than a rock breaker in order to assist in limiting vibrations. The use of rotary grinders generally generates dust and this may be suppressed by spraying with water.

To assist in reducing vibrations and over-break of the sandstone, we recommend that initial saw cutting of the excavation perimeters through the bedrock may be provided using rock saw attachments fitted to the excavator. Rock sawing of the excavation perimeter has several

advantages as it often reduces the need for rock bolting as the cut faces generally remain more stable and require a lower level of rock support than hammer cut excavations, ground vibrations from rock saws are minimal and the saw cuts will provide a slight increase in buffer distance for use of rock hammers. However, the effectiveness of such approach must be confirmed by the results of vibration monitoring.

Groundwater seepage monitoring should be carried out during bulk excavation works and prior to finalising the design of a pump out facility. Outlets into the stormwater system will require Council approval.

Furthermore, any existing buried services, which run below the site, will require diversion prior to the commencement of excavation or alternatively be temporarily supported during excavation, subject to permission or other instructions from the relevant service authorities. Enquiries should also be made for further information and details, such as invert levels, on the buried services.

4.4.2 Excavation Monitoring

Consideration should be made to the impact of the proposed development upon neighbouring structures, roadways and services. Basement excavation retention systems should be designed so as to limit lateral deflections.

Contractors should also consider the following limits associated with carrying out excavation and construction activities:

- Limit lateral deflection of temporary or permanent retaining structures;
- Limit vertical settlements of ground surface at common property boundaries and services easement; and
- Limit Peak Particle Velocities (PPV) from vibrations, caused by construction equipment or excavation, experienced by any nearby structures and services.

Monitoring of deflections of retaining structures and surface settlements should be carried out by a registered surveyor at agreed points along the excavation boundaries and along existing building foundations / services / pavements and other structures located within or near the zone of influence of the excavation. Owners of existing services adjacent to the site should be consulted to assess appropriate deflection limits for their infrastructures. Measurements should be taken in the following sequence:

- Before commencing installation of retaining structures where appropriate to determine the baseline readings. Two independent sets of measurements must be taken confirming measurement consistency;
- After installation of the retaining structures, but before commencement of excavation;
- After excavation to a depth of 1.5m;
- After excavation to the base of the excavation;
- After de-stressing and removal of any rows of supports; and
- One month after completion of the permanent retaining structure or after three consecutive measurements not less than a week apart showing no further movements, whichever is the latter.

4.5 Groundwater Considerations

Groundwater was observed in all monitoring wells as detailed in **Table 3-2**, all of which are above the assumed lowest BEL RL of -2.7m. Groundwater within the western half of the site was within the marine soil profile (Unit 2a) whereas the groundwater levels measured within the eastern half of the site was within the bedrock profile.

The volume of groundwater entering the basement excavation (which will require dewatering) decreases as the depth of embedment of the perimeter shoring system increases. The designer must consider an appropriate length of retention system which should provide an appropriate groundwater cut off.

Council and WaterNSW may not allow permanent dewatering; therefore, the basement must be designed as a tanked structure. EI is of the opinion that during basement excavation, a partially drained structure on the eastern half of the site is feasible with sound engineering design. For the operational phase of the building, a water tight wall should be constructed along the eastern boundary for a tanked basement design.

The seal into bedrock provided by the secant piling should permit use of a conventional sump and pump system for the western half of the site during construction. Due to the low permeability of the bedrock profile, any groundwater inflows into the excavation from the slope at the rear east of the site should also be able to be handled by a sump and pump system

Temporary dewatering for construction purposes is normally allowed provided it is properly designed and managed to ensure that the likely drawdown will have no adverse impact on adjoining structures/infrastructures. A dewatering licence may also be required. Groundwater quality testing will be required to permit discharge into the stormwater system.

Dewatering has the potential to cause drawdown and ground settlement below adjoining sites; the extent of the drawdown depends upon the depth to which the cut-off system is installed and the pumping operations. Settlements may affect adjoining buildings supported on shallow footing systems and if records of the footing systems of the adjoining buildings are available, these should be reviewed to assess the risk from dewatering.

A critical factor relating to dewatering of the site is the maintenance of the depressed groundwater levels until the building has significant weight to prevent movement should the pump system fail and the groundwater level rise.

A detailed monitoring program should be implemented to identify the risks and trigger levels decided for when the contingency measures need to be taken.

4.5.1 Seepage Analysis

In the GTA completed by EI, a three-dimensional finite element groundwater seepage model was used to complete seepage analysis for this site based on the groundwater level data and subsurface material permeability mentioned in **Sections 3.2.1** and **3.2.2** above. The adopted shoring system is comprised of secant pile walls on the northern, southern and western elevations founded at least 3.0m below BEL, with a freely draining soldier pile wall to the east. A water tight wall will be constructed for the eastern wall during basement construction to create a tanked basement. Summary of the groundwater take below:

- Construction phase: 0.49ML from the initial pore water dewatering, plus 2.61 ML/year during bulk excavation, or 3.1ML in the first year.
- Operational phase: Zero.

The expected drawdown settlement as a result of groundwater lowering is estimated to be negligible at the western site boundary, and about 3.9mm at the eastern site boundary.

Reference should be made to EI's GTA report for the details of the seepage analysis.

4.6 Excavation Retention

4.6.1 Support Systems

From a geotechnical perspective, it is critical to maintain the stability of all adjacent structures and infrastructures during demolition, excavation and construction works.

Based on the provided architectural plans, the proposed basement outline abuts the western site boundary and has a minimum setback of approximately 3.0m from the northern, eastern and southern boundaries. Based on the depth of the excavation, the encountered subsurface conditions, groundwater table, and limited setbacks, temporary batters are not recommended for this site. Unsupported vertical cuts of the soil are not recommended for this site as these carry the risk of potential slumping/collapse especially after a period of wet weather. Slumping/Collapse of the material may result in injury to personnel and/or damage to nearby structures/infrastructures and equipment.

A suitable retention system will be required for the support of the entire depth of the excavation. Where temporary anchors cannot be installed, internal props should be used. For this site, we recommend the following:

- An internally propped soldier pile wall with shotcrete in between the piles installed to below BEL and into Unit 3 or better along the eastern elevation is feasible where the groundwater is within the bedrock profile.; and
- A secant pile along the western, southern and eastern portion of the site where the groundwater is shallow and within a sandy profile (Unit 2a). The piles should be installed below BEL and into Unit 3 or better to form an adequate cut-off.
 - Alternate piles are first drilled and concreted at a close spacing. The intermediate piles are then installed by drilling out the soil between each pair and part of the already installed piles. Should the second 'hard' piles disengage from the first 'soft' piles, then remedial works would be required to rectify any seepage inflows. Any gaps between the piles as a result of installation misalignment may lead to loss of material and water inflow from behind the wall which may result in settlements adjacent to the wall and damage to neighbouring structures and services. The resulting out of position piles may also affect internal layout/clearances. Shotcrete panels must be installed progressively as excavation proceeds.

Only grout injected CFA piles should be used for this site for the piles within the sandy profile to the west. Due to the collapsible nature of the sandy soils and the presence of groundwater, bored piers are not recommended in this western area. Bored piles may be feasible along the eastern elevation. The proposed pile locations should take into account the presence of buried services and structures. Further advice should be sought from prospective piling contractors who should be provided with a copy of this report.

The retention system will need to be installed to depths which satisfy stability, piping, founding and groundwater cut-off considerations. Internal props and shotcrete must be installed progressively as excavation proceeds.

If a fully tanked basement is adopted, a water-tight wall needs to be constructed in front of the eastern soldier pile wall to sufficient height.

Working platforms may also be required. We can complete the design of the working platform, if commissioned to do so.

4.6.2 Excavation adjacent to TfNSW Assets

Reference should be made to the TfNSW Geotechnical Technical Direction (GTD) 2020/001 dated 2 July 2020, with regards to excavation/shoring adjacent to Barrenjoey Road. This document outlines requirements for excavations adjacent to TfNSW infrastructure and includes the level of geotechnical investigation required, dilapidation surveying, instrumentation and monitoring during construction, trigger levels and contingency plans.

Instrumentation (e.g. inclinometers) and monitoring is typically required where the excavation exceeds 3 m in height (for cantilevered shoring walls) or 6 m in height (for anchored or propped shoring walls). A geotechnical monitoring plan may be required by TfNSW prior to construction for this site.

As the site of the proposed development lies adjacent to both TfNSW assets, the asset owner may require further assessment of the potential impact of the proposed development on their assets. In order to assess the latter, a 2D numerical model using a commercially available computer program, such as PLAXIS, will be required. This model will enable the assessment of the potential impact of the proposed development on the TfNSW assets and predict the likely movements in the shoring wall. EI can provide such a service if commissioned to do so.

4.6.3 Retaining Wall Design Parameters

The following parameters may be used for static design of temporary and permanent retaining walls at the subject site. EI note that the below parameters, particularly with determining lateral earth pressures, are for preliminary planning purposes. We recommend that detailed analysis such as the use of finite element analysis software be used to design retaining walls.

- Conventional free-standing cantilever walls which support areas where movement is of little concern (i.e. where only gardens or open areas are to be retained), may be designed using a triangular lateral earth pressure distribution and an 'active' earth pressure coefficient, K_a , as shown in **Table 4-1**;
- Cantilevered walls, where the tops of which are restrained by the floor slabs of the permanent structure or which support movement sensitive elements, should be designed using a triangular lateral earth pressure distribution and an 'at rest' earth pressure coefficient, K_0 , as shown in **Table 4-1** below;
- For progressively anchored or propped walls where minor movements can be tolerated (provided there are no buried movement sensitive services), we recommend the use of a trapezoidal earth pressure distribution of $5H$ kPa for soil, where H is the retained height in meters. These pressures should be assumed to be uniform over the central 50% of the support system, tapering to nil at top and bottom;
- For progressively anchored or propped walls which support areas which are highly sensitive to movement (such as areas where movement sensitive structures or infrastructures or buried services are located in close proximity), we recommend the use of a trapezoidal earth pressure distribution of $8H$ kPa for soil, where ' H ' is the retained height in meters. These pressures should be assumed to be uniform over the central 50% of the support system, tapering to nil at top and bottom;
- All surcharge loading affecting the walls (including from construction equipment, construction loads, adjacent high level footings, etc.) should be adopted in the retaining wall design as an additional surcharge using an 'at rest' earth pressure coefficient, K_0 ;

- Full hydrostatic pressures should be taken into consideration in the design of the retaining walls, considering the highest groundwater level measured from long-term groundwater monitoring. The hydrostatic pressure should extend to the base of the perimeter cut-off.
- For piles embedded into Unit 3 or better, the allowable lateral toe resistance values outlined in **Table 4-1** below may be adopted. These values assume excavation is not carried out within the zone of influence of the wall toe and the rock does not contain adverse defects etc. The upper 0.3m depth of the socket should not be taken into account to allow for tolerance and disturbance effects during excavation.

Table 4-1 Geotechnical Design Parameters

Material ¹		Unit 1 Fill/Topsoil	Unit 2a Marine Soil	Unit 2b Residual Soil	Unit 3 Very Low Strength Sandstone/ Laminite	Unit 4 Low to Medium Strength Laminite
RL of Top of Unit (m AHD) ²		2.31 to 12.93	1.24 to 2.01	-0.5 to 0.9	-3.9 to 11.8	-10.26 to 9.7
Bulk Unit Weight (kN/m ³)		17	17	17	24	24
Friction Angle, ϕ' (°)		25	30	25	35	40
Earth Pressure Coefficient s	At rest, K_o ³	0.58	0.50	0.58	-	-
	Active, K_a ³	0.41	0.33	0.41	-	-
	Passive, K_p ³	-	3.00	2.46	-	-
Allowable Bearing Pressure (kPa) ₅		-	-	-	700	1000
Allowable Shaft Adhesion (kPa) ^{4,5}	in Compression	-	-	-	70	100
	in Uplift	-	-	-	35	50
Allowable Toe Resistance (kPa)		-	-	-	300	500
Allowable Bond Stress (kPa)		-	-	-	-	50
Earthquake Site Risk Classification		<ul style="list-style-type: none"> ▪ AS 1170.4:2007 indicates an earthquake subsoil class of Class C_e (Shallow Soil) ▪ AS 1170.4:2007 indicates that the hazard factor (z) for Sydney is 0.08. 				

Notes:

- More detailed descriptions of subsurface conditions are available on the borehole logs presented in **Appendix A**.
- Approximate levels of top of unit at the time of our investigation. Levels may vary across the site.
- Earth pressures are provided on the assumption that the ground behind the retaining walls is horizontal.
- Side adhesion values given assume there is intimate contact between the pile and foundation material and should achieve a clean socket roughness category R2 or better. Design engineer to check both 'piston pull-out' and 'cone liftout' mechanics in accordance with AS4678-2002 Earth Retaining Structures.
- To adopt these parameters we have assumed that:
 - Footings have a nominal socket of at least 0.3m, into the relevant founding material;
 - For piles, there is intimate contact between the pile and foundation material (a clean socket roughness category of R2 or better);
 - Potential soil and groundwater aggressivity will be considered in the design of piles and footings;
 - Piles should be drilled in the presence of a Geotechnical Engineer prior to pile construction to verify that ground conditions meet design assumptions. Where groundwater ingress is encountered during pile excavation, concrete is to be placed as soon as possible upon completion of pile excavation. Pile excavations should be pumped dry of water prior to pouring concrete, or alternatively a tremmie system could be used;
 - The bases of all pile, pad and strip footing excavations are cleaned of loose and softened material and water is pumped out prior to placement of concrete;
 - The concrete is poured on the same day as drilling, inspection and cleaning.
 - The allowable bearing pressures given above are based on serviceability criteria of settlements at the footing base/pile toe of less than or equal to 1% of the minimum footing dimension (or pile diameter).

4.7 Slope Stability and Landslide Risk

4.7.1 Geotechnical Hazard Risk Zone

With reference to Pittwater Council's LEP 2014 Geotechnical Risk Management Map (GTH_015), the site is classified as being within the H1 (highest category) landslip hazard zone therefore the site requires a Geotechnical Landslide Risk Assessment to be conducted. An excerpt of the geotechnical hazard map is shown below in **Plate 3**:




Plate 3: Site location over geotechnical hazard map (Pittwater LEP 2014)

EI has prepared a Landslide Risk Assessment (LRA) report for this site (referenced E25203.G14, dated 8 August 2024), which assessment summary is presented below.

4.7.1 Risk Assessment

EI's LRA report, which prepared for the purposes of a DA submission to Northern Beaches Council, and in accordance with requirements of NBC's Pittwater Geotechnical Risk Management Policy, concludes that:

- The proposed site development can be undertaken, and
- The proposed works can achieve an **Acceptable Risk Level** in accordance with recommendations of AGS 2007, provided that all the recommendations of the report are properly implemented during and following development.

Engineering controls are recommended to ensure **Acceptable Risk Levels** can be achieved. These controls are to be embraced in the detailed design and construction phases of the development, and are to be reviewed for geotechnical purposes prior to commencement of construction, as discussed in the report.

Reference should be made to EI's LRA report for detailed risk assessment, and the recommendations for guidance on various design components, in regard to geotechnical requirements.

4.8 Foundations

The most competent foundation stratum at the site is the medium strength sandstone and in view of the moderate depths to the bedrock, we recommend that building is supported on shallow or pile footings (depending on the footprint of proposed basement and subsurface conditions) founded into weathered bedrock. However, the option of high level footings founded in the residual clay is also provided.

4.8.1 Shallow Footings in Rock

Following basement excavation to RL -1.5m to -2.7m, we expect Unit 3 and 4 materials to be exposed at BEL across the majority of the site. Some areas may still expose marine or residual soil, with bedrock at a shallow depth below.

It is recommended that all footings for the building be founded within the sandstone bedrock of similar strength of at least Unit 3 or better to provide uniform support and reduce the potential for differential settlements.

Pad or strip footings founded within Unit 3 and 4 may be preliminarily designed for an allowable bearing capacity of 700kPa and 1000kPa, respectively, based on serviceability.

Geotechnical inspections of foundations are recommended to determine that the required bearing capacity has been achieved and to determine any variations that may occur between the boreholes and inspected locations.

4.8.2 Pile Footings

Alternatively, the proposed development may be supported on deep foundations, such as piles, founded into sandstone bedrock.

For piles founded into weathered sandstone bedrock, these must be embedded a minimum of 0.5m into sandstone, and can be designed for a maximum allowable bearing pressure of 700kPa in Unit 3, 1000kPa in Unit 4. The allowable shaft adhesion in sandstone bedrock may be designed as 10% of the allowable bearing pressure (or 5% for uplift) for the socket length in excess of 0.5m.

At least the initial drilling of piles should be completed in the presence of a geotechnical engineer to verify that ground conditions meet design assumptions.

Where groundwater ingress is encountered during pile excavation, concrete is to be placed as soon as possible upon completion of pile excavation. Pile excavations should be pumped dry of water prior to pouring concrete, or alternatively a tremmie system could be used. Concrete must be poured on the same day as drilling, inspection and drilling.

The aggressivity of natural soils and groundwater (if encountered) should be taken into consideration in the design.

4.9 Basement Floor Slab

Following bulk excavations for the proposed basement, Unit 3 or 4 bedrock is expected to be exposed at the basement floor BEL, with some areas possibly exposing soil at the western end of the site. The basement floor slab should be designed fully tanked and the design is likely to be controlled by the hydrostatic uplift pressures.

5. Further Geotechnical Inputs

Below is a summary of the previously recommended additional work that needs to be carried out:

- Design of working platforms (if required) for construction plant by an experienced and qualified geotechnical engineer;
- Classification of all excavated material transported off site;
- Witnessing installation of support measures (if required);
- Geotechnical inspections of all new footings/piles by an experienced geotechnical professional before concrete or steel are placed to verify their bearing capacity and the in-situ nature of the founding strata; and
- Ongoing monitoring of groundwater inflows into the bulk excavation.

We recommend that a meeting be held after initial structural design has been completed to confirm that our recommendations have been correctly interpreted. We also recommend a meeting at the commencement of construction to discuss the primary geotechnical issues and inspection requirements.

6. Statement of Limitations

This report has been prepared for the exclusive use of William Allen and Palmdev Pty Ltd who is the only intended beneficiary of EI's work. The scope of the assessment carried out for the purpose of this report is limited to those agreed with William Allen and Palmdev Pty Ltd

No other party should rely on the document without the prior written consent of EI, and EI undertakes no duty, or accepts any responsibility or liability, to any third party who purports to rely upon this document without EI's approval.

EI has used a degree of care and skill ordinarily exercised in similar investigations by reputable members of the geotechnical industry in Australia as at the date of this document. No other warranty, expressed or implied, is made or intended. Each section of this report must be read in conjunction with the whole of this report, including its appendices and attachments.

The conclusions presented in this report are based on a limited investigation of conditions, with specific sampling and test locations chosen to be as representative as possible under the given circumstances.

EI's professional opinions are reasonable and based on its professional judgment, experience, training and results from analytical data. EI may also have relied upon information provided by the Client and other third parties to prepare this document, some of which may not have been verified by EI.

EI's professional opinions contained in this document are subject to modification if additional information is obtained through further investigation, observations, or validation testing and analysis during construction. In some cases, further testing and analysis may be required, which may result in a further report with different conclusions.

We draw your attention to the document "Important Information", which is included in **Appendix E** of this report. The statements presented in this document are intended to advise you of what your realistic expectations of this report should be. The document is not intended to reduce the level of responsibility accepted by EI, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in so doing.

Should you have any queries regarding this report, please do not hesitate to contact EI.

References

- AS1289.6.3.1:2004, *Methods of Testing Soils for Engineering Purposes*, Standards Australia.
- AS1726:2017, *Geotechnical Site Investigations*, Standards Australia.
- AS2159:2009, *Piling – Design and Installation*, Standards Australia.
- AS3600:2009, *Concrete Structures*, Standards Australia
- Safe Work Australia Excavation Work Code of Practice, dated January 2020 – WorkCover NSW
- NSW Department of Finance and Service, Spatial Information Viewer, maps.six.nsw.gov.au.
- NSW Department of Mineral Resources (1983) Sydney 1:100,000 Geological Series Sheet 9130 (Edition 1). Geological Survey of New South Wales, Department of Mineral Resources.


Abbreviations

AHD	Australian Height Datum
AS	Australian Standard
BEL	Bulk Excavation Level
B EGL	Below Existing Ground Level
BH	Borehole
DBYD	Dial Before You Dig
DP	Deposited Plan
EI	EI Australia
GI	Geotechnical Investigation
NATA	National Association of Testing Authorities, Australia
RL	Reduced Level
SPT	Standard Penetration Test
T-C	Tungsten-Carbide
UCS	Unconfined Compressive Strength


Figures

Figure 1 Site Locality Plan

Figure 2 Borehole Location Plan



Drawn:	J.O.
Approved:	S.K.
Date:	21-11-23
Scale:	Not To Scale



Map Source: Site Survey Plan prepared by Beveridge Williams - Project No. 2101343, Drawing Ref. 2101343, Sheet 1 of 5, Version B, dated 6 September 2021

LEGEND (Note: All locations are approximate)

- - - Site boundary
- - - Proposed basement boundary
- ⊕ Location of Borehole (EI Australia, Geotechnical Investigation 2021)
- ⊖ Location of Monitoring Well (EI Australia, Geotechnical Investigation 2021)
- ⊕ Location of Borehole and Monitoring Well (EI Australia, Additional Geotechnical Investigation 2023)
- ⊖ Location of Monitoring Well Only (EI Australia, Additional Geotechnical Investigation 2023)

Suite 6.01, 55 Miller Street, PYRMONT 2009
Ph (02) 9516 0722 Fax (02) 9518 5088

Drawn:	J.O.
Approved:	S.K.
Date:	11-7-24

Palmdev Pty Ltd
 Additional Geotechnical Investigation
 1112-1116 Barrenjoey Road, Palm Beach NSW
 Borehole Location Plan

Figure:	2
Project:	E25203.G04

Appendix A – Borehole Logs And Explanatory
Notes



BOREHOLE LOG

BH ID: BH101M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 1 of 2

Started 11 June 2021
Completed 11 June 2021
Logged By KX **Date** 11 June 2021
Review By SR **Date** 14 July 2021

Drilling Contractor BG Drilling **Surface RL** ≈2.31 m (AHD) **Northing** 6281290.4050 (MGA 2020 Zone 56)
Plant Christie CE180 **Inclination** 90° **Easting** 344162.6980 (MGA 2020 Zone 56)

METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY / REL. DENSITY	MATERIAL ORIGIN & OBSERVATIONS
AD/T	18/09/2023 12:00 AM GWNE	BH101M_0.50-0.95 SPT 0.50-0.95 3,2,3 N=5	█	0.00	[Pattern]	2.31	FILL: Sandy CLAY: low plasticity, dark brown.	M < PL	-	FILL
				0.30	[Pattern]	2.01	Silty SAND: fine grained, brown.		L	RESIDUAL SOIL
		BH101M_1.50-1.95 SPT 1.50-1.95 6,13,19 N=32	█	1.50	[Pattern]	0.81	From 1.50m, pale grey	M		
		BH101M_3.00-3.28 SPT 3.00-3.28 10,18/130 mm HB N=R	█	3.23	[Pattern]	-0.92			D	
				4						
				5						
				6						
				7						
				8						
				9						
				10						

Log continued on next page.



BOREHOLE CORE LOG

BH ID: BH101M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 2 of 2

Started 11 June 2021
Completed 11 June 2021
Logged By KX **Date** 11 June 2021
Review By SR **Date** 14 July 2021

Drilling Contractor BG Drilling **Surface RL** ≈2.31 m (AHD) **Northing** 6281290.4050 (MGA 2020 Zone 56)
Plant Christie CE180 **Inclination** 90° **Easting** 344162.6980 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50)						DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING							
									VL ₀₋₁	L ₀₋₃	M ₁	H ₃	VH ₁₀	EH		30	100	300	1000	3000			
				0			Log continued from previous page.																
		100	93	4			LAMINITE: SANDSTONE(80%) and CLAYSTONE(20%); sandstone is fine grained, pale grey/grey/orange/red. Thinly bedded.								4.73: JT 50-60° PR RO CN								
		100	60	5											5.54-5.61: XWS								
				5.82			From 5.82m, grey/pale grey																
				6				DW							6.27-6.29: XWS 6.43-6.46: XWS 6.54-6.60: XWS								
		100	81	8											8.27-8.29: XWS								
				6.49			Terminated at 8.80m. Target Depth Reached.																
				9																			
				10																			

This log should be read in conjunction with EI Australia's accompanying explanatory notes.




MONITORING WELL LOG

BH ID: BH101M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 1 of 1

Started 11 June 2021
Completed 11 June 2021
Logged By KX **Date** 11 June 2021
Review By SR **Date** 14 July 2021

Drilling Contractor BG Drilling **Surface RL** ≈2.31 m (AHD) **Northing** 6281290.4050 (MGA 2020 Zone 56)
Plant Christie CE180 **Inclination** 90° **Easting** 344162.6980 (MGA 2020 Zone 56)



This log should be read in conjunction with EI Australia's accompanying explanatory notes.

Project	Proposed Development	Depth Range	3.23m to 8.80m BEGL	
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	BG Drilling	
Position	Refer to Figure 2	Drill Rig	Christie CE180	
Job No.	E25203.G04	Logged	KX	Date 11 / 06 / 2021
Client	Palmdev Pty Ltd	Surface RL	≈ 2.31 m	
		Inclination	-90°	
		Box	1-2 of 2	
		Checked	SR	Date 14 / 07 / 2021







BOREHOLE LOG

BH ID: BH103

Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Started	27 October 2021
Client	Palmdev Pty Ltd	Completed	27 October 2021
Job No.	E25203.G04	Logged By	KX Date 27 October 2021
Sheets	1 of 3	Review By	SR Date 14 December 2021

Drilling Contractor	Tightsite Geotechnical & Environmental Drilling	Surface RL	≈12.00 m (AHD)	Northing	6281299.1780 (MGA 2020 Zone 56)
Plant	Tight-Access Rig	Inclination	90°	Easting	344186.0210 (MGA 2020 Zone 56)

METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY / REL. DENSITY	MATERIAL ORIGIN & OBSERVATIONS
HA	GWNE	BH103_0.25-0.35		0.00		12.00	FILL: Silty SAND: fine grained, brown, trace rootlets, medium to coarse, angular to sub-angular gravels	D	-	FILL
WB				1.00		11.00	<i>Log continued on next page.</i>			
				1.00						
				2.00						
				3.00						
				4.00						
				5.00						
				6.00						
				7.00						
				8.00						
				9.00						
				10.00						

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH103

Location 1112-1116 Barrenjoey Road, Palm Beach NSW **Started** 27 October 2021
Client Palmdev Pty Ltd **Completed** 27 October 2021
Job No. E25203.G04 **Logged By** KX **Date** 27 October 2021
Sheets 2 of 3 **Review By** SR **Date** 14 December 2021

Drilling Contractor Tightsite Geotechnical & Environmental Drilling **Surface RL** ≈12.00 m (AHD) **Northing** 6281299.1780 (MGA 2020 Zone 56)
Plant Tight-Access Rig **Inclination** 90° **Easting** 344186.0210 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50)						DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING										
									VL ₀₋₁	L ₀₋₃	M ₁	H ₃	VH ₁₀	EH		30	100	300	1000	3000						
							Log continued from previous page.																			
NMLC	90-80%	100	59	0		4.84	LAMINITE: SANDSTONG(30%) and CLAYSTONE(70%); sandstone is fine grained, dark red/orange brown/pale brown/pale grey. Thinly bedded, with ironstone layers.	XW																		
		100	15	1			2.55-2.58: XWS 2.70-2.80: XWZ 2.85: JT 70° UN RO CN 3.12: JT 70-80° UN RO CN																			
		100	35	2			3.67: JT 60-70° PR RO CN																			
		100	34	3			4.05-4.33: SZ																			
		100	37	4			4.70-4.86: XWZ 4.95-5.11: XWZ																			
		100	16	5			5.20-5.27: XWS 5.32-5.36: XWS 5.56-5.62: XWS 5.76-5.79: XWS																			
		100	46	6			6.00-6.40: XWZ																			
		100	16	7			6.67-6.77: XWZ																			
		100	16	8			7.08-7.12: XWS																			
		100	16	9			7.82: JT 40-50° PR RO CN																			
100	16	10	9.64-9.68: XWS 9.90-10.08: CS																							

This log should be read in conjunction with EI Australia's accompanying explanatory notes.

Project	Proposed Development	Depth Range	1.00m to 9.00m BEGL	
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	TightSite	
Position	Refer to Figure 2	Drill Rig	Hand Portable	
Job No.	E25203.G04	Logged	KX	Date 27 / 10 / 2021
Client	Palmdev Pty Ltd	Surface RL	≈ 12.0 m	
		Inclination	-90°	
		Box	1-2 of 3	
		Checked	SR	Date 14 / 07 / 2021



Project	Proposed Development	Depth Range	9.00m to 13.00m BEGL	
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	TightSite	
Position	Refer to Figure 2	Drill Rig	Hand Portable	
Job No.	E25203.G04	Logged	KX	Date 27 / 10 / 2021
Client	Palmdev Pty Ltd	Surface RL	≈ 12.0 m	
		Inclination	-90°	
		Box	3 of 3	
		Checked	SR	Date 14 / 07 / 2021





BOREHOLE LOG

BH ID: BH104M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW	Started 27 October 2021
Client Palmdev Pty Ltd	Completed 27 October 2021
Job No. E25203.G04	Logged By KX Date 27 October 2021
Sheets 1 of 3	Review By SR Date 14 December 2021

Drilling Contractor Tightsite Geotechnical & Environmental Drilling	Surface RL ≈12.00 m (AHD)	Northing 6281281.7610 (MGA 2020 Zone 56)
Plant Tight-Access Rig	Inclination 90°	Easting 344181.6980 (MGA 2020 Zone 56)

METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY / REL. DENSITY	MATERIAL ORIGIN & OBSERVATIONS
HA	GWNE	BH104M_0.20-0.30		0.00		12.00	FILL: Silty SAND: fine grained, brown, trace rootlets, medium to coarse, angular to sub-angular gravels	D	-	FILL
				0.47		11.53	<i>Log continued on next page.</i>			
				1						
				2						
				3						
				4						
				5						
				6						
				7						
				8						
				9						
				10						

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH104M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 2 of 3
Started 27 October 2021
Completed 27 October 2021
Logged By KX **Date** 27 October 2021
Review By SR **Date** 14 December 2021

Drilling Contractor Tightsite Geotechnical & Environmental Drilling
Plant Tight-Access Rig
Surface RL ≈12.00 m (AHD)
Inclination 90°
Northing 6281281.7610 (MGA 2020 Zone 56)
Easting 344181.6980 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50)						DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING										
									VL ₀₋₁	L ₀₋₃	M ₁	H ₃	VH ₁₀	EH		30	100	300	1000	3000						
NMLC	90-80%	100	64	0		7.35	Log continued from previous page.																			
				LAMINITE: SANDSTONE(10%) and CLAYSTONE(90%); sandstone is fine grained, red brown/pale brown/pale grey. Thinly bedded.																						
		100	85	2																						
				LAMINITE: SANDSTONE(30%) and SHALE(70%); sandstone is fine grained, grey and brown, with pale grey lamination, thinly bedded.																						
		100	37	3							XW															
		100	57	4																						
		100	70	4.65																						
100	67	5						DW																		
				6																						
				7																						
				8																						
				9																						
				10																						

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH104M

Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Started	27 October 2021
Client	Palmdev Pty Ltd	Completed	27 October 2021
Job No.	E25203.G04	Logged By	KX Date 27 October 2021
Sheets	3 of 3	Review By	SR Date 14 December 2021

Drilling Contractor	Tightsite Geotechnical & Environmental Drilling	Surface RL	≈12.00 m (AHD)	Northing	6281281.7610 (MGA 2020 Zone 56)
Plant	Tight-Access Rig	Inclination	90°	Easting	344181.6980 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50)	DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING				
											30	100	300	1000	3000
	90-80%	100	80	11	[Graphic Log Pattern]		LAMINITE: SANDSTONE(30%) and SHALE(70%); sandstone is fine grained, grey and brown, with pale grey lamination, thinly bedded.			10.43: JT 45° UN RO CN					
		100	23	12	[Graphic Log Pattern]										
				12.57			Terminated at 12.57m. Target Depth Reached.								
				13											
				14											
				15											
				16											
				17											
				18											
				19											
				20											

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



MONITORING WELL LOG

BH ID: BH104M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 1 of 2

Started 27 October 2021
Completed 27 October 2021
Logged By KX **Date** 27 October 2021
Review By SR **Date** 14 December 2021

Drilling Contractor Tightsite Geotechnical & Environmental Drilling **Surface RL** ≈12.00 m (AHD) **Northing** 6281281.7610 (MGA 2020 Zone 56)
Plant Tight-Access Rig **Inclination** 90° **Easting** 344181.6980 (MGA 2020 Zone 56)

WATER	SAMPLES & FIELD TESTS	DEPTH (m)	GRAPHIC LOG	RL (m AHD)	MATERIAL DESCRIPTION	MOISTURE CONDITION	BACKFILL DETAILS	STANDPIPE DETAILS
GWNE	BH104M_0.20-0.30	0.00		12.00	FILL: Silty SAND: fine grained, brown, trace rootlets, medium to coarse, angular to sub-angular gravels	D		Well Stickup =0.0m (RL 12.0m)
		0.47		11.53	LAMINITE: SANDSTONE(10%) and CLAYSTONE (90%); sandstone is fine grained, red brown/pale brown/pale grey. Thinly bedded.			
90-80%		1						
		4.65		7.35	LAMINITE: SANDSTONE(30%) and SHALE(70%); sandstone is fine grained, grey and brown, with pale grey lamination, thinly bedded.			
		5					Grout 0.00m - 7.50m	
		7					Bentonite 7.00m - 7.50m	0.0m - 8.0m PVC casing (50mm Ø)
		8						8.0m - 11.0m PVC screen (50mm Ø)

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



MONITORING WELL LOG

BH ID: BH104M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW	Started 27 October 2021
Client Palmdev Pty Ltd	Completed 27 October 2021
Job No. E25203.G04	Logged By KX Date 27 October 2021
Sheets 2 of 2	Review By SR Date 14 December 2021

Drilling Contractor Tightsite Geotechnical & Environmental Drilling	Surface RL ≈12.00 m (AHD)	Northing 6281281.7610 (MGA 2020 Zone 56)
Plant Tight-Access Rig	Inclination 90°	Easting 344181.6980 (MGA 2020 Zone 56)

WATER	SAMPLES & FIELD TESTS	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	MOISTURE CONDITION	BACKFILL DETAILS		STANDPIPE DETAILS
90-80%		11			LAMINITE: SANDSTONE(30%) and SHALE(70%); sandstone is fine grained, grey and brown, with pale grey lamination, thinly bedded.		Sand 7.50m - 12.57m		
		12		-0.57	Terminated at 12.57m. Target Depth Reached.				
		13							
		14							
		15							
		16							
		17							
		18							
		19							
		20							

This log should be read in conjunction with EI Australia's accompanying explanatory notes.

CORE PHOTOGRAPH OF BOREHOLE: BH104M

Project	Proposed Development	Depth Range	0.47m to 10.00m BEGL	
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	TightSite	
Position	Refer to Figure 2	Surface RL	≈ 12.0 m	
Job No.	E25203.G04	Inclination	-90°	
Client	Palmdev Pty Ltd	Box	1-2 of 3	
		Drill Rig	Hand Portable	
		Logged	KX	Date 27 / 10 / 2021
		Checked	SR	Date 14 / 07 / 2021



CORE PHOTOGRAPH OF BOREHOLE: BH104M

Project	Proposed Development	Depth Range	10.0m to 12.57m BEGL	
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	TightSite	
Position	Refer to Figure 2	Drill Rig	Hand Portable	
Job No.	E25203.G04	Logged	KX	Date 27 / 10 / 2021
Client	Palmdev Pty Ltd	Surface RL	≈ 12.0 m	
		Inclination	-90°	
		Box	3 of 3	
		Checked	SR	Date 14 / 07 / 2021





BOREHOLE LOG

BH ID: BH201M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 1 of 3
Started 04 October 2023
Completed 04 October 2023
Logged By LL **Date** 04 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Geosense Drilling Engineers **Surface RL** ≈1.24 m (AHD) **Northing** 6281319.6500 (MGA 2020 Zone 56)
Plant Comacchio Geo 205 **Inclination** 90° **Easting** 344162.9080 (MGA 2020 Zone 56)

METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY / REL. DENSITY	MATERIAL ORIGIN & OBSERVATIONS
AD/T	06/10/2023 11:20 AM 	BH201M_0.20-0.30		0.00		1.24	SAND: medium grained, yellow brown / red brown, trace seashell.	M	VL	MARINE SOIL
		BH201M_0.50-0.95 SPT 0.50-0.95 0, 1, 1 N=2		1			W			
		BH201M_1.50-1.65 BH201M_1.50-1.95 SPT 1.50-1.95 7, 11, 16 N=27 BH201M_1.65-1.95		1.65		-0.41	Sandy CLAY: low plasticity, yellow brown/red, with ironstone gravels	M < PL	VSt	RESIDUAL SOIL
				2.50		-1.26	From 2.50m, grading into extremely weathered sandstone.	H		
				3.00		-1.76	<i>Log continued on next page.</i>			
				4						
				5						
				6						
				7						
				8						
				9						
				10						

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH201M

Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Started	04 October 2023	
Client	Palmdev Pty Ltd	Completed	04 October 2023	
Job No.	E25203.G04	Logged By	LL	Date 04 October 2023
Sheets	2 of 3	Review By	SK	Date 21 November 2023

Drilling Contractor	Geosense Drilling Engineers	Surface RL	≈1.24 m (AHD)	Northing	6281319.6500 (MGA 2020 Zone 56)
Plant	Comacchio Geo 205	Inclination	90°	Easting	344162.9080 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50)						DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING				
									VL ₀₋₁	L ₀₋₃	M ₁	H ₃	VH ₁₀	EH		30	100	300	1000	3000
				0			<i>Log continued from previous page.</i>													
		100	32	3.00		-2.06	SANDSTONE: fine grained, dark red	DW												
		100	68	3.30			LAMINITE: SANDSTONE(20%) and CLAYSTONE(80%); sandstone is fine grained, pale grey / grey / orange / red. Thinly bedded.													
				4.00																
		100	75	5.00																
				6.00				DW												
				7.00																
				8.00																
				8.76		-7.52	SANDSTONE: fine grained, brown / yellow / pale grey / red.													
				9.00																
				10.00																

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH201M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 3 of 3

Started 04 October 2023
Completed 04 October 2023
Logged By LL **Date** 04 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Geosense Drilling Engineers **Surface RL** ≈1.24 m (AHD) **Northing** 6281319.6500 (MGA 2020 Zone 56)
Plant Comacchio Geo 205 **Inclination** 90° **Easting** 344162.9080 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50) ▼ - Axial ▽ - Diametral	DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING
								VL ₀₋₁ L ₀₋₃ M ₁ H ₃ VH ₁₀ EH			30 100 300 1000 3000
		100	5	10.00		-8.76	LAMINITE: SANDSTONE(10%) and CLAYSTONE(90%); sandstone is fine grained, pale grey/grey.	XW - DW		10.43: JT 60° RO Fe VN	
	60%	100	100	11.50		-10.26	LAMINITE: SANDSTONE(20%) and SHALE(80%); sandstone is fine to medium grained, pale grey/grey.	DW - SW		11.53: BP 0° RO Fe VN	
		99	97	14.00				SW			
				15.49		-14.25	Terminated at 15.49m. Target Depth Reached.				

This log should be read in conjunction with EI Australia's accompanying explanatory notes.




MONITORING WELL LOG

BH ID: BH201M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW	Started 04 October 2023
Client Palmdev Pty Ltd	Completed 04 October 2023
Job No. E25203.G04	Logged By LL Date 04 October 2023
Sheets 1 of 2	Review By SK Date 21 November 2023

Drilling Contractor Geosense Drilling Engineers	Surface RL ≈1.24 m (AHD)	Northing 6281319.6500 (MGA 2020 Zone 56)
Plant Comacchio Geo 205	Inclination 90°	Easting 344162.9080 (MGA 2020 Zone 56)



This log should be read in conjunction with EI Australia's accompanying explanatory notes.











MONITORING WELL LOG

BH ID: BH201M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW	Started 04 October 2023
Client Palmdev Pty Ltd	Completed 04 October 2023
Job No. E25203.G04	Logged By LL Date 04 October 2023
Sheets 2 of 2	Review By SK Date 21 November 2023

Drilling Contractor Geosense Drilling Engineers	Surface RL ≈1.24 m (AHD)	Northing 6281319.6500 (MGA 2020 Zone 56)
Plant Comacchio Geo 205	Inclination 90°	Easting 344162.9080 (MGA 2020 Zone 56)

WATER	SAMPLES & FIELD TESTS	DEPTH (m)	GRAPHIC LOG	RL (m AHD)	MATERIAL DESCRIPTION	MOISTURE CONDITION	BACKFILL DETAILS		STANDPIPE DETAILS
		10.00		-8.76	LAMINITE: SANDSTONE(10%) and CLAYSTONE (90%); sandstone is fine grained, pale grey/grey.		Sand 4.90m - 15.49m		
		11							
		11.50		-10.26	LAMINITE: SANDSTONE(20%) and SHALE(80%); sandstone is fine to medium grained, pale grey/grey.				
		12							
		13							
		14							
		15							
				-14.25	Terminated at 15.49m. Target Depth Reached.				
		16							
		17							
		18							
		19							
		20							

This log should be read in conjunction with EI Australia's accompanying explanatory notes.

CORE PHOTOGRAPH OF BOREHOLE: BH201M

Project	Proposed Development	Depth Range	3.0m to 10.0m BEGL
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	Geosense Drilling
Position	Refer to Figure 2	Drill Rig	Comacchio Geo 205
Job No.	E25203.G04	Surface RL	≈ 1.24 m
Client	Palmdev Pty Ltd	Inclination	-90°
		Box	1,2 of 4
		Logged	LL Date 4 / 10 / 2023
		Checked	SK Date 21 / 11 / 2023



CORE PHOTOGRAPH OF BOREHOLE: BH201M

Project	Proposed Development	Depth Range	10.0m to 15.49m BEGL
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	Geosense Drilling
Position	Refer to Figure 2	Drill Rig	Comacchio Geo 205
Job No.	E25203.G04	Logged	LL Date 4 / 10 / 2023
Client	Palmdev Pty Ltd	Inclination	-90°
		Surface RL	≈ 1.24 m
		Box	3,4 of 4
		Checked	SK Date 21 / 11 / 2023





BOREHOLE LOG

BH ID: BH202M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 1 of 3
Started 05 October 2023
Completed 05 October 2023
Logged By LL **Date** 05 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Geosense Drilling Engineers **Surface RL** ≈2.40 m (AHD) **Northing** 6281312.0780 (MGA 2020 Zone 56)
Plant Comacchio Geo 205 **Inclination** 90° **Easting** 344177.3470 (MGA 2020 Zone 56)

METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY / REL. DENSITY	MATERIAL ORIGIN & OBSERVATIONS
AD/T	06/10/2023 11:20 AM ▼ ▲	BH202M_0.50-0.95 SPT 0.50-0.95 2,4,7 N=11 BH202M_1.50-1.95 SPT 1.50-1.95 6,12,13 N=25 BH202M_2.50-2.60 BH202M_3.00-3.15 SPT 3.00-3.15 15/150 mm HB N=R		0.00		2.40	FILL: Silty SAND: dark grey, with gravels.	-	-	FILL
				0.50		1.90	SAND: fine to medium grained, brown, trace ironstone.	M	MD	MARINE SOIL
				1.50		0.90	Clayey SAND: sand is fine grained, pale grey/yellow brown / red, trace ironstone.	M	D	RESIDUAL SOIL
				3.00		-0.60	From 3.00m, grading into extremely weathered laminite.	W	H	
				3.22		-0.82	Log continued on next page.			

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH202M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW	Started 05 October 2023
Client Palmdev Pty Ltd	Completed 05 October 2023
Job No. E25203.G04	Logged By LL Date 05 October 2023
Sheets 2 of 3	Review By SK Date 21 November 2023

Drilling Contractor Geosense Drilling Engineers	Surface RL ≈2.40 m (AHD)	Northing 6281312.0780 (MGA 2020 Zone 56)
Plant Comacchio Geo 205	Inclination 90°	Easting 344177.3470 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50) ▼ - Axial ▽ - Diametral	DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING
								VL 0-1 L 0-3 M 1 H 3 VH 10 EH			30 100 300 1000 3000
				0			<i>Log continued from previous page.</i>				
NMLC	80%	100	51	4	-		LAMINITE: SANDSTONE(60%) and CLAYSTONE(40%); sandstone is fine grained, pale grey/grey/orange/red. Thinly bedded.	▼	3.26: BP 0° PR RO Fe VN 3.40: BP 0° PR RO Fe VN 3.50: JT 30° ST RO Fe SN 3.80-3.88: XWS 4.33: BP 0° PR RO Fe VN 4.55: JT 10° RO Fe VN 4.62: JT 10° RO Fe CL 4.67: JT 10° PR RO Fe SN 5.26-5.43: SZ RO Fe Infilled 6.20: JT 70° PR RO Fe SN 6.38: BP 0° PR RO Fe VN 7.10: JT 80° PR RO Fe Infilled 7.40: JT 70° IR RO Fe Infilled		
		100	80	6	-			DW	▼		
		100	100	8.85	-	-6.45		LAMINITE: SANDSTONE(50%) and SHALE(50%); sandstone is fine to medium grained, pale grey, trace ironstaining.	▼		
				10							

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH202M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW	Started 05 October 2023
Client Palmdev Pty Ltd	Completed 05 October 2023
Job No. E25203.G04	Logged By LL Date 05 October 2023
Sheets 3 of 3	Review By SK Date 21 November 2023

Drilling Contractor Geosense Drilling Engineers	Surface RL ≈2.40 m (AHD)	Northing 6281312.0780 (MGA 2020 Zone 56)
Plant Comacchio Geo 205	Inclination 90°	Easting 344177.3470 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50)	DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING					
											30	100	300	1000	3000	
	80%	100	100	10.00		-7.60	LAMINITE: SANDSTONE(50%) and SHALE(50%); sandstone is fine to medium grained, pale grey, trace ironstaining. From 10.00m, SANDSTONE(80%) and SHALE(20%).	SW - FR	VL ₀₋₁ L ₀₋₃ M ₁ H ₃ VH ₁₀ EH	11.75-11.76: XWS						
				10.12		-10.12	Terminated at 12.52m. Target Depth Reached.									
				11												
				12												
				13												
				14												
				15												
				16												
				17												
				18												
				19												
				20												

This log should be read in conjunction with EI Australia's accompanying explanatory notes.




MONITORING WELL LOG

BH ID: BH202M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 1 of 2

Started 05 October 2023
Completed 05 October 2023
Logged By LL **Date** 05 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Geosense Drilling Engineers **Surface RL** ≈2.40 m (AHD) **Northing** 6281312.0780 (MGA 2020 Zone 56)
Plant Comacchio Geo 205 **Inclination** 90° **Easting** 344177.3470 (MGA 2020 Zone 56)



This log should be read in conjunction with EI Australia's accompanying explanatory notes.



MONITORING WELL LOG

BH ID: BH202M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 2 of 2

Started 05 October 2023
Completed 05 October 2023
Logged By LL **Date** 05 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Geosense Drilling Engineers **Surface RL** ≈2.40 m (AHD) **Northing** 6281312.0780 (MGA 2020 Zone 56)
Plant Comacchio Geo 205 **Inclination** 90° **Easting** 344177.3470 (MGA 2020 Zone 56)

WATER	SAMPLES & FIELD TESTS	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	MOISTURE CONDITION	BACKFILL DETAILS	STANDPIPE DETAILS
80%		10.00		-7.60	LAMINITE: SANDSTONE(50%) and SHALE(50%); sandstone is fine to medium grained, pale grey, trace ironstaining. From 10.00m, SANDSTONE(80%) and SHALE (20%).			
		11			Terminated at 12.52m. Target Depth Reached.			
		12						
		13		-10.12				
		14						
		15						
		16						
		17						
		18						
		19						
		20						

This log should be read in conjunction with EI Australia's accompanying explanatory notes.

CORE PHOTOGRAPH OF BOREHOLE: BH202M

Project	Proposed Development	Depth Range	3.22m to 12.52m BEGL				
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	Geosense Drilling				
Position	Refer to Figure 2	Drill Rig	Comacchio Geo 205				
Job No.	E25203.G04	Surface RL	≈ 2.4 m	Logged	LL	Date	5 / 10 / 2023
Client	Palmdev Pty Ltd	Inclination	-90°	Checked	SK	Date	21 / 11 / 2023
		Box	1,2,3 of 3				






MONITORING WELL LOG

BH ID: BH203M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 1 of 1

Started 11 October 2023
Completed 11 October 2023
Logged By LL **Date** 11 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Geosense Drilling Engineers **Surface RL** ≈2.50 m (AHD) **Northing** 6281285.1540 (MGA 2020 Zone 56)
Plant Comacchio Geo 205 **Inclination** 90° **Easting** 344169.3190 (MGA 2020 Zone 56)



This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE LOG

BH ID: BH204M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW	Started 10 October 2023
Client Palmdev Pty Ltd	Completed 11 October 2023
Job No. E25203.G04	Logged By LL Date 11 October 2023
Sheets 1 of 3	Review By SK Date 21 November 2023

Drilling Contractor Tightsite Geotechnical & Environmental Drilling	Surface RL ≈12.92 m (AHD)	Northing 6281323.4510 (MGA 2020 Zone 56)
Plant Hand Portable Rig	Inclination 90°	Easting 344196.7060 (MGA 2020 Zone 56)

METHOD	GROUND WATER LEVELS	SAMPLES & FIELD TESTS	SAMPLE RECOVERY	DEPTH (m)	GRAPHIC LOG	RL (m(AHD))	MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY / REL. DENSITY	MATERIAL ORIGIN & OBSERVATIONS
HA	GWNE	BH204M_0.20-0.30	█	0.00	[Graphic Log: Hatched pattern from 0.00 to 1.12m]	12.92	TOPSOIL: Silty CLAY: low plasticity, yellow brown/orange/grey, with rootlets.	M < PL	-	TOPSOIL
		BH204M_0.80-0.90	█	0.80		12.12	From 0.80m, trace ironstone gravels			
				1.12		11.80	<i>Log continued on next page.</i>			
				2						
				3						
				4						
				5						
				6						
				7						
				8						
				9						
				10						

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH204M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 2 of 3

Started 10 October 2023
Completed 11 October 2023
Logged By LL **Date** 11 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Tightsite Geotechnical & Environmental Drilling **Surface RL** ≈12.92 m (AHD) **Northing** 6281323.4510 (MGA 2020 Zone 56)
Plant Hand Portable Rig **Inclination** 90° **Easting** 344196.7060 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50)						DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING					
									VL ₀₋₁	L ₀₋₃	M ₁	H ₃	VH ₁₀	EH		30	100	300	1000	3000	
				0			<i>Log continued from previous page.</i>														
		100	33	1			SANDSTONE: fine to medium grained, pale yellow / red / pale grey						1.17-1.50: XWZ								
				2				DW					1.87-2.16: CZ								
		100	92	3									2.81-2.88: XWS								
				3.74		9.18	CLAYSTONE: pale grey/grey						3.37: JT 80° IR RO Clay VN 3.51-3.53: XWS 3.64-3.68: XWS								
		100	89	4				DW													
				5																	
		100	90	5.63		7.29	LAMINITE: SANDSTONE(50%) and SHALE(50%), sandstone is fine grained, pale grey/grey/orange/red.						5.49: JT 60° IR RO CN								
				6																	
		100	100	7									6.28-6.30: CS								
				8				DW - SW													
		100	88	9																	
				9.88		3.03	<i>From 9.89m, pale grey, thinly bedded.</i>														

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BOREHOLE CORE LOG

BH ID: BH204M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 3 of 3

Started 10 October 2023
Completed 11 October 2023
Logged By LL **Date** 11 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Tightsite Geotechnical & Environmental Drilling
Surface RL ≈12.92 m (AHD)
Plant Hand Portable Rig
Inclination 90°
Northing 6281323.4510 (MGA 2020 Zone 56)
Easting 344196.7060 (MGA 2020 Zone 56)

METHOD	Flush Return	TCR %	RQD %	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	WEATHERING	ESTIMATED STRENGTH Is(50)							DISCONTINUITIES & ADDITIONAL DATA	FRACTURE SPACING																							
									VL ₀₋₁	L ₀₋₃	M ₁	H ₃	VH ₁₀	EH	30		100	300	1000	3000																				
	0%	100	94	11					▼																															
		100	75	12					▼																															
		100	100	13					FR																															
		100	100	14																																				
		100	100	15																																				
		100	100	16																																				
				16.58			Terminated at 16.58m. Target Depth Reached.																																	

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



MONITORING WELL LOG

BH ID: BH204M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 1 of 2

Started 10 October 2023
Completed 11 October 2023
Logged By LL **Date** 11 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Tightsite Geotechnical & Environmental Drilling **Surface RL** ≈12.92 m (AHD) **Northing** 6281323.4510 (MGA 2020 Zone 56)
Plant Hand Portable Rig **Inclination** 90° **Easting** 344196.7060 (MGA 2020 Zone 56)

WATER	SAMPLES & FIELD TESTS	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	MOISTURE CONDITION	BACKFILL DETAILS	STANDPIPE DETAILS
GWNE	BH204M_0.20-0.30	0.00		12.92	TOPSOIL: Silty CLAY: low plasticity, yellow brown/orange/grey, with rootlets.	M < PL		Well Stickup =0.0m (RL 12.92m)
	BH204M_0.80-0.90	0.80		12.12	From 0.80m, trace ironstone gravels			
			1.12	11.80	SANDSTONE: fine to medium grained, pale yellow / red / pale grey			
			3.74	9.18	CLAYSTONE: pale grey/grey			
			5.63	7.29	LAMINITE: SANDSTONE(50%) and SHALE(50%), sandstone is fine grained, pale grey/grey/orange/red.			
0%		9.89	3.03	From 9.89m, pale grey, thinly bedded.				0.0m - 13.60m PVC casing (50mm Ø)

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



MONITORING WELL LOG

BH ID: BH204M

Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Client Palmdev Pty Ltd
Job No. E25203.G04
Sheets 2 of 2

Started 10 October 2023
Completed 11 October 2023
Logged By LL **Date** 11 October 2023
Review By SK **Date** 21 November 2023

Drilling Contractor Tightsite Geotechnical & Environmental Drilling **Surface RL** ≈12.92 m (AHD) **Northing** 6281323.4510 (MGA 2020 Zone 56)
Plant Hand Portable Rig **Inclination** 90° **Easting** 344196.7060 (MGA 2020 Zone 56)

WATER	SAMPLES & FIELD TESTS	DEPTH (m)	GRAPHIC LOG	RL (mAHD)	MATERIAL DESCRIPTION	MOISTURE CONDITION	BACKFILL DETAILS		STANDPIPE DETAILS
0%		11 12 13 14 15 16		-3.66	Terminated at 16.58m. Target Depth Reached.		Bentonite 10.00m - 12.00m Sand 12.00m - 16.58m		13.60m - 15.10m PVC screen (50mm Ø)
		17 18 19 20							


This log should be read in conjunction with EI Australia's accompanying explanatory notes.

Project	Proposed Development	Depth Range	1.12m to 10.0m BEGL	
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	TightSite	
Position	Refer to Figure 2	Drill Rig	Hand Portable	
Job No.	E25203.G04	Surface RL	≈ 12.92 m	Logged
Client	Palmdev Pty Ltd	Inclination	-90°	Date
		Box	1,2 of 3	Date
				10 / 10 / 2023
				21 / 11 / 2023



CORE PHOTOGRAPH OF BOREHOLE: BH204M

Project	Proposed Development	Depth Range	10.0m to 16.58m BEGL	
Location	1112-1116 Barrenjoey Road, Palm Beach NSW	Contractor	TightSite	
Position	Refer to Figure 2	Drill Rig	Hand Portable	
Job No.	E25203.G04	Logged	LL	Date 11 / 10 / 2023
Client	Palmdev Pty Ltd	Inclination	-90°	
		Box	3 of 3	
		Checked	SK	Date 21 / 11 / 2023




Project Proposed Development
Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Position Refer to Figure 2
Job No. E25203.G03
Client Palmdev Pty Ltd

Sheet 1 of 1
Date Started 27/10/2021
Date Completed 27/10/2021
Logged By KX **Date** 27/10/2021
Reviewed By SR **Date** 14/12/2021

Inclination -90°

DEPTH (m)	NO OF BLOWS PER 100 mm
0.00-0.10	0
0.10-0.20	1
0.20-0.30	1
0.30-0.40	7
0.40-0.50	13
0.50-0.52	15/20mm HB



Termination Remark
 DCP Refused at 0.52 m depth.
 HB Hammer Bounced

Final Depth (m)	0.52
-----------------	------

Project Proposed Development
Location 1112-1116 Barrenjoey Road, Palm Beach NSW
Position Refer to Figure 2
Job No. E25203.G03
Client Palmdev Pty Ltd


Sheet 1 of 1
Date Started 27/10/2021
Date Completed 27/10/2021
Logged By KX **Date** 27/10/2021
Reviewed By SR **Date** 14/12/2021

Drilling Contractor

Drill Rig

Inclination -90°

DEPTH (m)	NO OF BLOWS PER 100 mm
0.00-0.10	2
0.10-0.20	4
0.20-0.30	11
0.30-0.40	9
0.40-0.50	15
0.50-0.55	12/50mm HB



Termination Remark
 DCP Refused at 0.55 m depth.
 HB Hammer Bounced

Final Depth (m)	0.55
------------------------	------

EXPLANATION OF NOTES, ABBREVIATIONS & TERMS USED ON BOREHOLE AND TEST PIT LOGS

DRILLING/EXCAVATION METHOD

HA	Hand Auger	ADH	Hollow Auger	NQ	Diamond Core - 47 mm
DT	Diatube Coring	RT	Rotary Tricone bit	NMLC	Diamond Core - 52 mm
NDD	Non-destructive digging	RAB	Rotary Air Blast	HQ	Diamond Core - 63 mm
AD*	Auger Drilling	RC	Reverse Circulation	HMLC	Diamond Core - 63 mm
*V	V-Bit	PT	Push Tube	EX	Tracked Hydraulic Excavator
*T	TC-Bit, e.g. AD/T	WB	Washbore	HAND	Excavated by Hand Methods

PENETRATION RESISTANCE

L	Low Resistance	Rapid penetration/ excavation possible with little effort from equipment used.
M	Medium Resistance	Penetration/ excavation possible at an acceptable rate with moderate effort from equipment used.
H	High Resistance	Penetration/ excavation is possible but at a slow rate and requires significant effort from equipment used.
R	Refusal/Practical Refusal	No further progress possible without risk of damage or unacceptable wear to equipment used.

These assessments are subjective and are dependent on many factors, including equipment power and weight, condition of excavation or drilling tools and experience of the operator.

WATER

▽ Standing Water Level

◁ Partial water loss

▷ Water Seepage

◀ Complete Water Loss

GWNO GROUNDWATER NOT OBSERVED - Observation of groundwater, whether present or not, was not possible due to drilling water, surface seepage or cave-in of the borehole/ test pit.

GWNE GROUNDWATER NOT ENCOUNTERED - Borehole/ test pit was dry soon after excavation. However, groundwater could be present in less permeable strata. Inflow may have been observed had the borehole/ test pit been left open for a longer period.

SAMPLING AND TESTING

SPT	Standard Penetration Test to AS1289.6.3.1-2004
4,7,11 N=18	4,7,11 = Blows per 150mm. N = Blows per 300mm penetration following a 150mm seating drive
30/80mm	Where practical refusal occurs, the blows and penetration for that interval are reported, N is not reported
RW	Penetration occurred under the rod weight only, N<1
HW	Penetration occurred under the hammer and rod weight only, N<1
HB	Hammer double bouncing on anvil, N is not reported

Sampling

DS	Disturbed Sample
ES	Sample for environmental testing
BDS	Bulk disturbed Sample
GS	Gas Sample
WS	Water Sample
U50	Thin walled tube sample - number indicates nominal sample diameter in millimetres

Testing

FP	Field Permeability test over section noted
FVS	Field Vane Shear test expressed as uncorrected shear strength (sv= peak value, sr= residual value)
PID	Photoionisation Detector reading in ppm
PM	Pressuremeter test over section noted
PP	Pocket Penetrometer test expressed as instrument reading in kPa
WPT	Water Pressure tests
DCP	Dynamic Cone Penetrometer test
CPT	Static Cone Penetration test
CPTu	Static Cone Penetration test with pore pressure (u) measurement

GEOLOGICAL BOUNDARIES

————— = Observed Boundary (position known)	- - - - - = Observed Boundary (position approximate)	- - ? - - ? - - ? - - = Boundary (interpreted or inferred)
---	---	---

ROCK CORE RECOVERY








TCR=Total Core Recovery (%)

RQD = Rock Quality Designation (%)

$$= \frac{\text{Length of core recovered}}{\text{Length of core run}} \times 100$$

$$= \frac{\sum \text{Axial lengths of core} > 100\text{mm}}{\text{Length of core run}} \times 100$$

METHOD OF SOIL DESCRIPTION USED ON BOREHOLE AND TEST PIT LOGS

	FILL		ORGANIC SOILS (OL, OH or Pt)		CLAY (CL, CI or CH)
	COUBLES or BOULDERS		SILT (ML or MH)		SAND (SP or SW)
	GRAVEL (GP or GW)	Combinations of these basic symbols may be used to indicate mixed materials such as sandy clay			

CLASSIFICATION AND INFERRED STRATIGRAPHY

Soil is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS 1726:2017, Section 6.1 – Soil description and classification.


PARTICLE SIZE CHARACTERISTICS

Fraction	Components	Sub Division	Size mm
Oversize	BOULDERS		>200
	COBBLES		63 to 200
Coarse grained soil	GRAVEL	Coarse	19 to 63
		Medium	6.7 to 19
		Fine	2.36 to 6.7
	SAND	Coarse	0.6 to 2.36
		Medium	0.21 to 0.6
		Fine	0.075 to 0.21
Fine grained soil	SILT		0.002 to 0.075
	CLAY		<0.002

GROUP SYMBOLS

Major Divisions	Symbol	Description
GRAVEL More than 50% of coarse fraction is >2.36mm	GW	Well graded gravel and gravel-sand mixtures, little or no fines, no dry strength.
	GP	Poorly graded gravel and gravel-sand mixtures, little or no fines, no dry strength.
	GM	Silty gravel, gravel-sand-silt mixtures, zero to medium dry strength.
	GC	Clayey gravel, gravel-sand-clay mixtures, medium to high dry strength.
	SW	Well graded sand and gravelly sand, little or no fines, no dry strength.
	SP	Poorly graded sand and gravelly sand, little or no fines, no dry strength.
SAND More than 50% of coarse fraction is <2.36 mm	SM	Silty sand, sand-silt mixtures, zero to medium dry strength.
	SC	Clayey sand, sandy-clay mixtures, medium to high dry strength.
	ML	Inorganic silts of low plasticity, very fine sands, rock flour, silty or clayey fine sands, zero to medium dry strength.
CLAY Liquid Limit less < 50%	CL, CI	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, medium to high dry strength.
	OL	Organic silts and organic silty clays of low plasticity, low to medium dry strength.
	MH	Inorganic silts of high plasticity, high to very high dry strength.
	CH	Inorganic clays of high plasticity, high to very high dry strength.
OH Liquid Limit > 50%	OH	Organic clays of medium to high plasticity, medium to high dry strength.
	PT	Peat muck and other highly organic soils.

PLASTICITY PROPERTIES



MOISTURE CONDITION

Symbol	Term	Description
D	Dry	Non-cohesive and free-running.
M	Moist	Soils feel cool, darkened in colour. Soil tends to stick together.
W	Wet	Soils feel cool, darkened in colour. Soil tends to stick together, free water forms when handling.

Moisture content of cohesive soils shall be described in relation to plastic limit (PL) or liquid limit (LL) for soils with higher moisture content as follows: Moist, dry of plastic limit ($w < PL$); Moist, near plastic limit ($w \approx PL$); Moist, wet of plastic limit ($w < PL$); Wet, near liquid limit ($w \approx LL$); Wet, wet of liquid limit ($w > LL$).

CONSISTENCY

Symbol	Term	Undrained Shear Strength (kPa)	SPT "N" #
VS	Very Soft	≤ 12	≤ 2
S	Soft	>12 to ≤ 25	>2 to ≤ 4
F	Firm	>25 to ≤ 50	>4 to ≤ 8
St	Stiff	>50 to ≤ 100	>8 to ≤ 15
VSt	Very Stiff	>100 to ≤ 200	>15 to ≤ 30
H	Hard	>200	>30
Fr	Friable	-	-

DENSITY

Symbol	Term	Density Index %	SPT "N" #
VL	Very Loose	≤ 15	0 to 4
L	Loose	>15 to ≤ 35	4 to 10
MD	Medium Dense	>35 to ≤ 65	10 to 30
D	Dense	>65 to ≤ 85	30 to 50
VD	Very Dense	>85	Above 50

In the absence of test results, consistency and density may be assessed from correlations with the observed behaviour of the material. # SPT correlations are not stated in AS1726:2017, and may be subject to corrections for overburden pressure, moisture content of the soil, and equipment type.

MINOR COMPONENTS

Term	Assessment Guide	Proportion by Mass
Add 'Trace'	Presence just detectable by feel or eye but soil properties little or no different to general properties of primary component	Coarse grained soils: $\leq 5\%$ Fine grained soil: $\leq 15\%$
Add 'With'	Presence easily detectable by feel or eye but soil properties little or no different to general properties of primary component	Coarse grained soils: 5 - 12% Fine grained soil: 15 - 30%
Prefix soil name	Presence easily detectable by feel or eye in conjunction with the general properties of primary component	Coarse grained soils: $>12\%$ Fine grained soil: $>30\%$

CLASSIFICATION AND INFERRED STRATIGRAPHY

Rock is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS1726 – 2017, Section 6.2 – Rock identification, description and classification.

ROCK MATERIAL STRENGTH CLASSIFICATION

Symbol	Term	Point Load Index, $I_{s(50)}$ (MPa) [#]	Field Guide
VL	Very Low	0.03 to 0.1	Material crumbles under firm blows with sharp end of pick; can be peeled with knife; too hard to cut a triaxial sample by hand. Pieces up to 30 mm can be broken by finger pressure.
L	Low	0.1 to 0.3	Easily scored with a knife; indentations 1 mm to 3 mm show in the specimen with firm blows of pick point; has dull sound under hammer. A piece of core 150 mm long by 50 mm diameter may be broken by hand. Sharp edges of core may be friable and break during handling.
M	Medium	0.3 to 1	Readily scored with a knife; a piece of core 150 mm long by 50 mm diameter can be broken by hand with difficulty.
H	High	1 to 3	A piece of core 150 mm long by 50 mm diameter cannot be broken by hand but can be broken with pick with a single firm blow; rock rings under hammer.
VH	Very High	3 to 10	Hand specimen breaks with pick after more than one blow; rock rings under hammer.
EH	Extremely High	>10	Specimen requires many blows with geological pick to break through intact material; rock rings under hammer.

[#] **Rock Strength Test Results** ▼ Point Load Strength Index, $I_{s(50)}$, Axial test (MPa)

● Point Load Strength Index, $I_{s(50)}$, Diametral test (MPa)

Relationship between rock strength test result ($I_{s(50)}$) and unconfined compressive strength (UCS) will vary with rock type and strength, and should be determined on a site-specific basis. However UCS is typically $20 \times I_{s(50)}$.

ROCK MATERIAL WEATHERING CLASSIFICATION

Symbol	Term	Field Guide
RS	Residual Soil	Soil developed on extremely weathered rock; the mass structure and substance fabric are no longer evident; there is a large change in volume but the soil has not been significantly transported.
XW	Extremely Weathered	Rock is weathered to such an extent that it has soil properties - i.e. it either disintegrates or can be remoulded, in water.
DW	Distinctly Weathered	Rock strength usually changed by weathering. The rock may be highly discoloured, usually by iron staining. Porosity may be increased by leaching, or may be decreased due to deposition of weathering products in pores. In some environments it is convenient to subdivide into Highly Weathered and Moderately Weathered, with the degree of alteration typically less for MW.
	MW	
SW	Slightly Weathered	Rock slightly discoloured but shows little or no change of strength relative to fresh rock.
FR	Fresh	Rock shows no sign of decomposition or staining.

ABBREVIATIONS AND DESCRIPTIONS FOR ROCK MATERIAL AND DEFECTS

CLASSIFICATION AND INFERRED STRATIGRAPHY

Rock is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS1726 – 2017, Section 6.2 – Rock identification, description and classification.

DETAILED ROCK DEFECT SPACING

Defect Spacing			Bedding Thickness (Stratification)	
Spacing/width (mm)	Descriptor	Symbol	Term	Spacing (mm)
<20	Extremely Close	EC	Thinly laminated	<6
			Laminated	6 – 20
20-60	Very Close	VC	Very thinly bedded	20 – 60
60-200	Close	C	Thinly bedded	60 – 200
200-600	Medium	M	Medium bedded	200 – 600
600-2000	Wide	W	Thickly bedded	600 – 2,000
2000-6000	Very Wide	VW	Very thickly bedded	> 2,000

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT TYPES

Defect Type	Abbr.	Description
Joint	JT	Surface of a fracture or parting, formed without displacement, across which the rock has little or no tensile strength. May be closed or filled by air, water or soil or rock substance, which acts as cement.
Bedding Parting	BP	Surface of fracture or parting, across which the rock has little or no tensile strength, parallel or sub-parallel to layering/ bedding. Bedding refers to the layering or stratification of a rock, indicating orientation during deposition, resulting in planar anisotropy in the rock material.
Contact	CO	The surface between two types or ages of rock.
Sheared Surface	SSU	A near planar, curved or undulating surface which is usually smooth, polished or slickensided.
Sheared Seam/ Zone (Fault)	SS/SZ	Seam or zone with roughly parallel almost planar boundaries of rock substance cut by closely spaced (often <50 mm) parallel and usually smooth or slickensided joints or cleavage planes.
Crushed Seam/ Zone (Fault)	CS/CZ	Seam or zone composed of disoriented usually angular fragments of the host rock substance, with roughly parallel near-planar boundaries. The brecciated fragments may be of clay, silt, sand or gravel sizes or mixtures of these.
Extremely Weathered Seam/ Zone	XWS/XWZ	Seam of soil substance, often with gradational boundaries, formed by weathering of the rock material in places.
Infilled Seam	IS	Seam of soil substance, usually clay or clayey, with very distinct roughly parallel boundaries, formed by soil migrating into joint or open cavity.
Vein	VN	Distinct sheet-like body of minerals crystallised within rock through typically open-space filling or crack-seal growth.

NOTE: Defects size of <100mm SS, CS and XWS. Defects size of >100mm SZ, CZ and XWZ.

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT SHAPE AND ROUGHNESS

Shape	Abbr.	Description	Roughness	Abbr.	Description
Planar	PR	Consistent orientation	Polished	POL	Shiny smooth surface
Curved	CU	Gradual change in orientation	Slickensided	SL	Grooved or striated surface, usually polished
Undulating	UN	Wavy surface	Smooth	SM	Smooth to touch. Few or no surface irregularities
Stepped	ST	One or more well defined steps	Rough	RO	Many small surface irregularities (amplitude generally <1mm). Feels like fine to coarse sandpaper
Irregular	IR	Many sharp changes in orientation	Very Rough	VR	Many large surface irregularities, amplitude generally >1mm. Feels like very coarse sandpaper

Orientation:

Vertical Boreholes – The dip (inclination from horizontal) of the defect.

Inclined Boreholes – The inclination is measured as the acute angle to the core axis.

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT COATING

DEFECT COATING			DEFECT APERTURE		
Coating	Abbr.	Description	Aperture	Abbr.	Description
Clean	CN	No visible coating or infilling	Closed	CL	Closed.
Stain	SN	No visible coating but surfaces are discoloured by staining, often limonite (orange-brown)	Open	OP	Without any infill material.
Veneer	VNR	A visible coating of soil or mineral substance, usually too thin to measure (< 1 mm); may be patchy	Infilled	-	Soil or rock i.e. clay, silt, talc, pyrite, quartz, etc.

Appendix B – Cross Sections

Project ID: E25203.G04

Horizontal Scale: Not to scale


Project Title: Additional Geotechnical Investigation

Vertical Scale: 1:200

Location: 1112-1116 Barrenjoey Road, Palm Beach NSW

Client: Palmdev Pty Ltd

Cross Section A-A'



Chainage (m) 0 3.0 34.5 35.7

Project ID: E25203.G04

Horizontal Scale: Not to scale

Project Title: Additional Geotechnical Investigation

Vertical Scale: 1:200

Location: 1112-1116 Barrenjoey Road, Palm Beach NSW


Client: Palmdev Pty Ltd

Cross Section B-B'



Western Site Boundary

Eastern Site Boundary



Project ID: E25203.G04

Horizontal Scale: Not to scale


Project Title: Additional Geotechnical Investigation

Vertical Scale: 1:200

Location: 1112-1116 Barrenjoey Road, Palm Beach NSW

Client: Palmdev Pty Ltd

Cross Section C-C'



Project ID: E25203.G04

Horizontal Scale: Not to scale


Project Title: Additional Geotechnical Investigation

Vertical Scale: 1:200

Location: 1112-1116 Barrenjoey Road, Palm Beach NSW

Client: Palmdev Pty Ltd

Cross Section D-D'



Appendix C – Laboratory Certificates

CLIENT DETAILS

Contact Kaiyu Xu
 Client EI AUSTRALIA
 Address SUITE 6.01
 55 MILLER STREET
 PYRMONT NSW 2009

Telephone 61 2 9516 0722
 Facsimile (Not specified)
 Email kaiyu.xu@eiaustralia.com.au

Project **E25203.G03 1112-1116 Barrenjoey Rd, Palm**
 Order Number **E25203.G03**
 Samples 2

LABORATORY DETAILS

Manager Huong Crawford
 Laboratory SGS Alexandria Environmental
 Address Unit 16, 33 Maddox St
 Alexandria NSW 2015

Telephone +61 2 8594 0400
 Facsimile +61 2 8594 0499
 Email au.environmental.sydney@sgs.com

SGS Reference **SE220690 R0**
 Date Received 15/6/2021
 Date Reported 22/6/2021

COMMENTS

Accredited for compliance with ISO/IEC 17025 - Testing. NATA accredited laboratory 2562(4354).

SIGNATORIES



Dong LIANG
 Metals/Inorganics Team Leader



Shane MCDERMOTT
 Inorganic/Metals Chemist

Soluble Anions (1:5) in Soil/Solids by Ion Chromatography [AN245] Tested: 17/6/2021

PARAMETER	UOM	LOR	BH101M 0.5-0.95m	BH102 3.0-3.45m
			SOIL - 11/6/2021 SE220690.001	SOIL - 11/6/2021 SE220690.002
Chloride	mg/kg	0.25	18	110
Sulfate	mg/kg	5	22	63

pH in soil (1:5) [AN101] Tested: 17/6/2021

PARAMETER	UOM	LOR	BH101M 0.5-0.95m	BH102 3.0-3.45m
			SOIL - 11/6/2021 SE220690.001	SOIL - 11/6/2021 SE220690.002
pH	pH Units	0.1	5.7	4.8

Conductivity and TDS by Calculation - Soil [AN106] Tested: 17/6/2021

PARAMETER	UOM	LOR	BH101M 0.5-0.95m	BH102 3.0-3.45m
			SOIL - 11/6/2021 SE220690.001	SOIL - 11/6/2021 SE220690.002
Conductivity of Extract (1:5 dry sample basis)	µS/cm	1	27	130

Moisture Content [AN002] Tested: 21/6/2021

PARAMETER	UOM	LOR	BH101M 0.5-0.95m	BH102 3.0-3.45m
			SOIL - 11/6/2021 SE220690.001	SOIL - 11/6/2021 SE220690.002
% Moisture	%w/w	1	9.2	34.3

METHOD

METHODOLOGY SUMMARY

- AN002** The test is carried out by drying (at either 40°C or 105°C) a known mass of sample in a weighed evaporating basin. After fully dry the sample is re-weighed. Samples such as sludge and sediment having high percentages of moisture will take some time in a drying oven for complete removal of water.
- AN101** pH in Soil Sludge Sediment and Water: pH is measured electrometrically using a combination electrode and is calibrated against 3 buffers purchased commercially. For soils, sediments and sludges, an extract with water (or 0.01M CaCl₂) is made at a ratio of 1:5 and the pH determined and reported on the extract. Reference APHA 4500-H+.
- AN106** Conductivity and TDS by Calculation: Conductivity is measured by meter with temperature compensation and is calibrated against a standard solution of potassium chloride. Conductivity is generally reported as µmhos/cm or µS/cm @ 25°C. For soils, an extract of as received sample with water is made at a ratio of 1:5 and the EC determined and reported on the extract, or calculated back to the as-received sample. Salinity can be estimated from conductivity using a conversion factor, which for natural waters, is in the range 0.55 to 0.75. Reference APHA 2510 B.
- AN245** Anions by Ion Chromatography: A water sample is injected into an eluent stream that passes through the ion chromatographic system where the anions of interest ie Br, Cl, NO₂, NO₃ and SO₄ are separated on their relative affinities for the active sites on the column packing material. Changes to the conductivity and the UV-visible absorbance of the eluent enable identification and quantitation of the anions based on their retention time and peak height or area. APHA 4110 B

FOOTNOTES

<p>* NATA accreditation does not cover the performance of this service.</p> <p>** Indicative data, theoretical holding time exceeded.</p> <p>*** Indicates that both * and ** apply.</p>	<p>- Not analysed.</p> <p>NVL Not validated.</p> <p>IS Insufficient sample for analysis.</p> <p>LNR Sample listed, but not received.</p>	<p>UOM Unit of Measure.</p> <p>LOR Limit of Reporting.</p> <p>↑↓ Raised/lowered Limit of Reporting.</p>
--	--	---

Unless it is reported that sampling has been performed by SGS, the samples have been analysed as received. Solid samples expressed on a dry weight basis.

Where "Total" analyte groups are reported (for example, Total PAHs, Total OC Pesticides) the total will be calculated as the sum of the individual analytes, with those analytes that are reported as <LOR being assumed to be zero. The summed (Total) limit of reporting is calculated by summing the individual analyte LORs and dividing by two. For example, where 16 individual analytes are being summed and each has an LOR of 0.1 mg/kg, the "Totals" LOR will be 1.6 / 2 (0.8 mg/kg). Where only 2 analytes are being summed, the "Total" LOR will be the sum of those two LORs.

Some totals may not appear to add up because the total is rounded after adding up the raw values.

If reported, measurement uncertainty follow the ± sign after the analytical result and is expressed as the expanded uncertainty calculated using a coverage factor of 2, providing a level of confidence of approximately 95%, unless stated otherwise in the comments section of this report.

Results reported for samples tested under test methods with codes starting with ARS-SOP, radionuclide or gross radioactivity concentrations are expressed in becquerel (Bq) per unit of mass or volume or per wipe as stated on the report. Becquerel is the SI unit for activity and equals one nuclear transformation per second.

Note that in terms of units of radioactivity:

- a. 1 Bq is equivalent to 27 pCi
- b. 37 MBq is equivalent to 1 mCi

For results reported for samples tested under test methods with codes starting with ARS-SOP, less than (<) values indicate the detection limit for each radionuclide or parameter for the measurement system used. The respective detection limits have been calculated in accordance with ISO 11929.

The QC and MU criteria are subject to internal review according to the SGS QAQC plan and may be provided on request or alternatively can be found here: www.sgs.com.au/en-gb/environment-health-and-safety.

This document is issued by the Company under its General Conditions of Service accessible at www.sgs.com/en/Terms-and-Conditions.aspx. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.

Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client only. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law .

This report must not be reproduced, except in full.

Point Load Strength Index Report

Project: E25203.G03, 1112-1116 Barrenjoey Rd, Palm Beach

Project No.: 31264/5259D-L

Client: **EI Australia**

Report No.: 21/1884

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW

Report Date: 22/06/2021

Test Method: AS 4133.4.1

Page: 1 OF 1

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)


Date Samples Drilled / Taken: 11/06/2021

Date Samples Drilled / Taken:

Borehole No. 101M

Borehole No.

Depth	Test Type	Is(50) (Mpa)	Rock Type	Failure Type	Moisture	Depth	Test Type	Is(50) (Mpa)	Rock Type	Failure Type	Moisture
3.30	A	0.052	TS	3	M						
4.39	A	0.062	TS	3	M						
5.28	A	0.086	TS	3	M						
5.84	A	0.110	TS	3	M						
6.34	A	0.085	TS	3	M						
7.40	A	0.130	TS	3	M						
8.34	A	0.089	TS	3	M						

<p>FAILURE TYPE</p> <p>1= FRACTURE THROUGH BEDDING OR WEAK PLANE</p> <p>2= FRACTURE ALONG BEDDING</p> <p>3= FRACTURE THROUGH ROCK MASS</p> <p>4= FRACTURE INFLUENCED BY NATURAL DEFECT OR DRILLING</p> <p>5= PARTIAL FRACTURE OR CHIP (INVALID RESULT)</p>	<p>TEST TYPE</p> <p>A= AXIAL</p> <p>D= DIAMETRAL</p> <p>I= IRREGULAR</p> <p>C= CUBE</p>	<p>MOISTURE CONDITION</p> <p>W= WET</p> <p>M= MOIST</p> <p>D= DRY</p>	<p>ROCK TYPE</p> <p>SS= SANDSTONE</p> <p>ST= SILTSTONE</p> <p>SH= SHALE</p> <p>YS= CLAYSTONE</p> <p>IG= IGNEOUS</p>
<p>Remarks:</p>			 Approved Signatory..... Orlando Mendoza - Laboratory Manager
<p>Technician: FV</p>			



STS Geotechnics Pty Ltd
 14/1 Cowpasture Place, Wetherill Park NSW 2164
 Phone: (02)9756 2166 | Email: enquiries@stsgo.com.au



Point Load Strength Index Report

Project: E25203.G03: 1112 - 1116 Barrenjoey Road, Palm Beach
Client: El Australia Pty Ltd
 Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009
 Test Method: AS4133.4.1


Project No.: 31380/5855D-L
 Report No.: 21/3558
 Report Date: 30/11/2021
 Page: 1 of 1

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)						Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)					
Date Samples Drilled / Taken: 27/10/21						Date Samples Drilled / Taken: 27/10/21					
Borehole No. 103						Borehole No. 104					
Depth	Test Type	Is(50) (Mpa)	Rock Type	Failure Type	Moisture	Depth	Test Type	Is(50) (Mpa)	Rock Type	Failure Type	Moisture
1.47	A	0.023	SS	3	W	1.27	A	0.024	SS	3	M
2.40	A	0.400	SS	3	M	2.38	A	0.020	SS	3	M
3.78	A	0.039	TS	3	W	4.65	A	0.057	SS	3	M
4.53	A	0.750	SS	3	W	5.79	A	0.120	SS	3	M
6.49	A	0.640	SS	3	M	7.44	A	0.160	SS	3	M
7.44	A	0.073	SS	3	M	8.71	A	0.063	SS	3	M
9.22	A	0.180	SS	3	M	9.67	A	0.260	SS	3	M
10.34	A	0.120	SS	3	M	10.38	A	0.330	SS	3	M
11.43	A	0.290	SS	3	M	11.51	A	0.340	SS	3	M
12.43	A	0.200	SH	3	M	12.43	A	0.200	SS	3	M

FAILURE TYPE	TEST TYPE	MOISTURE CONDITION	ROCK TYPE
1= FRACTURE THROUGH BEDDING OR WEAK PLANE	A= AXIAL	W= WET	SS= SANDSTONE
2= FRACTURE ALONG BEDDING	D= DIAMETRICAL	M= MOIST	ST= SILTSTONE
3= FRACTURE THROUGH ROCK MASS	I= IRREGULAR	D= DRY	SH= SHALE
4= FRACTURE INFLUENCED BY NATURAL DEFECT OR DRILLING	C= CUBE		YS= CLAYSTONE
5= PARTIAL FRACTURE OR CHIP (INVALID RESULT)			IG= IGNEOUS

Remarks:

Technician: FV

Approved Signatory.....

 Orlando Mendoza - Laboratory Manager

CLIENT DETAILS

LABORATORY DETAILS

Contact **Lawrence Li**
 Client **EI AUSTRALIA**
 Address **SUITE 6.01
 55 MILLER STREET
 PYRMONT NSW 2009**

Manager **Huong Crawford**
 Laboratory **SGS Alexandria Environmental**
 Address **Unit 16, 33 Maddox St
 Alexandria NSW 2015**

Telephone **61 2 95160722**
 Facsimile **(Not specified)**
 Email **Lawrence.Li@eiaustralia.com.au**

Telephone **+61 2 8594 0400**
 Facsimile **+61 2 8594 0499**
 Email **au.environmental.sydney@sgs.com**

Project **E25203.G04 Barrenjoey Road, Palm Beach**
 Order Number **E25203.G04**
 Samples **3**

SGS Reference **SE255220 R0**
 Date Received **13/10/2023**
 Date Reported **20/10/2023**

COMMENTS

Accredited for compliance with ISO/IEC 17025 - Testing. NATA accredited laboratory 2562(4354).

SIGNATORIES



Huong CRAWFORD
 Production Manager



Ying Ying ZHANG
 Laboratory Technician

Soluble Anions (1:5) in Soil/Solids by Ion Chromatography [AN245] Tested: 20/10/2023

PARAMETER	UOM	LOR	BH201M_0.5-0.95	BH202M_2.5-2.6	BH204M_0.8-0.9
			SOIL - 4/10/2023 SE255220.001	SOIL - 5/10/2023 SE255220.002	SOIL - 10/10/2023 SE255220.003
Chloride	mg/kg	0.25	22	26	5.8
Sulfate	mg/kg	5	40	29	31

pH in soil (1:5) [AN101] Tested: 20/10/2023

PARAMETER	UOM	LOR	BH201M_0.5-0.95	BH202M_2.5-2.6	BH204M_0.8-0.9
			SOIL - 4/10/2023 SE255220.001	SOIL - 5/10/2023 SE255220.002	SOIL - 10/10/2023 SE255220.003
pH	pH Units	0.1	8.7	5.3	5.2

Conductivity and TDS by Calculation - Soil [AN106] Tested: 20/10/2023

PARAMETER	UOM	LOR	BH201M_0.5-0.95	BH202M_2.5-2.6	BH204M_0.8-0.9
			SOIL - 4/10/2023 SE255220.001	SOIL - 5/10/2023 SE255220.002	SOIL - 10/10/2023 SE255220.003
Conductivity of Extract (1:5 dry sample basis)	µS/cm	1	92	38	22

Moisture Content [AN002] Tested: 18/10/2023

PARAMETER	UOM	LOR	BH201M_0.5-0.95	BH202M_2.5-2.6	BH204M_0.8-0.9
			SOIL - 4/10/2023 SE255220.001	SOIL - 5/10/2023 SE255220.002	SOIL - 10/10/2023 SE255220.003
% Moisture	%w/w	1	13.1	15.1	21.6

METHOD

METHODOLOGY SUMMARY

- AN002** The test is carried out by drying (at either 40°C or 105°C) a known mass of sample in a weighed evaporating basin. After fully dry the sample is re-weighed. Samples such as sludge and sediment having high percentages of moisture will take some time in a drying oven for complete removal of water.
- AN101** pH in Soil Sludge Sediment and Water: pH is measured electrometrically using a combination electrode and is calibrated against 3 buffers purchased commercially. For soils, sediments and sludges, an extract with water (or 0.01M CaCl₂) is made at a ratio of 1:5 and the pH determined and reported on the extract. Reference APHA 4500-H+.
- AN106** Conductivity and TDS by Calculation: Conductivity is measured by meter with temperature compensation and is calibrated against a standard solution of potassium chloride. Conductivity is generally reported as µmhos/cm or µS/cm @ 25°C. For soils, an extract of as received sample with water is made at a ratio of 1:5 and the EC determined and reported on the extract, or calculated back to the as-received sample. Salinity can be estimated from conductivity using a conversion factor, which for natural waters, is in the range 0.55 to 0.75. Reference APHA 2510 B.
- AN245** Anions by Ion Chromatography: A water sample is injected into an eluent stream that passes through the ion chromatographic system where the anions of interest ie Br, Cl, NO₂, NO₃ and SO₄ are separated on their relative affinities for the active sites on the column packing material. Changes to the conductivity and the UV-visible absorbance of the eluent enable identification and quantitation of the anions based on their retention time and peak height or area. APHA 4110 B

FOOTNOTES

*	NATA accreditation does not cover the performance of this service.	-	Not analysed.	UOM	Unit of Measure.
**	Indicative data, theoretical holding time exceeded.	NVL	Not validated.	LOR	Limit of Reporting.
***	Indicates that both * and ** apply.	IS	Insufficient sample for analysis.	↑↓	Raised/lowered Limit of Reporting.
		LNR	Sample listed, but not received.		

Unless it is reported that sampling has been performed by SGS, the samples have been analysed as received. Solid samples expressed on a dry weight basis.

Where "Total" analyte groups are reported (for example, Total PAHs, Total OC Pesticides) the total will be calculated as the sum of the individual analytes, with those analytes that are reported as <LOR being assumed to be zero. The summed (Total) limit of reporting is calculated by summing the individual analyte LORs and dividing by two. For example, where 16 individual analytes are being summed and each has an LOR of 0.1 mg/kg, the "Totals" LOR will be 1.6 / 2 (0.8 mg/kg). Where only 2 analytes are being summed, the " Total" LOR will be the sum of those two LORs.

Some totals may not appear to add up because the total is rounded after adding up the raw values.

If reported, measurement uncertainty follow the ± sign after the analytical result and is expressed as the expanded uncertainty calculated using a coverage factor of 2, providing a level of confidence of approximately 95%, unless stated otherwise in the comments section of this report.

Results reported for samples tested under test methods with codes starting with ARS-SOP, radionuclide or gross radioactivity concentrations are expressed in becquerel (Bq) per unit of mass or volume or per wipe as stated on the report. Becquerel is the SI unit for activity and equals one nuclear transformation per second.

Note that in terms of units of radioactivity:

- a. 1 Bq is equivalent to 27 pCi
- b. 37 MBq is equivalent to 1 mCi

For results reported for samples tested under test methods with codes starting with ARS-SOP, less than (<) values indicate the detection limit for each radionuclide or parameter for the measurement system used. The respective detection limits have been calculated in accordance with ISO 11929.

The QC and MU criteria are subject to internal review according to the SGS QAQC plan and may be provided on request or alternatively can be found here: www.sgs.com.au/en-gb/environment-health-and-safety.

This document is issued by the Company under its General Conditions of Service accessible at www.sgs.com/en/Terms-and-Conditions.aspx. Attention is drawn to the limitation of liability, indemnification and jurisdiction issues defined therein.

Any holder of this document is advised that information contained hereon reflects the Company's findings at the time of its intervention only and within the limits of Client's instructions, if any. The Company's sole responsibility is to its Client only. Any unauthorized alteration, forgery or falsification of the content or appearance of this document is unlawful and offenders may be prosecuted to the fullest extent of the law .

This report must not be reproduced, except in full.

Atterberg Limits and Linear Shrinkage Report

Project: E25203.G04, 1112-1116 Barrenjoey Road, PALM BEACH

Project No.: 31380

Client: **EI AUSTRALIA**

Report No.: 23/3623

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009

Report Date: 30/10/2023


Test Method: AS1289.3.1.2,3.2.1,3.4.1,2.1.1

Page: 1 OF 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	8148D-L/1	8148D-L/2	8148D-L/3			
Sample Location	Borehole 201M	Borehole 202M	Borehole 204M			
Material Description	Silty Sandy Clay, red grey, with gravel (CL)	Clayey Sand, yellow brown, trace of gravel (SC)	Silty Clay, grey brown, with sand/gravel(CH)			
Depth (m)	1.5 - 1.95	1.5 - 1.95	0.2 - 0.3			
Sample Date	4/10/2023	4/10/2023	4/10/2023			
Sample History	Oven Dried	Oven Dried	Oven Dried			
Method of Preparation	Dry Sieved	Dry Sieved	Dry Sieved			
Liquid Limit (%)	32	34	51			
Plastic Limit (%)	19	22	23			
Plasticity Index	13	12	28			
Linear Shrinkage (%)	7.0	6.0	12.0			
Mould Size (mm)	127	127	127			
Crumbing	N	N	N			
Curling	N	N	N			

Remarks:


 Approved Signatory.....

Technician: AW

Orlando Mendoza - Laboratory Manager

Moisture Content of Soil and Aggregate Samples

Project: E25203.G04, 1112-1116 Barrenjoey Road, PALM BEACH

Project No.: 31380

Client: EI AUSTRALIA

Report No.: 23/3623

Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009

Report Date: 30/10/2023

Test Method: AS1289.2.1.1

Page: 2 OF 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	8148D-L/1	8148D-L/2	8148D-L/3			
Sample Location	Borehole 201M	Borehole 202M	Borehole 204M			
Material Description	Silty Sandy Clay, red grey, with gravel (CL)	Clayey Sand, yellow brown, trace of gravel (SC)	Silty Clay, grey brown, with sand/gravel(CH)			
Depth (mm)	1.5 - 1.95	1.5 - 1.95	0.2 - 0.3			
Sample Date	4/10/2023	4/10/2023	4/10/2023			
Moisture Content (%)	14.9	16.4	26.8			

Remarks:



Approved Signatory.....

Technician: AW

Orlando Mendoza - Laboratory Manager

Appendix D – Vibration Limits

German Standard DIN 4150 – Part 3: 1999 provides guideline levels of vibration velocity for evaluating the effects of vibration in structures. The limits presented in this standard are generally considered to be conservative.

The DIN 4150 values (maximum levels measured in any direction at the foundation, OR, maximum levels measured in (x) or (y) directions, in the plane of the uppermost floor), are summarised in **Table A** below.

It should be noted that peak vibration velocities higher than the minimum figures in **Table A** for low frequencies may be quite ‘safe’, depending on the frequency content of the vibration and the actual conditions of the structures.

It should also be noted that these levels are ‘safe limits’, up to which no damage due to vibration effects has been observed for the particular class of building. ‘Damage’ is defined by DIN 4150 to include even minor non-structural cracking in cement render, the enlargement of cracks already present, and the separation of partitions or intermediate walls from load bearing walls. Should damage be observed at vibration levels lower than the ‘safe limits’, then it may be attributed to other causes. DIN 4150 also states that when vibration levels higher than the ‘safe limits’ are present, it does not necessarily follow that damage will occur. Values given are only a broad guide.

Table A DIN 4150 – Structural Damage – Safe Limits for Building Vibration

Group	Type of Structure	Peak Vibration Velocity (mm/s)			
		At Foundation Level at a Frequency of:			Plane of Floor of Uppermost Storey
		Less than 10 Hz	10 Hz to 50 Hz	50 Hz to 100 Hz	All Frequencies
1	Buildings used for commercial purposes, industrial buildings and buildings of similar design	20	20 to 40	40 to 50	40
2	Dwellings and buildings of similar design and/or use	5	5 to 15	15 to 20	15
3	Structures that because of their particular sensitivity to vibration, do not correspond to those listed in Group 1 and 2 and have intrinsic value (e.g. buildings that are under a preservation order)	3	3 to 8	8 to 10	8

Note: For frequencies above 100 Hz, the higher values in the 50 Hz to 100 Hz column should be used.

Appendix E – Important Information

SCOPE OF SERVICES

The geotechnical report (“the report”) has been prepared in accordance with the scope of services as set out in the contract, or as otherwise agreed, between the Client And EI Australia (“EI”). The scope of work may have been limited by a range of factors such as time, budget, access and/or site disturbance constraints.

RELIANCE ON DATA

EI has relied on data provided by the Client and other individuals and organizations, to prepare the report. Such data may include surveys, analyses, designs, maps and plans. EI has not verified the accuracy or completeness of the data except as stated in the report. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations (“conclusions”) are based in whole or part on the data, EI will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented or otherwise not fully disclosed to EI.

GEOTECHNICAL ENGINEERING

Geotechnical engineering is based extensively on judgment and opinion. It is far less exact than other engineering disciplines. Geotechnical engineering reports are prepared for a specific client, for a specific project and to meet specific needs, and may not be adequate for other clients or other purposes (e.g. a report prepared for a consulting civil engineer may not be adequate for a construction contractor). The report should not be used for other than its intended purpose without seeking additional geotechnical advice. Also, unless further geotechnical advice is obtained, the report cannot be used where the nature and/or details of the proposed development are changed.

LIMITATIONS OF SITE INVESTIGATION

The investigation programme undertaken is a professional estimate of the scope of investigation required to provide a general profile of subsurface conditions. The data derived from the site investigation programme and subsequent laboratory testing are extrapolated across the site to form an inferred geological model, and an engineering opinion is rendered about overall subsurface conditions and their likely behaviour with regard to the proposed development. Despite investigation, the actual conditions at the site might differ from those inferred to exist, since no subsurface exploration program, no matter how comprehensive, can reveal all subsurface details and anomalies. The engineering logs are the subjective interpretation of subsurface conditions at a particular location and time, made by trained personnel. The actual interface between materials may be more gradual or abrupt than a report indicates.

SUBSURFACE CONDITIONS ARE TIME DEPENDENT

Subsurface conditions can be modified by changing natural forces or man-made influences. The report is based on conditions that existed at the time of subsurface exploration. Construction operations adjacent to the site, and natural events such as floods, or ground water fluctuations, may also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. EI should be kept apprised of any such events, and should be consulted to determine if any additional tests are necessary.

VERIFICATION OF SITE CONDITIONS

Where ground conditions encountered at the site differ significantly from those anticipated in the report, either due to natural variability of subsurface conditions or construction activities, it is a condition of the report that EI be notified of any variations and be provided with an opportunity to review the recommendations of this report. Recognition of change of soil and rock conditions requires experience and it is recommended that a suitably experienced geotechnical engineer be engaged to visit the site with sufficient frequency to detect if conditions have changed significantly.

REPRODUCTION OF REPORTS

This report is the subject of copyright and shall not be reproduced either totally or in part without the express permission of this Company. Where information from the accompanying report is to be included in contract documents or engineering specification for the project, the entire report should be included in order to minimize the likelihood of misinterpretation from logs.

REPORT FOR BENEFIT OF CLIENT

The report has been prepared for the benefit of the Client and no other party. EI assumes no responsibility and will not be liable to any other person or organisation for or in relation to any matter dealt with or conclusions expressed in the report, or for any loss or damage suffered by any other person or organisation arising from matters dealt with or conclusions expressed in the report (including without limitation matters arising from any negligent act or omission of EI or for any loss or damage suffered by any other party relying upon the matters dealt with or conclusions expressed in the report). Other parties should not rely upon the report or the accuracy or completeness of any conclusions and should make their own inquiries and obtain independent advice in relation to such matters.

OTHER LIMITATIONS

EI will not be liable to update or revise the report to take into account any events or emergent circumstances or fact occurring or becoming apparent after the date of the report.