

## GEOTECHNICAL ASSESSMENT REPORT

for

## PROPOSED ALTERATIONS AND ADDITIONS

at

## 24 DE LAURET AVENUE, NEWPORT, NSW

**Prepared For** 

Simon Cave & Abby Beck

Project No.: 2023-173 September 2023

#### **Document Revision Record**

Issue No	Date	Details of Revisions
0	26 <sup>th</sup> September 2023	Original issue

#### Copyright

© This Report is the copyright of Crozier Geotechnical Consultants. Any unauthorised reproduction or usage by any person other than the addressee is strictly prohibited.

#### GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1 – To be submitted with Development Application

	Development Application for				
	Name of Applicant				
	Address of site 24 De Lauret Avenue, Newport, NSW				
	ion made by geotechnical engineer or engineering geologist or coastal engineer (where applicable) as part of a nical report				
<del>geotechni</del> 2009 and	Crozier on behalf ofCrozier Geotechnical Consultantson this the 26 <sup>th</sup> September 2023_ certify that ical engineer or engineering geologist or coastal engineer as defined by the Geotechnical Risk Management Policy for Pit 1 am authorised by the above erganisation/company to issue this document and to certify that the erganisation/company has a nal indemnity policy of at least \$2million. 1:	ttwater -			
	have prepared the detailed Geotechnical Report referenced below in accordance with the Australia Geomechanics S Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management Policy for Pittwater - 2009	iociety's			
	am willing to technically verify that the detailed Geotechnical Report referenced below has been prepared in accordance Australian Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Mana Policy for Pittwater - 2009				
	6.0 of the Geotechnical Risk Management Policy for Pittwater - 2009. I confirm that the results of the risk assessment for the pi	roposed			
المعط					
	have provided the coastal process and coastal forces analysis for inclusion in the Geotechnical Report				
Geotechn	nical Report Details:				
	Report Title: Geotechnical Assessment for Proposed Alterations and Additions				
	Report Date:         26 <sup>th</sup> September 2023         Project No.:         2023-173				
	Author: J. Dee and T. Crozier				
	Author's Company/Organisation: Crozier Geotechnical Consultants				
Documen	ntation which relate to or are relied upon in report preparation:				
	Architectural Drawings - Contemporary Architecture, Project No.: 2221, Drawing No.: DA01 -				
	DA17, Dated: 25/09/2023				
	Site Survey – Hammond Smealie & Co Pty Ltd, Drawing no.: 15280, Dated: 19/04/2022				
□ □ Geotechn	have examined the site and the proposed development in detail and have carried out a risk assessment in accordance with Section 6.0 of the Geotechnical Risk Management Policy for Pittwater - 2009. I confirm that the results of the risk assessment for the proposed development are in compliance with the Geotechnical Risk Management Policy for Pittwater - 2009 and further detailed geotechnical reporting is not required for the subject site.         have examined the site and the proposed development/alteration in detail and I am of the opinion that the Development Application only involves Minor Development/Alteration that does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 requirements.         have examined the site and the proposed development/alteration is separate from and is not affected by a Geotechnical Hazard and does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Report or Risk Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 requirements.         have provided the coastal process and coastal forces analysis for inclusion in the Geotechnical Report         Geotechnical Report Details:         Report Title:       Geotechnical Assessment for Proposed Alterations and Additions         Report Date:       26 <sup>th</sup> September 2023         Project No.:       2023-173				

I am aware that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support of a Development Application for this site and will be relied on by Pittwater Council as the basis for ensuring that the Geotechnical Risk Management aspects of the proposed development have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

NUSTPALIAN ΙΝΣΡΤΌΤΕ ΟΕ Signature ...... GLOSCIENTISTS  $\alpha_{i}$ 10.00 The second se Name ... Troy Crozier. . ° . Chartered Professional Status... RPGeo (AIG) ej. Membership No. ... 10197. ····TROY·CROZIER Company... Crozier Geotochnical Consultants

## GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1(a) - Checklist of Requirements for Geotechnical Risk Management Report for Development Application -

	Development Application for
	Name of Applicant Address of site24 De Lauret Avenue, Newport, NSW
The follow checklist i	ing checklist covers the minimum requirements to be addressed in a Geotechnical Risk Management Geotechnical Report. This s to accompany the Geotechnical Report and its certification (Form No. 1).
Geotechr	ical Report Details:
	Report Title:       Geotechnical Assessment for Proposed Alterations and Additions         Report Date:       26 <sup>th</sup> September 2023       Project No.: 2023-173         Author:       J. Dee and T. Crozier
	Author's Company/Organisation: Crozier Geotechnical Consultants
Please m	ark appropriate box
	Comprehensive site mapping conducted31 <sup>st</sup> August 2023 (date)
	Mapping details presented on contoured site plan with geomorphic mapping to a minimum scale of 1:200 (as appropriate) Subsurface investigation required
	No Justificationrelatively minor works
	Yes Date conducted
	Geotechnical model developed and reported as an inferred subsurface type-section Geotechnical hazards identified Above the site On the site Below the site Beside the site
	Geotechnical hazards described and reported Risk assessment conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 Consequence analysis Frequency analysis
	Risk calculation Risk assessment for property conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 Risk assessment for loss of life conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 Assessed risks have been compared to "Acceptable Risk Management" criteria as defined in the Geotechnical Risk Management Policy for Pittwater - 2009 Opinion has been provided that the design can achieve the "Acceptable Risk Management" criteria provided that the specified
	conditions are achieved. Design Life Adopted: 100 years Other
	Geotechnical Conditions to be applied to all four phases as described in the Geotechnical Risk Management Policy for Pittwater - 2009 have been specified Additional action to remove risk where reasonable and practical have been identified and included in the report. Risk assessment within Bushfire Asset Protection Zone.
geotechnic for the life	e that Pittwater Council will rely on the Geotechnical Report, to which this checklist applies, as the basis for ensuring that the al risk management aspects of the proposal have been adequately addressed to achieve an "Acceptable Risk Management" level of the structure, taken as at least 100 years unless, there is a structure, taken as at least 100 years unless, there is a structure is a stru

d to remove foreseeable risk	X-11 .
Signature	$\langle \bigcirc$
NameTroy Crozier	
Chartered Professional StatusRPGeo (AIG)	151
Membership No10197.03	lang f
Company Crozier Geotochnical Consultants	Sport of
and the second sec	р. <sup>.</sup> .



## **TABLE OF CONTENTS**

1.0	INTR	ODUCTION	Page 1
2.0	SITE	FEATURES	
	2.1.	Description	Page 2
	2.2.	Geology	Page 2
3.0	FIELI	D WORK	
	3.1.	Methods	Page 2
	3.2.	Field Observations	Page 3
4.0	COM	MENTS	
	4.1.	Geotechnical Model	Page 5
	4.2.	Geotechnical Assessment	Page 5
	4.3.	Site Specific Risk Assessment	Page 6
	4.4.	Conditions Relating to Design and Construction Monitoring	Page 7
	4.5.	Design Life of Structure	Page 7
5.0	CON	CLUSION	Page 8
6.0	REFE	RENCES	Page 9

#### APPENDICES

- 2 Risk Assessment Tables
- **3** AGS Terms and Descriptions
- 4 Hillside Construction Guidelines



**Date:** 26<sup>th</sup> September 2023 **Project No:** 2023-173 **Page:** 1 of 9

## GEOTECHNICAL ASSESSMENT FOR PROPOSED ALTERATIONS AND ADDITIONS 24 DE LAURET AVENUE, NEWPORT, NSW

#### **1. INTRODUCTION:**

This report details the results of a landslip assessment required by Northern Beaches Council for proposed alterations and additions at 24 De Lauret Avenue, Newport, NSW. The assessment was undertaken by Crozier Geotechnical Consultants (CGC) at the written request of Contemporary Architecture on behalf of the clients Simon Cave and Abby Beck.

It is understood that the proposed works involve minor alterations and additions to the existing site structure which will include the construction of a new laundry room on Level 1. The proposed works will only require minor bulk excavation to  $\leq 0.5$ m depth.

The site is located within the H1 (highest category) landslip hazard zone as identified within Northern Beaches Councils precinct (Geotechnical Risk Management Policy for Pittwater – 2009).

To meet the Councils Policy requirements for land classified as H1 we will need to provide a detailed Geotechnical Report which meets the requirements of Paragraph 6.5 of that policy. This report must include a landslide risk assessment to the methods of AGS 2007 for the site and proposed works, plans, geological sections and provide recommendations for construction and to ensure stability is maintained for a preferred design life of 100 years. It is recommended that the client make themselves aware of the Policy and its requirements.

The proposed works are relatively minor from a geotechnical perspective and appear unlikely to be affected by a significant geotechnical hazard. As this is the case then reporting has be reduced in line with Paragraph 6.2 and 6.3 of the Councils Policy.

The investigation comprised:

- a) A detailed geotechnical inspection and mapping of the site and adjacent properties by a Geotechnical Engineer.
- b) Review of CGC database on local geotechnical conditions



The following plans were supplied and relied upon for the work:

- Architectural Drawings Contemporary Architecture, Project No.: 2221, Drawing No.: DA01 – DA17, Dated: 25/09/2023
- Site Survey Hammond Smealie & Co Pty Ltd, Drawing no.: 15280, Dated: 19/04/2022

#### 2. SITE FEATURES:

#### 2.1. Description:

The site is an irregular shaped block of land situated on the high northern side of the road within steep south to south west dipping topography at mid slope level. Site levels vary broadly from a low of approximately RL 43m along the front southern boundary to a high in excess of RL 66.03m with the high northernmost reaches not surveyed due to dense vegetation.

#### 2.2. Geology:

Reference to the Sydney 1:100,000 Geological Series sheet 9130 indicates that the site is underlain by Newport Formation (Upper Narrabeen Group) rock (Rnn) which is of middle Triassic Age. The Newport Formation typically comprises interbedded laminite, shale and quartz to lithic quartz sandstones and pink clay pellet sandstones that tend to deep weathering and produce a weak rock mass containing clay bands and fracturing. Deposits of the Hawkesbury Sandstone are shown to the east (upslope) of the site which typically comprises medium to coarse grained quartz sandstone with minor lenses of shale and laminite. Morphological features often associated with the weathering of Hawkesbury Sandstone are the formation of near flat ridge tops with steep angular side slopes that consist of sandstone terraces and cliffs in part covered with sandy colluvium. The terraced areas often contain thin sandy clay to clayey sand residual soil profiles with intervening rock (ledge) outcrops.

#### **3. FIELD WORK:**

#### 3.1. Methods:

The field investigation comprised a walk over inspection and mapping of the site and limited inspection of adjacent properties on the 31<sup>st</sup> August 2023 by a Geotechnical Engineer which included a photographic record of site conditions as well as geological/geomorphological mapping of the site and adjacent land.

Explanatory notes are included in Appendix: 1.



#### 3.2. Field Observations:

The site is accessed via De Lauret Avenue which comprises a relatively flat bituminous sealed pavement separated from the site by a concrete kerb, gutter and driveway, shared with No. 20, 22 and 26 De Lauret Avenue. There were no signs of significant cracking observed within the roadway to indicate any impending geotechnical concern however some minor cracking was observed within the shared driveway slab.

A timber garage structure is situated adjacent to the front boundary with a set of stairs extending up into the site through a steep south to south west dipping, relatively densely vegetated slope. The garage is anticipated to have been excavated up to 2.50m below pre-development ground levels. Photograph 1 below provides a view of the front of the site from the roadway.



Photograph 1: View of the front of the site, looking broadly north from the roadway

Multiple sandstone boulders were observed within the front garden of the site with all appearing to be relatively embedded below ground levels and none exhibiting any signs of impending instability.

The main site dwelling comprises a two and three storey timber and steel structure of anticipated construction age <30 years that is suspended above ground surface via steel columns and founded via a series of concrete piers, embedded at unknown depths. The dwelling appeared to be in good condition with no signs of excessive settlement or cracking to indicate any underlying geotechnical concern.



The rear of the site comprises a steep south to south west dipping, densely vegetated slope that extends from the rear of the site dwelling to the rear boundary. The slope featured multiple sandstone outcrops interpreted as detached boulders as well as multiple large trees, one of which was >20 metres in height and appeared to be deceased. There were no signs of significant potential instability or significant seepage/water flow observed within the rear garden of site.

The neighbouring dwelling to the east (No. 26 De Lauret Avenue) contains a four and five storey masonry dwelling setback from the shared boundary by a minimum of 1.75m. The property is at similar levels as the site along the shared boundary. The visible aspects of the structures appeared in good condition with no signs of cracking or excessive settlement to indicate any impending geotechnical concern. No boulders or significant stability hazards were observed on the adjacent slope.

The neighbouring property immediately to the west (No. 22 De Lauret Avenue) is a battle-axe style block with access corridor along the site western boundary. It contains a single storey masonry carport structure and an inclinator immediately adjacent to the shared boundary with the property dwelling unobservable due to boundary setbacks and vegetation. No. 20 De Lauret Avenue, located further west, does not share a common boundary with the site however features a one and two storey masonry dwelling setback from the western site boundary by approximately 5.00m. Both properties are at similar levels as the site along the shared boundary and the visible aspects appeared to be in good condition and did not exhibit any signs of impending geotechnical concern.

Three properties to the north and east(No. 53, 55 & 57 Loombah Road) share a common boundary with the site with all unobservable due to elevations, setbacks and vegetation. Based on available imagery, the properties all contain dwelling structures setback from the shared boundary >10m.

The neighbouring buildings and properties were only inspected from within the site or from the road reserve however the visible aspects did not show any signs of large-scale slope instability or other major geotechnical concerns which would impact the site.



#### 4. COMMENTS:

#### 4.1. Geotechnical Model:

Based on previous investigations nearby, the sub-surface conditions within the site are expected to comprise predominantly fill and colluvial soils over residual soils and sandstone bedrock of at least low strength, with the bedrock potentially at depths in excess of 2.00m however variability can be high within the local geological sequence.

#### 4.2. Geotechnical Assessment:

The geotechnical inspection did not identify any signs of previous or impending large scale or deep-seated landslip instability within the site or adjacent properties. The existing main residential structure appears to be >15 years of age and shows no signs of slope movement whilst there are no indications of excess surface stormwater flow, groundwater seepage or erosion.

The proposed works involve the rear northern extension of the existing Level 1 to facilitate the construction of a laundry room. The proposed works will require a minor localised excavation (<0.50m in depth) and will be entirely restricted to the rear garden of site with setbacks to neighbouring boundaries a minimum of approximately 5.00m.

The excavation is anticipated to extend entirely through fill and colluvial soils, potentially featuring sandstone boulders. Safe short term batter slopes of 1.00:1.00 (H:V) are anticipated to be readily achievable within the confines of site with respect to the neighbouring properties.

It is anticipated that due to the nature of the excavation that the majority of boulders within the vicinity of the footprint of proposed works site will be removed. Boulders within a 1.0V:1.5H influence zone of an excavation base are recommended to be removed or secured by way of rock bolts and/or underpinning prior to or during any excavation on site. This will help to prevent potential movement both during and after excavation works. Boulders that are determined to be retained during the excavation and construction phase are subject to further geotechnical inspection by CGC.

Additionally multiple large trees were observed within the rear garden of the site with a potentially deceased gumtree of height >20m situated in the vicinity of proposed works. Therefore, the proposed excavation has potential to undermine this tree with any collapse likely having major consequences. It is recommended that an arborist be engaged as to the health and stability of any trees with respect to the proposed works within a 1.0 V: 1.5 H influence zone of the base of the excavation footprint.



Any new footings are recommended to extend through any topsoil/fill as well as colluvium and residual soils encountered to bear within/atop competent sandstone bedrock. Investigation was not undertaken into footing style, depth of foundation condition of the existing dwelling structure however, based on the age and construction style of the building it is anticipated that it is founded atop sandstone bedrock. The new eastern dwelling extension should have a matching foundation as the existing dwelling unless differential settlement is factored into structural design.

The recommendations and conclusions in this report are based on an assessment utilizing only surface observations and a limited inspection of neighbouring properties. However, based on the site geological and topographical conditions, along with existing structures, it is considered that the updated residential structure will have a design life of 50 years from completion of the proposed works.

The proposed development is suitable for the site and can be completed with negligible risk to neighbouring properties provided the recommendations and conclusions of this report are adhered to.

#### 4.3. Site Specific Risk Assessment:

Based on our site investigation we have identified the following geological/geotechnical landslip hazards which need to be considered in relation to the existing site and the proposed works. The hazards are:

A. Earth slide  $(<5m^3)$  of fill and colluvial soils within existing slope.

A qualitative assessment of risk to life and property related to these hazards is presented in Table A and B, Appendix: 3, and is based on methods outlined in Appendix: C of the Australian Geomechanics Society (AGS) Guidelines for Landslide Risk Management 2007. AGS terms and their descriptions are provided in Appendix: 4.

The Risk to Life from Hazard A was estimated to be up to **1.41 x 10<sup>-6</sup>**, whilst the Risk to Property was considered to be **'Low'**. The hazard was therefore considered to be **'Unacceptable**' when assessed against the criteria of the AGS 2007 and the Geotechnical Risk Management Policy.

The above risk to life and property from Hazard A has been assessed assuming a "worst case" soil profile and surface stormwater flow as well as insufficient retention systems constructed within the site. Where appropriate retention systems are installed the anticipated risks are expected to reduce within acceptable levels.



#### 4.4. Conditions Relating to Design and Construction Monitoring:

If requested by Council to complete Forms: 2b and 3 as part of construction, building and post-construction certificate requirements of the Councils Geotechnical Risk Management Policy 2009, it will be necessary for Crozier Geotechnical Consultants to:

- 1. Review and approve the structural drawings for compliance with the recommendations of this report,
- 2. Inspect new footings before concrete or steel are placed to verify their bearing capacity and the in-situ nature of the founding strata,

The client and builder should make themselves familiar with the Councils Geotechnical Policy. Crozier Geotechnical Consultants can <u>not</u> sign Form: 3 of the policy for an occupation certificate if it has not reviewed structural designs and been called to site to undertake any required inspections.

#### 4.5. Design Life of Structure:

We have interpreted the design life requirements specified within Council's Risk Management Policy to refer to structural elements designed to support the existing structures, control stormwater and maintain the risk of instability within the 'Acceptable' risk management criteria. Specific structures and features that may affect the maintenance and stability of the site in relation to the proposed and existing development are considered to comprise:

- stormwater and subsoil drainage systems,
- retaining walls and instability,
- maintenance of trees/vegetation on this and adjacent properties.

Man-made features should be designed and maintained for a design life consistent with surrounding structures (as per AS2870 - 2011 (50 years)). It will be necessary for the structural and geotechnical engineers to incorporate appropriate design and inspection procedures during the construction period. Additionally, the property owner should adopt and implement a maintenance and inspection program.

If this maintenance and inspection schedule are not maintained the design life of the property cannot be attained. A recommended program is given in Table: C in Appendix: 3 and should also include the following guidelines.

- The conditions on the block don't change from those present at the time this report was prepared, except for the changes due to this development.
- There is no change to the property due to an extraordinary event external to this site
- The property is maintained in good order and in accordance with the guidelines set out in;
  - a) CSIRO sheet BTF 18
  - b) Australian Geomechanics "Landslide Risk Management" Volume 42, March 2007.
  - c) AS 2870-2011, Australian Standard for Residential Slabs and Footings



Where changes to site conditions are identified during the maintenance and inspection program, reference should be made to relevant professionals (e.g. structural engineer, geotechnical engineer or Council). Where the property owner has any lack of understanding or concerns about the implementation of any component of the maintenance and inspection program the relevant engineer should be contacted for advice or to complete the component. It is assumed that Council will control development on neighbouring properties, carry out regular inspections and maintenance of the road verge, stormwater systems and large trees on public land adjacent to the site so as to ensure that stability conditions do not deteriorate with potential increase in risk level to the site.

Also, individual Government Departments will maintain public utilities in the form of power lines, water and sewer mains to ensure they don't leak and increase either the local groundwater level or landslide potential.

#### 5. CONCLUSION:

The inspection and assessment identified that the site is located within steep south dipping slopes however it showed no obvious slope movement, excess surface stormwater flow or seepage, erosion or instability within the site or adjacent properties. Indications of existing landslip hazards were not observed, and the proposed works are relatively minor from a geotechnical point of view and should not create instability.

It is anticipated that due to the nature of the excavation that the majority of boulders within the vicinity of the footprint of proposed works site will be removed. Boulders within a 1.0V:1.5H influence zone of an excavation base are recommended to be removed or secured by way of rock bolts and/or underpinning prior to or during any excavation on site.

It is recommended that an arborist be engaged as to the health and stability of any trees with respect to the proposed works within a 1.0 V: 1.5 H influence zone of the base of the excavation footprint.

The risks associated with the proposed development can be maintained within 'Acceptable' risk management criteria levels with negligible impact to neighbouring or site structures provided the recommendations of this report and any future geotechnical directive are implemented. As such the site is considered suitable for the proposed construction works provided that the recommendations outlined in this report are followed.

non

Prepared by: James Dee Geotechnical Engineer

T by

Reviewed by: Troy Crozier Principal Engineering Geologist MAIG. RPGeo; 10197

Project No: 2023-173 Newport, September 2023



#### 6.0. REFERENCES:

- 1. Australian Geomechanics Society 2007, "Landslide Risk Assessment and Management", Australian Geomechanics Journal Vol 42, No 1, March 2007.
- 2. Geotechnical Risk Management Policy for Pittwater, 2009.



## Appendix 1



## NOTES RELATING TO THIS REPORT

#### Introduction

These notes have been provided to amplify the geotechnical report in regard to classification methods, specialist field procedures and certain matters relating to the Discussion and Comments section. Not all, of course, are necessarily relevant to all reports.

Geotechnical reports are based on information gained from limited subsurface test boring and sampling, supplemented by knowledge of local geology and experience. For this reason, they must be regarded as interpretive rather than factual documents, limited to some extent by the scope of information on which they rely.

#### **Description and classification Methods**

The methods of description and classification of soils and rocks used in this report are based on Australian Standard 1726, Geotechnical Site Investigation Code. In general, descriptions cover the following properties - strength or density, colour, structure, soil or rock type and inclusions.

Soil types are described according to the predominating particle size, qualified by the grading of other particles present (eg. Sandy clay) on the following bases:

Soil Classification	Particle Size
Clay	less than 0.002 mm
Silt	0.002 to 0.06 mm
Sand	0.06 to 2.00 mm
Gravel	2.00 to 60.00mm

Cohesive soils are classified on the basis of strength either by laboratory testing or engineering examination. The strength terms are defined as follows:

	Undrained
<b>Classification</b>	<u>Shear Strength kPa</u>
Very soft	Less than 12
Soft	12 - 25
Firm	25 – 50
Stiff	50 – 100
Very stiff	100 - 200
Hard	Greater than 200

Non-cohesive soils are classified on the basis of relative density, generally from the results of standard penetration tests (SPT) or Dutch cone penetrometer tests (CPT) as below:

	<u>SPT</u>	<u>CPT</u>
Relative Density	"N" Value (blows/300mm)	Cone Value (Qc – MPa)
Very loose	less than 5	less than 2
Loose	5 – 10	2 – 5
Medium dense	10 – 30	5 -15
Dense	30 – 50	15 – 25
Very dense	greater than 50	greater than 25

Rock types are classified by their geological names. Where relevant, further information regarding rock classification is given on the following sheet.



#### Sampling

Sampling is carried out during drilling to allow engineering examination (and laboratory testing where required) of the soil or rock.

Disturbed samples taken during drilling to allow information on colour, type, inclusions and, depending upon the degree of disturbance, some information on strength and structure.

Undisturbed samples are taken by pushing a thin-walled sample tube into the soil and withdrawing a sample of the soil in a relatively undisturbed state. Such samples yield information on structure and strength, and are necessary for laboratory determination of shear strength and compressibility. Undisturbed sampling is generally effective only in cohesive soils.

#### **Drilling Methods**

The following is a brief summary of drilling methods currently adopted by the company and some comments on their use and application.

**Test Pits** – these are excavated with a backhoe or a tracked excavator, allowing close examination of the insitu soils if it is safe to descent into the pit. The depth of penetration is limited to about 3m for a backhoe and up to 6m for an excavator. A potential disadvantage is the disturbance caused by the excavation.

**Large Diameter Auger (eg. Pengo)** – the hole is advanced by a rotating plate or short spiral auger, generally 300mm or larger in diameter. The cuttings are returned to the surface at intervals (generally of not more than 0.5m) and are disturbed but usually unchanged in moisture content. Identification of soil strata is generally much more reliable than with continuous spiral flight augers, and is usually supplemented by occasional undisturbed tube sampling.

**Continuous Sample Drilling** – the hole is advanced by pushing a 100mm diameter socket into the ground and withdrawing it at intervals to extrude the sample. This is the most reliable method of drilling soils, since moisture content is unchanged and soil structure, strength, etc. is only marginally affected.

**Continuous Spiral Flight Augers –** the hole is advanced using 90 – 115mm diameter continuous spiral flight augers which are withdrawn at intervals to allow sampling or insitu testing. This is a relatively economical means of drilling in clays and in sands above the water table. Samples are returned to the surface, or may be collected after withdrawal of the auger flights, but they are very disturbed and may be contaminated. Information from the drilling (as distinct from specific sampling by SPT's or undisturbed samples) is of relatively lower reliability, due to remoulding, contamination or softening of samples by ground water.

**Non-core Rotary Drilling** - the hole is advanced by a rotary bit, with water being pumped down the drill rods and returned up the annulus, carrying the drill cuttings. Only major changes in stratification can be determined from the cuttings, together with some information from 'feel' and rate of penetration.

**Rotary Mud Drilling** – similar to rotary drilling, but using drilling mud as a circulating fluid. The mud tends to mask the cuttings and reliable identification is again only possible from separate intact sampling (eg. From SPT).

**Continuous Core Drilling** – a continuous core sample is obtained using a diamond-tipped core barrel, usually 50mm internal diameter. Provided full core recovery is achieved (which is not always possible in very weak rocks and granular soils), this technique provides a very reliable (but relatively expensive) method of investigation.

### **Standard Penetration Tests**

Standard penetration tests (abbreviated as SPT) are used mainly in non-cohesive soils, but occasionally also in cohesive soils as a means of determining density or strength and also of obtaining a relatively undisturbed sample. The test procedures is described in Australian Standard 1289, "Methods of Testing Soils for Engineering Purposes" – Test 6.3.1.

The test is carried out in a borehole by driving a 50mm diameter split sample tube under the impact of a 63kg hammer with a free fall of 760mm. It is normal for the tube to be driven in three successive 150mm increments and the 'N' value is taken



as the number of blows for the last 300mm. In dense sands, very hard clays or weak rock, the full 450mm penetration may not be practicable and the test is discontinued.

The test results are reported in the following form.

- In the case where full penetration is obtained with successive blow counts for each 150mm of say 4, 6 and 7 as 4, 6, 7 then N = 13
- In the case where the test is discontinued short of full penetration, say after 15 blows for the first 150mm and 30 blows for the next 40mm then as 15, 30/40mm.

The results of the test can be related empirically to the engineering properties of the soil. Occasionally, the test method is used to obtain samples in 50mm diameter thin wall sample tubes in clay. In such circumstances, the test results are shown on the borelogs in brackets.

#### **Cone Penetrometer Testing and Interpretation**

Cone penetrometer testing (sometimes referred to as Dutch Cone – abbreviated as CPT) described in this report has been carried out using an electrical friction cone penetrometer. The test is described in Australia Standard 1289, Test 6.4.1.

In tests, a 35mm diameter rod with a cone-tipped end is pushed continually into the soil, the reaction being provided by a specially designed truck or rig which is fitted with an hydraulic ram system. Measurements are made of the end bearing resistance on the cone and the friction resistance on a separte 130mm long sleeve, immediately behind the cone. Transducers in the tip of the assembly are connected buy electrical wires passing through the centre of the push rods to an amplifier and recorder unit mounted on the control truck.

As penetration occurs (at a rate of approximately 20mm per second) their information is plotted on a computer screen and at the end of the test is stored on the computer for later plotting of the results.

The information provided on the plotted results comprises: -

- Cone resistance the actual end bearing force divided by the cross-sectional area of the cone expressed in MPa.
- Sleeve friction the frictional force on the sleeve divided by the surface area expressed in kPa.
- Friction ratio the ratio of sleeve friction to cone resistance, expressed in percent.

There are two scales available for measurement of cone resistance. The lower scale (0 - 5 MPa) is used in very soft soils where increased sensitivity is required and is shown in the graphs as a dotted line. The main scale (0 - 50 MPa) is less sensitive and is shown as a full line. The ratios of the sleeve friction to cone resistance will vary with the type of soil encountered, with higher relative friction in clays than in sands. Friction ratios 1% - 2% are commonly encountered in sands and very soft clays rising to 4% - 10% in stiff clays.

In sands, the relationship between cone resistance and SPT value is commonly in the range: -

- Qc (MPa) = (0.4 to 0.6) N blows (blows per 300mm)
- In clays, the relationship between undrained shear strength and cone resistance is commonly in the range: -

Qc = (12 to 18) Cu

Interpretation of CPT values can also be made to allow estimation of modulus or compressibility values to allow calculations of foundation settlements.

Inferred stratification as shown on the attached reports is assessed from the cone and friction traces and from experience and information from nearby boreholes, etc. This information is presented for general guidance, but must be regarded as being to some extent interpretive. The test method provides a continuous profile of engineering properties, and where precise information on soil classification is required, direct drilling and sampling may be preferable.

#### **Dynamic Penetrometers**

Dynamic penetrometer tests are carried out by driving a rod into the ground with a falling weight hammer and measuring the blows for successive 150mm increments of penetration. Normally, there is a depth limitation of 1.2m but this may be extended in certain conditions by the use of extension rods.



Two relatively similar tests are used.

- Perth sand penetrometer a 16mm diameter flattened rod is driven with a 9kg hammer, dropping 600mm (AS1289, Test 6.3.3). The test was developed for testing the density of sands (originating in Perth) and is mainly used in granular soils and filling.
- Cone penetrometer (sometimes known as Scala Penetrometer) a 16mm rod with a 20mm diameter cone end is driven with a 9kg hammer dropping 510mm (AS 1289, Test 6.3.2). The test was developed initially for pavement sub-grade investigations, and published correlations of the test results with California bearing ratio have been published by various Road Authorities.

### Laboratory Testing

Laboratory testing is generally carried out in accordance with Australian Standard 1289 "Methods of Testing Soil for Engineering Purposes". Details of the test procedure used are given on the individual report forms.

#### **Borehole Logs**

The bore logs presented herein are an engineering and/or geological interpretation of the subsurface conditions, and their reliability will depend to some extent on frequency of sampling and the method of drilling. Ideally, continuous undisturbed sampling or core drilling will provide the most reliable assessment, but this is not always practicable, or possible to justify on economic grounds. In any case, the boreholes represent only a very small sample of the total subsurface profile.

Interpretation of the information and its application to design and construction should therefore take into account the spacing of boreholes, the frequency of sampling and the possibility of other than 'straight line' variations between the boreholes.

Details of the type and method of sampling are given in the report and the following sample codes are on the borehole logs where applicable:

- D **Disturbed Sample** Е Environmental sample В Bulk Sample PP Pocket Penetrometer Test SPT Standard Penetration Test U50 50mm Undisturbed Tube Sample 63mm " " " " U63 Core С
- DT Diatube

#### Ground Water

Where ground water levels are measured in boreholes there are several potential problems:

- In low permeability soils, ground water although present, may enter the hole slowly or perhaps not at all during the time it is left open.
- A localised perched water table may lead to an erroneous indication of the true water table.
- Water table levels will vary from time to time with seasons or recent weather changes. They may not be the same at the time of construction as are indicated in the report.
- The use of water or mud as a drilling fluid will mask any ground water inflow. Water has to be blown out of the hole and drilling mud must first be washed out of the hole if water observations are to be made. More reliable measurements can be made by installing standpipes which are read at intervals over several days, or perhaps weeks for low permeability soils. Piezometers, sealed in a particular stratum, may be interference from a perched water table.

#### **Engineering Reports**

Engineering reports are prepared by qualified personnel and are based on the information obtained and on current engineering standards of interpretation and analysis. Where the report has been prepared for a specific design proposal (eg. A three-storey building), the information and interpretation may not be relevant if the design proposal is changed (eg. to a twenty-storey building). If this happens, the Company will be pleased to review the report and the sufficiency of the investigation work.



Every care is taken with the report as it relates to interpretation of subsurface condition, discussion of geotechnical aspects and recommendations or suggestions for design and construction. However, the Company cannot always anticipate or assume responsibility for:

- unexpected variations in ground conditions the potential for this will depend partly on bore spacing and sampling frequency,
- changes in policy or interpretation of policy by statutory authorities,
- the actions of contractors responding to commercial pressures,

If these occur, the Company will be pleased to assist with investigation or advice to resolve the matter.

#### **Site Anomalies**

In the event that conditions encountered on site during construction appear to vary from those which were expected from the information contained in the report, the Company requests that it immediately be notified. Most problems are much more readily resolved when conditions are exposed than at some later stage, well after the event.

#### **Reproduction of Information for Contractual Purposes**

Attention is drawn to the document "Guidelines for the Provision of Geotechnical Information in Tender Documents", published by the Institution of Engineers Australia. Where information obtained from this investigation is provided for tendering purposes, it is recommended that all information, including the written report and discussion, be made available. In circumstances where the discussion or comments section is not relevant to the contractual situation, it may be appropriate to prepare a special ally edited document. The Company would be pleased to assist in this regard and/or to make additional report copies available for contract purposes at a nominal charge.

#### Site Inspection

The Company will always be pleased to provide engineering inspection services for geotechnical aspects of work to which this report is related. This could range from a site visit to confirm that conditions exposed are as expected, to full time engineering presence on site.



## PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007





(after V Gardiner & R V Dackombe (1983).Geomorphological Field Manual. George Allen & Unwin).

Australian Geomechanics Vol 42 No 1 March 2007

#### PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

#### APPENDIX E - GEOLOGICAL AND GEOMORPHOLOGICAL MAPPING SYMBOLS AND TERMINOLOGY



Examples of Mapping Symbols (after Guide to Slope Risk Analysis Version 3.1 November 2001, Roads and Traffic Authority of New South Wales).

Australian Geomechanics Vol 42 No 1 March 2007



## Appendix 2

#### TABLE : A

#### Landslide risk assessment for Risk to life

HAZARD	Description	Impacting	Likelihood of Slide	Spatial Impact of Slide		Occupancy	Evacuation	Vulnerability	Risk to Life
	Landslip (earth slide <5m <sup>3</sup> ) of fill and colluvial soils within existing slope			a) Dwelling situated below steep colluvial slope, impact a 10%		a) Person in dwelling 18hr/day avge	<ul> <li>a) Likely to not evacuate</li> </ul>	a) Person in dwelling, minor damage only	
			Possible	Prob. of Impact	Impacted				
		a) Existing site dwelling	0.001	0.50	0.10	0.7500	0.75	0.05	1.41E-06

\* hazards considered in current condition and/or without remedial/stabilisation measures or poor support systems

\* likelihood of occurrence for design life of 100 years \* Spatial Impact - Probaility of Impact r

Probaility of Impact refers to slide impacting structure/area expressed as a % (i.e. 1.00 = 100% probability of slide impacting area if slide occurs).

Impacted refers to expected % of area/structure damaged if slide impacts (i.e. small, slow earth slide will damage small portion of house structure such as 1 bedroom (5%), where as large boulder roll may damage/destroy >50%)

\* neighbouring houses considered for impact of slide to bedroom unless specified, due to high occupancy and lower potential for evacuation.

\* considered for person most at risk, where multiple people occupy area then increased risk levels

\* for excavation induced landslip then considered for adjacent premises/buildings founded off shallow footings, unless indicated

\* evacuation scale from Almost Certain to not evacuate (1.0), Likely (0.75), Possible (0.5), Unlikely (0.25), Rare to not evacuate (0.01). Based on likelihood of person knowing of landslide and completely evacuating area prior to landslide impact.

\* vulnerability assessed using Appendix F - AGS Practice Note Guidelines for Landslide Risk Management 2007

#### TABLE : B

#### Landslide risk assessment for Risk to Property

HAZARD	Description	Impacting	Likelihood		Consequences		Risk to Property
	Landslip (earth slide <5m <sup>3</sup> ) of fill and colluvial soils within existing slope	a) Existing site dwelling	Unlikely	The event might occur under very adverse circumstances over the design life.	Minor	Limited Damage to part of structure or site or INSIGNIFICANT damage to neighbouring properties, requires some stabilisation.	Low

\* hazards considered in current condition, without remedial/stabilisation measures and during construction works.

\* qualitative expression of likelihood incorporates both frequency analysis estimate and spatial impact probability estimate as per AGS guidelines.

\* qualitative measures of consequences to property assessed per Appendix C in AGS Guidelines for Landslide Risk Management.

\* Indicative cost of damage expressed as cost of site development with respect to consequence values: Catastrophic : 200%, Major: 60%, Medium: 20%, Minor: 5%, Insignificant: 0.5%.

\* Cost of site development estimated at

\$50,000

## TABLE: C

### Recommended Maintenance and Inspection Program

Structure	Maintenance/ Inspection Item	Frequency	
Stormwater drains.	Owner to inspect to ensure that the open drains, and pipes are free of debris & sediment build-up. Clear surface grates and litter. Owner to check and flush retaining wall drainage pipes/systems	Every year or following each major rainfall event. Every 7 years or where dampness/moisture	
Retaining Walls. or remedial measures	Owner to inspect walls for deveation from as constructed condition and repair/replace.	Every two years or following major rainfall event.	
Large Trees on or adjacent to site	Arborist to check condition of trees and remove as required. Where tree within steep slopes (>18°) or adjacent to structures requires geotechincal inspection prior to removal	Every five years	
Slope Stability	Geotechnical Engineering Consultant to check on site stability and maintenance	Five years after construction is completed.	

<u>N.B.</u> Provided the above shedule is maintained the design life of the property should conform with Councils Risk Management Policy.



# Appendix 3

#### **APPENDIX A**

#### **DEFINITION OF TERMS**

#### INTERNATIONAL UNION OF GEOLOGICAL SCIENCES WORKING GROUP ON LANDSLIDES, COMMITTEE ON RISK ASSESSMENT

- **Risk** A measure of the probability and severity of an adverse effect to health, property or the environment. Risk is often estimated by the product of probability x consequences. However, a more general interpretation of risk involves a comparison of the probability and consequences in a non-product form.
- **Hazard** A condition with the potential for causing an undesirable consequence (*the landslide*). The description of landslide hazard should include the location, volume (or area), classification and velocity of the potential landslides and any resultant detached material, and the likelihood of their occurrence within a given period of time.
- **Elements at Risk** Meaning the population, buildings and engineering works, economic activities, public services utilities, infrastructure and environmental features in the area potentially affected by landslides.
- **Probability** The likelihood of a specific outcome, measured by the ratio of specific outcomes to the total number of possible outcomes. Probability is expressed as a number between 0 and 1, with 0 indicating an impossible outcome, and 1 indicating that an outcome is certain.
- **Frequency** A measure of likelihood expressed as the number of occurrences of an event in a given time. See also Likelihood and Probability.
- Likelihood used as a qualitative description of probability or frequency.
- **Temporal Probability** The probability that the element at risk is in the area affected by the landsliding, at the time of the landslide.
- **Vulnerability** The degree of loss to a given element or set of elements within the area affected by the landslide hazard. It is expressed on a scale of 0 (no loss) to 1 (total loss). For property, the loss will be the value of the damage relative to the value of the property; for persons, it will be the probability that a particular life (the element at risk) will be lost, given the person(s) is affected by the landslide.
- **Consequence** The outcomes or potential outcomes arising from the occurrence of a landslide expressed qualitatively or quantitatively, in terms of loss, disadvantage or gain, damage, injury or loss of life.
- **Risk Analysis** The use of available information to estimate the risk to individuals or populations, property, or the environment, from hazards. Risk analyses generally contain the following steps: scope definition, hazard identification, and risk estimation.
- **Risk Estimation** The process used to produce a measure of the level of health, property, or environmental risks being analysed. Risk estimation contains the following steps: frequency analysis, consequence analysis, and their integration.
- **Risk Evaluation** The stage at which values and judgements enter the decision process, explicitly or implicitly, by including consideration of the importance of the estimated risks and the associated social, environmental, and economic consequences, in order to identify a range of alternatives for managing the risks.
- **Risk Assessment** The process of risk analysis and risk evaluation.
- **Risk Control or Risk Treatment** The process of decision making for managing risk, and the implementation, or enforcement of risk mitigation measures and the re-evaluation of its effectiveness from time to time, using the results of risk assessment as one input.
- Risk Management The complete process of risk assessment and risk control (or risk treatment).

### LANDSLIDE RISK MANAGEMENT

- **Individual Risk** The risk of fatality or injury to any identifiable (named) individual who lives within the zone impacted by the landslide; or who follows a particular pattern of life that might subject him or her to the consequences of the landslide.
- **Societal Risk** The risk of multiple fatalities or injuries in society as a whole: one where society would have to carry the burden of a landslide causing a number of deaths, injuries, financial, environmental, and other losses.
- Acceptable Risk A risk for which, for the purposes of life or work, we are prepared to accept as it is with no regard to its management. Society does not generally consider expenditure in further reducing such risks justifiable.
- **Tolerable Risk** A risk that society is willing to live with so as to secure certain net benefits in the confidence that it is being properly controlled, kept under review and further reduced as and when possible.

In some situations risk may be tolerated because the individuals at risk cannot afford to reduce risk even though they recognise it is not properly controlled.

- Landslide Intensity A set of spatially distributed parameters related to the destructive power of a landslide. The parameters may be described quantitatively or qualitatively and may include maximum movement velocity, total displacement, differential displacement, depth of the moving mass, peak discharge per unit width, kinetic energy per unit area.
- <u>Note</u>: Reference should also be made to Figure 1 which shows the inter-relationship of many of these terms and the relevant portion of Landslide Risk Management.

## PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

#### APPENDIX C: LANDSLIDE RISK ASSESSMENT

## QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY

#### **QUALITATIVE MEASURES OF LIKELIHOOD**

Approximate Annual Probability Indicative Notional Value Boundary		Implied Indicative Landslide Recurrence Interval		Description	Descriptor	Level
10-1	5x10 <sup>-2</sup>	10 years	•	The event is expected to occur over the design life.	ALMOST CERTAIN	А
10-2	5x10 <sup>-3</sup>	100 years	20 years	The event will probably occur under adverse conditions over the design life.	LIKELY	В
10-3		1000 years	200 years 2000 years	The event could occur under adverse conditions over the design life.	POSSIBLE	С
10-4	5x10 <sup>-4</sup>	10,000 years	2000 vears	The event might occur under very adverse circumstances over the design life.	UNLIKELY	D
10-5	5x10 <sup>-5</sup> 5x10 <sup>-6</sup>	100,000 years		The event is conceivable but only under exceptional circumstances over the design life.	RARE	Е
10-6	3x10	1,000,000 years	200,000 years	The event is inconceivable or fanciful over the design life.	BARELY CREDIBLE	F

Note: (1) The table should be used from left to right; use Approximate Annual Probability or Description to assign Descriptor, not vice versa.

#### **QUALITATIVE MEASURES OF CONSEQUENCES TO PROPERTY**

Approximate Cost of Damage				
Indicative Value	Notional Boundary	— Description	Descriptor	Level
200%	1000/	Structure(s) completely destroyed and/or large scale damage requiring major engineering works for stabilisation. Could cause at least one adjacent property major consequence damage.	CATASTROPHIC	1
60%	100% 40%	Extensive damage to most of structure, and/or extending beyond site boundaries requiring significant stabilisation works. Could cause at least one adjacent property medium consequence damage.	MAJOR	2
20%	40%	Moderate damage to some of structure, and/or significant part of site requiring large stabilisation works. Could cause at least one adjacent property minor consequence damage.	MEDIUM	3
5%	1%	Limited damage to part of structure, and/or part of site requiring some reinstatement stabilisation works.	MINOR	4
0.5%	1/0	Little damage. (Note for high probability event (Almost Certain), this category may be subdivided at a notional boundary of 0.1%. See Risk Matrix.)	INSIGNIFICANT	5

Notes: (2) The Approximate Cost of Damage is expressed as a percentage of market value, being the cost of the improved value of the unaffected property which includes the land plus the unaffected structures.

(3) The Approximate Cost is to be an estimate of the direct cost of the damage, such as the cost of reinstatement of the damaged portion of the property (land plus structures), stabilisation works required to render the site to tolerable risk level for the landslide which has occurred and professional design fees, and consequential costs such as legal fees, temporary accommodation. It does not include additional stabilisation works to address other landslides which may affect the property.

(4) The table should be used from left to right; use Approximate Cost of Damage or Description to assign Descriptor, not vice versa

## PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

## APPENDIX C: – QUALITATIVE TERMINOLOGY FOR USE IN ASSESSING RISK TO PROPERTY (CONTINUED)

LIKELIHOOD		CONSEQUENCES TO PROPERTY (With Indicative Approximate Cost of Damage)				
	Indicative Value of Approximate Annual Probability	1: CATASTROPHIC 200%	2: MAJOR 60%	3: MEDIUM 20%	4: MINOR 5%	5: INSIGNIFICANT 0.5%
A – ALMOST CERTAIN	10-1	VH	VH	VH	Н	M or L (5)
B - LIKELY	10 <sup>-2</sup>	VH	VH	Н	М	L
C - POSSIBLE	10-3	VH	Н	М	М	VL
D - UNLIKELY	10 <sup>-4</sup>	Н	М	L	L	VL
E - RARE	10-5	М	L	L	VL	VL
F - BARELY CREDIBLE	10 <sup>-6</sup>	L	VL	VL	VL	VL

## QUALITATIVE RISK ANALYSIS MATRIX – LEVEL OF RISK TO PROPERTY

Notes: (5) For Cell A5, may be subdivided such that a consequence of less than 0.1% is Low Risk.

(6) When considering a risk assessment it must be clearly stated whether it is for existing conditions or with risk control measures which may not be implemented at the current time.

#### **RISK LEVEL IMPLICATIONS**

Risk Level		Example Implications (7)		
VH VERY HIGH RISK		Unacceptable without treatment. Extensive detailed investigation and research, planning and implementation of treatment options essential to reduce risk to Low; may be too expensive and not practical. Work likely to cost more than value of the property.		
Н	HIGH RISK	Unacceptable without treatment. Detailed investigation, planning and implementation of treatment options required to reduce risk to Low. Work would cost a substantial sum in relation to the value of the property.		
М	MODERATE RISK	May be tolerated in certain circumstances (subject to regulator's approval) but requires investigation, planning and implementation of treatment options to reduce the risk to Low. Treatment options to reduce to Low risk should be implemented as soon as practicable.		
L LOW RISK		Usually acceptable to regulators. Where treatment has been required to reduce the risk to this level, ongoing maintenance is required.		
VL	VERY LOW RISK	Acceptable. Manage by normal slope maintenance procedures.		

Note: (7) The implications for a particular situation are to be determined by all parties to the risk assessment and may depend on the nature of the property at risk; these are only given as a general guide.



## Appendix 4

## PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007

### **APPENDIX G - SOME GUIDELINES FOR HILLSIDE CONSTRUCTION**

#### **GOOD ENGINEERING PRACTICE**

#### POOR ENGINEERING PRACTICE

ADVICE	GOOD ENGINEERING PRACTICE	POOR ENGINEERING PRACTICE
ADVICE GEOTECHNICAL	Obtain advice from a qualified, experienced geotechnical practitioner at early	Prepare detailed plan and start site works before
ASSESSMENT	stage of planning and before site works.	geotechnical advice.
PLANNING	lweet all a state and a state of the state o	
SITE PLANNING	Having obtained geotechnical advice, plan the development with the risk arising from the identified hazards and consequences in mind.	Plan development without regard for the Risk.
DESIGN AND CONS		
HOUSE DESIGN	Use flexible structures which incorporate properly designed brickwork, timber or steel frames, timber or panel cladding. Consider use of split levels. Use decks for recreational areas where appropriate.	Floor plans which require extensive cutting and filling. Movement intolerant structures.
SITE CLEARING	Retain natural vegetation wherever practicable.	Indiscriminately clear the site.
ACCESS & DRIVEWAYS	Satisfy requirements below for cuts, fills, retaining walls and drainage. Council specifications for grades may need to be modified. Driveways and parking areas may need to be fully supported on piers.	Excavate and fill for site access before geotechnical advice.
EARTHWORKS	Retain natural contours wherever possible.	Indiscriminatory bulk earthworks.
Cuts	Minimise depth. Support with engineered retaining walls or batter to appropriate slope. Provide drainage measures and erosion control.	Large scale cuts and benching. Unsupported cuts. Ignore drainage requirements
FILLS	Minimise height. Strip vegetation and topsoil and key into natural slopes prior to filling. Use clean fill materials and compact to engineering standards. Batter to appropriate slope or support with engineered retaining wall. Provide surface drainage and appropriate subsurface drainage.	Loose or poorly compacted fill, which if it fails may flow a considerable distance including onto property below. Block natural drainage lines. Fill over existing vegetation and topsoil. Include stumps, trees, vegetation, topsoil boulders, building rubble etc in fill.
ROCK OUTCROPS	Remove or stabilise boulders which may have unacceptable risk.	Disturb or undercut detached blocks o
& BOULDERS	Support rock faces where necessary.	boulders.
RETAINING WALLS	Engineer design to resist applied soil and water forces. Found on rock where practicable. Provide subsurface drainage within wall backfill and surface drainage on slope above. Construct wall as soon as possible after cut/fill operation.	Construct a structurally inadequate wall such a sandstone flagging, brick or unreinforced blockwork. Lack of subsurface drains and weepholes.
FOOTINGS	Found within rock where practicable. Use rows of piers or strip footings oriented up and down slope. Design for lateral creep pressures if necessary. Backfill footing excavations to exclude ingress of surface water.	Found on topsoil, loose fill, detached boulder or undercut cliffs.
SWIMMING POOLS	Engineer designed. Support on piers to rock where practicable. Provide with under-drainage and gravity drain outlet where practicable. Design for high soil pressures which may develop on uphill side whilst there may be little or no lateral support on downhill side.	
DRAINAGE		
SURFACE	Provide at tops of cut and fill slopes. Discharge to street drainage or natural water courses. Provide general falls to prevent blockage by siltation and incorporate silt traps. Line to minimise infiltration and make flexible where possible. Special structures to dissipate energy at changes of slope and/or direction.	Discharge at top of fills and cuts. Allow water to pond on bench areas.
SUBSURFACE	Provide filter around subsurface drain. Provide drain behind retaining walls. Use flexible pipelines with access for maintenance. Prevent inflow of surface water.	Discharge roof runoff into absorption trenches.
SEPTIC & Sullage	Usually requires pump-out or mains sewer systems; absorption trenches may be possible in some areas if risk is acceptable. Storage tanks should be water-tight and adequately founded.	Discharge sullage directly onto and into slopes Use absorption trenches without consideration of landslide risk.
EROSION CONTROL & LANDSCAPING	Control erosion as this may lead to instability. Revegetate cleared area.	Failure to observe earthworks and drainag recommendations when landscaping.
DRAWINGS AND S	ITE VISITS DURING CONSTRUCTION	
DRAWINGS	Building Application drawings should be viewed by geotechnical consultant	
SITE VISITS	Site Visits by consultant may be appropriate during construction/ MAINTENANCE BY OWNER	
OWNER'S	Clean drainage systems; repair broken joints in drains and leaks in supply	
RESPONSIBILITY	pipes. Where structural distress is evident see advice.	
	If seepage observed, determine causes or seek advice on consequences.	

## PRACTICE NOTE GUIDELINES FOR LANDSLIDE RISK MANAGEMENT 2007



