Prepared for Construct By Design Site Address: 27 Bellevue Avenue Avalon

3<sup>rd</sup> September 2020

Member of Arboriculture Australia No. 1286

Member of International Society of Arboriculture No. 157768

Bachelor of Horticultural Science, University Sydney.

AQF Level 2, 3 & 5 Diploma in Arboriculture

Graduate Certificate AQF Level 8 University Melbourne

Tree Risk Assessment Qualification (TRAQ)

#### Statement

Bradshaw Consulting Arborists is a company that exclusively provides tree consultancy within the tree industry. There is no conflict of interest concerning the recommendations outlined in this report.

Bradshaw Consulting Arborists (Tristan Bradshaw) Po Box 48 St Ives 2075 0411 608 001

info@bradshawtreeservices.com.au

# Contents

1	Intro	oduction	3
	1.1	The Site	3
	1.2	Method	4
2	Bod	y Observations Results	6
3	Disc	ussion	12
4	Reco	ommendations	13
5	Refe	erences	14
6	Арр	endix A	15
	6.1	Appendix B Tree locations	16
	6.2	TPZ incursion of retained trees	17
	6.3	Tree Protection Plan	
	6.4	Appendix C Methodology for Determining Tree Retention Value	19
	6.5	Appendix D Table 2 Step 1 Landscape Significance Rating	20
	6.6	Appendix E Table 3 Estimating Safe Useful Life Expectancy (SULE) Step 2	21
	6.7	Appendix F Table 4 Determining Tree Retention Values	22
7	Арр	endix G Tree Protection specifications	23
8	Inst	allation of Drip line irrigation	25
9	Qua	lifications and Experience	26

Figure 1 Site Location <sup>(3)</sup>	3
Figure 2 Drawing taken from AS 4970-2009	23
Figure 3 Trunk Protection	24
Figure 4 Trunk and branch Protection (AS 4970-2009)	24
Figure 5 Drip irrigation spacing	25

# **1** Introduction

This report has been prepared by Tristan Bradshaw for Construct by Design at the property of 27 Bellevue Avenue Avalon. The report request was to inspect 43 trees, at the back of the property and any on surrounding properties. The trees' characteristics have been listed in Table 5 page 7. The aim is to determine the health and condition of the trees and their retention values to aid in determining a suitable house design. The inspection of the site was undertaken on the 12<sup>th</sup> February 2019 and again on the 4<sup>th</sup> September 2019.

A predevelopment application report was completed on 15<sup>th</sup> February 2019 and an Arboricultural Impact Statement completed on the 6<sup>th</sup> September 2019. This Final Arboricultural Impact statement was completed on 3<sup>rd</sup> September 2020.

Survey plan supplied by Bee & Lethbridge dated 11/1/2019 and Architectural plans by Shed received 31/8/2020 have been used in this assessment. See appendix B.

Tree numbers have been assigned to each tree on the survey plan. The trees have also been numbered onsite using metal tags.

The property is not within the RFS 10/50 vegetation clearing code.

The property is within the Northern Beaches council area and any tree taller than 5 metres is covered by their tree protection policy. The site's development is managed by Pittwater Local Environment Plan.

There is no heritage listing for this site. The site is not within a heritage conservation area.

The site is not within a 10/50 vegetation entitlement clearing area.

### 1.1 The Site

The site is composed of a house with trees surrounding it.



Figure 1 Site Location <sup>(3)</sup>

## 1.2 Method

The inspection of the site was undertaken on the 12<sup>th</sup> February 2019 and 4<sup>th</sup> September 2019.

The inspection method used was the Visual Tree Assessment (VTA) method (Mattheck & Breloer 2010. <sup>(1)</sup>). This method involves inspecting the trees from ground level, using binoculars to aid in identification of any external signs of decay, physical damage, growth related structural defects and the site conditions where the tree is growing. This method will ascertain whether there is need for a more detailed inspection of any part of the tree. No aerial or subterranean inspections were carried out. See appendix A for the complete flow chart.

The Diameter at Breast Height (DBH) was estimated. The height of the measurement was at 140 cm above the ground.

The height of the tree was estimated.

The canopy spread of the tree was estimated.

**Health:** Based on vigour, callus development, % of deadwood, dieback, fruiting levels, internode lengths

- (E) Excellent
- (G) Good
- (F) Fair
- (P) Poor
- (D) Dead

Age Class: (Y) Young=Recently Planted

- (S) Semi mature <20% of life expectancy
- (M) Mature 20-80% of life expectancy
- (O) Over Mature >80% of life expectancy

**Condition:** Base on the structural integrity of the tree, cavities, fungal decay, branch failure, branch taper, sap or kino exudate, fruiting bodies, root condition.

- (E) Excellent
- (G) Good
- (F) Fair
- (P) Poor

#### Visual Habitat

This assessment is based on a visual observation of the tree, included in the VTA method.

Habitat trees are trees that provide microhabitats, these can include hollows, deeply fissured bark, cracks, epiphytes or forms of decay (Bütler, R., Lachat, T., Larrieu, L., & Paillet, Y., 2013).

# 2 Body Observations Results

 Table 1 Individual tree characteristics

Tree Number	Botanical Name	DBH(mm)	DAB(mm)	Canopy N	Canopy S	Canopy E	Canopy W	Height	Health	Age	Condition	SULE	Landscape significance	Retention Value	Habitat	Structural Root Zone (SRZ)	Tree Protection Zone (TPZ)	Percentage encroachment	Notes
1	<i>Angophora costata</i> (Sydney Red Gum)	260	280	2	5	0	4	14	E	Μ	E	>40	V High	High	No	1.9	3.1	3.3%	
2	Eucalyptus resinifera (Red Mahogany)	500	600	8	7	6	6	15	G	Μ	F	15-40	High	High	No	2.7	6.0	0%	
3	E. Sp.	250	300	2	2	2	2	8	DEAD	NA	Р	0	V Low	V Low	No	2.0	3.0	0%	DEAD
4	<i>Angophora costata</i> (Sydney Red Gum)	320	320	4	0	3	2	10	G	Μ	G	15-40	V High	High	No	2.1	3.8	0%	
5	<i>Angophora costata</i> (Sydney Red Gum)	320	340	3	5	4	3	9	G	Μ	G	15-40	V High	High	No	2.1	3.8	0%	
6	Eucalyptus robusta (Swamp Mahogany)	400	400	7	6	6	5	13	F	Μ	G	15-40	V High	High	No	2.3	4.8	0%	Epicormics and dieback

Tree Number	Botanical Name	DBH(mm)	DAB(mm)	Canopy N	Canopy S	Canopy E	Canopy W	Height	Health	Age	Condition	SULE	Landscape significance	Retention Value	Habitat	Structural Root Zone (SRZ)	Tree Protection Zone (TPZ)	Percentage encroachment	Notes
7	<i>Corymbia gummifera</i> (Red Bloodwood)	290	290	4	4	4	4	13	Р	ОМ	Р	<5	High	Low	No	2.0	3.5	0%	80% of the upper canopy dead.
8	Cinnamomum camphora (Camphor Laurel)	250	270	3	3	3	3	8	Р	SM	Р	5-15	Low	V Low	No	1.9	3.0	0%	Weed species
9	Eucalyptus botryioides (Southern Mahogany)	270	270	2	0	1	1	4	F	M	Ρ	5-15	High	Mod	No	1.9	3.2	3%	Significantly unbalanced
10	Eucalyptus globioidea (Stringy Bark)	300	310	5	2	2	4	11	F	ОМ	F	5-15	High	Mod	No	2.0	3.6	0%	Dying
11	Eucalyptus globioidea (Stringy Bark)	220	220	3	0	0	3	10	Р	М	F	5-15	High	Mod	No	1.8	2.6	0%	Dying
12	Phoenix canariensis (Canary Island Date Palm)	550	600	4	4	4	4	8	G	М	G	>40	Low	Mod	No	2.7	4	2.3%	
13	Eucalyptus globioidea (Stringy Bark)	260	270	4	2	5	2	9	Р	М	F	<5	High	Low	No	1.9	3.1	0%	DEAD

Tree Number	Botanical Name	DBH(mm)	DAB(mm)	Canopy N	Canopy S	Canopy E	Canopy W	Height	Health	Age	Condition	SULE	Landscape significance	Retention Value	Habitat	Structural Root Zone (SRZ)	Tree Protection Zone (TPZ)	Percentage encroachment	Notes
14	<i>Callistemon viminallis</i> (Bottle Brush)	200	210	1	1	1	1	7	G	SM	G	15-40	Mod	Mod	No	1.7	2.4	0%	
15	Phoenix canariensis (Canary Island Date Palm)	500	500	3	3	3	3	3	G	Μ	G	>40	Low	Mod	No	2.5	4.0	0%	
16	<i>Angophora costata</i> (Sydney Red Gum)	950	890	7	4	6	6	14	F	М	Ρ	<5	V High	Low	No	3.2	11.4	37%	Cavity significant, canopy dieback
17	Syagrus romanzoffiana (Cocos Palm)	270	270	3	3	3	3	7	E	М	G	15-40	Low	Low	No	1.9	4	100%	
18	<i>Livingstonia australis</i> (Cabbage Tree Palm)	290	300	3	3	3	3	10	E	М	G	>40	V High	High	No	2.0	4	100%	Within 2 metres of existing house.
19	<i>Washingtonia filifera</i> (Cotton Palm)	310	330	2	2	2	2	5	G	М	G	>40	Mod	Mod	No	2.1	3	100%	
20	Syagrus romanzoffiana (Cocos Palm)	260	280	3	3	3	3	9	E	М	E	>40	Low	Low	No	1.9	4	100%	

Tree Number	Botanical Name	DBH(mm)	DAB(mm)	Canopy N	Canopy S	Canopy E	Canopy W	Height	Health	Age	Condition	SULE	Landscape significance	Retention Value	Habitat	Structural Root Zone (SRZ)	Tree Protection Zone (TPZ)	Percentage encroachment	Notes
21	<i>Angophora costata</i> (Sydney Red Gum)	510	560	6	6	6	6	14	E	М	G	>40	V High	High	No	2.6	6.1	<10%	
22	<i>Angophora costata</i> (Sydney Red Gum)	580	580	9	0	5	5	14	E	М	Р	<5	V High	Low	No	2.6	7.0	20%	Bracket fungus, dieback.
23	<i>Angophora costata</i> (Sydney Red Gum)	400	420	7	5	6	5	14	G	М	G	>40	V High	High	No	2.3	4.8	6%	
24	<i>Angophora costata</i> (Sydney Red Gum)	500	520	5	5	5	5	14	G	М	G	>40	V High	High	No	2.5	6.0	9%	
25	Glochidion ferdinandi (Cheese Tree)	300	300	6	0	4	4	9	F	М	F	5-15	V High	Mod	No	2.0	3.6	0%	
26	<i>Angophora costata</i> (Sydney Red Gum)	800	890	5	8	8	8	14	F	М	G	>40	V High	High	No	3.2	9.6	13%	
27	Eucalyptus globioidea (Stringy Bark)	220	230	2	3	0	3	8	F	SM	G	15-40	V High	High	No	1.8	2.6	0%	
28	<i>Angophora costata</i> (Sydney Red Gum)	200	240	3	2	0	3	7	F	SM	F	15-40	V High	High	No	1.8	2.4	0%	

Tree Number	Botanical Name	DBH(mm)	DAB(mm)	Canopy N	Canopy S	Canopy E	Canopy W	Height	Health	Age	Condition	SULE	Landscape significance	Retention Value	Habitat	Structural Root Zone (SRZ)	Tree Protection Zone (TPZ)	Percentage encroachment	Notes
29	<i>Angophora costata</i> (Sydney Red Gum)	400	420	5	7	5	5	13	G	М	G	>40	V High	High	No	2.3	4.8	7%	
30	<i>Corymbia gummifera</i> (Red Bloodwood)	400	410	3	6	4	4	12	F	OM	F	15-40	V High	High	No	2.3	4.8	20%	
31	<i>Angophora costata</i> (Sydney Red Gum)	360	390	6	4	5	5	13	F	М	Ρ	<5	V High	Low	No	2.2	4.3	100%	Decaying root system. Whole tree failure
32	<i>Angophora costata</i> (Sydney Red Gum)	260	270	4	3	3	3	10	Р	OM	Р	<5	V High	Low	No	1.9	3.1	20%	Significant dieback
33	<i>Angophora costata</i> (Sydney Red Gum)	380	400	4	4	5	5	12	F	М	Р	5-15	V High	Mod	No	2.3	4.6	13%	
34	<i>Corymbia gummifera</i> (Red Bloodwood)	390	430	4	4	4	4	12	G	М	G	15-40	V High	High	No	2.3	4.7	100%	
35	Eucalyptus globioidea (Stringy Bark)	260	270	5	0	3	3	12	F	М	F	5-15	High	Mod	No	1.9	3.1	100%	
36	Eucalyptus globioidea (Stringy Bark)	220	230	1	1	1	1	10	Р	SM	Ρ	<5	High	Low	No	1.8	2.6	100%	

Tree Number	Botanical Name	DBH(mm)	DAB(mm)	Canopy N	Canopy S	Canopy E	Canopy W	Height	Health	Age	Condition	SULE	Landscape significance	Retention Value	Habitat	Structural Root Zone (SRZ)	Tree Protection Zone (TPZ)	Percentage encroachment	Notes
37	<i>Lophostemon confertus</i> (Brush Box)	700	740	6	6	6	6	15	E	Μ	E	>40	High	High	No	2.9	8.4	18%	
38	<i>Syzygium smithii</i> (Common Lilly Pilly)	320	360	4	4	4	4	10	Р	ОМ	Ρ	<5	High	Low	No	2.2	3.8	100%	Dying
39	<i>Glochidion ferdinandi</i> (Cheese Tree)	310	400	7	0	5	5	11	F	М	F	5-15	V High	Mod	No	2.3	3.7	100%	
40	<i>Largerstroemia indica</i> (Crepe Myrtle)	210	210	3	3	3	3	7	F	М	G	15-40	Mod	Mod	No	1.7	2.5	100%	
41	Jacaranda mimosifolia (Jacaranda)	250	270	3	3	3	3	9	G	М	G	15-40	Mod	Mod	No	1.9	3.0	25%	
42	<i>Corymbia maculata</i> (Spotted Gum)	250	270	2	3	0	3	9	G	Μ	Ρ	15-40	V High	High	No	1.9	3.0	0%	
43	Corymbia maculata (Spotted Gum)	350	400	5	5	5	5	14	G	M	G	>40	V High	High	No	2.3	4.2	0%	

## **3** Discussion

Of the 43 trees assessed a large number of trees are located on council property and neighbours' properties. A preliminary development arborist report was submitted to ensure a large number of trees of high retention were retained and protected. This includes surrounding trees in neighbours' properties and council owned trees.

Trees around the periphery of the block have been retained to maintain a treed landscape, maintaining privacy and inclusion of the building into the surrounding landscape.

Of the 43 trees assessed, trees 17, 18, 19, 20, 40 and 41 are either exempt tree species or within 2 metres of the existing house. Council approval is not required to remove these trees.

Of the remaining 37 trees, trees 37, 42 and 43 are in the neighbouring property of 29 Bellevue Avenue Avalon. There is no impact projected for trees 42 and 43. The encroachment to tree 37 is 18%. This is a major encroachment as per Australian Standard 4970-2009, however this species is very tolerant to root disturbance and the development is unlikely to affect the long term health or condition of the tree. If construction works are proposed through the summer months irrigation is recommended to compensate for root loss.

Of the remaining 34 trees, trees 1, 2, 3, 4, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 21, 24, 27, 28 and 29 are located on council property. It is proposed that all these trees are retained and protected. Projected impact to the TPZ have been included in table 5 page 7. No incursion is greater than 10%. This is in accordance with AS 4970-2009.

Tree 21 has a projected incursion of <10%, the impact is from the entry driveway and turning area. The entry driveway will have very little impact as this is an existing driveway. It is proposed this driveway is removed and replaced. New driveway levels are very similar to the existing driveway. There should be no excavation deeper than the existing driveway, this will maintain the existing root system of the tree that is likely under the driveway.

The proposed new curb and gutter beside this tree is located within the existing roadway and will be raised higher than the natural ground level. Hand excavation must occur as tree roots may be located. Any tree roots are to be retained. Foam with low compression can be wrapped around any identified tree roots and concrete poured around the tree roots. This will allow tree root expansion over time and retention to ensure the long-term health of the trees.

Of the remaining 14 trees, trees 16, 22, 31, 32, 36 and 38 are of low retention value and it is recommended they are removed. Tree 38 was incorrectly identified as *Syzygium paniculatum* in the initial Arboricultural assessment. The tree has since been identified as Syzygium smithii.

Tree 16 is experiencing dieback; the tree has a significantly large hollow trunk with decay. From the visual inspection this tree should be removed as it is at risk of whole tree failure.

Tree 22 has a large bracket fungus in one of the trunks of the tree, swelling is evident. Pruning would remove the risk; however, the resulting tree is unbalanced and would be prone to limb drop because of the significant change in wind patterns through the tree. It is recommended this tree be removed.

Tree 31 appears to be in fair health; however, the exposed root system looks to have been severed many years prior for the existing lower driveway entry. The structural root system is decaying, and the tree is prone to whole tree failure. Sydney Red Gum trees that fail in strong winds often have decay of anchor roots. This tree is structurally unsound and should be removed.

Tree 32 is in poor health; the tree is dying. This tree is likely to die within the next 5 years. Removal is recommended.

Trees 36 and 38 are in poor health. There is extensive deadwood and epicormic growth from these trees. They are stressed and declining. Removal is recommended.

Of the remaining 8 trees, tree 25 is in fair health, this tree is within the proposed raise walkway and is likely to affect construction of the walkway and impede its width. It is recommended this tree be removed.

Tree 23 has less than 10% encroachment into the TPZ and should be retained.

Trees 26 and 33 have a 13% incursion to the TPZ this is marginally more than the acceptable 10% as per AS 4970-2009. It is recommended these trees are irrigated through the construction process. Irrigation times are to be scheduled buy the project arborist.

Trees 30, 34, 35 and 39 are impacted negatively by this proposal and should be removed.

## **4** Recommendations

- 1. Removal of trees 16, 17, 18, 19, 20, 22, 25, 30, 31, 33, 34, 35, 36, 38, 39, 40 and 41.
- 2. Retain and protect trees 1-15, 21, 23, 24, 26, 27, 28, 29, 33, 37, 42 and 43.
- 3. Tree removal should be conducted by an Arborist with a minimum (Australian Qualification Framework) AQF level 3.
- 4. Work must be undertaken as per the Code of Practice Amenity Tree Industry 1998.
- 5. The tree removal process and staff should be skilled and undertake the removal of the tree as per the minimum industry standards.
- 6. Appoint project arborist. Minimum AQF Level 5 with 5 years' experience.
- 7. Retain and protect trees as per tree protection plan section 6.3. This is a combination of physical fencing, trunk protection and ground protection. See Section 7 Appendix G for specifications.
- 8. Irrigation is recommended for all trees retained. Scheduling of irrigation times to be coordinated by the project arborist. See section 8 regarding irrigation installation specifications.
- 9. Areas denoted as suspended slabs must have ground protection installed prior to any works conducted at the site. This can be left in situ if unable to be removed after construction.
- 10. Project arborist must supervise works within the TPZ of retained trees. This includes but not limited to excavation stage and piering works for basement concrete slabs, removal of existing driveway beside tree 21 and 29. Removal of the paving and retaining walls within TPZ of tree 37. Excavation to install curb and gutter. Piering for raise walkway within the TPZ. All excavation within TPZ should be by hand to a depth of 700mm, beyond this hydraulic equipment can be used. No heavy equipment is to enter TPZ.

- 11. Tree protection zones that have been fenced: if access is required to undertake construction ground protection and trunk protection must be installed for the duration of works.
- 12. The project arborist must inspect the site once every 2 months and provide a letter of recommendations and/or photographic evidence that tree protection has not been compromised.

# **5** References

- 1. Bütler, R., Lachat, T., Larrieu, L. and Paillet, Y., 2013. 2.1 Habitat trees: key elements for forest biodiversity. *Integrative approaches as an opportunity for the conservation of forest biodiversity*, p.84.
- 2. Australian Standard, A.S., 4970, 2009. Protection of trees on development sites, Sydney.
- 3. Australian Standard A.S., 4373-2007. Pruning of Amenity Trees, 2007, Sydney
- https://www.google.com/maps/place/27+Bellevue+Ave,+Avalon+Beach+NSW+2107/@-33.638329,151.3276809,18z/data=!4m5!3m4!1s0x6b0d532cb3dfe7b9:0x1b8a406b6506f2d2
   l8m2!3d-33.6380566!4d151.3269674. Viewed 3<sup>rd</sup> September 2020.
- Mattheck & Breloer 2010. The Body Language of Trees a handbook for failure analysis. Research for Amenity Trees series published by The Stationery Office, Norwich, United Kingdom.
- NSW Government e planning spatial viewer, 2020. <u>https://www.planningportal.nsw.gov.au/propertyreports/9de60642-47ca-4f2d-a485-19a7c1d9cbe8.pdf</u>. Viewed 3<sup>rd</sup> September 2020.
- 7. Northern Beaches Council Trees. <u>https://www.northernbeaches.nsw.gov.au/planning-development/tree-management/private-land</u>. Viewed 3<sup>rd</sup> September 2020.
- RFS 10/50. <u>https://www.rfs.nsw.gov.au/plan-and-prepare/1050-vegetation-clearing/tool</u>. Viewed 3<sup>rd</sup> September 2020.



# 6.1 Appendix B Tree locations



## 6.2 TPZ incursion of retained trees



## 6.3 Tree Protection Plan



# 6.4 Appendix C Methodology for Determining Tree Retention Value

The aim of this process is to determine the relative value of each tree for retention (i.e. its Retention Value) in the context of development. This methodology assists in the decision-making process by using a systematic approach. The key objective of process is to ensure the retention of good quality trees that make a positive contribution to these values and ensure that adequate space is provided for their long term preservation. The Retention Value of a tree is a balance between its sustainability in the setting in which it is located (the 'landscape') and its significance within that setting (landscape significance).

#### Step 1: Determining the Landscape Significance Rating

The 'landscape significance' of a tree is a measure of its contribution to amenity, heritage, and ecological values. While these values are fairly subjective and difficult to assess consistently, some measure is necessary to assist in determining the Retention Value of each tree. To ensure in a consistent approach, the assessment criterion shown in Table 2 should be used. A Tree may be considered 'significant' for one or more reasons. A tree may meet one or more of the criteria in any value category (heritage, ecology or amenity) shown in Table 2 to achieve the specified rating. For example, a tree may be considered 'significant' and given a rating of 1, even if it is only significant based on the amenity criteria.

Based in the criterion in this table, each tree should be assigned a landscape significance rating as follows:

- 1. Significant
- 2. Very High
- 3. High
- 4. Moderate
- 5. Low
- 6. Very Low
- 7. Insignificant

#### Step 2: Determining Safe Useful Life Expectancy (SULE)

The sustainability of a tree in the landscape is a measure of its remaining lifespan in consideration of its current health, condition and suitability to the locality and site conditions. The assessment of the remaining lifespan of a tree is a fairly objective assessment when carried out by a qualified Consulting Arborist. Once a visual assessment of each tree is completed (using the Visual Tree Assessment criteria), the arborist can make an informed judgement about the quality and remaining lifespan of each tree. The Safe Useful Life Expectancy (SULE) methodology (refer to Table 3) can be used to categorise trees as follows:

- Long (Greater than 40 years)
- Medium (Between 15 and 40 years)
- Short (Between 5 and 15 years)
- Transient (less than 5 years)
- Dead or Hazardous (no remaining SULE)

The SULE of a tree is calculated based on an estimate of the average lifespan of the species in an urban area, less its estimated current age and then further modified where necessary in consideration of its current health, condition (structural integrity) and suitability to the site.

# 6.5 Appendix D Table 2 Step 1 Landscape Significance Rating

RATINGS	HERITAGE VALUE	ECOLOGICAL VALUE	AMENITY VALUE
1. SIGNIFICANT	The subject tree is listed as a Heritage item under the Local Environment Plan (LEP) with a local, state, or national level of significance or is listed on Council's Significant Tree Register.	The subject tree is scheduled as a Threatened Species as defined under the Threatened Species Conversation Act 1995 (NSW) or the Environmental Protection and Biodiversity Conservation Act 1999.	The subject tree has a very large live crown size exceeding 100m2 with normal to dense foliage cover, is located in a visually prominent position in the landscape, exhibits very good form and habit typical of the species.
	The subject tree forms part of the curtilage of a Heritage Item (building/structure/artefact as defined under the LEP) and has a known or documented association with that item.	The tree is a locally indigenous species, representative of the original vegetation of the area and is known as an important food, shelter or nesting tree for endangered or threatened fauna species.	The Subject tree makes a significant contribution to the amenity and visual character of the area by creating a sense of place or creating a sense of identity.
	The subject tree is a Commemorative Planting having been planted by an important historical person (s) or to commemorate an important historical event.	The subject tree is a Remnant Tree, being a tree in existence prior to development of the area.	The tree is visually prominent in view form surrounding areas, being a landmark or visible from a considerable distance.
2. VERY HIGH	The tree has a strong historical association with a heritage item (building/structure/artefact/garden etc) within or adjacent the property and/or exemplifies a particular era or style of landscape design associated with the original development of the site.	The tree is a locally indigenous species representative of the original vegetation of the area and is a dominant or associated canopy species of an Endangered Ecological Community (EEC) formerly occurring in the area occupied by the site.	The subject tree has a very large live crown size exceeding 60m2, a crown density exceeding 70% (normal-dense), is a very good representative of the species in terms of its form and branching habit or is aesthetically distinctive and makes a positive contribution to the visual character and the amenity of the area.
3. HIGH	The tree has a suspected historical association with a heritage item or landscape supported by anecdotal or visual evidence.	The tree is a locally indigenous and representative of the original vegetation of the area and the tree is located within a defined vegetation link/wildlife corridor or has known wildlife habitat value.	The tree is a good representative of the species in terms of its form and branching habit with minor deviations from normal (e.g. crown distortion/suppression) with a crown density of at least 70% (normal); The subject tree is visible form the street and/or surrounding properties and makes a positive contribution to the visual character and the amenity of the area.
4. MODERATE	The tree has no known or suspected historical association but does not detract or diminish the value the value of the item and is sympathetic to the original era of planting.	The subject tree is a non-local native or exotic species that is protected under the provisions of the DCP.	The subject tree has a medium live crown size exceeding $25m^2$ ; The tree is a fair representative of the species, exhibiting moderate deviations from typical form (distortion/suppression etc) with a crown density of more than 50% (thinning to normal). The tree is visible from surrounding properties but is not visually prominent- view may be partially obscured by other vegetation or built forms. The tree makes a fair contribution to the visual character and amenity of the area.
5. LOW	The subject tree detracts from heritage values and diminishes the value of the heritage item.	The subject tree is scheduled as exempt (not protected) under the provisions of this DCP due to its species, nuisance or position relative to buildings or other structures.	The subject tree has a small live crown of less than 25m <sup>2</sup> and can be replaced within the short term (5-10 years) with new tree planting.
6. VERY LOW	The subject tree is causing significant damage to a heritage item.	The subject tree is listed as an Environment Weed Species in the Local Government Area, being invasive, or is a nuisance species.	The subject tree is not visible from surrounding properties (visibility obscured) and makes a negligible contribution or has a negative impact on the amenity and visual character of the area. The tree is a poor representative of the species, showing significant deviations from the typical form and branching habit with a crown density of less than 50%.

# 6.6 Appendix E Table 3 Estimating Safe Useful Life Expectancy (SULE) Step 2

		1
1 Estimate the age of the tree		
2 Establish the average life span of the	species	
3 Determine whether the average life sp	an nee	ds to be modified due to local environmental situation
4 Estimate remaining life expectancy		
Life Expectancy	=	average modified life span of species - age of tree
5 Consider how health may affect safety	/ (& lon	gevity)
6 Consider how tree structure may affect	t safety	/
7 Consider how location will affect safety	y	
8 Determine safe life expectancy		
Safe Life Expectancy	=	life expectancy modified by health, structure and location
9 Consider economics of management (	cost vs	benefit of retention)
10 Consider adverse impacts on better tre	ees	
11 Consider sustaining amenity - making	space	for new trees
L I		
12 Determine SULE		1
Safe Useful Life Expectancy	=	safe life expectancy modified by economics, effects on better trees and sustaining amenity

Ref. Barrell, Jeremy (1996) Pre-development Tree Assessment Proceedings of the International Conference on Trees and Building Sites (Chicago) International Society of arboriculture, Illinois, USA

## 6.7 Appendix F Table 4 Determining Tree Retention Values

The Retention Value of a tree is increased or diminished based on its sustainability in the landscape, which is expressed as its SULE. A tree that has a high Landscape Significance Rating, but low remaining SULE, has a diminished value for retention and therefore has an appropriate Retention Value assigned. Conversely a tree with a low Landscape Significance Rating even with a long remaining SULE, is also considered of low Retention Value. This logic is reflected in the matrix shown in Table 1.

Once the landscape Significance Rating and SULE category have been determined, the following matrix can be used to determine a relative value (or priority) for retention:



#### TABLE 1 – DETERMINING TREE RETENTION VALUES

# 7 Appendix G Tree Protection specifications

#### Tree Protection Fencing (See Figure 2 below)

Tree protection is to be carried out on all trees to be retained on site.

All fencing should be at the perimeter of the Tree Protection Zone (TPZ).

The TPZ must be enclosed with a fully supporting chainmesh protective fencing. The fencing shall be secure and fastened to prevent movement. The fencing shall have a lockable opening for access. Roots greater than 30mm diameter are not to be damaged/severed during the construction of the fence. See Figure 2 Drawing taken from AS 4970-2009below.

The enclosed area must be free of weeds and grass, the application of a 75mm layer of leaf mulch to the tree protection zone (TPZ) must be maintained for the duration of works.

Two signs on either side of the fencing are to be erected showing the name and contact details of the site Arborist and the words NO ENTRY clearly written.

No work is to be undertaken within this Tree Protection Zone; this includes:

-No removal or pruning of trees

-No construction, stockpiling or storage of chemicals, soil, and cement. Or the movement of machinery, parking and personnel is to occur within the TPZ.

-No refuelling, dumping of waste, placement of fill or Soil level changes.

-No lighting of fires or physical damage to protected trees.

-No temporary or permanent installation of utilities or signs.

-No service trenches should pass through the TPZ, unless approved and supervised by the project arborist.

#### Example of tree protection fencing



Figure 2 Drawing taken from AS 4970-2009



Figure 4 Trunk and branch Protection (AS 4970-2009)



**Figure 3 Trunk Protection** 

#### **Trunk Protection**

Hessian or similar material is used as a wrap around the trunk to a height of 2.6 metres from the base of the tree. Covering the hessian are timbers 100x50x2500mm These are to be spaced around the trunk with gaps of approximately 100mm. The timbers are to be secured with metal strapping. These materials are not to be directly fastened to the tree. See Figure 3 and Figure 4 above.

# 8 Installation of Drip line irrigation

Subsurface irrigation systems shall comprise of Netafim (or equivalent) pressure compensating inline dripper pipe with anti-siphon ability and copper oxide impregnated diaphragm. The subsurface lines are to be installed at a maximum of 300mm spacing's and at a rate nominated to provide the required precipitation rate to the planted garden beds whilst not exceeding the manufacturer's maximum length of drip line and to maintain an application uniformity of 90% and/or maximum frictional pressure loss representing the difference between the operating pressure and minimum operating pressure of the emitters as recommended by the manufacturers.

Drip irrigation shall be installed on the soil surface or below mulch if this has been specified. The subsurface laterals are to be pegged with steel pegs 300mm in length at a maximum of 2m centres along each drip line run. All solenoid valves providing irrigation water to areas of drip irrigation shall be fitted with a valve sized plastic bodied filter unit incorporating a disc filtration element equivalent to 120-mesh filtration. The system shall incorporate a line sized nylon ball valve located prior to the inlet of the filter and installed below ground level within a plastic valve enclosure. The filter enclosure to be sized so that filter may be easily maintained (JUMBO Valve box).

Where drip tubing is to be installed under mulch or buried directly in the soil, the contractor shall include a PVC or PE pipe to form a manifold for all of the drip tubes for both ends of the tubing, as follows:

- A water supply manifold connected to the drip irrigation filter and solenoid valve assembly.
- A water collection (drain) manifold connected to the downstream ends of all drip poly tubing runs.
- All ends of the water supply manifold shall be fitted with manually operated flushing valves.
- At least one end of the collection manifold shall be fitted with a manually operated flushing valve.
- At least one end of the collection manifold shall be fitted with an automatic drain valve.
- Air release valve shall be fitted at the highest point in the water supply manifold.
- Generally, all drain valves shall be installed at the lowest point of a drain manifold.

• Vacuum & drain valves may be interchanged, to suit the relative ground levels at the installation, the intention being that upon closure of the solenoid valve, air is allowed to enter the tubing at the high point and water is allowed to drain from the low point. All vacuum breaker valves, flushing and drain valves shall be housed within a 1910 valve box.

A manual timer or computerised timer with watering times scheduled by the project arborist should be used. See figure below.



Figure 5 Drip irrigation spacing

## 9 Qualifications and Experience

#### TRISTAN BRADSHAW

Postal Address: PO Box 48 St Ives, NSW. 2075. Mobile: 0411 608 001 Email: <u>info@bradshawtreeservices.com.au</u> Industry Licence AL1286-1

#### **Professional Memberships**

Member of the International Society of Arboriculture. No: 157768

Member of Arboriculture Australia No. 1286

#### Qualifications

2016-2018 Graduate Certificate in Arboriculture AQF8 at Melbourne University.

2015 Tree Risk Assessment Qualification (TRAQ)

2013-2014 Diploma of Arboriculture AQF5 at Ryde TAFE. Distinction

2012 Certificate III in Arboriculture at Ryde TAFE

2011 Certificate IV in Occupational Health and Safety

2010 Aboriginal Sites Awareness Course by Aboriginal Heritage Office

1996-1999 Bachelor of Horticultural Science at University of Sydney. Honours+

Tristan Bradshaw has been involved in the Horticultural and Arboricultural Industry since 1995. From a young age this was an interest and the business Bradshaw Horticultural Services incorporated Horticultural consulting work and landscaping. In 2000 Tristan undertook the Level 2 Arboriculture course at Ryde TAFE. The business progressively specialised in consulting, tree removal, pruning and stump grinding works. Extensive hands on knowledge was developed during the climbing of trees undertaking pruning or removal and during storm events understanding the tolerances of trees.

In 2009 the new business name Bradshaw Tree Services was registered to reflect works only being undertaken in the tree industry. The business operated throughout Sydney employing up to 25 people. Tristan Bradshaw's main role was as a consultant advising clients and writing reports. In 2019 Bradshaw Tree Services ceased operations and Tristan Bradshaw opened Bradshaw Consulting Arborists exclusively undertaking tree consultancy.

Tristan Bradshaw with continued education has attained a Level 8 qualification, attends the annual Arboriculture conferences taking part in the seminars to broaden his knowledge.

This assessment was carried out from the ground and covers what was reasonably able to be assessed and available to this assessor at the time of inspection. No subterranean inspections were carried out. The preservation methods recommended where applicable are not a guarantee of the tree survival but are designed to reduce impacts and give the trees the best possible chance of adapting to new surroundings.

#### Limitations on the use of this report:

This report is to be utilised in its entirety only. Any written or verbal submission, report or presentation that includes statements taken from the findings, discussions, conclusions or recommendations made in this report, may only be used where the whole or the original report is referenced in, and directly attached to that submission, report or presentation.

#### Assumptions:

Care has been taken to obtain information from reliable resources. All data has been verified insofar as possible: however, Bradshaw Consulting Arborists can neither guarantee nor be responsible for the accuracy of information provided by others.

#### Unless stated otherwise:

-Information contained in this report covers only the tree/s that was/were examined and reflects the condition of the tree at the time of the assessment: and

-The inspection was limited to visual examination of the subject tree without dissection, excavation, probing or coring. There is no warranty or guarantee, expressed or implied, that problems or deficiencies of the subject tree may not arise in the future.

-The assessment does not identify hazards and associated risk; this report is not a risk assessment.

Yours sincerely,

Thou Min

Tristan Bradshaw (BHort Sci (USYD), Dip Arb AQF 5 (TAFE), Grad Cert AQF 8 (UMELB), TRAQ