# rain Tree consulting

### **Arboricultural Management**

PO Box 326 AVALON NSW 2107 Mobile 0419 250 248

9 December 2019

# 3 CENTRAL ROAD

**AVALON BEACH, NSW** 

## RESIDENTIAL DEVELOPMENT **PROPOSAL**

## ARBORICULTURAL IMPACT ASSESSMENT REPORT

Report Ref No- RTC-16719

Prepared for Avalon Central Pty Limited C/- Cottee Parker Architects Pty Limited L4, 50 Stanley Street EAST SYDNEY, NSW p: 9366 1133

Prepared by Mark A. Kokot AQF Level 5 Consulting arborist



CONTENTS	page
INTRODUCTION	3
METHODOLOGY	4
1. SUMMARY OF ASSESSMENT	5
1.1 General tree assessment	5
1.2 The development proposal Figure 1, showing proposed development footprint	5 5
1.3 Discussions of development impacts – prescribed trees	6
2. CONCLUSIONS & RECOMMENDATIONS	8
2.1 Tree removal	8
2.2 Recommended tree management & protection principles Figure 2, showing tree protection detail Table 1, certification requirements & hold points	8 9 10
APPENDICES	12
Appendix- A: Terminology, notes & references Appendix- B: Tree Retention Values <i>Checklist</i> Appendix- C: Tree Assessment Schedule Appendix- D: Tree Location Plan	13 14 15 20

#### INTRODUCTION

This report has been commissioned by Avalon Central Pty Limited C/- Cottee Parker Architects to assess the remaining Useful Life Expectancy (ULE) and potential impacts that may occur to significant trees in relation to a new development proposal. The new development proposal consists of constructing new residential apartment block facility within Lot 27 of DP 9151 being known as 3 Central Avenue AVALON BEACH, NSW 2107.

Recommendations for retention or removal of trees is based on the trees condition, accorded ULE category and potential impacts that may occur to trees under this development application.

Within a notional root zone radius development encroachments and occupancy within tree protection zones are referred to as No impact (0%) incursion, Low impact (<10%) of minor consequence, Medium impact (<20%) incursion where the project arborist is to demonstrate the tree(s) remain viable by tree sensitive construction techniques, and High level impact (>20%) where design changes or further information is required to manage tree vitality. Where site restrictions within notional root zone radiuses exists development impacts or occupancy disturbances within tree protection zones are determined based on authors experience, observations of site conditions, soil type and topography.

The trees assessed have been identified by their accorded tree number corresponding with tree numbers provided within Survey Plan Sheet 2 of Drawing No. 125698, and are referenced by number throughout this report. For additional trees not plotted on provided documentation their location has been estimated by taking offsets from existing trees and structures. The trees and their location may be referenced within the Tree Assessment Schedule and Tree Location Plan Appendices C and D.

Care has been taken to obtain information from reliable sources. All data has been verified as far as possible, however, I can neither guarantee nor be responsible for the accuracy of information provided by others.

#### DISCLAIMER & LIMITATION ON THE USE OF THIS REPORT

This report is to be utilized in its entirety only. Any written or verbal submission, report or presentation that includes statements taken from the findings, discussions, conclusions or recommendations made in this report, may only be used where the whole of the original report (or copy) is referenced in, and directly to that submission, report or presentation. Unless stated otherwise: Information contained in this report covers only the tree/s that were examined and reflects the condition of the trees at the time of inspection: and the inspection was limited to visual examination of the subject tree without dissection, excavation, probing or coring. There is no warranty or guarantee, expressed or implied, that problems or deficiencies of the subject tree/s may not arise in the future. Arborist cannot guarantee that a tree will be healthy or safe under all circumstances, or for a specific period of time. Trees are a living entity and change continuously, they can be managed but not controlled and to be associated near one involves some degree of risk.

#### **METHODOLOGY**

- In preparation for this report a limited site and ground level Visual Tree Assessment (VTA) was conducted on Wednesday 6<sup>th</sup> November 2019 by the author of this report. The principles of VTA were primarily adopted from components of Mattheck & *Breloer* 1994 '*The Body Language of Trees*' with very basic risk values determined by criteria explained within the ISA TRAQ manual 2013. The inspection included assessment of the overall health and vigour of the trees, tree form, structure and structural condition commencing from near the lower trunk to the upper first order branch division as best as site conditions would allow. On completion of the VTA the retention value of the tree was summarised utilizing the tree assessment Checklist shown within Appendix- B.
- The inspection was limited to a visual assessment from within the subject site where the retention value, condition and diameters of neighbouring trees was estimated. Tree height and canopy spread was estimated and expressed in metres with trunk diameters measured at approximately 1.4 metres above ground level, rounded off to the nearest 50mm and expressed as DBH (Diameter at Breast Height). The height of palms was taken from ground level to the top of the crown shaft only, and excludes the central apical spear projection.
- This report utilizes the current Australian Standards 'Protection of Trees on Development Sites' AS 4970 2009 as explained within Notes of Appendix-A. To retain specific trees and ensure their viability development must take into consideration protection of the Tree Protection Zone (TPZ) radius as identified within Appendix- A Notes: *acceptable incursions*. As a guide to determining impacts the Structural Root Zone (SRZ) & Tree Protection Zone (TPZ) setbacks have been provided within Appendix- C the SRZ & TPZ distance column.
  - Unless specified otherwise all distances and development offsets within this report are taken from the centre of the tree.
- iv Plans and documentation received to assist in preparation of this report include:

Cottee Parker Architects job No: 5914 specific to:

- Floor Plan Basement 01 Dwg No. SK2007 issue A dated 25.11.19
- Floor Plan Lower Ground Dwg No. SK2008 issue A dated 25.11.19
- Ground Floor Plan Dwg No. SK2009 issue A dated 25.11.19
- Floor Plan Level 1 Dwg No. SK2010 issue A dated 25.11.19
- Section A & B Dwg No. SK3101 issue A dated --,--,--

#### Intrax Consulting Group

Survey Plan Drawing No. 125698 Sheet 2 rev A dated 20.11.2019

#### 1. SUMMARY OF ASSESSMENT

#### 1.1 General tree assessment

1.1.1 Forty one (41) trees have been assessed under this development proposal with smaller shrubs at or <4m in height located within the assessment area. Of the trees assessed five (5) trees are located within neighbouring properties, Thirteen (13) trees are situated within adjacent Council verges of which T19, 23 & 24 are partly located on the boundary, four (4) contain low retention values and three (3) trees are non-prescribed exempt species. <a href="Exempt trees"><u>Exempt trees</u></a> are identified as trees: 5, 5a(x3) & 27. Being non-prescribed trees and exempt from protection the trees are permitted to be managed (pruned, removed or relocated) without Council consent. Should an exempt

trees and exempt from protection the trees are permitted to be managed (pruned, removed or relocated) without Council consent. Should an exempt specimen require retention prior to works occurring within specified Tree Protection Zone (TPZ) setbacks further advice from an appointed project arborist is required.

<u>Low retention value trees</u> are identified as trees: 6, 14, 28 & 37. The trees have been assessed as containing structural decline having low remaining safe site usefulness. The trees are considered trees which should not restrict development applications due to their short remaining life expectancies.

Neighbouring trees are identified as trees: 1a, 2, 20, 21 & 22. Design proposes a minor basement Tree Protection Zone (TPZ) occupancy adjacent tree 2, with T20 containing Laneway vehicle impact damage that may become problematic in the future. T20 may also require minor canopy reduction pruning to adequately clear the proposed building line elevation. Remaining trees receive negligible TPZ interference by design.

<u>Council managed trees</u> are identified as trees: 1, 12, 13, 17, 19, 23, 24, 30, 31, 32, 33, 34 & 35. Trees 12, 13 & 17 are located where alterations occur within designated tree protection zones with remaining trees unlikely to be affected by the design proposal given correct tree protection methodology.

1.1.2 The majority of trees assessed are considered viable for retention without change in existing site conditions or modification within their Tree Protection Zone (TPZ) radiuses, refer Appendix- C the SRZ & TPZ distance column.

#### 1.2 The development proposal

1.2.1 The development proposal consists of constructing a new residential apartment facility with deep excavation for basement levels and associated infrastructure to accommodate design.

Figure 1, showing proposed development footprint



#### 1.3 Discussions of development impacts – prescribed trees

- 1.3.1 Trees which fall within proposed building footprints, or receive high level canopy impact or encroachments within Structural & Tree Root Zone areas requiring removal to accommodate design are identified as trees: 4, 4a, 6, 7, 10, 11, 14, 15, 16, 18, 19, 23, 24, 25, 26, 28, 28a, 29 & 37.

  Of these trees T6, 14, 28 & 37 contain low retention values and trees 18, 19, 23, 24 & 25 are located where their location to and within infrastructure (retaining walls & kerb) will likely become problematic in the future.
- 1.3.2 Remaining tree discussions and encroachments by design is summarised as follows:
  - Tree 1 & 1a Negligible basement encroachment by design within TPZ setbacks with fence lines to be constructed to protect underlying tree roots.
  - Tree 2 Minor encroachment by basement footprint where no over excavation beyond the line of the basement cut is recommended to manage additional encroachment within the 7.2m TPZ. Landscape and minor works are to be mindful of tree protection requirements specific to works within the TPZ and 2.7m SRZ exclusion zone.
  - Tree 3 Minor TPZ occupancy by landscape design with basement cut located outside of the 3.6m TPZ. Landscape and minor works are to be mindful of tree protection requirements specific to works within the TPZ and 2.1m SRZ exclusion zone.
  - Trees 8 & 9 Retainable in design given appropriate tree protection with minor TPZ occupancy as shown within Plan SK2009. Trees likely to receive low level root zone impacts due to restricted root spread by adjacent T10 & 11. Landscape and minor works are to be mindful of tree protection requirements with suspended walkway above ground level to minimise impacts within tree protection zones.
  - T12 & 13 T12 specific, design proposes a moderate to high level of TPZ interference with slight SRZ occupancy by new site access and bin loading bay proposed within the 2.4m SRZ & 5.4m TPZ. Similarly T13 receives a moderate to low and manageable level of occupancy within the 3m TPZ. The retention of the trees requires tree sensitive design techniques such that underlying tree roots are not disrupted by works. This should include suspending structures above ground level, no compaction or excavation cut within structural root zones without prior arborist advice and tree root investigations to provide more information on the impact to critical roots. Final engineered and civil design drawings including sections and elevations of the pathway sweep and suspended bin loading bay are to be provided for review and endorsement by an appointed project arborist prior to obtaining a Construction Certificate (CC). In specific the waste enclosure or bin loading bay is to be suspended above ground level and preferably cantilevered towards T17 to minimise disturbance within tree protection zones. New entrance gate and boundary fence construction is to be mindful of tree protection requirements specific to spanning across the SRZ, and suspended or constructed on top of ground level within tree protection zones.

- T17 Design proposes a major to high level of coverage and disturbance within a 13.8m TPZ. The TPZ has been determined by two trunk diameters of 550 & 600mm(Ø) where individual stems would normally contain between 6 to 7m TPZ setbacks. Given individual stem diameters a 6m development exclusion zone is recommended as being a tree protection area (TPA). Within the TPA no works should occur primarily due to tree and canopy lean to the north where landscape design and an increased tree management area should be provided towards and within Apartment 5 courtyard. Within the 6m TPA existing levels are to remain with no site modifications and landscape infrastructure installed without prior project arborist advice, which includes any boundary fence or wall construction within the TPZ as identified with Elevation 01, Section B and Plan SK2009. As specified within T12 & 13 discussions clearer more detailed engineered design drawings and footing plan for the suspended bin loading bay is required to address areas of footing location, potential root conflict by excavation with details of footing excavation and construction methodology within the 3.5m SRZ to be reviewed and endorsed by an appointed project arborist. Within the SRZ tree root investigations should be conducted to identify the location and impact to critical roots by the proposal.
- Trees 20, 21 & 22 receive negligible impact by design being protected by adjacent Laneway road infrastructure. Canopy conflicts may exist where T20 may require minor canopy reduction pruning to accommodate Apartment 7 building elevation.
- Trees 30 to 34 Given the setback of the development footprint, basement cut and site access minor to negligible TPZ occupancy occurs by design. Landscape and minor works are to be mindful of tree protection requirements specific to works within the TPZ and SRZ exclusion zones.
- Trees 35 & 36 Within a 3.5m radius of T36 existing levels for landscape design should remain at RL7.4 where minor excavation to accommodate the access pathway within the 3.6m TPZ is unlikely to affect tree vitality. No landscape alteration works are to occur within SRZ setbacks without prior arborist advice. Pathway construction is to adopt tree sensitive design techniques being constructed on top of ground level within the SRZ to avoid disruption to underlying tree roots. Landscape and boundary fence works are to be mindful of tree protection requirements specific to the SRZ exclusion zone, spanning over SRZ areas with fence construction suspended on top of ground level within tree protection zones.

#### 2. CONCLUSIONS & RECOMMENDATIONS

#### 2.1 Tree Removal

2.1.1 Under the current proposal and with the consent of Council nineteen (19) trees require or are recommended for removal to accommodate design. The nineteen trees are identified as trees: 4, 4a, 6, 7, 10, 11, 14, 15, 16, 18, 19, 23, 24, 25, 26, 28, 28a, 29 & 37.

Exempt non-prescribed trees 5, 5a & 27 are permitted to be managed (pruned, removed or relocated) without the consent of Council.

#### 2.2 Recommended tree management & protection principles

2.2.1 In addition to the recommendations provided within this report and Australian Standard AS4970 – 2009 Protection of Trees on Development Sites the following summary and/or additional recommendations are provided as a guide for tree protection during works:


#### Specific recommendations

- Trees 12, 13 & 17. A summary of tree management requirements are discussed below based on development site disturbances within the SRZ & TPZ:
  - Detailed engineered or civil design plans including footing locations and areas of excavation for the suspended bin loading bay and swept path are to be reviewed and endorsed by an appointed project arborist prior to obtaining a Construction Certificate (CC).
  - Where excavation is proposed within the SRZ detailed tree root investigations are to be conducted to provide more information on the location and likely impact on critical tree roots.
  - Where possible suspended structures should be cantilevered towards trees with proposed fill for uniform footpath levels to be of a certified clean uncontaminated free draining sandy loam material to avoid detrimental capping of the natural soil surface.
  - Tree 17 requires a 6m tree protection area where no disturbance or major alteration is to occur, primarily to the southern anchoring root zone being those roots that take up stain of tree lean. To mitigate overall TPZ encroachment and occupancy by the proposed design landscape retaining walls or structures should be excluded from the 6m TPA. The tree protection area is to be appropriately fenced, managed and maintained at existing levels. Should alterations within the TPA be required further advice and certification from an appointed project arborist is to be obtained prior to the commencement of works.

#### 2.2.2 General requirements

- 1. Prior to demolition works Tree Protection Fencing (TPF) and/or zones as identified within Figure 2 are recommended to be located under the guidance of an appointed site arborist. Unless specified otherwise the location of tree protection fencing is to be positioned to allow for adequate work access and/or be located at the extremity of the TPZ radius, see SRZ & TPZ distance column Appendix- C.
  Where design & construction access may be restrictive timber beam trunk protection is recommended to be installed, with ground protection mats provided to protect underlying tree roots within tree protection zones or areas.
- 2. In accordance with AS4970 2009 (1.4.4) a Project Arborist is to be engaged to monitor, supervise excavation within TPZ setbacks, advise and provide certification of protection works conducted. The project arborist is recommended to be suitably qualified having a minimum Australian Qualification Framework (AQF) Level 4 certification and be competent in methodology of protecting trees on development sites.
- 3. The project arborist is to provide final certification outlining tree protection measures with photographic evidence of ongoing works retained for certification purposes (AS4970 S/5.5.2 *Final certification*).
- 4. The project arborist is to be familiar with protection measures specific to Australian Standard AS4970 'Protection of Trees on Development Sites' – 2009 requirements with any modification in Tree Protection Fencing (TPF) or Zones (Z) to be compliant with AS4970 Section 4.5 Other Tree Protection Measures.

Figure 2: tree protection fencing, ground and trunk protection detail



All tree protection fencing requires appropriate signage clearly stating *a TPZ restriction area* being a designated Tree Protection Zone.

- 5. **Hold points**: Hold points specific to *no works are to commence without arborist advice, inspections & certifications*: 1) No works shall occur within the SRZ without prior arborist advice and certification. 2) No excavation shall occur within the TPZ without prior project arborist notification and/or site supervision.
  - It is the responsibility of the principle contractor to complete each task identified within Table 1 to ensure trees are appropriately managed in accordance with Australian Standard AS 4970 2009 Protection of Trees on Development Sites.

Table 1, certification requirements & hold points

1	Pre- construction	Prior to works install tree protection fencing & zones as specified or as directed by the site arborist
		Project arborist to review and endorse suspended design drawings to protect underlying tree roots adjacent T12 & 17
2	During construction	Project arborist to supervise & certify approved works within the SRZ and TPZ
3	Post construction	Prior to handover project arborist to provide final inspection & certification of tree health & vitality

- 6. Unless specified otherwise during approved excavation within TPZ setbacks excavation is to be conducted manually (by hand) under the supervision of an appointed project arborist. Where approved by the arborist the pruning of roots at or <30mm(Ø) is to be conducted in accordance with AS4970 2009 Section 4.5.4 Root protection during works within the TPZ, such that tree roots are not damaged or ripped beyond the point of excavation by site machinery. Where larger roots have been encountered they are to be referred to an independent Level 5 arborist for further advice. For deep excavations exposed roots at the excavated cut face are to be protected with jute mesh, geotextile fabric or similar being secured in place to avoid drying of roots and the exposed soil profile.
- 7. The storage of materials and fill within tree protection zones is to be avoided. Should storage be required further advice and certification from the appointed project arborist is recommended.
- 8. Canopy pruning / tree removal: where required tree removal and canopy reductions are to be approved by the Local Government Authority. Works are to be conducted by a suitably qualified AQF Level 3 arborist in accordance with AS4373 Pruning Standards, and specifically be conducted in accordance with Safe Work Australia Guide to managing risks of tree trimming and removal works 2016 (www.swa.gov.au).
- 9. Boundary fence and minor retaining wall construction: to avoid disturbance to underlying tree roots boundary fences and landscape retaining walls should span across the SRZ being suspended above ground level supported by pier and beam construction within the TPZ.

- Additional inground services which may include landscape works, sewer, stormwater, water and electrical services, final design and impact to trees shall be reviewed and endorsed by the project arborist prior to their installment.
- 11. To ensure tree(s) are appropriately protected the development site superintendent is recommended to be familiar with all tree protection requirements as outlined within this report. The superintendent is responsible for informing all subcontractors of the responsibilities and requirements of tree protection prior to their engagement.

Should you require further liaisons in this matter please contact me direct on 0419 250 248

Yours sincerely

Mark A Kokot

AQF Level 5 consulting arborist

Diploma of Hort/Arboriculture (AQF5), Associate Diploma Parks Management (AQF4) Certified Arborist / Tree Surgeon (AQF3), ISA Tree Risk Assessment Qualified 6/2014 Member: ISA, Arboriculture Australia & IACA, Working With Children No: WWC0144637E





Ref No: RTC-16719 3 Central Rd AVALON BEACH – arborist DA – 9.12.2019

# Appendix- A: Terminology, noted & references 13 Appendix- B: Tree Retention Values *Checklist* 14 Appendix- C: Tree Assessment Schedule 15 Appendix- D: Tree Location Plan 20

#### **APPENDIX- A:** Terminology, notes & references

**Acceptable Risk:** Exposure to or reject risk of varying degrees. The acceptable risk is defined as 'The person who accepts some degree of risk in return for a benefit being exposed to some risk of varying degree.


Age classes: (I) Immature refers to a well established but juvenile tree. (ESM) refers to an early semi mature tree not of juvenile appearance. (SM) Semi-mature refers to a tree at growth stages advancing into maturity and full size. (LSM) Late Semi-Mature, refers to a tree between semi-mature and close to mature. (EM) refers to a tree at the first stages of maturity. (M) Mature refers to a full size tree with some capacity for future growth. (LM) Late mature refers to a tree entering into over maturity (OM) and likely first stages of senescence. Health: Refers to a trees vigor exhibited by the crown density, leaf colour, presence of epicormic shoots, ability to withstand disease invasion and the degree of dieback, Condition: Refers to the tree's form and growth habit, as modified by its environment (aspect, suppression by other trees, soils) and the state of the scaffold (i.e. Trunk and major branches), including structural defects such as cavities, crooked trunks or week trunk / branch junctions. These are not directly connected with health and it is possible for a tree to be healthy but in poor condition. **Decay:** (N) – an area of wood that is undergoing decomposition. (V) – decomposition of an area of wood by fungi or bacteria. **Decline:** Is the response of a tree to a reduction of energy levels resulting from stress. Recovery from decline is difficult and slow; is usually irreversible. Defect: A identifiable fault in a tree. Epicormic Shoots: Shoots that arise from latent or adventitious buds that occur on stems and branches and on suckers produced from the base of the tree. A symptom / result of stress related factors. Footprint: The area occupied by site structures, including the dwelling driveways and hard surfaces. Included Bark: (Inclusion) a genetic weak fault, pattern of development at branch junctions where the bark is turned inwards rather than pushed out, can pose a potential hazard. Order of branches: First order being those that are the first to extend from the main trunk or codominant limbs, second order branches extend from the first order and third order branches extend from the second order. **Probability:** The likelihood of some event happening. **Risk:** Is the probability of something adverse happening. **Suppression:** Restrained growth pattern from competition of other trees or structures. Wound: Damage inflicted upon a tree through injury to its living cells, may continue to develop further weakening of the structure compromising structural integrity.


**NOTE 1**: This report acknowledges the current **Australian Standards 'Protection of Trees on Development Sites'** AS 4970 – 2009 with reference to the Tree Protection Zone (TPZ): being a combination of the root and crown area requiring protection. The TPZ takes into consideration the Structural Root Zone (SRZ): The area required for tree stability. Determined by AS4970 - 2009 Figure 1, Table of determining the SRZ, section 3.3.5 of the standards. The standard states where a greater than 10% encroachment occurs the arborist is to take into consideration the schedule of determining impacts as set within AS4970 s. 3.3.4. Encroachments are referred to within this report as major or minor encroachments (AS4970 s. 3.3.2 & 3.3.3). Below is the terminology used for estimated percentage of development incursion used within this report. To retain specific trees and ensure their viability development must take into consideration protection of the TPZ radius.


#### NOTE 2: The extent of inclusion within the TPZ radius has been categorised as follows:


Development encroachments are referred to as No impact (0%) incursion, Low impact (<10%) of minor consequence, Medium impact (<20%) incursion where the project arborist is to demonstrate the tree/s remain viable by tree sensitive construction techniques, and High level impact (>20%) where design changes or further information is required to manage tree vitality.

Showing acceptable incursion within the TPZ (AS4970)









#### **SELECTED REFERENCES:**

<u>Barrell J. 1993</u>, 'Preplanning Tree Surveys: Safe useful Life expectancy (SULE) is the Natural Progression", Arboricultural Journal 17: 1, February 1993, pp. 33-46.

International Society of Arboriculture (ISA) 2013, Tree Risk Assessment Manual, Martin Graphics, Champaign Illinois U.S.

Mattheck, C. & Breloer, H.(1994) The Body Language of Trees. Research for Amenity Trees No.4 the Stationary Office. London.

<u>Matheny N. & Clark J. 1998</u>, Trees & Development 'A Technical Guide to Preservation of Trees During Land Development' International Society of Arboriculture, Champaign USA.

<u>Standards Australia 2009</u>, *Australian Standards 4970 Protection of Trees on Development Sites* - Standards Australia, Sydney, Australia.

#### APPENDIX- B: Tree Retention Value Checklist @rainTree consulting

VTA i) Landscape Significance (LS): The significance of a tree in the landscape is a combination of its amenity, environmental and heritage values.

Values may be subjective however, are based after IACA Sustainable Retention Index Value (SRVI) which offer a visual understanding of the relative importance of the tree to the environment. The Landscape Significance for this assessment is described in seven categories to assist in determining the retention value of trees.

1 Sigi	nificant	2	Very High	3	High	4	Moderate	5	Low	6	Very Low	7	Insignificant
--------	----------	---	-----------	---	------	---	----------	---	-----	---	----------	---	---------------

#### ii) Visual Tree Assessment (VTA)

, •	Sual free Assessment (VTA)							
0	If appropriate to VTA - *exempt trees from Local Government Authority (LGA) Tree Management or Preservation Orders (TPO)	2E	Trees location likely to be affected by infrastructure restricting root growth potential, or tree has potential to cause infrastructure damage where risk					
0A	Noxious or invasive species located within heritage conservation area		mitigation or rectification works may likely compromise tree, trees may be contained within a vault having restricted root development / anchorage					
1	Trees that are dead, significantly declining >75% volume or obviously hazardous	3	This rating incorporates trees that may require further investigation of defects such as cavities or symptoms indicating internal decay to an extent that					
2	Trees that are structurally damaged. Have poor structure or weak & detrimental large stem inclusions capable or failure opposed to 2B. Tree also may be affected by extensive borer damage, fungal pathogens (wood rot) or viruses. Some symptoms may be reversible, remediated or controlled give appropriate management.		cannot be quantified under visual examination. Further inspections may be in the way of arborist climbing inspection within the canopy, root crown investigation and/or drill penetrating or Picus Sonic Tomograph ultrasound testing procedures to determine percentage of internal decay.					
2A	Tree damage specific to basal and/or root plate damage, very shallow soils or steep topography resulting in poor anchorage where condition may become problematic in near future / may include trees with included bark splits to ground level	4	Trees which appear specifically environmentally stressed by drought, poor soil or site conditions. Symptoms may be reversible given appropriate management					
2B	Defect specific to stem inclusions development (weak branch attachments) where the condition may not be immediately detrimental however, require annual to biannual	5	Trees that would benefit from crown maintenance pruning as identified within the Australian Standards AS 4373 – 2007 Pruning of Amenity Trees					
	monitoring with control to prevent stem failure by installing slings, cable or bracing. Tree may also contain multi stems or codominant twin stems	5A	Trees that require little or no maintenance at time of inspection other than close monitoring					
2C	Tree may contain minor wounds, pest or minor pathogen activity, altered from storm damaged to an extent that is not considered immediately detrimental - may also display average form. Likely to require close annual monitoring or minor corrective pruning	6	Trees may be typical for species type, of good form and visual condition for age class  May have suppressed one sided canopies or are low risk trees					
2D	Trees significantly altered by recent storm or over pruning events which may reduce retention values due to average form- or tree extensively pruned for power line clearance	7	VTA restricted by canopy or plant material vine or ivy covering tree parts, or site conditions which do not allow access- fences to neighbouring sites					

**iii)** Retention Value (RV): Determined by [1] tree fee of visual defects and viable for retention, [2] viable for retention with minor faults which may reduce ULE, [3] trees which should not restrict development applications containing faults that are likely to become problematic in the short term, [4] trees to be considered for removal due to average condition.

1	High retention	2	Medium retention	3	Low retention	4	Consider removal
---	----------------	---	------------------	---	---------------	---	------------------

iv) <u>U.L.E. categories</u> Useful Life Expectancy (after *Barrell* 1996, modified by the author). A trees U.L.E. category is the life expectancy of the tree modified first by its age, health, condition, safety and location. U.L.E. assessments are not static but may be modified as dictated by changes in trees health and environment.

- 1. Long U.L.E. Appear retainable at the time of assessment for over 40 years with an acceptable degree of risk assuming reasonable maintenance.
- 2. Medium U.L.E. Appear to be retainable at the time of assessment for 15 to 40 years with an acceptable degree of risk assuming reasonable maintenance.
- 3. Short U.L.E. Trees appear to be retainable at the time of assessment for 5 to 15 years with an acceptable degree of risk assuming reasonable maintenance.
- 4. Very short Removal- Trees which should be scheduled for removal within the very short term or as specified within this report.
- 5. Small, young or regularly pruned Trees under 5m in height that can be easily moved or replaced, includes screen plantings or hedge lines.

#### APPENDIX- C: Tree Assessment Schedule

	Trees requiring remove - subject to Local Gove					n	Trees with low retention values: senescence, developing defects or being *exempt trees from the LGA Tree Preservation Order (TPO)							
Tree No	Botanical Name COMMON NAME	Height x spread (m)	DBH (mm)	SRZ TPZ	Age	Health	Condition	Signifi -cance	VTA	RV	U. L.E.	Comments CV = Council verge tree NT= Neighbouring tree		
1 CV	Melaleuca quinquenervia Paperbark	15 x 12	800	3m 9.6	M	Good	Fair	3	2C/3	2	2?	Open cavity & wound on lower trunk N side benefit from further investigations, with minor stem inclusion development throughout		
1a NT	Phoenix canariensis Phoenix Palm	8 x 6	600	4	EM	Good	Good	4	7	1	2	Restricted VTA, above ground visual parts appear in good order		
2 NT	Eucalyptus robusta Swamp Mahogany	17 x 14	600	7.2	M	Fair / Good	Fair / Good	3	4/7	2	3	Environmentally stressed minor decline in canopy, epicormic shouts throughout upper branch scaffolds, minor wounds evident on lower branch scaffolds with no significant branch overhang		
3	Angophora floribunda Rough Barked Apple	12 x 6	300	2.1 3.6	ESM	Fair / Good	Fair / Good	3	4	2	2	Environmentally stressed minor decline in canopy with minor fine tip decline		
4	Glochidion ferdinandi Cheese Tree	6 x 5	150, 100	2.1 4.2	ESM	Good	Good	4/3	6	1	1	Skewed bowing trunk at ground level with no significant defects noted		
4a	Glochidion ferdinandi Cheese Tree	7 x 8	300at base	3.6	ESM	Good	Fair / Good	4/3	2C/B	2	3	Twin stems at 0.4m with minor stem inclusion development = likely to become problematic in the future, contains past reduction pruning cuts E side to 2.4m		
*5	Citharexylum spinosum Fiddlewood	11 x 9	750at base	2.8 9	ESM	Fair / Poor	Fair	5	0/2C	2	3	Exempt tree species, appears stressed with lower epicormic shoots throughout and minor junction faults		
*5a x3	Nerium oleander Oleander	av 6 x 6	av 500at base	2.5 6	SM	Good	Fair / Good	5	0/6	2	3	Exempt tree species, multi stemmed at base		
6	Corymbia gummifera Bloodwood	9 x 2	250	3	ESM	Fair	Poor	4	2D/4	3	<3	Past significant pruning modifying form with significant decline in canopy = low retention value		
7	Acmena smithii Lilly Pilly	4 x 4	200	1.8 2.4	ESM	Good	Fair	4/3	2C	2	2	Extensive epicormic growth shoots at base, low broad form with past pruning cuts evident		

	Trees requiring remove - subject to Local Gove					n	Trees with low retention values: senescence, developing defects or being *exempt trees from the LGA Tree Preservation Order (TPO)							
Tree No	Botanical Name COMMON NAME	Height x spread	DBH (mm)	SRZ TPZ	Age	Health	Condition	Signifi -cance	VTA	RV	U. L.E.	Comments CV = Council verge tree		
8	Angophora costata Angophora	(m) 15 x 14	550	2.7m 6.6	ESM	Good	Good	3	6	1	1	NT= Neighbouring tree  Suppressed canopy form biomass & slight lean NW, with no significant defects noted		
9	Angophora costata Angophora	14 x 13	500	2.6 6	ESM	Good	Good	3	6	1	1	Suppressed canopy form biomass & slight lean N, with no significant defects noted		
10 x3	Angophora costata Angophora	9 x 7	250	3	ESM	Good	Good	3	6	1	1	Three (3) trees in group averaging 250(Ø) trunks, with no significant defects noted. Likely to require <4m TPZ's		
11	Angophora costata Angophora	7 x 5	250	3	ESM	Good	Good	3	6	1	1	Suppressed canopy form biomass E, with no significant defects noted. Likely to require <4m TPZ		
12 CV	Corymbia gummifera Bloodwood	8 x 5	250, 200	2.4 5.4	ESM	Fair / Good	Good	3	4/6	1	2	Suppressed canopy form biomass SW, very slight decline in canopy – appears slightly environmentally stressed		
13 CV	Eucalyptus acmenoides White mahogany	6 x 5	250	3	ESM	Good	Fair / Good	3	6	1	2	Suppressed canopy form biomass NNW with no significant defects noted		
14	Corymbia gummifera Bloodwood	8 x 5	200	1.8 2.4	ESM	Fair	Fair / Poor	4	4	3	<3	Environmentally stressed, significant decline in canopy, W stem dead, suppressed canopy form = low retention value		
15	Angophora costata Angophora	12 x 14	500	2.6 6	ESM	Good	Good	3	6	1	1	Suppressed canopy form biomass S, low broad canopy 8m S, with no significant defects noted		
16	Eucalyptus robusta Swamp Mahogany	9 x 6	300	2.1 3.6	ESM	Good	Fair / Good	3	2E	2	2	Skewed trunk, base at existing driveway with suppressed canopy form		
17 CV	Eucalyptus piperita Sydney Peppermint	11 x 11	550, 600	3.5 13.8	EM	Fair / Good	Fair / Good	3	4/2C	2	2	Twin stems at ground level, moderate lean & suppressed canopy form biomass N, slightly environmentally stressed with slight decline in canopy, past termite activity noted at pruned stub end cuts		
18	Glochidion ferdinandi Cheese Tree	5 x 3	150at base	1.5	ı	Good	Good	4	6	1	2/5	Twin stems at ground level with no significant defects noted		

	Trees requiring remover - subject to Local Gov					n	Trees with low retention values: senescence, developing defects or being *exempt trees from the LGA Tree Preservation Order (TPO)							
Tree No	Botanical Name COMMON NAME	Height x spread (m)	DBH (mm)	SRZ TPZ	Age	Health	Condition	Signifi -cance	VTA	RV	U. L.E.	Comments CV = Council verge tree NT= Neighbouring tree		
19 CV	Corymbia citriodora Lemon Scented Gum	14 x 10	300	2.1 3.6	ESM	Good	Good	4	2E	2	2	Majority of tree base on Council verge. Tree location to infrastructure likely to become problematic in the future with no significant defects noted		
20 NT	Angophora costata Angophora	9 x 12	500	2.6 6	ESM	Good	Fair / Good	3	2C	2	2	Vehicle impact wound at 3m, low canopy form extending into site by 2m at 3m above ground level		
21 NT	Angophora costata Angophora	9 x 8	350	2.3 4.2	ESM	Good	Fair / Good	3	2C	2	2	Skewed lower narrow trunk with no significant defects noted		
22 NT	Glochidion ferdinandi Cheese Tree	8 x 9	250, 250, 300	9.6	ESM	Good	Fair / Good	3	2B	2	2	Main stems dividing at 1m with very minor stem inclusion development with low broad form		
23 CV	Callistemon viminalis Bottle Brush	6 x 5	350at base	4.2	SM	Fair / Good	Fair / Poor	4	2A/4	3	3	Majority of tree base on Council verge. Three (3) stems at base, N side stem inclusion development at ground level – likely to become problematic in the future, upper branch scaffolds with minor damage = low retention value		
24 CV	Leptospermun petersonii Lemon Scented Tea Tree	5 x 5	250at base	3	ESM	Fair / Good	Fair	4	2B	2	3/5	Majority of tree base on Council verge. Low bowing lean W, twin stems at 1.2m with minor stem inclusion development - likely to become problematic in the future		
25	Leptospermun petersonii Lemon Scented Tea Tree	6 x 7	250, 350	7.2	ESM	Fair / Good	Fair	4/3	2A/B	2	3	Majority of tree base within site. Significant low bowing lean 6m W at 3m above ground level. Twin stems at ground level with stem inclusion development + minor stem inclusion development within lower branch scaffolds		
26	Callistemon viminalis Bottle Brush	7 x 5	250at base	1.8 3	SM	Fair / Good	Fair	4	4/2B	2	3	Environmentally stressed with low foliage volume, twin stems at 1m with stem inclusion development		
*27	Callistemon Harkness Bottle Brush	2.5 x 2	100at base	1.5	SM	Good	Fair / Good	5	0/7/2 B	2	3/5	Exempt species height class. Restricted VTA vine covered, appears Environmentally stressed		

	Trees requiring remove - subject to Local Gove					n	Trees with lo					developing defects or being *exempt TPO)
Tree No	Botanical Name COMMON NAME	Height x spread (m)	DBH (mm)	SRZ TPZ	Age	Health	Condition	Signifi -cance	VTA	RV	U. L.E.	Comments CV = Council verge tree NT= Neighbouring tree
28	Callistemon viminalis Bottle Brush	7 x 4	250at base	1.8	SM	Fair / Good	Fair	5	7/2A	3	<3	Suppressed canopy form biomass NNW, lower base abnormalities with vine covered canopy = low retention value
28a	Leptospermun petersonii Lemon Scented Tea Tree	5 x 3	250at base	1.8 3	SM	Good	Fair	5	2C	2	3	Suppressed canopy form + moderate lean NE, with past stub end pruning cuts at 1.2m E side
29	Leptospermun petersonii Lemon Scented Tea Tree	8 x 6	350at base	4.2	M	Good	Fair	5	2B/A	2	3	One sided canopy biomass E, twin stems at ground level with stem inclusion development, + minor stem inclusion development at 0.6m W side
30 CV	Leptospermun petersonii Lemon Scented Tea Tree	5 x 5	100	1.5 2	ESM	Good	Good	5	6	1	2	Suppressed canopy form with low broad canopy
31 CV	Melaleuca quinquenervia Paperbark	14 x 12	800	9.6	EM	Good	Fair / Good	3	2B	2	2	Lower branch scaffolds with minor stem inclusion development throughout, canopy suppressed on W side with biomass extending NNE - E
32 CV	Eucalyptus acmenoides White mahogany	9 x 4	200	1.8 2.4	ESM	Fair / Poor	Fair	4	4/2C	2	3	Environmentally stressed significant decline in canopy with epicormic shouts throughout & minor wound at base W
33 CV	Eucalyptus acmenoides White mahogany	16 x 7	350	2.3 4.2	ESM	Fair / Good	Good	3	4	1	2	Slightly environmentally stressed, tall forest form with low live crown ratio, minor skewed lower trunk with no significant defects noted
34 CV	Glochidion ferdinandi Cheese Tree	9 x 10	250, 200	2.4 5.4	ESM	Good	Good	3	2C	2	1	Minor wound at 0.4m NE, with no significant defects noted
35 CV	Eucalyptus acmenoides White mahogany	16 x 10	450	2.5 5.4	ESM	Good	Good	3	6	1	1	minor wound at base W side, Suppressed canopy form biomass NNW, canopy low 7m within site at near 6m above ground level
36	Glochidion ferdinandi Cheese Tree	7 x 8	300	3.6	ESM	Good	Fair / Good	3	2C/6	1	1	Suppressed canopy form, low bowing canopy N to 5m at 2.5m above ground level, past pruning cuts evident at 1.8m N side (drip line TPA)

	Trees requiring remov - subject to Local Government			n	Trees with low retention values: senescence, developing defects or being *exentrees from the LGA Tree Preservation Order (TPO)							
Tree No	Botanical Name COMMON NAME	Height x spread (m)	DBH (mm)	SRZ TPZ	Age	Health	Condition	Signifi -cance	VTA	RV	U. L.E.	Comments CV = Council verge tree NT= Neighbouring tree
37	Eucalyptus robusta Swamp Mahogany	12 x 12	450	2.5 5.4	ESM	Poor	Fair / Poor	4/3	4	3	<3	Environmentally stressed significant decline in canopy throughout upper branch scaffolds = low retention value

#### APPENDIX- D: Tree Location Plan

