

SITE STORMWATER MANAGEMENT PLAN


~ 1:200

- Pittwater 21 DCP Section B5 Water Management Compliance -
- B5.1 Water Management Plan
    - storm water addressed within this plan, rainwater, grey water and waste water details by others as per industry standards
  - B5.4 Storm Water Harvesting
    - refer BASIX certificate by others, noting 5000l rainwater storage specified
  - B5.5 Rainwater Tanks
    - not applicable as no increase in impervious area, although note 5000l rainwater storage specified
  - B5.7 Storm Water Management Onsite Detention
    - OSD (30000l) specified to restrict post development peak flows to 'greenfields' conditions
  - B5.9 Stormwater Management Water Quality
    - pre screening to Rainwater Tank and SQID treatment system detailed within 600x600x900 Service Pit
  - Other than Low Density Residential
  - B5.10 Stormwater Discharge into Public
    - to new kerb inlet pit on Darley St East and new 375 RCP over to the existing existing KIP SPP50171 on southern side of Darley St East.

Detailed drainage is to be sized for Construction Certificate submission / Tender documentation by the buildings consulting hydraulic engineer to BCA and Australian Standards and to include pre screening of organic matter before entry to Rainwater tank. Variations to layout to be reviewed and approved by Barrenjoey Consulting Engineers before construction.


STORMWATER FLOW SUMMARY  
(DRAINS ANALYSIS)

Site area	- 1749m2
Existing impervious area	- ~1250 m2 (0m2 modeled)
Proposed impervious area	- ~1500 m2 (1749m2 modeled)
Detention Volume modeled	- 30000l (inc HED chamber)
PSD modeled	- 39 l/s
Existing Site Discharge (100% Pervious ie Greenfields)	
5yr ARI Storm	- 54 l/s
100yr ARI Storm	- 87 l/s
Post Development Site Discharge	
5yr ARI Storm	- 53 l/s (20 uncon, 33 via OSD)
100yr ARI Storm	- 72 l/s (33 uncon, 39 via OSD)




EXISTING INFRASTRUCTURE  
DARLEY ST EAST

NTS



OSD TANK DETAIL

1:100



SECTION 1 THROUGH OSD TANK

~ 1:20

OSD CONTROL  
ORIFICE PLATE DETAIL

1:10


STORMWATER NOTES

1. All roof collection components (ie gutters / DPs etc) are to be located / sized by the Developments Hydraulic Consultant for a 1% AEP event capacity.
2. All Trunk Drainage pipes, as shown on this plan are to be minimum of 300mm dia uno.
3. All pipes to be uPVC to AS 1254:2002.
4. All pipes to be laid at the grade required to match pit invert levels.
5. All pipes to be installed and laid in accordance with AS 3500.3:2003.
6. Thrust blocks to be installed to the trunk drainage pipes in accordance with AS 3500.3:2003.
7. All roof guttering/ down pipes / valley gutters / box gutters etc are to be sized and installed in accordance with AS 3500.3:2003.
8. All pits are to be proprietary uv resistant polypropylene or similar unless noted (approved by the Engineer) and are to include a min 50mm sediment trap in the base and a maximesh screen laid at 45° across the pit to protect the outlet pipe.
9. All pits greater than 600mm in depth are to be proprietary precast concrete (approved by the Engineer).
10. All pits greater than 1000mm in depth are to have adequate access requirements in accordance with OH&S/Workover requirements (ie: minimum dimensions 900x600mm with step irons).
11. All works are to be inspected and certified by the Principle Certifying Authority prior to backfilling.
12. All works requiring certification by the Engineer will require a works as executed survey prepared by a registered Surveyor detailing all levels etc as on the Engineering plans.
13. The system is to be flushed and cleaned of all sediment and debris annually.
14. The system will require regular cleaning and maintenance to ensure its ability to function is maintained.
15. To ensure the system's ability to function is maintained it is to be inspected and certified as operating effectively by a licensed plumber every 5 years, and a engineer every 20yrs.




AS 3500.3 PUMP SYSTEM  
REQUIREMENTS

DARLEY STREET



BASEMENT DRAINAGE PLAN


1:200



PUMP OUT SUMP DETAIL


~ 1:20

Sump to collect seepage (tbc), drive / parking area runoff.  
System to include a proprietary oil and grease separator (+ continuing service/cleaning schedule) .  
refer to AS3500.3 requirements re pump out capacity, volume and alarm requirements etc.  
All to be reviewed / confirmed during construction based on site conditions encountered




NEW KERB INLET PIT DETAIL

~ 1:20




SECTION 1

~ 1:20




SECTION 2

~ 1:20



SECTION 3

~ 1:20



PIPE TRENCH DETAIL

~ 1:20

SECTION 9 PUMPED SYSTEMS

9.1 SCOPE OF SECTION

This Section specifies criteria for pumped systems.

9.2 GENERAL

Pumped systems are for areas normally less than 2000 m<sup>2</sup> where it is not possible for the stormwater to be discharged by gravity through the available gravitational point of connection.  
The pumping equipment shall include a wet well, pumps and motors, pipework and electrical equipment and be located to facilitate easy connection to either the surface water system or the pumped point of connection.

NOTE: An illustration of the application of this Section is given in Appendix L.

9.3 WET WELLS

9.3.1 General

Wet wells, for submersible or non-submersible type pumps, shall be installed in accessible locations.

9.3.2 Construction and materials

The structure shall be sound and constructed of materials that will resist corrosion from ground water and aggressive soils.  
Authorized materials include pre-cast or cast in situ reinforced concrete, corrosion-resistant metals, brickwork or glass-reinforced plastics.

9.3.3 Base

The base shall be constructed of materials compatible with the walls and shall maintain a self-cleansing gradient towards the pump inlet. The base shall be supported on stable ground.

9.3.4 Cover

The cover shall be constructed of similar materials to that of the wet well and shall have removable access openings sized for maintenance purposes. If the access opening is airtight, a breather pipe with a non-corrodible screen shall be installed.

9.3.5 Ladders

Where a wet well exceeds a depth of 1.2 m, a ladder, in accordance with Clause 8.6.5.4, shall be installed.

9.3.6 Combined effective storage

The capacity of the pumped system shall be achieved by a combination of pump capacity and wet well storage between the high and low working levels of the wet well. The combined effective storage comprising the volume able to be pumped in 30 min plus the

wet well storage shall not be less than the volume of the run-off from the storm of ARI = 10 years and duration of 120 min, or as otherwise directed by the authority having jurisdiction. The maximum pump capacity shall be as detailed in Clause 9.4(a). The minimum wet well storage between the high and low working levels expressed in cubic metres shall be 1% of the catchment area in m<sup>2</sup> but in any case shall not be less than 3 m<sup>3</sup>. NOTE: The minimum pump capacity should be 10 L/s.

9.3.7 Alarm

High-level and low-level alarms shall be installed in each wet well and located clear of the discharge from the inlet pipe so that false alarms are prevented. The high level alarm should be set no higher than 100 mm above the invert of the inlet pipe, provided that flooding of habitable or storage areas and vehicle garages shall be avoided. Where flooding could occur the overflow and high-level alarm shall be lowered accordingly to prevent flooding.

9.3.8 Inlet

The invert of the inlet pipe to the wet well shall be located at least 100 mm above the level of the Design Top Water Level.

9.3.9 Sealing

All pipes or apparatus passing through a wall or cover of a wet well shall be sealed with a compatible material.

9.4 PUMPS

The pumps shall be suitable for unscreened stormwater and shall be installed as follows:

(a) Pumps shall be in duplicate. The maximum capacity of each pump shall be selected so that the capacity of the system receiving the discharge is not exceeded. The pump controls shall be set up to enable alternate pump operation at each start. In the event that a pump fails to operate when the water level in the wet well reaches the pump start, the other pump shall be activated and a visible alarm initiated. In the event that both pumps fail to operate, an audible alarm shall be initiated.

(b) Pumping equipment shall be securely fixed to the wet well using corrosion-resistant fixings.

(c) Pumps shall be fitted with a gate valve and non-return valve on the delivery side of each pump.

(d) Pumps shall have flanges or unions installed to facilitate removal.

(e) Pumps shall be controlled so as to limit the number of starts per hour to within the capacity of the electrical motors and equipment, and shall, as far as practicable, empty the contents of the wet well at each operation.

(f) The required pumping rate shall be calculated based on an assessment of the expected inflow and, where appropriate, the allowable discharge rate.

9.5 RISING MAINS


Rising mains shall comply with the relevant Sections of AS/NZS 3500.1 and this Standard, and connect to—

(a) a stormwater or inlet pit; or

(b) direct to a stormwater drain.

9.6 ELECTRICAL CONNECTION


All electrical motors and equipment shall be installed in accordance with AS/NZS 3000.



EXSITING SITE SURVEY

~ 1:300

for detail refer survey by SDG Land Development Solutions ref 7766



SERVICE PIT / OUTLET PIPE DETAIL

~ 1:20

THE PIT IS TO INCLUDE MEASURES TO ACHIEVE THE FOLLOWING LEVELS OF QUALITY CONTROL

(+ continuing service/cleaning schedule) -

Pre-screening of organic matter (eg. leaf litter) prior to collection of rainwater.

Primary treatment (eg. physical screening, rapid sedimentation techniques) of stormwater to collect and retain gross pollutants (i.e. litter and organic matter), coarse sediments (with associated entrained pollutants), and oil and grease prior to the discharge of stormwater from the land

Secondary treatment (eg. fine particle sedimentation and filtration techniques) of stormwater to collect and retain medium to fine sediments (with associated entrained pollutants) prior to the discharge of stormwater from the land

ISSUE:		
Prelim	22. 06. 2019	Issued for comment
DA	24. 06. 2019	Issued for DA submission

Barrenjoey Consulting Engineers pty ltd  
Stormwater Structural Civil  
PO Box 672  
Avon NSW 21107  
M: 0418 620 550  
E: lucashce@bigpond.com  
ABN: 13124694917  
ACN: 124694917

PROJECT:  
PROPOSED AGED  
HEALTH CARE FACILITY  
26 DARLEY STREET  
MONA VALE  
for ~ THOMPSON HEALTH CARE

DRAWING :  
STORMWATER MANAGEMENT  
DETAILING 1

Job No :  
**190609**  
Drawing No  
**SW2<sub>DA</sub>**  
Document Certification  
Barrenjoey Consulting Engineers pty ltd  
per  
Lucas Molloy MIEA CPEng NER Director