



SITE DRAINAGE PLAN






TYPICAL SURFACE INLET PIT DETAIL

STORMWATER SYSTEM DESIGN DATA

SITE DATA

SITE AREA = 860 m<sup>2</sup> (100%)
PROPOSED IMPERVIOUS AREA = 445.6 m<sup>2</sup> (52%)
PROPOSED LANDSCAPED AREA = 414.4 m<sup>2</sup> (48%)
EXISTING IMPERVIOUS AREA = 392.5 m<sup>2</sup> (46%)
EXISTING LANDSCAPED AREA = 467.5 m<sup>2</sup> (54%)



## STORMWATER MANAGEMENT PLAN 13 SAINT ANDREWS GATE, ELANORA HEIGHTS DRAWN DATE CHECKED SCALE @ A1

DATE CHECKED SCALE ®

17 FEBRUARY 2025 1:100

BE Civil (Hons) MIE Aust:



STORM-

"Seascape" Suite 7 22-26 Fisher Rd Dee Why NSW 2099 T 02 9982 7092 F 02 9982 5898 enquire@taylorconsulting.net.au www.taylorconsulting.net.au

DRAINAGE NOTES

+ DENOTES EXISTING GROUND LEVEL

CONSTRUCTION DETAILS.

20 MPa MASS CONCRETE.

CONSTRUCTION WORKS.

PLUMBING CODE.

AVOID TREE ROOTS

BENCHMARK NAIL

IN TOP OF KERB R.L. 84.56 (A.H.D.) MAKE GOOD ALL DISTURBED AREAS.

CONSULTING FOR MORE INFORMATION.

STORM EVENTS AND CLEANED EVERY 6 MONTHS.

FALL STORMWATER PIPES AT 1% MIN. UNLESS OTHERWISE NOTED.

ALL STORMWATER PIPES TO HAVE SOLVENT CEMENT WATERTIGHT JOINTS.

SURFACE GRATES 300 SQ. UNLESS OTHERWISE NOTED.

REMOVE REDUNDANT DRAINAGE PITS AND SEAL PIPES.

APPROVED PRE-CAST PITS MAY BE USED.

SUB-SOIL DRAINAGE TO BE CONNECTED TO THE SITE DRAINAGE SYSTEM AS NECESSARY.

CHECK & LOCATE DEPTH OF EXISTING MAINS & SERVICES PRIOR TO CONSTRUCTION OF STORMWATER SYSTEM AS VARIATIONS IN POSITION OF MAINS COULD AFFECT DRAINAGE

INSPECTIONS MUST BE UNDERTAKEN BY THIS OFFICE (BY PRIOR ARRANGEMENT WITH

ENGINEER) DURING CONSTRUCTION TO ENABLE FULL CERTIFICATION UPON COMPLETION OF

ALL CONSTRUCTION OF COUNCIL DRAINAGE WORKS TO COMPLY WITH COUNCIL STANDARD.

PIT BENCHING TO BE HALF THE OUTGOING PIPE DIAMETER. CONCRETE FOR BENCHING TO BE

ALL PIPES TO BE LAID ON COMPACTED FINE CRUSHED ROCK OR SAND BEDDING 75mm THICK
& PIPES BACKFILLED WITH COMPACTED SAND TO 300mm ABOVE TOP OF PIPE, ELSE
ATTACHED TO UNDERSIDE OF STRUCTURE AT 600mm c/c AS NECESSARY

PIPE ROUTES SHOWN ARE INDICATIVE ONLY AND SHOULD BE AS NECESSARY ACCORDING TO

CONTRACTOR SHALL ENSURE THAT SERVICES TO BUILDINGS NOT AFFECTED BY THE WORKS ARE NOT DISRUPTED. CONTRACTOR SHALL CONSTRUCT TEMPORARY SERVICES TO MAINTAIN EXISTING SUPPLY TO BUILDINGS WHERE REQUIRED. ONCE WORKS ARE COMPLETE

AND COMMISSIONED THE CONTRACTOR SHALL REMOVE ALL TEMPORARY SERVICES AND

STORMWATER SYSTEM REQUIRES SIGNIFICANT MAINTENANCE DUE TO POTENTIAL HIGH

POLLUTANT LOAD. FILTERS AND POLLUTANT TRAPS SHOULD BE CHECKED AFTER LARGE

PLUMBING AND DRAINAGE WORKS TO COMPLY WITH AS-3500, THE NATIONAL DRAINAGE &

WHERE POSSIBLE DRAINAGE LINES SHALL BE LAID IN AREAS PREVIOUSLY DISTURBED BY OTHER SITE WORKS AND FOLLOW TOPOGRAPHICAL FEATURES TO REDUCE IMPACT AND

THIS STORMWATER MANAGEMENT PLAN HAS BEEN PREPARED FOR SUBMISSION TO COUNCIL/CERTIFEIR AND DOES NOT NECESSARILY CONTAIN ALL APPROPRIATE INFORMATION TO ENABLE FOR ISSUE TO PLUMBER/BUILDER FOR CONSTRUCTION. CONTACT TAYLOR

SITE CONDITIONS, TREE POSITIONS ETC. CONFIRM SIGNIFICANT CHANGES IN PIPES SYSTEM

DETAILS WITH SUPERVISING ENGINEER PRIOR TO COMMENCEMENT OF DRAINAGE