Horton Coastal Engineering Coastal & Water Consulting

HORTON COASTAL ENGINEERING PTY LTD 18 Reynolds Cres Beacon Hill NSW 2100 +61 (0)407 012 538 peter@hortoncoastal.com.au www.hortoncoastal.com.au ABN 31 612 198 731 ACN 612 198 731

Northern Beaches Council Attention: Daniel Milliken (submitted online at the NSW Planning Portal at https://www.planningportal.nsw.gov.au/)

23 February 2023

Development Application DA2021/1612 for Upgraded Coastal Protection Works at 1190-1196 and 1204 Pittwater Road Narrabeen – Safe Design Risk Assessment

1. INTRODUCTION AND BACKGROUND

On 15 September 2022, Northern Beaches Council (in an email from Daniel Milliken to Peter Horton) requested the following:

A "safe design risk assessment considering any hazards to people using the proposed works or in the vicinity of the proposed works. This assessment shall include the following (numbering added for convenience):

- 1. the purpose(s) for which it was designed
- 2. hazard identification, risk assessment and risk control for the key lifecycle stages of the structure, including construction, operation and demolition.
- 3. any control measures necessary to ensure that the plant, substance or structure is without risks to health and safety when used for the purpose(s) for which it was designed or any reasonably foreseeable related activities.
- 4. any likely threats to public safety over the life of the works
- 5. an assessment of any change in likely threats to public safety over the life of the works in response to climate change
- 6. confirmation that any likely threats to public safety over the life of the works do not extend onto public land
- 7. what measures have been incorporated to manage any risk to life and public safety from coastal hazards.

If any hazards relating to the design of the structure that create a risk to the health or safety of persons who are to carry out any construction work on the structure, and are associated only with the particular design and not with other designs of the same type of structure, have been identified please provide the safe design report (obligations under section 295 of the *Work Health and Safety Regulation 2011* (NSW))".

A response to the above is set out below.

2. RESPONSE TO REQUEST FOR INFORMATION

2.1 Item 1 – Purpose

The purpose of the proposed coastal protection works at 1190-1196 and 1204 Pittwater Road Narrabeen is to allow residential development to remain at the subject properties with an acceptably low risk of being damaged by coastal hazards (such as coastal erosion/recession and wave runup) over an acceptably long design life of 60 years. The subject properties already have rock boulder protection works at and seaward, but these are not adequate to provide sufficient protection for an immediate severe storm event, let alone over a design life of 60 years.

The works have also been designed to meet the requirements of relevant legislation, including Section 27(1)(a) of the *Coastal Management Act 2016*, namely that "the works will not, over the life of the works unreasonably limit or be likely to unreasonably limit public access to or the use of a beach or headland, or pose or be likely to pose a threat to public safety". This has been achieved by proposing the placement of the works entirely on private property, and by designing the works to not be damaged by an acceptably rare storm occurring over an acceptably long life (and in fact substantially improving public access along the beach, and public safety, compared to the existing situation).

2.2 Item 2 - Hazard Identification, Risk Assessment and Risk Control

Key hazard identification, risk assessment and risk control considerations for the construction, operation and demolition stages of the works are outlined in Table 1, Table 2 and Table 3 respectively.

Hazard	Risk (prior to controls)	Controls	Residual Risk
Severe storm damaging works or existing development during construction	Medium	Construction of bund containing rock boulders excavated from the subject properties and seaward, plus removal of plant and equipment from beach if severe storm is forecast	Low
Severe storm damaging bund and exposing working platform material	High	Appropriate coastal engineering design of bund, including geotextile filter layer to reduce risk of washout of fine material landward of the bund, plus requirement for Contractor to maintain bund and clean up any material that escapes	Low
Injury to workers during construction activities	Medium	Contractor to implement project WHS Management Plan	Low
Damage to residential development from construction activities	Medium	Alignment of proposed works as far seaward as possible to satisfy public access and coastal processes requirements	Low
Member of public entering works area and being injured	Low- Medium	Bund and signage to delineate works area from public beach, plus ensuring no significant exposed and/or non-signaged or non-fenced hazards at the end of each work day	Low

Hazard	Risk (prior	Controls	Residual
	to controls)		Risk
Severe coastal storm	High	Works have been designed for an acceptably rare storm	Low
damaging works		occurring over an acceptably long life, plus the works are to	
		be inspected after severe storms to assess if repairs are	
	•	required	
Unacceptable	High	Structure has been designed with appropriate cover and	Low
deterioration of		concrete strength to satisfy the durability criteria over the	
structure over design		design life in <i>AS 3600</i> for the marine environment, and	
life		allowance for corrosion of anchors, plus will be subject to a	
		Maintenance Management Plan requiring that the owners	
		maintain the works over the design life	
Beach user trapped on	Medium	In typical high tide conditions at times of low sand levels,	Low
beach in coastal storm		members of the public could climb up the proposed two	
with elevated waves and water levels		access stairs if required, or at the Clarke Street, Mactier	
		Street or South Narrabeen SLSC locations (assuming that	
		Council would provide safe access at these locations). The	
		longest distance to an access out is likely to be about 30m.	
		It is unlikely that the public would be on the beach in	
		severe storms, which are foreseeable in advance, and	
		Council would generally be expected to close public beach	
		accessways at these times. If a member of the public had	
		made the decision to ignore the risks and to enter the beach	
		in a severe storm, access out may be possible at the stairs at	
		the subject properties or other locations as noted above.	
		The owners would consider installation of permanent	
		stainless steel ladders attached to the seawall below the	
		base of the stairs to enable egress at times of exceptionally	
		low sand levels	
Fall from top of seawall	High	Barrier to prevent falls at top of seawall complying with	Low
to beach below		Building Code of Australia	
Fall on stairs	Medium	Riser and going of stairs, plus handrail, complying with	Low
		Building Code of Australia. The fall risk at the end of the	
		stairs at times of exceptionally low sand levels would	
		largely be managed through the owners being educated on	
		the issue, plus having lockable safety gates at the top of the	
		stairs (where required) to exclude children and other	
		unsuitable people from going down the stairs at these times	
Wave overtopping	Medium	Wave return, and removal wave barriers for the stairs, have	Low
causing injury to person		been included in design to reduce volume and frequency of	
near seawall crest in		wave overtopping. Owners will be educated on the issue,	
subject properties		namely that they should not be near the seawall crest at	
		times of severe storms with elevated waves and ocean	
		water levels , and to deploy the barriers when required	

Table 2: Hazard identification, risk assessment and risk control for operation stage of proposed works

Horton Coastal Engineering

Coastal & Water Consulting

Table 3: Hazard identification, risk assessment and risk control for demolition stage of proposed works

Hazard	Risk (prior to controls)	Controls	Residual Risk
Debris remaining on beach from demolished structures	High	Requirement for contractor to appropriately sieve beach material and prepare a demolition methodology for review of Council, including details on measures to reduce risk of deleterious material ending up on beach	Low
Severe storm damaging works area	Medium	Removal of plant and equipment from beach if severe storm is forecast	Low
Injury to workers during construction activities	Medium	Contractor to implement project Work Health and Safety Management Plan	Low

Item 3 – Control Measures 2.3

The wording of this item is considered to more appropriately be "any control measures necessary to ensure that the plant, substance or structure has acceptably low risks to health and safety when used for the purpose(s) for which it was designed or any reasonably foreseeable related activities" (change in italics).

Control measures to reduce risks to health and safety during construction, operation and demolition stages of the works were outlined in Table 1, Table 2 and Table 3 respectively.

2.4 Item 4 – Public Safety

There are no likely threats to public safety over the life of the works. The works have been designed for an acceptably rare storm occurring over an acceptably long life, plus the works are to be inspected after severe storms to assess if repairs are required.

The structure has been designed with appropriate cover and concrete strength to satisfy the durability criteria over the design life in AS 3600 for the marine environment, and allowance for corrosion of anchors, plus will be subject to a Maintenance Management Plan requiring that the owners maintain the works over the design life.

Various controls were listed in Table 2 to address risks associated with a beach user being trapped on the beach in a coastal storm.

2.5 Item 5 – Public Safety under Climate Change

Climate change (in particular sea level rise) was allowed for in the design of the works. That is, the works have been designed for an acceptably rare storm occurring over an acceptably long life, including consideration of climate change.

2.6 Item 6 - Threats to Public Safety on Public Land

As noted in Section 2.4, there are no likely threats to public safety over the life of the works, which by definition means that there are no likely threats to public safety over the life of the works on public land.

It can also be noted that with the works entirely on private property, the risk identified in Table 2 of a beach user trapped on the beach in a coastal storm arises from hazards on public land (namely elevated waves and water levels), that would occur irrespective of whether the proposed works were carried out or not. This risk arises with the beach user located on public land, not the subject properties.

There are no stairs exiting the beach at the subject properties or adjacent public areas of Clarke Street, Mactier Street or South Narrabeen SLSC at present. That is, the proposed works are creating safer egress from the beach in emergencies than the present situation of climbing over haphazard and potentially mobile boulders.

2.7 Item 7 – Measures to Manage any Risk to Life and Public Safety from Coastal Hazards

Control measures to manage risks to life and public safety during construction, operation and demolition stages of the works were outlined in Table 1, Table 2 and Table 3 respectively, including risks related to coastal hazards.

During construction, identified risks related to coastal hazards comprised a "severe storm damaging works or existing development during construction", and a "severe storm damaging bund and exposing working platform material".

During operation, identified risks related to coastal hazards comprised a "severe coastal storm damaging works", and a "beach user trapped on beach in coastal storm with elevated waves and water levels".

During demolition, an identified risk related to coastal hazards comprised "a severe storm damaging works area".

The control measures were outlined in the respective tables above as noted.

2.8 Safe Design Report

The request as follows is addressed in this section:

If any hazards relating to the design of the structure that create a risk to the health or safety of persons who are to carry out any construction work on the structure, and are associated only with the particular design and not with other designs of the same type of structure, have been identified please provide the safe design report (obligations under section 295 of the *Work Health and Safety Regulation 2011* (NSW)¹)".

It is considered that the particular design of the proposed works has the same sort of risks to the health or safety of persons who are to carry out any construction work, as other designs of the same type of structure (ie different forms of seawall designs). For example, the construction risks identified in Table 1 (namely a "severe storm damaging works or existing development during construction", a "severe storm damaging bund and exposing working platform material", "injury to

¹ Note that this should have been written as the *Work Health and Safety Regulation 2017*.

workers during construction activities", and "members of public entering works area and being injured") would be common to any seawall project. "Damage to residential development from construction activities" may not be common to all seawall projects, but the risk of damage to infrastructure located landward of the seawall would be.

Therefore, the particular design of the proposed works has the same sort of risks to the health or safety of construction workers as other seawall designs, and there is no requirement to consider Section 295 of the *Work Health and Safety Regulation 2017* in this particular matter.

3. SALUTATION

Should you require any additional information or clarification, please do not hesitate to contact Peter Horton via mobile on 0407 012 538, or via email at peter@hortoncoastal.com.au.

Yours faithfully HORTON COASTAL ENGINEERING PTY LTD

Refer Horson

Peter Horton Director and Principal Coastal Engineer

This report has been prepared by Horton Coastal Engineering Pty Ltd on behalf of and for the exclusive use of Narrabeen Seawall Construction Pty Ltd (the client), and is subject to and issued in accordance with an agreement between the client and Horton Coastal Engineering. Horton Coastal Engineering accepts no liability or responsibility whatsoever for the report in respect of any use of or reliance upon it by any third party. Copying this report without the permission of the client or Horton Coastal Engineering is not permitted.