

JAK NEWPORT PTY LTD



Geotechnical Investigation

54-58 Beaconsfield Street, Newport, NSW

Document Control

Report Title: Geotechnical Investigation, 54-58 Beaconsfield Street, Newport, NSW

Report No: E26083.G03_Rev1

Со	ppies	Recipient	
1	Soft Copy (PDF – Secured, issued by email)	Kevin Lam JAK Newport Pty Ltd 10 James Street WATERLOO NSW 2017	
Pro Pro	Original (Saved to Digital Archives) 07 - Projects\E26083_JAK jects_Newport_GI\05_Deliverables\Work in gress\E26083.G03_Rev1 - Geotechnical Investigation bort.docx)	El Australia Suite 6.01, 55 Miller Street, PYRMONT NSW 2009	

Author	Technical Reviewer		
Keyn	John Marie Contraction of the Co		

Kaiyu Xu		Stephen Kim		
Geotechnical Engineer		Senior Geotechnical Engineer		
Revision	Details	Date	Amended By	
	Original	11 October 2023		
1	Updated architectural drawings	6 May 2024	KX	

© 2024 El Australia (El) ABN: 42 909 129 957

This report is protected by copyright law and may only be reproduced, in electronic or hard copy format, if it is copied and distributed in full and with prior written permission by EI.



Table of Contents

				Page Number
1.	INT	RODUC	TION	1
	1.1	Backgr	ound	1
	1.2	Propos	ed Development	1
	1.3	Objecti	ves	1
	1.4	Scope	of Works	2
	1.5	Constra	aints	3
2.	SITI	E DESCI	RIPTION	4
	2.1	Site De	escription and Identification	4
	2.2	Local L	and Use	5
	2.3	Region	al Setting	5
3.	INV	ESTIGA	TION RESULTS	7
	3.1	Stratigr	raphy	7
	3.2	Ground	dwater Observations	8
	3.3	Test Re	esults	8
4.	REC	COMME	NDATIONS	10
	4.1	Geotec	chnical Issues	10
	4.2	Dilapida	ation Surveys	10
	4.3	Excava	ation Methodology	10
		4.3.1	Excavation Assessment	10
		4.3.2	Excavation Monitoring	11
	4.4	Ground	dwater Considerations	12
	4.5	Excava	ation Retention	13
		4.5.1	Support Systems	13
		4.5.2	Retaining Wall Design Parameters	13
	4.6	Founda	ations	16
	4.7	Basem	ent Floor Slab	16
5.	FUR	RTHER C	GEOTECHNICAL INPUTS	17
6.	STA	TEMEN	T OF LIMITATIONS	18
RE	FERE	ENCES		19
ΑB	BRE	VIATION	IS	19



Schedule of Tables

Table 1-1	Augering and Rock Coring Depths	2
Table 1-2	Hand Augering and DCP Depths	3
Table 2-1	Summary of Site Information	4
Table 2-2	Summary of Local Land Use	5
Table 2-3	Topographic and Geological Information	5
Table 3-1	Summary of Subsurface Conditions	7
Table 3-2	Groundwater Levels	8
Table 3-3	Summary of Soil Laboratory Test Results	8
Table 4-1	Geotechnical Design Parameters	15

Appendices

FIGURES

Figure 1 Site Locality Plan

Figure 2 Borehole Location Plan

APPENDIX A - BOREHOLE LOGS AND EXPLANATORY NOTES

APPENDIX B – LABORATORY CERTIFICATES

APPENDIX C - VIBRATION LIMITS

APPENDIX D – IMPORTANT INFORMATION



1. Introduction

1.1 Background

At the request of JAK Newport Pty Ltd (the Client), El Australia (El) has carried out a Geotechnical Investigation (GI) for the proposed development at 54-58 Beaconsfield Street, Newport, NSW (the Site).

This GI report has been prepared to provide advice and recommendations to assist in the preparation of designs for the proposed development. The investigation has been carried out in accordance with the agreed scope of works outlined in EI's proposal referenced P21473.1, dated 22nd June 2023, and with the Client's signed authorisation to proceed, dated 28th July 2023.

1.2 Proposed Development

The following documents, supplied by the Client, were used to assist with the preparation of this GI report:

- Site Survey Plan prepared by SCS Engineering Surveyors Job Number 18084, Drawings No. 18084-DET-01 dated 22 April 2023;
- Architectural Drawings prepared by PBD Architects Project Number 2311, Drawing Nos.
 DA000 to DA004, DA100 to DA104, DA200, DA201, and DA300 to DA302, Issue B, dated 2
 May 2024; and
- Geotechnical Assessment Report prepared by JK Geotechnics Job Number 32714BCrpt, dated 29 October 2019.

Based on the provided documents, EI understands that the proposed development involves the demolition of the existing site structures and the construction of a three-storey residential development overlying a single-level basement. The basement level is proposed to have a Finished Floor Level (FFL) of between RL 13.0m AHD. A Bulk Excavation Level (BEL) of approximately RL 12.7m AHD is assumed, which includes allowance for the construction of the basement slab. To achieve the BEL, excavation depths from 3.7m to 10.7m Below Existing Ground Level (BEGL) have been estimated. Locally deeper excavations may be required for footings, lift overrun pits, crane pads, and service trenches.

1.3 Objectives

The objective of the GI was to assess site surface and subsurface conditions at six borehole locations, and to provide preliminary geotechnical advice and recommendations addressing the following:

- Excavation methodologies and monitoring requirements
- Groundwater considerations
- Vibration considerations
- Excavation support requirements, including preliminary geotechnical design parameters for retaining walls and shoring systems
- Building foundation options, including;
 - Preliminary design parameters



- Earthquake loading factor in accordance with AS1170.4:2007
- The requirement for additional geotechnical works

1.4 Scope of Works

The scope of works for the GI included:

- Preparation of a Work Health and Safety Plan;
- Review of relevant geological maps for the project area;
- Site walkover inspection by a Geotechnical Engineer to assess topographical features and site conditions;
- Scanning of proposed borehole locations for buried conductive services using a licensed service locator with reference to Dial Before You Dig (DBYD) plans;
- Auger drilling of three boreholes (BH1M, BH2, BH3M) by a track-mounted drill rig using solid flight augers equipped with a 'Tungsten-Carbide' (T-C) bit. The boreholes were auger drilled to depths as shown in **Table1-1** below.
- Continuation of BH1M, BH2, BH3M using NMLC diamond coring techniques to termination depths shown above in Table 1-1. The rock core photographs are presented in Appendix A

Table 1-1 Augering and Rock Coring Depths

	A	Augering		Rock Coring	
Borehole ID	Depth (m)	RL (m AHD)	Depth (m)	RL (m AHD)	
BH1M	4.48	13.02	9.62	7.88	
BH2	2.46	16.84	9.05	10.25	
внзм	6.45	13.15	12.00	7.60	

- Standard Penetration Testing (SPT) was carried out (as per AS 1289.6.3.1-2004), where possible, during auger drilling of the boreholes to assess soil strength/relative densities
- Measurements of groundwater seepage/levels, where possible, in the augered sections
 of the boreholes during and shortly after completion of auger drilling
- The strength of the bedrock in the augered sections of the boreholes was assessed by observation of the auger penetration resistance using a T-C drill bit and examination of the recovered rock cuttings. It should be noted that rock strengths assessed from augered boreholes are approximate and strength variances can be expected.
- The approximate surface levels shown on the borehole logs were interpolated from spot levels shown on the supplied survey plan. Approximate borehole locations are shown on Figure 2
- Hand auger drilling of three boreholes (BH4, BH5, and BH6) within grassy areas of the site to a refusal depth of 0.8m BEGL (RL 23.7m)



Three Dynamic Cone Penetrometer (DCP) tests (DCP1, DCP2 and DCP3) were carried out adjacent to BH4, BH5 and BH6 these were carried out to refusal depths of 0.5m (RL 23.9m), 0.75m (RL 23.7m) and 0.7m BEGL (RL 23.8m), respectively;

Table 1-2 Hand Augering and DCP Depths

D 1 . 1 . 1 . 1 . 1 . 1 . 1 . 1	Hand Aug	er Depth	DCP Depth	
Borehole ID	Depth (m)	RL (m AHD)	Depth (m)	RL (m AHD)
BH4	1.1	22.4	1.7	21.8
BH5	1.2	19.8	1.9	19.1
BH6	0.9	19.1	1.6	18.4

- Borehole BH1M and BH3M were converted into groundwater monitoring wells with depths of 9.62m BEL (RL 7.88m) and 12.0m BEGL (RL 7.6m) to allow for long-term groundwater monitoring
- Soil and rock samples were sent to STS Geotechnics Pty Ltd (STS) and SGS Australia (SGS), which are National Australian Testing Authority (NATA) accredited laboratories, for testing and storage.
- Preparation of this GI report.

El's Geotechnical Engineer was present full-time onsite to set out the borehole locations, direct the testing and sampling, log the subsurface conditions and record groundwater levels.

1.5 Constraints

The GI was limited by the intent of the investigation and the presence of existing site structures. The discussions and advice presented in this report are preliminary and intended to assist in the preparation of initial designs for the proposed development. Further additional investigations in the form of boreholes in the northern areas of the site are required following demolition of the existing structures. Further geotechnical inspections should be carried out during construction to confirm the geotechnical and groundwater models, and the preliminary design parameters provided in this report.



2. Site Description

2.1 Site Description and Identification

The site identification details and associated information are presented in **Table 2-1** below while the site locality is shown on **Figure 1**. An aerial photograph of the site is presented in **Plate 1** below.

Table 2-1 Summary of Site Information

Information	Detail
Street Address	54-58 Beaconsfield Street, Newport, NSW
Lot and Deposited Plan (DP) Identification	Lot 7B DP 162021, Lot 6 DP 1096088, 5B DP 158658
Brief Site Description	At the time of our investigation, the three lots were occupied by single storey weatherboard residential dwellings. The dwellings are accessed by a concrete driveway extending uphill from Beaconsfield Street, the driveways varied from fair to poor. The remaining areas of the site were covered with lawns and garden areas.
	The site frontage separating the development site from Beaconsfield, was formed with the use of battered soil, and minor retaining walls.
Site Area	The site area is approximately 2,114m ² (based on the provided survey plan referenced above).



Plate 1: Aerial photograph of the site (source: Metromap, dated 6/5/23)



2.2 Local Land Use

The site is situated within an area of residential use. Current uses on surrounding land at the time of our presence on site are described in **Table 2-2** below. For the sake of this report, the site boundary adjacent to Beaconsfield Street shall be adopted as the Southern site boundary.

Table 2-2 Summary of Local Land Use

Direction Relative to Site	Land Use Description
North	The northern site boundary adjoins a series of residential properties: 19 Queens Parade, a residential brick building offset approximately 16m North-East from the site boundary, with an in ground pool about 2m from the site boundary. 15-17 Queens Parade, a concrete and masonry apartment and townhouse complex with
	an excavated basement carpark of unknown depth. This development is offset approximately 6m from the site boundary.
	11 Queens Parade forms part of a larger development enclosed within SP 105766. This development wraps around the northern and western boundary of the site. Various sections of this development have excavated ground floors and basement levels. The offset from the northern and western boundary various between 1m and 6m.
East	Property at 52 Beaconsfield Street is a double-storey weathered board residential house, with attached carport, lawns and a concrete driveway. The main house has an offset of about 3m from the eastern boundary.
South	Beaconsfield Street is two lane asphalt paved road. Beyond this is a serious of brick and masonry dwellings. These structures are set back from the site boundary between 20 and 35m.
West	11 Queens Parade. Various sections of this property have excavated ground floors and basement levels; however there is no basement excavation beneath the western site elevation. The offset of the building from the western boundary varies between 1m and 4m.

2.3 Regional Setting

Attribute

The site topography and geological information for the locality is summarised in **Table 2-3** below.

Table 2-3 Topographic and Geological Information

Description

Topography	The site is located on the high north side of the road within gentle to moderately (8-10°), South-West dipping topography with site levels varying from R.L. 16.1mAHD at the South-West site corner to R.L. 23.52mAHD at the North-East site corner.
Regional Geology	Information on regional sub-surface conditions, referenced from NSW Department of Mineral Resources. NSW Seamless Geology Data Package, Catalogue Number: 9232 indicates the site to be underlain by the Burralow Formation (member of the Gosford Subgroup), a fine-grained, micaceous, quartz- to quartz-lithic sandstone; interbedded with siltstone, grey shale and red-brown claystone.





Plate 2: Excerpt of geological map showing location of site.



3. Investigation Results

3.1 Stratigraphy

For the development of a site-specific geotechnical model, the stratigraphy observed in the GI has been grouped into five geotechnical units. A summary of the subsurface conditions across the site, interpreted from the assessment results, is presented in **Table 3-1** below. More detailed descriptions of subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**. The details of the methods of soil and rock classifications, explanatory notes and abbreviations adopted on the borehole logs are also presented in **Appendix A**.

Table 3-1 Summary of Subsurface Conditions

Unit	Material ²	Depth to Top of Unit (m BEGL) ¹	RL of Top of Unit (m AHD) ¹	Observed Thickness (m)	Comments
1	Fill/Topsoil	0.00	17.5 to 23.5	0.4 to 0.8	Fill and topsoil was assessed, based on our observations during drilling and DCP/SPT tests to be poorly compacted. Sections of concreted driveway were cracked and degrading.
2	Residual Soil	0.4 to 0.8	16.85 to 22.7	3.83 to 5.9	High plasticity, stiff to very stiff becoming hard silty clay and sandy clay with trace ironstone gravels , grading into extremely weathered sandstone with depth. SPT values ranged from 17 to refusal indicated by hammer bounce.
3	Class V Sandstone	4.48 to 6.45	13.02 to 14.58	0.62 to 0.67	Distinctly weathered, very low to low strength sandstone, with very closely spaced defects.
4	Class IV Sandstone	4.72 to 5.15	12.35 to 14.58	1.45 to 2.08	Distinctly to slightly weathered, low to medium strength sandstone with siltstone laminations. The sandstone generally consisted of closely spaced defects. Unit 4 was not observed in BH3M.
5	Class III Sandstone	6.6 to 7.07	10.9 to 12.53	_4	Slightly weathered to fresh, high strength sandstone. The Sandstone generally consisted of moderately spaced defects. We note that in BH3M, thinly laminated laminite (comprising of sandstone and siltstone) was noted between 10.0m to 10.7m BEGL, or RL 9.6m to 8.9m.

Note 1 Approximate depth and level at the time of our assessment. Depths and levels may vary across the site.



Note 2 For more detailed descriptions of the subsurface conditions, reference should be made to the borehole logs attached to **Appendix A.**

Note 3 Observed up to termination depth in BH4 to BH6.

Note 4 Observed up to termination depth in BH1M to BH3M.

3.2 Groundwater Observations

No groundwater or significant seepage was observed during or after auger drilling of the boreholes. Water circulation due to coring within the boreholes prevented further observations of groundwater levels within BH1M, BH2 and BH3M.

Groundwater monitoring wells were installed in BH1M and BH3M. The groundwater levels were then measured within the monitoring wells as per **Table 3-2** below:

Table 3-2 Groundwater Levels

Borehole ID	Measurement Date	Depth to Groundwater (m BEGL)	Groundwater RL (m AHD)
BH1M	3/8/23	5.65	11.85
внзм	3/8/23	6.76	12.84

3.3 Test Results

Three soil samples were selected for laboratory testing to assess the following:

- Atterberg Limits and Linear Shrinkage
- Soil aggressivity (pH, chloride and sulfate content and electrical conductivity).

A summary of the soil test results is provided in **Table 3-2 and Table 3-3** below. Laboratory test certificates are presented in **Appendix B**.

Table 3-3 Summary of Soil Laboratory Test Results

Test/ Sample ID Unit		BH1M_1.5-1.95	BH1M_3.0-3.45	BH3_3.0-3.45
		2	2	2
Material Description ¹		Silty CLAY	Silty CLAY	Silty CLAY
Aggressivity	Chloride CI (ppm)	30	-	140
	Sulfate SO ₄ (ppm)	37	-	47
	pH	4.8	-	4.9
	Electrical Conductivity (µS/cm)	41	-	110
	Moisture Content (%)	6.6	16.9	8.5
Atterberg Limits	Liquid Limit (%)	-	60.0	-
	Plastic Limit (%)	-	24.0	-
	Plasticity Index (%)	-	36.0	-
	Linear Shrinkage (%)	-	15.0	-

Note 1 More detailed descriptions of the subsurface conditions at each borehole location are available on the borehole logs presented in **Appendix A**.

The Atterberg Limits result on the selected clay sample indicated clays to be highly plastic and moderate shrink-swell potential.

The assessment indicated low permeability soil was present above the groundwater table. In accordance with Tables 6.4.2(C) and 6.5.2(C) of AS 2159:2009 'Piling – Design and



Installation', the results of the pH, chloride and sulfate content and electrical conductivity of the soil provided the following exposure classifications:

- 'Mild' for buried concrete structural elements; and
- 'Non-Aggressive' for buried steel structural elements.

23 selected rock core samples were tested by Macquarie to estimate the Point Load Strength Index (Is_{50}) values to assist with rock strength assessment. The results of the testing are summarised on the attached borehole logs.

The point load strength index tests correlated reasonably well with our field assessments of rock strength. The approximate Unconfined Compressive Strength (UCS) of the rock core, estimated from correlations with the point load strength index test results, varied from <1 MPa to 80 MPa.



4. Recommendations

4.1 Geotechnical Issues

Based on the results of the assessment, we consider the following to be the main geotechnical issues for the proposed development:

- Basement excavation and retention to limit lateral deflections and ground loss as a result of excavations, resulting in damage to nearby structures
- Rock excavation
- Foundation design for building loads

4.2 Dilapidation Surveys

Prior to excavation and construction, we recommend that detailed dilapidation surveys be carried out on all structures and infrastructures surrounding the site that falls within the zone of influence of the excavation to allow assessment of the recommended vibration limits and protect the client against spurious claims of damage. The zone of influence of the excavation is defined by a distance back from the excavation perimeter of twice the total depth of the excavation. The reports would provide a record of existing conditions prior to commencement of the work. A copy of each report should be provided to the adjoining property owner who should be asked to confirm that it represents a fair assessment of existing conditions. The reports should be carefully reviewed prior to demolition and construction.

4.3 Excavation Methodology

4.3.1 Excavation Assessment

Prior to any excavation commencing, we recommend that reference be made to the Safe Work Australia Excavation Work Code of Practice, dated January 2020.

EI understands, based on the client supplied Architectural Drawings, that the proposed basement will require a BEL of RL 12.7m AHD including an allowance for the construction of a basement slab. To achieve the BEL excavation depths ranging from 3.7m to 10.7m BEGL are assumed. Locally deeper excavations for footings, service trenches, crane pads and lift overrun pits may be required.

Based on the borehole logs, the proposed basement excavations will therefore extend through Unit all units as outlined in **Table 3-1** above. As such, an engineered retention system must be installed prior to excavation commencing.

Units 1 and 2 could be excavated using buckets of large earthmoving Hydraulic Excavators, particularly if fitted with 'Tiger Teeth'. Excavation of Units 3, 4 and 5 (where encountered) may present hard ripping, or "hard rock" excavation conditions. Ripping would require a high capacity and heavy bulldozer for effective production. Wear and tear should also be allowed for. The use of a smaller size bulldozer will result in lower productivity and higher wear and tear, and this should be allowed for. Alternatively, hydraulic rock breakers, rock saws, ripping hooks or rotary grinders could be used, though productivity would be lower and equipment wear increased, and this should be allowed for.

Should rock hammers be used for the excavation of bedrock, excavation should commence away from the adjoining structures and the transmitted vibrations monitored to assess how close the hammer can operate to the adjoining structures while maintaining transmitted



vibrations within acceptable limits. To fall within these limits, we recommend that the size of rock hammers does not exceed a medium sized rock hammer (900 kg) such as a Krupp 580, and be trialled with a vibration monitor prior to use. The transmitted vibrations from rock hammers should be measured to determine how close each individual hammer can operate to the adjoining buildings.

The vibration measurements can be carried out using either an attended or an unattended vibration monitoring system. An unattended vibration monitoring system must be fitted with an alarm in the form of a strobe light or siren or alerts sent directly to the site supervisor to make the plant operator aware immediately when the vibration limit is exceeded. The vibration monitor must be set to trigger the alarm when the overall Peak Particle Velocity (PPV) exceeds set limits outlined by a vibration monitoring plan. Reference should be made to **Appendix C** for a guide to acceptable limits of transmitted vibrations.

If it is found that the transmitted vibrations by the use of rock hammers are unacceptable, then it would be necessary to change to a smaller excavator with a smaller rock hammer, or to a rotary grinder, rock saws, jackhammers, ripping hooks, chemical rock splitting and milling machines. Although these are likely to be less productive, they would reduce or possibly eliminate risks of damage to adjoining properties through vibration effects transmitted via the ground. Such equipment would also be required for detailed excavation, such as footings or service trenches, and for trimming of faces. Final trimming of faces may also be completed using a grinder attachment rather than a rock breaker in order to assist in limiting vibrations. The use of rotary grinders generally generates dust and this may be supressed by spraying with water.

To assist in reducing vibrations and over-break of the sandstone, we recommend that initial saw cutting of the excavation perimeters through the bedrock may be provided using rock saw attachments fitted to the excavator. Rock sawing of the excavation perimeter has several advantages as it often reduces the need for rock bolting as the cut faces generally remain more stable and require a lower level of rock support than hammer cut excavations, ground vibrations from rock saws are minimal and the saw cuts will provide a slight increase in buffer distance for use of rock hammers. However, the effectiveness of such an approach must be confirmed by the results of vibration monitoring.

Groundwater seepage monitoring should be carried out during bulk excavation works and prior to finalising the design of a pump out facility. Outlets into the stormwater system will require Council approval.

Furthermore, any existing buried services, which run below the site, will require diversion prior to the commencement of excavation or alternatively be temporarily supported during excavation, subject to permission or other instructions from the relevant service authorities. Enquiries should also be made for further information and details, such as invert levels, on the buried services.

4.3.2 Excavation Monitoring

Consideration should be made to the impact of the proposed development upon neighbouring structures, roadways and services. Basement excavation retention systems should be designed so as to limit lateral deflections.

Contractors should also consider the following limits associated with carrying out excavation and construction activities:

- Limit lateral deflection of temporary or permanent retaining structures;
- Limit vertical settlements of ground surface at common property boundaries and services easement; and



 Limit Peak Particle Velocities (PPV) from vibrations, caused by construction equipment or excavation, experienced by any nearby structures and services.

Monitoring of deflections of retaining structures and surface settlements should be carried out by a registered surveyor at agreed points along the excavation boundaries and along existing building foundations / services/ pavements and other structures located within or near the zone of influence of the excavation. Owners of existing services adjacent to the site should be consulted to assess appropriate deflection limits for their infrastructures. Measurements should be taken in the following sequence:

- Before commencing installation of retaining structures where appropriate to determine the baseline readings. Two independent sets of measurements must be taken confirming measurement consistency;
- After installation of the retaining structures, but before commencement of excavation;
- After excavation to the first row of supports or anchors, but prior to installation of these supports or anchors;
- After excavation to any subsequent rows of supports or anchors, but prior to installation of these supports or anchors;
- After excavation to the base of the excavation;
- After de-stressing and removal of any rows of supports or anchors; and
- One month after completion of the permanent retaining structure or after three consecutive measurements not less than a week apart showing no further movements, whichever is the latter.

4.4 Groundwater Considerations

Groundwater was observed in all monitoring wells as detailed in **Table 3-2**, the highest recorded groundwater was measured just above the proposed BEL for the lowest basement level RL of 12.7m AHD. The groundwater levels are within Class IV sandstone bedrock.

Based on the low permeability of the bedrock profile any groundwater inflows into the excavation should not have an adverse impact on the proposed development or on the neighbouring sites and should be manageable. However, we expect that some seepage inflows into the excavation along the soil/rock interface and through any defects within the sandstone bedrock (such as jointing, and bedding planes, etc.) particularly following a period of heavy rainfall. The initial flows into the excavation may be locally high, but would be expected to decrease considerably with time as the bedding seams/joints are drained. We recommend that monitoring of seepage be implemented during the excavation works to confirm the capacity of the drainage system.

We expect that any seepage that does occur will be able to be controlled by a conventional sump and pump system. We recommend that a sump-and-pump system be used both during construction and for permanent groundwater control below the basement floor slab.

In the long term, drainage should be provided behind all basement retaining walls, around the perimeter of the basement and below the basement slab. The completed excavation should be inspected by the hydraulic engineer to confirm that adequate drainage has been allowed for. Drainage should be connected to the sump-and-pump system and discharging into the stormwater system. The permanent groundwater control system should take into account any possible soluble substances in the groundwater which may dictate whether or not groundwater can be pumped into the stormwater system.



The design of drainage and pump systems should take the above issues into account along with careful ongoing inspections and maintenance programs.

For the design of a drained basement, council and DPE may require seepage analysis as well as long-term groundwater monitoring to confirm the suitability of a drained basement for this development.

4.5 Excavation Retention

4.5.1 Support Systems

From a geotechnical perspective, it is critical to maintain the stability of all adjacent structures and infrastructures during demolition, excavation and construction works.

Based on the provided architectural plans, the basement has limited setbacks from the site boundaries that the zone of influence extends beyond site boundaries. Based on the depth of the excavation, the encountered subsurface conditions and limited setbacks, temporary batters are not recommended for this site. Unsupported vertical cuts in soil are not recommended for this site, due to the risk of soil slumping especially after a period of wet weather. Soil Slumping may results in injury to personnel and/or damage to nearby structures/infrastructures and equipment.

A suitable retention system will be required for the support of the excavation. For this site, EI recommends an anchored and/or propped soldier pile wall with mass concrete in between the piles be founded into Unit 5 - Class III Sandstone below BEL.

Due to the presence of the basement structures adjacent to the site, anchors installation may not be possible and internal props may be required. Details of nearby basements, shoring pile walls and anchors must be obtained prior to final design.

Bored piles are considered to be the most suitable for this site. Tremie pumps may be required where high groundwater seepage inflows are present during the drilling of the bored piles. However, relatively large capacity piling rigs will be required for drilling through the Sandstone bedrock. The proposed pile locations should take into account the presence of buried services.

Further advice should be sought from prospective piling contractors who should be provided with a copy of this report.

Working platforms may also be required. We can complete the design of the working platform, when commissioned to do so.

4.5.2 Retaining Wall Design Parameters

The following parameters may be used for static design of temporary and permanent retaining walls at the subject site:

- Conventional free-standing cantilever walls which support areas where movement is of little concern (i.e. where only gardens or open areas are to be retained), may be designed using a triangular lateral earth pressure distribution and an 'active' earth pressure coefficient, K_a, as shown in **Table 4-1**.
- Cantilevered walls, where the tops of which are restrained by the floor slabs of the
 permanent structure or which support movement sensitive elements, should be designed
 using a triangular lateral earth pressure distribution and an 'at rest' earth pressure
 coefficient, K_o, as shown in **Table 4-1** below



- For progressively anchored or propped walls where minor movements can be tolerated (provided there are no buried movement sensitive services), we recommend the use of a trapezoidal earth pressure distribution of 5H kPa for soil, where H is the retained height in meters. These pressures should be assumed to be uniform over the central 50% of the support system, tapering to nil at top and bottom
- For progressively anchored or propped walls which support areas which are highly sensitive to movement (such as areas where movement sensitive structures or infrastructures or buried services are located in close proximity), we recommend the use of a trapezoidal earth pressure distribution of 8H kPa for soil, where 'H' is the retained height in meters. These pressures should be assumed to be uniform over the central 50% of the support system, tapering to nil at top and bottom
- All surcharge loading affecting the walls (including from construction equipment, construction loads, adjacent high level footings, etc.) should be adopted in the retaining wall design as an additional surcharge using an 'at rest' earth pressure coefficient, Ko
- The retaining walls should be designed as drained and measures are to be taken to provide complete and permanent drainage behind the walls. Strip drains protected with a non-woven geotextile fabric should be used behind the shotcrete infill panels for soldier pile walls. The embedded pipes must, however, be wrapped with a non-woven geotextile fabric (such as Bidim A34) to act as a filter against subsoil erosion
- For piles embedded into Unit 4 or better, the allowable lateral toe resistance values outlined in Table 4-1 below may be adopted. These values assume excavation is not carried out within the zone of influence of the wall toe and the rock does not contain adverse defects etc. The upper 0.3m depth of the socket should not be taken into account to allow for tolerance and disturbance effects during excavation.
- If temporary anchors extend beyond the site boundaries, then permission from the neighbouring properties would need to be obtained prior to installation. Also, the presence of neighbouring basements and/or services and their levels must be confirmed prior to finalising anchor design.
- Anchors should have their bond length within Unit 3 or better. For the design of anchors bonded into Unit 3 or better, the allowable bond stress value outlined in **Table 4-1** below may be used, subject to the following conditions:
 - 1. Anchor bond lengths of at least 3m behind the 'active' zone of the excavation (taken as a 45 degree zone above the base of the excavation) is provided;
 - 2. Overall stability, including anchor group interaction, is satisfied;
 - All anchors should be proof loaded to at least 1.33 times the design working load before locked off at working load. Such proof loading is to be witnessed by and engineer independent of the anchoring contractor. We recommend that only experienced contractors be considered for anchor installation with appropriate insurances;
 - 4. If permanent anchors are to be used, these must have appropriate corrosion provisions for longevity.



Table 4-1 Geotechnical Design Parameters

	Mate	erial ¹	Unit 1: Fill	Unit 2: Residual Soil	Unit 3: Class V Sandstone	Unit 4: Class IV Sandstone	Unit 5: Class III Sandstone
Bulk Unit Weight (kN/m³) Friction Angle, φ' (°)		17 27	19 25	24 35	24 40	24 50	
							Earth
Pressure Coefficient	Acti	ve, K _a ³	0.38	0.41	0.27	-	-
S	Pas	sive, K _p ³	2.66	2.46	3.69	-	-
Allowable Bearing Pressure (kPa) ⁵		-	150	800	1500	3500	
Allowable St		in Compression	-	=	80	150	350
Adhesion (kl	` '	in Uplift	-	-	40	75	175
Allowable Toe Resistance (kPa)		-	-	-	500	1000	
Allowable Bond Stress (kPa)		-	-	50	100	250	

Earthquake Site Risk Classification

- AS 1170.4:2007 indicates an earthquake subsoil class of Class C_e.(Shallow Soil)
- AS 1170.4:2007 indicates that the hazard factor (z) for Sydney is 0.08.

Notes:

- More detailed descriptions of subsurface conditions are available on the borehole logs presented in Appendix A.
- Approximate levels of top of unit at the time of our investigation. Levels may vary across the site.
- Earth pressures are provided on the assumption that the ground behind the retaining walls is horizontal.
- 3 4 Side adhesion values given assume there is intimate contact between the pile and foundation material and should achieve a clean socket roughness category R2 or better. Design engineer to check both 'piston pull-out' and 'cone liftout' mechanics in accordance with AS4678-2002 Earth Retaining Structures.
- To adopt these parameters we have assumed that:
 - Footings have a nominal socket of at least 0.5m, into the relevant founding material;
 - For piles, there is intimate contact between the pile and foundation material (a clean socket roughness category of R2 or better);

 - Potential soil and groundwater aggressivity will be considered in the design of piles and footings;
 Piles should be drilled in the presence of a Geotechnical Engineer prior to pile construction to verify that ground conditions meet design assumptions. Where groundwater ingress is encountered during pile excavation, concrete is to be placed as soon as possible upon completion of pile excavation. Pile excavations should be pumped dry of water prior to pouring concrete, or alternatively a tremmie system could be used;
 - The bases of all pile, pad and strip footing excavations are cleaned of loose and softened material and water is pumped out prior to placement of concrete;
 - The concrete is poured on the same day as drilling, inspection and cleaning.
 - The allowable bearing pressures given above are based on serviceability criteria of settlements at the footing base/pile toe of less than or equal to 1% of the minimum footing dimension (or pile diameter).



4.6 Foundations

The most competent foundation stratum at the site is the Unit 5 Class III Sandstone bedrock and in view of the shallow depths to Class III Sandstone, we recommend that building is supported on pad and pile footings founded into Unit 5 Sandstone bedrock. However, the option of high level footings founded in Unit 4 sandstone is also provided.

Following bulk excavation to RL 12.7m AHD, we expect Unit 3 Residual Clay or Unit 4 Class IV Sandstone materials to be exposed at the majority of the site at BEL. All footings in Unit 4 may be designed as shallow pad/strip footings for an allowable bearing capacity of 1500kPa.

Footings extended into Unit 5 Class III Sandstone may be designed for an allowable bearing capacity of 3500kPa. However piles or deep pad footings may be required in the south-west corner of the site to reach Class III Sandstone.

We note that no cored boreholes were completed at the rear of the site due to site access. We recommend that additional cored boreholes be completed to the rear to confirm the quality of sandstone in this area following demolition.

Geotechnical inspections of foundations are recommended to determine that the required bearing capacity has been achieved and to determine any variations that may occur between the boreholes and inspected locations.

4.7 Basement Floor Slab

Following bulk excavations for the proposed basement, sandstone bedrock is expected to be exposed at the basement floor BEL.

Following the removal of all loose and softened materials, we recommend that underfloor drainage be provided and should comprise a strong, durable, single sized washed aggregate such as 'blue metal gravel'. Joints in the concrete floor slab should be designed to accommodate shear forces but not bending moments by using dowelled and keyed joints. The basement floor slab should be isolated from columns. The completed excavation should be inspected by the hydraulic engineer to confirm the extent of the drainage required.

In addition, a system of sub-soil drains comprising a durable single sized aggregate with perforated drains/pipes leading to sumps should be provided. The basement floor slab should be isolated from columns.

Permission may need to be obtained from the NSW Department of Primary Industries (DPI) and possibly Council for any permanent discharge of seepage into the drainage system. Given the subsurface conditions, we expect that seepage volumes would be low and within the DPI limits. However, if permission for discharge is not obtained, the basement may need to be designed as a tanked basement.



5. Further Geotechnical Inputs

Below is a summary of the previously recommended additional work that needs to be carried out:

- Additional Geotechnical Investigation in the form of three cored boreholes to confirm the depth and quality of Unit 5 Sandstone bedrock in the northern elevation
- Long term groundwater monitoring and seepage modelling
- Stability assessment of temporary batters using computer modelling, if required
- Dilapidation surveys
- Design of working platforms (if required) for construction plant by an experienced and qualified geotechnical engineer
- Classification of all excavated material transported off site
- Witnessing installation of support measures and proof-testing of anchors (if required)
- Geotechnical inspections of all new footings/piles by an experienced geotechnical professional before concrete or steel are placed to verify their bearing capacity and the insitu nature of the founding strata
- Ongoing monitoring of groundwater inflows into the bulk excavation

We recommend that a meeting be held after initial structural design has been completed to confirm that our recommendations have been correctly interpreted. We also recommend a meeting at the commencement of construction to discuss the primary geotechnical issues and inspection requirements.



6. Statement of Limitations

This report has been prepared for the exclusive use of Kevin Lam and JAK Newport Pty Ltd who is the only intended beneficiary of El's work. The scope of the assessment carried out for the purpose of this report is limited to those agreed with Kevin Lam and JAK Newport Pty Ltd

No other party should rely on the document without the prior written consent of EI, and EI undertakes no duty, or accepts any responsibility or liability, to any third party who purports to rely upon this document without EI's approval.

El has used a degree of care and skill ordinarily exercised in similar investigations by reputable members of the geotechnical industry in Australia as at the date of this document. No other warranty, expressed or implied, is made or intended. Each section of this report must be read in conjunction with the whole of this report, including its appendices and attachments.

The conclusions presented in this report are based on a limited investigation of conditions, with specific sampling and test locations chosen to be as representative as possible under the given circumstances.

El's professional opinions are reasonable and based on its professional judgment, experience, training and results from analytical data. El may also have relied upon information provided by the Client and other third parties to prepare this document, some of which may not have been verified by El.

El's professional opinions contained in this document are subject to modification if additional information is obtained through further investigation, observations, or validation testing and analysis during construction. In some cases, further testing and analysis may be required, which may result in a further report with different conclusions.

We draw your attention to the document "Important Information", which is included in **Appendix D** of this report. The statements presented in this document are intended to advise you of what your realistic expectations of this report should be. The document is not intended to reduce the level of responsibility accepted by EI, but rather to ensure that all parties who may rely on this report are aware of the responsibilities each assumes in so doing.

Should you have any queries regarding this report, please do not hesitate to contact El.



References

AS1289.6.3.1:2004, Methods of Testing Soils for Engineering Purposes, Standards Australia.

AS1726:2017, Geotechnical Site Investigations, Standards Australia.

AS2159:2009, Piling – Design and Installation, Standards Australia.

AS3600:2009, Concrete Structures, Standards Australia

Safe Work Australia Excavation Work Code of Practice, dated January 2020 - WorkCover NSW

NSW Department of Finance and Service, Spatial Information Viewer, maps.six.nsw.gov.au.

NSW Department of Mineral Resources. NSW Seamless Geology Data Package, Catalogue Number: 9232, Version 0221 - 2.1, COLQUHOUN G.P., HUGHES K.S., DEYSSING L., BALLARD J.C., FOLKES C.B, PHILLIPS G., TROEDSON A.L. & FITZHERBERT J.A. 2021. New South Wales Seamless Geology dataset, version 2.1 [Digital Dataset]. Geological Survey of New South Wales, Department of Regional NSW, Maitland.

Geoscience Australia and Australian Stratigraphy Commission. (2017). Australian Stratigraphic Units Database.

Abbreviations

AHD Australian Height Datum
AS Australian Standard
BEL Bulk Excavation Level

BEGL Below Existing Ground Level

BH Borehole

DBYD Dial Before You Dig
DP Deposited Plan
El El Australia

GI Geotechnical Investigation

NATA National Association of Testing Authorities, Australia

RL Reduced Level

SPT Standard Penetration Test

T-C Tungsten-Carbide


UCS Unconfined Compressive Strength



		1.1	ro	C
	IU	u	re	10
-			-	

Figure 1 Site Locality Plan

Figure 2 Borehole Location Plan





Drawn: J.O.

Approved: S.K.

Date: 11/10/2023

Scale: Not To Scale

JAK Newport Pty Ltd


Geotechnical Investigation 54-58 Beaconsfield Street, Newport NSW

Site Locality Plan

Figure:

1

Project: E26083.G03



LEGEND (All Locations are Approximate)

Site boundary

Basement boundary

Borehole locations

Monitoring well locations




Drawn:	K.P.	
Approved:	K.X.	
Date:	06-05-24	

JAK Newport Pty Ltd Geotechnical Investigation 54-58 Beaconsfield Street, Newport NSW

Borehole Location Plan

Project: E26083.G03





BH ID: BH1M

Location 54-58 Beaconsfield Street, Newport Started 06 July 2023 06 July 2023 Client JAK Newport Completed **Job No.** E26083 **Logged By** DD Date 06 July 2023 Sheets 1 of 2 **Review By** Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈17.50 m (AHD) Northing 6274211.5196 (MGA 2020 Zone 56) Plant Comacchio Geo 205 Inclination 90° 343349.5257 (MGA 2020 Zone 56) Easting CONSISTENCY / REL. DENSITY GROUND WATER LEVELS SAMPLE RECOVER MOISTURE CONDITION (mAHD) GRAPHIC LOG DEPTH (m) METHOD SAMPLES & MATERIAL ORIGIN MATERIAL DESCRIPTION FIELD TESTS & OBSERVATIONS 퓝 0.00 TOPSOIL: Clayey SILT: low plasticity, dark brown, with fine grained sand, with rootlets, no odour TOPSOIL M < PL 0.65 Silty CLAY: high plasticity, mottled grey-red, with fine to medium RESIDUAL SOIL sub-angular to sub-rounded iron indurated siltstone BH1M_1.50-1.95 SPT 1.50-1.95 6,12,18 N=30 VSt AD/T M < PL BH1M_3.00-3.45 SPT 3.00-3.45 10,18,20 N=38 3. From 3.45m, high plasticity, mottled red and grey, with ironstone gravels, grading into extremely weathered material 3.45 Н SPT 4.00-4.25 18,22/100 mm HB N=R 43.02 Log continued on next page.

This log should be read in conjunction with El Australia's accompanying explanatory notes.



BH ID: BH1M

Location 54-58 Beaconsfield Street, Newport Started 06 July 2023 06 July 2023 Client Completed JAK Newport 06 July 2023 **Job No.** E26083 **Logged By** DD Date Sheets 2 of 2 **Review By** Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈17.50 m (AHD) Northing 6274211.5196 (MGA 2020 Zone 56) Comacchio Geo 205 343349.5257 (MGA 2020 Zone 56) Plant Inclination 90° **Easting** ESTIMATED STRENGTH Is(50) ▼ - Axial ▽ - Diametral FRACTURE SPACING GRAPHIC LOG Flush Return Ξ RL (mAHD) RQD % METHOD TCR % DISCONTINUITIES & ADDITIONAL DATA DEPTH (MATERIAL DESCRIPTION 300 300 3000 3000 EZTZ Log continued from previous page. LAMINITE: orange-grey, very thinly bedeed 4.90-4.99: XWS clay 5.18: JT 50° PR SL Clay VN LAMINITE: dark grey Siltstone [20%], and grey fine grained Sandstone [80%], thinly bedded 5.15 5.20: JT 50° UN SM CN 5.26: JT 50° PR SM CN 8 26 5.85: JT 90° IR CL MW 6.08-6.11: CS SANDSTONE: fine grained, grey and interbedded dark grey 6.60 siltstone, medium bedded NMLC 100 7 FR 8.77 From 8.77m, From 8.77m, increasing Siltstone lamination, 8.91: JT 70° PR SM Fe SN thinly bedded Terminated at 9.62m. Target Depth Reached. This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BH ID: BH1M

Location 54-58 Beaconsfield Street, Newport 06 July 2023 Started JAK Newport 06 July 2023 Client Completed E26083 DD Date Job No. **Logged By** 06 July 2023 Sheets 1 of 1 **Review By** Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈17.50 m (AHD) Northing 6274211.5196 (MGA 2020 Zone 56) Comacchio Geo 205 Plant Inclination 90° Easting 343349.5257 (MGA 2020 Zone 56) MOISTURE GRAPHIC LOG (m AHD) WATER SAMPLES & FIELD TESTS DEPTH MATERIAL DESCRIPTION BACKFILL DETAILS STANDPIPE DETAILS 귒 0.80 TOPSOIL: Clayey SILT: low plasticity, dark brown, Well Stickup =0.0m with fine grained sand, with rootlets, no odour (RL 17.50m) Cuttings 0.00m - 1.00m 0.65 Silty CLAY: high plasticity, mottled grey-red, with fine to medium sub-angular to sub-rounded iron indurated siltstone BH1M_1.50-1.95 SPT 1.50-1.95 6,12,18 N=30 0.0m - 4.0m PVC casing (50mm Ø) GWNE Bentonite 1.00m - 4.00m BH1M 3.00-3.45 SPT 3.00-3.45 10,18,20 N=38 From 3.45m, high plasticity, mottled red and grey, with ironstone gravels, grading into extremely 3.45 weathered material SPT 4.00-4.25 18,22/100 mm HB N=R BH1M_4.50-4.80 4.48 LAMINITE: orange-grey, very thinly bedeed LAMINITE: dark grey Siltstone [20%], and grey fine grained Sandstone [80%], thinly bedded %06 SANDSTONE: fine grained, grey and interbedded 6.60 dark grey siltstone, medium bedded Sand 4.0m - 9.62m 4 00m - 9 62m PVC screen (50mm Ø) 95% From 8.77m, From 8.77m, increasing Siltstone lamination, thinly bedded 9 Terminated at 9.62m. Target Depth Reached. This log should be read in conjunction with El Australia's accompanying explanatory notes.



CORE PHOTOGRAPH OF BOREHOLE: BH1M

Project Proposed Residential Development

54-58 Beaconsfield Street, Newport NSW Location

Position See Figure 2

Job No. E26083.G03

Client JAK Newport Pty Ltd **Depth Range** 4.48m to 9.62m BEGL

Geosense Drilling Pty Ltd Contractor

Drill Rig Comacchio Geo 205

Logged DD **Date** 6 /11/2023 Checked SK Date 10/10/2023



Surface RL ≈17.50m AHD

1 of 1

Inclination -90°

Box



BH ID: BH2

Location 54-58 Beaconsfield Street, Newport Started 06 July 2023 06 July 2023 Client JAK Newport Completed **Job No.** E26083 **Logged By** DD Date 06 July 2023 Sheets 1 of 2 **Review By** Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈19.30 m (AHD) Northing 6274174.8975 (MGA 2020 Zone 56) Plant Comacchio Geo 205 Inclination 90° 343393.1808 (MGA 2020 Zone 56) Easting GROUND WATER LEVELS CONSISTENCY / REL. DENSITY SAMPLE RECOVER' MOISTURE CONDITION (mAHD) DEPTH (m) GRAPHIC LOG METHOD MATERIAL ORIGIN SAMPLES & MATERIAL DESCRIPTION FIELD TESTS & OBSERVATIONS 퓝 0.00 TOPSOIL: Silty CLAY: high plasticity, dark brown, with rootlets, trace fine grained sand, no odour TOPSOIL BH2_0.50-0.95 SPT 0.50-0.95 9,9,15 N=24 Silty CLAY: high plasticity, mottled grey and red, with fine to medium sub-angular to sub-rounded iron indurated siltstone, no odour RESIDUAL SOIL AD/T BH2_1.50-1.90 SPT 1.50-1.90 12,18,18/100 mm HB N=R M < PLVSt - H 16.84 2.46 Log continued on next page. 3.

This log should be read in conjunction with El Australia's accompanying explanatory notes.



BH ID: BH2

Location 54-58 Beaconsfield Street, Newport Started 06 July 2023 06 July 2023 Client JAK Newport Completed **Job No.** E26083 **Logged By** DD Date 06 July 2023 Sheets 2 of 2 **Review By** Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈19.30 m (AHD) Northing 6274174.8975 (MGA 2020 Zone 56) Plant Comacchio Geo 205 Inclination 343393.1808 (MGA 2020 Zone 56) 90° Easting ESTIMATED STRENGTH Is(50) ▼ - Axial ▽ - Diametral FRACTURE SPACING GRAPHIC LOG Flush Return Ξ RL (m AHD) RQD % METHOD TCR % DISCONTINUITIES & ADDITIONAL DATA MATERIAL DESCRIPTION 300 300 3000 3000 EZTZ Log continued from previous page. Silty CLAY: high plasticity, silty sandy CLAY; high plasticity, mottled orange-grey (Extremely Weathered) 100 0 XW 15.07 4.23 NO CORE: 490mm thick SANDSTONE: fine grained, orange and grey, very thinly bedded, with clay seams 4.91: JT 80° PR SM clay Infilled 5.00-6.00: XWS $\,$ clay %06 74 0 XW NMLC SANDSTONE: grey and orange-grey, fine grained, thinly 6.21: JT 50° IR RO CN bedded 7.06: JT 50° PR SM Fe SN 107 SW 61 7.75-7.81: XWS clay 8.40: JT 90° UN RO CN Terminated at 9.05m. Target Depth Reached. This log should be read in conjunction with EI Australia's accompanying explanatory notes.



CORE PHOTOGRAPH OF BOREHOLE: BH2

Project Proposed Residential Development

Location 54-58 Beaconsfield Street, Newport NSW

Position See Figure 2

Job No. E26083.G03

Client JAK Newport Pty Ltd

Depth Range 2.46m to 9.05m BEGL

Contractor Geosense Drilling Pty Ltd

Drill Rig Comacchio Geo 205

Logged DD Date 7/7/2023

Checked SK **Date** 10/10/2023



Surface RL ≈ 19.3m AHD

1-2 of 2

Inclination -90°

Box



BH ID: BH3M

Location 54-58 Beaconsfield Street, Newport Started 07 July 2023 07 July 2023 Client JAK Newport Completed **Job No.** E26083 **Logged By** DD Date 07 July 2023 1 of 3 Sheets **Review By** SK Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈19.40 m (AHD) Latitude Plant Comacchio Geo 205 Inclination 90° Longitude CONSISTENCY / REL. DENSITY GROUND WATER LEVELS SAMPLE RECOVER MOISTURE CONDITION (mAHD) DEPTH (m) GRAPHIC LOG METHOD SAMPLES & FIELD TESTS MATERIAL ORIGIN MATERIAL DESCRIPTION & OBSERVATIONS 귚 0.00 19.40 CONCRETE: 150mm thick

FILL: Silty SAND: dark brown, with clay, no odour Ы CONCRETE 0.15 FILL Μ Silty CLAY: high plasticity, mottled grey and red, with fine to medium sub-angular to sub-rounded iron indurated siltstone, no odour 0.55 RESIDUAL SOIL BH3M_1.50-1.95 SPT 1.50-1.95 8,8,12 N=20 VSt BH3M_3.00-3.45 3-SPT 3.00-3.45 12,16,22 N=38 AD/T M < PL BH3M_4.50-4.95 SPT 4.50-4.95 12,18,22 N=40 Н BH3M_6.00-6.45 SPT 6.00-6.45 3,7,10 N=17 St _ _12.93 Log continued on next page. 9-This log should be read in conjunction with El Australia's accompanying explanatory notes.



BH ID: BH3M

Location 54-58 Beaconsfield Street, Newport Started 07 July 2023 JAK Newport 07 July 2023 Client Completed **Job No.** E26083 Date **Logged By** DD 07 July 2023 10 October 2023 Sheets 2 of 3 **Review By** SK Date **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈19.40 m (AHD) Latitude Plant Comacchio Geo 205 Inclination 90° Longitude ESTIMATED STRENGTH Is(50) ▼ - Axial ▽ - Diametral FRACTURE SPACING DEPTH (m) GRAPHIC LOG Flush Return RL (mAHD) RQD % METHOD TCR % DISCONTINUITIES & ADDITIONAL DATA MATERIAL DESCRIPTION 300 300 3000 3000 EZTZ Log continued from previous page. SANDSTONE: orange-brown, very thinly bedded SW 6.67-6.69: CS From 7.08m, SANDSTONE: fine grained, pale grey, 7.08 medium bedded 7.69-7.71: CS 85% 100 72 8-NMLC FR From 8.57m, From 8.57m, with Siltstone Laminations 8.73: JT 70° UN RO CN 8.76-8.81: CS %06 9.86: JT 60° RO CN

This log should be read in conjunction with EI Australia's accompanying explanatory notes.



BH ID: BH3M

Location 54-58 Beaconsfield Street, Newport Started 07 July 2023 JAK Newport Completed 07 July 2023 Client **Job No.** E26083 **Logged By** DD Date 07 July 2023 Sheets 3 of 3 **Review By** SK Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈19.40 m (AHD) Latitude Plant Comacchio Geo 205 Inclination 90° Longitude ESTIMATED STRENGTH Is(50) ▼ - Axial ▽ - Diametral FRACTURE SPACING GRAPHIC LOG Flush Return RL (m AHD) Ξ RQD % METHOD TCR % DISCONTINUITIES & ADDITIONAL DATA MATERIAL DESCRIPTION E K W W 300 300 3000 3000 From 8.57m, From 8.57m, with Siltstone Laminations LAMINITE: pale grey fine grained sandstone, dark grey siltstone, laminated 10.05 MW 10.75 SANDSTONE: grey, with dark grey interbedded Siltstone, medium bedded 9 39 FR 11.79: JT 60° RO CN Terminated at 12.00m. Target Depth Reached. 13-14-15 18-19-

This log should be read in conjunction with El Australia's accompanying explanatory notes.



BH ID: BH3M

Location 54-58 Beaconsfield Street, Newport 07 July 2023 Started 07 July 2023 Client JAK Newport Completed **Job No.** E26083 **Logged By** DD Date 07 July 2023 Sheets 1 of 2 **Review By** SK Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈19.40 m (AHD) Latitude Comacchio Geo 205 90° Plant Inclination Longitude MOISTURE CONDITION GRAPHIC LOG (m AHD) WATER SAMPLES & FIELD TESTS DEPTH (MATERIAL DESCRIPTION BACKFILL DETAILS STANDPIPE DETAILS 귒 0.80 19.40 CONCRETE: 150mm thick
19.25 FILL: Silty SAND: dark brown, with clay, no odour Well Stickup =0.0m (RL 19.40m) 0.15 М 0.55 Silty CLAY: high plasticity, mottled grey and red, with fine to medium sub-angular to sub-rounded iron indurated siltstone, no odour 0.00m - 2.00m BH3M_1.50-1.95 SPT 1.50-1.95 8,8,12 N=20 0.0m - 3.0m PVC casing (50mm Ø) Bentonite 2.00m - 3.00m BH3M 3.00-3.45 SPT 3.00-3.45 12,16,22 N=38 BH3M_4.50-4.95 SPT 4.50-4.95 12,18,22 N=40 BH3M_6.00-6.45 SPT 6.00-6.45 3,7,10 N=17 SANDSTONE: orange-brown, very thinly bedded 6.47 From 7.08m, SANDSTONE: fine grained, pale grey, 7.08 medium bedded Sand 3.0m - 12.0m 3.00m - 12.00m PVC screen (50mm Ø) 85% From 8.57m, From 8.57m, with Siltstone Laminations 9 %06 This log should be read in conjunction with El Australia's accompanying explanatory notes.



CORE PHOTOGRAPH OF BOREHOLE: BH3M

Project Proposed Residential Development

Location 54-58 Beaconsfield Street, Newport NSW

Position See Figure 2

Job No. E26083.G03

Client JAK Newport Pty Ltd **Depth Range** 6.47m to 12.0m BEGL

Geosense Drilling Pty Ltd Contractor

Drill Rig Comacchio Geo 205

Logged DD Date 10/7/2023 Checked SK 10/10/2023 **Date**



Surface RL ≈19.4m AHD

-90°

1-2 of 2

Inclination

Box



BH ID: BH3M

Location 54-58 Beaconsfield Street, Newport Started 07 July 2023 JAK Newport 07 July 2023 Client Completed Date **Job No.** E26083 Logged By DD 07 July 2023 10 October 2023 Sheets 2 of 2 **Review By** SK Date **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈19.40 m (AHD) Latitude Plant Comacchio Geo 205 Inclination 90° Longitude GRAPHIC LOG RL (mAHD) DEPTH (m) SAMPLES & FIELD TESTS MATERIAL DESCRIPTION BACKFILL DETAILS STANDPIPE DETAILS From 8.57m, From 8.57m, with Siltstone Laminations LAMINITE: pale grey fine grained sandstone, dark grey siltstone, laminated 10.05 SANDSTONE: grey, with dark grey interbedded Siltstone, medium bedded 10.75 12-Terminated at 12.00m. Target Depth Reached. 13 16-18-19-

This log should be read in conjunction with El Australia's accompanying explanatory notes.



BH ID: BH4

Location 54-58 Beaconsfield Street, Newport Started 07 July 2023 JAK Newport 07 July 2023 Client Completed **Job No.** E26083 07 July 2023 **Logged By** DD Date Sheets 1 of 1 **Review By** SK Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈23.50 m (AHD) Latitude Plant Hand Portable Rig Inclination 90° Longitude GROUND WATER LEVELS CONSISTENCY / REL. DENSITY SAMPLE RECOVERY MOISTURE CONDITION GRAPHIC LOG RL (m AHD) DEPTH (m) METHOD DCP SAMPLES & FIELD TESTS MATERIAL ORIGIN & OBSERVATIONS MATERIAL DESCRIPTION **BLOWS** 5 10 15 20 25 30 0.00 TOPSOIL: Silty CLAY: low plasticity, dark brown, with rootlets, with fine grained sand, no odour TOPSOIL ¥ St -VSt Silty CLAY: high plasticity, mottled grey and red, with fine to medium sub-angular to sub-rounded iron indurated siltstone, no odour RESIDUAL SOIL 0.80 Terminated at 1.10m. Practical Auger Refusal.

This log should be read in conjunction with El Australia's accompanying explanatory notes.



BH ID: BH5

Location 54-58 Beaconsfield Street, Newport Started 07 July 2023 JAK Newport Completed 07 July 2023 Client **Job No.** E26083 07 July 2023 **Logged By** DD Date Sheets 1 of 1 **Review By** SK Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈21.00 m (AHD) Latitude Plant Hand Portable Rig Inclination 90° Longitude GROUND WATER LEVELS CONSISTENCY / REL. DENSITY SAMPLE RECOVERY MOISTURE CONDITION GRAPHIC LOG RL (m AHD) DEPTH (m) METHOD DCP SAMPLES & FIELD TESTS MATERIAL ORIGIN & OBSERVATIONS MATERIAL DESCRIPTION **BLOWS** 5 10 15 20 25 30 0.00 TOPSOIL: Clayey SILT: low plasticity, dark brown, with rootlets, trace fine grained sand, no odour TOPSOIL M ≈ PL Silty CLAY: high plasticity, mottled grey-red, with fine to medium sub-angular to sub-rounded iron indurated siltstone, no odour RESIDUAL SOIL ¥ M < PL St 19.80 Terminated at 1.20m. Practical Auger Refusal. 22 11



BH ID: BH6

Location 54-58 Beaconsfield Street, Newport Started 07 July 2023 JAK Newport 07 July 2023 Client Completed **Job No.** E26083 **Logged By** DD Date 07 July 2023 Sheets 1 of 1 **Review By** SK Date 10 October 2023 **Drilling Contractor** Geosense Drilling Engineers Surface RL ≈20.50 m (AHD) Latitude Plant Hand Portable Rig Inclination 90° Longitude GROUND WATER LEVELS CONSISTENCY / REL. DENSITY SAMPLE RECOVERY MOISTURE CONDITION GRAPHIC LOG RL (m AHD) DEPTH (m) METHOD DCP SAMPLES & FIELD TESTS MATERIAL ORIGIN & OBSERVATIONS MATERIAL DESCRIPTION **BLOWS** 5 10 15 20 25 30 0.00 TOPSOIL: Silty CLAY: low plasticity, dark brown, with fine grained sand, with rootlets, no odour TOPSOIL ¥ Silty CLAY: high plasticity, mottled grey and red, with RESIDUAL SOIL fine to medium sub-angular to sub-rounded iron indurated siltstone, no odour 19.60 Terminated at 0.90m. Practical Auger Refusal.



EXPLANATION OF NOTES, ABBREVIATIONS & TERMS USED ON BOREHOLE AND TEST PIT LOGS

DRILLING/EXCAVATION METHOD

HA	Hand Auger	ADH	Hollow Auger	NQ	Diamond Core - 47 mm
DT	Diatube Coring	RT	Rotary Tricone bit	NMLC	Diamond Core - 52 mm
NDD	Non-destructive digging	RAB	Rotary Air Blast	HQ	Diamond Core - 63 mm
AD*	Auger Drilling	RC	Reverse Circulation	HMLC	Diamond Core - 63 mm
*V	V-Bit	PT	Push Tube	EX	Tracked Hydraulic Excavator
*T	TC-Bit, e.g. AD/T	WB	Washbore	HAND	Excavated by Hand Methods

PENETRATION RESISTANCE

1 Low Resistance Rapid penetration/ excavation possible with little effort from equipment used.

Penetration/ excavation possible at an acceptable rate with moderate effort from equipment used. М **Medium Resistance**

Penetration/ excavation is possible but at a slow rate and requires significant effort from Н **High Resistance**

equipment used.

Refusal/Practical Refusal No further progress possible without risk of damage or unacceptable wear to equipment used. R

These assessments are subjective and are dependent on many factors, including equipment power and weight, condition of excavation or drilling tools and experience of the operator.

WATER

GWNO

¥ Standing Water Level

Partial water loss

Complete Water Loss GROUNDWATER NOT OBSERVED - Observation of groundwater, whether present or not, was not possible

due to drilling water, surface seepage or cave-in of the borehole/ test pit.

GROUNDWATER NOT ENCOUNTERED - Borehole/ test pit was dry soon after excavation. However, **GWNE**

groundwater could be present in less permeable strata. Inflow may have been observed had the borehole/ test pit

been left open for a longer period.

SAMPLING AND TESTING

Standard Penetration Test to AS1289.6.3.1-2004 SPT

4,7,11 = Blows per 150mm. N = Blows per 300mm penetration following a 150mm seating drive 4,7,11 N=18 Where practical refusal occurs, the blows and penetration for that interval are reported, N is not reported 30/80mm

Penetration occurred under the rod weight only, N<1 RW

НW Penetration occurred under the hammer and rod weight only, N<1

Hammer double bouncing on anvil, N is not reported НВ

Sampling

Disturbed Sample DS

Sample for environmental testing ES

Bulk disturbed Sample BDS Gas Sample GS Water Sample ws

Thin walled tube sample - number indicates nominal sample diameter in millimetres U50

Testing

Field Permeability test over section noted FΡ

Field Vane Shear test expressed as uncorrected shear strength (sv= peak value, sr= residual value) FVS

PID Photoionisation Detector reading in ppm Pressuremeter test over section noted PΜ

Pocket Penetrometer test expressed as instrument reading in kPa P

WPT Water Pressure tests

Dynamic Cone Penetrometer test DCP Static Cone Penetration test CPT

Static Cone Penetration test with pore pressure (u) measurement CPTu

GEOLOGICAL BOUNDARIES

- -?- -?- -?- - = Boundary – Observed Boundary ----= Observed Boundary (interpreted or inferred) (position known) (position approximate)

ROCK CORE RECOVERY

TCR=Total Core Recovery (%)

RQD = Rock Quality Designation (%)

 $\underline{Length\ of\ core\ recovered} \times 100$ $-\frac{\sum Axial\ lengths\ of\ core > 100mm}{100} \times 100$ Length of core run Length of core run



METHOD OF SOIL DESCRIPTION USED ON BOREHOLE AND TEST PIT LOGS



FILL

COUBLES or BOULDERS



ORGANIC SOILS (OL, OH or Pt)

SILT (ML or MH)



CLAY (CL, CI or CH)

SAND (SP or SW)

GRAVEL (GP or GW)

Combinations of these basic symbols may be used to indicate mixed materials such as sandy clay

CLASSIFICATION AND INFERRED STRATIGRAPHY

Soil is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS 1726:2017, Section 6.1 – Soil description and classification.

PARTIC	PARTICLE SIZE CHARACTERISTICS				GROUP SYMBOLS		
Fraction	Components	Sub	Size	Major Di	Major Divisions		Description
Oversize	BOULDERS	Division	mm >200	70	GRAVEL More than 50% of coarse fraction is >2.36mm	GW	Well graded gravel and gravel-sand mixtures, little or no fines, no dry strength.
Oversize	COBBLES		63 to 200	LS Iding than	/EL 50% rctio	GP	Poorly graded gravel and gravel-sand mixtures, little or no fines, no dry
		Coarse	19 to 63	SOILS excludir ater tha	GRAVEL e than 50% rse fractio	01	strength.
	GRAVEL	Medium	6.7 to 19	Soil o	ore	GM	Silty gravel, gravel-sand-silt mixtures, zero to medium dry strength.
Coarse		Fine	2.36 to 6.7	RAII % of ion is	≥ 0	GC	Clayey gravel, gravel-sand-clay mixtures, medium to high dry strength.
grained soil		Coarse	0.6 to 2.36	SE G In 659 fracti	% of n is	SW	Well graded sand and gravelly sand, little or no fines, no dry strength.
	SAND	Medium	0.21 to 0.6	COARSE GRAINED SOILS More than 65% of soil excluding oversize fraction is greater than 0.075mm SAND GRAVEL More than 50% of coarse fraction is	ND n 50° actio	SP	Poorly graded sand and gravelly sand, little or no fines, no dry strength.
		Fine	0.075 to 0.21		SAND e than 50% rse fraction <2.36 mm	SM	Silty sand, sand-silt mixtures, zero to medium dry strength.
Fine	SILT		0.002 to 0.075	-	More	SC	Clayey sand, sandy-clay mixtures, medium to high dry strength.
soil			ding	> SS	ML	Inorganic silts of low plasticity, very fine sands, rock flour, silty or clayey fine sands, zero to medium dry strength.	
60	PLASTIC	ITY PROPE	KIIES	INED SOILS of soil excluding stron is less than 75mm Liquid Limit less 50%	CL, CI	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, medium to high dry strength.	
50	# 10° 30			FINE GRAINED SOILS More than 35% of soil excluding oversized fraction is less than 0.075mm	Liquic	OL	Organic silts and organic silty clays of low plasticity, low to medium dry strength.
ND EX		CH or OF	1 1013	IE GF an 3¢ zed fi	- ^%	МН	Inorganic silts of high plasticity, high to very high dry strength.
CH or OH CH or OH CH or OH MH or OH			FIN re that restize the restize that resting the restize that resting the restize that resting the resting the resting that resting the resting that resting the resting that resting the resting the resting that resting the resting the resting that resting the resting the resting that resting the resting the resting the resting the resting that resting the r	Liquid Limit > than 50%	СН	Inorganic clays of high plasticity, high to very high dry strength.	
			Mo Mo		ОН	Organic clays of medium to high plasticity, medium to high dry strength.	
0 10 20 30 40 50 60 70 80 90 100 LIQUID LIMIT W., %				High Orga so	nic	PT	Peat muck and other highly organic soils.

MOISTURE CONDITION

Symbol	Term	Description
D	Dry	Non- cohesive and free-running.
M	Moist	Soils feel cool, darkened in colour. Soil tends to stick together.
W	Wet	Soils feel cool, darkened in colour. Soil tends to stick together, free water forms when handling.

Moisture content of cohesive soils shall be described in relation to plastic limit (PL) or liquid limit (LL) for soils with higher moisture content as follows: Moist, dry of plastic limit (w < PL); Moist, near plastic limit ($w \approx PL$); Moist, wet of plastic limit (w < PL); Wet, near liquid limit ($w \approx LL$), Wet, wet of liquid limit (w > LL),

CONSISTENCY						
Symbol Torm		Undrained Shear Strength (kPa)	SPT "N" #			
VS	Very Soft	≤ 12	≤ 2			
S	Soft	>12 to ≤ 25	>2 to ≤ 4			
F	Firm	>25 to ≤ 50	>4 to 8			
St	Stiff	>50 to ≤ 100	>8 to 15			
VSt	Very Stiff	>100 to ≤ 200	>15 to 30			
Н	Hard	>200	>30			
Fr	Friable	-	•			

DENSITY							
Symbol	Term	Density Index %	SPT "N" #				
VL	Very Loose	≤ 15	0 to 4				
L	Loose	>15 to ≤ 35	4 to 10				
MD	Medium Dense	>35 to ≤ 65	10 to 30				
D	Dense	>65 to ≤ 85	30 to 50				
VD	Very Dense	>85	Above 50				

In the absence of test results, consistency and density may be assessed from correlations with the observed behaviour of the material. # SPT correlations are not stated in AS1726:2017, and may be subject to corrections for overburden pressure, moisture content of the soil, and equipment type.

MINOR COMPONENTS						
Term	Assessment Guide	Proportion by Mass				
Add 'Trace'	Presence just detectable by feel or eye but soil properties little or no different to general properties of primary component	Coarse grained soils: ≤ 5% Fine grained soil: ≤ 15%				
Add 'With'	Presence easily detectable by feel or eye but soil properties little or no different to general properties of primary component	Coarse grained soils: 5 - 12% Fine grained soil: 15 - 30%				
Prefix soil name	Presence easily detectable by feel or eye in conjunction with the general properties of primary component	Coarse grained soils: >12% Fine grained soil: >30%				



TERMS FOR ROCK MATERIAL STRENGTH AND WEATHERING

CLASSIFICATION AND INFERRED STRATIGRAPHY

Rock is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS1726 – 2017, Section 6.2 – Rock identification, description and classification.

ROCK MATERIAL STRENGTH CLASSIFICATION

Symbol	Term	Point Load Index, Is ₍₅₀₎ (MPa) #	Field Guide
VL	Very Low	0.03 to 0.1	Material crumbles under firm blows with sharp end of pick; can be peeled with knife; too hard to cut a triaxial sample by hand. Pieces up to 30 mm can be broken by finger pressure.
L	Low	0.1 to 0.3	Easily scored with a knife; indentations 1 mm to 3 mm show in the specimen with firm blows of pick point; has dull sound under hammer. A piece of core 150 mm long by 50 mm diameter may be broken by hand. Sharp edges of core may be friable and break during handling.
М	Medium	0.3 to 1	Readily scored with a knife; a piece of core 150 mm long by 50 mm diameter can be broken by hand with difficulty.
Н	High	1 to 3	A piece of core 150 mm long by 50 mm diameter cannot be broken by hand but can be broken with pick with a single firm blow; rock rings under hammer.
VH	Very High	3 to 10	Hand specimen breaks with pick after more than one blow; rock rings under hammer.
EH	Extremely High	>10	Specimen requires many blows with geological pick to break through intact material; rock rings under hammer.

^{*}Rock Strength Test Results

Point Load Strength Index, Is₍₅₀₎, Axial test (MPa)

Point Load Strength Index, Is₍₅₀₎, Diametral test (MPa)

Relationship between rock strength test result ($Is_{(50)}$) and unconfined compressive strength (UCS) will vary with rock type and strength, and should be determined on a site-specific basis. However UCS is typically 20 x $Is_{(50)}$.

ROCK MATERIAL WEATHERING CLASSIFICATION

Sym	bol	Term	Field Guide			
RS		Residual Soil	Soil developed on extremely weathered rock; the mass structure and substance fabric are no longer evident; there is a large change in volume but the soil has not been significantly transported.			
XW		Extremely Weathered	Rock is weathered to such an extent that it has soil properties - i.e. it either disintegrates or can be remoulded, in water.			
	HW		Rock strength usually changed by weathering. The rock may be highly discoloured, usually by iron staining. Porosity may be increased by leaching, or			
DW	MW	Distinctly Weathered	may be decreased due to deposition of weathering products in pores. In some environments it is convenient to subdivide into Highly Weathered and Moderately Weathered, with the degree of alteration typically less for MW.			
SW	'	Slightly Weathered	Rock slightly discoloured but shows little or no change of strength relative to fresh rock.			
FR		Fresh	Rock shows no sign of decomposition or staining.			



ABBREVIATIONS AND DESCRIPTIONS FOR ROCK **MATERIAL AND DEFECTS**

CLASSIFICATION AND INFERRED STRATIGRAPHY

Rock is broadly classified and described in Borehole and Test Pit Logs using the preferred method given in AS1726 – 2017, Section 6.2 – Rock identification, description and classification.

DETAILED ROCK DEFECT SPACING

Defect Spacing		Bedding Thickness (Stratification)	
Term Description		Term	Spacing (mm)
Massive	No levering apparent	Thinly laminated	<6
Massive	No layering apparent	Laminated	6 – 20
la diatio at	Lavarina irrat visible, little effect on properties	Very thinly bedded	20 – 60
Indistinct	Layering just visible; little effect on properties	Thinly bedded	60 – 200
		Medium bedded	200 – 600
Distinct	Layering (bedding, foliation, cleavage) distinct; rock breaks more easily parallel to layering	Thickly bedded	600 – 2,000
	rook breaks more easily parallel to layering	Very thickly bedded	> 2,000

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT TYPES

Defect Type	Abbr.	Description
Joint	JT	Surface of a fracture or parting, formed without displacement, across which the rock has little or no tensile strength. May be closed or filled by air, water or soil or rock substance, which acts as cement.
		Surface of fracture or parting, across which the rock has little or no tensile strength, parallel or sub-parallel to layering/ bedding. Bedding refers to the layering or stratification of a rock, indicating orientation during deposition, resulting in planar anisotropy in the rock material.
Contact	СО	The surface between two types or ages of rock.
Sheared Surface	SSU	A near planar, curved or undulating surface which is usually smooth, polished or slickensided.
Sheared Seam/ Zone (Fault)	SS/SZ	Seam or zone with roughly parallel almost planar boundaries of rock substance cut by closely spaced (often <50 mm) parallel and usually smooth or slickensided joints or cleavage planes.
Crushed Seam/ Zone (Fault)	CS/CZ	Seam or zone composed of disoriented usually angular fragments of the host rock substance, with roughly parallel near-planar boundaries. The brecciated fragments may be of clay, silt, sand or gravel sizes or mixtures of these.
Extremely Weathered Seam/ Zone	XWS/XWZ	Seam of soil substance, often with gradational boundaries, formed by weathering of the rock material in places.
Infilled Seam	IS	Seam of soil substance, usually clay or clayey, with very distinct roughly parallel boundaries, formed by soil migrating into joint or open cavity.
Vein	VN	Distinct sheet-like body of minerals crystallised within rock through typically open-space filling or crack-seal growth.

NOTE: Defects size of <100mm SS, CS and XWS. Defects size of >100mm SZ, CZ and XWZ.

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT SHAPE AND ROUGHNESS

Shape	Abbr.	Description	Roughness	Abbr.	Description
Planar	PR	Consistent orientation	Polished	POL	Shiny smooth surface
Curved	CU	Gradual change in orientation	Slickensided	SL	Grooved or striated surface, usually polished
Undulating	UN	Wavy surface	Smooth	SM	Smooth to touch. Few or no surface irregularities
Stepped	ST	One or more well defined steps	Rough	RO Many small surface irregularities (amplitude generally <1r Feels like fine to coarse sandpaper	
Irregular	IR	Many sharp changes in orientation	Very Rough	VR	Many large surface irregularities, amplitude generally >1mm. Feels like very coarse sandpaper

Orientation:

Vertical Boreholes – The dip (inclination from horizontal) of the defect. Inclined Boreholes – The inclination is measured as the acute angle to the core axis.

ABBREVIATIONS AND DESCRIPTIONS FOR DEFECT COATING			DEFECT APERTURE		
Coating	Abbr.	Description	Aperture	Abbr.	Description
Clean	CN	No visible coating or infilling	Closed	CL	Closed.
Stain	SN	No visible coating but surfaces are discoloured by staining, often limonite (orange-brown)	Open	OP	Without any infill material.
Veneer	I V/NR	A visible coating of soil or mineral substance, usually too thin to measure (< 1 mm); may be patchy	Infilled	-	Soil or rock i.e. clay, silt, talc, pyrite, quartz, etc.



GEOTECHNICS PTY

STS Geotechnics Pty Ltd

14/1 Cowpasture Place, Wetherill Park NSW 2164 Phone: (02)9756 2166 | Email: enquiries@stsgeo.com.au



Point Load Strength Index Report

Project: E26083.G03.01, 54 - 58 Beaconsfield St, NEWPORT

Client: El AUSTRALIA

Address: Suite 6.01, 55 Miller St, PYRMONT

Test Method: AS 4133.4.1

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

Project No.: 31380/7854D-L

Report No.: 23/2220 Report Date: 18/07/2023 Page: 1 OF 1

Borehole / Sample No.	Depth (m)	Date Sampled	Date Tested	Test Type	Is (MPa)	Is ₍₅₀₎ (MPa)	Rock Type	Failure Type	Moisture
BH1M	4.75	08/07/2023	18/07/2023	А	1.1	1.1	SS	3	М
BH1M	5.30	08/07/2023	18/07/2023	А	0.77	0.77	SS	3	D
BH1M	6.31	08/07/2023	18/07/2023	А	2.6	2.7	SS	3	D
BH1M	6.80	08/07/2023	18/07/2023	А	1.7	1.7	SS	3	D
BH1M	7.20	08/07/2023	18/07/2023	А	1.3	1.3	SS	3	D
BH1M	8.47	08/07/2023	18/07/2023	А	2.7	2.7	SS	3	D
BH1M	9.47	08/07/2023	17/07/2023	А	2.7	2.7	SS	3	D
BH2	3.87	08/07/2023	18/07/2023	A	0.026	0.026	ST	3	М
BH2	4.83	08/07/2023	18/07/2023	А	0.14	0.15	SS	3	М
BH2	5.43	08/07/2023	18/07/2023	А	0.022	0.022	ST	3	М
BH2	6.53	08/07/2023	18/07/2023	А	0.76	0.78	SS		
BH2	6.91	08/07/2023	18/07/2023	А	0.63	0.6			
BH2	7.18	08/07/2023	18/07/2023	А	0.71	0.72	ST	3	D
BH2	7.88	08/07/2023	18/07/2023	А	3.1	3.1	SS	3	D
BH2	8.12	08/07/2023	18/07/2023	А	2.5	2.5	SS	3	D
BH2	8.86	08/07/2023	18/07/2023	А	2.6	2.5	SS	3	D
BH3M	6.61	08/07/2023	18/07/2023	A	0.28	0.29	ST	3	M
внзм	7.49	08/07/2023	18/07/2023	А	2	2	ST	3	D
внзм	8.05	08/07/2023	18/07/2023	А	1.8	1.8	ST	3	D
внзм	8.96	08/07/2023	18/07/2023	А	2.1	2.1	SS	3	D
внзм	9.27	08/07/2023	18/07/2023	А	4.1	4	SS	3	D
внзм	10.83	08/07/2023	18/07/2023	А	1.3	1.3	ST	3	D
внзм	11.12	08/07/2023	18/07/2023	А	1.7	1.7	ST	3	D
ure Type				Test Type		Moisure Conditio		Rock Type	

1 = Fracture through bedding or weak plane

2 = Fracture along bedding

3 = Fracture through rock mass

4 = Fracture influenced by natural defect or drilling

5 = Partial fracture or chip (invalid result)

Remarks:

A = AxialD = Diametrial

I = Irregular C = Cube

W = Wet M = Moist D = Dry

Rock Type

SS = Sandstone ST = Siltstone SH = Shale

YS = Claystone IG = Igneous

Approved Signatory.....

Fernando Velasquez Senior Geotechnician

Technician: FV

Date of Issue: 07/12/21 Form: RPS70 Revision: 4



STS Geotechnics Pty Ltd

14/1 Cowpasture Place, Wetherill Park NSW 2164 Phone: (02)9756 2166 | Email: enquiries@stsgeo.com.au



Atterberg Limits and Linear Shrinkage Report

Project: 54 - 58 BEACONSFIELD STREET, NEWPORT Project No.: 31380

Client: EI AUSTRALIA Report No.: 23/2518
Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009 Report Date: 1/08/2023

Test Method: AS1289.3.1.2,3.2.1,3.4.1,2.1.1 Page: 1 of 2

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

CTC / Comusts				
STS / Sample No.	7854D-L/1			
Sample Location	Borehole 1M			
Material Description	Silty Clay, red brown grey/yellow, trace of gravel (CL)			
Depth (m)	3.0 - 3.45			
Sample Date	8/72023			
Sample History	Oven Dried			
Method of Preparation	Dry Sieved			
Liquid Limit (%)	60			
Plastic Limit (%)	24			
Plasticity Index	36			
Linear Shrinkage (%)	15.0			
Mould Size (mm)	250		_	
Crumbing	N			
Curling	N			

Remarks:

Approved Signatory.....

Technician: DH Orlando Mendoza - Laboratory Manager

Form RPS13 Date of Issue: 31/05/21 Revision: 2



Test Method: AS1289.2.1.1

STS Geotechnics Pty Ltd

14/1 Cowpasture Place, Wetherill Park NSW 2164 Phone: (02)9756 2166 | Email: enquiries@stsgeo.com.au



Page: 2 of 2

Moisture Content of Soil and Aggregate Samples

Project: 54 - 58 BEACONSFIELD STREET, NEWPORT	Project No.:	31380
Client: El AUSTRALIA	Report No.:	23/2518
Address: Suite 6.01, 55 Miller Street, Pyrmont NSW 2009	Report Date:	1/08/2023

Sampling Procedure: Samples Supplied By Client (Not covered under NATA Scope of Accreditation)

STS / Sample No.	7854D-L/1			
Sample Location	Borehole 1M			
Material Description	Silty Clay, red brown grey/yellow, trace of gravel (CL)			
Depth (mm)	3.0 - 3.45			
Sample Date	8/07/2023			
Moisture Content (%)	16.9			

_						
D	Δ	n	12	r	kς٠	

Approved Signatory......

Technician: DH Orlando Mendoza - Laboratory Manager

Form: RPS12 Date Of Issue: 31/05/21 Revision: 2

Appendix C – Vibration Limits

German Standard DIN 4150 – Part 3: 1999 provides guideline levels of vibration velocity for evaluating the effects of vibration in structures. The limits presented in this standard are generally considered to be conservative.

The DIN 4150 values (maximum levels measured in any direction at the foundation, OR, maximum levels measured in (x) or (y) directions, in the plane of the uppermost floor), are summarised in **Table A** below.

It should be noted that peak vibration velocities higher than the minimum figures in **Table A** for low frequencies may be quite 'safe', depending on the frequency content of the vibration and the actual conditions of the structures.


It should also be noted that these levels are 'safe limits', up to which no damage due to vibration effects has been observed for the particular class of building. 'Damage' is defined by DIN 4150 to include even minor non-structural cracking in cement render, the enlargement of cracks already present, and the separation of partitions or intermediate walls from load bearing walls. Should damage be observed at vibration levels lower than the 'safe limits', then it may be attributed to other causes. DIN 4150 also states that when vibration levels higher than the 'safe limits' are present, it does not necessarily follow that damage will occur. Values given are only a broad guide.

Table A DIN 4150 – Structural Damage – Safe Limits for Building Vibration

Group		Peak Vibration Velocity (mm/s)					
	Type of Structure	At Foundation	Plane of Floor of Uppermost Storey				
		Less than 10 Hz	10 Hz to 50 Hz	50 Hz to 100 Hz	AII Frequencies		
1	Buildings used for commercial purposes, industrial buildings and buildings of similar design	20	20 to 40	40 to 50	40		
2	Dwellings and buildings of similar design and/or use	5	5 to 15	15 to 20	15		
3	Structures that because of their particular sensitivity to vibration, do not correspond to those listed in Group 1 and 2 and have intrinsic value (e.g. buildings that are under a preservation order)	3	3 to 8	8 to 10	8		

Note: For frequencies above 100 Hz, the higher values in the 50 Hz to 100 Hz column should be used.





Important Information



SCOPE OF SERVICES

The geotechnical report ("the report") has been prepared in accordance with the scope of services as set out in the contract, or as otherwise agreed, between the Client And El Australia ("El"). The scope of work may have been limited by a range of factors such as time, budget, access and/or site disturbance constraints.

RELIANCE ON DATA

El has relied on data provided by the Client and other individuals and organizations, to prepare the report. Such data may include surveys, analyses, designs, maps and plans. El has not verified the accuracy or completeness of the data except as stated in the report. To the extent that the statements, opinions, facts, information, conclusions and/or recommendations ("conclusions") are based in whole or part on the data, El will not be liable in relation to incorrect conclusions should any data, information or condition be incorrect or have been concealed, withheld, misrepresented or otherwise not fully disclosed to El.

GEOTECHNICAL ENGINEERING

Geotechnical engineering is based extensively on judgment and opinion. It is far less exact than other engineering disciplines. Geotechnical engineering reports are prepared for a specific client, for a specific project and to meet specific needs, and may not be adequate for other clients or other purposes (e.g. a report prepared for a consulting civil engineer may not be adequate for a construction contractor). The report should not be used for other than its intended purpose without seeking additional geotechnical advice. Also, unless further geotechnical advice is obtained, the report cannot be used where the nature and/or details of the proposed development are changed.

LIMITATIONS OF SITE INVESTIGATION

The investigation programme undertaken is a professional estimate of the scope of investigation required to provide a general profile of subsurface conditions. The data derived from the site investigation programme and subsequent laboratory testing are extrapolated across the site to form an inferred geological model, and an engineering opinion is rendered about overall subsurface conditions and their likely behaviour with regard to the proposed development. Despite investigation, the actual conditions at the site might differ from those inferred to exist, since no subsurface exploration program, no matter how comprehensive, can reveal all subsurface details and anomalies. The engineering logs are the subjective interpretation of subsurface conditions at a particular location and time, made by trained personnel. The actual interface between materials may be more gradual or abrupt than a report indicates.

SUBSURFACE CONDITIONS ARE TIME DEPENDENT

Subsurface conditions can be modified by changing natural forces or man-made influences. The report is based on conditions that existed at the time of subsurface exploration. Construction operations adjacent to the site, and natural events such as floods, or ground water fluctuations, may also affect subsurface conditions, and thus the continuing adequacy of a geotechnical report. El should be kept appraised of any such events, and should be consulted to determine if any additional tests are necessary.

VERIFICATION OF SITE CONDITIONS

Where ground conditions encountered at the site differ significantly from those anticipated in the report, either due to natural variability of subsurface conditions or construction activities, it is a condition of the report that EI be notified of any variations and be provided with an opportunity to review the recommendations of this report. Recognition of change of soil and rock conditions requires experience and it is recommended that a suitably experienced geotechnical engineer be engaged to visit the site with sufficient frequency to detect if conditions have changed significantly.

REPRODUCTION OF REPORTS

This report is the subject of copyright and shall not be reproduced either totally or in part without the express permission of this Company. Where information from the accompanying report is to be included in contract documents or engineering specification for the project, the entire report should be included in order to minimize the likelihood of misinterpretation from logs.

REPORT FOR BENEFIT OF CLIENT

The report has been prepared for the benefit of the Client and no other party. El assumes no responsibility and will not be liable to any other person or organisation for or in relation to any matter dealt with or conclusions expressed in the report, or for any loss or damage suffered by any other person or organisation arising from matters dealt with or conclusions expressed in the report (including without limitation matters arising from any negligent act or omission of El or for any loss or damage suffered by any other party relying upon the matters dealt with or conclusions expressed in the report). Other parties should not rely upon the report or the accuracy or completeness of any conclusions and should make their own inquiries and obtain independent advice in relation to such matters.

OTHER LIMITATIONS

El will not be liable to update or revise the report to take into account any events or emergent circumstances or fact occurring or becoming apparent after the date of the report.