

## **Traffic Engineer Referral Response**

Application Number:	DA2024/1562
Proposed Development:	Demolition works and construction of a residential flat building including strata subdivision
Date:	25/02/2025
Responsible Officer	
Land to be developed (Address):	Lot A DP 24923 , 5 Lauderdale Avenue FAIRLIGHT NSW 2094

#### Officer comments

<u>Proposal description:</u> Demolition works and construction of a residential flat building including strata subdivision

The proposal is for the demolition of the existing structures and construction of a residential development comprising 5 residential apartments (5 x 3-bedroom apartments) and car parking for 11 vehicles (10 residential including 1 accessible parking space and 1 visitor space) accessed via a car lift to Lauderdale Avenue.

The Traffic team has reviewed the following documents:

- Plans (Master Set) Amended Revision DA1, designed by Platform Architects, dated 29/10/2024
- Traffic Impact Assessment (TIA), Reference 0947r01v02, prepared by PDC Consultants dated 29/10/2024, and
- Statement of Environmental Effects prepared by BBF Town Planners dated September 2024.

#### **Notes/comments**

- Application of the Manly DCP car parking rates to the proposed development would result in 8 residential parking spaces and 2 visitor parking spaces. 11 parking spaces are proposed (10 residential spaces including 1 accessible parking space and 0 visitor spaces). For the proposed development, residential parking in excess of the DCP requirement is proposed (10 residential spaces exceeding the residential spaces required by 2 spaces). Reallocating one of the excess resident parking on site can address visitor parking shortfall of 1 space.
- The shortfall of visitor parking space is not considered acceptable given that:
  - Some relaxation of DCP requirements could be considered in areas that are close to good public transport, shops, and recreational facilities, and where there is a noticeable level of walking and cycling activity. However, these arguments would be more relevant to residential parking and do not justify a reduced parking supply for visitors when there is already an excess of residential parking being provided.
  - consideration to the approval of a lower level of parking than DCP rates would be given, in view of the site constraints. This is not applicable to this site as the site is not constrained in terms of its ability to provide parking. Any increased parking

DA2024/1562 Page 1 of 7



- demand on-street as a result of parking shortfall for this development will exacerbate existing high levels of parking congestion in the area.
- the off-street parking shortfall and relying upon on-street parking opportunities is not considered appropriate given that there is a very high parking demand on the street nearby. Lauderdale Avenue and Fairlight Cres currently suffer from high levels of traffic congestion, particularly in peak periods.
- Accessible parking space (1 space) is proposed in compliance with the requirements of the DCP (Section 3.6.3.2) and will improve the equitability of access to the premises for persons with a disability. On the Architectural plans, a bollard is provided for the disabled shared areas, as shown in Figure 2.2 of the Australian Standard AS2890.6:2009 Parking Facilities-Off Street Parking for People with Disability.
- The architectural plans for parking spaces, the access driveway, and the car lift on the Basement Levels have been dimensioned and are adequately sized in accordance with AS2890.1.
- Swept path plots have been included in Appendix 2 of the traffic report and demonstrated that access to the lift by the B99 vehicles is possible. For safety reasons and to avoid congestion on Lauderdale Avenue, the plans include a waiting bay on the access driveway to manage ingress/egress movements. The access driveway has been widened to accommodate these turning movements and to ensure that passing opportunities for vehicles passing in opposing directions will be available.
- The Manly DCP 2013 requires the provision of one (1) bicycle stand for every three (3) car parking spaces. The proposed plans detail the provision of four (4) bicycle parking spaces, satisfying Council's DCP requirements and catering for alternate travel mode options.

#### **Traffic generation**

The proposal will generate minimal traffic during peak periods; therefore, it will not have any unacceptable implications in terms of road network capacity performance.

#### Conclusion

The plans require minor amendments to include one extra visitor parking space, which will be conditioned; however, the amendments required are not sufficient to prevent the application from being supported.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

#### **Recommended Traffic Engineer Conditions:**

# CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

### **Construction Traffic Management Plan**

A Construction Traffic Management Plan (CTMP) and report shall be prepared by a Transport for NSW accredited person and submitted to Council via an application for a Permit to Implement Traffic Control. The application form can be accessed via

https://www.northernbeaches.nsw.gov.au/council/forms. Approval of the permit application by the Northern Beaches Council Traffic Team is required prior to issue of any Construction Certificate.

DA2024/1562 Page 2 of 7



### The CTMP must address following:

- The proposed phases of construction works on the site, and the expected duration of each construction phase.
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken.
- Make provision for all construction materials to be stored on site, at all times.
- The proposed areas within the site to be used for the storage of excavated materials, construction materials and waste containers during the construction period.
- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed.
- Where access is required across private property not in the direct ownership of the proponent, such as a private road/driveway, community title road or right of way, the CTMP is to include:
  - Evidence of the legal right and terms to use the access route or provide owners consent from the owners/strata/community association.
  - Demonstrate that direct access from a public space/road is not viable for each stage of works
  - An assessment to be carried out of the physical constraints of the Right of Carriageway to determine the maximum size of vehicle that may access the site via the Right of Carriageway during construction.
  - Unless owner/strata/community associations consent is obtained, vehicles are not to exceed 24 tonnes or 7.5 metres in length (an assessment must be undertaken that the surface is capable of supporting up to 24 tonnes, otherwise the weight limit should be reduced in the CTMP). If consent is obtained, a copy must be included in the CTMP.
  - No construction vehicles, materials or plant are to be located or parked in the private road/driveway, community title road or right of way.
  - How any disruption to other users of the private road/driveway, community title road or right of way will be minimised and all users kept informed of likely disruption where the access will be closed or blocked for any given time.
  - o If trees are located within or overhang the access route, a tree protection plan prepared by an Arborist with minimum AQF Level 5 in arboriculture demonstrating how any trees within the Right of Carriageway will be protected from damage by construction vehicles. Should any tree protection measures be required on private land in accordance with AS4970-2009 Protection of trees on development sites, owner's consent must be obtained.
  - A Dilapidation report, including photographic surveys, of the private road/driveway/right of way must be included prior to any works commencing on the site. The report must detail the physical condition of the private road/driveway/right of way, and any other adjacent private property assets (including trees) or adjacent public property that may be adversely affected by vehicles servicing the development site to undertake works or activity during site works.
  - A requirement for Post-Construction Dilapidation Reports, including photos of any damage evident at the time of inspection, to be submitted after the completion of works and prior to the Occupation certificate. The report must:
    - Compare the post-construction report with the pre-construction report,
    - Clearly identify any recent damage or change to the private road/driveway/right of way and whether or not it is likely to be the result of the development works,
    - Should any damage have occurred, identify remediation actions taken.
    - Be submitted to Council with the Occupation Certificate.

DA2024/1562 Page 3 of 7



- The proposed method of loading and unloading excavation and construction machinery, excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site.
- Make provision for parking onsite. All Staff and Contractors are to use any basement parking once available.
- Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site are not permitted unless approved by Council prior.
- Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian safety.
- The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site.
- The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site.
- Specify that the public roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council.
- The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent.
- Proposed protection for Council and adjoining properties.
- The location and operation of any on site crane.

The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – "Manual of Uniform Traffic Control Devices", RMS' Manual – "Traffic Control at Work Sites".

All fees and charges associated with the review of this plan is to be in accordance with Council's Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

A copy of the approved CTMP must be kept on-site at all times while work is being carried out.

The development is to be undertaken in accordance with the Construction Traffic Management Plan approved by Northern Beaches Council Traffic Team.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems.

### **Vehicle Access & Parking**

All internal driveways, vehicle turning areas, garages and vehicle parking space/ loading bay

DA2024/1562 Page 4 of 7



dimensions must be designed and constructed to comply with the relevant section of AS 2890 (Off-street Parking standards).

With respect to this, the following revision(s) must be undertaken to the parking allocation:

- 9 residential spaces
- 2 residential visitor spaces
- 2 residential visitor spaces must be line marked as "Residential Visitor Only".

These amendment(s) must be clearly marked on the plans submitted to the Principal Certifier prior to the issue of a Construction Certificate.

Reason: To ensure compliance with Australian Standards relating to manoeuvring, access and parking of vehicle.

## CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

#### **Demolition Traffic Management Plan**

As a result of the site constraints, limited vehicle access and parking, a Demolition Traffic Management Plan (DTMP) and report shall be prepared by a Transport for NSW accredited person and submitted to Council via an application for a Permit to Implement Traffic Control. The application form can be accessed via https://www.northernbeaches.nsw.gov.au/council/forms. Approval of the permit application by the Northern Beaches Council Traffic Team is required prior to issue of any Construction Certificate.

Due to heavy traffic congestion throughout the area, truck movements will be restricted during the major commuter peak times being 8.00-9.30am and 4.30-6.00pm.

#### The DTMP must:-

- Make provision for all construction materials to be stored on site, at all times.
- The DTMP is to be adhered to at all times during the project.
- Specify construction truck routes and truck rates. Nominated truck routes are to be distributed over the surrounding road network where possible.
- Provide for the movement of trucks to and from the site, and deliveries to the site. Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site is not permitted unless prior approval is granted by Council's Traffic Engineers.
- Specify that, due to the proximity of the site adjacent to #### School, no heavy vehicle movements or construction activities effecting vehicle and pedestrian traffic are permitted in school zone hours (8:00am-9:30am and 2:30pm-4:00pm weekdays).
- Include a Traffic Control Plan prepared by an TfNSW accredited traffic controller for any activities involving the management of vehicle and pedestrian traffic.
- Specify that a minimum fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measures.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes, structures proposed on the footpath areas (hoardings, scaffolding or temporary shoring) and extent of tree protection zones around Council street trees.
- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the DTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of

DA2024/1562 Page 5 of 7



construction activities. These communications must be documented and submitted to Council prior to work commencing on site.

- Specify spoil management process and facilities to be used on site.
- Specify that the roadway (including footpath) must be kept in a serviceable condition for the duration of demolition. At the direction of Council, the applicant is to undertake remedial treatments such as patching at no cost to Council.

The DTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – "Manual of Uniform Traffic Control Devices", RMS' Manual – "Traffic Control at Work Sites".

All fees and charges associated with the review of this plan is to be in accordance with Council's Schedule of Fees and Charges and are to be paid at the time that the Demolition Traffic Management Plan is submitted.

Reason: This condition is to ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems. The DTMP is intended to minimise impact of construction activities on the surrounding community, in terms of vehicle traffic (including traffic flow and parking) and pedestrian amenity adjacent to the site.

## CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

#### Implementation of Demolition Traffic Management Plan

All works and demolition activities are to be undertaken in accordance with the approved Demolition Traffic Management Plan (DTMP). All controls in the DTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the DTMP be impacted by surrounding major development not encompassed in the approved DTMP, the DTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved DTMP is to be kept onsite at all times and made available to the accredited certifier or Council on request.

Reason: To ensure compliance and Council's ability to modify the approved Construction Traffic Management Plan where it is deemed unsuitable during the course of the project.

#### Implementation of Construction Traffic Management Plan

All works and construction activities are to be undertaken in accordance with the approved Construction Traffic Management Plan (CTMP). All controls in the CTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the CTMP be impacted by surrounding major development not encompassed in the approved CTMP, the CTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved CTMP is to be kept onsite at all times and made available to Council on request.

Reason: To ensure compliance of the developer/builder in adhering to the Construction Traffic Management procedures agreed and are held liable to the conditions of consent.

#### **Ongoing Management**

The applicant shall be responsible in ensuring that the road reserve remains in a serviceable state during the course of the demolition and building works.

Reason: To ensure public safety.

DA2024/1562 Page 6 of 7



# CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

### Allocation of parking spaces (strata title)

All carparking spaces are to be assigned to individual units. All residential units must be assigned a minimum of one parking space. Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure parking availability for residents and visitors in accordance with the Manly Development Control Plan.

#### **Disabled Parking Spaces**

Where disabled parking spaces are provided they must be in accordance with AS2890.6:2009.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure compliance with Australian Standards.

#### Shared Zone Bollard

A bollard is to be provided at the shared zone between disabled spaces in accordance to Australian Standards AS2890.6:2009.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of any Occupation Certificate.

Reason: To ensure compliance with Australian Standards.

## ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

#### Landscaping adjoining vehicular access

The applicant must ensure that the planting chosen for any land immediately adjacent to the driveway and adjacent to any driveway intersections must not exceed a height of 1m.

Reason: To maintain unobstructed sight distance for motorists.

DA2024/1562 Page 7 of 7