

14 April 2025



Sekisui House Services (NSW) Pty Limited
Ground Floor 68 Waterloo Road
MACQUARIE PARK NSW 2113

Dear Sir/Madam

Application Number: DA2024/0492
Address: Lot 1 DP 524083 , 21 A Warili Road, FRENCHS FOREST NSW 2086
Lot 1 DP 1298188 , 49 Blackbutts Road, FRENCHS FOREST NSW 2086
Proposed Development: Neighbourhood title subdivision comprising of 13 lots and new road access

Please find attached the Notice of Determination for the above mentioned Application.

You should thoroughly read the Notice of Determination and be aware of any conditions imposed that affect the development and guide the next steps in the process before you can commence works and/or the use.

A copy of the Assessment Report associated with this application is available to view in the Planning and Development > Application Search section of Council's website at www.northernbeaches.nsw.gov.au

If you have any questions regarding the decision or the conditions, please contact Council to speak to the assessment officer or the undersigned on 1300 434 434 or via email quoting the Application number, property address and the description of works to council@northernbeaches.nsw.gov.au

Regards,



Steven Findlay
Manager Development Assessments

NOTICE OF DETERMINATION OF A DEVELOPMENT APPLICATION

Application Number:	DA2024/0492 PAN-430158
Applicant:	Sekisui House Services (NSW) Pty Limited Ground Floor 68 Waterloo Road MACQUARIE PARK NSW 2113
Property:	Lot 1 DP 524083 21 A Warili Road FRENCHS FOREST NSW 2086 Lot 1 DP 1298188 49 Blackbutts Road FRENCHS FOREST NSW 2086
Description of Development:	Neighbourhood title subdivision comprising of 13 lots and new road access
Determination:	Approved Consent Authority: Northern Beaches Council
Date of Determination:	11/04/2025
Date from which the consent operates:	14/04/2025
Date on which the consent lapses:	14/04/2030

Under section 4.18(1) of the EP&A Act, notice is given that the above development application has been determined by the granting of consent using the power in section 4.16(1)(a) of the EP&A Act, subject to the conditions specified in this notice.

Reasons for approval

The development proposal meets the Objects of the Environmental Planning and Assessment Act 1979, contained in Section 1.3, having considered the relevant provisions under s.4.15 of the aforementioned Act. Consequently, the development is considered to be in the public interest, subject to conditions.

Community views

The application was notified in accordance with Council's Community Participation Plan and the Environmental Planning and Assessment Regulation 2021. Any submissions received representing community views were considered as part of the assessment of the application. Conditions of consent included within this Notice of Determination have been applied to ensure that the development satisfies the Objects of the Environmental Planning and Assessment Act and will not result in unacceptable environmental impacts.

Request a review of the determination

If you are dissatisfied with this determination, you may request a review of the determination:

- You do not have the right to request a review of the determination under section 8.3 of the EP&A Act if you are excluded from those developments listed under Section 8.2(2) of the EP&A Act.
- You may request a review of the consent authority's decision under section 8.3(1) of the EP&A Act. The application must be lodged to and determined by the consent authority within 6 months from the date that the original determination was registered on the NSW Planning Portal. Prospective applicants for a Review of Determination are encouraged to lodge a review application with Council as soon as possible, to enable a full review and determination.

Rights to appeal

You have a right under section 8.7 of the EP&A Act to appeal to the Court within 6 months after the date on which the determination appealed against is notified or registered on the NSW planning portal.

Objector's right of appeal against the determination

An objector who is dissatisfied with the consent authority's determination to grant consent, in relation to Designated Development only has the right to appeal to the Court against the determination under section 8.8 of the EP&A Act within 28 days after the date that the objector was notified of the determination appealed against.

Dictionary

The Dictionary at the end of this consent defines words and expressions for the purposes of this determination.

Signed

On behalf of the Consent Authority



Name

Steven Findlay, Manager Development Assessments

Date

11/04/2025

Terms and Reasons for Conditions

Under section 88(1)(c) of the EP&A Regulation, the consent authority must provide the terms of all conditions and reasons for imposing the conditions other than the conditions prescribed under section 4.17(11) of the EP&A Act. The terms of the conditions and reasons are set out below.

GENERAL CONDITIONS

1. Approved Plans and Supporting Documentation

Development must be carried out in accordance with the following approved plans (stamped by Council) and supporting documentation, except where the conditions of this consent expressly require otherwise.

Approved Plans				
Plan Number	Revision Number	Plan Title	Drawn By	Date of Plan
0923/3D	-	Plan Showing Proposed Neighbourhood Scheme	YSCO Geomatics	23/1/2025
C01.41	3	GENERAL ARRANGEMENT PLAN	Enspire Solutions Pty Ltd	31/03/2025
C03.01	4	EROSION AND SEDIMENTATION CONTROL PLAN	Enspire Solutions Pty Ltd	31/03/2025
C03.21	3	EROSION AND SEDIMENTATION CONTROL DETAILS	Enspire Solutions Pty Ltd	31/03/2025
C04.01	4	EARTHWORKS CUT AND FILL PLAN	Enspire Solutions Pty Ltd	31/03/2025
C04.21	3	EARTHWORKS CUT AND FILL SECTIONS	Enspire Solutions Pty Ltd	31/03/2025
C05.01	5	SITEWORKS AND STORMWATER MANAGEMENT PLAN SHEET 01	Enspire Solutions Pty Ltd	31/03/2025
C05.02	5	SITEWORKS AND STORMWATER MANAGEMENT PLAN SHEET 02	Enspire Solutions Pty Ltd	31/03/2025
C06.01	3	ROAD TYPICAL CROSS SECTIONS	Enspire Solutions Pty Ltd	31/03/2025
C07.01	3	ROAD LONGITUDINAL SECTION	Enspire Solutions Pty Ltd	31/03/2025
C11.01	4	PAVEMENT, SIGNAGE AND LINEMARKING PLAN - SHEET 01	Enspire Solutions Pty Ltd	31/03/2025

C11.02	3	PAVEMENT, SIGNAGE AND LINEMARKING PLAN - SHEET 02	Enspire Solutions Pty Ltd	31/03/2025
C13.01	2	SITE SECTIONS	Enspire Solutions Pty Ltd	31/03/2025
C14.01	3	SITWORKS DETAILS	Enspire Solutions Pty Ltd	31/03/2025
C15.01	2	RETAINING WALL ELEVATIONS - SHEET 01	Enspire Solutions Pty Ltd	31/03/2025
C15.02	2	RETAINING WALL ELEVATIONS - SHEET 02	Enspire Solutions Pty Ltd	31/03/2025
C17.01	4	OSD TANK PLAN AND SECTION	Enspire Solutions Pty Ltd	31/03/2025
C18.01	3	STORMWATER DETAILS	Enspire Solutions Pty Ltd	31/03/2025
C20.01	3	PRE-DEVELOPMENT CATCHMENT PLAN	Enspire Solutions Pty Ltd	31/03/2025
C20.21	4	POST-DEVELOPMENT CATCHMENT PLAN	Enspire Solutions Pty Ltd	31/03/2025
C22.01	3	TURNING PLAN	Enspire Solutions Pty Ltd	31/03/2025

Note: Plan Showing Proposed Neighbourhood Scheme is to be consistent with all other plans.

Approved Reports and Documentation			
Document Title	Version Number	Prepared By	Date of Document
Operational Waste Management Plan	B	Consulting. An elephant Foot company.	13/03/2024
Preliminary Site Investigation	20499/1-AA	Geotechnique Pty Ltd	31/01/2024
Detailed Site Investigation	20499/2-AA	Geotechnique Pty Ltd	16/08/2024
Geotechnical Investigation Report	1	Crozier Geotechnical Consultants	26/03/2024
Landscape Architecture - DA Package	A	Taylor Brammer	5/04/2024
Civil Engineering and Stormwater Report	3	Enspire	15/01/2025
Traffic Impact Assessment	2.0	SCT Consulting	26 March 2024
Flora and Fauna Assessment	Final	Kingfisher	April then updated July and

			September 2024
Arboricultural Impact Assessment Report	2.0	The Tree Guardian Arboricultural Consultancy	1 August 2024
Neighbourhood Management Statement	Form 30	Colin Biggers & Paisley Lawyers	06/09/2024

In the event of any inconsistency between the approved plans, reports and documentation, the approved plans prevail.

In the event of any inconsistency between the approved plans and a condition of this consent, the condition prevails.

Reason: To ensure all parties are aware of the approved plans and supporting documentation that applies to the development.

2. Compliance with Other Department, Authority or Service Requirements

The development must be carried out in compliance with all recommendations and requirements, excluding general advice, within the following:

Other Department, Authority or Service	EDMS Reference	Dated
Ausgrid - UG Cables and Kiosk	Ausgrid Referral Response - UG Cables and Kiosk	16.12.2022
Ausgrid - Subdivision	Ausgrid Referral Response - Subdivision	17.05.2024

(NOTE: For a copy of the above referenced document/s, please see Application Tracking on Council's website www.northernbeaches.nsw.gov.au)

Reason: To ensure the work is carried out in accordance with the determination and the statutory requirements of other departments, authorities or bodies.

3. Prescribed Conditions

- (a) All building works must be carried out in accordance with the requirements of the Building Code of Australia (BCA).
- (b) BASIX affected development must comply with the schedule of BASIX commitments specified within the submitted BASIX Certificate (demonstrated compliance upon plans/specifications is required prior to the issue of the Construction Certificate);
- (c) A sign must be erected in a prominent position on any site on which building work, subdivision work or demolition work is being carried out:
 - (i) showing the name, address and telephone number of the Principal Certifier for the work, and
 - (ii) showing the name of the principal contractor (if any) for any building work and a telephone number on which that person may be contacted outside working hours, and
 - (iii) stating that unauthorised entry to the work site is prohibited.

Any such sign is to be maintained while the building work, subdivision work or demolition work is being carried out, but must be removed when the work has been

completed.

- (d) Residential building work within the meaning of the Home Building Act 1989 must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the following information:

- (i) in the case of work for which a principal contractor is required to be appointed:
 - A. the name and licence number of the principal contractor, and
 - B. the name of the insurer by which the work is insured under Part 6 of that Act,
- (ii) in the case of work to be done by an owner-builder:
 - A. the name of the owner-builder, and
 - B. if the owner-builder is required to hold an owner-builder permit under that Act, the number of the owner-builder permit.

If arrangements for doing the residential building work are changed while the work is in progress so that the information notified under becomes out of date, further work must not be carried out unless the Principal Certifier for the development to which the work relates (not being the Council) has given the Council written notice of the updated information.

- (e) Development that involves an excavation that extends below the level of the base of the footings of a building on adjoining land, the person having the benefit of the development consent must, at the person's own expense:
- (i) protect and support the adjoining premises from possible damage from the excavation, and
 - (ii) where necessary, underpin the adjoining premises to prevent any such damage.
 - (iii) must, at least 7 days before excavating below the level of the base of the footings of a building on an adjoining allotment of land, give notice of intention to do so to the owner of the adjoining allotment of land and furnish particulars of the excavation to the owner of the building being erected or demolished.
 - (iv) the owner of the adjoining allotment of land is not liable for any part of the cost of work carried out for the purposes of this clause, whether carried out on the allotment of land being excavated or on the adjoining allotment of land.

In this clause, allotment of land includes a public road and any other public place.

Reason: Legislative requirement.

4. **General Requirements**

- (a) Unless authorised by Council:
Building construction and delivery of material hours are restricted to:
- 7.00 am to 5.00 pm inclusive Monday to Friday,
 - 8.00 am to 1.00 pm inclusive on Saturday,
 - No work on Sundays and Public Holidays.

Demolition and excavation works are restricted to:

- 8.00 am to 5.00 pm Monday to Friday only.

(Excavation work includes the use of any excavation machinery and the use of

jackhammers, rock breakers, excavators, loaders and the like, regardless of whether the activities disturb or alter the natural state of the existing ground stratum or are breaking up/removing materials from the site).

- (b) Construction certificate plans are to be in accordance with all finished levels identified on approved plans. Notes attached to plans indicating tolerances to levels are not approved.
- (c) Should any asbestos be uncovered on site, its demolition and removal must be carried out in accordance with WorkCover requirements and the relevant Australian Standards.
- (d) At all times after the submission of the Notice of Commencement to Council, a copy of the Development Consent and Construction Certificate is to remain onsite at all times until the issue of an Occupation Certificate. The consent shall be available for perusal of any Authorised Officer.
- (e) Where demolition works have been completed and new construction works have not commenced within 4 weeks of the completion of the demolition works that area affected by the demolition works shall be fully stabilised and the site must be maintained in a safe and clean state until such time as new construction works commence.
- (f) Onsite toilet facilities (being either connected to the sewer or an accredited sewer management facility) for workers are to be provided for construction sites at a rate of 1 per 20 persons.
- (g) Prior to the release of the Construction Certificate, payment of the following is required:
 - i) Long Service Levy - Payment should be made to Service NSW (online or in person) or alternatively to Northern Beaches Council in person at a Customer Service Centre. Payment is not required where the value of the works is less than \$250,000. The Long Service Levy is calculated on 0.25% of the building and construction work. The levy rate and level in which it applies is subject to legislative change. The applicable fee at the time of payment of the Long Service Levy will apply.
 - ii) Section 7.11 or Section 7.12 Contributions Plan – Payment must be made to Northern Beaches Council. Where the subject land to which the development is proposed is subject to either a Section 7.11 or 7.12 Contributions Plan, any contribution to which the development is liable under the respective plan that applies is to be paid to Council. The outstanding contribution will be indexed at time of payment in accordance with the relevant Contributions Plan.
 - iii) Prior to the release of the first subdivision certificate, payment of the following is required:
Housing and Productivity Contribution - Payment must be made on the NSW Planning Portal for development to which this contribution applies. The amount payable is subject to indexation at the time of payment.
- (h) The applicant shall bear the cost of all works associated with the development that occurs on Council's property.
- (i) No skip bins, building materials, demolition or excavation waste of any nature, and no hoist, plant or machinery (crane, concrete pump or lift) shall be placed on Council's footpaths, roadways, parks or grass verges without Council Approval.
- (j) Demolition materials and builders' wastes are to be removed to approved waste/recycling centres.
- (k) No trees or native shrubs or understorey vegetation on public property (footpaths, roads, reserves, etc.), on the land to be developed, or within adjoining properties,

shall be removed or damaged during excavation or construction unless specifically approved in this consent including for the erection of any fences, hoardings or other temporary works.

(l) Prior to the commencement of any development onsite for:

- i) Building/s that are to be erected
- ii) Building/s that are situated in the immediate vicinity of a public place and is dangerous to persons or property on or in the public place
- iii) Building/s that are to be demolished
- iv) For any work/s that is to be carried out
- v) For any work/s that is to be demolished

The person responsible for the development site is to erect or install on or around the development area such temporary structures or appliances (wholly within the development site) as are necessary to protect persons or property and to prevent unauthorised access to the site in order for the land or premises to be maintained in a safe or healthy condition. Upon completion of the development, such temporary structures or appliances are to be removed within 7 days.

(m) A "Road Opening Permit" must be obtained from Council, and all appropriate charges paid, prior to commencement of any work on Council property. The owner/applicant shall be responsible for all public utilities and services in the area of the work, shall notify all relevant Authorities, and bear all costs associated with any repairs and/or adjustments as those Authorities may deem necessary.

(n) The works must comply with the relevant Ausgrid Network Standards and SafeWork NSW Codes of Practice.

(o) Should any construction cranes be utilised on site, they are to be fitted with bird deterrents along the counterweight to discourage raptor (bird) nesting activity. Deterrents are to remain in place until cranes are dismantled. Selection of deterrent methods is to be undertaken in accordance with the recommendations of a suitably qualified ecologist.

(p) Requirements for new swimming pools/spas or existing swimming pools/spas affected by building works.

- (1) Child resistant fencing is to be provided to any swimming pool or lockable cover to any spa containing water and is to be consistent with the following;

Relevant legislative requirements and relevant Australian Standards (including but not limited) to:

- (i) Swimming Pools Act 1992
- (ii) Swimming Pools Amendment Act 2009
- (iii) Swimming Pools Regulation 2018
- (iv) Australian Standard AS1926 Swimming Pool Safety
- (v) Australian Standard AS1926.1 Part 1: Safety barriers for swimming pools
- (vi) Australian Standard AS1926.2 Part 2: Location of safety barriers for swimming pools.

(2) A 'KEEP WATCH' pool safety and aquatic based emergency sign, issued by Royal Life Saving is to be displayed in a prominent position within the pool/spa area.

(3) Filter backwash waters shall be conveyed to the Sydney Water sewerage system in sewered areas or managed on-site in unsewered areas in a

manner that does not cause pollution, erosion or run off, is separate from the irrigation area for any wastewater system and is separate from any onsite stormwater management system.

- (4) Swimming pools and spas must be registered with the Division of Local Government.

Reason: To ensure that works do not interfere with reasonable amenity expectations of residents and the community.

FEES / CHARGES / CONTRIBUTIONS

5. Policy Controls

Northern Beaches Section 7.12 Contributions Plan 2024

A monetary contribution of \$15,382.75 is payable to Northern Beaches Council for the provision of local infrastructure and services pursuant to section 7.12 of the Environmental Planning & Assessment Act 1979 and the Northern Beaches Section 7.12 Contributions Plan (as amended).

The monetary contribution is based on a development cost of \$1,538,275.00.

The total amount payable will be adjusted at the time the payment is made, in accordance with the provisions of the Northern Beaches Section 7.12 Contributions Plan (as amended).

Details demonstrating compliance, by way of written receipts issued by Council, are to be submitted to the Certifier prior to issue of any Construction Certificate or, if relevant, the Subdivision Certificate (whichever occurs first).

A copy of the Contributions Plan is available for inspection at 725 Pittwater Road, Dee Why or on Council's website at Northern Beaches Council - Development Contributions.

Reason: To provide for contributions in accordance with the Contribution Plan to fund the provision of new or augmented local infrastructure and services.

6. Security Bond

A bond (determined from cost of works) of \$10,000 and an inspection fee in accordance with Council's Fees and Charges paid as security are required to ensure the rectification of any damage that may occur to the Council infrastructure contained within the road reserve adjoining the site as a result of construction or the transportation of materials and equipment to and from the development site.

An inspection fee in accordance with Council adopted fees and charges (at the time of payment) is payable for each kerb inspection as determined by Council (minimum (1) one inspection).

All bonds and fees shall be deposited with Council prior to Construction Certificate or demolition work commencing, and details demonstrating payment are to be submitted to the Certifier prior to the issue of the Construction Certificate.

To process the inspection fee and bond payment a Bond Lodgement Form must be completed with the payments (a copy of the form is attached to this consent and alternatively a copy is

located on Council's website at www.northernbeaches.nsw.gov.au).

Reason: To ensure adequate protection of Council's infrastructure.

7. Housing and productivity contribution - Development consents

1. The housing and productivity contribution (HPC) set out in the table below, but as adjusted in accordance with condition 2, is required to be made:

Contribution Type	Amount
Housing and Productivity Contribution	\$12,000 per residential lot
Total:	\$144,000 (12 residential lots)

2. The amount payable at the time of payment is the amount shown in condition 1 as the total housing and productivity contribution adjusted by multiplying it by:

highest PPI number

consent PPI number

where—

highest PPI number is the highest PPI number for a quarter following the June quarter 2023 and up to and including the 2nd last quarter before the quarter in which the payment is made.

consent PPI number is the PPI number last used to adjust HPC rates when consent was granted.

June quarter 2023 and PPI have the meanings given in clause 22 (4) of the Environmental Planning and Assessment (Housing and Productivity Contribution) Order 2023.

If the amount adjusted in accordance with this condition is less than the amount at the time consent is granted, the higher amount must be paid instead.

3. The HPC must be paid before the issue first construction certificate in relation to the development, or before the commencement of any work authorised by this consent (if no construction certificate is required). However, if development is any of the kinds set out in the table below, the total housing and productivity contribution must be paid as set out in the table:

Development	Time by which HPC must be paid
Development consisting only of residential subdivision within the meaning of the HPC Order	Before the issue of the first subdivision certificate

High-density residential development within the meaning of the HPC Order for which no construction certificate is required	Before the issue of the first strata certificate
Development that consists only of residential strata subdivision (within the meaning of the HPC Order) or only of residential strata subdivision and a change of use of an existing building	Before the issue of the first strata certificate
Manufactured home estate for which no construction certificate is required	Manufactured home estate for which no construction certificate is required

4. The HPC must be paid using the NSW planning portal (<https://pp.planningportal.nsw.gov.au/>).

5. If the Minister administering the Environmental Planning and Assessment Act 1979 agrees, the HPC (apart from any transport project component) may be made, instead of as a monetary contribution, in the following ways:
 - a) the dedication or provision of land for the purpose of regional infrastructure in the region in which the development will be carried out,
 - b) the carrying out of works for the purpose of regional infrastructure in the region in which the HPC development will be carried out.

If the HPC is made partly as a monetary contribution, the amount of the part payable is the amount of the part adjusted in accordance with condition 2 at the time of payment.

6. Despite condition 1, a housing and productivity contribution is not required to be made to the extent that a planning agreement excludes the application of Subdivision 4 of Division 7.1 of the Environmental Planning and Assessment Act 1979 to the development, or the Environmental Planning and Assessment (Housing and Productivity Contribution) Order 2023 exempts the development from the contribution. The amount of the contribution may also be reduced under the order, including if payment is made before 1 July 2025.

Reason: Statutory requirement.

8. **Construction, Excavation and Associated Works Security Bond(s)**
The applicant is to lodge a bond with Council for the following:

Crossing / Kerb & Gutter / Footpath Works

As security against any damage or failure to complete the construction of any vehicular crossings, kerb and gutter, any footpath works and removal of any redundant driveways required as part of this consent a bond of \$50000

Security Bond

As security against damage to Council's roads fronting the site caused by the transport and disposal of materials and equipment to and from the site a bond of \$40000

Maintenance for Civil Works

A maintenance bond of \$15000 for the construction of the 1.5m wide footpath for the Blackbutts frontage and vehicle crossings. The maintenance bond will only be refunded upon completion of the six month maintenance period, if work has been completed in accordance with the approved plans and to the satisfaction of Council. The maintenance bond is to be paid prior to Council prior to issuing of practical completion.

Details confirming payment of the bond(s) are to be submitted to the Principal Certifier prior to the issue of the Construction Certificate.

Reason: Protection of Council's infrastructure.

BUILDING WORK – BEFORE ISSUE OF A CONSTRUCTION CERTIFICATE**9. Street Lighting**

Prior to the issue of a Construction Certificate, location and details of street lighting is to be provided to the Certifier.

A suitably qualified professional is to confirm that the design for lighting will minimise impact on neighbouring properties. This includes that all lighting must face away from the neighbouring properties to the west.

Reason: To minimise lighting impacts to neighbouring properties.

10. Amendments to the approved plans

The following amendments are to be made to the approved plans:

i) DELETED

ii) Along the entire southern boundary of lot 13, species obtaining a mature height of 2m are to be provided.

iii) Along the eastern boundary (lots 5-13), species obtaining a mature height of 3m are to be provided.

iv) DELETED

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of the Construction Certificate.

Reason: To require amendments to the plans endorsed by the consent authority following assessment of the development.

BEFORE ISSUE OF A SUBDIVISION WORKS CERTIFICATE**11. On-Site Stormwater Detention**

The Applicant is to provide a certification of drainage plans detailing the provision of on-site stormwater detention in accordance with Northern Beaches Council's Water Management for Development Policy, and generally in accordance with the concept drainage plans prepared by Enspire, drawing number 230057-00-DA C5.01(Rev 4), C5.02(Rev 4), C17.01 (Rev 17.01), dated 22/1/25. Detailed drainage plans are to be prepared by a suitably qualified Civil

Engineer, who has membership to Engineers Australia, National Engineers Register (NER) or Professionals Australia (RPENG) and registered in the General Area of Practice for civil engineering.

The drainage plans must address the following:

i. Detail the installation of a orifice plate as detailed in the DRAINS model.

ii. Deleted

Detailed drainage plans, including engineering certification, are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: To ensure appropriate provision for the disposal of stormwater and stormwater management arising from the development.

12. **Submission of Engineering Plans**

The application is to include four (4) copies of Civil Engineering plans for the design of a new road and stormwater drainage under community Lot number 1; including footpath, kerb and gutter, and indented parallel parking bay, which are to be generally in accordance with the Council's specification for engineering works - AUS-SPEC #1. The plan shall be prepared by a qualified civil engineer.

The design must include the following information:

a) Construct a new internal access road, minimum 6m wide; with the exception of the 5.5m wide section from Warili Road to the property boundary of No.21 Warili Road and Lot 13.

b) Kerb and gutter (vertical faced only) and associated stormwater drainage for the full length of the internal access road.

c) The access road driveway crossing at Warili Road is to include a kerb splay to enable access for Council's Waste vehicle.

d) Construct a 1.5m wide concrete footpath on the eastern side of the road, from Warili Road connecting with the existing footpath on Blackbutts Road.

e) Construct a 12.2m radius turning circle for Council's 10.5m Waste vehicle to turn around in a continuous movement.

f) A swept path analysis is required for a widened road design which enables both Council's 10.5m waste vehicle and a B99 design vehicle to pass simultaneously on the curved section of road. The final kerb alignment and road layout must be approved by Council's Traffic Engineer.

g) Construct a single consolidated indented parking bay south of the turning circle providing 5 visitor parking spaces. The parking bay should be 2.1m wide and indented with a 45 degree angle transition to facilitate entry and exit. Linemarking of the intermediate spaces should be 6m in length and the end spaces 6.3m in length. Parking spaces must be designed and constructed to comply with the relevant section of AS 2890 (Off-street Parking standards).

The submitted Signage and Linemarking Plans, Drawing No.230057-00-DA-C11.01 and 230057-00-DA-C11.02 Revision 1, must be amended and submitted to Council's Traffic team

prior to the issue of any Construction Certificate:

- Installation of double dividing barrier line (BB lines) from Warili Road to the start of the turning area.
- Installation of an unbroken yellow 'No Stopping' line (C3 line) in the turning circle.
- Removal of proposed signage.
- Removal of proposed 'Give Way' holding line.

Details demonstrating compliance are to be submitted to Council for approval prior to the issue of the Subdivision Works Certificate.

Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification. To prevent parking along the internal access road and reduce signage clutter.

13. **Utilities Services**

Prior to the issue of the Subdivision Works Certificate, written evidence of the following service provider requirements must be provided to the Principal Certifier:

- a) a letter from Ausgrid demonstrating that satisfactory arrangements can be made for the installation and supply of electricity,
- b) a response from Sydney Water as to whether the proposed works subject to this consent would affect any Sydney Water infrastructure, and whether further requirements need to be met, and
- c) other relevant utilities or services - that the development as proposed to be carried out is satisfactory to those other service providers, or if it is not, the changes that are required to make the development satisfactory to them.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Subdivision Works Certificate.

Reason: To ensure relevant utility and service providers' requirements are provided to the Principal Certifier.

14. **Submission of Roads Act Application for Civil Works in the Public Road**

The Applicant is to submit an application for approval for Infrastructure works on Councils roadway. Engineering plans for the new development works within the road reserve and this development consent are to be submitted to Council for approval under the provisions of Sections 138 and 139 of the Roads Act 1993.

1) The application is to include Civil Engineering plans for the design of a 1.5m wide concrete footpath within the Blackbutts footpath reserve to replace the existing concrete footpath for the full frontage of the site.

2) Vehicle crossings in Blackbutts Road and Warili Road.

3) The stormwater connection of the 375mm outlet pipe to Councils stormwater pit in Warili Road. The stormwater drainage longsection is to detail all service locations to AHD determined by a services locator in the footpath area.

The Plans are to be in accordance with the Council's specification for engineering works - AUS-SPEC #1 and standard engineering drawings. The plans shall be prepared by a qualified Civil Engineer.

The fee associated with the assessment and approval of the application is to be in accordance with Council's Fee and Charges.

An approval is to be submitted to the Certifier prior to the issue of the Subdivision Works Certificate

Reason: To ensure engineering works are constructed in accordance with relevant standards and Council's specification.

15. Pre-Commencement Dilapidation Report

The applicant must prepare and submit a dilapidation report providing an accurate record of the existing condition of adjoining public property and public infrastructure (including roads, gutter, footpaths, etc). A copy of the report must be provided to Council, any other owners of public infrastructure and the owners of adjoining and affected private properties (including all adjacent properties to the west that abut the internal road).

The dilapidation report must be submitted to Council for written approval and the written approval is then to be submitted to the Principal Certifier prior to the issue of the any Subdivision Works Certificate and the commencement of any works including demolition.

Reason: Protection of Council's Infrastructure during construction.

16. Construction Traffic Management Plan

A Construction Traffic Management Plan (CTMP) and report shall be prepared by a Transport for NSW accredited person and submitted to and approved by the Northern Beaches Council Traffic Team prior to issue of any Construction Certificate.

The CTMP must address following:

- The proposed phases of construction works on the site, and the expected duration of each construction phase.
- The proposed order in which works on the site will be undertaken, and the method statements on how various stages of construction will be undertaken.
- Make provision for all construction materials to be stored on site, at all times.
- The proposed areas within the site to be used for the storage of excavated materials, construction materials and waste containers during the construction period.
- The proposed method of access to and egress from the site for construction vehicles, including access routes and truck routes through the Council area and the location and type of temporary vehicular crossing for the purpose of minimising traffic congestion and noise in the area, with no access across public parks or reserves being allowed.
- Where access is required across private property not in the direct ownership of the proponent, such as a private road/driveway, community title road or right of way, the CTMP is to include:
 - Evidence of the legal right and terms to use the access route or provide owners consent from the owners/strata/community association.
 - Demonstrate that direct access from a public space/road is not viable for each stage of works.
 - An assessment to be carried out of the physical constraints of the Right of Carriageway to determine the maximum size of vehicle that may access the site

via the Right of Carriageway during construction.

- Unless owner/strata/community associations consent is obtained, vehicles are not to exceed 24 tonnes or 7.5 metres in length (an assessment must be undertaken that the surface is capable of supporting up to 24 tonnes, otherwise the weight limit should be reduced in the CTMP). If consent is obtained, a copy must be included in the CTMP.
- No construction vehicles, materials or plant are to be located or parked in the private road/driveway, community title road or right of way.
- How any disruption to other users of the private road/driveway, community title road or right of way will be minimised and all users kept informed of likely disruption where the access will be closed or blocked for any given time.
- If trees are located within or overhang the access route, a tree protection plan prepared by an Arborist with minimum AQF Level 5 in arboriculture demonstrating how any trees within the Right of Carriageway will be protected from damage by construction vehicles. Should any tree protection measures be required on private land in accordance with AS4970-2009 Protection of trees on development sites, owner's consent must be obtained.
- A Dilapidation report, including photographic surveys, of the private road/driveway/right of way must be included prior to any works commencing on the site. The report must detail the physical condition of the private road/driveway/right of way, and any other adjacent private property assets (including trees) or adjacent public property that may be adversely affected by vehicles servicing the development site to undertake works or activity during site works.
- A requirement for Post-Construction Dilapidation Reports, including photos of any damage evident at the time of inspection, to be submitted after the completion of works and prior to the Occupation certificate. The report must:
 - Compare the post-construction report with the pre-construction report,
 - Clearly identify any recent damage or change to the private road/driveway/right of way and whether or not it is likely to be the result of the development works,
 - Should any damage have occurred, identify remediation actions taken.
 - Be submitted to Council with the Occupation Certificate.
- The proposed method of loading and unloading excavation and construction machinery, excavation and building materials, formwork and the erection of any part of the structure within the site. Wherever possible mobile cranes should be located wholly within the site.
- Make provision for all Staff and Contractors to use parking onsite.
- Temporary truck standing/ queuing locations in a public roadway/ domain in the vicinity of the site are not permitted unless approved by Council prior.
- Specify that, due to the proximity of the site in proximity to Mimosa Public School and Davidson High School, no heavy vehicle movements or construction activities effecting vehicle and pedestrian traffic are permitted in school zone hours (8:00am-9:30am and 2:30pm-4:00pm weekdays).
- Include a Traffic Control Plan prepared by a person with suitable RMS accreditation for any activities involving the management of vehicle and pedestrian safety.
- The proposed manner in which adjoining property owners will be kept advised of the timeframes for completion of each phase of development/construction process. It must also specify that a minimum Fourteen (14) days notification must be provided to adjoining property owners prior to the implementation of any temporary traffic control measure.
- Include a site plan showing the location of any site sheds, location of requested Work Zones, anticipated use of cranes and concrete pumps, structures proposed on the

footpath areas (hoardings, scaffolding or shoring) and any tree protection zones around Council street trees.

- Take into consideration the combined construction activities of other development in the surrounding area. To this end, the consultant preparing the CTMP must engage and consult with developers undertaking major development works within a 250m radius of the subject site to ensure that appropriate measures are in place to prevent the combined impact of construction activities, such as (but not limited to) concrete pours, crane lifts and dump truck routes. These communications must be documented and submitted to Council prior to work commencing on site.
- The proposed method/device to remove loose material from all vehicles and/or machinery before entering the road reserve, any run-off from the washing down of vehicles shall be directed to the sediment control system within the site.
- Specify that the public roadway (including footpath) must be kept in a serviceable condition for the duration of construction. At the direction of Council, undertake remedial treatments such as patching at no cost to Council.
- The proposed method of support to any excavation adjacent to adjoining properties, or the road reserve. The proposed method of support is to be designed and certified by an appropriately qualified and practising Structural Engineer, or equivalent.
- Proposed protection for Council and adjoining properties.
- The location and operation of any on site crane.

The CTMP shall be prepared in accordance with relevant sections of Australian Standard 1742 – “Manual of Uniform Traffic Control Devices”, RMS’ Manual – “Traffic Control at Work Sites”.

All fees and charges associated with the review of this plan is to be in accordance with Council’s Schedule of Fees and Charges and are to be paid at the time that the Construction Traffic Management Plan is submitted.

A copy of the approved CTMP must be kept on-site at all times while work is being carried out. The development is to be undertaken in accordance with the Construction Traffic Management Plan approved by Northern Beaches Council Traffic Team.

Reason: To ensure public safety and minimise any impacts to the adjoining pedestrian and vehicular traffic systems.

CONDITIONS THAT MUST BE ADDRESSED PRIOR TO ANY COMMENCEMENT

17. Tree Removal Within the Property

This consent approves the removal of existing prescribed trees on the subject site as listed below:

- a) T7, T71, T72, T74 (*Corymbia maculata*), T10 (*Corymbia gummifera*), T60 (*Magnolia soulangeana*), T64, T81, T120 (*Callistemon viminalis*), T75 (*Livistona australis*), T77 (*Banksia integrifolia*), T79 (*Backhousia citriodora*), T82 (*Yucca*), and T121 (*Acacia decurrens*),
- b) a qualified AQF level 5 Arborist shall identify these trees on site and tag or mark prior to removal.

Reason: To enable authorised development works.

18. Work Zones and Permits

Prior to commencement of the associated works, the applicant shall obtain a Work Zone Permit where it is proposed to reserve an area of road pavement for the parking of vehicles associated with a construction site.

A separate application is required with a Traffic Guidance Scheme for standing of construction vehicles in a trafficable lane.

Reason: To ensure Work zones are monitored and installed correctly.

19. Land Contamination Assessment

After demolition and removal of site features, sampling and testing of soils beneath the buildings, loading dock and concrete handstand area at twelve additional sampling locations is to be undertaken by a suitably qualified consultant to satisfy sampling requirements for a site area of 1.018 hectares (ha) as per NSW EPA (2022) Contaminated Land Guidelines - Sampling Design part 1 - application.

In addition to this, sampling locations are required to be provided directly adjacent, and within the footprint of the incinerator.

If contamination is identified, a suitably qualified Environmental Consultant is to provide appropriate remediation and validation, if required. Any remediation recommended by the consultant is to be implemented into the development.

Reason: To ensure the effective management of potential land contamination.

DURING BUILDING WORK

20. Project Arborist

A Project Arborist with minimum AQF Level 5 in arboriculture shall be engaged to provide tree protection measures in accordance with AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment.

The Project Arborist shall be in attendance and supervise all works for the proposed footpath near existing trees T3 (Liquidamber street tree), and within the property T4, T5, T8, T9 (Corymbia maculata), including: advice on final location and construction methodology. The Project Arborist shall provide certification to the Certifier that all tree protection measures under AS4970-2009 have been satisfied, and the recommendations listed for the protection of the existing tree(s) have been carried out satisfactorily to ensure no impact to the health of the tree(s). Photographic documentation of the condition of all trees to be retained shall be recorded, including at commencement, during the works and at completion.

Note: Any potential impact to trees as assessed by the Project Arborist will require redesign of any approved component to ensure existing trees upon the subject site and adjoining properties are preserved and shall be the subject of a modification application where applicable.

Reason: Tree protection.

21. Protection of Existing Street Trees

All existing street trees in the vicinity of the works shall be retained during all construction stages, and the street tree(s) fronting the development site shall be protected by tree protection fencing in accordance with Section 4 of AS4970-2009 Protection of trees on development sites. As a minimum the tree protection fencing for street tree(s) fronting the development site shall consist of standard 2.4m panel length to four sides and in accordance with Australian Standard 4687-2007 Temporary Fencing and Hoardings, unless otherwise directed by an Arborist with minimum AQF Level 5 in arboriculture. All fencing shall be located to allow for unrestricted and safe pedestrian access upon the road verge.

All street trees within the road verge are protected under Northern Beaches Council

development control plans, except where Council's written consent for removal has been obtained. The felling, lopping, topping, ringbarking, or removal of any tree(s) is prohibited. No excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of street trees.

Reason: Street tree protection.

22. **Tree and Vegetation Protection**

a) Existing trees and vegetation shall be retained and protected, including:

- i) all trees within the site not approved for removal,
- ii) all trees and vegetation located on adjoining properties,
- iii) all trees and vegetation within the road reserve.

b) Tree protection shall be undertaken as follows:

- i) tree protection shall be in accordance with AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment,
- ii) existing ground levels shall be maintained within the tree protection zone of trees to be retained, unless authorised by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iii) removal of existing tree roots at or >25mm (Ø) diameter is not permitted without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture,
- iv) no excavated material, building material storage, site facilities, nor landscape materials are to be placed within the canopy dripline of trees and other vegetation required to be retained,
- v) structures are to bridge tree roots at or >25mm (Ø) diameter unless directed by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture on site,
- vi) excavation for stormwater lines and all other utility services is not permitted within the tree protection zone, without consultation with an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture including advice on root protection measures,
- vii) should either or all of v) or vi) occur during site establishment and construction works, an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall provide recommendations for tree protection measures. Details including photographic evidence of works undertaken shall be submitted by the Arborist/Project Arborist to the Principal Certifier,
- viii) any temporary access to, or location of scaffolding within the tree protection zone of a protected tree or any other tree to be retained during the construction works is to be undertaken using the protection measures specified in sections 4.5.3 and 4.5.6 of AS4970-2009 Protection of trees on development sites,
- ix) the activities listed in section 4.2 of AS4970-2009 Protection of trees on development sites, shall not occur within the tree protection zone of any tree on the lot or any tree on an adjoining site,
- x) tree pruning from within the site to enable approved works shall not exceed 10% of any tree canopy, and shall be in accordance with AS4373-2007 Pruning of amenity trees,
- xi) the tree protection measures specified in this clause must: i) be in place before work commences on the site, and ii) be maintained in good condition during the construction period, and iii) remain in place for the duration of the construction works.

The Principal Certifier must ensure that:

c) The arboricultural works listed in a) and b) are undertaken as compliant to AS4970-2009 Protection of trees on development sites, and any recommendations of an approved Arboricultural Impact Assessment and/or Project Arborist as applicable.

Reason: Tree and vegetation protection.

23. Compliance with Ecologist's Recommendations – During Construction

All impact mitigation measures specified in the approved Flora and Fauna Assessment Report/Biodiversity Development Assessment Report are to be implemented at the appropriate stage of development.

Compliance with these measures is to be certified by the Project Ecologist in writing to the Principal Certifier prior to issue of any Occupation Certificate.

Reason: To confirm compliance with wildlife and habitat protection/replacement measures.

24. Wildlife Protection

If construction activity associated with this development results in injury or displacement of a native mammal, bird, reptile or amphibian, a licensed wildlife rescue and rehabilitation organisation must be contacted for advice.

Reason: To protect native wildlife.

25. Protection of Habitat Features

All natural landscape features, including any rock outcrops, native vegetation and/or watercourses, are to remain undisturbed during the construction works, except where affected by necessary works detailed on approved plans.

Reason: To protect wildlife habitat.

26. Road Reserve

The applicant shall ensure the public footways and roadways adjacent to the site are maintained in a safe condition at all times during the course of the work.

Reason: Public safety.

27. Installation and Maintenance of Sediment and Erosion Controls

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004) and the Erosion and Sediment Control Plan prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: Protection of the receiving environment.

28. Staff and Contractor Parking

The applicant is to make provision for parking for all construction staff and contractors for the duration of the project. All Staff and Contractors are to use the available on-site parking.

Reason: To ensure minimum impact of construction activity on local parking amenity.

29. Implementation of Construction Traffic Management Plan

All works and construction activities are to be undertaken in accordance with the approved

Construction Traffic Management Plan (CTMP). All controls in the CTMP must be maintained at all times and all traffic management control must be undertaken by personnel having appropriate TfNSW accreditation. Should the implementation or effectiveness of the CTMP be impacted by surrounding major development not encompassed in the approved CTMP, the CTMP measures and controls are to be revised accordingly and submitted to Council for approval. A copy of the approved CTMP is to be kept onsite at all times and made available to Council on request.

Reason: To ensure compliance of the developer/builder in adhering to the Construction Traffic Management procedures agreed and are held liable to the conditions of consent.

30. **Ongoing Management**

Traffic management procedures and systems must be in place and practised during the course of the project to ensure safety and minimise the effect on adjoining pedestrian and vehicular traffic systems. These procedures and systems must be in accordance with AS 1742.3 2009 Manual of Uniform Traffic Control Devices and Council's Development Control Plans.

Note: A plan of traffic management is to be submitted to and approved by the Principal Certifier.

The applicant shall be responsible in ensuring that the road reserve remains in a serviceable state during the course of the demolition and building works.

Reason: To ensure pedestrian safety and continued efficient network operation.

31. **Traffic Control During Road Works**

Lighting, fencing, traffic control and advanced warning signs shall be provided for the protection of the works and for the safety and convenience of the public and others in accordance with RMS Traffic Control At Work Sites Manual (<http://www.rms.nsw.gov.au/business-industry/partners-suppliers/documents/technical-manuals/tcws-version-4/tcwsv4i2.pdf>) and to the satisfaction of the Roads Authority. Traffic movement in both directions on public roads, and vehicular access to private properties is to be maintained at all times during the works

Reason: Public Safety.

32. **Site filling - Virgin Excavated Natural Material (VENM)**

Where site fill material is necessary, fill materials must:

1. Be Virgin Excavated Natural Material (VENM) only, as defined in The Protection of the Environment Operations Act 1997.
2. Be free of slag, hazardous, contaminated, putrescibles, toxic or radioactive excavated material and soil, rock or similar material. Putrescibles and non-putrescibles solid waste (including demolition material) is not permitted.

The Applicant shall provide certification by a N.A.T.A. approved laboratory to the Principal Certifier for approval prior to importation of material.

Reason: To ensure protection of the natural environment.

33. Waste Management During Development

The reuse, recycling or disposal of waste during works must be done generally in accordance with the Waste Management Plan for this development.

Details demonstrating compliance must be submitted to the Principal Certifier.

Reason: To ensure demolition and construction waste is recycled or reused and to limit landfill.

34. Removal of Excavated Material

Any materials to be excavated and removed from the site is to be classified prior to disposal at an appropriately licensed landfill, or potential re-use at other sites, in accordance with:

Waste Classification Guidelines Part 1: Classifying Waste (NSW EPA, 2014);

NSW EPA resource recovery exemptions and orders under the Protection of the Environment Operations (Waste) Regulation 2014; or

Protection of the Environment Operations Act 1997 (POEO Act), for Virgin Excavated Natural Material (VENM).

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the fill being imported to the site.

Reason: To ensure that excavated material/fill is of an acceptable standard.

35. Importation of Fill

Any imported soil (fill) must be assessed by a qualified environmental consultant prior to importation, to ensure suitability for the proposed use. In addition, the imported fill must, not contain asbestos and ash, be free of unusual odour, not be discoloured and not be acid sulphate soil or potential acid sulphate soil. The imported fill should either be virgin excavated natural material (VENM) or excavated natural material (ENM).

Prior to the importation of any landfill material onto the site, a waste classification report is to be prepared in accordance with the NSW Environment Protection Authority Guidelines, the report shall state in an end statement that the fill material is suitable for the proposed use on the land.

Details demonstrating compliance are to be submitted to the Principal Certifier.

Reason: For protection of environment.

ON-GOING CONDITIONS THAT MUST BE COMPLIED WITH AT ALL TIMES

36. Landscape Maintenance

If any landscape materials/components or planting under this consent fails, they are to be replaced with similar materials/components. Trees, shrubs and groundcovers required to be planted under this consent are to be mulched, watered and fertilised as required at the time of planting. If any tree, shrub or groundcover required to be planted under this consent fails, they are to be replaced with similar species to maintain the landscape theme and be generally in accordance with the approved Landscape Plans and any conditions of consent.

Reason: To maintain local environmental amenity.

37. Compliance with Ecologist's Recommendations – Ongoing

All impact mitigation measures specified in the approved Flora and Fauna Assessment Report/Biodiversity Development Assessment Report are to be implemented at the appropriate stage of development.

Successful establishment/initiation of ongoing biodiversity measures is to be certified by the Project Ecologist in writing to the Principal Certifier prior to issue of any Occupation Certificate.

Reason: To confirm compliance with wildlife and habitat protection/replacement measures.

38. Protection of Habitat Features

All natural landscape features, including any rock outcrops, native vegetation, soil and/or watercourses, are to remain undisturbed except where affected by necessary works detailed on approved plans.

Reason: To protect wildlife habitat.

39. Traffic Management

Traffic management procedures and systems must be in place and practised during the course of the project to ensure safety and minimise the effect on adjoining pedestrian and vehicular traffic systems. These procedures and systems must be in accordance with AS 1742.3 2009 Manual of Uniform Traffic Control Devices and Council's Development Control Plans.

Note: A plan of traffic management is to be submitted to and approved by the Principal Certifier.

Reason: To ensure pedestrian safety and continued efficient network operation.

40. Positive Covenant for Council and Contractor Indemnity

A positive covenant shall be created on the title of the land prior to the issue of a Subdivision Certificate requiring the proprietor of the land to provide access to the waste storage facilities. The terms of the positive covenant are to be prepared to Council's requirements, (Appendix E of the Waste Management Guidelines), at the applicant's expense and endorsed by Council prior to lodgement with NSW Land Registry Services. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

Reason: To ensure ongoing access for servicing of waste facilities.

41. Geotechnical Recommendations

Any ongoing recommendations of the risk assessment required to manage the hazards identified in the Geotechnical Report referenced in Condition 1 of this consent are to be maintained and adhered to for the life of the development.

Reason: To ensure geotechnical risk is mitigated appropriately.

BEFORE ISSUE OF A SUBDIVISION CERTIFICATE

42. Nest Boxes

A minimum of 2 nest boxes are to be installed in retained trees / throughout the trees within areas of retained native vegetation / on the site as recommended in the approved Flora and Fauna Assessment (Ecological Consultants Australia Pty Ltd TA Kingfisher Urban Ecology and Wetlands, September 2024).

Nest boxes must be attached in accordance with industry best practice (e.g. expandable tree

sensitive methods).

Written certification of compliance is to be prepared by the Project Ecologist and submitted to the Certifier prior to issue of the Subdivision Works Certificate.

Reason: To maintain wildlife habitat.

43. Amendment to Landscape Plan

The submitted Landscape Plan is to be amended in accordance with the following:

- The submitted landscape plan will have to be consistent with the Duffys Forest Ecological community determination as established within the submitted Flora and Fauna Assessment.

Compliance with these measures is to be certified by the Project Ecologist in writing to the Principal Certifier prior to issue of any Occupation Certificate.

Reason: To maintain and replace habitat on the site.

44. Compliance with Ecologist's Recommendations – Post Construction

All impact mitigation measures specified in the approved Flora and Fauna Assessment Report/Biodiversity Development Assessment Report are to be implemented at the appropriate stage of development.

Written and photographic evidence of compliance is to be prepared by the Project Ecologist and provided to the Principal Certifier prior to issue of a Subdivision Certificate.

Reason: To confirm compliance with wildlife and habitat protection/replacement measures.

45. Boundary Identification Survey

A boundary identification survey, prepared by a Registered Surveyor, shall be provided in respect of the subject site.

The plans submitted for the Construction Certificate are to accurately reflect the property boundaries as shown on the boundary identification survey, with setbacks between the property boundaries and the approved works consistent with those nominated on the Approved Plans of this consent.

Details demonstrating compliance are to be submitted to the Certifier prior to the issue of a Subdivision Works Certificate.

Reason: To ensure all approved works are constructed within the subject site and in a manner anticipated by the development consent.

46. Authorisation of Legal Documentation Required for Waste Services

The original completed request form (NSW Land Registry Services standard form 13PC) must be submitted to Council for authorisation prior to the issue of the Subdivision Certificate. A copy of the work-as-executed plan (details overdrawn on a copy of the approved plan) must be included with the above submission. A Compliance Certificate, issued by the Certifying Authority, shall also be provided in the submission to Council.

If Council is to issue the Compliance Certificate for these works, the fee is to be in accordance with Council's Fees and Charges.

Reason: To create encumbrances on the land.

47. Neighbourhood Management Statement for Waste Services

Where a development proposes the creation of a neighbourhood scheme, the Neighbourhood Management Statement shall include wording in relation to the provision of waste services in accordance with Appendix D of Northern Beaches Council Waste Management Guidelines

Reason: To ensure ongoing access for servicing of waste facilities.

48. Positive Covenant for On-site Stormwater Detention

A positive covenant (under the provisions of Section 88B of the Conveyancing Act 1919) is to be created on the final plan of subdivision and accompanying 88B instrument, requiring the proprietor of the land to maintain the on-site stormwater detention structure in accordance with the standard requirements of Council. The terms of the positive covenant are to be prepared to Council's standard requirements, which are available from Northern Beaches Council. Northern Beaches Council shall be nominated as the sole authority empowered to release, vary or modify such covenant.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Subdivision Certificate

Reason: To ensure ongoing maintenance of the on-site detention system.

49. Provision of Services for Subdivision

The applicant is to ensure all services including water, electricity, telephone and gas (or arrangements for a suitable alternative to gas) are provided, located and certified by a registered surveyor on a copy of the final plan of subdivision.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Subdivision Certificate.

Reason: To ensure that utility services have been provided to the newly created lots.

50. Right of Carriageway

The Applicant shall create a right of carriageway (under the provisions of Section 88B of the Conveyancing Act) on the final plan of subdivision and accompanying 88B instrument, to include all vehicular access and manoeuvring areas.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Subdivision Certificate.

Reason: Council's subdivision standards and the statutory requirements of the Conveyancing Act 1919.

51. Restriction as to User (On-site Stormwater Detention)

The Applicant shall create a restriction as to user (under the provisions of Section 88B of the Conveyancing Act) on the final plan of subdivision and accompanying 88B instrument for the on-site stormwater detention system, restricting any alteration or additions to the system. The terms of such restriction are to be prepared to Council's standard requirements. Council shall be nominated as the party to release, vary or modify such restriction.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the

issue of the Subdivision Certificate.

Reason: To ensure no modification to the on-site stormwater detention structure without Council's approval.

52. Certification of Road and Drainage works and the On-site Stormwater Detention System (New Subdivision)

A Compliance Certificate is to be submitted by a suitably qualified Civil Engineer, who has membership to Engineers Australia, National Engineers Register (NER) or Professionals Australia (RPENG) and has appropriate experience and competence in the related field confirming to the satisfaction of the Principal Certifier that the stormwater drainage system and on-site stormwater detention system, road construction works, retaining walls and associated works have been constructed in accordance with the approved subdivision works certificate and relevant conditions of Development Consent. The Subdivision Certificate will not be released until this certification has been submitted and the Principal Certifier has confirmed that this condition has been satisfied.

Reason: To ensure the Engineering works have been built in accordance with the approved plans.

53. Sydney Water Compliance Certification

The Applicant shall submit a Section 73 Compliance Certificate under the Sydney Water Act 1994 issued by Sydney Water Corporation. Application must be made through an authorised Water Servicing Co-ordinator. Please refer to the Building Developing and Plumbing section of the web site www.sydneywater.com.au <<http://www.sydneywater.com.au>> then refer to "Water Servicing Coordinator" under "Developing Your Land" or telephone 13 20 92 for assistance.

Following application a "Notice of Requirements" will advise of water and sewer infrastructure to be built and fees to be paid. Please make early contact with the coordinator, since building of water/sewer infrastructure can be time consuming and may impact on other services and building, driveway or landscape design.

Details demonstrating compliance are to be submitted to the Principal Certifier prior to the issue of the Subdivision Certificate.

Reason: To ensure compliance with the statutory requirements of Sydney Water.

54. Subdivision Certificate Application

The Applicant shall submit a Subdivision Certificate Application to Council, which is to include a completed Subdivision Certificate form and checklist, a final plan of subdivision prepared in accordance with the requirements of the Conveyancing Act 1919, the final plan of subdivision and all relevant documents including electronic copies. This documentation is to be submitted to Council prior to the issue of the Subdivision Certificate. All plans of survey are to show connections to at least two Survey Co-ordination Permanent Marks. The fee payable is to be in accordance with Council's fees and charges.

Reason: Statutory requirement of the Conveyancing Act 1919.

55. Stormwater Treatment Measures Operation and Management Plan

An Operation and Maintenance Plan is to be prepared to ensure the proposed stormwater treatment measures remain effective.

The Plan must be attached or referred to in the Neighbourhood Management Statement and contain the following:

1. Detail on the stormwater treatment measures:
 - a) Work as executed drawings
 - b) Intent of the stormwater treatment measures including modelled pollutant removal rates
 - c) Site detail showing catchment for each device
 - d) Vegetation species list associated with each type of vegetated stormwater treatment measure
 - e) Impervious area restrictions to maintain the water balance for the site
 - f) Funding arrangements for the maintenance of all stormwater treatment measures
 - g) Identification of maintenance and management responsibilities
 - h) Maintenance and emergency contact information

2. Maintenance schedule and procedure - establishment period of one year following commissioning of the stormwater treatment measure:

- a) Activity description, and duration and frequency of visits

Additionally for vegetated devices:

- b) Monitoring and assessment to achieve an 80 percent survival rate for plantings
 - c) Management of weeds, pests and erosion, with weed and sediment cover limited to a maximum of 5 percent of the total area of the stormwater treatment measure

3. Maintenance schedule and procedure - ongoing

- a) Activity description, and duration and frequency of visits
 - b) Routine maintenance requirements
 - c) Work Health and Safety requirements
 - d) Waste management and disposal
 - e) Traffic control (if required)
 - f) Renewal, decommissioning and replacement timelines and activities of all stormwater treatment measures (please note that a DA may be required if an alternative stormwater treatment measure is proposed)
 - g) Requirements for inspection and maintenance records, noting that these records are required to be maintained and made available to Council upon request.

Details demonstrating compliance shall be submitted to Council prior to the release of the Subdivision Certificate.

Reason: Protection of the receiving environment.

56. **Erosion and Sediment Control Plan**

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points

- Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifier for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment.

57. Preparation of the Neighbourhood Management Statement

The Neighbourhood management Statement is to contain by laws to cover the maintenance and renewal of the following infrastructure:

- 1) The on site stormwater detention system and water quality control devices including all filter cartridges and pit inserts.
 - 2) Collection of waste by Council in accordance with Council's standard by law wording.
 - 3) All other infrastructure including the street lighting, the internal road, drainage and footpaths.
- The Neighbourhood management Statement is to be submitted to Council for review and approval prior to release of the subdivision certificate.

Reason: For the ongoing maintenance of the community association infrastructure.

58. Detailed Design of Stormwater Treatment Measures - Major

A certificate from a Civil Engineer, stating that the stormwater treatment measures have been designed in accordance with the Enspire Solutions Pty Ltd plans, report listed below and Council's Water Management for Development Policy.

- Civil Engineering and Stormwater Report, project 230057, dated 08 March 2024
- 230057-00-DA-C05.02 dated 7/03/2024
- 230057-00-DA-C05.01 dated 7/03/2024
- 230057-00-DA-C20.21 dated 7/03/2024
- 230057-00-DA-C18.01 dated 7/03/2024
- 230057-00-DA-C17.01 dated 7/03/2024

The certificate shall be submitted to the Certifier prior to the release of the Construction Certificate.

Reason: Protection of the receiving environment.

59. Positive Covenant, Restriction as to User and Registration of Encumbrances for Stormwater Treatment Measures

A positive covenant shall be created on the title of the land requiring the proprietor of the land to maintain the stormwater treatment measures in accordance with the standard requirements of Council, the manufacturer and as required by the Stormwater Treatment Measures Operation and Maintenance Plan.

A restriction as to user shall be created on the title over the stormwater treatment measures, restricting any alteration to the measures.

The terms of the positive covenant and restriction as to user are to be prepared to Council's standard requirements (available from Council) at the applicant's expense and endorsed by the Northern Beaches Council's delegate prior to lodgement with the Department of Lands. Northern Beaches Council shall be nominated as the party to release, vary or modify such covenant.

A copy of the certificate of title demonstrating the creation of the positive covenant and restriction as to user is to be submitted to the Principal Certifier prior to the issue of the Subdivision Certificate.

Reason: To identify encumbrances on land, ensure ongoing maintenance, and ensure modification to the stormwater treatment measures is not carried out without Council's approval.

60. Certification for the Installation of Stormwater Treatment Measures

A certificate from a Civil Engineer, who has membership to Engineers Australia and the National Engineers Register must be provided, stating that the stormwater treatment measures have been installed in accordance with the certificate approved plans. The certificate must confirm that stormwater treatment measures are completed, online, in good condition and are not impacted by sediment.

The certificate shall be submitted to the Principal Certifier prior to the release of an Subdivision Certificate.

Reason: Protection of the receiving environment.

61. Stormwater Treatment Measures Operation and Maintenance Plan

An Operation and Maintenance Plan is to be prepared to ensure the proposed stormwater treatment measures remain effective.

The Plan must be attached to the Positive Covenant (and the community or strata management statement if applicable) and contain the following:

1. Detail on the stormwater treatment measures:
 - a) Work as executed drawings
 - b) Intent of the stormwater treatment measures including modelled pollutant removal rates
 - c) Site detail showing catchment for each device
 - d) Vegetation species list associated with each type of vegetated stormwater treatment measure
 - e) Impervious area restrictions to maintain the water balance for the site
 - f) Funding arrangements for the maintenance of all stormwater treatment measures
 - g) Identification of maintenance and management responsibilities
 - h) Maintenance and emergency contact information
2. Maintenance schedule and procedure - establishment period of one year following commissioning of the stormwater treatment measure:
 - a) Activity description, and duration and frequency of visitsAdditionally for vegetated devices:
 - b) Monitoring and assessment to achieve an 80 percent survival rate for plantings
 - c) Management of weeds, pests and erosion, with weed and sediment cover limited to a maximum of 5 percent of the total area of the stormwater

treatment measure

3. Maintenance schedule and procedure - ongoing
 - a) Activity description, and duration and frequency of visits
 - b) Routine maintenance requirements
 - c) Work Health and Safety requirements
 - d) Waste management and disposal
 - e) Traffic control (if required)
 - f) Renewal, decommissioning and replacement timelines and activities of all stormwater treatment measures (please note that a DA may be required if an alternative stormwater treatment measure is proposed)
 - g) Requirements for inspection and maintenance records, noting that these records are required to be maintained and made available to Council upon request.

Details demonstrating compliance shall be submitted to the Principal Certifier prior to the release of the Subdivision Certificate.

Reason: Protection of the receiving environment.

62. Works as Executed Drawings - Stormwater Treatment Measures

Works as Executed Drawings for the stormwater treatment measures must be prepared in accordance with Council's Guideline for Preparing Works as Executed Data for Council Stormwater Assets.

The drawings shall be submitted to the Principal Certifier prior to the release of the Subdivision Certificate.

Reason: Protection of the receiving environment.

63. Landscape Completion

Landscape works are to be implemented in accordance with the approved Landscape Plans, and inclusive of the following conditions:

- a) landscape works are to be contained within the legal property boundaries,
- b) tree, shrub and groundcover planting shall be installed as indicated on the approved Landscape Plans, unless otherwise imposed by conditions,
- c) all tree planting shall be pre-ordered to equal the container size as nominated in the Plant Schedule; planted into a prepared planting hole 1m x 1m x 600mm depth generally, backfilled with a sandy loam mix or approved similar, mulched to 75mm depth minimum and maintained, and watered until established; and shall be located at least 3.0 metres from buildings or more, at least 1.5 metres from common boundaries; and located within garden bed,
- d) mass planting shall be installed in accordance with the approved Landscape Plans.

Prior to the release of a Subdivision Certificate, details (from a landscape architect, landscape designer or qualified horticulturalist) shall be submitted to the Principal Certifier, certifying that the landscape works have been completed in accordance with any conditions of consent.

Reason: Environmental amenity.

64. Condition of retained Vegetation

Prior to the release of a Subdivision Certificate, a report prepared by an Arborist/Project Arborist with minimum AQF Level 5 in arboriculture shall be submitted to the Principal Certifier, assessing the health and impact on all existing trees required to be retained, including the following information:

- a) compliance to any Arborist recommendations for tree protection generally and during excavation works,
- b) extent of damage sustained by vegetation as a result of the construction works,
- c) any subsequent remedial works required to ensure the long term retention of the vegetation.

Reason: Tree and vegetation protection.

65. Engagement of Project Ecologist

A Project Ecologist is to be employed for the duration of the approved works to ensure all biodiversity protection measures are carried out in accordance with **XX** Report (reference).

The Project Ecologist must have one of the following memberships / accreditation:

- Practising member of the NSW Ecological Consultants Association (<https://www.ecansw.org.au/find-a-consultant/>) OR
- Biodiversity Assessment Method Accredited Assessor under the relevant legislation (<https://customer.lmbc.nsw.gov.au/assessment/AccreditedAssessor>)

Evidence of engagement of the Project Ecologist is to be provided to the Certifier prior to issue of the Subdivision Works Certificate.

Reason: To protect native vegetation and wildlife.

66. No Clearing of Vegetation and no weeds

Unless otherwise exempt, no vegetation is to be cleared prior to issue of a Subdivision Works Certificate.

No Priority or environmental weeds (as specified in the Northern Beaches Local Weed Management Plan) are to be imported on to the site prior to or during construction works.

All Priority weeds (as specified in the Northern Beaches Local Weed Management Plan) within the development footprint are to be removed using an appropriate control method.

Details demonstrating compliance are to be submitted to the Certifier prior to issue of Subdivision Works Certificate.

Reason: To protect native vegetation.

67. Vehicular Swept Paths and Kerb Splay

A swept path analysis is required for a widened road design which enables both Council's 10.5m waste vehicle and a B99 design vehicle to pass simultaneously on the curved section of road.

Vehicular manoeuvring paths must also be provided to demonstrate Council's 10.5m waste vehicle can enter or depart the site onto Warili Road in a forward direction without encroaching on required car parking spaces. Details demonstrating compliance with this condition must be submitted to the Council's Traffic team prior to the issue of the Subdivision Certificate.

A plan showing the modified kerb splay to enable Council's 10.5m waste vehicle to enter and exit the internal access road onto Warili Road shall be submitted to and approved by Council

prior to the issue of the Construction Certificate.

Reason: To ensure access for the development site and compliance with Australian Standards relating to manoeuvring and parking of vehicles and to ensure vehicles do not impact the kerb and gutter and cause ongoing maintenance concerns.

General advisory notes

This consent contains the conditions imposed by the consent authority which are to be complied with when carrying out the approved development. It is an offence under the EP&A Act to carry out development that is not in accordance with this consent. However, this consent is not an exhaustive list of all obligations which may relate to the carrying out of the development under the EP&A Act, EP&A Regulation and other legislation.

Some of these additional obligations are set out in the Conditions of development consent: advisory notes, which has been uploaded to the NSW Planning Portal as a separate document. The consent should be read together with the advisory notes to ensure the development is carried out lawfully.

Dictionary

The following terms have the following meanings for the purpose of this determination (except where the context clearly indicates otherwise):

Approved plans and documents means the plans and documents endorsed by the consent authority, a copy of which is included in this notice of determination.

AS means Australian Standard published by Standards Australia International Limited and means the current standard which applies at the time the consent is issued.

Building work means any physical activity involved in the erection of a building.

Certifier means a council or a person that is registered to carry out certification work under the Building and Development Certifiers Act 2018.

Construction certificate means a certificate to the effect that building work completed in accordance with specified plans and specifications or standards will comply with the requirements of the EP&A Regulation and Environmental Planning and Assessment (Development Certification and Fire Safety) Regulation 2021.

Council means Northern Beaches Council.

Court means the Land and Environment Court of NSW.

EPA means the NSW Environment Protection Authority.

EP&A Act means the Environmental Planning and Assessment Act 1979.

EP&A Regulation means the Environmental Planning and Assessment Regulation 2021.

Independent Planning Commission means Independent Planning Commission of New South Wales constituted by section 2.7 of the EP&A Act.

Local planning panel means Northern Beaches Local Planning Panel.

Occupation certificate means a certificate that authorises the occupation and use of a new building or a change of building use for an existing building in accordance with this consent.

Principal certifier means the certifier appointed as the principal certifier for building work or subdivision work under section 6.6(1) or 6.12(1) of the EP&A Act respectively.

Site work means any work that is physically carried out on the land to which the development the subject of this development consent is to be carried out, including but not limited to building work, subdivision work, demolition work, clearing of vegetation or remediation work.

Stormwater drainage system means all works and facilities relating to: the collection of stormwater, the reuse of stormwater, the detention of stormwater, the controlled release of stormwater, and connections to easements and public stormwater systems.

Strata certificate means a certificate in the approved form issued under Part 4 of the Strata Schemes Development Act 2015 that authorises the registration of a strata plan, strata plan of subdivision or notice of conversion.

Subdivision certificate means a certificate that authorises the registration of a plan of subdivision under Part 23 of the Conveyancing Act 1919.

Subdivision works certificate means a certificate to the effect that subdivision work completed in accordance with specified plans and specifications will comply with the requirements of the EP&A Regulation.

Sydney district or regional planning panel means Sydney North Planning Panel. Some of these additional obligations are set out in the Conditions of development consent: advisory notes, which has been uploaded to the NSW Planning Portal as a separate document. The consent should be read together with the Conditions of development consent: advisory notes to ensure the development is carried out lawfully.

The approved development must be carried out in accordance with the conditions of this consent. It is an offence under the EP&A Act to carry out development that is not in accordance with this consent.