

Natural Environment Referral Response - Riparian

Application Number:	DA2021/2555
Date:	23/02/2022
To:	Kye Miles
Land to be developed (Address):	Lot 1 DP 499733 , 80 Hudson Parade CLAREVILLE NSW 2107

Reasons for referral

This application seeks consent for the following:

- All Development Applications on land, and located within 40 metres of land, containing a watercourse, or
- All Development Applications on land containing a wetland, or located within 100m of land containing a wetland,
- All Development Applications on land that is mapped as "DCP Map Waterways and Riparian Land".

And as such, Council's Natural Environment Unit officers are required to consider the likely impacts on drainage regimes.

Officer comments

This application has been assessed against relevant legislation and policy relating to waterways, riparian areas, and groundwater. The site abuts Pittwater estuary and as such the development must not significantly impact on the biophysical, hydrological or ecological integrity of the estuary, or the quantity and quality of surface and ground water flows that it receives. The development must not significantly affect seagrass beds or other estuarine habitats.

The development is unlikely to have a significantly impact on the biophysical, hydrological or ecological integrity of the estuary, or the quantity and quality of surface and ground water flows that it receives.

The proposal is therefore supported.

Note: Should you have any concerns with the referral comments above, please discuss these with the Responsible Officer.

Recommended Natural Environment Conditions:

CONDITIONS TO BE SATISFIED PRIOR TO THE ISSUE OF THE CONSTRUCTION CERTIFICATE

Erosion and Sediment Control Plan

An Erosion and Sediment Control Plan (ESCP) shall be prepared by an appropriately qualified person and implemented onsite prior to commencement. The ESCP must meet the requirements outlined in the Landcom publication Managing Urban Stormwater: Soils and Construction - Volume 1, 4th Edition (2004). The ESCP must include the following as a minimum:

- Site Boundaries and contours
- Approximate location of trees and other vegetation, showing items for removal or retention (consistent with any other plans attached to the application)
- Location of site access, proposed roads and other impervious areas (e.g. parking areas and site facilities)
- Existing and proposed drainage patterns with stormwater discharge points
- Locations and methods of all erosion and sediment controls that must include sediment fences, stabilised site access, materials and waste stockpiles locations, location of any stormwater pits on the site and how they are going to be protected.
- North point and scale.

Details demonstrating compliance are to be submitted to the Certifying Authority for approval prior to the issue of the Construction Certificate.

Reason: Protection of the receiving environment.

CONDITIONS TO BE COMPLIED WITH DURING DEMOLITION AND BUILDING WORK

Installation and Maintenance of Sediment and Erosion Controls

Council proactively regulates construction sites for sediment management.

Sediment and erosion controls must be installed in accordance with Landcom's 'Managing Urban Stormwater: Soils and Construction' (2004), and the Erosion and Sediment Control Plan prepared by Stephen Crosby & Associates Pty Ltd, prior to commencement of any other works on site.

Erosion and sediment controls are to be adequately maintained and monitored at all times, particularly after periods of rain, and shall remain in proper operation until all development activities have been completed and vegetation cover has been re-established across 70 percent of the site, and the remaining areas have been stabilised with ongoing measures such as jute mesh or matting.

Reason: Protection of the receiving environment.

Aquatic sediment management

Environmental safeguards (e.g. silt curtains) are to be used during construction to prevent the escape of turbid plumes into the aquatic environment. The silt curtains must be carefully placed and secured to ensure they do not drag over any nearby seagrass beds.

The safeguards must be regularly maintained and removed once the works are completed.

Reason: Protection of seagrass.

Use of equipment and vessels in the vicinity of seagrass

No equipment is to be placed on any seagrass beds.

Inshore infrastructure for mooring vessels and plant must be used where suitable. Where mooring lines or cables are required, they shall be suitably buoyed prior to laying and kept buoyed once laid to prevent cable drag or swing damage (scalping). Where this is impractical, contractors should use a floating rope.

Vessels must have adequate clearance over seagrass beds, including allowance for tidal movement, swell/wind wave heights and vessel propulsion.

Reason: Protection of seagrass.

CONDITIONS WHICH MUST BE COMPLIED WITH PRIOR TO THE ISSUE OF THE OCCUPATION CERTIFICATE

Removal of Sediment and Erosion Controls

Before demobilising from the site and once vegetation cover has been re-established across 70 percent of the site, the applicant is to remove all temporary sediment and erosion controls.

Any area of the site that requires ongoing stabilisation must have jute mesh or matting incorporated into the revegetated area. Mulch may be used on slopes subject to sheet flow with a gradient of no more than 1 metre in height for every 3 horizontal metres. Mulch must be laid to a depth of 50-100mm. If using mulch within two metres of the top of bank of a waterway, coir logs or similar must be placed at the downslope edge of the mulched area to prevent migration of the mulch to the waterway.

Details demonstrating compliance are to be submitted to the Principal Certifying Authority for approval prior to the issue of the Occupation Certificate.

Reason: Protection of the receiving environment