GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER

FORM NO. 1 – To be submitted with Development Application

| | | Dovolonment Ar | nlication for | | | \neg |
|----------------------------|---------------------------------|---|---|--------------------------------|--|--------------------------------|
| | | Development Ap | oplication for | | Name of Applicant | |
| | | Address of site | 1 Kanir | nbla Crescei | nt, Bilgola Plateau | |
| Decla | ration | made by geotechi | nical engineer or e | ngineering g | eologist or coastal engineer (where applicable) as part o | of a geotechni |
| | | | | | report | |
| ı, <u> </u> | | Ben White (insert name) | on behalf of | | Geotechnical Group Pty Ltd Trading or Company Name) | |
| | | , | | (. | Taking or company manney | |
| on this | _ | | 01/22 | _ | I am a geotechnical engineer or engineering geologist or coastal | - |
| | | | | | r - 2009 and I am authorised by the above organisation/compan rent professional indemnity policy of at least \$2million. | y to issue |
| lease ⊴ | Prep | | | | w in accordance with the Australia Geomechanics Society's Land Risk Management Policy for Pittwater - 2009 | dslide Risk |
| ₃ | Aust | | | | cal Report referenced below has been prepared in accordance we ment Guidelines (AGS 2007) and the Geotechnical Risk Managor | |
|] | para for t | agraph 6.0 of the G he proposed develo | eotechnical Risk Ma | nagement Police iance with the | in detail and have carried out a risk assessment in accordant olicy for Pittwater - 2009. I confirm the results of the risk asse e Geotechnical Risk Management Policy fro Pittwater - 2009 bject site. | essment |
|] | only | involves Minor Deve | elopment/Alterations t | hat do not req | eration in detail and am of the opinion that the Development Appl juire a Detailed Geotechnical Risk Assessment and hence my re for Pittwater – 2009 requirements for Minor Development/Altera | port is in |
|] | Prov | vided the coastal pro | cess and coastal force | es analysis for | r inclusion in the Geotechnical Report | |
| G | eotech | nical Report Detail | s: | | | |
| | Rep | ort Title: Geotechnic | al Report 1 Kanimbl | a Crescent, I | Bilgola Plateau | |
| | Rep | ort Date: 31/01/22 | | | | |
| | Auth | or : BEN WHITE | | | | |
| | Auth | or's Company/Orga | nisation : WHITE GEO | OTECHNICAL | GROUP PTY LTD | |
| | Docume | entation which relat | te to or are relied up | on in report p | preparation: | |
| | | | | - | de Risk Management March 2007. | |
| | Wh | ite Geotechni | cal Group com | pany arch | nives. | |
| pplica ie pro iken a | tion for posed o as at le | this site and will be development have b | relied on by Pittwate been adequately addi ess otherwise stated | er Council as ressed to ach | abovementioned site is to be submitted in support of a D the basis for ensuring that the Geotechnical Risk Managemen nieve an "Acceptable Risk Management" level for the life of the in the Report and that reasonable and practical measures | it aspects of ne structure, |
| | | | Signature | Relu | d. | |
| | | | Name | Ben White | 9 | |
| | | | Chartered Profession | nal Status | MScGEOLAusIMM CP GEOL | |
| | | | Membership No. | 222757 | | |
| | | | Company | White Ge | eotechnical Group Pty Ltd | |

GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1(a) - Checklist of Requirements for Geotechnical Risk Management Report for Development Application

| | • |
|-------------------|---|
| | Development Application for |
| | Name of Applicant |
| | Address of site 1 Kanimbla Crescent, Bilgola Plateau |
| Report. | lowing checklist covers the minimum requirements to be addressed in a Geotechnical Risk Management Geotechnical This checklist is to accompany the Geotechnical Report and its certification (Form No. 1). Geotechnical Report Details: |
| | Report Title: Geotechnical Report 1 Kanimbla Crescent, Bilgola Plateau |
| | Report Date: 31/01/22 |
| | Author: BEN WHITE |
| | Author's Company/Organisation WHITE GEOTECHNICAL GROUP PTY LTD |
| Please ⊠ | mark appropriate box Comprehensive site mapping conducted 29/04/21. |
| \boxtimes | (date) Mapping details presented on contoured site plan with geomorphic mapping to a minimum scale of 1:200 (as appropriate) Subsurface investigation required No Justification |
| | ☐ Yes Date conducted 29/04/21. Geotechnical model developed and reported as an inferred subsurface type-section Geotechnical hazards identified ☐ Above the site ☐ On the site ☐ Below the site |
| | ☐ Beside the site Geotechnical hazards described and reported Risk assessment conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 ☐ Consequence analysis ☐ Frequency analysis |
| | Risk calculation Risk assessment for property conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 Risk assessment for loss of life conducted in accordance with the Geotechnical Risk Management Policy for Pittwater - 2009 Assessed risks have been compared to "Acceptable Risk Management" criteria as defined in the Geotechnical Risk Management Policy for Pittwater - 2009 |
| | Opinion has been provided that the design can achieve the "Acceptable Risk Management" criteria provided that the specified conditions are achieved. Design Life Adopted: |
| _ | ⊠100 years □Other specify |
| \boxtimes | Geotechnical Conditions to be applied to all four phases as described in the Geotechnical Risk Management Policy for Pittwater – 2009 have been specified |
| | Additional action to remove risk where reasonable and practical have been identified and included in the report. Risk Assessment within Bushfire Asset Protection Zone |
| the geo Manage | vare that Pittwater Council will rely on the Geotechnical Report, to which this checklist applies, as the basis for ensuring that otechnical risk management aspects of the proposal have been adequately addressed to achieve an "Acceptable Risk ement" level for the life of the structure, taken as at least 100 years unless otherwise stated, and justified in the Report and that able and practical measures have been identified to remove foreseeable risk. |
| | Signature # ## Signature |
| | Name Ben White |
| | Chartered Professional Status MScGEOLAusIMM CP GEOL |
| | Membership No. 222757 |

Company

White Geotechnical Group Pty Ltd



J3391A. 31st January, 2022. Page 1.

GEOTECHNICAL INVESTIGATION:

Additions and Alterations at 1 Kanimbla Crescent, Bilgola Plateau

1. Proposed Development

- **1.1** Construct a first and second floor extension on the downhill side of the house.
- **1.2** Construct a new first floor addition to the E side of the house.
- **1.3** Construct a new carport on the uphill side of the property.
- 1.4 Construct a staircase on the W side of the property by excavating to a maximum depth of ~2.0m.
- 1.5 Construct a storeroom in the void-space underneath the house by excavating to a maximum depth of ~1.5m.
- 1.6 Construct a level lawn area on the downhill side of the property by filling to a maximum depth of ~1.2m.
- 1.7 Various other internal alterations and additions.
- **1.8** Details of the proposed development are shown on 12 drawings prepared by Lein Architects, project number 2108, drawings numbered A01 and A12, dated 13th January, 2022.

2. Site Description

- **2.1** The site was inspected on the 29th April, 2021.
- 2.2 This residential property is on the low side of the road and has a SE aspect. The block is located on the moderate to steeply graded upper reaches of a hillslope. The slope falls across the property at angles averaging ~19°.



J3391A. 31st January, 2022. Page 2.

2.3 At the road frontage, a gravel driveway runs to a parking area on the uphill side of the property (Photo 1). The slope between the road frontage and the house has been terraced with a series of stable stack rock retaining walls, reaching ~1.5m high (Photo 2). One of these walls was observed to be partially supported directly onto outcropping Medium Strength Sandstone (Photo 3). The part two-storey brick house is supported on brick walls and steel posts. The supporting walls show no significant signs of movement and the supporting posts stand vertical (Photo 4). A stable stack rock wall reaching ~1.2m high and lining the E neighbouring boundary supports the cut for the neighbouring property. A moderate to steeply sloping lawn falls to the lower boundary. A large dislodged sandstone joint block was observed to be sitting in a stable position on the slope under the W side of the house (Photo 6).

3. Geology

The Sydney 1:100 000 Geological sheet indicates the site is underlain by Hawkesbury Sandstone. It is described as a medium to coarse grained quartz sandstone with very minor shale and laminite lenses.

4. Subsurface Investigation

Six Dynamic Cone Penetrometer (DCP) tests were put down to determine the relative density of the overlying soil and the depth to bedrock. The locations of the tests are shown on the site plan attached. It should be noted that a level of caution should be applied when interpreting DCP test results. The test will not pass through hard buried objects so in some instances it can be difficult to determine whether refusal has occurred on an obstruction in the profile or on the natural rock surface. This is not expected to be an issue for the testing on this site. However, excavation and foundation budgets should always allow for the possibility that the interpreted ground conditions in this report vary from those encountered during excavations. See the appended "Important information about your report" for a more comprehensive explanation. The results are as follows:



J3391A. 31st January, 2022. Page 3.

| | DCP T | EST RESULTS | 6 – Dynamic | Cone Penet | rometer | |
|------------------------|------------------------------|---------------------------|-------------------------------|----------------------------|----------------------------|-------------------------------|
| Equipment: 9 | kg hammer, 51 | 0mm drop, conic | cal tip. | | Standard: AS12 | 89.6.3.2 - 1997 |
| Depth(m) Blows/0.3m | DCP 1 (~RL99.6) | DCP 2 (~RL101.4) | DCP 3 (~RL98.6) | DCP 4 (~RL102.1) | DCP 5 (~RL105.6) | DCP 6 (~RL107.2) |
| 0.0 to 0.3 | 17 | 5 | 1F | Rock | 3 | 9F |
| 0.3 to 0.6 | # | # | F | Exposed at | 3 | F |
| 0.6 to 0.9 | | | 4 | Surface | 3 | 4 |
| 0.9 to 1.2 | | | 60 | | 10 | # |
| 1.2 to 1.5 | | | # | | 9 | |
| 1.5 to 1.8 | | | | | 25 | |
| 1.8 to 2.1 | | | | | # | |
| | Refusal on Rock @ 0.2m | Refusal on Rock @ 0.1m | Refusal on Rock @ 1.15m | | Refusal on Rock @ 1.8m | Refusal on Rock @ 0.95m |

#refusal/end of test. F=DCP fell after being struck showing little resistance through all or part of the interval.

DCP Notes:

- DCP1 Refusal on rock @ 0.2m, DCP bouncing off rock surface, clean dry tip.
- DCP2 Refusal on rock @ 0.1m, DCP bouncing off rock surface, white impact dust on dry tip.
- DCP3 Refusal on rock @ 1.15m, DCP bouncing off rock surface, dark brown muddy sand streaking down length of DCP, orange and red mottled sandy clay on wet tip.
- DCP4 Rock exposed at the surface.
- DCP5 Refusal on rock @ 1.8m, DCP bouncing off rock surface, white impact dust on dry tip.
- DCP6 Refusal on rock @ 0.95m, DCP bouncing off rock surface, white impact dust on dry tip.

5. Geological Observations/Interpretation

The surface features of the block are controlled by the outcropping and underlying sandstone bedrock that steps down the property forming sub-horizontal benches between the steps. Where the grade is steeper, the steps are larger and the benches narrower. Where the slope eases, the opposite is true. Where the rock is not exposed, it is overlain by sandy soils and sandy clays that fill the bench step formation. Filling has been placed above and below the



J3391A. 31st January, 2022.

Page 4.

house for landscaping. In the test locations, the depth to rock ranged between 0.1 to 1.8m

below the current surface, being slightly deeper due to the presence of fill and the stepped

nature of the underlying bedrock. The outcropping sandstone on the property is estimated to

be medium strength or better and similar strength rock is expected to underlie the entire site.

See Type Section attached for a diagrammatical representation of the expected ground

materials.

6. Groundwater

Normal ground water seepage is expected to move over the buried surface of the rock and

through the cracks. Due to the slope and elevation of the block, the water table is expected

to be many metres below the base of the proposed excavation.

7. Surface Water

No evidence of significant surface flows were observed on the property during the inspection.

Normal sheet wash from the slope above will be intercepted by the street drainage system

for Kanimbla Crescent above.

8. Geotechnical Hazards and Risk Analysis

No geotechnical hazards were observed above or beside the property. The moderate to

steeply graded slope that falls across the property and continues below is a potential hazard

(Hazard One). The vibrations from the proposed excavation are a potential hazard

(Hazard Two). The proposed excavations are a potential hazard until retaining walls are in

place (Hazard Three). The proposed excavation undercutting the footings for the house is a

potential hazard (Hazard Four). The proposed fill for the lawn area is a potential hazard until

retaining walls are in place (Hazard Five).



J3391A. 31st January, 2022. Page 5.

Risk Analysis Summary

| HAZARDS | Hazard One | Hazard Two |
|-----------------------------|---|--|
| TYPE | The moderate to steep slope that falls across the property and continues below failing and impacting on the proposed works. | The vibrations produced during the proposed excavation impacting on the surrounding structures. |
| LIKELIHOOD | 'Unlikely' (10 ⁻⁴) | 'Possible' (10 ⁻³) |
| CONSEQUENCES TO PROPERTY | 'Medium' (15%) | 'Medium' (15%) |
| RISK TO PROPERTY | 'Low' (2 x 10 ⁻⁵) | 'Moderate' (2 x 10 ⁻⁴) |
| RISK TO LIFE | 9.1 x 10 ⁻⁷ /annum | 5.3 x 10 ⁻⁷ /annum |
| COMMENTS | This level of risk is 'ACCEPTABLE'. | This level of risk to life and property is 'UNACCEPTABLE'. To move risk to 'ACCEPTABLE' levels, the recommendations in Section 12 are to be followed. |

RISK ANALYSIS CONTINUED ON THE NEXT PAGE



J3391A. 31st January, 2022. Page 6.

| HAZARDS | Hazard Three | Hazard Four | Hazard Five |
|--------------------------|------------------------------------|------------------------------------|------------------------------------|
| TYPE | The excavations for | | |
| | the stairs and | | |
| | storeroom (up to a | The proposed | The proposed fill (up |
| | maximum depth of | excavation | to a maximum height |
| | ~2.0m) collapsing | undercutting the | of 1.2m) failing and |
| | onto the work site | footings of the house | impacting the |
| | before retaining | causing failure. | proposed works. |
| | structures are in | | |
| | place. | | |
| LIKELIHOOD | 'Possible' (10 ⁻³) | 'Possible' (10 ⁻³) | 'Possible' (10 ⁻³) |
| CONSEQUENCES TO PROPERTY | 'Medium' (15%) | 'Medium' (35%) | 'Medium' (15%) |
| RISK TO PROPERTY | 'Moderate' (2 x 10 ⁻⁴) | 'Moderate' (2 x 10 ⁻⁴) | 'Moderate' (2 x 10 ⁻⁴) |
| RISK TO LIFE | 8.3 x 10 ⁻⁶ /annum | 5.3 x 10 ⁻⁵ /annum | 6.0 x 10 ⁻⁵ /annum |
| COMMENTS | This level of risk to | This level of risk to life | This level of risk to |
| | property is | and property is | property is |
| | 'TOLERABLE'. To move | 'UNACCEPTABLE'. To | 'UNACCEPTABLE'. To |
| | risk to 'ACCEPTABLE' | move risk to | move risk to |
| | levels, the | 'ACCEPTABLE' levels, | 'ACCEPTABLE' levels |
| | recommendations in | the recommendations | the recommendations |
| | Section 12 and 13 are | in Section 13 are to be | in Section 14 are to be |
| | to be followed. | followed. | followed. |

(See Aust. Geomech. Jnl. Mar 2007 Vol. 42 No 1, for full explanation of terms)

9. Suitability of the Proposed Development for the Site

The proposed development is suitable for the site. No geotechnical hazards will be created by the completion of the proposed development provided it is carried out in accordance with the requirements of this report and good engineering and building practice.

10. Stormwater

The fall is away from the street. The stormwater engineer is to refer to council stormwater policy for suitable options for stormwater disposal.



J3391A.

31st January, 2022.

Page 7.

11. Excavations

An excavation to a maximum depth of $^{\sim}2.0\text{m}$ is required for the proposed staircase on the W

side of the property. Another excavation to a maximum depth of ~1.5m is required to create

a level platform for the storeroom.

These excavations are expected to be through soils and clay with Medium Strength Rock

expected at depths of between ~0.1m and ~1.8m below the current surface in the area of the

proposed works.

It is envisaged that excavations through sandy soils and sand can be carried out with an

excavator and bucket, and excavations through rock will require grinding or rock sawing and

breaking.

12. Vibrations

Possible vibrations generated during excavations through soil and clay will be below the

threshold limit for building damage. It is expected that most of the excavation will be through

Medium Strength Sandstone or better.

Excavations through rock should be carried out to minimise the potential to cause vibration

damage to the subject house and neighbouring property to the W. Allowing ~0.5m for

backwall drainage, the setbacks are as follows:

Flush with the existing walls of the subject house.

• ~0.5m from the W common boundary.

~1.5m from the W neighbouring carport.

Close controls by the contractor over rock excavation are recommended so excessive

vibrations are not generated.

Excavation methods are to be used that limit peak particle velocity to 8mm/sec at the subject

walls. Vibration monitoring will be required to verify this is achieved. The vibration monitoring



J3391A. 31st January, 2022. Page 8.

equipment must include a light/alarm so the operator knows if vibration limits have been exceeded. It also must log and record vibrations throughout the excavation works.

In Medium Strength Rock or better techniques to minimise vibration transmission will be required. These include:

- Rock sawing the excavation perimeter to at least 1.0m deep prior to any rock breaking with hammers, keeping the saw cuts below the rock to be broken throughout the excavation process.
- Limiting rock hammer size.
- Rock hammering in short bursts so vibrations do not amplify.
- Rock breaking with the hammer angled away from the nearby sensitive structures.
- Creating additional saw breaks in the rock where vibration limits are exceeded.

13. Excavation Support Requirements

The excavation for the proposed staircase on the W side of the property will reach a maximum depth of ~2.0m. The excavation for the proposed store room will reach a maximum depth of ~1.5m. Allowing for 0.5m of backwall drainage, the setbacks are as follows:

- Flush with the existing walls of the subject house.
- ~0.5m from the W common boundary.
- ~1.5m from the W neighbouring carport.

As the deepest part of the excavation is ~3.0m from the neighbouring carport, only the existing walls of the subject house and the W common boundary will lie within the zone of influence of the proposed excavations. In this instance, the zone of influence is the area above a theoretical 45° line from the top of Medium Strength Rock, towards the surrounding structures and boundaries.



J3391A. 31st January, 2022.

Page 9.

Where the walls of the subject house fall within the zone of influence of the excavation, exploration pits along the walls will need to be put down by the builder to determine the

foundation depth and material. These are to be inspected by the geotechnical consultant.

If the foundations are found to be supported on rock or extend below the zone of influence

of the proposed excavation, the excavation may commence. If they are not, the supporting

walls will need to be underpinned to rock or to below the zone of influence of the cut prior to

the excavation commencing. See the site plan attached for the minimum extent of the

required exploration pits/underpinning.

Underpinning is to follow the underpinning sequence 'hit one miss two'. Under no

circumstances is the bulk excavation to be taken to the edges of the walls and then

underpinned. Underpins are to be constructed from drives that should be proportioned

according to footing type and size. Allowances are to be made for drainage through the

underpinning to prevent a build-up of hydrostatic pressure. Underpins that are not designed

as retaining walls are to be supported by retaining walls. The void between the retaining walls

and the underpinning is to be filled with free-draining material such as gravel.

During the excavation for the staircase, the geotechnical consultant is to inspect the

excavation to confirm the stability of the cut to go flush with the footings.

Where the W common boundary falls within the zone of influence of the excavation, the cut

faces through soil and clay will require the installation of shoring installed before excavation

through rock commences. Staged temporary or permanent support installed along the W side

as the excavation is progressed in spans not less than 2.0m horizontally is one suitable shoring

technique in this location. The support is to be designed by the structural engineer in

consultation with the geotechnical consultant. The temporary support is to remain in place

until the retaining walls are built. See site plan attached for extent of minimum required

shoring.



J3391A. 31st January, 2022.

Page 10.

The remaining sides of the excavation are expected to stand at near-vertical angles for a short

period of time until the retaining walls are in place, provided they are kept from becoming

saturated.

Upslope runoff is to be diverted from the cut faces by sandbag mounds or other diversion

works. Unsupported cut batters through soil, and clay are to be covered to prevent access of

water in wet weather and loss of moisture in dry weather. The covers are to be tied down

with metal pegs or other suitable fixtures so they can't blow off in a storm. The materials and

labour to construct the retaining walls are to be organised so on completion of the excavation

they can be constructed as soon as possible. The excavation is to be carried out during a dry

period. No excavations are to commence if heavy or prolonged rainfall is forecast.

Upon completion of the excavation, it is recommended all cut faces be supported with

retaining walls to prevent any potential future movement of joint blocks in the cut face that

can occur over time, when unfavourable jointing is obscured behind the excavation face.

Additionally, retaining walls will help control seepage and to prevent minor erosion and

sediment movement. Excavation spoil may be used for landscaping on site.

All excavation spoil is to be removed from site following the current Environmental Protection

Agency (EPA) waste classification guidelines.

14. Fill

A fill to create a level lawn area is to be placed on the downhill side of the property. No fills

are to be laid until retaining walls are in place. The fill will reach a maximum depth of between

~1.2m. The surface is to be prepared before any fills are laid by removing any organic matter

and topsoil. Fills are to be laid in a loose thickness not exceeding 0.3m before being

moderately compacted. Tracking the machine over the loose fill in 1 to 2 passes should be

sufficient. Immediately behind the retaining walls (say to 1.5m), the fills are to be compacted

with light weight equipment such as a hand-held plate compactor so as not to damage the



J3391A. 31st January, 2022. Page 11.

retaining walls. Where light weight equipment is used, fills are to be laid in a loose thickness not exceeding 0.2m before being compacted. No structures are to be supported on fill.

15. Retaining Walls

For cantilever or singly-propped retaining walls, it is suggested the design be based on a triangular pressure distribution of lateral pressures using the parameters shown in Table 1.

Table 1 – Likely Earth Pressures for Retaining Walls

| | Earth Pressure Coefficients | | | | | |
|---|-----------------------------|-------------------------|--------------|----------|--|--|
| Unit | Unit weight (kN/m³) | 'Active' K _a | 'At Rest' K₀ | Passive | | |
| Fill, Sandy Soil, and Residual Clay | 20 | 0.40 | 0.55 | N/A | | |
| Medium Strength Sandstone | 24 | 0.00 | 0.01 | 4000 kPa | | |

For rock classes refer to Pells et al "Design Loadings for Foundations on Shale and Sandstone in the Sydney Region". Australian Geomechanics Journal 1978.

It is to be noted that the earth pressures in Table 1 assume a level surface above the structure, do not account for any surcharge loads, and assume retaining walls are fully drained. Rock strength and relevant earth pressure coefficients are to be confirmed on site by the geotechnical consultant.

It should be noted that passive pressure is an ultimate value and should have an appropriate safety factor applied. No passive resistance should be assumed for the top 0.4m to account for any disturbance from the excavation.

All retaining walls are to have sufficient back-wall drainage and be backfilled immediately behind the structure with free-draining material (such as gravel). This material is to be



J3391A.

31st January, 2022.

Page 12.

wrapped in a non-woven Geotextile fabric (i.e., Bidim A34 or similar), to prevent the drainage

from becoming clogged with silt and clay. If no back-wall drainage is installed in retaining

walls, the likely hydrostatic pressures are to be accounted for in the structural design.

16. Foundations

Due to the steep grade of the slope below the location of the proposed extensions, piers

potted at least 0.3m into Medium Strength Sandstone are suitable footings for the proposed

extensions to the house. This material is expected at depths up to a maximum of ~1.2m below

the current surface. Where footings are over an exposed sloping rock surface, they may be

supported off level pads cut into the rock.

Due to the presence of fill and a downslope retaining wall, the proposed carport is to be

supported off piers or pads taken to Medium Strength Sandstone. This material is expected

at a maximum depth of ~1.0m below the current surface.

The plans show a soldier pile wall is to be constructed to support the proposed fill on the

downhill side of the property. This retaining wall is to be embedded into the underlying

Medium Strength Sandstone. Construction of a soldier pile wall embedded into rock will

require a mini piling rig or similar capable of drilling through Medium to High Strength Rock.

It is to be noted that a standard domestic excavator is not able to drill through Medium

Strength Rock and is not suitable for this job. This material is expected at a depth of between

~0.2m and ~1.1m below the current surface.

A maximum allowable bearing pressure of 1000kPa can be assumed for footings on Medium

Strength Sandstone.

Naturally occurring vertical cracks (known as joints) commonly occur in sandstone. These are

generally filled with soil and are the natural seepage paths through the rock. They can extend

to depths of several metres and are usually relatively narrow but can range between 0.1 to

0.8m wide. If a footing falls over a joint in the rock, the construction process is simplified if,



J3391A. 31st January, 2022.

Page 13.

with the approval of the structural engineer, the joint can be spanned or, alternatively, the

footing can be repositioned so it does not fall over the joint.

NOTE: If the contractor is unsure of the footing material required, it is more cost effective to

get the geotechnical consultant on site at the start of the footing excavation to advise on

footing depth and material. This mostly prevents unnecessary over-excavation in clay like

shaly rock but can be valuable in all types of geology.

17. Geotechnical Review

The structural plans are to be checked and certified by the geotechnical engineer as being in

accordance with the geotechnical recommendations. On completion a Form 2B will be issued.

This form is required for the Construction Certificate to proceed.

18. Inspections

The client and builder are to familiarise themselves with the following required inspections

as well as council geotechnical policy. We cannot provide geotechnical certification for the

owners or the regulating authorities if the following inspections have not been carried out

during the construction process.

• During the excavation for the staircase, the geotechnical consultant is to inspect the

excavation to confirm the stability of the cut to go flush with the footings.

• All footings are to be inspected and approved by the geotechnical consultant while

the excavation equipment is still onsite and before steel reinforcing is placed or

concrete is poured.

White Geotechnical Group Pty Ltd.

ditte

Ben White M.Sc. Geol., AusIMM., CP GEOL.

No. 222757

Engineering Geologist.



J3391A. 31st January, 2022. Page 14.





Photo 2



J3391A. 31st January, 2022. Page 15.







Photo 4



J3391A. 31st January, 2022. Page 16.







Photo 6




J3391A. 31st January, 2022. Page 17.


Important Information about Your Report

It should be noted that Geotechnical Reports are documents that build a picture of the subsurface conditions from the observation of surface features and testing carried out at specific points on the site. The spacing and location of the test points can be limited by the location of existing structures on the site or by budget and time constraints of the client. Additionally, the test themselves, although chosen for their suitability for the particular project, have their own limiting factors. The testing gives accurate information at the location of the test, within the confines of the test's capability. A geological interpretation or model is developed by joining these test points using all available data and drawing on previous experience of the geotechnical consultant. Even the most experienced practitioners cannot determine every possible feature or change that may lie below the earth. All of the subsurface features can only be known when they are revealed by excavation. As such, a Geotechnical report can be considered an interpretive document. It is based on factual data but also on opinion and judgement that comes with a level of uncertainty. This information is provided to help explain the nature and limitations of your report.

With this in mind, the following points are to be noted:

- If upon the commencement of the works the subsurface ground or ground water conditions prove different from those described in this report, it is advisable to contact White Geotechnical Group immediately, as problems relating to the ground works phase of construction are far easier and less costly to overcome if they are addressed early.
- If this report is used by other professionals during the design or construction process, any questions should be directed to White Geotechnical Group as only we understand the full methodology behind the report's conclusions.
- The report addresses issues relating to your specific design and site. If the proposed project design changes, aspects of the report may no longer apply. Contact White Geotechnical if this occurs.
- This report should not be applied to any other project other than that outlined in section 1.0.
- This report is to be read in full and should not have sections removed or included in other documents as this can result in misinterpretation of the data by others.
- It is common for the design and construction process to be adapted as it progresses (sometimes
 to suit the previous experience of the contractors involved). If alternative design and construction
 processes are required to those described in this report, contact White Geotechnical Group. We
 are familiar with a variety of techniques to reduce risk and can advise if your proposed methods
 are suitable for the site conditions.





TYPE SECTION – Diagrammatical Interpretation of expected Ground Materials NEW CLEARSTOREY ROOF NEW METAL ROOF ON TIMBER ROOF FRAME NEW PORTICO ROOF OVER ENTRANCE PORTICO **ENTRY** LIVING BED 1 1800MM HIGH PRIVACY SCREEN GROUND FLOOR RL 106.130 FC CLADDING ON TIMBER STUD BED 3 ED 2 STORE ROOM . OSD TANK SECTION A NEW PROPOSED CLEARSTOREY WINDOW EXISTING ROOF NEW PITCHED ROOF OVER KITCHEN EXTENSION FCL RL 108.870 SKYLIGHTS ON SKILLION ROOF LAUNDRY CARPORT O **Expected Ground Materials** FC CLADDING ON -NEW BRICK TIMBER STUD FRAME EXTENSION Fill GROUND FLOOR RL 106.130 Topsoil NEW STAIRCASE Sandy Clay – Firm to Stiff EXISTING BALCONY Hawkesbury Sandstone - Medium Strength STORE ROOM O LOWER GROUND RL 102.960 SECTION B

Drafting Services Provided by

LIENARCHITECTS

Ph: 0447 711 977 simon@ilenarchitects.com.au

GENERAL NOTES

All dimensions in millimetres. Levels are in metres. Use figured dimensions only. Check dimensions on site. Do not scale off drawings.

This drawing is subject to copyright and must not be copy, used or reproduced without the consent of Planned Environment P/L.

| Rev. | Description | Date |
|------|---------------------|------------|
| 1 | EXISTING PLAN | 11.05.2021 |
| 2 | PRELIMINARY | 13.05.2021 |
| 3 | PRELIMINARY | 18.05.2021 |
| 4 | FOR COORDINATION | 19.05.2021 |
| 5 | FOR DA REVIEW | 24.05.2021 |
| Α | FOR DA SUBMISSION | 25.05.2021 |
| В | DA AMENDMENT REVIEW | 29.09.2021 |
| С | DA AMENDMENT | 07.10.2021 |
| D | DA AMENDMENT | 13.01.2022 |

Architect

PLANNED ENVIRONMENT P/L

JOHN WOOD

john@piannedenvironment.com Ph: 0418 246 809

PO BOX 150, GULGONG NSW 2852

Client

JOHN AND HELEN WOOD

Prole

ALTERATIONS AND ADDITIONS TO EXISTING DWELLING

Address

1 KANIMBLA CRES. BILGOLA PLATEAU NSW 2107 LOT 152 DP 29335


Sheet Name

SECTIONS

| Project no. | Sheet no. | Rev. |
|-------------|-----------|------|
| 2108 | A08 | D |
| | | |
| Scale | Date | |

DEVELOPMENT APPLICATION

EXAMPLES OF GOOD HILLSIDE PRACTICE



EXAMPLES OF POOR HILLSIDE PRACTICE

