
Sent: 9/05/2019 5:17:33 PM
Subject: RMS Response - DA2018/1924
Attachments: 20181211 - Report_-_Traffic.pdf; Warringah_Forest_PM_Existing & Future.jpg; Forest Way_PM Traffic Increases.jpg; northern-beaches-hospital-update-1601.pdf; 20190509 - RMS Response - Modeling for Forestway Shopping Centre.pdf;

	Luke Perry
	Northern Beaches Council

Dear Sir/Madam,

Please find attached Roads and Maritime Services response for the above.

RMS Reference: SYD18/01143/04 (A27302261)
Council Reference: DA2018/1924

Regards,

Amanda Broderick
Development Assessment Officer
Network Management | Journey Management
P: 8849 2391

www.rms.nsw.gov.au

Every journey matters

Roads and Maritime Services

Level 5/27 Argyle Street Parramatta NSW 2150

From: no_reply@northernbeaches.nsw.gov.au [mailto:no_reply@northernbeaches.nsw.gov.au]

Sent: Tuesday, 11 December 2018 8:07 AM

To: Development Sydney

Subject: Request for Services Progress - DA2018/1924

11 December 2018



Dear Sir/Madam



Request for Concurrence on Development Application to Maritime Service (Traffic Generating Development under SEPP Infrastructure)

Development Application No. DA2018/1924

Description: Alterations and Additions to the Forest Way shopping centre

Address: Forestway Shopping Centre Forest Way FRENCHS FOREST



The above application is deemed to require Concurrence.

To access the documentation please go to:



<https://eservices1.warringah.nsw.gov.au/ePlanning/live/Public/XC.Track/SearchApplication.aspx?id=processid>

Your referral response comments would be greatly appreciated within 21 days of the date of this letter.

Enquiries regarding this Development Application may be made to Luke Perry on 1300 434 434 Monday to Friday between 8.30am to 5.00pm or via email council@northernbeaches.nsw.gov.au .

Yours faithfully,



Luke Perry

Planner



This email is intended only for the addressee and may contain confidential information. If you receive this email in error please delete it and any attachments and notify the sender immediately by reply email. Transport for NSW takes all care to ensure that attachments are free from viruses or other defects.

Transport for NSW assume no liability for any loss, damage or other consequences which may arise from opening or using an attachment.



Consider the environment. Please don't print this e-mail unless really necessary.



**Transport
for NSW**

Before printing, please consider the environment

IMPORTANT NOTICE: This email and any attachment to it are intended only to be read or used by the named addressee. It is confidential and may contain legally privileged information. No confidentiality or privilege is waived or lost by any mistaken transmission to you. Roads and Maritime Services is not responsible for any unauthorised alterations to this email or attachment to it. Views expressed in this message are those of the individual sender, and are not necessarily the views of Roads and Maritime Services. If you receive this email in error, please immediately delete it from your system and notify the sender. You must not disclose, copy or use any part of this email if you are not the intended recipient.

INVESCO ASSET MANAGEMENT AUSTRALIA
(HOLDINGS) LIMITED

TRAFFIC REPORT FOR
PROPOSED EXPANSION OF
FORESTWAY SHOPPING CENTRE,
FRENCHS FOREST

DECEMBER 2018

COLSTON BUDD ROGERS & KAFES PTY LTD
ACN 002 334 296
Level 18 Tower A
Zenith Centre
821 Pacific Highway
CHATSWOOD NSW 2067

Telephone: (02) 9411 2411
Facsimile: (02) 9411 2422
Email: cbrk@cbrk.com.au

REF: 10857/2

TABLE OF CONTENTS

1. INTRODUCTION	1
2. EXISTING CONDITIONS.....	2
3. IMPLICATIONS OF PROPOSED DEVELOPMENT	7

ATTACHMENT A – PROPOSED FOREST WAY ACCESS

ATTACHMENT B – VEHICLE TURN PATHS

ATTACHMENT C – RUSSELL AVENUE TRAFFIC SIGNAL OPTION

I. INTRODUCTION

- I.1 Colston Budd Rogers and Kafes Pty Ltd has been commissioned by Invesco Asset Management Australia (Holdings) Limited to prepare a report examining the traffic implications of the proposed expansion of Forestway Shopping Centre, Frenchs Forest (the 'Site'). The Site location is shown in Figure I.
- I.2 The existing shopping centre comprises some 9577m² GLA with some 428 car parking spaces (including some 80 spaces within Sorlie Place). Access is provided from Forest Way, Russell Avenue, Grace Avenue and Sorlie Place. It is proposed to expand the shopping centre to some 21,593m² GLA and increase parking provision to some 841 spaces (including the 80 spaces in Sorlie Place). Access will be provided from Forest Way (with modifications to the existing pedestrian signals to allow for left in, left out and right out) and Grace Avenue.
- I.3 The traffic assessment takes into account the upgrades to the adjacent road network along Forest Way and Warringah Road as part of the Northern Beaches Hospital project. Prior to lodging the DA, discussions have been held with the RMS regarding appropriate access to the site and in particular the form of access on Forest Way. At the request of the RMS an alternative access arrangement has been investigated, left in/left out on Forest Way with the traffic signals at the intersection of Forest Way/Russell Avenue (with the existing pedestrian signals on Forest Way relocated to Russell Avenue).

I.4 This report assesses the implications of the proposed redevelopment of Forestway Shopping Centre through the following chapters:

- Chapter 2 - describing the existing conditions; and
- Chapter 3 - assessing the traffic implications of the proposed development.

2. EXISTING CONDITIONS

Site Location

2.1 Forestway Shopping Centre is located on the northern part of the block bounded by Forest Way to the east, Russell Avenue to the north and Grace Avenue to the west. Frenchs Forest Public School is located to the south of the Site. Surrounding land use is predominantly residential with some commercial development on the northern side of the Russell Avenue opposite the site. To the east of the Site are The Forest High School and the Northern Beaches Hospital.

2.2 The existing shopping centre comprises some 9,577m² GLA with some 428 car parking spaces (including some 80 spaces within Sorlie Place). Access is provided from Forest Way (left in only), Russell Avenue (all movements) and Grace Avenue (all movements). Service access to the centre is provided from Sorlie Place and Grace Avenue.

Road Location

2.3 The road network in the vicinity of the Site comprises Warringah Road, Forest Way, Grace Avenue, Russell Avenue, Naree Road and Sorlie Place. Warringah Road is an arterial road connecting the northern beaches with the lower north shore. In the vicinity of the Site it is a six lane divided road with additional turn lanes at major intersections. As part of the Northern Beaches Hospital project Warringah Road is being upgraded to improve traffic flow.

- 2.4 Forest Way is an arterial road connecting Warringah Road to the south with Mona Vale Road to the north. Adjacent to the Site, it is a six lane divided road. The intersection of Warringah Road and Forest Way is traffic signal controlled. Pedestrian signals are located on Forest Way, towards the southern frontage of the Site. These provide pedestrian access to the shopping centre and to the bus stops located either side of Forest Way. As part of the Northern Beaches Hospital project, Forest Way is being upgraded to improve traffic flow.
- 2.5 Russell Avenue is located along the northern boundary of the site and connects Forest Way to the east with Grace Avenue to the west. It provides for one traffic lane in each direction. With exception of the right turn out of Russell Avenue in the weekday morning peak period, all movements are permitted at the intersection of Russell Avenue and Forest Way. As part of the upgrade of Forest Way, a separate right turn bay into Russell Avenue has been provided on Forest Way. Due to the high traffic flows on Forest Way, there can be long delays in turning right out of Russell Avenue onto Forest Way.
- 2.6 Grace Avenue is located along the western boundary of the site and is a collector road providing access to development to the west of Forest Way. It provides for one traffic lane in each direction with kerb side parking located clear of intersections. The intersection of Grace Avenue and Russell Avenue is controlled by a single lane roundabout. To the south Fitzpatrick Street connects Grace Avenue to Warringah Road.
- 2.7 Sorlie Place is located to the south of Site's western frontage and provides an at-grade car park (some 80 spaces). Sorlie Place connects to Grace Avenue at two locations with one way traffic flow in a clockwise direction. Sorlie Place provides
-

service access to the existing shopping centre. During school set down and pick up periods the southern side of Sorlie Place is used as a school bus zone.

- 2.8 Naree Road is located to the north of the site and forms part of an east west road running parallel to Warringah Road. As part of the Northern Beaches Hospital Project, Naree Road is being upgraded from a two lane to a four lane road with traffic signals constructed at the intersection Naree Road and Forest Way.

Traffic Flows

- 2.9 Traffic generated by the proposed development will have its greatest effects during weekday afternoon and Saturday midday peak periods when it combines with other traffic on the surrounding road network. In order to gauge traffic conditions, traffic counts were undertaken at these times at the following intersections:

- Warringah Road/Forest Way (traffic signals);
- Forest Way/Russell Avenue (unsignalised);
- Forest Way/Naree Road (traffic signals);
- Grace Avenue/Russell Avenue (roundabout);
- Grace Avenue/Sorlie Place (unsignalised);
- Pedestrian signals on Forest Way; and
- Shopping centre access points on Forest Way, Russell Avenue and Grace Avenue (all unsignalised)

- 2.10 The results of the surveys are summarised in Table 2.1 and displayed in Figures 2 and 3.
-

Table 2.1: Existing Two-Way (Sum of Both Directions) Peak Hour Traffic Flows		
Road	Weekday Afternoon	Saturday Midday
Warringah Road		
– east of Forest Way	3705	3515
– west of Forest Way	3175	2775
Forest Way		
– north of Naree Road	3340	4165
– south of Naree Road	3120	4110
– south of Russell Avenue	2970	3815
– north of Warringah Road	3390	4020
Russell Avenue		
– east of Forest Way	510	465
– west of Grace Avenue	400	385
Grace Avenue		
– north of Russell Avenue	835	695
– south of Russell Avenue	835	650
– north of Sorlie Place (N)	845	610
– south of Sorlie Place (S)	830	595
Sorlie Place		
– entry	130	160
– exit	140	150
Naree Road		
– east of Forest Way	640	555
Site Accesses		
– Forest Way (entry only)	160	200
– Russell Avenue	285	355
– Grace Avenue	120	155

2.11 Table 2.1 reveals that:

- Warringah Road carried some 2,800 to 3,700 vehicles per hour two-way during the surveyed weekday afternoon and Saturday midday peak hours. Traffic flows were highest east of Forest Way. Traffic flows were highest during the weekday afternoon peak period;

- Forest Way carried some 3,000 to 4,200 vehicles per hour two-way during the surveyed weekday afternoon and Saturday midday peak hours. Traffic flows were highest during the Saturday peak hour;
- Russell Avenue carried some 400 to 500 vehicles per hour two-way during the surveyed weekday afternoon and Saturday midday peak hours. Traffic flows were highest west of Forest Way;
- Grace Avenue carried some 600 to 850 vehicles per hour two-way during the surveyed weekday afternoon and Saturday midday peak hours. Traffic flows were highest during the weekday afternoon peak hour;
- Sorlie Place carried some 150 vehicles per hour two-way during the surveyed weekday afternoon and Saturday midday peak hours;
- Naree Road carried some 550 to 650 vehicles per hour two-way during the surveyed weekday afternoon and Saturday midday peak hours. Traffic flows were highest during the weekday afternoon peak hour; and
- The existing shopping centre generated some 850 to 1020 vehicles per hour two-way during the surveyed weekday afternoon and Saturday midday peak hours. The highest traffic generation was during the Saturday peak hour.

2.12 Observations of traffic flows around the existing centre found that:

- traffic flows in Sorlie Place were generally associated with the shopping centre; and
-

- due to delays turning right out of Russell Avenue onto Forest Way, traffic departing the shopping centre and with a destination of Warringah Road (east) would use Grace Avenue (south) and Fitzpatrick Street to access Warringah Road.

Intersection Operations

- 2.13 The capacity of the road network is largely determined by the capacity of its intersections to cater for peak period traffic flows. The surveyed intersections have been analysed using the SIDRA 8 Network computer program for the traffic flows shown in Figures 2 and 3.
- 2.14 SIDRA 8 Network allows the analysis of a network of intersections and the interaction of traffic flows between intersections. It provides a number of performance measures. The most useful measure provided is average delay per vehicle expressed in seconds per vehicle.
- 2.15 Based on average delay per vehicle, SIDRA estimates the following levels of service (LOS):
- For traffic signals, the average delay per vehicle in seconds is calculated as $\text{delay}/(\text{all vehicles})$, for roundabouts the average delay per vehicle in seconds is selected for the movement with the highest average delay per vehicle, equivalent to the following LOS:
- | | | | |
|----------|---|-----|---|
| 0 to 14 | = | "A" | Good |
| 15 to 28 | = | "B" | Good with minimal delays and spare capacity |
| 29 to 42 | = | "C" | Satisfactory with spare capacity |
-

43 to 56	=	"D"	Satisfactory but operating near capacity
57 to 70	=	"E"	At capacity and incidents will cause excessive delays. Roundabouts require other control mode
>70	=	"F"	Unsatisfactory and requires additional capacity

- For give way and stop signs, the average delay per vehicle in seconds is selected from the movement with the highest average delay per vehicle, equivalent to following LOS:

0 to 14	=	"A"	Good
15 to 28	=	"B"	Acceptable delays and spare capacity
29 to 42	=	"C"	Satisfactory but accident study required
43 to 56	=	"D"	Near capacity and accident study required
57 to 70	=	"E"	At capacity and requires other control mode
>70	=	"F"	Unsatisfactory and requires other control mode

- 2.16 It should be noted that for roundabouts, give way and stop signs, in some circumstances, simply examining the highest individual average delay can be misleading. The size of the movement with the highest average delay per vehicle should also be taken into account. Thus, for example, an intersection where all movements are operating at a level of service A, except one which is at level of service E, may not necessarily define the intersection level of service as E if that movement is very small. That is, longer delays to a small number of vehicles may not justify upgrading an intersection unless a safety issue was also involved.

- 2.17 The analysis found that:

- The intersection of Warringah Road and Forest Way operates with average delays of less than 60 seconds per vehicle in the weekday afternoon peak
-
-

period. This represents level of service D/E at capacity. In the Saturday midday peak hour the intersection operates with average delays per vehicle of less than 35 seconds per vehicle. This represents level of service C, a satisfactory level of intersection operation;

- The intersection of Forest Way and Russell Avenue operates with average delays of less than 45 seconds per vehicle for the movements with the highest delay (right turn out of Russell Avenue) during the weekday afternoon and Saturday midday peak periods. This represents level of service C/D, satisfactory but near capacity. All other movements operate with average delays of less than 30 seconds per vehicle (level of service B/C or better). As noted previously, due to delays in turning right out of Russell Avenue in the peak periods, traffic from the shopping centre uses Grace Avenue/Fitzpatrick Street to access Warringah Road (eastbound);
 - The intersection of Forest Way and Naree Road operates with average delays of less than 20 seconds per vehicle during the weekday afternoon and Saturday midday peak periods. This represents level of service B, a reasonable level of service with spare capacity; and
 - The intersection of Grace Avenue and Russell Avenue operates with average delays of less than 15 seconds per during the weekday afternoon and Saturday midday peak periods. This represents level of service A/B, a good level of service.
-

Road Network Improvements

2.18 As part of the Northern Beaches Hospital project, a number of road network upgrades are under construction adjacent and in the vicinity of the Site. These include:

- Grade separation of the intersections of Warringah Road with Forest Way and Wakehurst Parkway;
- New pedestrian bridges over Warringah Road;
- Traffic signals at the intersection of Forest Way and Naree Road;
- Widening of Naree Road from two to four traffic lanes; and
- Improvements to the indented bus bays along Forest Way (both sides) adjacent to the shopping centre.

2.19 These works are at various stages of construction and will be completed prior to the opening of the redeveloped Shopping Centre. Thus the assessment of the traffic effects of the proposed redevelopment of the Shopping Centre takes into account these changes to the road network.

Public Transport

2.20 The site is adjacent to bus services which operate along Forest Way with bus stops located on Forest Way adjacent to the shopping centre. Bus services are provided by Forest Way Coaches. Services include:

- route 260: North Sydney to Terry Hills;
 - route 270: City QVB to Terry Hills;
 - route 271: City QVB to Belrose;
-

- route 274: City QVB to Davidson, via Frenchs Forest;
- route 278: Chatswood to Killarney Heights;
- route 279: Frenchs Forest to Chatswood;
- route 280: Chatswood to Warringah Mall;
- route 281: Chatswood to Davidson;
- route 282: Chatswood to Davidson and Belrose;
- route 283: Chatswood to Belrose
- route 284: Chatswood to Terry Hills and Duffys Forest; and
- route L70: City QVB to Terry Hills.

2.21 Pedestrian access to the bus services on the opposite side of Forest Way are provided by the existing pedestrian traffic signals on Forest Way.

2.22 In addition Sydney Buses operates a number of services along Warringah Road to the south with bus stops located to the east and west of Forest Way. Bus stops on the southern side of Warringah Road are accessible using the pedestrian bridge at the intersection with Forest Way. These services include:

- route 136: Manly to Chatswood (via Warringah Mall);
- route 169: City Wynyard to Manly, via Narraweena;

2.23 Thus the Site is highly accessible by public transport with numerous local and regional bus services connecting the Site with the local area and regional destinations such as Chatswood, Manly and the City.

3. IMPLICATIONS OF PROPOSED DEVELOPMENT

3.1 This chapter assesses the implications of the proposed development through the following sections.

- proposed development;
- public transport;
- pedestrians;
- parking provision;
- access and internal layout;
- servicing;
- traffic effects;
- discussions with RMS; and
- summary

Proposed Development

3.2 It is proposed the existing shopping centre will be redeveloped to provide some 21,593m² GLA. Demolition of the existing car park will provide new retail area across two levels. Parking (some 741 spaces) will be provided across a rooftop and two basement levels below and above the new retail areas. This excludes the existing 80 spaces in Sorlie Place. These parking levels will be interconnected by internal ramps with access from Forest Way (left in, left out and right out via modifications to the existing pedestrian signals) and Grace Avenue (all movements).

Public Transport

- 3.3 As previously discussed, the Site is close to bus services on Forest Way which provide local and regional connections. The site therefore has good access to public transport.
- 3.4 The proposed development will increase retail and employment densities close to these public transport services. The proposal would therefore strengthen the existing demand for these services.
- 3.5 The proposed development is therefore consistent with government objectives and the planning principles of:
- (a) improving accessibility to employment and services by walking, cycling, and public transport;
 - (b) improving the choice of transport and reducing dependence solely on cars for travel purposes;
 - (c) moderating growth in the demand for travel and the distances travelled, especially by car; and
 - (d) supporting the efficient and viable operation of public transport services.

Pedestrians

- 3.6 Pedestrian access will be provided to the redeveloped Shopping Centre from Forest Way, Russell Avenue and Sorlie Place. Pedestrian access will be maintained
-

across Forest Way with the pedestrian signals provided at the new site access on Forest Way.

Parking Provision

3.7 The parking requirements for different development types are set out in Warringah DCP 2011. For shopping centres, the DCP suggest the following rates:

- centres less than 10,000m² GLA – 6.1 space per 100m² GLA;
- centres 10,000m² to 20,000m² GLA – 5.6 spaces per 100m² GLA;
- centres 20,000m² to 30,000m² GLA – 4.3 spaces per 100m² GLA; and
- centres over 30,000m² – 4.1 spaces per 100m² GLA.

3.8 Using these rates the existing shopping centre would require 585 spaces and the expanded shopping centre 930 spaces.

3.9 Surveys of parking demand for the existing shopping centre (including parking in Sorlie Place) found a peak parking demand of 85% occupancy on a weekday and 75% occupancy on a Saturday. Thus peak surveyed parking demand was found to be 3.8 spaces per 100m².

3.10 As the surveyed parking demand is much lower than the parking required using the suggested DCP rates, application of the DCP rate for the redeveloped centre is considered inappropriate. Using the surveyed parking rate provides a more accurate baseline for estimating parking requirements for the redeveloped centre. The use of the surveyed parking rate as a baseline is also considered more appropriate than determining parking requirements for the various components of centre. This is because the various components of the centre will have peak

parking demands at different times. The surveyed parking rate takes this into account with the existing centre providing range of different uses.

3.11 Applying the surveyed parking rate to the redeveloped shopping centre results in a requirement for 820 spaces. However the DCP rates for shopping centres notes that as the size of the centre increases, parking required per 100m² decreases. The rate for a shopping centre of 22,000m² is some 30% less than the rate for shopping centre of some 9,500m². Being conservative and applying a reduction in the parking rate of 15%, (3.3 spaces per 100m²) the redeveloped shopping centre would require 720 spaces. This is satisfied by the provision of 741 spaces. In practice parking in Sorlie Place (80 spaces) and on Grace Avenue (some 20 spaces) is also used by shopping centre customers, thus increasing parking provision to some 841 spaces

3.12 Appropriate accessible, motorcycle and bicycle parking will be provided in accordance with Council requirements

Access and Internal Layout

3.13 Vehicular access to the redeveloped shopping centre is proposed from Forest Way and Grace Avenue. The existing pedestrian signals on Forest Way will be modified to provide traffic signal controlled access (left in, left out and right out) to/from the shopping centre. A concept design of the proposed Forest Way access has been prepared by TTW and is provided in Attachment A. The new signalized access will allow right turns out of the Site (as well as left in/left out). Right turn access from the shopping centre onto Forest Way is currently provided from Russell Avenue. As noted in Chapter 2, this movement can experience long delays in peak periods due to the high traffic flows on Forest Way and is not

permitted in the weekday morning peak period. Provision of direct right turn egress from the expanded shopping centre will have the following benefits:

- better egress from the centre onto Forest Way and hence greater access to Warringah Road for customers; and
- less traffic on Russell Avenue and Grace Avenue.

3.14 The proposed signals will have a two phase operation with 'green time' allocated to the exit from the centre limited to the current time allocated for the existing pedestrian signals. Thus during peak periods (when the pedestrian signals are activated each cycle) there would be no increase in delays to through traffic on Forest Way. The proposed access will provide three exit lanes (two right turn lanes and left turn lane) and a single entry lane. The left turn exit lane is proposed to be a turn left at any time with care. Details of the proposed operation of the new traffic signal controlled access are provided in the section on traffic effects.

3.15 Access will also be provided from Grace Avenue, south of Russell Avenue. This access will provide for all turning movements with single entry and two exit lanes.

3.16 Within the Site both accesses will provide connections to basement and rooftop car park levels via internal ramps. The new car parks will be designed to comply with the requirements of AS2890.1-2004 and AS2890.6-2009 with respect to parking space dimensions, provision of shared zones for accessible spaces, aisle widths, ramp grades and height clearances. A review of the plans has found that the car park layout generally complies with the requirements of AS2890.1-2004 (aisles 6.6 metres wide with parking spaces 2.6 metres wide by 5.4 metres long and 2.4 metre wide shared zones for accessible spaces).

-
-
- 3.17 Overall, subject to detailed design, the proposed access arrangements and car park layouts are considered appropriate and are generally in accordance with the requirements of AS2890.1-2004 and AS2890.6-2009. This is an improvement compared to the existing car park layout which is non-compliant with AS2890.1-2004 (narrow parking spaces and aisle widths).

Service Arrangements

- 3.18 The existing service area accessed from Grace Avenue (that services Aldi) will be modified and expanded to provide seven docks (including two compactors). This expanded service area will service Aldi, the specialised grocery and specialty shops. The service area has been designed to accommodate two 19 metre articulated trucks (for Aldi and the specialised grocery) plus rigid trucks. Management of the service area will be required as not all docks are accessible when a 19 metre articulated truck is parked in the Aldi dock. Deliveries to Aldi and the specialised grocery will be staggered during the day.
- 3.19 The modified Grace Avenue dock will be designed to comply with the requirements of AS2890.2-2002 with respect to grades, height clearances and maneuvering areas. Entry and exit to/from the dock will be in a forward direction. Truck turn paths are provided in Attachment B.
- 3.20 The existing Woolworths dock accessed from Sorlie Place will be modified to allow a 19 metre articulated truck to reverse into the dock and park wholly within the building. This is an improvement over the existing situation where the truck either unloads from Sorlie Place or parks partially within the building. Both of these outcomes affect traffic and pedestrian flow in Sorlie Place. Deliveries to
-
-

Woolworths will also be restricted so as not to occur in school set down and pick up periods.

- 3.21 To manage deliveries to the Site, a loading dock management plan will be prepared prior to the issue of a construction certificate. The loading dock management plan will address matters such as:
- truck arrival and departure routes;
 - loading dock hours of operation;
 - time restrictions for the Woolworths dock (no deliveries during school set down and pick up); and
 - staggering of deliveries by large trucks to the Grace Avenue dock.
- 3.22 Subject to detailed design and implementation of an appropriate loading dock management plan, the proposed service arrangements for the expanded shopping centre are considered appropriate.

Traffic Effects

- 3.23 The existing shopping centre was found to generate some 850 and 1020 vehicles per hour (two way) in the weekday afternoon and Saturday midday peak hours respectively. RMS Guidelines suggest that as shopping centres get larger the generation rate per 100m² GLA decreases reflecting a higher proportion of linked trips from a more diverse development.
- 3.24 For shopping centres between 20,000m² and 30,000m², RMS Guidelines suggest a generation of 6 vehicles per 100m² GLA in the weekday afternoon peak hour and 7 vehicles per hour per 100m² in the Saturday midday peak hour. Applying these
-
-

rates the redeveloped shopping centre, with some 21,593m² GLA, would generate some 1,300 vehicles per hour (two way) in the weekday afternoon peak hour and some 1,510 vehicles per hour (two way) in the Saturday midday peak hour. These are increases of 450 and 490 vehicles per hour (two way) in the weekday afternoon and Saturday midday peak hours respectively.

3.25 This additional traffic has been assigned to the road network based on existing travel patterns and adjustments for the changes in access arrangements. Existing traffic generated by the shopping centre has been redistributed to take into account the change in access arrangements. The results are summarized in Table 3.1 and displayed in Figures 2 and 3. It is expected that all additional traffic will use the on-site car park as surveys found that existing parking in Sorlie Place is at capacity during peak periods.

3.26 Table 3.1 reveals that:

- Traffic flows on Warringah Road would increase by some 65 to 120 vehicles per hour two-way during the weekday afternoon and Saturday midday peak hours;
- Traffic flows on Forest Way (north of the site access) would increase by some 40 to 90 vehicles per hour two-way during the weekday afternoon and Saturday midday peak hours. Between the Site access and Warringah Road, the increase in traffic flows would be higher at some 160 to 250 vehicles per hour two-way;

Table 3.1: Existing + Development Two-Way (Sum of Both Directions) Peak Hour Traffic Flows				
Road	Weekday Afternoon		Saturday Midday	
	Existing	+ Dev	Existing	+ Dev
Warringah Road				
– east of Forest Way	3705	+95	3515	+120
– west of Forest Way	3175	+65	2775	+110
Forest Way				
– north of Naree Road	3340	+40	4165	+45
– south of Naree Road	3120	+55	4110	+65
– south of Russell Avenue	2970	+95	3815	+90
– north of Warringah Road	3390	+160	4020	+250
Russell Avenue				
– east of Forest Way	510	-95	465	-85
– west of Grace Avenue	400	-40	385	-30
Grace Avenue				
– north of Russell Avenue	835	+115	695	+105
– south of Russell Avenue	835	+305	650	+375
– north of Sorlie Place (N)	845	+100	610	+70
– south of Sorlie Place (S)	830	+100	595	+70
Sorlie Place				
– entry	130	+0	160	+0
– exit	140	+0	150	+0
Naree Road				
– east of Forest Way	640	+15	555	+20
Site Accesses				
– Forest Way (entry only)	160	+315	200	+400
– Russell Avenue	285	-285	355	-355
– Grace Avenue	120	+405	155	+445

- Traffic flows on Russell Avenue would decrease by some 30 to 95 vehicles per hour two-way during the weekday afternoon and Saturday midday peak hours. This is due to the closure of the Russell Avenue access and provision of improved access onto Forest Way;
- Traffic flows on Grace Avenue, north of Russell Avenue and south of the Site access, would increase by some 70 to 100 vehicles per hour two-way during the weekday afternoon and Saturday midday peak hours. In the short section

between the site access and Russell Avenue, the increase in traffic flows would be higher at some 305 to 375 vehicles per hour two-way. This is due to the closure of the Russell Avenue access;

- Traffic flows in Sorlie Place would be unchanged as existing parking in Sorlie Place is at capacity during peak periods;
- Traffic flows on Naree Road would increase by some 15 to 20 vehicles per hour two-way during the weekday afternoon and Saturday midday peak hours.

3.27 The intersections analysed in Chapter 2 were reanalysed with development traffic in place and the upgrades currently under construction completed using the SIDRA 8 network program. The results of the analyses are summarised below:

- The intersection of Warringah Road and Forest Way would operate with average delays of less than 30 seconds per vehicle in the weekday and Saturday peak periods. This represents level of service B/C a satisfactory level of intersection operation;
- The intersection of Forest Way and the Site access would operate with average delays of less than 15 seconds per vehicle in the weekday and Saturday peak periods. This represents level of service A/B a good level of intersection operation. The analysis found that the 95% back of queue on Forest Way (northbound) was some 70 metres and would therefore not extend back to Warringah Road (some 140 metres south);

- The right turn movement out of Russell Avenue at the intersection of Forest Way and Russell Avenue would operate at capacity. However, it should be noted that this right turn movement has low traffic flows of some 5 to 10 vehicles per hour. Thus, in practice these low flows would use gaps created by traffic signals either side of Russell Avenue to turn right onto Forest Way. All other movements would operate with average delays of less than 30 seconds per vehicle (level of service B/C or better);
- The intersection of Forest Way and Naree Road would operate with average delays of less than 20 seconds per during the weekday afternoon and Saturday midday peak periods. This represents level of service B. a reasonable level of service with spare capacity;
- The intersection of Grace Avenue and Russell Avenue would operate with average delays of less than 15 seconds per during the weekday afternoon and Saturday midday peak periods. This represents level of service A/B. a good level of service; and
- The Grace Avenue access would operate with average delays of less than 15 seconds per during the weekday afternoon and Saturday midday peak periods. This represents level of service A/B. a good level of service.

3.28 Thus, with the revised access arrangements and the road upgrades currently under construction completed, the surrounding road network can satisfactorily accommodate additional traffic generated by the redeveloped shopping centre.

3.29 As a sensitivity test the SIDRA 8 network model was rerun with through traffic flows on Forest Way and Warringah Road increased by 10% to account for future

traffic growth (this equates to some 200 vehicles per hour in each direction on Forest Way). The analysis found that:

- The intersection of Warringah Road and Forest Way would operate with average delays of less than 35 seconds per vehicle in the weekday and Saturday peak periods. This represents level of service C a satisfactory level of intersection operation;
- The intersection of Forest Way and the Site access would operate with average delays of less than 15 seconds per vehicle in the weekday and Saturday peak periods. This represents level of service A/B a good level of intersection operation. The analysis found that the 95% back of queue on Forest Way (northbound) was some 80 metres and would therefore not extend back to Warringah Road (some 140 metres south); and
- The intersection of Forest Way and Naree Road would operate with average delays of less than 25 seconds per during the weekday afternoon and Saturday midday peak periods. This represents level of service B. a reasonable level of service with spare capacity.

3.30 In summary the sensitivity test found that with increased traffic flows along Forest Way and Warringah Road, the road network (with the road upgrades completed) would continue to operate at the same level of service with only minor increases in average delays and queue lengths.

Discussions with RMS

- 3.31 Prior to lodging the DA, discussions were initiated with the RMS regarding the proposed access onto Forest Way. The SIDRA 8 network modelling has been provided to RMS for review. However, at the time of DA lodgement no response to the modelling had been received. Initial RMS feedback was that the option of signalising the intersection of Forest Way and Russell Avenue should be investigated as an alternative to the proposed modifications to the existing pedestrian signals on Forest Way to allow signalised right turn egress from the Site. Access from Forest Way would be limited to left in/left out. Provision of traffic signals at the Russell Avenue would allow removal of the existing pedestrian signals (pedestrian crossing relocated to Russell Avenue). The RMS rationale for signalising the Russell Avenue intersection was that it would move the traffic signals further away from Warringah Road.
- 3.32 The option of signalising the intersection of Russell Avenue intersection with Forest Way was considered in early stages of planning for the redevelopment of the shopping centre. It was rejected as Russell Avenue is located some 100 metres south of the new traffic signal controlled intersection with Naree Road. RMS Guidelines suggest that traffic signal controlled intersections should be located a minimum of 130 metres apart. RMS has since advised that it may relax the minimum separation requirement if the Russell Avenue option results in benefits to the operation of traffic flow on Forest Way.
- 3.33 As requested by RMS we have analysed the operation of the Russell Avenue option using SIDRA 8 network. Traffic flows have been redistributed to take into account the changes in access arrangements (left in/left out to Forest Way, no right turn egress), no pedestrian signals on Forest Way and traffic signals at the
-
-

intersection of Russell Avenue and Forest Way. A concept design for traffic signals at the intersection of Russell Avenue and Forest Way is provided in Attachment C.

3.34 The analysis found that:

- Traffic flows on Russell Avenue and Grace Avenue (between the site access and Russell Avenue) would increase by some 150 to 240 vehicles per hour compared to the signalised site access option;
- Russell Avenue would require upgrading to at least two eastbound lanes between Grace Avenue and Forest Way;
- Pedestrian connectivity between the shopping centre and the bus stops on the eastern side of Forest Way is reduced (as the pedestrian crossing has been relocated to the north); and
- The SIDRA analysis found generally similar levels of service as the signalised access option. However the analysis found that:
 - 95% queue (southbound) extended back from Russell Avenue through the intersection at Naree Road; and
 - The 95% queue (northbound) on Forest Way from Russell Avenue was some 280 metres. This length extends almost back to Warringah Road (some 300 metres south of Russell Avenue). The longer northbound queue compared to the Site access option is due to the Russell Avenue intersection operating a three phase cycle (while the signalised Site access is a two phase cycle).


- 3.35 Overall, while the Russell Avenue option is a workable option it has a number of greater impacts compared to the signalised access option, including queuing extending closer to Warringah Road.

Summary


- 3.36 In summary, the main points relating to the traffic implications of the proposed expansion of Forestway Shopping Centre redevelopment are:

- i) the proposed redevelopment has good access to public transport services with local and regional bus services operating along Forest Way adjacent to the Site;
- ii) the proposed redevelopment is in accordance with government objectives and would increase retail and employment densities close to public transport services;
- iii) the proposed parking provision is appropriate;
- iv) access and internal layout are considered appropriate (subject to detailed design) in accordance with the requirements AS 2890.1-2004 and AS2890.6-2009;
- v) proposed service arrangements are considered appropriate (subject to detailed design) in accordance with the requirements of AS2890.2-2002 and implementation of a loading dock management plan;

- vi) with the proposed road upgrades under construction completed, the surrounding road network can satisfactorily accommodate the additional traffic generated by the proposed redevelopment;
- vii) the proposed signalised access on Forest Way has minimal impact on the operation of Forest Way with queues not extending back to Warringah Road;
- viii) the Russell Avenue traffic signal option has been investigated. While a workable option, it is not favoured as it has a number of greater impacts compared to the signalised access option, including queuing extending closer to Warringah Road.




Location Plan





**Existing weekday afternoon
peak hour traffic flows plus
development traffic**

Figure 2



ATTACHMENT A

PROPOSED FOREST WAY ACCESS



Filename: SKC06.dwg - USER: Ceng - Plot File Created: Sep 12, 2018 - 11:27am

SCALE 1:500 0 5 10 15 20 25
AT ORIGINAL SIZE

Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date
P3	PRELIMINARY	SB	GG	12.09.18										
P2	PRELIMINARY	SB	GG	12.09.18										
P1	PRELIMINARY	SB	GG	17.08.18										

Architect
THE BUCHAN GROUP
LEVEL 1, 7 KELLY STREET, ULTIMO, NSW, 2007

Civil Engineer
TTW Taylor Thomson Whitting
612 9439 7288 | 48 Chandos Street St Leonards NSW 2065

Project
FORESTWAY SHOPPING CENTRE REDEVELOPMENT

Sheet Subject
**SITEWORKS PLAN
FOREST WAY EXIT
BUS BAY RELOCATED**

PRELIMINARY

Scale : A1
1:500

Drawn
AS

Authorised

Job No
181210



Drawing No
SKC36

Revision
P3

Plot File Created: Sep 12, 2018 - 11:27am

ATTACHMENT B


VEHICLE TURN PATHS



NOTE:
SKETCH PLAN ONLY. PROPERTY BOUNDARIES, UTILITIES, KERBLINES & DIMENSIONS ARE SUBJECT TO SURVEY AND FINAL DESIGN. TRAFFIC MEASURES PROPOSED IN THIS PLAN ARE CONCEPT ONLY AND ARE SUBJECT TO FINAL DESIGN BY CIVIL ENGINEERS.



— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body

8.8m MEDIUM RIGID VEHICLE
SWEPT PATHS



— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body


8.8m MEDIUM RIGID VEHICLE SWEPT PATHS



NOTE:
SKETCH PLAN ONLY. PROPERTY BOUNDARIES, UTILITIES, KERBLINES & DIMENSIONS ARE SUBJECT TO SURVEY AND FINAL DESIGN. TRAFFIC MEASURES PROPOSED IN THIS PLAN ARE CONCEPT ONLY AND ARE SUBJECT TO FINAL DESIGN BY CIVIL ENGINEERS.



— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body

8.8m MEDIUM RIGID VEHICLE
SWEPT PATHS



— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body



DRAWN BY CBRK Pty Ltd_mc Ref: 10857 4 DECEMBER 2018



NOTE:
SKETCH PLAN ONLY. PROPERTY BOUNDARIES,
UTILITIES, KERBLINES & DIMENSIONS ARE SUBJECT TO
SURVEY AND FINAL DESIGN. TRAFFIC MEASURES
PROPOSED IN THIS PLAN ARE CONCEPT ONLY AND
ARE SUBJECT TO FINAL DESIGN BY CIVIL ENGINEERS.

— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body



10.7m LARGE RIGID VEHICLE
SWEPT PATHS



NOTE:
SKETCH PLAN ONLY. PROPERTY BOUNDARIES,
UTILITIES, KERBLINES & DIMENSIONS ARE SUBJECT TO
SURVEY AND FINAL DESIGN. TRAFFIC MEASURES
PROPOSED IN THIS PLAN ARE CONCEPT ONLY AND
ARE SUBJECT TO FINAL DESIGN BY CIVIL ENGINEERS.

— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body



10.7m LARGE RIGID VEHICLE
SWEPT PATHS



NOTE:
SKETCH PLAN ONLY. PROPERTY BOUNDARIES,
UTILITIES, KERBLINES & DIMENSIONS ARE SUBJECT TO
SURVEY AND FINAL DESIGN. TRAFFIC MEASURES
PROPOSED IN THIS PLAN ARE CONCEPT ONLY AND
ARE SUBJECT TO FINAL DESIGN BY CIVIL ENGINEERS.

— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body



19.0m ARTICULATED
VEHICLE SWEEP PATHS



NOTE:
SKETCH PLAN ONLY. PROPERTY BOUNDARIES,
UTILITIES, KERBLINES & DIMENSIONS ARE SUBJECT TO
SURVEY AND FINAL DESIGN. TRAFFIC MEASURES
PROPOSED IN THIS PLAN ARE CONCEPT ONLY AND
ARE SUBJECT TO FINAL DESIGN BY CIVIL ENGINEERS.

— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body

19.0m ARTICULATED
VEHICLE SWEEP PATHS



NOTE:
SKETCH PLAN ONLY. PROPERTY BOUNDARIES,
UTILITIES, KERBLINES & DIMENSIONS ARE SUBJECT TO
SURVEY AND FINAL DESIGN. TRAFFIC MEASURES
PROPOSED IN THIS PLAN ARE CONCEPT ONLY AND
ARE SUBJECT TO FINAL DESIGN BY CIVIL ENGINEERS.

— Swept Path of Vehicle Body
— Swept Path of Clearance to Vehicle Body

19.0m ARTICULATED
VEHICLE SWEEP PATHS

ATTACHMENT C

RUSSELL AVENUE TRAFFIC SIGNAL OPTION

Field

SCALE 1:500 0 5 10 15 20 25

AT ORIGINAL SIZE

m

P1	PRELIMINARY	SB	GG	06.11.18										
Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date	Rev	Description	Eng	Draft	Date

Civil Engineer

TTW **Taylor
Thomson
Whitting**

612 9439 7288 | 48 Chandos Street St Leonards NSW 2065

Sheet Subject


SITeworks PLAN
RUSSELL AVE FOREST WAY
INTERSECTION - OPTION 2
1 LEFT - 1 RIGHT

PRELIMINARY


Scale : A1	Drawn	Authorised
1:500	AS	
Job No	Drawing No	Revision
181210	SKC39	P1
Plot File Created: Nov 06, 2018 - 2:21pm		

Existing (PM)


Warringah / Forest




2027 (PM) With French's Forest
Warringah / Forest



Forest / Naree (PM)
(Increase) - vph



Forest / Russell (PM)
(Increase) - vph





Northern Beaches Hospital Road Connectivity and Network Enhancement Project

January 2016

Background

The NSW Government is planning to upgrade roads around the Northern Beaches Hospital with work proposed to be completed in time for the hospital opening in 2018. The upgrades would provide customers with a better travel experience, increased capacity on the road network and improved access through the area, including for pedestrians and cyclists.

Roads and Maritime Services is delivering the road upgrades in two stages:

- Stage 1 Connectivity Work will provide essential access to the Northern Beaches Hospital
- Stage 2 Network Enhancement Work would help increase the capacity of the road network and reduce congestion.

Roads and Maritime received planning approval on 29 June 2015 for the Concept Proposal and Stage 1 Connectivity Work in accordance with Part 5.1 of the *Environmental Planning and Assessment Act 1979*. Further information on the project's approval is available on the NSW Department for Planning and Environment's website at www.majorprojects.planning.nsw.gov.au/index.pl?action=view_job&job_id=6434

Following a competitive tendering process Roads and Maritime has contracted Ferrovial York Joint Venture to construct the road upgrades around the Northern Beaches Hospital.


Stage 2 Environmental Impact Statement

Roads and Maritime prepared an Environmental Impact Statement (EIS) for the Stage 2 Network Enhancement Work. The EIS was placed on public display from 22 July to 21 August 2015 with community and stakeholders invited to make a submission to the NSW Department of Planning and Environment.

The EIS outlined the key features of the proposal and the potential environmental, social and economic impacts resulting from the proposal during construction and operation. It also outlined measures to minimise and manage potential impacts.

There were 55 submissions received from the community, interest groups, government agencies and Warringah Council. Roads and Maritime has prepared a Submissions Report which responds to the matters the community and stakeholders raised. The report also provides additional information about design refinements proposed to the design displayed in the EIS.

You can view the Submissions Report on the NSW Department of Planning and Environment's website at www.majorprojects.planning.nsw.gov.au/index.pl?action=view_job&job_id=6622



Key

- Upgrade area
- Hospital site
- Median
- Footpath
- Shared path (pedestrian and cyclist)
- Underpass
- On-ramp into underpass
- Shared bridge (pedestrian and cyclist)
- Bus facility / bus lane
- Retaining wall
- Stage 1 Connectivity Work
- Noise barriers
- Permanent electronic message sign

0 50 100

Metres

Key features of the Stage 2 Network Enhancement Work

1. Western entry and exit points to and from the underpass for through traffic	11. Intersection of Hilmer Street and Warringah Road remains at surface with underpass extending beneath for through traffic
2. Removing the bus stop and relocating to the bus stop at Maxwell Parade	12. Intersection of Wakehurst Parkway and Warringah Road remains at surface with underpass extending beneath for through traffic
3. Changing the access at Fitzpatrick Avenue East	13. Westbound on-ramp into the underpass from surface (traffic travelling south from Wakehurst Parkway)
4. New shared pedestrian and cycle bridge	14. Eastern entry and exit points to and from the underpass for through traffic
5. Lengthening the bus bay	15. Widening Wakehurst Parkway to two lanes in each direction
6. Intersection of Forest Way and Warringah Road remains at surface with underpass extending beneath for through traffic	16. New connection to/from Aquatic Drive
7. Warringah Road widened to the south to provide two through lanes in each direction in the underpass and three lanes in each direction at the surface for access to the local road network	17. Retain existing pedestrian bridge
8. Breakdown bay in underpass	18. Widening of Allambie Road and upgrading the intersection with Warringah Road
9. New shared pedestrian and cycle bridge	
10. No straight across access from Hilmer Street to the hospital (and vice versa)	

This map refers to the Stage 2 network Enhancement Work only and does not include details of the Stage 1 Connectivity Work. Maps are indicative only. A more detailed layout is provided in the Submissions Report.

Key matters raised by submissions to the EIS

A total of 55 submissions were received in response to the display of the EIS for the Stage 2 Network Enhancement Work including:

- Six submissions from government agencies (or advisory bodies)
- One submission from Warringah Council
- One submission from Shore Regional Organisation of Councils (SHOROC)
- The remainder from members of the community and interest groups.

The most common points raised in the submissions include:

- Justification for the project, including the scale of the proposed Stage 2 Project and consideration of future public transport initiatives
- Project context with regard to local planning and development
- Traffic and transport including:
 - changes to local traffic arrangements
 - provision for pedestrians and cyclists
 - provision for public transport
 - car parking
 - alternative transport routes during construction
 - suggested design changes to improve performance of specific intersections
- Construction and traffic noise impacts
- The effectiveness of proposed noise mitigation measures
- Direct, indirect and cumulative impacts on biodiversity, including fauna connectivity and Duffys Forest Ecological Community
- Direct and indirect impacts on properties and businesses
- Reduced amenity in the local area, particularly with regard to the changed landscape character and visual impacts associated with noise barriers and other project elements.

The matters raised in submissions from the community and interest groups are outlined with a response provided in Chapter 3 of the Submissions Report. Chapter 4 of the Submissions Report provides a response to the matters raised in submissions by government agencies.

Design refinements

A number of design refinements have been made since the display of the EIS for the Stage 2 Network Enhancement Work. The refinements aim to address commitments made in the EIS, address comments received from the community, interest groups and government agencies, or result from further work carried out by Roads and Maritime since the display of the EIS.

The design refinements include a range of measures to improve bus priority, safety and traffic efficiency. Bus priority measures include the provision of eastbound bus priority lanes on Warringah Road on the approach and departure side of the intersections with Forest Way and Wakehurst Parkway.

Measures to improve safety and traffic efficiency include changes to the traffic lane arrangements on Forest Way and Wakehurst Parkway at the intersections with Warringah Road, together with improvements to lane merging arrangements eastbound on Warringah Road between Wakehurst Parkway and Allambie Road.

We have included a map to show the design refinements. For more information on these and other design refinements please also refer to Chapter 5 of the Submissions Report.

Revised safeguards and management measures

The EIS identified a range of environmental outcomes and management measures that would be needed to avoid or reduce the environmental impacts during construction and operation. Roads and Maritime has revised the environmental management measures for the project where appropriate after considering matters raised by the community and stakeholders in submissions.

If the project receives planning approval, the environmental management measures will guide the detailed design and delivery phases of the project.

The environmental management measures are detailed in Chapter 6 of the Submissions Report.

What are the key features of the Stage 2 Network Enhancement Work?

Proposed Warringah Road underpass

The Stage 2 Network Enhancement Work would involve widening on the southern side of Warringah Road from west of Fitzpatrick Avenue to west of Allambie Road and include:

- Providing four through lanes on Warringah Road (two lanes in each direction for east-west traffic) within a grade separated underpass (open slot) for about 1.3 kilometres. The underpass would be below ground level and below the intersections with Forest Way, Hilmer Street and Wakehurst Parkway
- Providing entry and exit points to and from the underpass at:
 - Warringah Road near Fitzpatrick Avenue East (western side)
 - Warringah Road about 350 metres east of the Wakehurst Parkway grade separated intersection (eastern side)
 - Providing a two-lane on-ramp (merging into one lane) from Wakehurst Parkway (southbound) into the underpass (westbound).

Proposed Warringah Road surface roads

The Stage 2 Network Enhancement Work would involve widening on the southern side of Warringah Road from west of Fitzpatrick Avenue East to west of Allambie Road to provide surface level lanes for the length of the proposal including:

- Westbound travel lanes on the southern side of Warringah Road
- Eastbound travel lanes on the northern side of Warringah Road
- Traffic using the Warringah Road underpass would travel below the intersections with Forest Way, Hilmer Street and Wakehurst Parkway. These intersections would form a surface level bridge for local access
- Upgrading/adjusting existing intersections of Warringah Road with Fitzpatrick Avenue East, Rodborough Road and Allambie Road.

Other proposed surface road upgrades

The Stage 2 Network Enhancement Work would also include:

- Widening Wakehurst Parkway from the intersection of Warringah Road to south of Aquatic Drive
- Providing a new connection at Aquatic Drive including the following movements:
 - Right in from Wakehurst Parkway (northbound)

- Left in from Wakehurst Parkway (southbound)
- Left out from Aquatic Drive onto Wakehurst Parkway (southbound).

Proposed upgrades for pedestrians and cyclists

The Stage 2 Network Enhancement Work would also include:

- Providing new shared bridges (pedestrian and cyclist):
 - Across Warringah Road west of the intersection of Forest Way (removal and replacement of the existing pedestrian bridge)
 - Across Warringah Road on the western side of the intersection with Hilmer Street (new pedestrian bridge)
- Removing the existing pedestrian crossing on Warringah Road at Hilmer Street
- Providing shared paths (pedestrian and cyclist) and footpaths on sections of Warringah Road, Wakehurst Parkway, Forest Way, Aquatic Drive and Allambie Road.

What happens next?

Stage 2 Network Enhancement Work

The NSW Department of Planning and Environment will consider the responses Roads and Maritime has provided to the submissions as part of its assessment of the project.

The Minister for Planning will then decide whether or not to approve the project and identify any conditions of approval that would apply. If approved, Roads and Maritime would continue to consult with the community, government agencies and other stakeholders during the detailed design and construction phases of the project.

Stage 1 Connectivity Work

Roads and Maritime received planning approval on 29 June 2015 for the Concept Proposal and Stage 1 Connectivity Work. Roads and Maritime is due to start construction of the Stage 1 Connectivity Work in December 2015. Construction will be carried out in stages and will start at the intersection of Wakehurst Parkway and Frenchs Forest Road. Construction activities for the Stage 1 Connectivity Work will include:

- Clearing trees and vegetation
- Relocating utilities and services including electricity, water, gas and telecommunications
- Installing boundary fencing around work areas to ensure safe separation of construction activity from traffic, pedestrians and cyclists
- Removing existing kerbs, footpaths, road barriers and median strips

- Adjustments to private properties including rebuilding driveways to fit in with the widened roads
- Removing structures and clearing land
- Moving soil and rock to create the foundations for the new road
- Constructing new sections of road including laying pavement, building new kerbs, footpaths, road barriers, median strips and installing new traffic lights
- Landscaping
- Finishing work including line marking, testing traffic signals, restoring areas used temporarily during construction.

For more information

For more information about the proposal please contact the project team:

Phone: 1300 367 459


Email: nbhroadwork@rms.nsw.gov.au

Web: www.rms.nsw.gov.au/projects/sydney-north/northern-beaches-hospital/index.html



If you need help understanding this information, please contact the Translating and Interpreting Service on **131 450** and ask them to call us on **1300 761 923**.

What are the next steps?



January 2016
RMS 15.623



Transport
Roads & Maritime
Services

Privacy Roads and Maritime Services ("RMS") is subject to the Privacy and Personal Information Protection Act 1998 ("PPIP Act") which requires that we comply with the Information Privacy Principles set out in the PPIP Act. All information in correspondence is collected for the sole purpose of assisting in the assessment of this proposal. The information received, including names and addresses of respondents, may be published in subsequent documents unless a clear indication is given in the correspondence that all or part of that information is not to be published. Otherwise RMS will only disclose your personal information, without your consent, if authorised by the law. Your personal information will be held by RMS at 27 Argyle Street, Parramatta NSW 2150. You have the right to access and correct the information if you believe that it is incorrect.

9 May 2019

RMS Reference: SYD18/01143/04 (A27302261)
Council Reference: DA2018/1924

The General Manager
Northern Beaches Council
PO BOX 882
MONA VALE NSW 1660

Attention: Luke Perry

Dear Sir/Madam

**ALTERATIONS AND ADDITIONS TO THE FOREST WAY SHOPPING CENTRE
FORESTWAY SHOPPING CENTRE FOREST WAY FRENCHS FOREST**

Reference is made to Council's correspondence dated 11 December 2018, regarding the abovementioned Application which was referred to Roads and Maritime Services (Roads and Maritime) for comment in accordance with SEPP Infrastructure 2007. Please note that the development was referred to Roads and Maritime for comment in accordance with SEPP Infrastructure 2007, however as modifications are proposed in relation to traffic signals consent in accordance with Section 87 the *Roads Act 1993* is necessary.

Roads and Maritime have found that the traffic counts in Figure 2 of the applicant's traffic report are significantly different to count data that Roads and Maritime have for this intersection, see Existing PM within attachment – (Warringah Forest PM Existing & Future.jpg). To cross check this data, Roads and Maritime conducted a SCATS count data check of this intersection for the day of the 21 March 2019 and can confirm that the applicants PM peak counts for the Warringah Road / Forest Way provided below (i.e. Figure 2 - - Traffic Report page 32) are incorrect.

Roads and Maritime has reviewed the submitted documentation and SIDRA modelling and request the following additional information be provided:

- a) The applicant is to conduct an updated SIDRA Network Model of the modelling that they have previously provided to Roads and Maritime.
- b) The updated SIDRA Network modelling will utilise data (attached to this letter) to model the following:
 - Future 2027 PM Peak (which includes background traffic growth and staged Development Traffic associated with the Frenchs Forest Precinct). The additional traffic increases associated with the Forestway Shopping Centre DA will need to be added to this traffic;
 - The proposed Forestway Shopping Centre signalised access arrangements will need to be modelled as per Roads and Maritime's requirements;

Roads and Maritime Services

- The intersection of Forest Way / Naree Road will need to be modified to provide for a dual right turn bay from Forest Way into Naree Road. (Please Note: This upgrade would be associated with the Frenchs Forest Stage 1 Precinct);
 - The intersection of Warringah Road / Forest Way will need to be modelled based on the layout within Page 2 of the attachment (northern-beaches-hospital-update-1601.pdf).
- c) To model the above future scenario, the applicant is required to use their existing weekday PM peak count data within Figure 2 of the attached report (20181211 - Report – Traffic.pdf), add in the additional traffic associated with the Forestway Shopping Centre DA, and then add the traffic increases depicted within the attachment (Forest Way PM Traffic Increases.jpg). However, for the intersection of Warringah Road / Forest Way, the applicant will be required **not** to use their PM peak hour traffic flows from Figure 2 of the attached report (20181211 - Report – Traffic.pdf) as this is incorrect, but to instead use the future 2027 PM flows depicted within the attachment (Warringah Forest PM Existing & Future.jpg) and then add in the additional traffic associated with the Forestway Shopping Centre DA.

The applicant is advised that the above information is required to allow Roads and Maritime to complete the assessment of this Application. Roads and Maritime may also request further information once the assessment is carried out.

Any inquiries in relation to this Application can be directed to Amanda Broderick on 8849 2391 or development.sydney@rms.nsw.gov.au.

Yours sincerely



Pahee Rathan
Senior Land Use Assessment Coordinator
North West Precinct

Attachments:

northern-beaches-hospital-update-1601.pdf
20181211 - Report – Traffic.pdf
Forest Way PM Traffic Increases.jpg
Warringah Forest PM Existing & Future.jpg