GENERAL NOTES

This plan is to be read in conjunction with Engineering plans, Architectural plans and any other plans or written instructions issued relating to the development at the subject site. All dimensions are NOMINAL. All dimensions and levels are to be checked by contractor before commencing work. Figured dimensions take preference to scale. Any discrepancies are to be confirmed by the designer All construction practices are to be in accordance with the current issue of the BCA and all other relevant Australian Standards and codes. All carpentry work to comply with AS 1684 Residential Timber Framed Construction. All prefabricated timber trusses and frames to be installed to the manufacturers details & specification. All concrete slabs, retaining walls, structural steel, foundations and footings to be designed and specified by the consulting structural engineer and built strictly in accordance with such details as approved. Structural construction setout to be approved by client

SITE NOTES / SITE PREPARATION

roots, remove from site. Stock pile existing excavated site topsoil for re-use in new garden bed areas, as required. Any existing sandstone boulders, rock and flagging pieces within the designated construction zone will be stockpiled for re-use in proposed planting areas to embankments for the construction of retaining walls and landscape features where required. Remove unwanted matter including stones exceeding 50mm, loose sticks, and branches, damaged roots and building rubbish. Remove existing grass/weeds from all proposed garden bed areas. Where required, spray areas with an approved herbicide. Cultivate by hand garden bed areas to a depth of 200mm. | Re-use stockpiled existing site topsoil to garden areas as required, and cultivate thoroughly into existing site soil.

SITE MANAGEMENT

Control any flow of water by diverting clean water away from any disturbed areas of the site. Ensure any contaminated/sediment laden water treated/filtered prior to leaving the site. Minimise disturbance and rehabilitate and revegetate areas as soon as possible. Maintain erosion and sediment controls by cleaning and repairing as required. Stockpile topsoil for re-use where possible.

SOIL CONSERVATION

Prior to commenencement of construction provide sediment fence, sediment trap and washout area to ensure the capture of water borne material generated from


the course of construction and shall not be removed until the site has been stabilised or landscaped to the superintendents satisfaction. The contractor shall ensure that no spoil or fill encroaches upon adjacent areas for the duration of works. Sediment fencing shall be secured by post (metal star pickets are with plastic safety caps) at 2000mm intervals with geo-textile fabric embedded 200mm in soil. All topsoil stripped from the site and stockpiled does not interfere with drainage lines and storm-water inlets and will be suitably converged with an

PLANTING NOTES / IRRIGATION

All garden beds and planter boxes to have irrigation installed Irrigation layout, pipe & fittings to be nominated by qualified tradespeople. Irrigation to be installed by qualified tradespeople. Irrigation system to be run as per installers recommendations

GARDEN BEDS

Garden beds to have organic garden mix cultivated into site soil. Imported soil to be free of weeds and toxins. Excavate holes for plants twice the size of the plants root ball. Ensure to remove pots from plants prior to installation. Trees to be staked and tied as



** Denotes native species

PLANT ESTABLISHMENT / MAINTENANCE

Regular maintenance is to be carried out to include

Watering-to maintain healthy growth, adjusted to suit seasons. Weeding to all garden and lawn areas. Pest and disease control. Trim hedge plantings to maintain desired heights. Tip pruning as required and fertilising as per species specification. Mowing and edging of all turfed areas