ALTERATIONS & ADDITIONS AT 4 STINSON PLACE, FORESTVILLE

- These drawings shall be read in conjunction with all architectural and other consultants drawings and specifications and with such other written instructions and sketches as may be issued during the course of the Contract. Any discrepancies shall be referred to the Superintendent before proceeding with any related works. Construction from these drawings, and their associated consultant's drawings is not to commence until approved by the Local Authorities.
- G3 All set out dimensions shall be obtained from Architect's and Engineer's details. All discrepancies shall be referred to the Architect and Engineer for decision before proceeding with related work.
- During construction the structure shall be maintained in a stable condition and no part shall be overstressed Temporary bracing shall be provided by the builder/subcontractor to keep the works and excavations stable at all times.

- G7 Any substitution of materials shall be approved by the Engineer and included in any tender. G8 All services, or conduits for servicing shall be installed prior to commencement of pavement construction

DRAINAGE NOTES

- D1 All drainage levels to be confirmed on site, prior to any construction commencing.
- D2 All pipes within the property to be a minimum of 100 dia upvc @ 1% minimum grade, uno.
- D3 All pits within the property are to be fitted with "weldlok" or approved equivalent grates:

 Light duty for landscaped areas
 Heavy duty where subjected to vehicular traffic
- D4 All pits within the property to be constructed as one of the following:
 1) Precast stormwater pits
 2) Cast insitu mass concrete
 3) Cement rendered 230mm brickwork subject to the relevant local a

- D7 All pits in roadways are to be fitted with heavy duty grates with locking bolts and continuous hinge.
- D8 Provide step irons to stormwater pits greater than 1200 in depth.
- D9 Trench back fill in roadways shall comprise sharp, clean granular back fill in accordance with the relevant local authority specification to non-trafficable areas to be compacted by rodding and tamping using a flat plate vibrator.
- D10 Where a high early discharge (hed) pit is provided all pipes are to be connected to the hed pit, uno.
- D11 Down pipes shall be a minimum of dn100 sw grade upvc or 100 x100 colorbond/zincalume steel, uno.
- D12 Colorbond or zincalume steel box gutters shall be a minimum of 450 wide x 150 deep. D13 Eaves gutters shall be a minimum of 125 wide x 100 deep (or of equivalent area) colorbond or zincalume
- D14 Subsoil drainage shall be provided to all retaining walls & embankments, with the lines feeding into the stormwater drainage system, uno.

EROSION AND SEDIMENT CONTROL NOTES

- E1 These notes are to be read in conjunction with erosion and sediment control details in this drawing set.
- The contractor shall implement all soil erosion and sediment control measures as necessary and to the satisfaction of the relevant local authority prior to the commencement of and during construction. No disturbance to the site shall be permitted other than in the immediate area of the works and no material shall be removed from the site without the relevant local authority approval. All erosion and sediment control devices to be installed and maintained in accordance with standards outlined in nsw department of housing's managing urban stormwater soils and constructions:
- Place straw bales length wise in a row as parallel as possible to the site contours, uno. Bale ends to be tightly butted. Bales are to be placed so that straws are parallel to the row. Bales are to be placed 1.5m to 2m downstops from the toe of the disturbed batter, uno.

- E6 Provide and maintain silt traps around all surface inlet pits until catchment is revegetated or paved.
- E7 The contractor shall regularly maintain all erosion and sediment control devices and remove accumulated si from such devices such that more than 60% of their capacity is lost. All the sill is to be placed outside the limit of works. The period for maintaining bese devices shall be at least until all disturbed areas are revegetated and further as may be directed by the superintendent or council.
- The contractor shall implement dust control by regularly wetting down (but not saturating) disturbed area.

- E11 The contractor shall grass seed all disturbed areas with an approved mix as soon as practicable after completion of earthworks and regrading.
- E13 When any devices are to be handed over to council they shall be in clean and stable condition

STANDARD LINE TYPES AND SYMBOLS			
	PROPOSED KERB & GUTTER		
	EXISTING KERB & GUTTER		
	PROPOSED BELOW GROUND PIPELINE		
	PROPOSED SUSPENDED PIPELINE		
	EXISTING PIPELINE		
	SUBSOIL DRAINAGE LINE		
	PROPOSED KERB INLET PIT		
	EXISTING KERB INLET PIT		
	PROPOSED JUNCTION OR INLET PIT		
	EXISTING JUNCTION OR INLET PIT		
	DESIGN CENTRELINE		
	EXISTING EDGE OF BITUMEN		
	TELECOMUNICATION CONDUIT		
	GAS MAIN		
	WATER MAIN		
	SEWER MAIN		
	UNDERGROUND ELECTRICITY CABLES		
	PERMANENT MARK & S.S.M.		
A A	BENCH MARK, SURVEY STATION		

	OVERLAND FLOW PATH
<u> </u>	GUTTER DRAINAGE DIRECTION
O&	DOWNPIPE
$\mathcal{O}_{\mathcal{A}}^{\mathcal{A}}$	DOWNPIPE WITH SIDE OVERFLOW
* * * * * *	PERVIOUS (GRASSED) AREAS
x RL=??	EXISTING (PRE-DEVELOPMENT) RL
x RL= ??	POST DEVELOPMENT RL
FALL	GRADED IMPERVIOUS AREA (ROOF, CONC SLABS ETC)
	SEDIMENT FENCE
	CROSSING PIPES
1	NODE POINT


LEGE	ND		
AHD	Australian height datum	SS	Stainless steel
AG ARI	Ag-pipe (Sub soil drainage) Average recurrence interval	SU	Box gutter sump Top of wall
BG	Box Gutter	TWI	Top of wall
BWI	Bottom water level	U/S	Underside of slab
CL	Cover level	VG	Vally gutter
CO	Clean out inspection opening	UNO	Unless noted otherwise
DCP	Discharge control pit		
DP	Down pipe		
DRP	Dropper pipe		
EBG	Existing box gutter		
FFG	Existing down pipe		
FG	Existing eaves gutter Eaves gutter		
FRC	Fiber reinforced concrete		
FW	Floor waste		
GD	Grated drain		
GSIP	Grated surface inlet pit		
HED	High early discharge		
HP	High point of gutter		
IL	Invert level		
10	Inspection opening		
O/F OSD	Overflow On-site detention		
PSD	On-site detention Permissible site discharge		
P1	Pipe 1		
RCP	Reinforced concrete pipe		
RHS	Rectangular hollow section		
RL	Reduced level		
RRJ	Rubber ring joint		
RRT	Rainwater re-use tank		
RWH	Rain water head		
RWO	Rain water outlet		
SLAP	Sealed lid access pit		
	Spreader pipe		
SPR	Spreader		

RECOMMENDED MAINTENA	NCE SCHED	ULE	
DISCHARGE CONTROL PIT (DCP)	FREQUENCY	RESPONSIBILITY	PROCEDURE
Inspect flap valve and remove any blockage.	Six monthly	Owner	Remove grate. Ensure flap valve moves freely and remove any blockages or debris.
Inspect screen and clean.	Six monthly	Owner	Revove grate and screen if required and clean it.
Inspect & remove any blockage of orifice.	Six monthly	Owner	Remove grate & screen to inspect orifice. see plan for location of dcp.
Inspect dcp sump & remove any sediment-sludge.	Six monthly	Owner	Remove grate and screen. Remove sediment/sludge build-up and check orifice and flap valve clear.
Inspect grate for damage or blockage.	Six monthly	Owner	Check both sides of grate for corrosion, (especially corners and welds) damage or blockage.
Inspect return pipe from storage and return any blockage.	Six monthly	Owner	Remove grate and screen. ventilate underground storage if present. open flap valve and remove any blockages in return line. Check for sludge/debris on upstream side of return line.
Inspect outlet pipe and remove any blockage.	Six monthly	Maintenance Contractor	Remove grate and screen. ventilate underground storage if present. Check orifice and remove any blockages in outlet pipe. Flush outlet pipe to confirm it drains freely. Check for sludge/debris on upstream side of return line.
Check fixing of step irons is secure.	Six monthly	Maintenance Contractor	Remove grate and ensure fixings secure prior to placing weight on step iron.
Inspect overflow weir & remove any blockage.	Six monthly	Maintenance Contractor	Remove grate and open cover to ventilate underground storage if present. ensure weir clear of blockages.
Empty basket at overflow weir (if present).	Six monthly	Maintenance Contractor	Remove grate and ventilate underground storage chamber if present. Empty basket, check fixings secure and not corroded.
Check attachment of orifice plate to wall of pit (gaps less than 5 mm).	Annually	Maintenance Contractor	Remove grate and screen. ensure plate mounted securely, tighten fixings if required. seal gaps as required.
Check attachment of screen to wall of pit.	Annually	Maintenance Contractor	Remove grate and screen. ensure screen fixings secure. repair as required.
Check screen for corrosion.	Annually	Maintenance Contractor	Remove grate and examine screen for rust or corrosion, especially at corners or welds.
Check attachment of flap valve to wall of .	Annually	Maintenance Contractor	Remove grate. Ensure fixings of valve are secure.
Check flap valve seals against wall of pit.	Annually	Maintenance Contractor	Remove grate. fill pit with water and check that flap seals against side of pit with minimal leakage.
Check any hinges of flap valve move freely.	Annually	Maintenance Contractor	Remove grate. Test valve hinge by moving flap to full extent.
Inspect dcp walls (internal and external, if appropriate) for cracks or spalling.	Annually	Maintenance Contractor	Remove grate to inspect internal walls. Repair as required. Clear vegetation from external walls if necessary and repair as required.
Check step irons for corrosion.	Annually	Maintenance Contractor	Remove grate. Examine step irons and repair any corrosion or damage.
Check orifice diameter correct and retains sharp edge.	Five yearly	Maintenance Contractor	Compare diameter to design (see work-as- executed) and ensure edge is not pitted or damaged.
STORAGE			
Inspect & remove any blockage of orifice.	Six monthly	Owner	Remove grate and screen. remove sediment/sludge build-up.
Check orifice diameter correct and retains sharp edge.	Six monthly	Owner	Remove blockages from grate and check if pit blocked.
Inspect screen and clean.	Six monthly	Owner	Remove debris and floatable material likely to be carried to grates.
Check attachment of orifice plate to wall of pit (gaps less than 5 mm).	Annually	Maintenance	Remove grate to inspect internal walls, repair as required, clear vegetation from external walls if necessary and repair as required.
Check attachment of screen to wall of pit.	Five yearly	Maintenance Contractor	Compare actual storage available with work-as executed plans. If volume loss is greater than 5%, arrange for reconstruction to replace the volume lost. Council to be notified of the proposal.
Check attachment of screen to wall of pit.	Five yearly	Maintenance Contractor	Check along drainage lines and at pits for subsidence likely to indicate leakages.

Contractor		5%, arrange for reconstruction to replace the vol proposal.					
ve	ve yearly Maintenance Contractor		e	Check along drainage lines and at pits	for subs	sid	
	D	14.03.23	3 REVIS	SED TANK D	DIMENSIONS	F.I.	
	С	10.03.23	3 REVI	SED TO SUI	T COUNCIL COMMENTS	F.I.	
	В	21.12.22	2 REVI	SED DRAINA	AGE DESIGN	F.I.	
	Α	20.12.22	2 ISSUI	ISSUED FOR APPROVAL			
	REV	DATE	DESC	CRIPTION		BY	
			•				_

COPYRIGHT All rights reserved. These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or	Enginee	ering <mark>Studio</mark>
copied wholly or in part without the written permission of Engineering Studio.	Phone: (02) 8020 2960 Email: info@engineeringstudio.com.au Web: www.engineeringstudio.com.au	Postal Address PO Box 7191 BAULKHAM HILLS NSW 2153

ALTERATIONS & ADDITIONS AT 4 STINSON PLACE, FORESTVILLE	JOB NUMBER: 220742	DWG NUMBER: C00.01	ORIGINAL SIZE:
FOR U+I BUILDING STUDIO	DESIGNED BY: S.R.	DECEMBER 2022	
GENERAL NOTES	DRAWN BY: J.W.	SCALE:	



SEDIMENT & EROSION CONTROL PLAN

1:200

- DENOTES SEDIMENT FENCE

NOTE: BUILDER/PLUMBER TO INVESTIGATE SITE CONDITIONS, CONFIRM STORMWATER CONNECTION HEIGHT LEVELS AND LOCATION TO ENSURE CONSISTENCY WITH THE DESIGN. ANY DISCREPANCIES OR CONFLICTS WHICH MAY AFFECT THE PROPOSED DESIGN TO BE REPORTED TO THE ENGINEER PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

	D	14.03.23	REVISED TANK DIMENSIONS	F.I.
	С	10.03.23	REVISED TO SUIT COUNCIL COMMENTS	F.I.
	 В	21.12.22	REVISED DRAINAGE DESIGN	F.I.
	Α	20.12.22	ISSUED FOR APPROVAL	J.W.
ΓE	REV	DATE	DESCRIPTION	BY

COPYRIGHT
All rights reserved.
These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written permission of Engineering Studio.




Phone: (02) 8020 2960
Email: info@engineeringstudio.com.au
Web: www.engineeringstudio.com.au

ALTERATIONS & ADDITIONS AT 4 STINSON PLACE, FORESTVILLE FOR U+1 BUILDING STUDIO	
SEDIMENT & EROSION	

CONTROL PLAN

JOB NUMBER:	DWG NUMBER:	ORIGINAL SIZE:
220742	C01.01	A3
DESIGNED BY: S.R.	DATE: DECEMBER 2022	
DRAWN BY: J.W.	SCALE:	



WATERPROOF COVERING SEDIMENT FENCE EARTH BANK TO PREVENT SCOUR OF STOCKPILE

OPTION 1 - EXISTING DRIVEWAY TO REMAIN

OPTION 2 - DRIVEWAY TO BE RENEWED


VEHICLE ACCESS TO SITE

VEHICLE ACCESS TO THE BUILDING SITE SHOULD BE RESTRICTED TO A SINGLE POINT SO AS TO REDUCE THE AMOUNT OF SOIL DEPOSITED ON THE STREET PAVEMENT.

BUILDING MATERIAL STOCKPILES

ALL STOCKPILES OF BUILDING MATERIAL SUCH AS SAND AND SOIL MUST BE PROTECTED TO PREVENT SCOUR AND EROSION.

THEY SHOULD NEVER BE PLACED IN THE STREET GUTTER WHERE THEY WILL WASH AWAY WITH THE FIRST RAINSTORM.



STRAW BALE DETAIL

SEDIMENT AND EROSION FENCE DETAIL

SANDBAG KERB SEDIMENT TRAP

IN CERTAIN CIRCUMSTANCES EXTRA SEDIMENT TRAPPING MAY BE NEEDED IN THE STREET GUTTER.

NOTE: BUILDER/PLUMBER TO INVESTIGATE SITE CONDITIONS, CONFIRM STORMWATER CONNECTION HEIGHT LEVELS AND LOCATION TO ENSURE CONSISTENCY WITH THE DESIGN. ANY DISCREPANCIES OR CONFLICTS WHICH MAY AFFECT THE PROPOSED DESIGN TO BE REPORTED TO THE ENGINEER PRIOR TO THE COMMENCEMENT OF CONSTRUCTION

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SI

	D	14.03.23	REVISED TANK DIMENSIONS	F.I.
	С	10.03.23	REVISED TO SUIT COUNCIL COMMENTS	F.I.
	В	21.12.22	REVISED DRAINAGE DESIGN	F.I.
_	А	20.12.22	ISSUED FOR APPROVAL	J.W.
ITE	REV	DATE	DESCRIPTION	BY


COPYRIGHT
All rights reserved.
These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written paramissing of Engineering Studio.



Email: info@engineeringstudio.com.au PO Box 7191 BAULKHAM HILLS NSW 2153

SEC

ALTERATIONS & ADDITIONS AT 4 STINSON PLACE, FORESTVILLE	JOB NUMBER: 220742	DWG NUMBER: C01.02	ORIGINAL SIZ
FOR U+I BUILDING STUDIO	DESIGNED BY: S.R.	DECEMBER 2022	
SEDIMENT & EROSION CONTROL DETAILS	DRAWN BY: J.W.	SCALE:	



STORMWATER DESIGN SUMMARY

COUNCIL: NORTHERN BEACHES COUNCIL

= 274 mm/h1%, 5 MIN STORM 2%, 5 MIN STORM = 242 mm/h 5%, 5 MIN STORM = 205 mm/h

TOTAL SITE AREA $= 694.00 \text{ m}^2$

NEW ROOF AREA $= 336.48 \text{ m}^2$ IMPERVIOUS PATHS & DRIVEWAYS $= 75.76 \text{ m}^2$ TOTAL IMPERVIOUS SITE AREA $= 412.24 \text{ m}^2$ IMPERVIOUS SITE PERCENTAGE = 59.4 %

215.4m² PROPOSED ROOF AREA DIRECTED TO COMBINED RAINWATER RE-USE/ ON-SITE DETENTION. HIGH LEVEL OVERFLOW DIRECTED TO LEVEL SPREADER VIA GRAVITY.

ALL ROOF DRAINAGE HAS BEEN DESIGNED TO SUIT 2% A.E.P. STORM EVENT

ON-SITE INFILTRATION DESIGN SUMMARY

A DRAINS MODEL HAS BEEN PREPARED TO ASSESS THE STORMWATER RUNOFF FROM THE PROPOSED DEVELOPMENT ON-SITE DETENTION HAS BEEN PROVIDED TO LIMIT THE 1% A.E.P. POST-DEVELOPED FLOW TO THE 20% A.E.P. PRE-DEVELOPMENT RUNOFF RATE. REFER TO THE SUMMARY ON THIS SHEET FOR MODELLING RESULTS.

COMBINED RAINWATER RE-USE/ OSD TANK

 $= 7.45 \text{ m}^3$ REQUIRED OSD STORAGE PROVIDED OSD STORAGE $= 7.45 \text{ m}^3$ ORIFICE DIAMETER = 29mm

ABOVE GROUND BASIN ON-SITE DETENTION

REQUIRED OSD STORAGE = 1.85 * 1.2 $= 2.22 \text{ m}^3$ PROVIDED OSD STORAGE $= 2.4 \text{ m}^3$ ORIFICE DIAMETER

STORMWATER DRAINAGE NOTES

- ALL DRAINAGE LINES SHALL BE uPVC (CLASS SH) STORMWATER DRAINAGE PIPE, U.N.O.
- ALL DRAINAGE LINES SHALL BE LAID @ 1% FALL MIN, U.N.O. - FIRST FLUSH RAINWATER DEVICES TO BE FITTED TO
- DRAINAGE LINES TO BUILDER'S DETAIL, TYPICAL - MINIMUM EFFECTIVE EAVES GUTTER SLOPE = 1:500 U.N.O.
- MINIMUM EFFECTIVE BOX GUTTER SLOPE = 1:200 U.N.O.
- MINIMUM EFFECTIVE EAVES GUTTER SIZE = 7400 mm²

(HALF ROUND 150)

LEGEND

Ø100 OR 100 x 75 RECTANGULAR DOWN PIPE, U.N.O.

8 INSPECTION POINT

RAINWATER SPREADER 8111

∜□ FIRST FLUSH RAINWATER DEVICE TO

BUILDERS DETAIL

(c) CHARGED PIPE

PROPOSED BELOW GROUND PIPELINE

PROPOSED SURFACE INLET PIT

OVERLAND FLOW PATH

BG1 300W x 120D BOX GUTTER

300W x 125D x 120L RAINWATER HEAD

WITH Ø100 DOWNPIPE

300W x 120D x 400L SUMP WITH Ø100 DOWNPIPE

& 300W x 70D OVERFLOW

NOTE: BUILDER/PLUMBER TO INVESTIGATE SITE CONDITIONS, CONFIRM STORMWATER CONNECTION HEIGHT LEVELS AND LOCATION TO ENSURE CONSISTENCY WITH THE DESIGN. ANY DISCREPANCIES OR CONFLICTS WHICH MAY AFFECT THE PROPOSED DESIGN TO BE REPORTED TO THE ENGINEER PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.

	E
NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE	RI

	О	14.03.23	REVISED TANK DIMENSIONS	F.I.	C A
	С	10.03.23	REVISED TO SUIT COUNCIL COMMENTS	F.I.	Т
	В	21.12.22	REVISED DRAINAGE DESIGN	F.I.	th S
	Α	20.12.22	ISSUED FOR APPROVAL	J.W.	c p
	REV	DATE	DESCRIPTION	BY	

COPYRIGHT All rights reserved. These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written





PO Box 7191 BAULKHAM HILLS NSW 2153

ALTERATIONS & ADDITIONS
AT 4 STINSON PLACE, FORESTVILLE
FOR U+I BUILDING STUDIO

STORMWATER DRAINAGE PLAN

JOB NUMBER:	DWG NUMBER:	ORIGINAL SIZE:
220742	C02.01	A3
DESIGNED BY: S.R.	DATE: DECEMBER 2022	
DRAWN BY: J.W.	SCALE:	





EngineeringStudio

Email: info@engineeringstudio.com.au PO Box 7191 BAULKHAM HILLS NSW 2153

Phone: (02) 8020 2960

CIVII & Structural

REVISED TANK DIMENSIONS

REVISED DRAINAGE DESIGN

SUED FOR APPROVAL

REVISED TO SUIT COUNCIL COMMENTS

0.03.23

21.12.22

20.12.22

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

NOTE: BUILDER/PLUMBER TO INVESTIGATE SITE CONDITIONS, CONFIRM STORMWATER CONNECTION HEIGHT LEVELS AND LOCATION TO ENSURE CONSISTENCY WITH THE DESIGN. ANY DISCREPANCIES OR CONFLICTS WHICH MAY AFFECT THE PROPOSED DESIGN TO BE REPORTED TO THE

ENGINEER PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.

C02 02

220742


ESIGNED BY


AT 4 STINSON PLACE, FORESTVILLE


FOR U+I BUILDING STUDIO

STORMWATER DETAILS SHEET

Α3








BALL VALVE RIGHT ANGLE TYPE BALL VALVE RIGHT ANGLE TYPE DUAL CHECK VALVE PUMP GARDEN TAP DRINKING WATER SUPPLY PIPES RAINWATER SUPPLY PIPES OWN PIPES

DIAGRAM NOTES:


- 1 DRAWING TO BE READ IN CONJUNCTION WITH SYDNEY WATER PLUMBING REQUIREMENTS
- 2 FOR TANKS 10,000 LITRES OR LESS, COUNCIL DEVELOPMENT CONSENT IS NOT REQUIRED, IF THEIR CONDITIONS FOR INSTALLATION ARE FOLLOWED.
- 3 FOR TANKS GREATER THAN 10,000 LITRES COUNCIL DEVELOPMENT CONSENT IS GENERALLY REQUIRED.
- 4 FOR TANKS MORE THAN 10,000 LITRES APPROVAL IS REQUIRED FOR BUILDING OVER SEWERS.
- 5 SYDNEY WATER'S APPROVAL IS REQUIRED FOR ANY TOP UP FROM DRINKING WATER SUPPLY, REGARDLESS OF TANK SIZE. NO DIRECT CONNECTION IS ALLOWED BETWEEN THE DRINKING WATER SUPPLY AND THE RAINWATER TANK SUPPLY.
- 6 RAINWATER PIPEWORK IS SHOWN ON THE DIAGRAM AS SUPPLYING INTERNAL AND EXTERNAL RAINWATER USES. CUSTOMERS MAY WANT ONE OR THE OTHER.
- 7 ANY DESIGNED ACCESS LID INTO RAINWATER RE-USE TANK IS TO HAVE A LOCKABLE LID. IF THE LID IS DESIGNED TO BE ACCESSED BY A MAINTENANCE PERSON, IT MUST BE AT LEAST 600 mm x 900 mm IN SIZE.



TYPICAL FIRST FLUSH DETAIL

DUAL DRINKING WATER & RAINWATER SUPPLY DIAGRAM

N.T.



TYPICAL EAVES GUTTER DETAIL

LIGHT DUTY ACCESS GRATE
WITH CHILD PROOF "J" BOLT
OR APPROVED EQUIVALENT.
REFER TO PLAN FOR PIT SIZE.

CONTRACTOR TO EXCAVATE
& BACKFILL PIT IN 150mm LAYERS
TO DENSITY OF ADJACENT SOIL

CONCRETE
BENCHING/SHAPING
TO BASE OF ALL PITS

AS PER PLAN.

TYPICAL SURFACE INLET PIT DETAIL

1:20

NOTE: BUILDER/PLUMBER TO INVESTIGATE SITE CONDITIONS, CONFIRM STORMWATER CONNECTION HEIGHT LEVELS AND LOCATION TO ENSURE CONSISTENCY WITH THE DESIGN. ANY DISCREPANCIES OR CONFLICTS WHICH MAY AFFECT THE PROPOSED DESIGN TO BE REPORTED TO THE ENGINEER PRIOR TO THE COMMENCEMENT OF CONSTRUCTION.

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SITE

	D	14.03.23	REVISED TANK DIMENSIONS	F.I.
	С	10.03.23	REVISED TO SUIT COUNCIL COMMENTS	F.I.
	В	21.12.22	REVISED DRAINAGE DESIGN	F.I.
	A	20.12.22	ISSUED FOR APPROVAL	J.W.
ITE	REV	DATE	DESCRIPTION	BY

COPYRIGHT
All rights reserved.
These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written permission of Engineering Studio.

Enginee	ringStudio CM & Shuctural

ALTERATIONS & ADDITIONS AT 4 STINSON PLACE, FORESTVILLE	JO
FOR U+I BUILDING STUDIO	DE
STORMWATER DETAILS SHEET	DR

3

JOB NUMBER:	DWG NUMBER:	ORIGINAL SIZE:
220742	C02.04	A3
DESIGNED BY: S.R.	DATE: DECEMBER 2022	
DRAWN BY: J.W.	SCALE:	

ALTONA AVENUE EXTERNAL CATCHMENT 1 AREA = 846m² EXTERNAL CATCHMENT 2 SUBJECT SITE KERB INLET EXISTING Ø375

THEREFORE GUTTER HAS SUFFICIENT CAPACITY.

5% A.E.P. ADDITIONAL FLOW DIRECTED TO KERB AND GUTTER

FROM SUBJECT SITE

CATCHMENT AREA (A)

TIME OF CONCENTRATION (t)

5% A.E.P. 5min RAINFALL INTENSITY (2015)

10% A.E.P. RUNOFF COEFFICIENT (C₁₀)

TOTAL FLOW DIRECTED TO KERB & GUTTER

ASSUMING 1% SLOPE, FLOW DEPTH IN GUTTER

5% A.E.P. RUNOFF COEFFICIENT (C₂₀)

1% A.E.P. PEAK FLOW RATE (Q₁₀₀)

AVERAGE 80% FRACTION IMPERVIOUS ASSUMED

PIT AND PIPE CAPACITY
THE RATIONAL METHOD HAS BEEN USED TO ESTIMATE THE PEAK
FLOW RATE OF THE EXTERNAL FLOW DIRECTED TO THE KERB INLET PIT AT THE END OF STINSON PLACE

CATCHMENT AREA (A) = 0.3828ha

TIME OF CONCENTRATION (t) 5% A.E.P. 5min RAINFALL INTENSITY (²⁰I₅) AVERAGE 80% FRACTION IMPERVIOUS ASSUMED 10% A.E.P. RUNOFF COEFFICIENT (C₁₀)

EXTERNA FLOW CALCULATIONS

GUTTER FLOW
THE RATIONAL METHOD HAS BEEN USED TO ESTIMATE THE PEAK FLOW RATE OF THE EXTERNAL FLOW DIRECTED TO THE KERB &

5% A.E.P. RUNOFF COEFFICIENT (C₂₀) = 0.851 1% A.E.P. PEAK FLOW RATE (Q₁₀₀) = C*A*I/360 $=\frac{0.851 *0.3828* 205}{360}$

 $= 0.185 \,\mathrm{m}^3/\mathrm{s}$

= 0.0846ha

= 205 mm/hr

 $= 0.008 \text{ m}^3/\text{s}$

= 0.049 m3/s

= 0.082m

= 5min

= 205 mm/hr

= 5min

= 0.81

= C*A*I/360 $= \frac{0.851 *0.0846* 205}{360}$ $= 0.041 \text{ m}^3/\text{s}$

= 0.851

ADDITIONAL FLOW DIRECTED TO KERB AND GUTTER FROM $=\frac{146*205}{3600}$ SUBJECT SITE $= 0.008 \text{ m}^3/\text{s}$

TOTAL FLOW DIRECTED TO KERB INLET PIT = 0.193 m3/s

A DRAINS MODEL HAS BEEN PREPARED TO CHECK SAG INLET AND Ø375 OUTLET PIPE CAPACITY.

CAPACITY= 0.256m³/s > 0.0192m³/s, THEREFORE OK

EXTERNAL CATCHMENT ASSESSMENT

NOTE: BUILDER/PLUMBER TO INVESTIGATE SITE CONDITIONS, CONFIRM STORMWATER CONNECTION HEIGHT LEVELS AND LOCATION TO ENSURE CONSISTENCY WITH THE DESIGN. ANY DISCREPANCIES OR CONFLICTS WHICH MAY AFFECT THE PROPOSED DESIGN TO BE REPORTED TO THE ENGINEER PRIOR TO THE COMMENCEMENT OF CONSTRUCTION

NOTE: DO NOT SCALE OFF DRAWINGS. REFER TO ARCHITECTURAL PLANS. VERIFY DIMENSIONS ON SIT

	D	14.03.23	REVISED TANK DIMENSIONS	F.I.
	С	10.03.23	REVISED TO SUIT COUNCIL COMMENTS	F.I.
	В	21.12.22	REVISED DRAINAGE DESIGN	F.I.
	A	20.12.22	ISSUED FOR APPROVAL	J.W.
ſΕ	REV	DATE	DESCRIPTION	BY

COPYRIGHT
All rights reserved.
These drawings, plans and specifications and the copyright are the property of Engineering Studio and must not be used, reproduced or copied wholly or in part without the written paramissing of Engineering Studio.



Phone: (02) 8020 2960 Email: info@engineeringstudio.com.au PO Box 7191 BAULKHAM HILLS NSW 2153

ALTERATIONS & ADDITIONS
AT 4 STINSON PLACE, FORESTVILLE
FOR U+I BUILDING STUDIO

EXTERNAL CATCHMENT	
ASSESSMENT	

Ī	JOB NUMBER:	DWG NUMBER:	ORIGINAL SIZE:
	220742	C03.01	A3
	DESIGNED BY: S.R.	DATE: DECEMBER 2022	
	DRAWN BY: J.W.	SCALE:	