

Our ref P-08-130 Council ref CC 0324/08 ABN61340837871
Telephone 02 9970 1111
Facsimile 02 9970 7150
Postal Address
PO Box 882
Mona Vale NSW 1660
DX 9018 Mona Vale

Environmental Compliance 8am to 5 30pm Mon - Thurs 8am to 5pm Fri Phone 9970 1111



2 July 2008

Oliver Higgins Wastewater PO Box 494 Newport NSW 2106

Dear Sir.

Re Construction Certificate CC 0324/08 Property 5 Chiltern Rd, Ingleside

Please find enclosed your approved Construction Certificate and stamped plans

Did you know that work is unable to commence until such time as a completed Notification of Commencement Form has been submitted to Council at least two (2) days prior to starting work? Not to do so is a breach of the Environmental Planning and Assessment Act, which would result in a Penalty Infringement Notice (on-the-spot fine) being issued to you and the builder

To assist you please find enclosed a 'Notification of Commencement and Principal Certifying Authority Service Agreement" form to enable you to appoint Pittwater Council as your Principal Certifying Authority (PCA)

If appointed as the PCA, Council would engage the services of Tom Miskovich & Associates Pty Ltd to carry out the various inspections as indicated in Part 6 of the enclosed "Notification of Commencement and Principal Certifying Authority Service Agreement form and ultimately issue an Occupation Certificate for your development Appointment and inspection fees are also detailed in the enclosed form

Council will endorse your completed 'Notice of Commencement and Principal Certifying Authority Service Agreement form and return a copy to the applicant with advice as to the required critical stage and other inspections to be carried out on behalf of Council

Council is committed to providing a quality service and would value your business in being appointed as the Principal Certifying Authority for your development

Yours faithfully

Development Compliance Group

Per Tom Miskovich & Associates Pty Ltd

SCANNED

OF JUL 2008

DITIMATER COUNCIL



Approved Construction Certificate CC 0324/08

ABN61340837871
Telephone 02 9970 1111
Facsimile 02 9970 7150
Postal Address
PO Box 882
Mona Vale NSW 1660
DX 9018 Mona Vale

Site Details 5 Chiltern Rd, Ingleside

Legal Description Lot 1 DP 808703

Type of Development Building Work

Associated Development Consent No

Description An on-site waste water disposal system

•

Dated 26 February 2008

Building Code of Australia Classification Class 10b

Details of plans, documents or Certificates to which this Construction Certificate relates

N0569/07

- Drawings No H-01, H-02, H-03, Issue B dated 21/01/91 prepared by Leffler Simes Architects.
- Plans 1 & 2 (site & irrigation layout plans),
- Drawing HAS1 by Oliver-Higgins Wastewater,
- Letter from Oliver Higgins Wastewater regarding DA condition C1, dated 1/6/08,
- · Recycled Water Policy document,
- Strcuuturia certificate from Kneebone, Beretta & Hall for the inground tank,
- Letter from Demlakian Engineers regarding DA conditions C2 & C4, dated 12/5/08,
- Soil Erosion & Sediment Control Plans C0, C1 & C2 prepared by Demlakian Engineers

I hereby certify that the above plans, documents or Certificates satisfy

- The relevant provisions of the Building Code of Australia, and
- The relevant conditions of Development Consent No N0569/07

And, that work completed in accordance with the documentation accompanying the application for this certificate (and any modifications as verified by me and shown on that documentation) will comply with the requirements of the Environmental Planning and Assessment Regulation, referred to in section 81A(5) of the Environmental Planning and Assessment Act 1979

Manchoe

Issued By Tom Donohoe
Accreditation Number BPB0096
Pittwater Council Consultant
Building Surveyor

Date of Endorsement 2 July 2008

Note You are reminded that pursuant to provisions of Clause 81A you must nominate whether Council or an accredited certifier will be the principal certifying authority, also you must give notice to Council of your intention to commence work at least two days beforehand



NOTIFICATION OF COMMENCEMENT & PRINCIPAL CERTIFYING AUTHORITY SERVICE AGREEMENT

under Environmental Planning and Assessment Act 1979 sections 81A (2) (b) (ii) or (c), or (4) (b) (ii) or (c) 86 (1) and (2)

About this form	Au sul • Th	e this form to appoint Pittwater Cou thority (PCA) to carry out nominated odivision works and to issue the req is form must be submitted to Pittwat ys prior to the commencement of wo	d inspections of the building / uired Occupation Certificate ter Council a minimum of two (2)
Who can complete this form?	on having the benefit of the cannot complete this form unless		
Applicant's Checklist	CoSigAtt	ad this document mplete pages 1 2 & 3 in on page 8 ach a copy of Owner Builder Permit arranty Insurance Certificate	t or Home Owner
Payment of fees			
		tical Stage Inspection fees (refer to time of booking the inspection	Part 6e of this form) must be paid a
		ue of Interim/Final Occupation Cert m) must be paid prior to release of	
Pittwater Council		Tel (612) 9970 1111	Fax (612) 9970 7150
Mona Vale Customer S Village Park, 1 Park Stre MONA VALE NSW 210	eet	Avalon Customer Service 59A Old Barrenjoey Road AVALON NSW 2108	Mailing Address PO Box 882 MONA VALE NSW 1660

1

1 DEVELOPMENT INFORMATION

1a) DEVELOPMENT CONSENT									
	Developme	nt Application N	lo NO569/07	Determination	mination Date 26 February 2008				
				<u></u>					
1b)	CONSTRU	ICTION CERT	IFICATE						
,		n Certificate No		Date of Issu	e 2 July	2008			
١	AND DEVELOPMENT DETAILS								
1c)		MENT DETA							
	Type of Work		Brief description	Brief description of development					
	☐ New Building		Installation of M	Installation of Waste Water Treatment Plant and Disposal Area					
		ıs / Alterations		vaste vvater i	caunenti	iant and Dispo	isai Alea		
	☐ Subdivi	sion							
,			. - I	··	-				
1d)	SITE DETA		-						
	Unit/Suite	Street No 5	Street Chiltern Ro	oad					
			<u> </u>						
	Suburb Ing	leside NSW 2	101			Lot No 1	Deposit /Strata Plan		
ľ							DP 808703		
l									
1e)	VALUE O	F PROPOSED	DEVELOPMEN	т					
`` ` [VALUE OF PROPOSED DEVELOPMENT							
	Estimated v	alue of propose	ed works \$49 000	00					
ι									
1f) į	DATE WORK IS TO COMMENCE								
	Minimum no	Minimum notice of two (2) days is required to be given prior to commencement of works							
	Data of som	· · · · · · · · · · · · · · · · · · ·							
l	Date of con	Date of commencement							
2		NT DETAILS							
		builder or othe	er contractor cann	not complete	this form	unless they a	are also the owner of the		
property									
ſ	Name (own	er)							
	Postal Addr	200	-						
	1 Ostal Addi	C33			Phone (I	H/B)			
					8.6 - b - 1 -				
					Mobile				
					Email				
ĺ	Fax								

. ,	COUNCIL					
PO Box 882				0 1111		
Mona Vale N	SW 1660	F	ax 997	70 7150		
COMPLIANC	E WITH DEVELOPM	ENT CO	DNSEN	т		
Have all condit	ions to be addressed p	rior to the	e comm	encement of works been satisfied?		
	YES			NO (see Note below)		
Please be aware		ese condi		y leave you liable and in Breach of the Environme s may include an on the spot fine and/or legal act		
If you are uncert	ain as to these requireme	nts please	contact	Council's Development Compliance Group		
			-			
WHO WILL B	E DOING THE BUIL	DING W	ORKS	?		
	Owner Builder	<u> </u>				
	Owner Builders Per	mıt No				
Copy of Owner Builders permit						
If you are an Owner-Builder for the residential building work exceeding \$5000 you must apply for a permit at NSW Office of Fair Trading, 1 Fitzwilliam Street, Parramatta NSW 2150 Australia Tel 61 2 98950111 Fax 61 2 9895 0222						
			OR			
	Licensed Builder Builder's License N	umber				
Name of Build	Builder's License N	umber		Phone		
	Builder's License N	umber		Phone Mobile		
Name of Build	Builder's License N	umber				
Name of Build Contact person	Builder's License Ni der on		nce Ce	Mobile Fax		
Name of Build	Builder's License Ni der on	Insura	nce Ce Yes	Mobile		
Name of Build Contact person	Builder's License Ni der on	Insura	Yes No - s	Mobile Fax entificate attached statement attached & signed by each own		
Name of Build Contact person	Builder's License Ni der on	Insura	Yes No - s of the	Mobile Fax Intificate attached Statement attached & signed by each own property that the reasonable market cost bour & materials to be used is less than		

6 RESPONSIBILITIES OF THE PRINCIPAL CERTIFYING AUTHORITY (PCA)

6a) Quality of Service

Pittwater Council will carry out PCA and inspection services in a professional manner and in accordance with the requirements of the Environmental Planning & Assessment Act 1979 and Council's Code of Conduct

6b) Site Signage

Pittwater Council will erect a sign on the site to advise the general public of the contact details of the PCA The sign will be erected during the Commencement Inspection, on Council's acceptance of appointment as PCA

6c) Inspections

Pittwater Council officers will undertake the Critical Stage Inspections of the work during construction and prior to issuing an Occupation Certificate to ascertain compliance of specified stages of construction with the Development Consent, Construction Certificate Building Code of Australia & relevant standards of construction On appointment as the PCA Pittwater Council will notify the applicant in writing of the Critical Stage & other Inspections

6d) Critical Stage and other inspections

The following stages of construction are required to be inspected by Council (as indicated by a ✓ in the relevant box)

Note Council's Development Compliance Officer will complete this section of the form

		Footing Inspection (prior to placement of concrete)	
		Slab and other Steel Inspection (prior to placement of concrete)	
Cniy		Frame Inspection (prior to fixing floor wall & ceiling linings)	Office Use Only
		Wet Area Waterproofing Inspection (prior to covering)	
nse		Stormwater Inspection (prior to backfilling of trenches)	
Office		Swimming Pool Safety Fence Inspection (prior to placement of water)	
ס	✓	Final Inspection (all works completed and prior to occupation of the building)	

Note Should the building works be completed in parts & not all aspects of a Critical Stage Inspection be ready additional inspections maybe required – with a further inspection fee payable

Eg If two slabs are prepared at separate times, two separate inspection bookings and fees are required

6e) Critical Stage and other inspection fees

An inspection fee is required for each inspection identified in Part 6d of this form A separate inspection fee is required for each Critical Stage Inspection. Should works be either incomplete or incorrect at the time of inspection a further separate reinspection fee will be required

Each inspection fee must be paid at the time of requesting the inspection

Fee Scale current to 30 June 2009

Critical Stage or other Inspection and re-inspections, including Final	\$245	(Code HINR)
Issue of Interim Occupation Certificate Issue of Final Occupation Certificate	\$330 \$330	(Code FOCC) (Code FOCC)

Please note that a failure to give correct notification of required inspections may result in the issuing of a Penalty Infringement Notice (PIN or on-the-spot fine) and/or a Notice and Order by Council and may result in refusal to issue an Occupation Certificate

6f) Inspection Results

Pittwater Council will provide written confirmation to the applicant of the inspection results and indicate if satisfactory or if additional works are required prior to reinspection

7 RESPONSIBILITIES OF THE APPLICANT

7a) Inspections

A minimum of forty-eight (48) hours notice (excluding weekends and public holidays) must be given to Council to enable the specified stages of construction to be inspected as identified in Item 6 of this agreement

Should an inspection be missed the applicant must advise Council in writing (as soon as practicable after the event) of that fact the circumstances causing the inspection to be missed and supporting documentation for Council's consideration. In such cases, the inspection fee, which would normally have been required, must still be paid.

The applicant must ensure that the Principal Contractor (Builder/Owner Builder) is advised of the required inspections and that the directions of Council's Development Compliance Officers are to be observed to ensure compliance with the Development Consent, Construction Certificate, Building Code of Australia and the terms of this agreement

7b) Booking of Inspections

The applicant shall request an inspection via Pittwater Council's Inspection Booking Hotline on **9970 1300** A minimum of forty-eight (48) hours notice must be provided to Council to arrange for completion of the inspection

At the time of requesting the inspection, Pittwater Council will confirm an inspection time and day name of inspecting officer and mobile contact number

Building works must **not** proceed to the subsequent stages of construction prior to obtaining a satisfactory inspection from Council for each stage of construction specified in Item 6d of this agreement

7c) Site Signage

The applicant is responsible to maintain the PCA signage provided by Pittwater Council at the site until the work is completed

The applicant is responsible to ensure that the Owner Builder or Principal Contractor (Builder) provide a rigid durable sign at the site, visible from the public place and maintained at the site until the work is completed. Such a sign shall display (a) the name, address and telephone number of the person, (b) an after-hours emergency telephone number for the person and (c) stating "Unauthorised Entry to the Site is Prohibited"

7d) Compliance with the Development Consent and Construction Certificate
All works must be carried out in accordance with the terms and conditions of Council's
Development Consent and the Construction Certificate and relevant provisions of the Building
Code of Australia and Environmental Planning and Assessment Act 1979

Development Consent and a Construction Certificate must be obtained for any amendments or variations to the development prior to the commencement of the amendment or variation

Works not in accordance with the approval and Building Code of Australia may result in the refusal to issue an Occupation Certificate Council may also serve a Notice and Order to comply with the approval and/or the institution of legal proceedings

7e) Structural Engineering and Other Specialist Details

The following details are to be forwarded to the PCA prior to commencement of the relevant stage of construction (as identified by a \checkmark) The details are to be prepared by a suitably qualified person to confirm compliance with the relevant provisions of the BCA and Australian Standards

Note Council's Development Compliance Officer will complete this section of the form

	☐ Timber framing details including bracing and tie-downs	7
	☐ Roof construction or roof truss details	
•	☐ Termite control measures Office Use	Only
	☐ Glazing details	
	☐ Mechanical ventilation details	
Only	☐ Wet area construction details	
Use (☐ Details of fire resisting construction	i
ge C	☐ Details of essential fire and other safety measures	
Office	☐ Sound transmission and insulation details	
	☐ Details of compliance with development consent conditions	

7f) Certification of Works

To ensure compliance with the Construction Certificate and Building Code of Australia (BCA), the applicant is to provide certification, verifying that the following specialist matters (identified by a ✓) have been carried out

Each certification must

- reference the approved Construction Certificate number property address, relevant provisions of the BCA, Australian Standards and approved drawings
- be prepared by an accredited certifier or other suitably qualified & experienced person to the satisfaction of Pittwater Council

Note Council's Development Compliance Officer will complete this section of the form

	۵	Survey detailing building setbacks, reduced levels of floors & ridge by a registered surveyor						
		Shoring and support for adjoining premises and structures by a structural engineer						
		Contiguous piers or piling by a structural engineer						
		Underpinning works by a structural engineer						
		Structural engineering works by a structural engineer						
		Retaining walls by a structural engineer Office Use Onli	y					
		Stormwater drainage works by a hydraulic engineer and surveyor						
		Landscaping works by the landscaper						
<u>~</u>		Condition of trees by an Arborist						
Onice Use Only		Mechanical ventilation by a mechanical engineer						
Š		Termite control and protection by a licensed pest controller						
		Waterproofing of wet areas by a licensed waterproofer or licensed builder						
)		Installation of glazing by a licensed builder						
		Installation of smoke alarm systems by a licensed electrician						
		Completion of construction requirements in a bush fire prone area by a competent person						
		Completion of requirements listed in the BASIX Certificate by a competent person						
		Fire resisting construction systems by a competent person						
		Smoke hazard management systems by a competent person						
		Essential fire safety and other safety measures by a competent person (Form 15a)						
		Completion of Bushland Management requirements by a suitably qualified person						
		Installation of Waste Water Management System by a suitably qualified person						
		Installation of the inclined lift by a suitably qualified person						
		Installation of sound attenuation measures by an acoustic engineer						
	✓	Matters required by Development Consent conditions						

This form is valid from 1st July 2008 to 30 June 2009

7g) Occupation Certificate

A Final Occupation Certificate must be obtained from the PCA prior to the occupation or use of a new building (or part of a building) or prior to the change of an existing building use/classification An inspection fee is to be paid to the PCA in accordance with the fee scale in Part 6e of this agreement

An application may be made to the PCA for an Interim Occupation Certificate, which will be considered in accordance with the provisions of the Environmental Planning and Assessment Act 1979 and conditions of development consent

Only the Principal Certifying Authority can issue an Occupation Certificate and the Environmental Planning and Assessment Act 1979 contains penalty provisions for failing to obtain a required Occupation Certificate

An application for an Interim or Final Occupation Certificate must be accompanied by a final or interim fire safety certificates as required by the EP&A Regulations, Clauses 80E or 80F for buildings other than Class 1 and 10

7h) Miscellaneous requirements

The applicant is required to ensure that valid public liability insurance cover to the value of \$10,000,000 (minimum) is held by the applicant and/or builder

The applicant is required to notify Council, in writing, of any change in the details or address of the applicant or head contractor

Pittwater Council may cancel the agreement if there is a breach of the agreement

YOUR SIGNATURE

I accept the terms and conditions of this service agreement, including the associated payment of fees and appoint Pittwater Council as the Principal Certifying Authority for the subject development

Signature Date

COUNCIL'S AGREEMENT TO APPOINTMENT


The relevant details in Parts 6d 7e & 7f of this agreement have been completed. Home Owners Warranty Insurance Certificate or Owner/Builders Permit or Statement has been provided where necessary and I acknowledge the appointment of Pittwater Council as the Principal Certifying Authority

on behalf of Pittwater Council Officer's name

Officer's signature Date


PRIVACY AND PERSONAL INFORMATION PROTECTION NOTICE


Purpose of collection	To enable Council to act as the Principal Certifying Authority for the development
Intended recipients	Pittwater Council staff
Supply	The information is required by legislation
Consequence of Non provision	Your application may not be accepted not processed or rejected for lack of information
Storage	Pittwater Council will store details of this form in a register that can be viewed by the public
Retention period	Hard copies will be destroyed after 7 years and electronic records will be kept indefinitely
	Please contact Council if this information you have provided is incorrect or changes





DELIVERY LINE 50 mas (E. SOLENOITS AUTOMATIC ROTATION BY ELECTRONIC CONTROLER AND SOLENOIDS XETIER JATE) 24 April 2007 1315712180710N BY NETGEIMS 13 AM PRESSURE COMPENSATING IRRIGATION LAYOUT DRIP SINE MACTERS REPORT 2001 & 609 5-RI AND ACCOMPANYING INSTALLE) IN COMPRANCE 30 Lives in (6×5) 23/72/ FLUSH COMMON 09 - AND WELLES 0 2 101 2008 衛の たかから BRCA BANA WAY WITH OUR HML ny Certificates associated with the issue of the Construction Certificate. This is a copy of submitted plans, documents or 80/200 PITTWATER COUNCIL CONSTRUCTION CERTIFICATE

PLAN 2









Oliver-Higgins Wastewater

WASTEWATER CONTRACTORS

WASTEWATER TREATMENT PLANTS; SUSTAINABLE DESIGN; GREYWATER TREATMENT; BENEFICIAL RE-USE

Pittwater Shire Council Vuko Place Warriewood NSW 2102 1st June 2008

DA No. N0569/07

Attention Kristy Wise

Dear Ms Wise,

In response to the requirements of Condition C1 of the above DA Consent, please be advised that the effluent disposal area has been designed by Martens and Associates Pty Ltd in accordance with the relevant Council and State Government Management Guidelines to ensure the application of the treated effluent to the proposed area is sustainable. (see 'Wastewater Management Study' ref No. 2001E609JR1 dated February 2003 and subsequent letter Dated 24 April 2007, ref No. 2001E609JC08_v1). These documents contain effluent re-use concept design modelling inclusive of daily water and nutrient modelling and the findings and recommendations of such modelling are contained therein.

Yours Sincerely

Kim Higgins

Number: CC 0324 08

This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.

Endorsed by: RG TM A

Date: 0 2 JUL 2008



HAMAZKAINE ARSHAK & SOPHIE GALSTAUN COLLEGE

5 Chiltern Road, Ingleside NSW 2101, Australia

Tel: (02) 9970 6984 - Fax: (02) 9970 6778 Email: admin@hasg.nsw.edu.au - Web: www.hasg.nsw.edu.au

RECYCLED WATER POLICY - 5 Chiltern Rd, Ingleside

The Hamazkaine Arshak & Sophie Galstaun College is committed to the development and operation of a safe, economically viable, environmentally sustainable and socially acceptable recycled water scheme.

Stakeholders:

- Hamazkaine Arshak & Sophie Galstaun College (HASGC) (owner)
- Government Jurisdictions
- Any person or group that has an interest or concern
- Oliver Higgins Wastewater Contractors (OHW) (contractors)

Recycled Wastewater Principles:

- Ensure risks are made explicit, are understood, managed and accepted by the stakeholders.
- OHW to educate HASGC of shared risks and responsibilities and their commitment to the continuous application of the risk management of the scheme.
- HASGC to educate all persons attending the College of shared risks and responsibilities.
- Risk management to be reviewed if, an event occurs eg breakdown, annually, or at the request of a stakeholder.
- The recycle scheme is to comply with all regulatory requirements.
- Any complaint, problem or fault reported, whether actual or perceived must be notified to
 the servicing agent and recorded in the site register as a permanent record for view by
 interested parties and for review of risk management.
- Ensure the treatment system and disposal areas are properly maintained. Carry out any rectification works as may be required to ensure the compliant operation of the scheme.
- This policy is to be reviewed annually to ascertain its ongoing suitability.

The objective of the recycled water scheme and the above principles is to use recycled water for the purposes of irrigation whilst ensuring that there are no adverse affects to public health or environment considerations.

	ER CO				UCTIO	V CERT	ATE
Number:	CC	03	241	80			
This is Certifica Constru	a co ates	py of associ	subn lated	nitted			
Endorse	d by:	Rin	T	MA	6		
Date:		0 2	JUL	ZUU8			

Vientyer of The Association of Consulting Engineers Australia



KNEEBONE, BERETTA & HALL PTY LTD

ACN 002 419 767

CONSULTING STRUCTURAL & CIVIL ENGINEERS
4 Macquarte Avenue PENRITH NSW 2750
Ph; (02) 4731 3833 Fax: (02) 4721 5442
E-Mail: Kneebone & pnc. com.au

Ref: 0056-C6 12 July 2002

STANDARD 6.3m DIAMETER TANK, BUILDER: PANTHER WATER TANKS.

This is to certify that we have designed the above 65,000 litre water tank and are satisfied that if constructed in accordance with the following details will be structurally adequate for water storage as an in-ground tank.

Tank Size - 6.3m diameter x 2.1m deep (internal dimensions)

Floor Slab . 110mm thick excavated into firm natural ground with a

safe bearing capacity of at least 300kPa.

Walls - 125mm thick reinforced with F82 fabric placed centrally.

Lap wall fabric 400mm into floor slab around perimeter of

wall.

Columns - Provide 4 columns equally spaced below roof slab. Use

150mm diameter PVC pipes concrete filled and reinforced with 1-Y12 bar full height of each column.

Roof Slab - 125mm thick reinforced with F82 fabric throughout bottom

of slab, 30mm cover.

Provide additional F82 fabric x 1000mm square top extra

over each column, 30mm cover,

Concrete strength to be 32MPa in accordance with

AS3600.

Maximum slump to be 80mm.

Number: CC O324(08

Number: CC O324(08

This is a popy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate.

Endorsed by: RC TM H


Endorsed by: RC TM H

All backfill material around tank to be porous rubble. Seal surface of backfill with 200mm thick layer of compacted clay

Adequate drainage must be provided to prevent uplift of tank due to buoyancy when empty.

Design is adequate for 6.3m diameter tank, fully in-ground with 150mm maximum thick soil covering over roof slab.

The roof slab is designed for light loading and is unsultable for crowd or vehicular loads.





12th May 2008 REF: 208083rpt20080512_Excavation Report

Mr Vic Nalbandian 22 Roger Street BROOKVALE NSW 2100 Demlakian Engineers Pty Limited T/A Demlakian Consulting Engineers ABN 25 270 948 695 Level 2, 5 Ridge Street North Sydney NSW 2060 Telephone: (02) 9955 4485 Facsimile: (02) 9955 6122

P.O. Box 6553 North Sydney 2059 Email: info@demlakian.com.au www.demlakian.com.au

RE: HAMAZKAINE ARSHAK & SOPHIE GALSTAUN SCHOOL INC. 5 CHILTERN ROAD INGLESIDE NSW

INTRODUCTION

Further to the requirements of Conditions C2 and C4 of Development Consent No. N0569/07 endorsed 26th February 2008 by Pittwater Council we confirm as follows.

A suitably qualified engineer has inspected the site and reviewed the requirements on the consent in regard to the site conditions and the proposed works.

The proposed works consist of upgrading the existing pump-out sewage system to an on -site sewage management facility. This requires construction of a series of treatment tanks adjacent to the location of the existing septic tank along with a pressure pipe to the existing sports field located adjacent the eastern boundary.

The conditions of consent require provision of an Erosion and Sediment Management Plan along with a Schedule of Works and procedures for excavation and retention of cuts to ensure site stability is maintained.

Accordingly this report and the accompanying drawings 208083/C0, C1, C2 and C3 provide the required details.

EROSION AND SEDIMENT MANAGEMET PLAN AND SCHEDULE OF WORKS

- 1. The proposed works will require localised excavation for the installation of tanks and slabs for pumps in the location of the treatment facility. The accompanying drawings indicate the protection measures in this location.
- 2. We have investigated the route of the proposed pipe trench to the infiltration area located under the Sports Field. The adjoining surface generally slopes into the site for most of the length of the trench and to the northeast in the area of Sports Field. Where the ground levels slope towards adjoining properties a sediment fence will be installed along boundaries, although the potential for runoff is minimal

Structural Engineers

Civil Engineers

Hydraulic Engineers

Project Managers

Rectification Engineers

DEMLAK

0324 08 This is a copy of submitted plans, documents or Certificates associated with the issue of the Construction Certificate. Endorsed by: Rh TMA



Date. 0 2 1111 2038 As noted the proposal is to excavate a series of trenches through the existing Sports Field to act as infiltration beds for treated effluent. The following measures will be implemented to protect this area of the works.

- To divert storm water running onto the excavated area a Cut-off drain will be constructed along the western side of Sports Field to intercept stormwater and redirect to the north of the proposed excavated area.
- This cut-off drain will be filtered through a series of hay bales prior to following the natural drainage path into the existing water storage dam.
- The excavation of the Sports Field will be surrounded by a sediment fence to filter runoff prior to following the natural drainage path into the existing water storage dam.
- The existing water storage dam will be used as a temporary sediment trap for the duration of the works. The accompanying drawings provide details for dosing with gypsum to allow sediments to settle as required prior to discharging the dam by pumping. If required the dam can be pumped through a sand filter.
- 4. An Infiltration Filter will be used around all affected existing storm water pits to protect the polluted stormwater into the drainage system.
- A Truck Shaker will be provided to wash down all vehicles prior to leaving the site.

PROCEDURES FOR EXCAVATION AND RETENTION OF CUT

The proposed extent of works involves minor shallow excavations for construction of the treatment facility along with a series of trenches for installation of pipes and infiltration beds. The typical trench depth is in the order of 1.0 metre. Our inspection has confirmed that the works are located in relatively level ground and thus there is no reason to expect that the works will cause site instability. The pipes can be installed by typical cut and cover trenching techniques. Where required the trench sides can be battered at a grade of 1 to 1 for stability or shoring may be used. This can be in the form of designed strutted timber planking or a proprietary "drag box".

CONCLUSION

We confirm that the measures indicated in this report and accompanying drawings provide adequate protection to the environment and the procedures for excavation and retention of cut are suitable for the site conditions.

Yours faithfully,

David Wilcox

BE (Hons I) MIEAust CPEng

Associate

DEMLAKIAN CONSULTING ENGINEERS

REF: 208083rpt20080512_Excavation Report

12th May 2008

DEMLAKIAN CONSULTING ENGINEERS **©Copyright**

ON-SITE WASTE WATER DISPOSAL SYSTEM CHILTERN ROAD NGLESIDE



BULK EXCAVATION & CIVIL WORKS NOTES

- prior finis real of shappets and shikes.

 Files that of completing promate place is because of vanets; more, informate piece is because of vanets; more, including a clima manufacture is professional promotion professional prof
- ts from shall be removed either than these affected by reed and draining earlie in accordance with council's free preservation order.
- whicher occase and all services shall be eated almed at all times to djoining properties affected by construction. e werk shall be carried set an adjability properties without the writte eralisaten from the owner.

- PRIng med as subgrade for resolvage 195X at anderd to AS 1289 S.1. Filling to be used for boose franchistom 195X standard to AS 1289 S.1. General Filling 155X standard to AS 1289 S.1.1
- All excessed earling that he pred risks using a seasch that risks of seitens. It invest does seaded, by risksing it is the season, day self spirit delected sheeld he excessed self by all lead 1. he self compatint, thather combinising any he required to ensure that the adopted is properly compatint.
- nterpolation of depths or levels on the drawings shall be performed locally for hunder purposes and confirmed on alls. Falls believen grid test shall stop be linear. li batters shall be constructed to a nan, singe of 156 although fielts ages may be dictated by the landercaping requirements. Super to be cased dhall be an atomyor than 14.
- The expensed natural ground surface shall be loosened to a depth of 26tom, mainture conditioned and compacted to the same requirements a for the FEI natural netwin EN. obers fill in placed on sloping ground (at a slope greater than 1981 enches shall be cut into the satural ground to a minimum depth of 198ms

- The filling works shall be tested during construction to assure compliand with specification. Testing frequency shall be set less than that but I test per 300 cobic seaters distributed evently throughout the full spanished and areas. material type per 540 square maters; which

- Campaction shall be reduced to 96X maximum dry density (to AS 029 5.1: within 1666 from the back of retaining walls.

REV.No DATE

ISSUED FOR APPROVAL REVISION

BY REV.No DATE

REVISION

NOT FOR CONSTRUCTION

CLIENT:

HAMAZKAINE ARSHAK & SOPHIE GALSTAUN SCHOOL INC.

DRAWING SCHEDULE

COMMISSION DEVANOS SESSION UNICER UZERSE BY DEVA

ON-SITE WASTE WATER DISPOSAL SYSTEM 5 CHILTERN ROAD INGLESIDE

208083

PRELIMINARY

R. KEACAM INCH. MITTS (ent.): In all locations where increment surfaces become settlemed or locationed due to adverse weather, ground coppies, or other Consex, all such settler of lease asserted should be presented down to the larvest otherse adversable bearing capacity of fraudation satisfied is an appearities.

CIVIL NOTES

- All exceptions shall be exist sheef free of valve by provision of rolled drains or drainage to exitable collection examps for reserved by pumping or named manns.
- The greater solved shall be consistented and the least logistics, also and exceeding 5 on the set desired sounds and expert and least the SEA of the entered shall peak the Than ship and control peaking the LLT-solven shall be set that LLT-solven shall be a limit of the shall peak of greater than LET. The antimist deal to approve for one by the particulated amplesses.
- ESG. All fill shall be free drabby. All earthworks to be LA.W. AS 3798. less certs satural shall be cospected in layers set exceeding Clies in a selected MB X of the scaleus dry density as deversited by AS CEN, L2.1 the satural shall be approved by the ampleser.
- A Lim vide, confinence sirrip of buffide grass shall be piaced bashed the back of it new harts immediately after the compartion of the feel-path grading, matchinged and replaced as required during the matchinance parties.
- SOIL & WATER MANAGEMENT PLAN NOTES
- NSTALL ALL BARRER FENCING TO EXCLUDE ACCESS TO THE NOMINATED RESTRICTED AREAS.
- CONSTRUCT EARTH BANKS AND CUT-OFF DRAINS TO DIRECT OVERLAND FLOW BEYOND THE SITE. CONSTRUCT EARTH BANKS & CUT-OFF DRAINS TO DIRECT OVERLAND FLOW TO THE DESIGNATED OUTLET PIT.
- STRP AND STOCKPILE TOPSOIL FROM THOSE LANDS TO BE EXPOSED TO CHISTRACTION ACTIVITIES.
- NDERTAKE WORKS ACCORDING TO THE ENGINEERING PLANS.
- SITE MSPECTION HAMITEMAKE CONDITIONS
 WASTE BIRS WILL BE EMPTIED AS NECESSARY, DISPOSAL OF WASTE WILL BE IN A HAMMER APPROVED BY THE SITE SUPERMITEMENT.
- THE SITE SUPERINTENDENT WILL INSPECT THE SITE AT LEAST WEEKLY AND WILL: nsure that drams operate properly and to effect any ecessary repairs;
- DHOVE SPILED SAND OR OTHER HATEBULS FROM HAZAND AREAS, CLUDING LANDS CLOSES THAN FIVE RETIRES FROM JAREAS OF RELY YOUNG THAN FOR THE SERON JAREAS OF RELY TROMES ESPECIALLY ATERNAYS AND PAYED AREAS. INOVE TRAPPED SEDMENT WHENEVER LESS THAN DESIGN WACITY REMAINS WITHIN THE STRUCTURE:
- REHADRITATED LANDS HAVE EFFECTIVELY REDUCED THE HAZARD AND TO INITIATE UPGRADING OR REPAIR AS NATE.
- ANT AN ERGSION AND SEDIMENT CONTROL NEASURES IN A FULLY UNCTIONING CONDITION UNTIL ALL EARTHWORK ACTIVITIES ARE OWNLETED AND THE SITE IS REPARAUTATED, AND

RUNOFF DIRECTED TO SEDIMENT TRAP / FENCE B

- HOVE TEMPORARY SOIL CONSERVATION STRUCTURES AS THE LAST TIVITY IN THE REHABILIT ATION PROGRAM.
- AL APANT OF THE STATUTION Y DAGRET, AND CARE RESPONSAILES, THE SITE APPROXIMENT AND CARE AT CASE OF CONCAST AND AND AND THE SAME AND AND THESE VALL FALLOW AND THE SAME AND AND THESE VALL FALLOW AND AND THE SAME AND AND AND THE SAME AND AND AND THE SAME AND THE SAME AND AND THE SAME AN

CONSTRUCTION NOTES - SITE STABILISATION ACCESS
1 STRP TOPSON & LEVEL SITE.

COMPACT SUBGRADE

CONSTRUCT HUMP IMMEDIATELY WITHIN BOUNDARY TO DIVERT WATER TO A SEDMENT FENCE OR SEDMENT TRAF

OVER ADEA WITH MEEDLE PRINCHED GEOTEXTILE OR 30mm IGGREGATE HANNIN LEHGTH 15m OR TO BULDING LUGHNENT, HRINNIN WOTH 3m.

STABILISED SITE ACCESS

THE NEED FOR DUST PREVENTION STRATEGES; AND ANY REMEDIAL WORKS TO BE UNDERTAKEN. NOOK WILL BE KEPT ON-SITE AND MADE A VAILABLE TO ANY CONSED PERSON ON REQUEST. IT WILL BE GIVEN TO THE PROJECTER AT THE CONCLUSION OF WORKS.

MOTE: ONLY TO BE USED AS TEMPORARY BANK WHERE HAXWIM UPSLOPE LINGTH IS BOM. OR WITHOUT CHANNEL ZIHO : NY) HAX.

THE TEMPORARY SEDMENT TRAP PIT SHALL BE CLEANED REGILARLY. IN THE EVENT THE GEOTEXTILE PILTER BECOMES CLOSEED DURBNG DEVATERING PLAMPING SHALL BE STOPPED AND THE FILTER CLEANED OR RESERVED.

UST SHALL BE CONTROLLED BY REGILLAR MOISTENING OF EXCAVATED GRYCES AND STOOPPLES.

THE TRUCK SHAKER SHALL BE REGULARLY CLEANED BY LIFTING, DISLODG REHOVENG SPOIL.

EROSION & SEDIMENT CONTROL NOTES ILL EROSION & SEDIMENT CONTROL MEASURES SHALL BE MAINTAINED AS HOMN ON THE DRAWNIGS.

EARTH BANK (CUT-OFF DRAIN)

- CONSTRUCTION NOTES CONSTRUCT WITH GRADIENT OF DX TO 5X.
- AVOID REMOVING TREES AND SHRUBS IF POSSIBLE
- EARTH BANKS TO BE ADEQUATELY COMPACTED IN ORDER TO PREVENT FAILURE DRAMS TO BE OF CIRCULAR, PARABOLIC OR TRAPEZOD CROSS SECTION NOT "V"
- PERHAMENT OR TEMPORARY STABILISATION OF THE EARTH BANK TO BE COMPLETED MITHIN IN DAY'S OF CONSTRUCTION.
- ALL DUTLETS FROM DISTURBED LANDS ARE TO FEED INTO A SEDWENT BASIN OR SHIPLAR.
- COMPACT BANK WITH A SUITABLE IMPLEMENT IN SITUATIONS WHERE THEY ARE REQUIRED TO PUNCTION FOR MORE THAN FIVE DAYS. ascharge rumoff collected from undsturbed lamos onto either a Stabilised or an undsturbed disposal site within the same sublationedit area from which the water organated.

EARTH BANKS TO BE FREE OF PROJECTIONS OR OTHERS BORGULARITIES THAT WILL IMPEDE HORMAL FLOW.

0324|09 py of submitted plans,

JUL

TMA

2008

DRAWING SCHEDULE

- CIVIL DRAWINGS
- C1. SEDIMENT & EROSION CONTROL PLAN CO. CIVIL NOTES & DRAWING SCHEDULE
- C2. SEDIMENT & EROSION CONTROL DETAILS









ML

AKIAN

ORIGINAL: A1 DWG

