

James McHugh



Onsite Wastewater Assessment: 17 Thompson Street, Scotland Island, NSW.

ENVIRONMENTAL



WATER



WASTEWATER



GEOTECHNICAL



CIVIL



PROJECT
MANAGEMENT



P2108321JR02V02
May 2022

Copyright Statement

Martens & Associates Pty Ltd (Publisher) is the owner of the copyright subsisting in this publication. Other than as permitted by the Copyright Act and as outlined in the Terms of Engagement, no part of this report may be reprinted or reproduced or used in any form, copied or transmitted, by any electronic, mechanical, or by other means, now known or hereafter invented (including microcopying, photocopying, recording, recording tape or through electronic information storage and retrieval systems or otherwise), without the prior written permission of Martens & Associates Pty Ltd. Legal action will be taken against any breach of its copyright. This report is available only as book form unless specifically distributed by Martens & Associates in electronic form. No part of it is authorised to be copied, sold, distributed or offered in any other form.

The document may only be used for the purposes for which it was commissioned. Unauthorised use of this document in any form whatsoever is prohibited. Martens & Associates Pty Ltd assumes no responsibility where the document is used for purposes other than those for which it was commissioned.

Limitations Statement

The sole purpose of this report and the associated services performed by Martens & Associates Pty Ltd is to provide an onsite wastewater assessment in accordance with the scope of services set out in the contract / quotation between Martens & Associates Pty Ltd and James McHugh (hereafter known as the Client). That scope of works and services were defined by the requests of the Client, by the time and budgetary constraints imposed by the Client, and by the availability of access to the site.

Martens & Associates Pty Ltd derived the data in this report primarily from a number of sources which may include for example site inspections, correspondence regarding the proposal, examination of records in the public domain, interviews with individuals with information about the site or the project, and field explorations conducted on the dates indicated. The passage of time, manifestation of latent conditions or impacts of future events may require further examination / exploration of the site and subsequent data analyses, together with a re-evaluation of the findings, observations and conclusions expressed in this report.

In preparing this report, Martens & Associates Pty Ltd may have relied upon and presumed accurate certain information (or absence thereof) relative to the site. Except as otherwise stated in the report, Martens & Associates Pty Ltd has not attempted to verify the accuracy or completeness of any such information (including for example survey data supplied by others).

The findings, observations and conclusions expressed by Martens & Associates Pty Ltd in this report are not, and should not be considered an opinion concerning the completeness and accuracy of information supplied by others. No warranty or guarantee, whether express or implied, is made with respect to the data reported or to the findings, observations and conclusions expressed in this report. Further, such data, findings and conclusions are based solely upon site conditions, information and drawings supplied by the Client etc. in existence at the time of the investigation.

This report has been prepared on behalf of and for the exclusive use of the Client, and is subject to and issued in connection with the provisions of the agreement between Martens & Associates Pty Ltd and the Client. Martens & Associates Pty Ltd accepts no liability or responsibility whatsoever for or in respect of any use of or reliance upon this report by any third party.

© May 2022
Copyright Martens & Associates Pty Ltd
All Rights Reserved

Head Office
Suite 201, 20 George St,
Hornsby, NSW 2077, Australia
ACN 070 240 890 ABN 85 070 240 890
Phone: +61-2-9476-9999
Fax: +61-2-9476-8767
Email: mail@martens.com.au
Web: www.martens.com.au

Document and Distribution Status							
Author(s)		Reviewer(s)		Project Manager		Signature	
Richard Kightley		Andrew Norris Gray Taylor		Gray Taylor			
Revision No.	Description	Status	Release Date	Document Location			
				File Copy	James McHugh		
1	For Client Review	Final	29.11.2021	1P	1P		
2	DA Submission	Final	17.05.2022	1P	1P		

Distribution Types: F = Fax, H = hard copy, P = PDF document, E = Other electronic format. Digits indicate number of document copies.

All enquiries regarding this project are to be directed to the Project Manager.

Contents

1 OVERVIEW.....	5
1.1 Background	5
1.2 Proposed Development	5
1.3 Scope of Work	5
1.4 Relevant Guidelines & Standards	5
2 SITE DESCRIPTION	7
2.1 Location and Setting	7
2.2 Field Investigations	8
2.3 Observed Geology and Soils	8
2.4 Groundwater	8
3 WASTEWATER ASSESSMENT	9
3.1 New Wastewater System	9
3.2 Design Wastewater Load	9
3.3 Land Capability Assessment for Effluent Reuse	9
3.4 Buffer Setbacks for Effluent Reuse Areas	11
3.5 Effluent Disposal Requirements	12
3.6 Geotechnical Considerations	13
3.7 Certification and Maintenance	13
3.8 Construction Certificate Requirements	14
4 REFERENCES	15
5 ATTACHMENT A – PROPOSED DEVELOPMENT PLANS	16
6 ATTACHMENT B – SITE WASTEWATER PLAN	17
7 ATTACHMENT C – BOREHOLE LOGS.....	18

1 Overview

1.1 Background

This report, prepared by Martens and Associates (MA), documents an onsite wastewater assessment undertaken at 17 Thompson Street (Lot 242 DP12749), Scotland Island, NSW ('the site'). The assessment was commissioned by the Client, James McHugh, to support a Development Application (DA) for a new dwelling.

A geotechnical investigation was undertaken in conjunction with the onsite wastewater assessment and is documented in a separate report P2108321JR01V02 (MA, 2022).

Proposed development plans are provided in Attachment A.

1.2 Proposed Development

Based on the review of proposed development plans prepared by Design by Waves (2022) (Attachment A), works include construction of:

- Two storey elevated dwelling with three bedrooms.
- Rain water tank(s).

1.3 Scope of Work

Scope of works for the wastewater assessment included:

1. Site walkover and subsurface investigations.
2. Assessment of wastewater generation rates.
3. Development of an onsite wastewater management solution for DA.

1.4 Relevant Guidelines & Standards

This assessment was undertaken in accordance with the following:

- *Australian / New Zealand Standard 1547 (2012), Onsite domestic wastewater management.*
- Department of Local Government, NSW Environment Protection Authority, NSW Health Department, NSW Department of Land and Water Conservation and the NSW Department of Urban Affairs and Planning (1998), *Environment and Health Protection*

Guidelines - Onsite Wastewater Management for Single Households.

2 Site Description

2.1 Location and Setting

Site information is summarised in Table 1.

Table 1: Site description summary.

Element	Description/Detail
Property address	17 Thompson Street, Scotland Island, NSW
Approximate site area (m ²)	1,377.8 m ² (WSS, 2021)
Lot / DP	Lot 242 / DP 12749
Existing site development	The site is mostly undeveloped. In the central portion, the site had been cut for construction purposes. Old pier and strip brick footings remain on site.
Aspect	North east
Typical slopes	Site slopes are approximately 40%. Site elevation ranges between approximately 26 mAHD along the north eastern boundary and 47 mAHD along the western boundary (WWS, 2021).
Vegetation	The site is generally densely vegetated with natural bush (grass, shrubs and trees).
Local Government Area (LGA)	Northern Beaches Council (NBC)
Drainage	Overland flow towards the north east onto Thompson Street.
Expected geology	Hawkesbury Sandstone comprising medium to coarse grained quartz sandstone with very minor shale and laminite lenses (Sydney 1:100,000 Geological Sheet 9130, 1983)
Expected soils	Watagan colluvial soils comprising of shallow to deep lithosols / siliceous sands and yellow podzolic soils on sandstones with moderately deep brown, red and greyed podzolic soils on shales (eSPADE 2021).

2.2 Field Investigations

Field investigations undertaken on 6 July, 2021 included:

1. Site walkover to assess existing conditions including vegetation, slopes, aspects, geology and hydrology.
2. Two boreholes BH104 and BH105 for wastewater assessment purpose by hand auger up to 1.4 m below ground level (mBGL) to characterise site soils (Attachment C) in potential onsite effluent disposal areas (Attachment B).
3. Additional borehole investigations: BH101, BH102, BH103a, BH103b were undertaken for geotechnical assessment (MA, 2021) to 0.6 mBGL along with four dynamic cone penetrometer tests up to 2.0 mBGL.

2.3 Observed Geology and Soils

BH104 and BH105 encountered clay loam to a depth of 0.2 mBGL overlaying fine sandy loam to a depth of 0.60 to 0.80 mBGL. Medium to light clays were observed under sandy loam to termination depths. BH104 was terminated at an investigation depth of 1.40 mBGL on weathered sandstone with BH105 terminated at 1.20 mBGL on weathered sandstone.

2.4 Groundwater

Groundwater was not observed during borehole drilling. A shallow groundwater table is not expected, however ephemeral groundwater may collect at the soil / rock interface after periods of substantial or prolonged rainfall.

3 Wastewater Assessment

3.1 New Wastewater System

Currently the site has no buildings or services, including no wastewater management system. The most suitable management system for the site, given the site characteristics and constraints, is a secondary treatment system coupled with a subsurface irrigation system.

An appropriate secondary wastewater treatment solution for the site would be provided by an aerated wastewater treatment system (AWTS) approved by NSW Department of Health.

3.2 Design Wastewater Load

Site population is calculated based on two persons for the first bedroom and one person for every other potential room. The proposed development contains 3 bedrooms. The design site occupancy is 4 persons.

Design hydraulic load for the proposed development scenario is provided in Table 2 and has been calculated using allowances from Table H1 of AS/NZS 1547 (2012). The proposed dwelling will be equipped with water reduction devices. Therefore, with a potential occupancy of 4 persons and a daily generation rate of 120 L/person/day the design wastewater load is 480 L/day (5 x 120 L/day).

Table 2: Design wastewater load for 17 Thompson Street, Scotland Island.

Total number of potential bedrooms	Design site occupants	Recommended wastewater flow allowance ¹	Design wastewater load (L/day)
3	4	120 L/person/day	480

Notes:

¹Based on AS/NZ 1547, 2012, Table H3 where full water-reduction facilities are implemented on dwellings.

3.3 Land Capability Assessment for Effluent Reuse

Suitability for onsite effluent reuse is assessed according to Tables 4 and 6 of NSW Department of Local Government *et al.* (NSW DLG, 1998) and is summarised in Table 3.

Table 3: Site suitability for onsite effluent reuse, according to NSW Department of Local Government *et al.* (1998).

Feature	Details of Irrigation Areas	Limitation Rating
Flood potential	> 1 in 20 yr flood	Minor
Sun and wind exposure	Moderate to high	Minor
Slope (%)	40%	Major
Landform	Side slope	Minor
Erosion potential	Low	Minor
Site drainage	No soil water logging	Minor
Fill	No fill	Minor
Rock outcrop (%)	<10	Minor
Geology/regolith	No major discontinuities	Minor
Depth to bedrock (m)	Expected >1 mBGL	Minor
Depth to water table (m)	Expected >1.5 mBGL	Minor
Soil permeability category	4	Minor
Coarse fragments (%)	5 to 10	Minor

Site slope is assessed as a major limitation to onsite effluent reuse. Remaining features are assessed as minor limitations. To address the slope limitation, it is proposed that sub surface drip irrigation be used to mitigate the risk of surface runoff of applied effluent as well as a 50% reduction in the proposed DIR in accordance with Table M2 of AS/NZS 1547 (2012). In addition, the geotechnical report is to address any concerns regarding the risk of irrigation impacting slope stability.

3.3.1 Effluent Application Rates for Subsurface Irrigation

Soil properties and corresponding recommended design irrigation rates (DIRs) according to AS/NZS 1547 (2012) for subsurface irrigation are given in Table 4. These are based on site investigations and assumptions of soil properties based on our experience in similar soil environments.

Table 4: DIR and soil properties for the site.

Soil Category	Depth (m) ¹	Texture	Indicative Permeability (K _{sat}) (m/d)	Design Irrigation Rate (DIR) (mm/day)
Topsoil	0.0 – 0.2	Clay loam	0.5 – 0.15	3.5
Subsoil	0.2 – 0.8	Fine sandy loam	> 3.0	4.0
Subsurface irrigation design				1.75 ²

Notes:

¹ Average value from 2 boreholes, depth of soil horizons varies across the site.

² DIR following 50% reduction in accordance with Table M2 AS/NZS 1547 (2012).

3.4 Buffer Setbacks for Effluent Reuse Areas

The final location of any proposed effluent management area (EMA) must provide for adequate buffer setbacks from property boundaries, sealed pathways, dwellings and surface waters. On the basis of our extensive experience with onsite systems in the local area (and in particular Scotland Island) we recommend and adopt site specific buffer setback distances. Adopted setback distances are in some instances less than those provided in DLG et al. (1998) and are considered appropriate. Table 5 provides a summary of recommended setback distances with DLG et al (1998) buffers in parentheses. Large trees have been provided with 1.5 m (from the trunk) buffer distance.

Table 5: Recommended buffer distances for absorption systems (DLG et al., 1998).

Site Feature	Buffer Distance (m)
Property Boundaries	2/1 (12/6) ^{1 2}
Dwellings	2/1 (6/3) ^{1 2}
Paths & Walkways	1 (6/3) ^{1 2}
Swimming Pools	6/3 ¹
Intermittent surface waters	40 (n/a) ³
Permanent surface waters	100 (n/a) ³

Note:

¹ X/Y = Downslope/Upslope of effluent disposal area.

² Recommended buffers for the site based on existing local experience with DLG et al. (1998) in parentheses.

³ The application of setbacks to Pittwater is not generally practical to be applied on Scotland Island.

Refer to the site plan in Attachment A for the proposed EMA, borehole locations, setback distances and location of the proposed building footprint (Attachment B).

3.5 Effluent Disposal Requirements

3.5.1 Irrigation Area

Based on the site design hydraulic load 480 L/day and adopted DIR of 1.75 mm/day, the required minimum irrigation area for effluent disposal is calculated in Table 6.

Table 6: Effluent disposal requirements for 17 Thompson Street, Scotland Island.

Treatment System	Effluent Volume (L/day)	DIR (mm/day)	Area Required (m ²)
Secondary (AWTS)	480	1.75	275

A suitable available EMA of 275 m² is shown in Attachment B.

3.5.2 Effluent Disposal Recommendations

Effluent disposal system is to be constructed in accordance with AS/NZS 1547 (2012) to meet the following minimum specifications:

- o EMA to be constructed as a subsurface irrigation system as shown on attached plan. Irrigation laterals are to be laid at 1 m centres parallel to site contours. Laterals are to be fixed in place. Laterals are to be laid directly into site topsoil at a depth of 150 mm.

- Irrigation laterals shall be pressure compensating dripline specifically designed for the purposes of subsurface effluent irrigation (e.g. 16 mm Netafim).
- Laterals are to be connected to a 25 mm distribution manifold running along the side of the EMA and to a 25 mm flushing main with manual control valve to allow for periodic flushing of solid materials from irrigation laterals. Flushing main is to be connected to the inlet of the AWTs.
- Minimum area of EMA to be 275 m².
- A 120 µm effluent filter is to be installed between the effluent storage tank / well and the EMA.
- No connection with other water reticulation systems is to occur and no standard hose fittings are to be connected to the system.
- Irrigation areas identified on the report plans are indicative only. Final location of all system elements are to be confirmed on site and to be subject of a Section 68 Local Government Act application to install a sewage facility.

3.6 Geotechnical Considerations

The proposed development geotechnical assessment is to take into account effluent being applied to site soils and any potential impact on slope stability. The geotechnical report is to address this risk as required.

3.7 Certification and Maintenance

The following certification and maintenance will be required:

- Inspection and certification of the system by Martens is required prior to commissioning.
- The wastewater management system should be maintained in accordance with manufacturer's recommendations and Council's requirements.
- All sewer works shall be installed in accordance with AS3500.2.2, National Plumbing and Drainage, Part 2.2, Sanitary Plumbing and Drainage.

3.8 Construction Certificate Requirements

Final system positioning and detailed designs of the sewage collection and reticulation systems shall be completed at the Section 68a approval stage.

4 References

Australian / New Zealand Standard 1547 (2012), Onsite domestic wastewater management. [AS/NZS 1547, 2012]

Department of Local Government, NSW Environment Protection Authority, NSW Health Department, NSW Department of Land and Water Conservation and the NSW Department of Urban Affairs and Planning (1998), Environment and Health Protection Guidelines - Onsite Wastewater Management for Single Households. [DLG et al., 1998]

Design Waves (2022) Site Plan, Drawing No 02, Revision DA.1, dated 03 May 2022.


Geological Survey of NSW (1983), Sydney 1:100,000 Geological Series Sheet 9130.

Martens and Associates (2021), Preliminary Geotechnical Assessment: 17 Thompson Street, Scotland Island, NSW, report reference P2108321JR01V01.


NSW Department of Environment & Heritage (2020), eSPADE, NSW soil and land information, www.environment.nsw.gov.au, accessed May 2020 (eSPADE).

Waterview Surveying Services (2021) Survey Plan, Project No 1323, dated 12 April 2020 (WSS, 2021).


5 Attachment A – Proposed Development Plans




DESIGN by WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 M 0439404650 E McHughdesign@outlook.com	REVISION		REVISION		PROJECT ADDRESS		DRAWING TITLE		CONTRACTORS NOTE		2001		 DWG NO: 02 REVISION: DA.1		
	DA 05.02.22 Issue for DA		FOR DA		17 THOMPSON ST SCOTLAND ISLAND 2105		SITE ANALYSIS PLAN (ROOF PLAN)		Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG		SCALE:			1:200 @ A3	
	DA.1 03.05.22 Remove Studio. w-water size										DRAWN BY:			JMc	
											THIS ISSUE:			03.05.22	
											FIRST ISSUE:			05.02.22	
				NOT FOR CONSTRUCTION											



DESIGNby WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 0439404650 McHughdesign@outlook.com	REVISION		REVISION	PROJECT ADDRESS	DRAWING TITLE	CONTRACTORS NOTE	2001		N DWG NO: 10 REVISION: DA.1
	DA 05.02.22 Issue for DA		FOR DA	17 THOMPSON ST SCOTLAND ISLAND 2105	UPPER FLOOR PLAN	Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG	SCALE:	1:200 @ A3	
	DA.1 03.05.22 Remove Studio. w-water size						DRAWN BY:	JMc	
							THIS ISSUE:	03.05.22	
							FIRST ISSUE:	02.08.21	
		NOT FOR CONSTRUCTION							



DESIGN by WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 M 0439404650 E McHughdesign@outlook.com	REVISION		REVISION		PROJECT ADDRESS		DRAWING TITLE		CONTRACTORS NOTE		2001 SCALE:1:200 @ A3 DRAWN BY:JMc THIS ISSUE:03.05.22 FIRST ISSUE:02.08.21 DWG NO:11 REVISION:DA.1		
	DA 05.02.22 Issue for DA				17 THOMPSON ST SCOTLAND ISLAND 2105		LOWER FLOOR PLAN		Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG				
	DA.1 03.05.22 Remove Studio. w-water size												
		FOR DA		CLIENT									
		NOT FOR CONSTRUCTION		MADDY									

LEGEND


- 

22500L Rainwater harvesting tank (2 x total)
- 

UPVC Pipe below ground (size TBC)
- 


OSSM area (see wastewater report)
- 

Retained tree TPZ + SRZ (see arborist report)




CONCEPT PLAN ONLY - FINAL DETAILS INCLUDING SIZES AND LOCATION OF PIPES, SIZE AND LOCATION OF WATER TANK, DP LOCATIONS, PUMPS AND FLOATS TO BE PROVIDED AT CC STAGE

DESIGN by WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 M 0439404650 E McHughdesign@outlook.com	REVISION		REVISION	PROJECT ADDRESS	DRAWING TITLE	CONTRACTORS NOTE	2001		 DWG NO: 15 REVISION: DA.1
	DA 05.02.22 Issue for DA		FOR DA	17 THOMPSON ST SCOTLAND ISLAND 2105	STORMWATER PLAN CONCEPT	Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG	SCALE:	1:200 @ A3	
	DA.1 03.05.22 Remove Studio. w-water size						DRAWN BY:	JMc	
							THIS ISSUE:	03.05.22	
							FIRST ISSUE:	02.08.21	
		NOT FOR CONSTRUCTION							




DESIGN by WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 M 0439404650 E McHughdesign@outlook.com	REVISION		REVISION		PROJECT ADDRESS		DRAWING TITLE		CONTRACTORS NOTE		2001		DWG NO: 20 REVISION: DA	
	DA 05.02.22 Issue for DA				17 THOMPSON ST SCOTLAND ISLAND 2105		NORTH ELEVATION		Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG					
					CLIENT									
					MADDY									
			FOR DA											
			NOT FOR CONSTRUCTION											



- LEGEND**
- TIMBER
 - GLAZING
 - METAL
 - METAL SHEET
 - FC SHEET


DESIGNby WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 M 0439404650 E McHughdesign@outlook.com	REVISION	REVISION	PROJECT ADDRESS	DRAWING TITLE	CONTRACTORS NOTE	2001		DWG NO: 21 REVISION: DA
	DA 05.02.22 Issue for DA	FOR DA	17 THOMPSON ST SCOTLAND ISLAND 2105	EAST ELEVATION	Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG	SCALE:	1:100 @ A3	
			CLIENT			DRAWN BY:	JMc	
			MADDY			THIS ISSUE:	05.02.22	
						FIRST ISSUE:	02.08.21	
		NOT FOR CONSTRUCTION						



LEGEND

- TIMBER
- GLAZING
- METAL
- METAL SHEET
- FC SHEET


DESIGNby WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 M 0439404650 E McHughdesign@outlook.com	REVISION		REVISION	PROJECT ADDRESS	DRAWING TITLE	CONTRACTORS NOTE	2001		DWG NO: 22 REVISION: DA
	DA 05.02.22 Issue for DA		FOR DA	17 THOMPSON ST	SOUTH ELEVATION	Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG	SCALE:	1:100 @ A3	
				SCOTLAND ISLAND 2105			DRAWN BY:	JMc	
				CLIENT			THIS ISSUE:	05.02.22	
				MADDY			FIRST ISSUE:	02.08.21	
		NOT FOR CONSTRUCTION							



LEGEND

- TIMBER
- GLAZING
- METAL
- METAL SHEET
- FC SHEET

DESIGNby WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 M 0439404650 E McHughdesign@outlook.com	REVISION		REVISION	PROJECT ADDRESS	DRAWING TITLE	CONTRACTORS NOTE	2001		DWG NO: 23 REVISION: DA	
	DA	05.02.22	Issue for DA	17 THOMPSON ST SCOTLAND ISLAND 2105	WEST ELEVATION THOMPSON STREET	Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG	SCALE:	1:100 @ A3		
	FOR DA						CLIENT	DRAWN BY:		JMc
							MADDY	THIS ISSUE:		05.02.22
								FIRST ISSUE:		02.08.21



DESIGNby WAVES JAMES T McHUGH PO Box 293 Church Point NSW 2106 M 0439404650 E McHughdesign@outlook.com	REVISION		REVISION	PROJECT ADDRESS	DRAWING TITLE	CONTRACTORS NOTE	2001		DWG NO: 24 REVISION: DA
	DA 05.02.22 Issue for DA		FOR DA NOT FOR CONSTRUCTION	17 THOMPSON ST SCOTLAND ISLAND 2105	LONG SECTION	Do not scale from drawing. Use marked dimensions. The Contractor shall check all figured dimensions on site before commencement of work. To be read in conjunction with all other Consultant's drawings The Designer is to be notified immediately of any discrepancies. Copyright on this drawing retained by the Designer. Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to DIAL BEFORE YOU DIG	SCALE:	1:100 @ A3	
				CLIENT			DRAWN BY:	JMc	
				MADDY			THIS ISSUE:	05.02.22	
							FIRST ISSUE:	02.08.21	

RIDGE
RL 43.00

UPPER FL
RL 39.625

LOWER FL
RL 36.75

10M ABOVE GROUND LEVEL

8.5M ABOVE GROUND LEVEL

1500
overhang

5°min

580
overhang

3500

DESIGN by WAVES

JAMES T McHUGH
PO Box 293
Church Point NSW 2106
M 0439404650 E McHughdesign@outlook.com

REVISION

DA 05.02.22 Issue for DA

REVISION

FOR DA

NOT FOR CONSTRUCTION

PROJECT ADDRESS

17 THOMPSON ST
SCOTLAND ISLAND 2105

CLIENT

MADDY

DRAWING TITLE

CROSS SECTION

CONTRACTORS NOTE

Do not scale from drawing. Use marked dimensions.
The Contractor shall check all figured dimensions on site before commencement of work.

To be read in conjunction with all other Consultant's drawings
The Designer is to be notified immediately of any discrepancies.
Copyright on this drawing retained by the Designer.

Prior to any earth works, Contractor is to contact any authorities necessary including but not limited to **DIAL BEFORE YOU DIG**

2001

SCALE: 1:100 @ A3

DRAWN BY: JMc

THIS ISSUE: 05.02.22

FIRST ISSUE: 05.02.22


DWG NO:

25

REVISION:

DA

6 Attachment B – Site Wastewater Plan



7 **Attachment C – Borehole Logs**

CLIENT	James McHugh	COMMENCED	06/07/2021	COMPLETED	06/07/2021	REF BH101 Sheet 1 OF 1 PROJECT NO. P2108321	
PROJECT	Preliminary Geotechnical Investigation	LOGGED	AG	CHECKED	KB		
SITE	17 Thompson St, Scotland Island, NSW	GEOLOGY	Hawkesbury Sandstone	VEGETATION	Shrubs		
EQUIPMENT	Hand Auger	LONGITUDE	151.29368	RL SURFACE	41 m	DATUM	AHD
EXCAVATION DIMENSIONS	ø75 mm x 0.60 m depth	LATITUDE	-33.6398	ASPECT	North	SLOPE	50 - 60%

Drilling				Sampling		Field Material Description							
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS / ASCS CLASSIFICATION	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY	DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
HA	L	Not Encountered	41.00		0.15/S/1 D 0.15 m			SC	TOPSOIL: Clayey SAND; fine to medium grained; dark grey and dark brown; with silt; trace rootlets.		VL		TOPSOIL
			0.20	40.80				SP		SAND; fine to medium grained; brown, pale brown and grey; with clay; trace silt; trace ironstone and sandstone gravels.		L	
											M		MD
			0.60						Hole Terminated at 0.60 m				0.60: Hand auger refusal on cobbles.
			0.8										
			1.0										
			1.2										
			1.4										
			1.6										
			1.8										

EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS



(C) Copyright Martens & Associates Pty. Ltd.

MARTENS & ASSOCIATES PTY LTD
Suite 201, 20 George St. Hornsby, NSW 2077 Australia
Phone: (02) 9476 9999 Fax: (02) 9476 8767
mail@martens.com.au WEB: http://www.martens.com.au

**Engineering Log -
BOREHOLE**

MARTENS 2.00 LIB.GLB Log MARTENS BOREHOLE P2108321BH101-9H105V01.GPJ <DrawingFile> 23/07/2021 14:14 10/02/00.04 Datalog Lib and In Situ Tool - DGO | Lib: Martens 2.00 2016-11-13 Pgf: Martens 2.00 2016-11-13

CLIENT	James McHugh			COMMENCED	06/07/2021	COMPLETED	06/07/2021	REF BH102					
PROJECT	Preliminary Geotechnical Investigation			LOGGED	AG	CHECKED	KB	Sheet 1 OF 1					
SITE	17 Thompson St, Scotland Island, NSW			GEOLOGY	Hawkesbury Sandstone	VEGETATION	Shrubs	PROJECT NO. P2108321					
EQUIPMENT	Hand Auger			LONGITUDE	151.29388	RL SURFACE	34.84 m	DATUM	AHD				
EXCAVATION DIMENSIONS	ø75 mm x 0.10 m depth			LATITUDE	-33.63987	ASPECT	North	SLOPE	5%				
Drilling		Sampling		Field Material Description									
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS / ASCS CLASSIFICATION	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY	DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
HA	L	Not Encountered		34.84				CL - CI	TOPSOIL: Clayey SILT; low to medium plasticity; dark grey and dark brown; trace sand.	M (=PL)			TOPSOIL
			0.10						Hole Terminated at 0.10 m				0.10: Hand auger refusal on cobbles and boulders.
			0.2										
			0.4										
			0.6										
			0.8										
			1.0										
			1.2										
			1.4										
			1.6										
			1.8										
EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS													
 (C) Copyright Martens & Associates Pty. Ltd.					MARTENS & ASSOCIATES PTY LTD Suite 201, 20 George St. Hornsby, NSW 2077 Australia Phone: (02) 9476 9999 Fax: (02) 9476 8767 mail@martens.com.au WEB: http://www.martens.com.au					Engineering Log - BOREHOLE			

CLIENT	James McHugh	COMMENCED	06/07/2021	COMPLETED	06/07/2021	REF BH103A Sheet 1 OF 1 PROJECT NO. P2108321	
PROJECT	Preliminary Geotechnical Investigation	LOGGED	AG	CHECKED	KB		
SITE	17 Thompson St, Scotland Island, NSW	GEOLOGY	Hawkesbury Sandstone	VEGETATION	Shrubs		
EQUIPMENT	Hand Auger	LONGITUDE	151.2939	RL SURFACE	34.1 m	DATUM	AHD
EXCAVATION DIMENSIONS	ø75 mm x 0.50 m depth	LATITUDE	-33.63993	ASPECT	North	SLOPE	5%

Drilling				Sampling		Field Material Description						
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS / ASCS CLASSIFICATION	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
HA	L	Not Encountered	34.10					SC	TOPSOIL: Clayey SAND; fine to medium grained; dark grey and dark brown; with silt; trace rootlets.		L	TOPSOIL
			0.20 33.90		0.3/S/1 D 0.30 m		SP	SAND; fine to medium grained; brown, pale brown and grey; with clay; trace silt; trace ironstone and sandstone gravels.		M		COLLUVIUM
			0.4							L - MD		
			0.50						Hole Terminated at 0.50 m			0.50: Hand auger refusal on cobbles and boulders.
			0.6									
			0.8									
			1.0									
			1.2									
			1.4									
			1.6									
			1.8									

EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS



(C) Copyright Martens & Associates Pty. Ltd.

MARTENS & ASSOCIATES PTY LTD
Suite 201, 20 George St. Hornsby, NSW 2077 Australia
Phone: (02) 9476 9999 Fax: (02) 9476 8767
mail@martens.com.au WEB: http://www.martens.com.au

**Engineering Log -
BOREHOLE**

CLIENT	James McHugh	COMMENCED	06/07/2021	COMPLETED	06/07/2021	REF BH103B Sheet 1 OF 1 PROJECT NO. P2108321	
PROJECT	Preliminary Geotechnical Investigation	LOGGED	AG	CHECKED	KB		
SITE	17 Thompson St, Scotland Island, NSW	GEOLOGY	Hawkesbury Sandstone	VEGETATION	Shrubs		
EQUIPMENT	Hand Auger	LONGITUDE	151.29334	RL SURFACE	34.1 m	DATUM	AHD
EXCAVATION DIMENSIONS	ø75 mm x 0.60 m depth	LATITUDE	-33.63993	ASPECT	North	SLOPE	5%

Drilling				Sampling		Field Material Description																
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS / ASCS CLASSIFICATION	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY	STRUCTURE AND ADDITIONAL OBSERVATIONS										
HA	L	Not Encountered		34.10	0.4/S/1 D 0.40 m			SC	TOPSOIL: Clayey SAND; fine to medium grained; dark grey and dark brown; with silt; trace rootlets.	M	L	TOPSOIL										
			SP	SAND; fine to medium grained; brown, pale brown and grey; with clay; trace silt; trace ironstone and sandstone gravels.				COLLUVIUM														
				0.20 33.90																		
				0.30 33.80													RESIDUAL SOIL					
	M-H			0.4					CLAY; medium to high plasticity; brown, pale yellow and orange; trace ironstone gravels; trace silt.	M (<PL)	F											
				0.60					Hole Terminated at 0.60 m			0.60: Handauger refusal on weathered rock.										
				0.8																		
				1.0																		
				1.2																		
				1.4																		
				1.6																		
				1.8																		

EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS



(C) Copyright Martens & Associates Pty. Ltd.

MARTENS & ASSOCIATES PTY LTD
Suite 201, 20 George St. Hornsby, NSW 2077 Australia
Phone: (02) 9476 9999 Fax: (02) 9476 8767
mail@martens.com.au WEB: http://www.martens.com.au

**Engineering Log -
BOREHOLE**

CLIENT	James McHugh		COMMENCED	06/07/2021	COMPLETED	06/07/2021	REF BH104						
PROJECT	Preliminary Geotechnical Investigation		LOGGED	AG	CHECKED	KB	Sheet 1 OF 1						
SITE	17 Thompson St, Scotland Island, NSW		GEOLOGY	Hawkesbury Sandstone	VEGETATION	Shrubs	PROJECT NO. P2108321						
EQUIPMENT		Hand Auger	LONGITUDE	151.2939	RL SURFACE	29.75 m	DATUM	AHD					
EXCAVATION DIMENSIONS		Ø75 mm x 1.40 m depth	LATITUDE	-33.6398	ASPECT	North	SLOPE	35 - 40%					
Drilling			Sampling		Field Material Description								
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS / ASCS CLASSIFICATION	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY	DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
HA	L	M	Not Encountered	29.75				CL	Clay LOAM; dark brown and dark grey; moderate structure; trace roots; trace sand.				
				0.20 29.55			S	Fine Sandy LOAM; brown, pale brown and grey; trace ironstone and sandstone gravels.				COLLUVIUM	
				0.80 28.95			CL-CH	CLAY; yellow, brown, orange and pale grey; moderate structure.				RESIDUAL SOIL	
				1.40				Hole Terminated at 1.40 m			1.40: Hand auger refusal on weathered rock/hard clay.		
EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS													
			MARTENS & ASSOCIATES PTY LTD Suite 201, 20 George St. Hornsby, NSW 2077 Australia Phone: (02) 9476 9999 Fax: (02) 9476 8767 mail@martens.com.au WEB: http://www.martens.com.au					Engineering Log - BOREHOLE					

MARTENS 2.00 LIB GLB Log MARTENS BOREHOLE P2108321BH101-9H105V01.GPJ <DrawingFile> 23/07/2021 14:14 10/02/00.04 D:\glb\lib and in situ\Tool - DGD\ Lib: Martens 2.00 2016-11-13 Proj: Martens 2.00 2016-11-13

CLIENT		James McHugh		COMMENCED	06/07/2021	COMPLETED	06/07/2021	REF BH105					
PROJECT		Preliminary Geotechnical Investigation		LOGGED	AG	CHECKED	KB	Sheet 1 OF 1					
SITE		17 Thompson St, Scotland Island, NSW		GEOLOGY	Hawkesbury Sandstone	VEGETATION	Shrubs	PROJECT NO. P2108321					
EQUIPMENT		Hand Auger		LONGITUDE	151.29417	RL SURFACE	28.34 m	DATUM	AHD				
EXCAVATION DIMENSIONS		ø75 mm x 1.20 m depth		LATITUDE	-33.6399	ASPECT	East	SLOPE	30 - 40%				
Drilling			Sampling		Field Material Description								
METHOD	PENETRATION RESISTANCE	WATER	DEPTH (metres)	DEPTH RL	SAMPLE OR FIELD TEST	RECOVERED	GRAPHIC LOG	USCS / ASCS CLASSIFICATION	SOIL/ROCK MATERIAL DESCRIPTION	MOISTURE CONDITION	CONSISTENCY	DENSITY	STRUCTURE AND ADDITIONAL OBSERVATIONS
HA	L	Not Encountered	28.34					CL	Clay LOAM; dark brown and dark grey; moderate structure; trace roots; trace sand.				COLLUVIUM
			0.20	28.14									
			0.4								M		
			0.60	27.74									
H			0.8					CI-CH	CLAY; medium to high plasticity; yellow, brown, orange and pale grey; moderate structure.				RESIDUAL SOIL
			1.0										
			1.2	1.20							M (<PL)		
			1.4										
			1.6										
			1.8										
									Hole Terminated at 1.20 m				1.20: Hand auger refusal on weathered rock/hard clay.
EXCAVATION LOG TO BE READ IN CONJUNCTION WITH ACCOMPANYING REPORT NOTES AND ABBREVIATIONS													
					MARTENS & ASSOCIATES PTY LTD Suite 201, 20 George St. Hornsby, NSW 2077 Australia Phone: (02) 9476 9999 Fax: (02) 9476 8767 mail@martens.com.au WEB: http://www.martens.com.au					Engineering Log - BOREHOLE			