

J3490A. 28<sup>th</sup> February, 2022 Page 1.

# 40 Bassett Street, Mona Vale

Geotechnical Comments for Section 4.55.

We have reviewed the existing geotechnical report, the original plans, and the 9 amended plans by Gartner Trovato, project number 2102, drawings numbered A.00 to A.08, dated 8/2/22.

The changes include:

• Minor alterations to the footprint of the proposed house and terrace.

The changes to the plans are minor from a geotechnical perspective. The changes do not alter the recommendations or the risk assessment in the report carried out by this firm numbered J3490 and dated the 22<sup>nd</sup> December, 2021.

White Geotechnical Group Pty Ltd.

Fellite

Ben White M.Sc. Geol., AuslMM., CP GEOL.

No. 222757

Engineering Geologist.

# GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1 – To be submitted with Development Application

Develo	Oment Application for Name of Applicant	
Addra	s of site 40 Bassett Street, Mona Vale	
	· · · · · · · · · · · · · · · · · · ·	
	ving checklist covers the minimum requirements to be addressed in a Geotechnical Risk <b>Declaration made b</b> nical engineer or engineering geologist or coastal engineer (where applicable) as part of a geotechnical	
l,	Ben White	
organisa	e 22/12/21 certify that I am a geotechnical engineer or engineering geologist of as defined by the Geotechnical Risk Management Policy for Pittwater - 2009 and I am authorised by the on/company to issue this document and to certify that the organisation/company has a current professional in at least \$10million.	he abov
l: Please i	ark appropriate box	
	have prepared the detailed Geotechnical Report referenced below in accordance with the Australia Geom Society's Landslide Risk Management Guidelines (AGS 2007) and the Geotechnical Risk Management F Pittwater - 2009	
	am willing to technically verify that the detailed Geotechnical Report referenced below has been pre accordance with the Australian Geomechanics Society's Landslide Risk Management Guidelines (AGS 2007 Geotechnical Risk Management Policy for Pittwater - 2009	
	have examined the site and the proposed development in detail and have carried out a risk assessment in acc with Section 6.0 of the Geotechnical Risk Management Policy for Pittwater - 2009. I confirm that the results of assessment for the proposed development are in compliance with the Geotechnical Risk Management F Pittwater - 2009 and further detailed geotechnical reporting is not required for the subject site.	of the risl
	have examined the site and the proposed development/alteration in detail and I am of the opinion that the Development only involves Minor Development/Alteration that does not require a Geotechnical Report Assessment and hence my Report is in accordance with the Geotechnical Risk Management Policy for Pittwat requirements.	or Risl
	have examined the site and the proposed development/alteration is separate from and is not affected by a George Hazard and does not require a Geotechnical Report or Risk Assessment and hence my Report is in accordance.	
	the Geotechnical Risk Management Policy for Pittwater - 2009 requirements. have provided the coastal process and coastal forces analysis for inclusion in the Geotechnical Report	
Geotecl	nical Report Details:	
	Report Title: Geotechnical Report 40 Bassett Street, Mona Vale Report Date: 22/12/21	
	Author: BEN WHITE	
	Author's Company/Organisation: WHITE GEOTECHNICAL GROUP PTY LTD	
Docume	ntation which relate to or are relied upon in report preparation:	
	Australian Geomechanics Society Landslide Risk Management March 2007.	
	White Geotechnical Group company archives.	
	are that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support Application for this site and will be relied on by Pittwater Council as the basis for ensuring that the Geo	

I am aware that the above Geotechnical Report, prepared for the abovementioned site is to be submitted in support of a Development Application for this site and will be relied on by Pittwater Council as the basis for ensuring that the Geotechnical Risk Management aspects of the proposed development have been adequately addressed to achieve an "Acceptable Risk Management" level for the life of the structure, taken as at least 100 years unless otherwise stated and justified in the Report and that reasonable and practical measures have been identified to remove foreseeable risk.

Signature	celut
Name	Ben White
Chartered Professional Statu	
Membership No.	222757
	White Geotechnical Group Pty Ltd

# GEOTECHNICAL RISK MANAGEMENT POLICY FOR PITTWATER FORM NO. 1(a) - Checklist of Requirements for Geotechnical Risk Management Report for Development Application

Develo	pment Application	for	Name of Applicant	
		l l	Name of Applicant	
Addres	s of site	40 Bassett Street, Mo	ona Vale	
Report. 7	This checklist is to ac	ccompany the Geotechnical	s to be addressed in a Geotechnical Risk Management Geotechnic Report and its certification (Form No. 1).	cal
	nical Report Detail	s: Report 40 Bassett Street	t Mona Vale	
Roport	Title: Geoleoninoari	topoit 40 Buddott office	i, mond valo	
Report	Date: 22/12/21			
Author:	BEN WHITE			
Author	's Company/Organ	isation: WHITE GEOTECH	INICAL GROUP PTY LTD	
Please m	nark appropriate bo	x		
$\boxtimes$	Comprehensive site	mapping conducted 7/6/21 (date)	_	
$\boxtimes$	Mapping details pres		with geomorphic mapping to a minimum scale of 1:200 (as appropriate	e)
$\boxtimes$	Subsurface investiga	·		•
	□ No	Justification		
	⊠ Yes	Date conducted 7/6/21	in inferred subsurface type-section	
	Geotechnical model		in interred subsurface type-section	
	☐ Above			
	⊠ On the	site		
	☐ Below	the site		
	☐ Beside	the site		
		ds described and reported		
	_		ne Geotechnical Risk Management Policy for Pittwater - 2009	
		equence analysis		
$\boxtimes$	Risk calculation	ency analysis		
		c property conducted in accord	dance with the Geotechnical Risk Management Policy for Pittwater - 20	109
			ordance with the Geotechnical Risk Management Policy for Pittwater - 2	
$\boxtimes$		e been compared to "Acceptal	ble Risk Management" criteria as defined in the Geotechnical Risk	-000
$\boxtimes$			chieve the "Acceptable Risk Management" criteria provided that the	
_	specified conditions			
	Design Life Adopted			
	⊠ 100 y∈ □ Other	ars		
	□ Otner	specify		
$\boxtimes$	Geotechnical Condit		phases as described in the Geotechnical Risk Management Policy for	
_	Pittwater - 2009 hav	•		
			e and practical have been identified and included in the report.	
	RISK assessment wil	thin Bushfire Asset Protection	i zone.	
that the g Managen	eotechnical risk mar nent" level for the lif	nagement aspects of the pro e of the structure, taken as	chnical Report, to which this checklist applies, as the basis for ensoposal have been adequately addressed to achieve an "Acceptable at least 100 years unless otherwise stated, and justified in the Redentified to remove foreseeable risk.	Risk
		<i>=</i>	Feelet	
		Signature		
		Name	Ben White	
		Chartered Professional Sta	atus MScGEOLAusIMM CP GEOL	
		Membership No.	222757	

Company White Geotechnical Group Pty Ltd



J3490. 22<sup>nd</sup> December, 2021. Page 1.

# **GEOTECHNICAL INVESTIGATION:**

New House and Pool at 40 Bassett Street, Mona Vale

# 1. Proposed Development

- **1.1** Demolish the existing house and garage.
- **1.2** Construct a new two storey house with garage attached.
- 1.3 Install a new pool by excavating to a maximum depth of ~2.8m.
- 1.4 Details of the proposed development are shown on 9 drawings prepared by Gartner Trovato, project number 2102, drawings numbered S4.55-00 and A.01 to A.08, Revision B, dated 15/12/21.

# 2. Site Description

- **2.1** The site was inspected on the 7<sup>th</sup> June, 2021.
- 2.2 This residential property is on the high side of the road and has a NE aspect. It is located on the gently graded lower reaches and toe of a hillslope. The ground surface from the downhill property boundary to the uphill side of the house is near level. The natural slope rises from the uphill side of the house to the uphill property boundary at an average angle of ~4°. The ground surface on the downhill side of the property is near level. The slope above the property continues at gentle angles.
- 2.3 At the road frontage, a gravel and concrete driveway runs along the E side of the house to a rendered masonry garage on the uphill side of the house (Photos 1 & 2). Between the road frontage and the house is a near level lawn area (Photo 1). The single storey rendered brick house is supported by brick walls and brick piers (Photos 3 & 4). The supporting walls and piers stand vertical and show no significant signs of movement (Photo 5). A gently sloping lawn extends from the uphill side of the house and garage to the uphill property boundary (Photo 6).



J3490. 22<sup>nd</sup> December, 2021. Page 2.

# 3. Geology

The Sydney 1:100 000 Geological sheet indicates the site is underlain by the Newport Formation of the Narrabeen Group. This is described as interbedded laminite, shale, and quartz to lithic quartz sandstone.

# 4. Subsurface Investigation

Three Auger holes were put down to identify the soil materials. Five Dynamic Cone Penetrometer (DCP) tests were put down to determine the relative density of the overlying soil and the depth to weathered rock. The locations of the tests are shown on the site plan. It should be noted that a level of caution should be applied when interpreting DCP test results. The test will not pass through hard buried objects so in some instances it can be difficult to determine whether refusal has occurred on an obstruction in the profile or on the natural rock surface. This is not expected to be an issue for the testing on this site. But due to the possibility that the actual ground conditions vary from our interpretation there should be allowances in the excavation and foundation budget to account for this. We refer to the appended "Important Information about Your Report" to further clarify. The results are as follows:

#### **AUGER HOLE 1** (~RL6.7) – AH1 (Photo 7)

Depth (m)	Material Encountered
0.0 to 0.4	TOPSOIL, sandy soil, dark brown, damp, fine to medium grained.
0.4 to 0.7	CLAY, brown orange, firm to stiff, moist.

End of Hole @ 0.7m in firm to stiff clay. No watertable encountered.

#### **TEST RESULTS CONTINUE ON NEXT PAGE**



J3490. 22<sup>nd</sup> December, 2021. Page 3.

# **AUGER HOLE 2** (~RL5.6) – AH1 (Photo 8)

rained.

End of Hole @ 1.1m in firm to stiff sandy clay. No watertable encountered.

# **AUGER HOLE 3** (~RL4.0) – AH1 (Photo 9)

Depth (m)	Material Encountered
0.0 to 0.1	<b>TOPSOIL</b> , sandy soil, dark brown, moist, fine to medium grained.
0.1 to 0.7	SAND, dark grey, orange/brown, moist, medium grained.
0.7 to 1.1	SANDY PEAT, black, moist.
1.1 to 1.2	SAND, brown, medium dense, moist.

Refusal @ 1.2m in medium dense sand. No watertable encountered.

#### **DCP TEST RESULTS ON NEXT PAGE**



J3490. 22<sup>nd</sup> December, 2021. Page 4.

DCP TEST RESULTS – Dynamic Cone Penetrometer					
Equipment: 9kg hammer, 510mm drop, conical tip.			Standard: AS1289.6.3.2 - 1997		
Depth(m) Blows/0.3m	<b>DCP 1</b> (~RL4.0)	DCP 2 (~RL4.3)	<b>DCP 3</b> (~RL4.9)	DCP 4	DCP 5
0.0 to 0.3	5	5	5	(~RL5.6) 5	(~RL6.7)
0.3 to 0.6	5	5	5	7	7
0.6 to 0.9	7	5	5	8	12
0.9 to 1.2	16	10	12	14	22
1.2 to 1.5	18	11	16	23	32
1.5 to 1.8	7	12	28	32	50
1.8 to 2.1	12	21	37	50	#
2.1 to 2.4	19	21	30	#	
2.4 to 2.7	17	8	50		
2.7 to 3.0	22	#	#		
3.0 to 3.3	#				
	Refusal on rock @ 3.0m	Refusal on rock @ 2.5m	End of Test @ 2.7m	End of Test @ 2.0m	End of Test @ 1.8m

#refusal/end of test. F = DCP fell after being struck showing little resistance through all or part of the interval.

#### **DCP Notes:**

DCP1 – Refusal on rock @ 3.0m, DCP bouncing off rock surface, brown sandy soil on wet tip.

DCP2 – Refusal on rock @ 2.5m, DCP thudding, dark brown soil and orange/brown clay on wet tip.

DCP3 – End of test @ 2.7m, DCP still going down, light and dark brown sandy soil on wet tip.

DCP4 – End of test @ 2.0m, DCP still going down, dark brown soil on damp tip.

DCP5 – End of test @ 1.8m, DCP still going down, dark brown soil on damp tip.

# 5. Geological Observations/Interpretation

The geology across the site is variable as the site is located on the toe and lower reaches of a hillslope. In the test locations at the near level portion of the property (DCP 1 to 3 & AH3), the ground materials consist of a sandy topsoil, Medium Dense Sand and sandy peat over Medium Dense Sand and firm to stiff sandy clays, with Extremely Low Strength Rock or better encountered at depths from between ~1.8m to ~3.0m below the current surface, being



J3490.

22<sup>nd</sup> December, 2021.

Page 5.

progressively shallower as the slope rises from the toe of the slope. For the ground tests at

the location of the proposed pool near the uphill property boundary (DCP4 & 5, AH1 & 2), the

ground materials consist of a sandy topsoil over clayey soil and clays/sandy clays, with

Extremely Low Strength Rock or better encountered at depths from between ~1.5m to ~1.8m

below the current surface. See the Type Section attached for a diagrammatical representation

of the expected ground materials.

6. Groundwater

Normal ground water seepage is expected to move over the buried surface of the weathered

rock and through the cracks in the rock.

From work done previously by this firm on Bassett Street, the watertable is expected at or

above ~RL1.8. If the house is to be supported on rock the foundations will be taken below the

watertable. See 'Section 16 Foundations'.

It is expected that the watertable will be below the base of the pool and any piers required

to support the pool (~RL3.9).

It should be noted the watertable fluctuates slightly with the tide and climatic changes.

7. Surface Water

No evidence of surface flows were observed on the property during the inspection. It is

expected that normal sheet wash will move onto the site from above the property during

heavy down pours.

8. Geotechnical Hazards and Risk Analysis

No geotechnical hazards were observed above, below or beside the property. The proposed

excavation for the pool is a potential hazard until retaining structures are in place

(Hazard One).

**RISK ANALYSIS SUMMARY ON NEXT PAGE** 



J3490. 22<sup>nd</sup> December, 2021. Page 6.

## Geotechnical Hazards and Risk Analysis - Risk Analysis Summary

HAZARDS	Hazard One
ТҮРЕ	The proposed excavation for the pool collapsing onto the work site and impacting the neighbouring properties before retaining structures are in place.
LIKELIHOOD	'Possible' (10 <sup>-3</sup> )
CONSEQUENCES TO PROPERTY	'Medium' (15%)
RISK TO PROPERTY	'Moderate' (2 x 10 <sup>-4</sup> )
RISK TO LIFE	8.3 x 10 <sup>-6</sup> /annum
COMMENTS	This level of risk to life and property is 'UNACCEPTABLE'. To move risk to 'ACCEPTABLE' levels, the recommendations in <b>Section 13</b> are to be followed.

(See Aust. Geomech. Jnl. Mar 2007 Vol. 42 No 1, for full explanation of terms)

# 9. Suitability of the Proposed Development for the Site

The proposed development is suitable for the site. No geotechnical hazards will be created by the completion of the proposed development provided it is carried out in accordance with the requirements of this report and good engineering and building practice.

#### 10. Stormwater

The fall is to Bassett Street. All stormwater from the proposed development is to be piped to the street drainage system through any tanks that may be required by the regulating authorities.

#### 11. Excavations

An excavation to a maximum depth of ~2.8m is required to install the proposed pool. The excavation is expected to be through topsoil, clayey soil and clay, with Extremely Low Strength Rock expected at depths from between ~1.5m to ~1.8m below the current surface. It is envisaged that excavations through soil, clay and Extremely Low Strength Rock can be carried out with an excavator and bucket.



J3490.

22<sup>nd</sup> December, 2021.

Page 7.

12. Vibrations

Possible vibrations generated during excavations through soil, clay and Extremely Low

Strength Rock will be below the threshold limit for building damage.

13. Excavation Support Requirements

An excavation to a maximum depth of ~2.8m is required to install the proposed pool. The

excavation is set back ~1.3m from the E common boundary. The E common boundary will be

within the zone of influence of the excavation. In this instance, the zone of influence is the

area above a theoretical 30° line through soil and a theoretical 45° line through

clay/weathered rock from the base of the excavation towards the surrounding structures and

boundaries.

The E common boundary fence is to be braced prior to the excavation commencing.

The E cut is to be temporarily supported with typical pool shoring such as braced form ply

until the pool structure is in place.

Where shoring is not required, the cut batters through soil, clay and Extremely Low Strength

Rock will stand at near vertical angles for a short period of time until the pool structure is in

place, provided the cut batters are kept from becoming saturated.

During the excavation process, the geotechnical consultant is to inspect the cut face in 1.5m

intervals as it is lowered to ensure ground materials are as expected and that additional

support is not required.

Upslope runoff is to be diverted from the cut faces by sandbag mounds or other diversion

works. All unsupported cut batters are to be covered to prevent access of water in wet

weather and loss of moisture in dry weather. The covers are to be tied down with metal pegs

or other suitable fixtures so they can't blow off in a storm. The materials and labour to

construct the pool structure are to be organised so on completion of the excavation it can be

constructed as soon as possible. The excavation is to be carried out during a dry period. No



J3490. 22<sup>nd</sup> December, 2021. Page 8.

excavations are to commence if heavy or prolonged rainfall is forecast. If the cut batters remain unsupported for more than a few days before the commencement of pool construction they are to be temporarily supported with typical pool shoring such as braced form ply until the pool structure is in place.

All excavation spoil is to be removed from site following the current Environmental Protection Agency (EPA) waste classification guidelines.

## 14. Retaining Structures

For cantilever or singly-propped retaining structures, it is suggested the design be based on a triangular pressure distribution of lateral pressures using the parameters shown in Table 1.

Table 1 – Likely Earth Pressures for Retaining Structures

	Earth Pressure Coefficients				
Unit	Unit weight (kN/m³)	'Active' K <sub>a</sub>	'At Rest' K₀		
Topsoil and Clayey Sand	20	0.40	0.55		
Residual Clays	20	0.35	0.45		
Extremely Low Strength Rock	22	0.25	0.35		

For rock classes refer to Pells et al "Design Loadings for Foundations on Shale and Sandstone in the Sydney Region". Australian Geomechanics Journal 1978.

It is to be noted that the earth pressures in Table 1 assume a level surface above the structure, do not account for any surcharge loads and assume retaining structures are fully drained. Ground materials and relevant earth pressure coefficients are to be confirmed on site by the geotechnical consultant.

All retaining structures are to have sufficient back-wall drainage and be backfilled immediately behind the structure with free-draining material (such as gravel). This material is to be wrapped in a non-woven Geotextile fabric (i.e. Bidim A34 or similar), to prevent the



J3490.

22<sup>nd</sup> December, 2021.

Page 9.

drainage from becoming clogged with silt and clay. If no back-wall drainage is installed in

retaining structures, the likely hydrostatic pressures are to be accounted for in the structural

design.

15. Site Classification

The site classification in accordance with AS2870-2011 for footings supported on Extremely

Low Strength Rock is Class S.

16. Foundations

It is recommended the house foundations be supported on Extremely Low Strength Rock or

better. This ground material is expected at depths from between ~2.5m to ~3.0m below the

current surface. A maximum allowable bearing pressure of 600kPa can be assumed for

footings on Extremely Low Strength Rock or better. Due to the presence of sand up to ~2m

thick and the watertable expected above the weathered rock on the downhill side of the

house it is recommended screw piles be utilised as the foundation system.

Note that we do not certify screw pile foundations. Screw pile design varies between

contractors and we are not privy to the details of individual design or how the screw pile

contractor converts torque to bearing pressure. As such, the screw pile contractor is totally

responsible for ensuring the screw piles can support the loads on the piles and that these are

within acceptable settlement limits.

The proposed pool is expected to be seated in Extremely Low Strength Rock on the uphill side.

This is a suitable foundation material. On the downhill side where the rock drops away with

the slope, piers taken to Extremely Low Strength Rock will be required to maintain a uniform

bearing material across the structure. The watertable is expected to be below the base of the

pool (~RL3.9) and below the base of any piers required on the downhill side of the pool. As

such, screw piles will not be required and the uphill side of the pool can be supported off the

exposed weathered rock with the downhill side supported by conventional piers.



J3490. 22<sup>nd</sup> December, 2021.

Page 10.

17. Inspections

The client and builder are to familiarise themselves with the following required inspections as well as council geotechnical policy. We cannot provide geotechnical certification for the Occupation Certificate if the following inspections have not been carried out during the construction process.

 During the excavation process, the geotechnical consultant is to inspect the cut face in 1.5m intervals as it is lowered to ensure ground materials are as expected and that

additional support is not required.

 All footings (excluding screw pile foundations) are to be inspected and approved by the geotechnical consultant while the excavation equipment is still onsite and before

steel reinforcing is placed or concrete is poured.

White Geotechnical Group Pty Ltd.

Felice

Ben White M.Sc. Geol., AusIMM., CP GEOL.

No. 222757

Engineering Geologist.



J3490. 22<sup>nd</sup> December, 2021. Page 11.



Photo 1



Photo 2



J3490. 22<sup>nd</sup> December, 2021. Page 12.




Photo 3



Photo 4



J3490. 22<sup>nd</sup> December, 2021. Page 13.




Photo 5



Photo 6



J3490. 22<sup>nd</sup> December, 2021. Page 14.



Photo 7: AH1 – downhole is from left to right.



Photo 8: AH2 – downhole is from left to right.



J3490. 22<sup>nd</sup> December, 2021. Page 15.



Photo 9: AH3 Downhole is from top to bottom.




J3490. 22<sup>nd</sup> December, 2021. Page 16.


## Important Information about Your Report

It should be noted that Geotechnical Reports are documents that build a picture of the subsurface conditions from the observation of surface features and testing carried out at specific points on the site. The spacing and location of the test points can be limited by the location of existing structures on the site or by budget and time constraints of the client. Additionally, the test themselves, although chosen for their suitability for the particular project, have their own limiting factors. The testing gives accurate information at the location of the test, within the confines of the test's capability. A geological interpretation or model is developed by joining these test points using all available data and drawing on previous experience of the geotechnical consultant. Even the most experienced practitioners cannot determine every possible feature or change that may lie below the earth. All of the subsurface features can only be known when they are revealed by excavation. As such, a Geotechnical report can be considered an interpretive document. It is based on factual data but also on opinion and judgement that comes with a level of uncertainty. This information is provided to help explain the nature and limitations of your report.

With this in mind, the following points are to be noted:

- If upon the commencement of the works the subsurface ground or ground water conditions prove different from those described in this report, it is advisable to contact White Geotechnical Group immediately, as problems relating to the ground works phase of construction are far easier and less costly to overcome if they are addressed early.
- If this report is used by other professionals during the design or construction process, any
  questions should be directed to White Geotechnical Group as only we understand the full
  methodology behind the report's conclusions.
- The report addresses issues relating to your specific design and site. If the proposed project design changes, aspects of the report may no longer apply. Contact White Geotechnical if this occurs.
- This report should not be applied to any other project other than that outlined in section 1.0.
- This report is to be read in full and should not have sections removed or included in other documents as this can result in misinterpretation of the data by others.
- It is common for the design and construction process to be adapted as it progresses (sometimes
  to suit the previous experience of the contractors involved). If alternative design and construction
  processes are required to those described in this report, contact White Geotechnical Group. We
  are familiar with a variety of techniques to reduce risk and can advise if your proposed methods
  are suitable for the site conditions.





# EXAMPLES OF GOOD HILLSIDE PRACTICE



# EXAMPLES OF POOR HILLSIDE PRACTICE

